



**Syracuse Label Company, Inc.**  
**110 Luther Avenue BCP Site (BCP Site #C734118)**  
**Periodic Review Report - July 1, 2013 - March 17, 2014**

May 2014

# Executive Summary

The 110 Luther Avenue Brownfield Cleanup Program (BCP) Site (BCP Site #C734118) consists of approximately 1.40-acres of land located at 110 Luther Avenue, Town of Salina, Onondaga County, New York. The Site owner is Syracuse Label Company, Inc. (Syracuse Label). The Site groundwater was found to be contaminated with volatile organic compounds (VOCs), primarily tetrachloroethene (PCE) and its degradation byproducts, trichloroethene (TCE), dichloroethene (DCE) and vinyl chloride (VC). The Site was remediated to commercial use cleanup standards and received a Certificate of Completion (COC) from the New York State Department of Environmental Conservation (NYSDEC) on December 22, 2011.

The Site is currently in the monitoring stage, and groundwater samples are collected from Site monitoring wells on a quarterly basis. Based on the data, concentrations of target compounds in groundwater have shown a notable decrease over time, with less degradation in samples taken from groundwater monitoring well MW-13.

Based on a review of quarterly groundwater monitoring results, and discussions with the NYSDEC, Syracuse Label implemented corrective measures to address the elevated concentrations of degradation byproducts identified in Site groundwater monitoring wells. Corrective measure activities were implemented in accordance with the *December 2012 Groundwater Monitoring Results and Corrective Measures Injection Work Plan* letter report (GHD Consulting Engineers, LLC, April 2013), which was submitted to, and approved by, the NYSDEC. The second phase of corrective measures was begun on November 9, 2013 and is currently being monitored quarterly and further evaluated.

The institutional controls and engineering controls for the Site remain in place and effective for protecting human health and the environment. The soil cover engineering controls remain in place. Groundwater monitoring has been completed in accordance with the Site Management Plan (SMP), which identified the need for quarterly groundwater monitoring. The sub-slab depressurization system (SSDS) engineering control is inspected monthly by Syracuse Label and the system was operating as planned through February 2014. On March 3, 2014 it was noticed that the blower fan that operates suction point risers 10, 11, 12, 13, and 14 had stopped working. The main blower fan continued to operate and provide a vacuum on the system. The failed blower fan was removed and sent to the manufacturer for evaluation and repairs. The NYSDEC was contacted and informed of the situation and the intent to reinstall the blower fan. The blower fan was rebuilt and re-installed during April 2014 (after the PRR reporting period end date of March 17, 2014). At the time of this PRR submittal, the blower fan was operating as intended and the SSDS was functioning as designed.

There is no need to revise the SMP or propose a change to the frequency of PRR submittals at this time. Groundwater will continue to be monitored on a quarterly basis in accordance with the SMP. The requirements necessary to discontinue Site monitoring have not been met at this time.

# Table of Contents

1.	Introduction .....	3
1.1	Purpose .....	3
1.2	Certification Period .....	3
1.3	Scope and Limitations .....	4
2.	Site Overview .....	5
2.1	Background .....	5
3.	Institutional and Engineering Controls .....	7
3.1	Institutional Controls .....	7
3.2	Engineering Controls .....	7
4.	Operations and Monitoring .....	9
4.1	Corrective Measures .....	11
5.	Recommendations .....	13

# Table Index

Table 1 – Groundwater Elevation Data
Table 2 – Summary of Groundwater Analytical Results

# Figure Index

Figure 1 – Site Location Map
Figure 2 – Site Layout
Figure 3 – Groundwater Monitoring Results and Flow Direction
Figure 4 – Sub-Slab Depressurization System Layout
Figure 5 – Soil Cover Engineering Controls
Figure 6 – Supplemental Injections Array

# Appendices

Appendix A - Institutional and Engineering Controls Certification Form
Appendix B - Property Ownership Information for Adjoining Property
Appendix C - Sub-Slab Depressurization System Inspection Checklists
Appendix D - Approval Notifications for EQulS Database Submittals
Appendix E - Groundwater Sampling and Injection Waste Disposal Manifests

# 1. Introduction

## 1.1 Purpose

This Periodic Review Report (PRR) is being submitted on behalf of Syracuse Label Company, Inc. (Syracuse Label) for the 110 Luther Avenue Brownfield Cleanup Program (BCP) Site (BCP Site No. C734118) located at 110 Luther Avenue, Town of Salina, New York (Figure 1). The purpose of this PRR, and attached documents, is to document that institutional and engineering controls, as described in the New York State Department of Environmental Conservation (NYSDEC)-approved Site Management Plan (SMP) and Environmental Easement, are in place in accordance with 6NYCRR Part 375-3. The following elements are included in this report:

- A complete description of all institutional and/or engineering controls employed at the Site;
- An evaluation of the plans developed for implementation of the engineering and institutional controls, regarding the continued effectiveness of any institutional and/or engineering controls required by the decision document for the Site;
- A certification prepared by a professional engineer or qualified environmental professional that the institutional controls and/or engineering controls employed at the Site during the period are:
  - Unchanged from the previous certification, unless approved by the Department, consistent with the SMP;
  - In place and effective;
  - Performing as designed, and that nothing has occurred that would (1) impair the ability of the controls to protect public health and environment, or (2) constitute a violation or failure to comply with any operation and maintenance plan for such controls;
- The institutional and engineering controls certification form as issued by the Department has been completed and included as Appendix A;
- Data tables and figures depicting results of quarterly groundwater monitoring activities conducted on-Site;
- Information related to ongoing corrective measures; and
- Groundwater sampling and injection waste disposal documentation (Appendix E).

## 1.2 Certification Period

NYSDEC requested that this Periodic Review Report (PRR) cover the period between March 17, 2013 and March 17, 2014; however, the initial PRR covered the period ending on June 30, 2013. To avoid the overlap of reporting periods, this PRR discusses maintenance and monitoring activities for the period between July 1, 2013 and March 17, 2014. During this period, Syracuse Label performed regular inspections of the engineering controls on-Site, including the sub-slab depressurization system (SSDS) and soil covers, and GHD Consulting Services, Inc. performed quarterly groundwater monitoring and groundwater remediation corrective measures.

### 1.3 Scope and Limitations

This report: has been prepared by GHD for Syracuse Label Company, Inc. and may only be used and relied on by Syracuse Label Company, Inc. for the purpose agreed between GHD and the Syracuse Label Company, Inc. as set out in section 1.1 of this report.

GHD otherwise disclaims responsibility to any person other than Syracuse Label Company, Inc. arising in connection with this report. GHD also excludes implied warranties and conditions, to the extent legally permissible.

The services undertaken by GHD in connection with preparing this report were limited to those specifically detailed in the report and are subject to the scope limitations set out in the report.

The opinions, conclusions and any recommendations in this report are based on conditions encountered and information reviewed at the date of preparation of the report. GHD has no responsibility or obligation to update this report to account for events or changes occurring subsequent to the date that the report was prepared.

The opinions, conclusions and any recommendations in this report are based on assumptions made by GHD described in this report. GHD disclaims liability arising from any of the assumptions being incorrect.

GHD has prepared this report based in part on information provided by Syracuse Label Company, Inc. and others who provided information to GHD (including Government authorities), which GHD has not independently verified or checked beyond the agreed scope of work. GHD does not accept liability in connection with such unverified information, including errors and omissions in the report which were caused by errors or omissions in that information.

The opinions, conclusions and any recommendations in this report are based on information obtained from, and testing undertaken at or in connection with, specific sample points. Site conditions at other parts of the Site may be different from the Site conditions found at the specific sample points.

Investigations undertaken in respect of this report are constrained by the particular Site conditions, such as the location of buildings, services and vegetation. As a result, not all relevant Site features and conditions may have been identified in this report.

Site conditions (including the presence of hazardous substances and/or Site contamination) may change after the date of this Report. GHD does not accept responsibility arising from, or in connection with, any change to the Site conditions. GHD is also not responsible for updating this report if the Site conditions change without further authorization to do so by Syracuse Label Company, Inc.

## 2. Site Overview

### 2.1 Background

The Site is located in the Town of Salina, Onondaga County, New York and is identified as Block 12 and Lots 04.1, 05.0, 06.1, 08.0, and 09.0 on the Onondaga County Tax Map (Tax Map No. 85-12). The Site is approximately 1.40-acres of land bounded by Albion Avenue to the northwest, Knapp Street to the northeast, Luther Avenue and a parcel operated by Brannock Devices Company, Inc. to the southeast, and an unpaved parking area operated by Bush Electronics to the southwest (see Figure 2).

The Site is currently developed with a two story building used for office space, light manufacturing, and warehouse operations. The portion of the Site not occupied by the building consists of paved parking and delivery areas, with minor landscaping areas.

The Remedial Investigation (RI), which was conducted under Brownfield Cleanup Agreement (BCA Index #B7-0811-09-08) between December 2009 and November 2010, characterized the nature and extent of contamination at the Site. The results of the RI, as reported in the RI Report (S&W Redevelopment of North America, LLC (SWRNA), January 2011, Revised: June 2011) determined that groundwater contamination, consisting of chlorinated volatile organic solvents (tetrachloroethene, trichloroethene, and their degradation products), existed in a discrete area located in the eastern/central portion of the Site (Figure 3).

A Remedial Action Work Plan (RAWP) was prepared by SWRNA (June 2011, Revised: September 2011), which:

- identified the remedial goals and remedial action objectives;
- discussed the remedy selection;
- summarized remedial action pilot test findings;
- summarized the sub-slab communication testing findings; and
- outlined the remedial design for the proposed remedial approach.

The proposed remedial approach was to remediate the Site to a Track 4 Restricted Use by meeting the Commercial Use Soil Cleanup Objectives (SCOs). This remediation approach included implementation of a groundwater remedy and engineering/institutional controls. The groundwater remedy included in-situ chemical reduction (ISCR), which consisted of injection of 11,100 pounds of a granular carbon and zero valent iron powder mixed into a slurry and 12 liters of a bacterial consortium (*Dehalococcoides*). The groundwater remedy was completed in a discrete area of the Site between February 2011 (pilot test) and July 2011 (full scale). The engineering controls consisted of maintaining the soil cover system and installing a sub-slab depressurization system (SSDS) in the existing on-Site building. The institutional controls included a Site groundwater use restriction, a Site use restriction restricting the use to Commercial or Industrial uses, and the requirement that a SSDS will be installed in any future buildings constructed on-Site.

An Environmental Easement (EE) for the Site was filed with the Onondaga County Clerk's Office on October 21, 2011. A Site Management Plan, which outlines Site restrictions and requirements of future maintenance and monitoring, was completed in November 2011. A Certificate of Completion (COC) allowing for commercial or industrial uses of the Site was received from the NYSDEC on December 22, 2011.

The reader of this PRR may refer to previous reports for more detail, as needed. These reports include:

- *Remedial Investigation*, Brownfield Cleanup Program, 110 Luther Avenue Site, 110 Luther Avenue, Liverpool, Onondaga County, New York, BCP Site #C734118, S&W Redevelopment of North America, LLC, January 2011, Revised: June 2011.
- *Remedial Action Work Plan*, Brownfield Cleanup Program, 110 Luther Avenue Brownfield Site, 110 Luther Avenue, Liverpool, Onondaga County, New York, S&W Redevelopment of North America, LLC, June 2011, Revised: September 2011.
- *Site Management Plan*, 110 Luther Avenue Site, Onondaga County, New York, NYSDEC Site Number: C734118, S&W Redevelopment of North America, LLC, August 2011, Revised: November 2011.
- *Final Engineering Report*, 110 Luther Avenue Site, Onondaga County, New York, NYSDEC Site Number: C734118, S&W Redevelopment of North America, LLC, September 2011, Revised: November 2011.
- *December 2012 Groundwater Monitoring Results and Corrective Measures Injection Work Plan*, 110 Luther Avenue BCP Site, Liverpool, New York, NYSDEC BCP Site #C734118, GHD Consulting Engineers, LLC, April 1, 2013.

### 3. Institutional and Engineering Controls

Based on identified groundwater contamination, potential soil vapor contamination, and the Site's past and present use, institutional and engineering controls are utilized at the Site to limit exposure risks. These institutional and engineering controls are described below.

#### 3.1 Institutional Controls

The institutional controls (ICs) for this Site are outlined in the NYSDEC-approved SMP (SWRNA, August 2011, Revised: November 2011), and include the following:

- An Environmental Easement filed with the Onondaga County Clerk's Office;
- A restriction on the use of groundwater without prior approval by NYSDEC;
- An Excavation Work Plan providing guidance for future excavations conducted on-Site;
- A use restriction limiting future Site use to commercial or industrial use without prior approval of the NYSDEC; and
- Monitoring for ownership changes of adjacent property (116 Luther Avenue - Tax Identification 085.-12-10.0).

##### 3.1.1 Groundwater

Groundwater is not being used at the Site.

##### 3.1.2 Excavations

No excavations have occurred on-Site during the certification period.

##### 3.1.3 Site Use

The Site use has not changed since the NYSDEC has issued the Certificate of Completion (COC).

##### 3.1.4 Ownership of Adjacent Property

Based on information from the Onondaga County Real Property Tax Services website (<http://www.ongov.net/rpts/propertyTaxInfo.html>) on March 31, 2014, the adjacent property located to the south of Syracuse Label has been owned by Salvatore A. Leonardi, Junior since 1995. Based on field observations, the property has been, and continues to be, operated as Brannock Devices Company, Inc. (Appendix B).

#### 3.2 Engineering Controls

The engineering controls (ECs) for this Site are outlined in the NYSDEC-approved SMP (SWRNA, August 2011, Revised: November 2011), and include the following:

##### 3.2.1 Sub-Slab Depressurization System

A sub-slab depressurization system (SSDS) was installed in the existing Site building in July 2011 by Radon Home Services, Inc. a certified radon mitigation contractor. The SSDS is a high vacuum system utilizing fourteen (14) suction points positioned at locations throughout the building (Figure 4). The system is designed to operate continuously to create a negative pressure beneath the



building slab in order to mitigate potential soil vapor intrusion issues. The extracted soil vapor is vented to the atmosphere.

System inspection forms, completed by Syracuse Label personnel monthly during the certification period, indicate that the system was operating continuously and that there was no need for repairs or maintenance through February 2014 (Appendix C). On March 3, 2014 it was noticed that the blower fan that is connected to suction point risers 10, 11, 12, 13, and 14 was not operating. Syracuse Label notified the NYSDEC via email of the situation and the intent to replace the fan as soon as practicable. Syracuse Label personnel removed the blower fan and sent it to the manufacturer for evaluation and repairs/replacement. It was determined that the blower fan stopped working due to an issue with the condensate line freezing during an extended period of below normal temperatures. The blower fan was rebuilt and re-installed on April 23, 2014 (after the PRR reporting period end date of March 17, 2014). Observation of the SSDS manometers located on each suction riser on April 24, 2014 indicated that the applied vacuum was similar to the previous readings, indicating the system was operating as intended. At the time of the submittal of this PRR, the SSDS was functioning as designed.

Additional information can be found in the Institutional and Engineering Controls Certification Form (Appendix A).

### 3.2.2 Soil Cover Engineering Control

Direct contact with soil/fill at the Site is mitigated by a soil cover system in place over the entirety of the Site. This soil cover system is comprised of existing asphalt pavement, existing concrete building slabs, and existing grassed areas. The location of the soil cover system is depicted in Figure 5.

The soil cover system was in place for the duration of the certification period and no maintenance was required to amend the soil cover system.

Additional information can be found in the Institutional and Engineering Controls Certification Form (Appendix A).

## 4. Operations and Monitoring

The NYSDEC-approved SMP (SWRNA, August 2011, Revised: November 2011) requires quarterly groundwater monitoring and reporting to demonstrate groundwater remedy effectiveness. The quarterly groundwater monitoring was completed in accordance with the SMP (Figure 2 and Tables 1 and 2). The quarterly monitoring is intended to assess the performance of the remedy and overall reduction in contamination on-Site. The laboratory sample results were transmitted to the NYSDEC on:

- July 25, 2013 (2<sup>nd</sup> Quarter 2013 sampling);
- October 29, 2013 (3<sup>rd</sup> Quarter 2013 sampling); and
- January 28, 2014 (4<sup>th</sup> Quarter 2013 sampling).

The 1<sup>st</sup> Quarter 2014 groundwater monitoring event was conducted as scheduled on March 26 and 27, 2014, after the 2014 PRR reporting period end date of March 17, 2014. The data from this groundwater monitoring event was not received prior to completing this PRR and will be included in the next PRR (March 2015).

Based on the data, concentrations of target compounds in groundwater have shown decreases over time, with several samples from monitoring wells at non-detect (ND) concentrations for PCE and TCE. The exception is samples taken from groundwater monitoring well MW-13, as shown in the summary tables below.

- MW-7:

Target Compounds	Baseline Concentration (February 2010)	Current Concentration (December 2013)
Tetrachloroethene (PCE)	27,000 micrograms per liter (ug/L)	ND (Laboratory reporting limit (LRL) of 40 ug/L)
Trichloroethene (TCE)	4,300 ug/L	ND (LRL of 40 ug/L)
cis-1,2-dichloroethene (cis-DCE)	2,600 ug/L	2,300 ug/L
trans-1,2-dichloroethene (trans-DCE)	Non-Detect (ND)	ND (LRL of 40 ug/L)
Vinyl chloride (VC)	260 ug/L	2,400 ug/L

- MW-8:

Target Compounds	Baseline Concentration (February 2010)	Current Concentration (December 2013)
Tetrachloroethene (PCE)	3,900 ug/L	ND (LRL of 40 ug/L)
Trichloroethene (TCE)	860 ug/L	ND (LRL of 40 ug/L)
cis-1,2-dichloroethene (cis-DCE)	2,500 ug/L	ND (LRL of 40 ug/L)
trans-1,2-dichloroethene (trans-DCE)	ND (LDL of 15 ug/L)	ND (LRL of 40 ug/L)
Vinyl chloride (VC)	250 ug/L	110 ug/L

- MW-11:

Target Compounds	Baseline Concentration (February 2011)	Current Concentration (December 2013)
Tetrachloroethene (PCE)	42,000 ug/L	ND (LRL of 50 ug/L)
Trichloroethene (TCE)	6,300 ug/L	ND (LRL of 50 ug/L)
cis-1,2-dichloroethene (cis-DCE)	3,800 ug/L	3,300 ug/L
trans-1,2-dichloroethene (trans-DCE)	ND (LDL of 380 ug/L)	ND (LRL of 50 ug/L)
Vinyl chloride (VC)	ND (LDL of 500 ug/L)	1,800 ug/L

- MW-12:

Target Compounds	Baseline Concentration (February 2010)	Current Concentration (December 2013)
Tetrachloroethene (PCE)	220 ug/L	ND (LRL of 10 ug/L)
Trichloroethene (TCE)	79 ug/L	ND (LRL of 10 ug/L)
cis-1,2-dichloroethene (cis-DCE)	670 ug/L	500 ug/L
trans-1,2-dichloroethene (trans-DCE)	ND (LDL of 3.8 ug/L)	ND (LRL of 10 ug/L)
Vinyl chloride (VC)	18 ug/L	130 ug/L

- MW-13:

Target Compounds	Baseline Concentration (February 2010)	Current Concentration (December 2013)
Tetrachloroethene (PCE)	410 ug/L	2,100 ug/L
Trichloroethene (TCE)	600 ug/L	1,100 ug/L
cis-1,2-dichloroethene (cis-DCE)	780 ug/L	16,000 ug/L
trans-1,2-dichloroethene (trans-DCE)	12 ug/L	ND (LRL of 200 ug/L)
Vinyl chloride (VC)	29 ug/L	370 ug/L

- MW-17:

Target Compounds	Baseline Concentration (February 2010)	Current Concentration (December 2013)
Tetrachloroethene (PCE)	14,000 ug/L	ND (LRL of 10 ug/L)
Trichloroethene (TCE)	2,000 ug/L	ND (LRL of 10 ug/L)
cis-1,2-dichloroethene (cis-DCE)	750 ug/L	2,400 ug/L
trans-1,2-dichloroethene (trans-DCE)	ND (LDL of 76 ug/L)	14 ug/L
Vinyl chloride (VC)	ND (LDL of 99 ug/L)	1,200 ug/L

Concentrations of cis-DCE and VC showed a sharp increase in most wells sampled following implementation of the pre-COC groundwater remedy (Table 2). The increases observed for cis-DCE and VC were expected as a result of the sequential degradation resulting from groundwater remediation efforts, which are degrading PCE and TCE into cis-DCE and VC. The concentrations of cis-DCE and VC have generally shown a decreasing trend following the initial increase, which is expected to continue over time as degradation continues (Table 2). Based on the groundwater data received to date, the qualitative exposure assessment assumptions regarding off-Site contamination have not changed and are still valid.

Groundwater sampling results for each quarterly sampling event were uploaded into the NYSDEC EQulS Database, approved by the EQulS Team, and are ready for use (Appendix D). The results for the 1<sup>st</sup> Quarter 2014 sampling event will also be uploaded into the NYSDEC EQulS Database once received.

#### 4.1 Corrective Measures

Based on a review of quarterly groundwater monitoring results, and discussions with the NYSDEC, Syracuse Label implemented supplemental rounds of injection to enhance degradation of Site groundwater contaminants, including degradation byproducts (cis-DCE and VC). A Corrective Measures Work Plan (GHD, April 2013) was developed and approved by the NYSDEC. The supplemental injections occurred in the vicinity of MW-1, MW-7, MW-8, MW-10, MW-11, MW-12,

MW-13, and MW-17 (Figure 6). The supplemental injection activities completed to date have been in compliance with the approved work plan.

The supplemental injections, which included additional substrate (carbon and zero valent iron) and inoculum (SDC-9 bacterial consortium) injections, were started on November 9, 2013 and are currently on-going. The on-going supplemental injections are in addition to the supplemental injections discussed in the previous PRR and are being conducted during this PRR period in the vicinity of MW-13 (Figure 6). Table 2 provides a summary of the groundwater data collected during this PRR reporting period. The data continue to show a generally decreasing trend since the supplemental injections were initiated. Implementation procedures and findings of the supplemental injections will be reported in a separate Corrective Measures Report. Due to operational concerns, the need for a second supplemental injection at MW-13 will be evaluated in consultation with the NYSDEC following receipt and review of the second (June) and third (September) quarter groundwater monitoring results.


## 5. Recommendations

Based on a review of the quarterly groundwater data, it is recommended that the ICs and ECs currently in place for the Site remain in place in order to ensure the continued effectiveness and protectiveness of the remedy. Groundwater monitoring should continue to be conducted on a quarterly basis as identified in the SMP. The effectiveness of the remedy should continue to be evaluated through these quarterly groundwater monitoring results. Periodic (i.e., monthly) Site inspections should be continued to assess the proper function of the SSDS and that the soil cover engineering controls are in place and functioning as intended. The effective operation of the replaced SSDS blower fan should be documented as part of the periodic inspections.

A Corrective Measures Report documenting the methods and findings of supplemental injections implemented in consultation with the NYSDEC will hereafter be prepared and submitted to the NYSDEC and New York State Department of Health (NYSDOH).



## Figures





Contour Interval: 10 Feet

Map Taken From: USGS 7.5 Minute Series  
Topographic Quadrangle;  
Syracuse West (1975, photorevised 1978)  
([www.nysgis.state.ny.us/quads/usgsdrg.htm](http://www.nysgis.state.ny.us/quads/usgsdrg.htm))




Syracuse Label Company, Inc  
Periodic Review Report for BCP Site #C734118  
July 1, 2013 to March 17, 2014  
Site Location Map




Job Number 86-14941  
Revision A  
Date 03.31.14

Figure 1





# LEGEND:

-  GROUNDWATER MONITORING WELL LOCATION AND ID
-  SOIL VAPOR MONITORING WELL LOCATION AND ID
-  BCP SITE BOUNDARY (APPROXIMATE)

- NOTES:
- GROUNDWATER MONITORING WELLS SAMPLED FOR IN-SITU CHEMICAL REDUCTION (ISCR) EFFECTIVENESS MONITORING INCLUDE MW-2, MW-7, MW-8, MW-11, MW-12, MW-13, AND MW-17.
  - GROUNDWATER MONITORING WELLS SAMPLED FOR SITE MONITORING INCLUDE MW-1, MW-10, MW-18, AND MW-19.




- NOTES:
- SITE FEATURES BASED ON SITE SURVEY BY IANUZI & ROMANS, P.C. MARCH 2010 AND NOVEMBER 2010.



Syracuse Label Company, Inc.  
Periodic Review Report for BCP Site #C734118  
July 1, 2013 to March 17, 2014  
Site Layout

Job Number 86-14941  
Revision A  
Date 03.31.14

## Figure 2



LEGEND:

GROUNDWATER MONITORING WELL LOCATION AND ID

SOIL VAPOR MONITORING WELL LOCATION AND ID

BCP SITE BOUNDARY (APPROXIMATE)

GROUNDWATER ELEVATION (DECEMBER 18, 2013)

GROUNDWATER ELEVATION CONTOURS AND FLOW DIRECTION (APPROXIMATE)

ANALYTE	DATE OF SAMPLING	CONCENTRATION (ug/L)

NOTES:

1. GROUNDWATER LEVEL AT MW-7 WAS DEPRESSED DUE TO PRESSURE BUILD-UP BEHIND THE J-PLUG. WATER LEVEL REBOUNDED ONCE J-PLUG WAS REMOVED.

2. DATA TABLES:

Baseline data is from either the remedial investigation (February 2010), remedial action pilot test baseline event (February 2011), full scale remedial action baseline event (June 2011), or 3rd quarter 2011 event (September 2011).

Most recent data is from either the 4th quarter 2012 event (December 2012) or the 4th quarter 2013 event (December 2013)

PCE - Tetrachloroethene  
TCE - Trichloroethene  
cis-DCE - cis-1,2-Dichloroethene  
trans-DCE - trans-1,2-Dichloroethene  
VC - Vinyl Chloride  
TOTAL - Total of PCE, TCE, cis-DCE, trans-DCE, and VC  
ND - Not Detected  
J - Estimated Value

Bold results indicate an exceedance of applicable groundwater standard

3. REFER TO DATA TABLES IN PERIODIC REVIEW REPORT FOR COMPLETE SUMMARY OF GROUNDWATER SAMPLING RESULTS

4. GROUNDWATER MONITORING WELLS SAMPLED FOR IN-SITU CHEMICAL REDUCTION (ISCR) EFFECTIVENESS MONITORING INCLUDE MW-2, MW-7, MW-8, MW-11, MW-12, MW-13, AND MW-17.

5. GROUNDWATER MONITORING WELLS SAMPLED FOR SITE MONITORING INCLUDE MW-1, MW-10, MW-18, AND MW-19.




NOTES:

1. SITE FEATURES BASED ON SITE SURVEY BY IANUZI & ROMANS, P.C. MARCH 2010 AND NOVEMBER 2010.



Syracuse Label Company, Inc.  
Periodic Review Report for BCP Site #C734118  
July 1, 2013 to March 17, 2014  
**Groundwater Monitoring Results  
and Flow Direction**

Job Number | 86-14941  
Revision | A  
Date | 03.31.14  
**Figure 3**



LEGEND:

- GROUNDWATER MONITORING WELL LOCATION AND ID
- SOIL VAPOR MONITORING WELL LOCATION AND ID
- BCP SITE BOUNDARY (APPROXIMATE)
- SSDS SUCTION POINT RISER LOCATION AND ID (14 LOCATIONS - APPROXIMATE)
- SSDS FAN LOCATION (2 LOCATIONS - APPROXIMATE)
- SSDS CONDENSATE CLEANOUT LOCATION (2 LOCATIONS - APPROXIMATE)
- SSDS SUCTION PIPE RUN (APPROXIMATE)
- SSDS SUB-SLAB PIPING (APPROXIMATE)

0 18 36 54 72'  
SCALE 1"=36' AT ORIGINAL SIZE



NOTES:  
1. SITE FEATURES BASED ON SITE SURVEY BY IANUZI & ROMANS, P.C. MARCH 2010 AND NOVEMBER 2010.




Syracuse Label Company, Inc.  
Periodic Review Report for BCP Site #C734118  
July 1, 2013 to March 17, 2014  
Sub-Slab Depressurization  
System Layout

Job Number 86-14941  
Revision A  
Date 03.13.14

Figure 4







Syracuse Label Company, Inc.  
 Periodic Review Report for BCP Site #C734118  
 July 1, 2013 to March 17, 2014  
**Supplemental Injections Array**

Job Number | 86-14941  
 Revision | A  
 Date | 03.31.14  
**Figure 6**

## Tables



# 110 LUTHER AVENUE BCP SITE (BCP SITE #C734118)

## PERIODIC REVIEW REPORT

TABLE 1: GROUNDWATER ELEVATION DATA

PAGE 1 OF 2

Monitoring Well I.D.	Date	Reference Point	Reference Elevation (feet)	DTW (feet)	DOW (feet)	Water Elevation (feet)	Volume (gal)
MW-1	9/22/2011	Top of PVC	97.75	2.10	11.11	95.65	0.36
	3/29/2012			2.32	11.11	95.43	0.35
	12/20/2012			2.41	11.11	95.34	0.35
	3/28/2013			2.45	11.11	95.30	0.35
	12/18/2013			2.55	11.11	95.20	0.34
MW-2	6/23/2011	Top of PVC	100.38	3.02	9.90	97.36	0.28
	8/29/2011			2.37	11.17	98.01	0.35
	9/22/2011			2.82	11.17	97.56	0.33
	3/29/2012			3.10	11.90	97.28	0.35
	6/28/2012			3.39	11.90	96.99	0.34
	9/13/2012			3.45	11.90	96.93	0.34
	12/19/2012			3.16	11.90	97.22	0.35
	3/28/2013			3.06	11.90	97.32	0.35
	6/27/2013			2.95	11.95	97.43	0.36
	9/26/2013			2.86	11.95	97.52	0.36
	12/18/2013			3.34	11.99	97.04	0.35
	3/26/2014			3.65	11.99	96.73	0.33
MW-3	12/19/2012	Top of PVC	100.21	2.15	NM	98.06	NM
	3/28/2013			2.22	NM	97.99	NM
MW-4	12/19/2012	Top of PVC	99.22	NM	NM	NM	NM
MW-5	12/19/2012	Top of PVC	99.65	2.28	NM	97.37	NM
	3/28/2013			2.32	NM	97.33	NM
MW-6	12/19/2012	Top of PVC	97.49	NM	NM	NM	NM
MW-7	6/23/2011	Top of PVC	97.28	2.73	15.80	94.55	2.09
	8/30/2011			2.31	15.71	94.97	2.14
	9/22/2011			3.35	15.71	93.93	1.98
	3/29/2012			3.04	15.79	94.24	2.04
	6/28/2012			2.95	15.79	94.33	2.05
	9/13/2012			4.89	15.79	92.39	1.74
	12/21/2012			2.92	15.79	94.36	2.06
	3/28/2013			3.35	16.29	93.93	2.07
	6/27/2013			2.17	15.36	95.11	2.11
	9/26/2013			7.11	15.36	90.17	1.32
	12/18/2013			8.00	15.36	89.28	1.18
	3/26/2014			2.83	15.36	94.45	2.00
MW-8	6/23/2011	Top of PVC	97.38	2.50	17.05	94.88	2.33
	8/30/2011			2.50	17.05	94.88	2.33
	9/22/2011			2.46	17.05	94.92	2.33
	3/30/2012			2.51	17.06	94.87	2.33
	6/28/2012			2.76	17.06	94.62	2.29
	9/13/2012			2.90	17.06	94.48	2.27
	12/21/2012			2.41	17.06	94.97	2.34
	3/28/2013			2.37	17.26	95.01	2.38
	6/27/2013			2.42	16.55	94.96	2.26
	9/26/2013			2.95	16.55	94.43	2.18
	12/18/2013			2.95	16.55	94.43	2.18
	3/26/2014			2.86	16.55	94.52	2.19
MW-9	12/19/2012	Top of PVC	97.14	NM	NM	NM	NM
MW-10	9/22/2011	Top of PVC	97.34	2.60	11.82	94.74	1.48
	3/29/2012			2.64	11.82	94.70	1.47
	12/21/2012			2.63	11.82	94.71	1.47
	3/28/2013			2.49	11.82	94.85	1.49
	12/18/2013			2.62	12.95	94.72	1.65



# 110 LUTHER AVENUE BCP SITE (BCP SITE #C734118)

## PERIODIC REVIEW REPORT

TABLE 1: GROUNDWATER ELEVATION DATA

PAGE 2 OF 2

Monitoring Well I.D.	Date	Reference Point	Reference Elevation (feet)	DTW (feet)	DOW (feet)	Water Elevation (feet)	Volume (gal)
MW-11	6/23/2011	Top of PVC	97.89	2.51	14.30	95.38	0.47
	8/29/2011			2.48	14.34	95.41	0.47
	9/22/2011			4.22	14.34	93.67	0.40
	3/29/2012			2.43	14.35	95.46	0.48
	6/28/2012			2.81	14.35	95.08	0.46
	9/13/2012			3.28	14.35	94.61	0.44
	12/19/2012			2.67	14.35	95.22	0.47
	3/28/2013			2.23	14.35	95.66	0.48
	6/27/2013			1.59	13.91	96.30	0.49
	9/26/2013			2.10	13.91	95.79	0.47
	12/18/2013			2.46	13.91	95.43	0.46
	3/26/2014			2.41	13.91	95.48	0.46
MW-12	6/23/2011	Top of PVC	98.02	2.27	15.60	95.75	0.53
	8/29/2011			2.12	15.60	95.90	0.54
	9/22/2011			2.32	15.60	95.70	0.53
	3/29/2012			2.16	15.61	95.86	0.54
	6/28/2012			2.05	15.61	95.97	0.54
	9/13/2012			3.08	15.61	94.94	0.50
	12/19/2012			2.25	15.60	95.77	0.53
	3/28/2013			2.00	15.60	96.02	0.54
	6/27/2013			2.02	15.60	96.00	0.54
	9/26/2013			2.34	15.60	95.68	0.53
	12/18/2013			2.30	15.60	95.72	0.53
	3/26/2014			2.35	15.60	95.67	0.53
MW-13	6/23/2011	Top of PVC	97.98	2.70	12.30	95.28	0.38
	8/29/2011			2.62	12.36	95.36	0.39
	9/22/2011			4.41	12.36	93.57	0.32
	3/29/2012			2.59	12.41	95.39	0.39
	6/28/2012			2.93	12.41	95.05	0.38
	9/13/2012			3.36	12.41	94.62	0.36
	12/19/2012			2.85	12.41	95.13	0.38
	3/28/2013			2.42	12.41	95.56	0.40
	6/27/2013			2.47	14.19	95.51	0.47
	9/26/2013			2.32	14.19	95.66	0.47
	12/18/2013			2.81	14.19	95.17	0.46
	3/26/2014			2.97	14.19	95.01	0.45
MW-14	12/19/2012	Top of PVC	100.40	3.89	NM	96.51	NM
	3/28/2013			3.55	NM	96.85	NM
MW-15	12/19/2012	Top of PVC	98.13	1.62	11.91	96.51	0.41
	3/28/2013			1.38	11.91	96.75	0.42
MW-16	12/19/2012	Top of PVC	97.80	2.27	12.11	95.53	0.39
	3/28/2013			1.80	12.11	96.00	0.41
MW-17	6/23/2011	Top of PVC	97.89	2.05	13.00	95.84	1.75
	8/29/2011			1.95	12.60	95.94	1.70
	9/22/2011			3.72	12.60	94.17	1.42
	3/29/2012			1.95	12.52	95.94	1.69
	6/28/2012			2.33	12.52	95.56	1.63
	9/13/2012			2.86	12.52	95.03	1.55
	12/19/2012			2.15	12.52	95.74	1.66
	3/28/2013			1.73	12.52	96.16	1.73
	6/27/2013			1.56	12.52	96.33	1.75
	9/26/2013			1.89	12.52	96.00	1.70
	12/18/2013			1.79	12.52	96.10	1.72
	3/26/2014			1.71	12.52	96.18	1.73
MW-18	9/22/2011	Top of PVC	96.86	4.19	12.61	92.67	1.35
	3/29/2012			2.44	12.61	94.42	1.63
	12/20/2012			2.36	12.58	94.50	1.64
MW-19	9/22/2011	Top of PVC	97.14	4.26	13.11	92.88	1.42
	3/29/2012			2.52	13.11	94.62	1.69
	12/20/2012			2.35	13.10	94.79	1.72





**110 LUTHER AVENUE BCP SITE (BCP SITE #C734118)**  
**PERIODIC REVIEW REPORT**  
**TABLE 2: SUMMARY OF GROUNDWATER ANALYTICAL RESULTS**  
**PAGE 1 OF 19**

Analyte	GW Std <sup>a</sup> (ug/L)	MW-2																							
		Dec-07	Feb-10		Jun-11		Aug-11		Sep-11		Mar-12		Jun-12		Sep-12										
		D.L.	D.L.	D.L.	D.L.	D.L.	D.L.	D.L.	D.L.	D.L.	R.L.	D.L.	R.L.	D.L.	R.L.										
<b>EPA Method 8260B</b>																									
Tetrachloroethene	5	U	1	22	U	0.81	R	0.81	R	0.81	U	0.36	1	U	0.36	1									
Trichloroethene	5	NS		1.2	J	U	0.62	R	0.62	R	0.62	U	0.46	1	U	0.46	1								
cis-1,2-dichloroethene	5	NS			U	0.99	U	0.99	R	0.99	R	0.99	U	0.81	1	U	0.81	1							
trans-1,2-dichloroethene	5	NS			U	0.76	U	0.76	R	0.76	R	0.76	U	0.90	1	U	0.90	1							
Vinyl chloride	2	NS			U	0.99	U	0.99	R	0.99	R	0.99	U	0.90	1	U	0.90	1							
<b>EPA Method RSK-175</b>																									
Ethane		NS		NS		U	4		U	4		U	4	5.9	0.49	1.5	U	0.93	7.2		U	0.49	7.5		
Ethene		NS		NS		U	3		U	3		U	3	12	0.52	1.5		U	1.2	6.7		U	0.52	7	
Methane		NS		NS		U	2	9.3			14		89	0.22	1		63		1.3	3.9		40		0.22	4
<b>EPA Method 6010B (total)</b>																									
Calcium		NS		NS		279,000		999,000		310,000		939,000	B	100	500	883,000		100	500	884,000		100	500		
Iron	300	NS		NS		18,500		138,000		27,100	B	25,400		19	50	70,300		19	50	86,800		19	50		
Magnesium	35,000	NS		NS		80,700		309,000		87,300		76,300		43	200	136,000		43	200	134,000		43	200		
Manganese	300	NS		NS		1,370		5,090		1,110		5,000	B	0.4	3	5,000		0.4	3	5,300		0.4	3		
<b>EPA Method 6010B (dissolved)</b>																									
Iron	300	NS		NS		NS		NS		NS		NS		NS		NS		NS		NS		NS		NS	
<b>EPA Method 300</b>																									
Nitrate as N	10,000	NS		NS		U	33	120		54	J		U	11	50		U	11	50		U	11	50		
Sulfate	250,000	NS		NS		76,600		43,100		57,300		70,000		1,700	10,000	76,400		3,500	20,000	51,000		7,000	40,000		
Chloride	250,000	NS		NS		1,440,000		793,000		972,000		1,140,000		5,600	10,000	1,200,000		5,600	10,000	1,250,000		5,600	10,000		
<b>EPA Method SM5310C</b>																									
Dissolved Organic Carbon - Quad		NS		NS		U	230		U	230		U	230	3,400	430	1,000	3,200	430	1,000	3,200	430	1,000	3,200	430	1,000
Total Organic Carbon - Quad		NS		NS		U	230		U	230	167,000		4,700	430	1,000	3,400	430	1,000	3,300	430	1,000	3,300	430	1,000	
<b>EPA Method 2320B</b>																									
Alkalinity		NS		NS		401,000		334,000	B	365,000		413,000		790	5,000	408,000		790	5,000	396,000		790	5,000		
<b>EPA Method SM2340B</b>																									
Hardness as Calcium Carbonate		NS		NS		1,030,000		3,760,000		1,130,000		2,660,000		100	500	2,760,000		100	500	2,760,000		100	500		
<b>EPA Method SM5210B</b>																									
Biochemical Oxygen Demand		NS		NS		13,200		1,300	J	174,000		3,500	2,000	2,000	3,200	2,000	2,000				UH	2,000	2,000		

NOTES:

All values reported as ug/L (parts per billion)

**Bold and heavy outlined cells indicate and exceedance of applicable groundwater standard or guidance value**

U – Analyzed for but not detected above laboratory detection limits

J – Indicates an estimated value

H – Sample was prepped or analyzed beyond the specified holding time

B – Analyte detected in the associated laboratory blank

b – Result detected in the USB

NS – Not sampled

NA – Not analyzed for

D.L. – Laboratory detection limit

R.L. – Laboratory reporting limit

D.F. – Laboratory dilution factor

\* - Reported as 1,2-Dichloroethene, Total is previous laboratory reports

Feb-11, Mar-11, and Apr-11 data represents pilot test baseline, 1<sup>st</sup> post-pilot test sampling event, and 2<sup>nd</sup> post-pilot test sampling event, respectively

Jun-11, Aug-11, and Sep-11 data represents full scale ISCR injection baseline, 1<sup>st</sup> post-ISCR sampling event, and 2<sup>nd</sup> post-ISCR sampling event, respectively

<sup>a</sup> - GW Std – Class GA Groundwater Quality Standard or Guidance Value from New York State Department of Environmental Conservation (NYSDEC) Division of Water

Technical and Operational Guidance Series (June 1998).



**110 LUTHER AVENUE BCP SITE (BCP SITE #C734118)**  
**PERIODIC REVIEW REPORT**  
**TABLE 2: SUMMARY OF GROUNDWATER ANALYTICAL RESULTS**  
**PAGE 2 OF 19**

Analyte	GW Std <sup>A</sup> (ug/L)	MW-2																	
		Dec-12			Mar-13			Jun-13			Sep-13			Dec-13					
		D.L.	R.L.		D.L.	R.L.		D.L.	R.L.		D.L.	R.L.		D.L.	R.L.				
<b>EPA Method 8260B</b>																			
Tetrachloroethene	5	U	0.36	1	U	0.36	1	U	0.36	1	U	0.36	1	U	0.36	1			
Trichloroethene	5	U	0.46	1	U	0.46	1	U	0.46	1	U	0.46	1	U	0.46	1			
cis-1,2-dichloroethene	5	U	0.81	1	U	0.81	1	U	0.81	1	U	0.81	1	U	0.81	1			
trans-1,2-dichloroethene	5	U	0.90	1	U	0.90	1	U	0.90	1	U	0.90	1	U	0.90	1			
Vinyl chloride	2	U	0.90	1	U	0.90	1	U	0.90	1	U	0.90	1	U	0.90	1			
<b>EPA Method RSK-175</b>																			
Ethane		1.7	J	0.49	7.5	7.6	0.49	7.5	U	0.49	7.5	U	0.49	7.5	3	J	1.5	7.5	
Ethene		U	0.52	7	U	0.52	7	2.5	J	0.52	7	U	0.52	7	U	1.5	7		
Methane		41	0.22	4	52	0.22	4	13	0.22	4	3.9	J	0.22	4	36	1	4		
<b>EPA Method 6010B (total)</b>																			
Calcium		693,000	100	500	NA		NA		NA		NA		NA		NA				
Iron	300	46,700	19	50	65,800	19	50	25,200	19	50	64,600	19	50	167,000	19	50			
Magnesium	35,000	86,100	43	200	NA		NA		NA		NA		NA		NA				
Manganese	300	3,500	0.4	3	NA		NA		NA		NA		NA		NA				
<b>EPA Method 6010B (dissolved)</b>																			
Iron	300	NS			1,500	19	50	1,600	19	50	1,900	19	50	1,600	19	50			
<b>EPA Method 300</b>																			
Nitrate as N	10,000	27	J	11	50	43	JH	20	50	66	20	50	25	J	20	50	U	20	50
Sulfate	250,000	65,300	7,000	40,000	79,000	7,000	40,000	81,600	7,000	40,000	65,200	7,000	40,000	72,700	700	4,000			
Chloride	250,000	936,000	5,600	10,000	1,260,000	5,600	10,000	1,220,000	5,600	10,000	938,000	5,600	10,000	991,000	5,600	10,000			
<b>EPA Method SM5310C</b>																			
Dissolved Organic Carbon - Quad		3,800	430	1,000	3,100	430	1,000	3,900	430	1,000	3,100	430	1,000	3,000	430	1,000			
Total Organic Carbon - Quad		2,400	430	1,000	4,500	430	1,000	10,300	430	1,000	4,200	430	1,000	3,500	430	1,000			
<b>EPA Method 2320B</b>																			
Alkalinity		388,000	790	5,000	458,000	790	5,000	473,000	790	5,000	482,000	790	5,000	418,000	790	5,000			
<b>EPA Method SM2340B</b>																			
Hardness as Calcium Carbonate		2,080,000	100	500	2,430,000	100	500	2,210,000	100	500	2,180,000	100	500	4,870,000	100	500			
<b>EPA Method SM5210B</b>																			
Biochemical Oxygen Demand		U	2,000	2,000	NS		NS		NS		NS		NS		NS				

**NOTES:**

All values reported as ug/L (parts per billion)

**Bold and heavy outlined cells indicate and exceedance of applicable groundwater standard or guidance value**

U – Analyzed for but not detected above laboratory detection limits

J – Indicates an estimated value

H – Sample was prepped or analyzed beyond the specified holding time

B – Analyte detected in the associated laboratory blank

b – Result detected in the USB

NS – Not sampled

NA – Not analyzed for

D.L. – Laboratory detection limit

R.L. – Laboratory reporting limit

D.F. – Laboratory dilution factor

<sup>A</sup> – Reported as 1,2-Dichloroethene, Total is previous laboratory reports

Feb-11, Mar-11, and Apr-11 data represents pilot test baseline, 1<sup>st</sup> post-pilot test sampling event, and 2<sup>nd</sup> post-pilot test sampling event, respectively

Jun-11, Aug-11, and Sep-11 data represents full scale ISCR injection baseline, 1<sup>st</sup> post-ISCR sampling event, and 2<sup>nd</sup> post-ISCR sampling event, respectively

<sup>A</sup> – GW Std – Class GA Groundwater Quality Standard or Guidance Value from New York State Department of Environmental Conservation (NYSDEC) Division of Water

Technical and Operational Guidance Series (June 1998).



**110 LUTHER AVENUE BCP SITE (BCP SITE #C734118)**  
**PERIODIC REVIEW REPORT**  
**TABLE 2: SUMMARY OF GROUNDWATER ANALYTICAL RESULTS**  
**PAGE 3 OF 19**

Analyte	GW Std <sup>^</sup> (ug/L)	MW-7											
		Jan-08	Feb-10	Feb-11	Mar-11	Apr-11	Jun-11	Aug-11					
<b>EPA Method 8260B</b>													
Tetrachloroethene	5	14,000	27,000	17,000	6,900	370 J	1,600	240 J					
Trichloroethene	5	1,700	4,300	2,600	3,600	150 J	3,300	520 J					
cis-1,2-dichloroethene	5	2,600 *	2,600	2,600	14,000	17,000	19,000	24,000					
trans-1,2-dichloroethene	5	U	U	U	U	U	U	U					
Vinyl chloride	2	560	260 J	620 J	460 J	690 J	1,100 J	8,500					
<b>EPA Method RSK-175</b>													
Ethane		NS	NS	4.7	8	4	5	U					8
Ethene		NS	NS	9.9	19	11	48	290					
Methane		NS	NS	240	350	160	230	390					
<b>EPA Method 6010B (total)</b>													
Calcium		NS	181,000	176,000	313,000	253,000	212,000	274,000					
Iron	300	NS	2,800	3,270	48,300	19,700	7,370	54,200					
Magnesium	35,000	NS	56,200	53,200	89,400	65,000	59,500	67,200					
Manganese	300	NS	150	314	2,270	1,130	649	2,010					
<b>EPA Method 6010B (dissolved)</b>													
Iron	300	NS	NS	NS	NS	NS	NS	NS					
<b>EPA Method 300</b>													
Nitrate as N	10,000	NS	NS	U	U	U	U	U					33
Sulfate	250,000	NS	NS	106,000	88,900	55,100	43,600.0	17,500					
Chloride	250,000	NS	NS	325,000	280,000	277,000	268,000	214,000					
<b>EPA Method SM5310C</b>													
Dissolved Organic Carbon - Quad		NS	NS	U	230	280,000	NR	115,000					303,000
Total Organic Carbon - Quad		NS	NS	U	230	282,000	207,000	123,000					305,000
<b>EPA Method 2320B</b>													
Alkalinity		NS	NS	326,000	521,000	506,000	468,000	594,000					B
<b>EPA Method SM2340B</b>													
Hardness as Calcium Carbonate		NS	NS	659,000	1,150,000	900,000	773,000	961,000					
<b>EPA Method SM5210B</b>													
Biochemical Oxygen Demand		NS	NS	U	650	464,000	>228,300	>241,200					783,000

**NOTES:**

All values reported as ug/L (parts per billion)

**Bold and heavy outlined cells indicate and exceedance of applicable groundwater standard or guidance value**

U – Analyzed for but not detected above laboratory detection limits

J – Indicates an estimated value

H – Sample was prepped or analyzed beyond the specified holding time

B – Analyte detected in the associated laboratory blank

b – Result detected in the USB

NS – Not sampled

NA – Not analyzed for

D.L. – Laboratory detection limit

R.L. – Laboratory reporting limit

D.F. – Laboratory dilution factor

\* - Reported as 1,2-Dichloroethene, Total is previous laboratory reports

Feb-11, Mar-11, and Apr-11 data represents pilot test baseline, 1<sup>st</sup> post-pilot test sampling event, and 2<sup>nd</sup> post-pilot test sampling event, respectively

Jun-11, Aug-11, and Sep-11 data represents full scale ISCR injection baseline, 1<sup>st</sup> post-ISCR sampling event, and 2<sup>nd</sup> post-ISCR sampling event, respectively

<sup>^</sup> - GW Std – Class GA Groundwater Quality Standard or Guidance Value from New York State Department of Environmental Conservation (NYSDEC) Division of Water

Technical and Operational Guidance Series (June 1998).



**110 LUTHER AVENUE BCP SITE (BCP SITE #C734118)**  
**PERIODIC REVIEW REPORT**  
**TABLE 2: SUMMARY OF GROUNDWATER ANALYTICAL RESULTS**  
**PAGE 4 OF 19**

Analyte	GW Std <sup>A</sup> (ug/L)	MW-7																										
		Sep-11				Mar-12				Jun-12				Sep-12				Dec-12										
		D.L.				D.L.	R.L.	D.F.		D.L.	R.L.	D.F.		D.L.	R.L.	D.F.		D.L.	R.L.	D.F.								
<b>EPA Method 8260B</b>																												
Tetrachloroethene	5	240	J		34	0.36	1	1		U	72	200	200		U	140	400	400		U	140	400	400					
Trichloroethene	5	380			170	J					140	J			U	180	400	400		U	180	400	400					
cis-1,2-dichloroethene	5	7,400			11,000	160	200	200		26,000				320	400	400	27,000			320	400	400	16,000		320	400	400	
trans-1,2-dichloroethene	5		U	38	36	0.9	1	1		U	180	200	200		U	360	400	400		U	360	400	400		360	400	400	
Vinyl chloride	2	4,300			4,300	180	200	200		8,400				180	200	200	8,900			360	400	400	8,100		360	400	400	
<b>EPA Method RSK-175</b>																												
Ethane			U	20	120	J	49	150	100		U	47	360	50		U	25	380	50		430			25	380	50		
Ethene		330			280	52	150	100		860			60	340	50		1,800			26	350	50		2,000		26	350	50
Methane		720			750	22	150	100		600			66	190	50		3,300			11	200	50		5,300		11	200	50
<b>EPA Method 6010B (total)</b>																												
Calcium		357,000			200,000	B	100	500	1		303,000			100	500	1	649,000			100	500	1		469,000	B	100	500	1
Iron	300	62,300	B		5,300	19	50	1		23,800			19	50	1		179,000			19	50	1		73,300	B	19	50	1
Magnesium	35,000	95,000			62,600	43	200	1		93,700			43	200	1		136,000			43	200	1		138,000	B	43	200	1
Manganese	300	1,430			220	B	0.4	3	1		430			0.4	3	1	1,800			0.4	3	1		1,000	B	0.4	3	1
<b>EPA Method 6010B (dissolved)</b>																												
Iron	300	NS			NS					NS				NS			NS				NS							
<b>EPA Method 300</b>																												
Nitrate as N	10,000		U	33		U	11	50	1		U	11	50	1		U	11	50	1		52			11	50	1		
Sulfate	250,000	30,200			47,000	350	2,000	1		12,300			350	2,000	1		U	350	2,000	1		3,500			350	2,000	1	
Chloride	250,000	340,000			260,000	1,400	2,500	5		315,000			1,400	2,500	5		363,000			1,400	2,500	5		424,000		1,400	2,500	5
<b>EPA Method SM5310C</b>																												
Dissolved Organic Carbon - Quad		457,000			18,500	430	1,000	1		308,000			17,400	40,000	40		1,250,000			17,400	40,000	40		334,000		4,300	10,000	10
Total Organic Carbon - Quad		520,000			19,400	430	1,000	1		287,000			17,400	40,000	40		1,210,000			17,400	40,000	40		351,000		4,300	10,000	10
<b>EPA Method 2320B</b>																												
Alkalinity		725,000	B		400,000	790	5,000	1		717,000	B	790	5,000	1		1,510,000			790	5,000	1		1,020,000		790	5,000	1	
<b>EPA Method SM2340B</b>																												
Hardness as Calcium Carbonate		1,280,000			757,000	100	500	1		1,140,000			100	500	1		2,180,000			100	500	1		1,740,000		100	500	1
<b>EPA Method SM5210B</b>																												
Biochemical Oxygen Demand		786,000			27,400	b	2,000	2,000	1		698,000	H	20,000	20,000	10		2,960,000			8,000	8,000	4		470,000		2,000	2,000	

**NOTES:**

All values reported as ug/L (parts per billion)

**Bold and heavy outlined cells indicate and exceedance of applicable groundwater standard or guidance value**

U – Analyzed for but not detected above laboratory detection limits

J – Indicates an estimated value

H – Sample was prepped or analyzed beyond the specified holding time

B – Analyte detected in the associated laboratory blank

b – Result detected in the USB

NS – Not sampled

NA – Not analyzed for

D.L. – Laboratory detection limit

R.L. – Laboratory reporting limit

D.F. – Laboratory dilution factor

<sup>A</sup> - Reported as 1,2-Dichloroethene, Total is previous laboratory reports

Feb-11, Mar-11, and Apr-11 data represents pilot test baseline, 1<sup>st</sup> post-pilot test sampling event, and 2<sup>nd</sup> post-pilot test sampling event, respectively

Jun-11, Aug-11, and Sep-11 data represents full scale ISCR injection baseline, 1<sup>st</sup> post-ISCR sampling event, and 2<sup>nd</sup> post-ISCR sampling event, respectively

<sup>A</sup> - GW Std – Class GA Groundwater Quality Standard or Guidance Value from New York State Department of Environmental Conservation (NYSDEC) Division of Water

Technical and Operational Guidance Series (June 1998).



**110 LUTHER AVENUE BCP SITE (BCP SITE #C734118)**  
**PERIODIC REVIEW REPORT**  
**TABLE 2: SUMMARY OF GROUNDWATER ANALYTICAL RESULTS**  
**PAGE 5 OF 19**

Analyte	GW Std <sup>A</sup> (ug/L)	MW-7																			
		Mar-13				Jun-13				Sep-13				Dec-13							
		D.L.	R.L.	D.F.		D.L.	R.L.	D.F.		D.L.	R.L.	D.F.		D.L.	R.L.	D.F.					
<b>EPA Method 8260B</b>																					
Tetrachloroethene	5	U	140	400	400	U	29	80	80	U	29	80	80	U	14	40	40				
Trichloroethene	5	U	180	400	400	U	37	80	80	U	37	80	80	U	18	40	40				
cis-1,2-dichloroethene	5	18,000	320	400	400	4,300	65	80	80	6,300	65	80	80	2,300	32	40	40				
trans-1,2-dichloroethene	5	U	360	400	400	U	72	80	80	U	72	80	80	U	36	40	40				
Vinyl chloride	2	7,900	360	400	400	3,300	72	80	80	3,000	72	80	80	2,400	36	40	40				
<b>EPA Method RSK-175</b>																					
Ethane		540	25	380	50	42	J	25	380	50	U	25	380	50	U	75	380	50			
Ethene		1,700	26	350	50	62	J	26	350	50	33	J	26	350	50	U	75	350	50		
Methane		6,000	11	200	50	1,000		11	200	50	530		11	200	50	2,900		50	200	50	
<b>EPA Method 6010B (total)</b>																					
Calcium		NA				NA				NA				NA							
Iron	300	58,300	19	50	1	647,000	19	50	1	343,000	19	50	1	93,800	19	50	1				
Magnesium	35,000	NA				NA				NA				NA							
Manganese	300	NA				NA				NA				NA							
<b>EPA Method 6010B (dissolved)</b>																					
Iron	300	17,500	19	50	1	488,000	B	19	50	1	364,000	19	50	1	88,200	19	50	1			
<b>EPA Method 300</b>																					
Nitrate as N	10,000	23	J	20	50	1	U	20	50	1	U	20	50	1	25	J	20	50	1		
Sulfate	250,000	7,400		350	2,000	1	U	350	2,000	1	U	350	2,000	1	U	350	2,000	1			
Chloride	250,000	356,000		1,400	2,500	5	162,000		1,400	2,500	5	312,000		2,800	5,000	10	334,000		5,600	10,000	20
<b>EPA Method SM5310C</b>																					
Dissolved Organic Carbon - Quad		123,000		4,300	10,000	10	2,460,000		43,400	100,000	100	1,940,000		43,400	100,000	100	458,000		43,400	100,000	100
Total Organic Carbon - Quad		126,000		4,300	10,000	10	2,280,000		43,400	100,000	100	1,890,000		43,400	100,000	100	489,000		43,400	100,000	100
<b>EPA Method 2320B</b>																					
Alkalinity		579,000		790	5,000	1	2,110,000		790	5,000	1	2,370,000		790	5,000	1	1,800,000		790	5,000	1
<b>EPA Method SM2340B</b>																					
Hardness as Calcium Carbonate		1,440,000		100	500	1	5,140,000		100	500	1	2,220,000		100	500	1	2,060,000		100	500	1
<b>EPA Method SM5210B</b>																					
Biochemical Oxygen Demand		NS				NS				NS				NS							

**NOTES:**

All values reported as ug/L (parts per billion)

**Bold and heavy outlined cells indicate and exceedance of applicable groundwater standard or guidance value**

U – Analyzed for but not detected above laboratory detection limits

J – Indicates an estimated value

H – Sample was prepped or analyzed beyond the specified holding time

B – Analyte detected in the associated laboratory blank

b – Result detected in the USB

NS – Not sampled

NA – Not analyzed for

D.L. – Laboratory detection limit

R.L. – Laboratory reporting limit

D.F. – Laboratory dilution factor

<sup>A</sup> - Reported as 1,2-Dichloroethene, Total is previous laboratory reports

Feb-11, Mar-11, and Apr-11 data represents pilot test baseline, 1<sup>st</sup> post-pilot test sampling event, and 2<sup>nd</sup> post-pilot test sampling event, respectively

Jun-11, Aug-11, and Sep-11 data represents full scale ISCR injection baseline, 1<sup>st</sup> post-ISCR sampling event, and 2<sup>nd</sup> post-ISCR sampling event, respectively

<sup>A</sup> - GW Std – Class GA Groundwater Quality Standard or Guidance Value from New York State Department of Environmental Conservation (NYSDEC) Division of Water

Technical and Operational Guidance Series (June 1998).



**110 LUTHER AVENUE BCP SITE (BCP SITE #C734118)**  
**PERIODIC REVIEW REPORT**  
**TABLE 2: SUMMARY OF GROUNDWATER ANALYTICAL RESULTS**  
**PAGE 6 OF 19**

Analyte	GW Std <sup>A</sup> (ug/L)	MW-8																										
		Jan-08		Feb-10		Jun-11		Aug-11		Sep-11		Mar-12		Jun-12		Sep-12												
		D.L.		D.L.		D.L.		D.L.		D.L.		D.L.	R.L.	D.F.	D.L.	R.L.	D.F.	D.L.	R.L.	D.F.								
<b>EPA Method 8260B</b>																												
Tetrachloroethene	5	6,200		3,900		1,500		380	J	1,100	J	82	0.36	1	1	1,000	72	200	200	9,500	72	200	200					
Trichloroethene	5	920		860		540		140	J	420	J	22	0.46	1	1	460	92	200	200	1,900	92	200	200					
cis-1,2-dichloroethene	5	1,600	*	2,500		1,700		5,100		7,900		140	3.2	4	4	4,000	160	200	200	8,000	160	200	200					
trans-1,2-dichloroethene	5		U		200		U	15		100	J	83	0.90	1	1	21	3.6	4	4	34	0.90	1	1					
Vinyl chloride	2	290		250		200		4,000		2,800		66	0.90	1	1	1,300	180	200	200	2,100	180	200	200					
<b>EPA Method RSK-175</b>																												
Ethane		NS		NS		15		20		30		74	0.49	1.5	1		U	47	360	50		U	25	380	50			
Ethene		NS		NS		14		290		710			U	52	150	100	270	J	60	340	50		U	26	350	50		
Methane		NS		NS		670		930		1,200		930		22	100	100	6,800		66	190	50	3,300		11	200	50		
<b>EPA Method 6010B (total)</b>																												
Calcium		NS		NS		202,000		263,000		284,000		284,000	B	100	500	1	209,000	100	500	1	231,000	100	500	1				
Iron	300	NS		NS		5,660		33,000		43,900		23,500		19	50	1	10,800	19	50	1	15,500	19	50	1				
Magnesium	35,000	NS		NS		62,500		76,400		82,000		101,000		43	200	1	72,100	43	200	1	78,800	43	200	1				
Manganese	300	NS		NS		1,990		3,870		3,730		710	B	0.4	3	1	2,000	0.4	3	1	1,600	0.4	3	1				
<b>EPA Method 6010B (dissolved)</b>																												
Iron	300	NS		NS		NS		NS		NS		NS				NS				NS								
<b>EPA Method 300</b>																												
Nitrate as N	10,000	NS		NS			U	33			U	33			U	33			U	11	50	1		36	J	11	50	1
Sulfate	250,000	NS		NS		81,100		4,500		3,500		44,600		1,700	10,000	5	49,600	U	700	4,000	2	71,000	3,500	20,000	10			
Chloride	250,000	NS		NS		431,000		482,000		474,000		538,000		2,800	5,000	10	414,000		2,800	5,000	10	406,000	2,800	5,000	10			
<b>EPA Method SM5310C</b>																												
Dissolved Organic Carbon - Quad		NS		NS			U	230	155,000		200,000		2,400		430	1,000	1	3,700		430	1,000	1	4,500		430	1,000	1	
Total Organic Carbon - Quad		NS		NS			U	230	173,000		168,000		2,400		430	1,000	1	2,800		430	1,000	1		U	430	1,000	1	
<b>EPA Method 2320B</b>																												
Alkalinity		NS		NS		385,000		633,000	B	643,000	B	420,000		790	5,000	1	466,000	B	790	5,000	1	420,000		790	5,000	1		
<b>EPA Method SM2340B</b>																												
Hardness as Calcium Carbonate		NS		NS		761,000		971,000		1,050,000		1,120,000		100	500	1	818,000		100	500	1	902,000		100	500	1		
<b>EPA Method SM5210B</b>																												
Biochemical Oxygen Demand		NS		NS		2,600		483,000		216,000			U	2,000	2,000	1		U	2,000	2,000	1	6,500		2,000	2,000	1		

**NOTES:**

All values reported as ug/L (parts per billion)

**Bold and heavy outlined cells indicate and exceedance of applicable groundwater standard or guidance value**

U – Analyzed for but not detected above laboratory detection limits

J – Indicates an estimated value

H – Sample was prepped or analyzed beyond the specified holding time

B – Analyte detected in the associated laboratory blank

b – Result detected in the USB

NS – Not sampled

NA – Not analyzed for

D.L. – Laboratory detection limit

R.L. – Laboratory reporting limit

D.F. – Laboratory dilution factor

\* - Reported as 1,2-Dichloroethene, Total is previous laboratory reports

Feb-11, Mar-11, and Apr-11 data represents pilot test baseline, 1<sup>st</sup> post-pilot test sampling event, and 2<sup>nd</sup> post-pilot test sampling event, respectively

Jun-11, Aug-11, and Sep-11 data represents full scale ISCR injection baseline, 1<sup>st</sup> post-ISCR sampling event, and 2<sup>nd</sup> post-ISCR sampling event, respectively

<sup>^</sup> - GW Std – Class GA Groundwater Quality Standard or Guidance Value from New York State Department of Environmental Conservation (NYSDEC) Division of Water

Technical and Operational Guidance Series (June 1998).



**110 LUTHER AVENUE BCP SITE (BCP SITE #C734118)**  
**PERIODIC REVIEW REPORT**  
**TABLE 2: SUMMARY OF GROUNDWATER ANALYTICAL RESULTS**  
**PAGE 7 OF 19**

Analyte	GW Std <sup>a</sup> (ug/L)	MW-8																								
		Dec-12			Mar-13			Jun-13			Sep-13			Dec-13												
		D.L.	R.L.	D.F.	D.L.	R.L.	D.F.	D.L.	R.L.	D.F.	D.L.	R.L.	D.F.	D.L.	R.L.	D.F.										
<b>EPA Method 8260B</b>																										
Tetrachloroethene	5	1,800	36	100	100	800	72	200	200	17 J	14	40	40	U	14	40	40									
Trichloroethene	5	470	46	100	100	380	92	200	200	U	18	40	40	U	18	40	40									
cis-1,2-dichloroethene	5	6,600	81	100	100	9,400	160	200	200	2,100	32	40	40	160	32	40	40									
trans-1,2-dichloroethene	5	U	90	100	100	U	180	200	200	U	36	40	40	U	36	40	40									
Vinyl chloride	2	2,700	90	100	100	4,300	180	200	200	2,000	36	40	40	67	36	40	40									
<b>EPA Method RSK-175</b>																										
Ethane		160	J	25	380	50	63	J	25	380	50	U	25	380	50	U	75	380	50							
Ethene		350		26	350	50	550		26	350	50	98	J	26	350	50	U	75	350	50						
Methane		6,100		11	200	50	1,900		11	200	50	2,400		11	200	50	1,900		50	200	50					
<b>EPA Method 6010B (total)</b>																										
Calcium		177,000	B	100	500	1	NA			NA			NA			NA										
Iron	300	8,100	B	19	50	1	269,000	19	50	1	585,000	19	50	1	333,000	19	50	1	89,500	19	50	1				
Magnesium	35,000	57,600	B	0.43	200	1	NA			NA			NA			NA										
Manganese	300	1,800	B	0.4	3	1	NA			NA			NA			NA										
<b>EPA Method 6010B (dissolved)</b>																										
Iron	300	NS				183,000	19	50	1	542,000	B	19	50	1	297,000	19	50	1	94,600	19	50	1				
<b>EPA Method 300</b>																										
Nitrate as N	10,000	39	J	11	50	1	U	20	50	1	U	20	50	1	25	J	20	50	1	20	J	20	50	1		
Sulfate	250,000	60,100		3,500	20,000	10	15,600		1,700	10,000	5	890	J	350	2,000	1	U	700	4,000	2	U	700	4,000	2		
Chloride	250,000	370,000		2,800	5,000	10	483,000		2,800	5,000	10	354,000		1,400	2,500	5	609,000		2,800	5,000	10	547,000		2,800	5,000	10
<b>EPA Method SM5310C</b>																										
Dissolved Organic Carbon - Quad		4,000		430	1,000	1	1,880,000		43,400	100,000	100	3,790,000		43,400	100,000	100	1,490,000		43,400	100,000	100	287,000		43,400	100,000	100
Total Organic Carbon - Quad		3,100		430	1,000	1	2,130,000		43,400	100,000	100	2,720,000		43,400	100,000	100	1,500,000		43,400	100,000	100	249,000		43,400	100,000	100
<b>EPA Method 2320B</b>																										
Alkalinity		392,000		790	5,000	1	2,130,000		790	5,000	1	2,000,000	B	790	5,000	1	2,380,000		790	5,000	1	1,780,000		790	5,000	1
<b>EPA Method SM2340B</b>																										
Hardness as Calcium Carbonate		678,000		100	500	1	2,110,000		100	500	1	2,830,000		100	500	1	2,430,000		100	500	1	2,100,000		100	500	1
<b>EPA Method SM5210B</b>																										
Biochemical Oxygen Demand		U	2,000	2,000	1	NS				NS			NS			NS				NS						

**NOTES:**

All values reported as ug/L (parts per billion)

**Bold and heavy outlined cells indicate and exceedance of applicable groundwater standard or guidance value**

U – Analyzed for but not detected above laboratory detection limits

J – Indicates an estimated value

H – Sample was prepped or analyzed beyond the specified holding time

B – Analyte detected in the associated laboratory blank

b – Result detected in the USB

NS – Not sampled

NA – Not analyzed for

D.L. – Laboratory detection limit

R.L. – Laboratory reporting limit

D.F. – Laboratory dilution factor

<sup>a</sup> - Reported as 1,2-Dichloroethene, Total is previous laboratory reports

Feb-11, Mar-11, and Apr-11 data represents pilot test baseline, 1<sup>st</sup> post-pilot test sampling event, and 2<sup>nd</sup> post-pilot test sampling event, respectively

Jun-11, Aug-11, and Sep-11 data represents full scale ISCR injection baseline, 1<sup>st</sup> post-ISCR sampling event, and 2<sup>nd</sup> post-ISCR sampling event, respectively

<sup>a</sup> - GW Std – Class GA Groundwater Quality Standard or Guidance Value from New York State Department of Environmental Conservation (NYSDEC) Division of Water

Technical and Operational Guidance Series (June 1998).



**110 LUTHER AVENUE BCP SITE (BCP SITE #C734118)**  
**PERIODIC REVIEW REPORT**  
**TABLE 2: SUMMARY OF GROUNDWATER ANALYTICAL RESULTS**  
**PAGE 8 OF 19**

Analyte	GW Std <sup>A</sup> (ug/L)	MW-11											
		Mar-08	Feb-10	Feb-11	Mar-11	Apr-11	Jun-11	Aug-11					
<b>EPA Method 8260B</b>		D.L.	D.L.	D.L.	D.L.	D.L.	D.L.	D.L.	D.L.	D.L.	D.L.	D.L.	D.L.
Tetrachloroethene	5	<b>14,000</b>	<b>20,000</b>	<b>42,000</b>	<b>4,200</b>	<b>2,200 J</b>	U 810	U 410					
Trichloroethene	5	<b>2,400</b>	<b>6,100</b>	<b>6,300</b>	<b>1,100</b>	U 310	U 620	<b>390 J</b>					
cis-1,2-dichloroethene	5	NS	<b>4,400</b>	<b>3,800</b>	<b>39,000</b>	<b>77,000</b>	<b>58,000</b>	<b>49,000</b>					
trans-1,2-dichloroethene	5	U 1,000	U 76	U 380	U 150	U 380	U 760	U 380					
Vinyl chloride	2	U 1,000	<b>270 J</b>	U 500	U 200	U 500	U 990	<b>1,100 J</b>					
<b>EPA Method RSK-175</b>													
Ethane		NS	NS	U 4	U 4	U 4	36	100					
Ethene		NS	NS	5.2	U 3	U 3	53	58					
Methane		NS	NS	46	4.8	8.7	270	170					
<b>EPA Method 6010B (total)</b>													
Calcium		NS	170,000	189,000	361,000	515,000	930,000	1,230,000					
Iron	300	NS	<b>34,900</b>	<b>37,300</b>	<b>298,000</b>	<b>459,000</b>	<b>470,000</b>	<b>1,070,000</b>					
Magnesium	35,000	NS	<b>50,800</b>	<b>55,700</b>	<b>82,300</b>	<b>111,000</b>	<b>140,000</b>	<b>178,000</b>					
Manganese	300	NS	233	<b>359</b>	<b>2,270</b>	<b>2,510</b>	<b>3,830</b>	<b>7,300</b>					
<b>EPA Method 6010B (dissolved)</b>													
Iron	300	NS	NS	NS	NS	NS	NS	NS					
<b>EPA Method 300</b>													
Nitrate as N	10,000	NS	NS	U 33	U 33	33 J	U 33	U 170					
Sulfate	250,000	NS	NS	107,000	40,100	100,000	106,000	124,000					
Chloride	250,000	NS	NS	<b>300,000</b>	<b>404,000</b>	<b>529,000</b>	<b>541,000</b>	<b>256,000</b>					
<b>EPA Method SM5310C</b>													
Dissolved Organic Carbon - Quad		NS	NS	U 230	1,290,000	NR	2,350,000	3,570,000					
Total Organic Carbon - Quad		NS	NS	U 230	1,310,000	2,280,000	2,720,000	4,620,000					
<b>EPA Method 2320B</b>													
Alkalinity		NS	NS	281,000	837,000	1,700,000	2,070,000	3,170,000					
<b>EPA Method SM2340B</b>													
Hardness as Calcium Carbonate		NS	NS	701,000	1,240,000	1,740,000	14,500,000	3,800,000					
<b>EPA Method SM5210B</b>													
Biochemical Oxygen Demand		NS	NS	U 650	>2,367,000	337,000	>2,412,000	>4,566,000					

**NOTES:**

All values reported as ug/L (parts per billion)

**Bold and heavy outlined cells indicate and exceedance of applicable groundwater standard or guidance value**

U – Analyzed for but not detected above laboratory detection limits

J – Indicates an estimated value

H – Sample was prepped or analyzed beyond the specified holding time

B – Analyte detected in the associated laboratory blank

b – Result detected in the USB

NS – Not sampled

NA – Not analyzed for

D.L. – Laboratory detection limit

R.L. – Laboratory reporting limit

D.F. – Laboratory dilution factor

<sup>A</sup> - Reported as 1,2-Dichloroethene, Total is previous laboratory reports

Feb-11, Mar-11, and Apr-11 data represents pilot test baseline, 1<sup>st</sup> post-pilot test sampling event, and 2<sup>nd</sup> post-pilot test sampling event, respectively

Jun-11, Aug-11, and Sep-11 data represents full scale ISCR injection baseline, 1<sup>st</sup> post-ISCR sampling event, and 2<sup>nd</sup> post-ISCR sampling event, respectively

<sup>A</sup> - GW Std – Class GA Groundwater Quality Standard or Guidance Value from New York State Department of Environmental Conservation (NYSDEC) Division of Water

Technical and Operational Guidance Series (June 1998).





**110 LUTHER AVENUE BCP SITE (BCP SITE #C734118)**  
**PERIODIC REVIEW REPORT**  
**TABLE 2: SUMMARY OF GROUNDWATER ANALYTICAL RESULTS**  
**PAGE 9 OF 19**

Analyte	GW Std <sup>^</sup> (ug/L)	MW-11																								
		Sep-11			Mar-12			Jun-12			Sep-12			Dec-12												
			D.L.		D.L.	R.L.	D.F.		D.L.	R.L.	D.F.		D.L.	R.L.	D.F.		D.L.	R.L.	D.F.							
<b>EPA Method 8260B</b>																										
Tetrachloroethene	5	370	J		58	3.6	10	10		U	14	40	40		U	290	800	800		U	290	800	800			
Trichloroethene	5	480	J		40	4.6	10	10		U	18	40	40		U	370	800	800		U	370	800	800			
cis-1,2-dichloroethene	5	45,000			53,000	650	800	800		47,000	1,600	2,000	2,000		59,000	650	800	800		45,000	650	800	800			
trans-1,2-dichloroethene	5		U	300	16	9.0	10	10		U	36	40	40		U	720	800	800		U	720	800	800			
Vinyl chloride	2	680	J		2,700	720	800	800		3,500	36	40	40		4,300	720	800	800		4,200	720	800	800			
<b>EPA Method RSK-175</b>																										
Ethane		100			9.1	0.49	1.5	1		1,800	47	360	50		1,100	25	380	50		1,800	49	750	100			
Ethene		66			9.4	0.52	1.5	1		2,100	60	340	50		1,500	26	350	50		3,300	52	700	100			
Methane		130			14	0.22	1	1		4,900	66	190	50		3,700	11	200	50		7,300	22	400	100			
<b>EPA Method 6010B (total)</b>																										
Calcium		1,240,000			1,390,000	B	500	2,500	5		1,450,000	500	2,500	5		1,590,000	500	2,500	5		1,240,000	1,000	5,000	10		
Iron	300	1,100,000			1,280,000		97	250	5		1,270,000	97	250	5		1,120,000	97	250	5		687,000	19	50	1		
Magnesium	35,000	178,000			169,000		43	200	1		184,000	43	200	1		210,000	43	200	1		155,000	43	200	1		
Manganese	300	7,900			6,600	B	0.4	3	1		6,600	0.4	3	1		6,800	0.4	3	1		3,800	0.4	3	1		
<b>EPA Method 6010B (dissolved)</b>																										
Iron	300	NS			NS					NS					NS					NS						
<b>EPA Method 300</b>																										
Nitrate as N	10,000		U	33		U	11	50	1		U	11	50	1		U	11	50	1		U	11	50	1		
Sulfate	250,000	176,000			U*	350	2,000	1		780	J	350	2,000	1		7,200	J	1,700	10,000	5		2,000	J	1,700	10,000	5
Chloride	250,000	241,000			343,000		2,800	5,000	10		470,000	1,400	2,500	5		455,000	1,400	2,500	5		479,000	1,400	2,500	5		
<b>EPA Method SM5310C</b>																										
Dissolved Organic Carbon - Quad		5,190,000			4,940,000		174,000	400,000	400		4,630,000	43,400	100,000	100		4,310,000	43,400	100,000	100		4,220,000	43,400	100,000	100		
Total Organic Carbon - Quad		4,430,000			4,600,000		174,000	400,000	400		4,950,000	43,400	100,000	100		4,450,000	43,400	100,000	100		4,030,000	43,400	100,000	100		
<b>EPA Method 2320B</b>																										
Alkalinity		3,310,000			3,620,000		790	5,000	1		3,800,000	B	790	5,000	1		3,470,000	790	5,000	1		3,070,000	790	5,000	1	
<b>EPA Method SM2340B</b>																										
Hardness as Calcium Carbonate		3,820,000			4,160,000		100	500	1		4,380,000	100	500	1		4,840,000	100	500	1		3,740,000	100	500	1		
<b>EPA Method SM5210B</b>																										
Biochemical Oxygen Demand		6,830,000			9,870,000	H	20,000	20,000	10		10,200,000	H	20,000	20,000	10		10,200,000	Hb	200,000	200,000	100		7,540,000	100,000	100,000	50

**NOTES:**

All values reported as ug/L (parts per billion)

**Bold and heavy outlined cells indicate and exceedance of applicable groundwater standard or guidance value**

U – Analyzed for but not detected above laboratory detection limits

J – Indicates an estimated value

H – Sample was prepped or analyzed beyond the specified holding time

B – Analyte detected in the associated laboratory blank

b – Result detected in the USB

NS – Not sampled

NA – Not analyzed for

D.L. – Laboratory detection limit

R.L. – Laboratory reporting limit

D.F. – Laboratory dilution factor

\* - Reported as 1,2-Dichloroethene, Total is previous laboratory reports

Feb-11, Mar-11, and Apr-11 data represents pilot test baseline, 1<sup>st</sup> post-pilot test sampling event, and 2<sup>nd</sup> post-pilot test sampling event, respectively

Jun-11, Aug-11, and Sep-11 data represents full scale ISCR injection baseline, 1<sup>st</sup> post-ISCR sampling event, and 2<sup>nd</sup> post-ISCR sampling event, respectively

<sup>^</sup> - GW Std – Class GA Groundwater Quality Standard or Guidance Value from New York State Department of Environmental Conservation (NYSDEC) Division of Water

Technical and Operational Guidance Series (June 1998).



**110 LUTHER AVENUE BCP SITE (BCP SITE #C734118)**  
**PERIODIC REVIEW REPORT**  
**TABLE 2: SUMMARY OF GROUNDWATER ANALYTICAL RESULTS**  
**PAGE 10 OF 19**

Analyte	GW Std <sup>a</sup> (ug/L)	MW-11																		
		Mar-13				Jun-13				Sep-13				Dec-13						
		D.L.	R.L.	D.F.	D.L.	R.L.	D.F.	D.L.	R.L.	D.F.	D.L.	R.L.	D.F.	D.L.	R.L.	D.F.				
<b>EPA Method 8260B</b>																				
Tetrachloroethene	5	U	290	800	800	U	36	100	100	U	72	200	200	U	18	50	50			
Trichloroethene	5	U	370	800	800	U	46	100	100	U	92	200	200	U	23	50	50			
cis-1,2-dichloroethene	5	37,000	650	800	800	9,600	160	200	200	20,000	320	400	400	3,300	41	50	50			
trans-1,2-dichloroethene	5	U	720	800	800	U	90	100	100	U	180	200	200	U	45	50	50			
Vinyl chloride	2	4,900	720	800	800	560	90	100	100	3,200	180	200	200	1,800	45	50	50			
<b>EPA Method RSK-175</b>																				
Ethane		1,400	49	750	100	U	49	750	100	U	49	750	100	U	150	750	100			
Ethene		3,400	52	700	100	180	J	52	700	100	250	J	52	700	100	540	J	150	700	100
Methane		7,500	22	400	100	170	J	22	400	100	2,900	22	400	100	12,000	100	400	100		
<b>EPA Method 6010B (total)</b>																				
Calcium		NA				NA				NA				NA						
Iron	300	615,000	19	50	1	1,110,000	97	250	5	683,000	19	50	1	453,000	19	50	1			
Magnesium	35,000	NA				NA				NA				NA						
Manganese	300	NA				NA				NA				NA						
<b>EPA Method 6010B (dissolved)</b>																				
Iron	300	556,000	19	50	1	NS				558,000	19	50	1	274,000	19	50	1			
<b>EPA Method 300</b>																				
Nitrate as N	10,000	UH	20	50	1	U	20	50	1	24	J	20	50	1	U	20	50	1		
Sulfate	250,000	U	350	2,000	1	1,900	J	350	2,000	1	U	1,700	10,000	5	450	J	350	2,000	1	
Chloride	250,000	366,000	1,400	2,500	5	328,000	1,400	2,500	5	350,000	1,400	2,500	5	364,000	1,400	2,500	5			
<b>EPA Method SM5310C</b>																				
Dissolved Organic Carbon - Quad		3,720,000	174,000	400,000	400	NS				2,480,000	174,000	400,000	400	1,570,000	174,000	400,000	400			
Total Organic Carbon - Quad		3,740,000	174,000	400,000	400	3,060,000	174,000	400,000	400	2,020,000	174,000	400,000	400	1,740,000	174,000	400,000	400			
<b>EPA Method 2320B</b>																				
Alkalinity		2,430,000	B	790	5,000	1	2,100,000	B	790	5,000	1	2,260,000	790	5,000	1	1,440,000	7,900	50,000	1	
<b>EPA Method SM2340B</b>																				
Hardness as Calcium Carbonate		4,410,000	100	500	1	4,290,000	100	500	1	2,770,000	100	500	1	3,540,000	100	500	1			
<b>EPA Method SM5210B</b>																				
Biochemical Oxygen Demand		NS				NS				NS				NS						

**NOTES:**

All values reported as ug/L (parts per billion)

**Bold and heavy outlined cells indicate and exceedance of applicable groundwater standard or guidance value**

U – Analyzed for but not detected above laboratory detection limits

J – Indicates an estimated value

H – Sample was prepped or analyzed beyond the specified holding time

B – Analyte detected in the associated laboratory blank

b – Result detected in the USB

NS – Not sampled

NA – Not analyzed for

D.L. – Laboratory detection limit

R.L. – Laboratory reporting limit

D.F. – Laboratory dilution factor

<sup>^</sup> - Reported as 1,2-Dichloroethene, Total is previous laboratory reports

Feb-11, Mar-11, and Apr-11 data represents pilot test baseline, 1<sup>st</sup> post-pilot test sampling event, and 2<sup>nd</sup> post-pilot test sampling event, respectively

Jun-11, Aug-11, and Sep-11 data represents full scale ISCR injection baseline, 1<sup>st</sup> post-ISCR sampling event, and 2<sup>nd</sup> post-ISCR sampling event, respectively

<sup>^</sup> - GW Std – Class GA Groundwater Quality Standard or Guidance Value from New York State Department of Environmental Conservation (NYSDEC) Division of Water

Technical and Operational Guidance Series (June 1998).



**110 LUTHER AVENUE BCP SITE (BCP SITE #C734118)**  
**PERIODIC REVIEW REPORT**  
**TABLE 2: SUMMARY OF GROUNDWATER ANALYTICAL RESULTS**  
**PAGE 11 OF 19**

Analyte	GW Std <sup>A</sup> (ug/L)	MW-12																		
		Mar-08	Feb-10		Jun-11		Aug-11		Sep-11		Mar-12			Jun-12			Sep-12			
		D.L.		D.L.		D.L.		D.L.		D.L.	R.L.	D.F.		D.L.	R.L.	D.F.		D.L.	R.L.	D.F.
<b>EPA Method 8260B</b>																				
Tetrachloroethene	5	1,200		220		23 J		20 J		17		8.1	0.36 1 1	7.4	1.8 5 5	22	1.8 5 5			
Trichloroethene	5	280		79		U	12	16 J		15		6.9	0.46 1 1	6.8	2.3 5 5	17	2.3 5 5			
cis-1,2-dichloroethene	5	NS		670		1,000		480		350		280	4.1 5 5	250	4.1 5 5	310	4.1 5 5			
trans-1,2-dichloroethene	5	U 20	20	U	3.8	U	15	U	7.6	U	1.5	U	0.90 1 1	U	4.5 5 5	U	4.5 5 5			
Vinyl chloride	2	U 20	20	18 J		45 J		100		66		95	0.90 1 1	57	4.5 5 5	64	4.5 5 5			
<b>EPA Method RSK-175</b>																				
Ethane		NS		NS		22		U 4		U 4		4.5	0.49 1.5 1		U 47	360 50	U 4.9	75 10		
Ethene		NS		NS		41		7.8		5.5		20	0.52 1.5 1		U 60	340 50	U 5.2	70 10		
Methane		NS		NS		61		110		74		280	22 100 100	340	66 190 50	130	2.2 40 10			
<b>EPA Method 6010B (total)</b>																				
Calcium		NS		NS		105,000		388,000		497,000		541,000 B	100 500 1	699,000	100 500 1	431,000	100 500 1			
Iron	300			NS		38,400		85,400		76,800		98,500	19 50 1	76,500	19 50 1	115,000	19 50 1			
Magnesium	35,000			NS		40,500		146,000		184,000		183,000	43 200 1	180,000	43 200 1	165,000	43 200 1			
Manganese	300			NS		583		1,500		2,110		2,500 B	0.4 3 1	3,500	0.4 3 1	2,000	0.4 3 1			
<b>EPA Method 6010B (dissolved)</b>																				
Iron	300			NS		NS		NS		NS		NS		NS		NS				
<b>EPA Method 300</b>																				
Nitrate as N	10,000			NS		U 33		U 33		U 33		U 11	50 1	U 11	50 1	U 11	50 1			
Sulfate	250,000			NS		4,200		66,600		71,900		67,500	1,700 10,000 5	70,500	1,700 10,000 5	82,000	1,700 10,000 5			
Chloride	250,000			NS		485,000		526,000		473,000		481,000	2,800 5,000 10	444,000	1,400 2,500 5	636,000	2,800 5,000 10			
<b>EPA Method SM5310C</b>																				
Dissolved Organic Carbon - Quad				NS		690 J		U 230		U 230		3,800	430 1,000 1	2,000	430 1,000 1	1,800	430 1,000 1			
Total Organic Carbon - Quad				NS		2,000		U 230		U 230		2,000	430 1,000 1	1,400	430 1,000 1	1,600	430 1,000 1			
<b>EPA Method 2320B</b>																				
Alkalinity				NS		142,000		469,000 B		482,000		380,000	790 5,000 1	433,000 B	790 5,000 1	456,000	790 5,000 1			
<b>EPA Method SM2340B</b>																				
Hardness as Calcium Carbonate				NS		429,000		1,570,000		2,000,000		2,100,000	100 500 1	2,490,000	100 500 1	1,760,000	100 500 1			
<b>EPA Method SM5210B</b>																				
Biochemical Oxygen Demand				NS		6,500		2,500		U 650		U 2,000	2,000 1	U 2,000	2,000 1	UH 2,000	2,000 1			

NOTES:

All values reported as ug/L (parts per billion)

**Bold and heavy outlined cells indicate and exceedance of applicable groundwater standard or guidance value**

U – Analyzed for but not detected above laboratory detection limits

J – Indicates an estimated value

H – Sample was prepped or analyzed beyond the specified holding time

B – Analyte detected in the associated laboratory blank

b – Result detected in the USB

NS – Not sampled

NA – Not analyzed for

D.L. – Laboratory detection limit

R.L. – Laboratory reporting limit

D.F. – Laboratory dilution factor

<sup>A</sup> - Reported as 1,2-Dichloroethene, Total is previous laboratory reports

Feb-11, Mar-11, and Apr-11 data represents pilot test baseline, 1<sup>st</sup> post-pilot test sampling event, and 2<sup>nd</sup> post-pilot test sampling event, respectively

Jun-11, Aug-11, and Sep-11 data represents full scale ISCR injection baseline, 1<sup>st</sup> post-ISCR sampling event, and 2<sup>nd</sup> post-ISCR sampling event, respectively

<sup>A</sup> - GW Std – Class GA Groundwater Quality Standard or Guidance Value from New York State Department of Environmental Conservation (NYSDEC) Division of Water

Technical and Operational Guidance Series (June 1998).



**110 LUTHER AVENUE BCP SITE (BCP SITE #C734118)**  
**PERIODIC REVIEW REPORT**  
**TABLE 2: SUMMARY OF GROUNDWATER ANALYTICAL RESULTS**  
**PAGE 12 OF 19**

Analyte	GW Std <sup>a</sup> (ug/L)	MW-12																				
		Dec-12				Mar-13				Jun-13				Sep-13				Dec-13				
		D.L.	R.L.	D.F.		D.L.	R.L.	D.F.		D.L.	R.L.	D.F.		D.L.	R.L.	D.F.		D.L.	R.L.	D.F.		
<b>EPA Method 8260B</b>																						
Tetrachloroethene	5	13	1.8	5	5	U	1.8	5	5	33	1.8	5	5	U	14	40	40	U	3.6	10	10	
Trichloroethene	5	15	2.3	5	5	U	2.3	5	5	26	2.3	5	5	U	18	40	40	U	4.6	10	10	
cis-1,2-dichloroethene	5	250	4.1	5	5	93	4.1	5	5	2,400	32	40	40	1,800	32	40	40	500	8.1	10	10	
trans-1,2-dichloroethene	5	U	4.5	5	5	U	4.5	5	5	U	4.5	5	5	U	36	40	40	U	9	10	10	
Vinyl chloride	2	58	4.5	5	5	4.9	J	4.5	5	5	63	4.5	5	5	220	36	40	40	130	9	10	
<b>EPA Method RSK-175</b>																						
Ethane		U	4.9	75	10	U	4.9	75	10	U	4.9	75	10	U	4.9	75	10	U	150	750	100	
Ethene		U	5.2	70	10	7.9	J	5.2	70	10	11	J	5.2	70	10	8.2	J	5.2	70	10	U	
Methane		140	2.2	40	10	130		2.2	40	10	1,400		2.2	40	10	4,700		22	400	100	12,000	
<b>EPA Method 6010B (total)</b>																						
Calcium		632,000	100	500	1	NA				NA				NA				NA				
Iron	300	95,300	19	50	1	942,000	97	250	5	956,000	97	250	5	834,000	97	250	5	712,000	19	50	1	
Magnesium	35,000	131,000	43	200	1	NA				NA				NA				NA				
Manganese	300	3,300	0.4	3	1	NA				NA				NA				NA				
<b>EPA Method 6010B (dissolved)</b>																						
Iron	300	NS				748,000	19	50	1	964,000	97	250	5	757,000	19	50	1	551,000	19	50	1	
<b>EPA Method 300</b>																						
Nitrate as N	10,000	24	J	11	50	1	UH	20	50	1	U	20	50	1	35	J	20	50	1	20	50	1
Sulfate	250,000	83,900		3,500	20,000	10	28,800		3,500	20,000	10	22,500		1,700	10,000	5	13,300	J	3,500	20,000	10	
Chloride	250,000	529,000		2,800	5,000	10	619,000		2,800	5,000	10	481,000		2,800	5,000	10	616,000		2,800	5,000	10	
<b>EPA Method SM5310C</b>																						
Dissolved Organic Carbon - Quad		800	J	430	1,000	1	2,930,000		43,400	100,000	100	3,200,000		43,400	100,000	100	2,660,000		43,400	100,000	100	
Total Organic Carbon - Quad		550	J	430	1,000	1	2,860,000		43,400	100,000	100	3,300,000		43,400	100,000	100	2,700,000		43,400	100,000	100	
<b>EPA Method 2320B</b>																						
Alkalinity		393,000		790	5,000	1	2,340,000		790	5,000	1	2,000,000	B	790	5,000	1	2,440,000		790	5,000	1	
<b>EPA Method SM2340B</b>																						
Hardness as Calcium Carbonate		2,120,000		100	500	1	2,430,000		100	500	1	2,980,000		100	500	1	2,720,000		100	500	1	
<b>EPA Method SM5210B</b>																						
Biochemical Oxygen Demand		U	2,000	2,000	1	NS				NS				NS				NS				

**NOTES:**

All values reported as ug/L (parts per billion)

**Bold and heavy outlined cells indicate and exceedance of applicable groundwater standard or guidance value**

U – Analyzed for but not detected above laboratory detection limits

J – Indicates an estimated value

H – Sample was prepped or analyzed beyond the specified holding time

B – Analyte detected in the associated laboratory blank

b – Result detected in the USB

NS – Not sampled

NA – Not analyzed for

D.L. – Laboratory detection limit

R.L. – Laboratory reporting limit

D.F. – Laboratory dilution factor

<sup>a</sup> - Reported as 1,2-Dichloroethene, Total is previous laboratory reports

Feb-11, Mar-11, and Apr-11 data represents pilot test baseline, 1<sup>st</sup> post-pilot test sampling event, and 2<sup>nd</sup> post-pilot test sampling event, respectively

Jun-11, Aug-11, and Sep-11 data represents full scale ISCR injection baseline, 1<sup>st</sup> post-ISCR sampling event, and 2<sup>nd</sup> post-ISCR sampling event, respectively

<sup>a</sup> - GW Std – Class GA Groundwater Quality Standard or Guidance Value from New York State Department of Environmental Conservation (NYSDEC) Division of Water

Technical and Operational Guidance Series (June 1998).



**110 LUTHER AVENUE BCP SITE (BCP SITE #C734118)**  
**PERIODIC REVIEW REPORT**  
**TABLE 2: SUMMARY OF GROUNDWATER ANALYTICAL RESULTS**  
**PAGE 13 OF 19**

Analyte	GW Std <sup>a</sup> (ug/L)	MW-13																										
		Mar-08			Feb-10			Jun-11			Aug-11			Sep-11			Mar-12			Jun-12			Sep-12					
		D.L.		D.L.		D.L.		D.L.		D.L.		D.L.	R.L.	D.F.		D.L.	R.L.	D.F.		D.L.	R.L.	D.F.		D.L.	R.L.	D.F.		
<b>EPA Method 8260B</b>																												
Tetrachloroethene	5	900		410		1,300		2,500		2,800		1,900	36	100	100	2,400	36	100	100	3,300	36	100	100					
Trichloroethene	5	470		600		1,300		1,800		2,000		1,300	46	100	100	1,400	46	100	100	1,900	46	100	100					
cis-1,2-dichloroethene	5	NS		780		12,000		11,000		7,800		8,900	81	100	100	9,200	160	200	200	9,700	81	100	100					
trans-1,2-dichloroethene	5	U 100	12 J		U 150		U 150		U 76		14	0.90	1	1	U	90	100	100	U	90	100	100						
Vinyl chloride	2	U 100	29		300 J		220 J		140 J		470	90	100	100	290	90	100	100	440	90	100	100						
<b>EPA Method RSK-175</b>																												
Ethane		NS		NS		9.3		4		U 4		14	0.49	1.5	1	U	47	360	50	U	4.9	75	10					
Ethene		NS		NS		24		10		6.6		39	0.52	1.5	1	U	60	340	50	U	5.2	70	10					
Methane		NS		NS		230		160		91		360	22	100	100	430	66	190	50	420	2.2	40	10					
<b>EPA Method 6010B (total)</b>																												
Calcium		NS		NS		130,000		97,000		96,900		334,000 B	100	500	1	111,000	100	500	1	878,000	100	500	1					
Iron	300	NS		NS		103,000		25,600		28,500		116,000	19	50	1	23,900	19	50	1	275,000	19	50	1					
Magnesium	35,000	NS		NS		37,900		29,800		30,500		115,000	43	200	1	36,800	43	200	1	224,000	43	200	1					
Manganese	300	NS		NS		757		201		236		2,000 B	0.4	3	1	250	0.4	3	1	6,700	0.4	3	1					
<b>EPA Method 6010B (dissolved)</b>																												
Iron	300	NS		NS		NS		NS		NS		NS				NS				NS								
<b>EPA Method 300</b>																												
Nitrate as N	10,000	NS		NS		190		U 33		U 33		U 11	50	1	U	11	50	1	U	11	50	1						
Sulfate	250,000	NS		NS		10,400		8,700		9,400		8,900	350	2,000	1	10,200	350	2,000	1	8,900	700	4,000	2					
Chloride	250,000	NS		NS		114,000		119,000		115,000		112,000	560	1,000	2	113,000	560	1,000	2	117,000	560	1,000	2					
<b>EPA Method SM5310C</b>																												
Dissolved Organic Carbon - Quad		NS		NS		560 J		410 J		580 J		3,000	430	1,000	1	2,800	430	1,000	1	5,200	430	1,000	1					
Total Organic Carbon - Quad		NS		NS		1,500		U 230		U 230		2,900	430	1,000	1	820 J	430	1,000	1	2,500	430	1,000	1					
<b>EPA Method 2320B</b>																												
Alkalinity		NS		NS		246,000		260,000 B		264,000		233,000	790	5,000	1	258,000 B	790	5,000	1	265,000	790	5,000	1					
<b>EPA Method SM2340B</b>																												
Hardness as Calcium Carbonate		NS		NS		480,000		365,000		368,000		1,310,000	100	500	1	429,000	100	500	1	3,110,000	100	500	1					
<b>EPA Method SM5210B</b>																												
Biochemical Oxygen Demand		NS		NS		10,200		660 J		1,100 J		2,900 H	2,000	2,000	1	2,600	2,000	2,000	1	UH	2,000	2,000	1					

**NOTES:**

All values reported as ug/L (parts per billion)

**Bold and heavy outlined cells indicate and exceedance of applicable groundwater standard or guidance value**

U – Analyzed for but not detected above laboratory detection limits

J – Indicates an estimated value

H – Sample was prepped or analyzed beyond the specified holding time

B – Analyte detected in the associated laboratory blank

b – Result detected in the USB

NS – Not sampled

NA – Not analyzed for

D.L. – Laboratory detection limit

R.L. – Laboratory reporting limit

D.F. – Laboratory dilution factor

<sup>a</sup> - Reported as 1,2-Dichloroethene, Total is previous laboratory reports

Feb-11, Mar-11, and Apr-11 data represents pilot test baseline, 1<sup>st</sup> post-pilot test sampling event, and 2<sup>nd</sup> post-pilot test sampling event, respectively

Jun-11, Aug-11, and Sep-11 data represents full scale ISCR injection baseline, 1<sup>st</sup> post-ISCR sampling event, and 2<sup>nd</sup> post-ISCR sampling event, respectively

<sup>a</sup> - GW Std – Class GA Groundwater Quality Standard or Guidance Value from New York State Department of Environmental Conservation (NYSDEC) Division of Water Technical and Operational Guidance Series (June 1998).



**110 LUTHER AVENUE BCP SITE (BCP SITE #C734118)**  
**PERIODIC REVIEW REPORT**  
**TABLE 2: SUMMARY OF GROUNDWATER ANALYTICAL RESULTS**  
**PAGE 14 OF 19**

Analyte	GW Std <sup>a</sup> (ug/L)	MW-13																							
		Dec-12				Mar-13				Jun-13				Sep-13				Dec-13							
		D.L.	R.L.	D.F.		D.L.	R.L.	D.F.		D.L.	R.L.	D.F.		D.L.	R.L.	D.F.		D.L.	R.L.	D.F.					
<b>EPA Method 8260B</b>																									
Tetrachloroethene	5	5,100	36	100	100	4,600	36	100	100	4,100	36	100	100	4,000	72	200	200	2,100	72	200	200				
Trichloroethene	5	2,600	46	100	100	2,500	46	100	100	2,300	46	100	100	2,100	92	200	200	1,100	92	200	200				
cis-1,2-dichloroethene	5	8,400	81	100	100	9,600	81	100	100	11,000	160	200	200	11,000	160	200	200	16,000	160	200	200				
trans-1,2-dichloroethene	5	U	90	100	100	U	90	100	100	U	90	100	100	U	180	200	200	U	180	200	200				
Vinyl chloride	2	480	90	100	100	500	90	100	100	220	90	100	100	450	180	200	200	370	180	200	200				
<b>EPA Method RSK-175</b>																									
Ethane		U	4.9	75	10	16	J	4.9	75	10	U	4.9	75	10	U	4.9	75	10	U	15	75	10			
Ethene		U	5.2	70	10	27	J	5.2	70	10	10	J	5.2	70	10	9.3	J	5.2	70	10	25	J	15	70	10
Methane		320	2.2	40	1	290		2.2	40	10	88		2.2	40	10	75		2.2	40	10	140		10	40	10
<b>EPA Method 6010B (total)</b>																									
Calcium		116,000	100	500	1	NA		NA		NA		NA		NA		NA		NA		NA					
Iron	300	29,300	19	50	1	347,000	19	50	1	35,900	19	50	1	56,300	19	50	1	891,000	97	250	5				
Magnesium	35,000	39,600	43	200	1	NA		NA		NA		NA		NA		NA		NA		NA					
Manganese	300	390	0.4	3	1	NA		NA		NA		NA		NA		NA		NA		NA					
<b>EPA Method 6010B (dissolved)</b>																									
Iron	300	NS				7,800	19	50	1	12,700	19	50	1	12,200	19	50	1	75,500	19	50	1				
<b>EPA Method 300</b>																									
Nitrate as N	10,000	U	11	50	1	46	JH	20	50	1	U	20	50	1	U	20	50	1	U	20	50	1			
Sulfate	250,000	7,400	700	4,000	2	9,200		700	4,000	2	9,200		700	4,000	2	12,000		700	4,000	2	11,200		700	4,000	2
Chloride	250,000	109,000	560	1,000	2	126,000		560	1,000	2	146,000		560	1,000	2	132,000		560	1,000	2	140,000		560	1,000	2
<b>EPA Method SM5310C</b>																									
Dissolved Organic Carbon - Quad		4,600	430	1,000	1	2,500		430	1,000	1	5,900		430	1,000	1	1,900		430	1,000	1	349,000		17,400	40,000	40
Total Organic Carbon - Quad		1,300	430	1,000	1	4,200		430	1,000	1	3,700		430	1,000	1	2,000		430	1,000	1	310,000		4,300	10,000	10
<b>EPA Method 2320B</b>																									
Alkalinity		240,000	790	5,000	1	249,000		790	5,000	1	238,000		790	5,000	1	250,000		790	5,000	1	480,000		1,600	10,000	1
<b>EPA Method SM2340B</b>																									
Hardness as Calcium Carbonate		452,000	100	500	1	3,330,000		100	500	1	1,760,000		100	500	1	1,310,000		100	500	1	5,240,000		100	500	1
<b>EPA Method SM5210B</b>																									
Biochemical Oxygen Demand		2,200	b	2,000	2,000	1	NS		NS		NS		NS		NS		NS		NS		NS				

**NOTES:**

All values reported as ug/L (parts per billion)

**Bold and heavy outlined cells indicate and exceedance of applicable groundwater standard or guidance value**

U – Analyzed for but not detected above laboratory detection limits

J – Indicates an estimated value

H – Sample was prepped or analyzed beyond the specified holding time

B – Analyte detected in the associated laboratory blank

b – Result detected in the USB

NS – Not sampled

NA – Not analyzed for

D.L. – Laboratory detection limit

R.L. – Laboratory reporting limit

D.F. – Laboratory dilution factor

\* - Reported as 1,2-Dichloroethene, Total is previous laboratory reports

Feb-11, Mar-11, and Apr-11 data represents pilot test baseline, 1<sup>st</sup> post-pilot test sampling event, and 2<sup>nd</sup> post-pilot test sampling event, respectively

Jun-11, Aug-11, and Sep-11 data represents full scale ISCR injection baseline, 1<sup>st</sup> post-ISCR sampling event, and 2<sup>nd</sup> post-ISCR sampling event, respectively

<sup>a</sup> - GW Std – Class GA Groundwater Quality Standard or Guidance Value from New York State Department of Environmental Conservation (NYSDEC) Division of Water

Technical and Operational Guidance Series (June 1998).



**110 LUTHER AVENUE BCP SITE (BCP SITE #C734118)**  
**PERIODIC REVIEW REPORT**  
**TABLE 2: SUMMARY OF GROUNDWATER ANALYTICAL RESULTS**  
**PAGE 15 OF 19**

Analyte	GW Std <sup>A</sup> (ug/L)	MW-17											
		Feb-10	Feb-11	Mar-11	Apr-11	Jun-11	Aug-11	Sep-11					
<b>EPA Method 8260B</b>		D.L.	D.L.	D.L.	D.L.	D.L.	D.L.	D.L.	D.L.	D.L.	D.L.	D.L.	D.L.
Tetrachloroethene	5	<b>14,000</b>	<b>8,800</b>	<b>6,300</b>	<b>6,900</b>	<b>7,600</b>	U 200	U 81					
Trichloroethene	5	<b>2,000</b>	<b>1,400</b>	<b>1,200</b>	<b>1,800</b>	<b>1,000</b>	U 160	U 62					
cis-1,2-dichloroethene	5	<b>750</b>	<b>1,000</b>	<b>780</b>	<b>1,400</b>	<b>940</b>	<b>21,000</b>	<b>12,000</b>					
trans-1,2-dichloroethene	5	U 76	U 76	U 30	U 38	U 76	U 190	U 76					
Vinyl chloride	2	U 99	U 99	U 40	U 50	U 99	<b>360 J</b>	<b>1,800</b>					
<b>EPA Method RSK-175</b>													
Ethane		NS	U 4	U 4	U 4	U 4	U 40	U 40					
Ethene		NS	U 3	U 3	U 3	U 3	U 30	41					
Methane		NS	11	27	9.5	32	2,100	2,100					
<b>EPA Method 6010B (total)</b>													
Calcium		NS	295,000	126,000	341,000	89,600	465,000	387,000					
Iron	300	NS	<b>50,000</b>	<b>13,200</b>	<b>36,400</b>	<b>924</b>	<b>89,200</b>	<b>58,900</b>					
Magnesium	35,000	NS	<b>102,000</b>	<b>35,500</b>	<b>110,000</b>	<b>21,100</b>	<b>81,500</b>	<b>85,400</b>					
Manganese	300	NS	<b>2,080</b>	<b>737</b>	<b>2,210</b>	<b>521</b>	<b>6,710</b>	<b>4,530</b>					
<b>EPA Method 6010B (dissolved)</b>													
Iron	300	NS	NS	NS	NS	NS	NS	NS					
<b>EPA Method 300</b>													
Nitrate as N	10,000	NS	U 33	U 33	U 33	U 33	U 33	UH 330					
Sulfate	250,000	NS	97,000	84,200	101,000	212,000	31,000	21,700					
Chloride	250,000	NS	193,000	213,000	222,000	89,700.0	169,000	<b>279,000</b>					
<b>EPA Method SM5310C</b>													
Dissolved Organic Carbon - Quad		NS	U 230	U 230	U 230	U 230	804,000	415,000					
Total Organic Carbon - Quad		NS	U 230	U 230	U 230	U 230	813,000	457,000					
<b>EPA Method 2320B</b>													
Alkalinity		NS	245,000	249,000	258,000	247,000	1,150,000 B	889,000					
<b>EPA Method SM2340B</b>													
Hardness as Calcium Carbonate		NS	1,160,000	461,000	1,300,000	310,000	1,500,000	1,320,000					
<b>EPA Method SM5210B</b>													
Biochemical Oxygen Demand		NS	U 650	U 650	U 650	1,400 J	>1,743,000	717,000					

**NOTES:**

All values reported as ug/L (parts per billion)

**Bold and heavy outlined cells indicate and exceedance of applicable groundwater standard or guidance value**

U – Analyzed for but not detected above laboratory detection limits

J – Indicates an estimated value

H – Sample was prepped or analyzed beyond the specified holding time

B – Analyte detected in the associated laboratory blank

b – Result detected in the USB

NS – Not sampled

NA – Not analyzed for

D.L. – Laboratory detection limit

R.L. – Laboratory reporting limit

D.F. – Laboratory dilution factor

<sup>A</sup> - Reported as 1,2-Dichloroethene, Total is previous laboratory reports

Feb-11, Mar-11, and Apr-11 data represents pilot test baseline, 1<sup>st</sup> post-pilot test sampling event, and 2<sup>nd</sup> post-pilot test sampling event, respectively

Jun-11, Aug-11, and Sep-11 data represents full scale ISCR injection baseline, 1<sup>st</sup> post-ISCR sampling event, and 2<sup>nd</sup> post-ISCR sampling event, respectively

<sup>A</sup> - GW Std – Class GA Groundwater Quality Standard or Guidance Value from New York State Department of Environmental Conservation (NYSDEC) Division of Water

Technical and Operational Guidance Series (June 1998).



**110 LUTHER AVENUE BCP SITE (BCP SITE #C734118)**  
**PERIODIC REVIEW REPORT**  
**TABLE 2: SUMMARY OF GROUNDWATER ANALYTICAL RESULTS**  
**PAGE 16 OF 19**

Analyte	GW Std <sup>a</sup> (ug/L)	MW-17																
		Mar-12				Jun-12				Sep-12				Dec-12				
		D.L.	R.L.	D.F.		D.L.	R.L.	D.F.		D.L.	R.L.	D.F.		D.L.	R.L.	D.F.		
<b>EPA Method 8260B</b>																		
Tetrachloroethene	5	9.7	1.8	5	5	3.6	0.38	1	1	U	18	50	50	U	18	50	50	
Trichloroethene	5	6.5	2.3	5	5	7.0	0.46	1	1	U	23	50	50	U	23	50	50	
cis-1,2-dichloroethene	5	2,700	41	50	50	4,300	65	80	80	3,500	41	50	50	3,800	41	50	50	
trans-1,2-dichloroethene	5	6.6	4.5	5	5	U	0.90	1	1	U	45	50	50	U	45	50	50	
Vinyl chloride	2	990	45	50	50	1,800	72	80	80	1,200	45	50	50	2,100	45	50	50	
<b>EPA Method RSK-175</b>																		
Ethane		260	0.49	1.5	1	400	47	360	50	470	9.8	150	20	490	25	380	50	
Ethene		160	52	150	100	460	60	340	50	390	10	140	20	560	26	350	50	
Methane		4,000	22	100	100	11,000	260	780	200	5,100	44	800	200	6,800	11	200	50	
<b>EPA Method 6010B (total)</b>																		
Calcium		256,000	B	100	500	1	242,000	100	500	1	295,000	100	500	1	254,000	100	500	1
Iron	300	22,500	19	50	1	24,800	19	50	1	41,200	19	50	1	23,400	19	50	1	
Magnesium	35,000	63,600	43	200	1	65,400	43	200	1	87,600	43	200	1	68,400	43	200	1	
Manganese	300	2,500	B	0.4	3	1	2,100	0.4	3	1	2,200	0.4	3	1	1,700	0.4	3	1
<b>EPA Method 6010B (dissolved)</b>																		
Iron	300	NS				NS				NS				NS				
<b>EPA Method 300</b>																		
Nitrate as N	10,000	U	11	50	1	U	11	50	1	U	11	50	1	36	J	11	50	1
Sulfate	250,000	28,000	1,700	10,000	5	28,800	1,700	#####	5	10,200	1,700	10,000	5	2,100		350	2,000	1
Chloride	250,000	260,000	1,400	2,500	5	253,000	1,400	2,500	5	280,000	1,400	2,500	5	234,000		1,400	2,500	5
<b>EPA Method SM5310C</b>																		
Dissolved Organic Carbon - Quad		6,600	430	1,000	1	20,300	430	1,000	1	2,600	430	1,000	1	35,600	430	1,000	1	
Total Organic Carbon - Quad		34,100	430	1,000	1	15,100	430	1,000	1	26,200	430	1,000	1	51,500	430	1,000	1	
<b>EPA Method 2320B</b>																		
Alkalinity		760,000	790	5,000	1	792,000	B	790	5,000	1	787,000	790	5,000	1	770,000	790	5,000	1
<b>EPA Method SM2340B</b>																		
Hardness as Calcium Carbonate		901,000	100	500	1	874,000	100	500	1	1,100,000	100	500	1	917,000	100	500	1	
<b>EPA Method SM5210B</b>																		
Biochemical Oxygen Demand		49,000	2,000	2,000	1	47,300	2,000	2,000	1	55,200	2,000	2,000	1	80,600	2,000	2,000	1	

**NOTES:**

All values reported as ug/L (parts per billion)

**Bold and heavy outlined cells indicate and exceedance of applicable groundwater standard or guidance value**

U – Analyzed for but not detected above laboratory detection limits

J – Indicates an estimated value

H – Sample was prepped or analyzed beyond the specified holding time

B – Analyte detected in the associated laboratory blank

b – Result detected in the USB

NS – Not sampled

NA – Not analyzed for

D.L. – Laboratory detection limit

R.L. – Laboratory reporting limit

D.F. – Laboratory dilution factor

<sup>a</sup> - Reported as 1,2-Dichloroethene, Total is previous laboratory reports

Feb-11, Mar-11, and Apr-11 data represents pilot test baseline, 1<sup>st</sup> post-pilot test sampling event, and 2<sup>nd</sup> post-pilot test sampling event, respectively

Jun-11, Aug-11, and Sep-11 data represents full scale ISCR injection baseline, 1<sup>st</sup> post-ISCR sampling event, and 2<sup>nd</sup> post-ISCR sampling event, respectively

<sup>a</sup> - GW Std – Class GA Groundwater Quality Standard or Guidance Value from New York State Department of Environmental Conservation (NYSDEC) Division of Water

Technical and Operational Guidance Series (June 1998).





**110 LUTHER AVENUE BCP SITE (BCP SITE #C734118)**  
**PERIODIC REVIEW REPORT**  
**TABLE 2: SUMMARY OF GROUNDWATER ANALYTICAL RESULTS**  
**PAGE 17 OF 19**

Analyte	GW Std <sup>a</sup> (ug/L)	MW-17																			
		Mar-13				Jun-13				Sep-13				Dec-13							
		D.L.	R.L.	D.F.		D.L.	R.L.	D.F.		D.L.	R.L.	D.F.		D.L.	R.L.	D.F.					
<b>EPA Method 8260B</b>																					
Tetrachloroethene	5	U	3.6	10	10	U	3.6	10	10	U	3.6	10	10	U	3.6	10	10				
Trichloroethene	5	U	4.6	10	10	U	4.6	10	10	U	4.6	10	10	U	4.6	10	10				
cis-1,2-dichloroethene	5	570	8.1	10	10	560	8.1	10	10	360	8.1	10	10	2,400	32	40	40				
trans-1,2-dichloroethene	5	U	9.0	10	10	U	9	10	10	U	9	10	10	14	9	10	10				
Vinyl chloride	2	410	9.0	10	10	320	9	10	10	470	9	10	10	1,200	36	40	40				
<b>EPA Method RSK-175</b>																					
Ethane		450	25	380	50	U	25	380	50	U	25	380	50	130	J	75	380	50			
Ethene		400	26	350	50	86	J	26	350	50	41	J	26	350	50	210	J	75	350	50	
Methane		5,100	11	200	50	1,200		11	200	50	2,800		11	200	50	12,000		200	800	200	
<b>EPA Method 6010B (total)</b>																					
Calcium		NA				NA				NA				NA							
Iron	300	62,200	19	50	1	121,000	19	50	1	170,000	19	50	1	63,200	19	50	1				
Magnesium	35,000	NA				NA				NA				NA							
Manganese	300	NA				NA				NA				NA							
<b>EPA Method 6010B (dissolved)</b>																					
Iron	300	21,600	19	50	1	131,000	19	50	1	131,000	19	50	1	53,400	19	50	1				
<b>EPA Method 300</b>																					
Nitrate as N	10,000	44	JH	20	50	1	U	20	50	1	25	J	20	50	1	U	20	50	1		
Sulfate	250,000	6,500		350	2,000	1	U	350	2,000	1	3,200	J	1,700	10,000	5	U	350	2,000	1		
Chloride	250,000	228,000		1,400	2,500	5	234,000		1,400	2,500	5	271,000		1,400	2,500	5	252,000		1,400	2,500	5
<b>EPA Method SM5310C</b>																					
Dissolved Organic Carbon - Quad		41,800		430	1,000	1	1,120,000		17,400	40,000	40	755,000		17,400	40,000	40	266,000		17,400	40,000	40
Total Organic Carbon - Quad		42,000		430	1,000	1	947,000		17,400	40,000	40	705,000		17,400	40,000	40	232,000		17,400	40,000	40
<b>EPA Method 2320B</b>																					
Alkalinity		830,000		790	5,000	1	1,550,000	B	790	5,000	1	1,960,000		790	5,000	1	1,320,000		790	5,000	1
<b>EPA Method SM2340B</b>																					
Hardness as Calcium Carbonate		1,430,000		100	500	1	1,860,000		100	500	1	2,730,000		100	500	1	1,290,000		100	500	1
<b>EPA Method SM5210B</b>																					
Biochemical Oxygen Demand		NS				NS				NS				NS							

**NOTES:**

All values reported as ug/L (parts per billion)

**Bold and heavy outlined cells indicate and exceedance of applicable groundwater standard or guidance value**

U – Analyzed for but not detected above laboratory detection limits

J – Indicates an estimated value

H – Sample was prepped or analyzed beyond the specified holding time

B – Analyte detected in the associated laboratory blank

b – Result detected in the USB

NS – Not sampled

NA – Not analyzed for

D.L. – Laboratory detection limit

R.L. – Laboratory reporting limit

D.F. – Laboratory dilution factor

<sup>^</sup> - Reported as 1,2-Dichloroethene, Total is previous laboratory reports

Feb-11, Mar-11, and Apr-11 data represents pilot test baseline, 1<sup>st</sup> post-pilot test sampling event, and 2<sup>nd</sup> post-pilot test sampling event, respectively

Jun-11, Aug-11, and Sep-11 data represents full scale ISCR injection baseline, 1<sup>st</sup> post-ISCR sampling event, and 2<sup>nd</sup> post-ISCR sampling event, respectively

<sup>^</sup> - GW Std – Class GA Groundwater Quality Standard or Guidance Value from New York State Department of Environmental Conservation (NYSDEC) Division of Water

Technical and Operational Guidance Series (June 1998).



**110 LUTHER AVENUE BCP SITE (BCP SITE #C734118)**  
**PERIODIC REVIEW REPORT**  
**TABLE 2: SUMMARY OF GROUNDWATER ANALYTICAL RESULTS**  
**PAGE 18 OF 19**

Analyte	GW Std <sup>a</sup> (ug/L)	DUPLICATE																		
		Feb-10 (MW-8)		Feb-11 (MW-17)		Mar-11 (MW-17)		Apr-11 (MW-17)		Jun-11 (MW-8)		Aug-11 (MW-8)		Sep-11 (MW-8)		Mar-12 (MW-10)		Jun-12 (MW-8)		
EPA Method 8260B		D.L.	D.L.	D.L.	D.L.	D.L.	D.L.	D.L.	D.L.	D.L.	D.L.	D.L.	D.L.	D.L.	D.L.	R.L.	R.L.	R.L.	R.L.	
Tetrachloroethene	5	3,500	14,000	4,000	11,000	1,700	330	500	J	U	0.36	1	3,000	29	80					
Trichloroethene	5	900	2,700	1,000	2,000	570	130	J	220	J	U	0.46	1	1,300	37	80				
cis-1,2-dichloroethene	5	2,500	1,900	740	1,200	1,800	3,900	5,500		54	0.81	1	6,500	65	80					
trans-1,2-dichloroethene	5	U	30	U	150	U	30	U	76	U	19	80	J	87	J	U	0.90	1	U	
Vinyl chloride	2	270	U	200	U	40	U	99	220	2,900	3,400	12	0.90	1	2,000	72	80			
EPA Method RSK-175																				
Ethane		NS	U	4	U	4	U	4	U	20	21	25	U	0.49	1.5	U	47	360		
Ethene		NS	U	3	U	3	U	3	U	15	320	640	1.2	J	0.52	1.5	U	60	340	
Methane		NS	23	24	8.7	390	1,000	1,100	21	0.22	1	3,500	66	190						
EPA Method 6010B (total)																				
Calcium		NS	305,000	128,000	324,000	200,000	265,000	282,000	171,000	B	100	500	210,000	100	500					
Iron	300	NS	52,400	14,100	32,900	5,460	33,300	43,400	8,600	19	50	10,800	19	50						
Magnesium	35,000	NS	106,000	36,200	100,000	62,100	77,000	82,400	60,200	43	200	71,400	43	200						
Manganese	300	NS	2,160	762	2,100	1,960	3,870	3,740	330	B	0.4	3	1,900	0.4	3					
EPA Method 6010B (dissolved)																				
Iron	300	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS						
EPA Method 300																				
Nitrate as N	10,000	NS	U	33	U	33	U	33	U	33	U	33	U	33	U	11	50	U	11	50
Sulfate	250,000	NS	97,800	83,200	99,800	81,000.0	4,400	4000.0	26,400	350	2,000	25,100	350	2,000						
Chloride	250,000	NS	196,000	209,000	222,000	433,000	469,000	468,000	180,000	1,400	2,500	419,000	1,400	2,500						
EPA Method SM5310C																				
Dissolved Organic Carbon - Quad		NS	U	230	U	230	U	230	U	230	164,000	198,000	2,900	430	1,000	2,900	430	1,000		
Total Organic Carbon - Quad		NS	U	230	U	230	U	230	U	230	172,000	177,000	1,000	430	1,000	2,700	430	1,000		
EPA Method 2320B																				
Alkalinity		NS	251,000	248,000	257,000	381,000	638,000	B	645,000	B	333,000	790	5,000	466,000	B	790	5,000			
EPA Method SM2340B																				
Hardness as Calcium Carbonate		NS	1,200,000	469,000	1,220,000	756,000	978,000	1,040,000	674,000	100	500	818,000	100	500						
EPA Method SM5210B																				
Biochemical Oxygen Demand		NS	U	650	U	650	U	650	4,000	363,000	>213,600	U	2,000	2,000	8,900	b	2,000	2,000		

**NOTES:**

All values reported as ug/L (parts per billion)

**Bold and heavy outlined cells indicate and exceedance of applicable groundwater standard or guidance value**

U – Analyzed for but not detected above laboratory detection limits

J – Indicates an estimated value

H – Sample was prepped or analyzed beyond the specified holding time

B – Analyte detected in the associated laboratory blank

b – Result detected in the USB

NS – Not sampled

NA – Not analyzed for

D.L. – Laboratory detection limit

R.L. – Laboratory reporting limit

D.F. – Laboratory dilution factor

<sup>a</sup> - Reported as 1,2-Dichloroethene, Total is previous laboratory reports

Feb-11, Mar-11, and Apr-11 data represents pilot test baseline, 1<sup>st</sup> post-pilot test sampling event, and 2<sup>nd</sup> post-pilot test sampling event, respectively

Jun-11, Aug-11, and Sep-11 data represents full scale ISCR injection baseline, 1<sup>st</sup> post-ISCR sampling event, and 2<sup>nd</sup> post-ISCR sampling event, respectively

<sup>a</sup> - GW Std – Class GA Groundwater Quality Standard or Guidance Value from New York State Department of Environmental Conservation (NYSDEC) Division of Water

Technical and Operational Guidance Series (June 1998).



**110 LUTHER AVENUE BCP SITE (BCP SITE #C734118)**  
**PERIODIC REVIEW REPORT**  
**TABLE 2: SUMMARY OF GROUNDWATER ANALYTICAL RESULTS**  
**PAGE 19 OF 19**

Analyte	GW Std <sup>A</sup> (ug/L)	DUPLICATE																							
		Sep-12 (MW-8)				Dec-12 (MW-19)				Mar-13 (MW-7)				Jun-13 (MW-8)				Sep-13 (MW-8)				Dec-13 (MW-8)			
		D.L.	R.L.			D.L.	R.L.			D.L.	R.L.			D.L.	R.L.			D.L.	R.L.			D.L.	R.L.		
<b>EPA Method 8260B</b>																									
Tetrachloroethene	5	6,800	72	200		U	0.36	1		U	140	400	17	J	14	40		U	14	40		U	14	40	
Trichloroethene	5	1,500	92	200		U	0.46	1		U	180	400		U	18	40		U	18	40		U	18	40	
cis-1,2-dichloroethene	5	7,000	160	200		U	0.81	1	16,000	320	400	2,100		32	40	140		32	40		U	32	40		
trans-1,2-dichloroethene	5	34	0.90	1		U	0.90	1		U	360	400		U	36	40		U	36	40		U	36	40	
Vinyl chloride	2	2,200	180	200		U	0.90	1	6,600	360	400	2,200		36	40	81		36	40		110		36	40	
<b>EPA Method RSK-175</b>																									
Ethane		U	25	380		U	0.49	7.5	470	25	380		U	25	380		U	25	380		U	75	380		
Ethene	46	J	26	350		U	0.52	7	1,400	26	350	62	J	26	350		U	26	350		U	75	350		
Methane	4,200	11	200		62		0.22	4	4,800	11	200	1,300		11	200	1,400		11	200		3,200		50	200	
<b>EPA Method 6010B (total)</b>																									
Calcium		228,000	100	500	44,200		100	500	NA			NA				NA				NA					
Iron	300	14,200	19	50	3,200		19	50	63,100	19	50	593,000	19	50	327,000	19	50	90,400		19	50				
Magnesium	35,000	77,700	43	200	8,300		43	200	NA			NA				NA				NA					
Manganese	300	1,600	0.4	3	180		0.4	3	NA			NA				NA				NA					
<b>EPA Method 6010B (dissolved)</b>																									
Iron	300	NS			NS				16,800	19	50	552,000	B	19	50	281,000	19	50	95,300		19	50			
<b>EPA Method 300</b>																									
Nitrate as N	10,000	35	J	11	50	60		11	50	23	J	20	50		U	20	50		U	20	50	28	J	20	50
Sulfate	250,000	74,200	1,700	10,000	27,000		1,700	10,000	14,100	1,700	10,000	18,700		1,700	10,000		U		700	4,000		U	700	4,000	
Chloride	250,000	407,000	1,400	2,500	151,000		1,400	2,500	309,000	1,400	2,500	406,000		1,400	2,500	607,000		5,600	10,000		542,000		2,800	5,000	
<b>EPA Method SM5310C</b>																									
Dissolved Organic Carbon - Quad		5,800		430	1,000	3,900		430	1,000	121,000		4,300	10,000	2,620,000		43,400	100,000	1,550,000		43,400	100,000	288,000		43,400	100,000
Total Organic Carbon - Quad		710	J	430	1,000	3,700		430	1,000	126,000		4,300	10,000	2,490,000		43,400	100,000	1,500,000		43,400	100,000	252,000		43,400	100,000
<b>EPA Method 2320B</b>																									
Alkalinity		419,000		790	5,000	207,000		790	5,000	589,000		790	5,000	1,900,000	B	790	5,000	2,330,000		790	5,000	1,770,000		790	5,000
<b>EPA Method SM2340B</b>																									
Hardness as Calcium Carbonate		888,000		100	500	144,000		100	500	1,500,000		100	500	2,860,000		100	500	2,440,000		100	500	2,130,000		100	500
<b>EPA Method SM5210B</b>																									
Biochemical Oxygen Demand		5,900		2,000	2,000		U	2,000	2,000	NS			NS			NS			NS			NS			

**NOTES:**

All values reported as ug/L (parts per billion)

**Bold and heavy outlined cells indicate and exceedance of applicable groundwater standard or guidance value**

U – Analyzed for but not detected above laboratory detection limits

J – Indicates an estimated value

H – Sample was prepped or analyzed beyond the specified holding time

B – Analyte detected in the associated laboratory blank

b – Result detected in the USB

NS – Not sampled

NA – Not analyzed for

D.L. – Laboratory detection limit

R.L. – Laboratory reporting limit

D.F. – Laboratory dilution factor

<sup>A</sup> - Reported as 1,2-Dichloroethene, Total is previous laboratory reports

Feb-11, Mar-11, and Apr-11 data represents pilot test baseline, 1<sup>st</sup> post-pilot test sampling event, and 2<sup>nd</sup> post-pilot test sampling event, respectively

Jun-11, Aug-11, and Sep-11 data represents full scale ISCR injection baseline, 1<sup>st</sup> post-ISCR sampling event, and 2<sup>nd</sup> post-ISCR sampling event, respectively

<sup>A</sup> - GW Std – Class GA Groundwater Quality Standard or Guidance Value from New York State Department of Environmental Conservation (NYSDEC) Division of Water

Technical and Operational Guidance Series (June 1998).

## **Appendices**

# **Appendix A** - Institutional and Engineering Controls Certification Form



Enclosure 2  
NEW YORK STATE DEPARTMENT OF ENVIRONMENTAL CONSERVATION  
Site Management Periodic Review Report Notice  
Institutional and Engineering Controls Certification Form



Site Details		Box 1
Site No.	C734118	
Site Name 110 Luther Ave. Site		
Site Address: 110 Luther Avenue	Zip Code: 13088	
City/Town: Liverpool		
County: Onondaga		
Site Acreage: 1.4		
Reporting Period: <del>March 17</del> , 2013 to March 17, 2014 July 1		
	YES	NO
1. Is the information above correct?	<input type="checkbox"/>	<input checked="" type="checkbox"/>
If NO, include handwritten above or on a separate sheet.		
2. Has some or all of the site property been sold, subdivided, merged, or undergone a tax map amendment during this Reporting Period?	<input type="checkbox"/>	<input checked="" type="checkbox"/>
3. Has there been any change of use at the site during this Reporting Period (see 6NYCRR 375-1.11(d))?	<input type="checkbox"/>	<input checked="" type="checkbox"/>
4. Have any federal, state, and/or local permits (e.g., building, discharge) been issued for or at the property during this Reporting Period?	<input type="checkbox"/>	<input checked="" type="checkbox"/>
If you answered YES to questions 2 thru 4, include documentation or evidence that documentation has been previously submitted with this certification form.		
5. Is the site currently undergoing development?	<input type="checkbox"/>	<input checked="" type="checkbox"/>

Box 2	
	YES NO
6. Is the current site use consistent with the use(s) listed below? Commercial and Industrial	<input checked="" type="checkbox"/> <input type="checkbox"/>
7. Are all ICs/ECs in place and functioning as designed? <i>The ICs/ECs were in place at the time of the PRR submittal as discussed in the PRR Report (GHD, April 2014)</i>	<input checked="" type="checkbox"/> <input type="checkbox"/>
IF THE ANSWER TO EITHER QUESTION 6 OR 7 IS NO, sign and date below and DO NOT COMPLETE THE REST OF THIS FORM. Otherwise continue.	
A Corrective Measures Work Plan must be submitted along with this form to address these issues.	
Signature of Owner, Remedial Party or Designated Representative	Date

**Box 2A**

YES NO

8. Has any new information revealed that assumptions made in the Qualitative Exposure Assessment regarding offsite contamination are no longer valid?

☐ ☒

If you answered YES to question 8, include documentation or evidence that documentation has been previously submitted with this certification form.

9. Are the assumptions in the Qualitative Exposure Assessment still valid?  
(The Qualitative Exposure Assessment must be certified every five years)

☒ ☐

If you answered NO to question 9, the Periodic Review Report must include an updated Qualitative Exposure Assessment based on the new assumptions.

**SITE NO. C734118****Box 3****Description of Institutional Controls**



<u>Parcel</u>	<u>Owner</u>	<u>Institutional Control</u>
085-12-04.1	Syracuse Label Co., Inc.	<p>Monitoring Plan</p> <p>IC/EC Plan</p> <p>Ground Water Use Restriction</p> <p>Site Management Plan</p> <p>Landuse Restriction</p> <p>O&amp;M Plan</p>
<p>A sub-slab depressurization system (SSDS) was installed in the existing Site building in 2011. The SSDS is a high vacuum system utilizing fourteen (14) suction points positioned at location shown on Figure 9. Photographs of the system installation are included in Appendix B of this SMP. The fourteen (14) suction points are identified herein, and will be referenced in the future, as S-1, S-2, S-3, and S-4 (clockwise around warehouse starting in the southwest corner); S-5, S-6, and S-7 (south to north along office area wall); S-8 and S-9 (northeastern rooms of building), and S-10, S-11, S-12, S-13, and S-14 (southeastern rooms of building).</p> <p>Each SSDS suction point consists of a 4 inch hole cored through the existing concrete slab. Each suction riser was constructed of 3 inch diameter schedule 40 polyvinyl chloride (PVC) piping. Each suction riser was connected to a single fan on the roof utilizing a trunk line network consisting of 4 inch diameter PVC piping. Each riser pipe is outfitted with a magnehelic pressure gauge, to allow for monitoring of system performance, and an interior baffle that can be adjusted to regulate airflow. All floor, wall, and roof penetrations were sealed with a VOC compliant urethane sealant. Design details are presented in the Operation and Maintenance Plan (Section 4 of this SMP).</p> <p>Procedures for monitoring the system, including inspections in the event that an identified severe condition occurs, are included in the Monitoring Plan (Section 3 of this SMP). Procedures for operating and maintaining the SSDS are documented in the Operation and Maintenance Plan (Section 4 of this SMP).</p>		
<p>A series of Institutional Controls is required by the RAWP to: (1) implement, maintain and monitor Engineering Control systems; (2) prevent future exposure to remaining contamination by controlling disturbances of the subsurface contamination; and, (3) limit the use and development of the Site to Commercial or Industrial uses only. Adherence to these Institutional Controls on the Site is required by the Environmental Easement and will be implemented under this Site Management Plan. These Institutional Controls are:</p> <ul style="list-style-type: none"> <li>• Compliance with the Environmental Easement and this SMP by the Grantor and the Grantor's successors and assigns;</li> <li>• All Engineering Controls must be operated and maintained as specified in this SMP;</li> <li>• All Engineering Controls on the Controlled Property must be inspected at a frequency and in a manner defined in the SMP;</li> <li>• Groundwater and other environmental or public health monitoring must be performed as defined in this SMP; and</li> <li>• Data and information pertinent to Site Management of the Controlled Property must be reported at the frequency and in a manner defined in this SMP.</li> </ul> <p>Institutional Controls identified in the Environmental Easement may not be discontinued without an amendment to or extinguishment of the Environmental Easement.</p> <p>The Site has a series of Institutional Controls in the form of Site restrictions. Adherence to these Institutional Controls is required by the Environmental Easement. Site restrictions that apply to the Controlled Property are:</p> <ul style="list-style-type: none"> <li>• The property may only be used for Commercial or Industrial use provided that the long-term Engineering and Institutional Controls included in this SMP are employed;</li> <li>• The property may not be used for a higher level of use, such as unrestricted, residential, or restricted residential use without additional remediation and amendment of the Environmental Easement, as approved by the NYSDEC;</li> <li>• All future activities on the property that will disturb remaining contaminated material must be conducted in accordance with this SMP and the Excavation Work Plan (Appendix C);</li> <li>• The use of the groundwater underlying the property is prohibited without treatment rendering it safe for intended use;</li> <li>• The potential for vapor intrusion must be evaluated for any buildings developed onsite, and any potential impacts that are identified must be monitored or mitigated;</li> <li>• Vegetable gardens and farming on the property are prohibited;</li> <li>• The Site owner or remedial party will submit to NYSDEC a written statement that certifies, under penalty of perjury, that: (1) controls employed at the Controlled Property are unchanged from the previous certification or that any changes to the controls were approved by the NYSDEC; and, (2)</li> </ul>		

nothing has occurred that impairs the ability of the controls to protect public health and environment or that constitute a violation or failure to comply with the SMP. NYSDEC retains the right to access such Controlled Property at any time in order to evaluate the continued maintenance of any and all controls. This certification shall be submitted annually, or an alternate period of time that NYSDEC may allow and will be made by an expert that the NYSDEC finds acceptable; and

- The Site owner is required to monitor whether there is a change in ownership of the adjacent property currently owned by The Brannock Device Company, located at 116 Luther Avenue. If a change in ownership occurs the current owner will need to be notified of the environmental conditions of the 110 Luther Avenue Site and afforded the option to evaluate the potential for soil vapor intrusion into the building. Notification must also be made to the NYSDEC if the adjacent property is sold or ownership is transferred.

#### 2.3.1 Excavation Work Plan

The Site has been remediated for commercial use. Any future intrusive work that will encounter or disturb the remaining contamination, including any modifications or repairs to the existing cover system will be performed in compliance with the Excavation Work Plan (EWP) that is attached as Appendix C to this SMP. Any work conducted pursuant to the EWP must also be conducted in accordance with the procedures defined in a Health and Safety Plan (HASP) and Community Air Monitoring Plan (CAMP) prepared for the Site. A sample HASP and CAMP are attached as Appendix D to this SMP that is in current compliance with DER-10, and 29 CFR 1910, 29 CFR 1926, and all other applicable Federal, State and local regulations. Based on future changes to State and federal health and safety requirements, and specific methods employed by future contractors, the HASP and CAMP will be updated and re-submitted with the notification provided in Section C-1 of the EWP. Any intrusive construction work will be performed in compliance with the EWP, HASP and CAMP, and will be included in the periodic inspection and certification reports submitted under the Site Management Reporting Plan (See Section 5).

The Site owner and associated parties preparing the remedial documents submitted to the State, and parties performing this work, are completely responsible for the safe performance of all intrusive work, the structural integrity of excavations, proper disposal of excavation de-water, control of runoff from open excavations into remaining contamination, and for structures that may be affected by excavations (such as building foundations and bridge footings). The Site owner will ensure that Site development activities will not interfere with, or otherwise impair or compromise, the engineering controls described in this SMP.

#### 2.3.2 Soil Vapor Intrusion Evaluation

Prior to the construction of any enclosed structures at the Site, an SVI evaluation will be performed to determine whether any mitigation measures are necessary to eliminate potential exposure to vapors in the proposed structure. Alternatively, an SVI mitigation system may be installed as an element of the building foundation without first conducting an investigation. This mitigation system will include a vapor barrier and passive sub-slab depressurization system that is capable of being converted to an active system.

Prior to conducting an SVI investigation or installing a mitigation system, a work plan will be developed and submitted to the NYSDEC and NYSDOH for approval. This work plan will be developed in accordance with the most recent NYSDOH "Guidance for Evaluating Vapor Intrusion in the State of New York". Measures to be employed to mitigate potential vapor intrusion will be evaluated, selected, designed, installed, and maintained based on the SVI evaluation, the NYSDOH guidance, and construction details of the proposed structure.

Preliminary (unvalidated) SVI sampling data will be forwarded to the NYSDEC and NYSDOH for initial review and interpretation. Upon validation, the final data will be transmitted to the agencies, along with a recommendation for follow-up action, such as mitigation. If any indoor air test results exceed NYSDOH guidelines, relevant NYSDOH fact sheets will be provided to all tenants and occupants of the property within 15 days of receipt of validated data.

SVI sampling results, evaluations, and follow-up actions will also be summarized in the next Periodic Review Report.

085-12-05.0

Syracuse Label Co., Inc.

Monitoring Plan

IC/EC Plan

Landuse Restriction

O&M Plan

Ground Water Use Restriction

Site Management Plan

A sub-slab depressurization system (SSDS) was installed in the existing Site building in 2011. The SSDS is a high vacuum system utilizing fourteen (14) suction points positioned at location shown on

Figure 9. Photographs of the system installation are included in Appendix B of this SMP. The fourteen (14) suction points are identified herein, and will be referenced in the future, as S-1, S-2, S-3, and S-4 (clockwise around warehouse starting in the southwest corner); S-5, S-6, and S-7 (south to north along office area wall); S-8 and S-9 (northeastern rooms of building), and S-10, S-11, S-12, S-13, and S-14 (southeastern rooms of building).

Each SSDS suction point consists of a 4 inch hole cored through the existing concrete slab. Each suction riser was constructed of 3 inch diameter schedule 40 polyvinyl chloride (PVC) piping. Each suction riser was connected to a single fan on the roof utilizing a trunk line network consisting of 4 inch diameter PVC piping. Each riser pipe is outfitted with a magnehelic pressure gauge, to allow for monitoring of system performance, and an interior baffle that can be adjusted to regulate airflow. All floor, wall, and roof penetrations were sealed with a VOC compliant urethane sealant. Design details are presented in the Operation and Maintenance Plan (Section 4 of this SMP).

Procedures for monitoring the system, including inspections in the event that an identified severe condition occurs, are included in the Monitoring Plan (Section 3 of this SMP). Procedures for operating and maintaining the SSDS are documented in the Operation and Maintenance Plan (Section 4 of this SMP).

A series of Institutional Controls is required by the RAWP to: (1) implement, maintain and monitor Engineering Control systems; (2) prevent future exposure to remaining contamination by controlling disturbances of the subsurface contamination; and, (3) limit the use and development of the Site to Commercial or Industrial uses only. Adherence to these Institutional Controls on the Site is required by the Environmental Easement and will be implemented under this Site Management Plan. These institutional Controls are:

- Compliance with the Environmental Easement and this SMP by the Grantor and the Grantor's successors and assigns;
- All Engineering Controls must be operated and maintained as specified in this SMP;
- All Engineering Controls on the Controlled Property must be inspected at a frequency and in a manner defined in the SMP;
- Groundwater and other environmental or public health monitoring must be performed as defined in this SMP; and
- Data and information pertinent to Site Management of the Controlled Property must be reported at the frequency and in a manner defined in this SMP.

Institutional Controls identified in the Environmental Easement may not be discontinued without an amendment to or extinguishment of the Environmental Easement.

The Site has a series of Institutional Controls in the form of Site restrictions. Adherence to these Institutional Controls is required by the Environmental Easement. Site restrictions that apply to the Controlled Property are:

- The property may only be used for Commercial or Industrial use provided that the long-term Engineering and Institutional Controls included in this SMP are employed;
- The property may not be used for a higher level of use, such as unrestricted, residential, or restricted residential use without additional remediation and amendment of the Environmental Easement, as approved by the NYSDEC;
- All future activities on the property that will disturb remaining contaminated material must be conducted in accordance with this SMP and the Excavation Work Plan (Appendix C);
- The use of the groundwater underlying the property is prohibited without treatment rendering it safe for intended use;
- The potential for vapor intrusion must be evaluated for any buildings developed onsite, and any potential impacts that are identified must be monitored or mitigated;
- Vegetable gardens and farming on the property are prohibited;
- The Site owner or remedial party will submit to NYSDEC a written statement that certifies, under penalty of perjury, that: (1) controls employed at the Controlled Property are unchanged from the previous certification or that any changes to the controls were approved by the NYSDEC; and, (2) nothing has occurred that impairs the ability of the controls to protect public health and environment or that constitute a violation or failure to comply with the SMP. NYSDEC retains the right to access such Controlled Property at any time in order to evaluate the continued maintenance of any and all controls. This certification shall be submitted annually, or an alternate period of time that NYSDEC may allow and will be made by an expert that the NYSDEC finds acceptable; and
- The Site owner is required to monitor whether there is a change in ownership of the adjacent property currently owned by The Brannock Device Company, located at 116 Luther Avenue. If a change in ownership occurs the current owner will need to be notified of the environmental conditions of the 110 Luther Avenue Site and afforded the option to evaluate the potential for soil vapor intrusion into the building. Notification must also be made to the NYSDEC if the adjacent property is sold or ownership is transferred.

### 2.3.1 Excavation Work Plan

The Site has been remediated for commercial use. Any future intrusive work that will encounter or disturb the remaining contamination, including any modifications or repairs to the existing cover system will be performed in compliance with the Excavation Work Plan (EWP) that is attached as Appendix C to this SMP. Any work conducted pursuant to the EWP must also be conducted in accordance with the procedures defined in a Health and Safety Plan (HASP) and Community Air Monitoring Plan (CAMP) prepared for the Site. A sample HASP and CAMP are attached as Appendix D to this SMP that is in current compliance with DER-10, and 29 CFR 1910, 29 CFR 1926, and all other applicable Federal, State and local regulations. Based on future changes to State and federal health and safety requirements, and specific methods employed by future contractors, the HASP and CAMP will be updated and re-submitted with the notification provided in Section C-1 of the EWP. Any intrusive construction work will be performed in compliance with the EWP, HASP and CAMP, and will be included in the periodic inspection and certification reports submitted under the Site Management Reporting Plan (See Section 5).

The Site owner and associated parties preparing the remedial documents submitted to the State, and parties performing this work, are completely responsible for the safe performance of all intrusive work, the structural integrity of excavations, proper disposal of excavation de-water, control of runoff from open excavations into remaining contamination, and for structures that may be affected by excavations (such as building foundations and bridge footings). The Site owner will ensure that Site development activities will not interfere with, or otherwise impair or compromise, the engineering controls described in this SMP.

### 2.3.2 Soil Vapor Intrusion Evaluation

Prior to the construction of any enclosed structures at the Site, an SVI evaluation will be performed to determine whether any mitigation measures are necessary to eliminate potential exposure to vapors in the proposed structure. Alternatively, an SVI mitigation system may be installed as an element of the building foundation without first conducting an investigation. This mitigation system will include a vapor barrier and passive sub-slab depressurization system that is capable of being converted to an active system.

Prior to conducting an SVI investigation or installing a mitigation system, a work plan will be developed and submitted to the NYSDEC and NYSDOH for approval. This work plan will be developed in accordance with the most recent NYSDOH "Guidance for Evaluating Vapor Intrusion in the State of New York". Measures to be employed to mitigate potential vapor intrusion will be evaluated, selected, designed, installed, and maintained based on the SVI evaluation, the NYSDOH guidance, and construction details of the proposed structure.

Preliminary (unvalidated) SVI sampling data will be forwarded to the NYSDEC and NYSDOH for initial review and interpretation. Upon validation, the final data will be transmitted to the agencies, along with a recommendation for follow-up action, such as mitigation. If any indoor air test results exceed NYSDOH guidelines, relevant NYSDOH fact sheets will be provided to all tenants and occupants of the property within 15 days of receipt of validated data.

SVI sampling results, evaluations, and follow-up actions will also be summarized in the next Periodic Review Report.

085-12-06.1

Syracuse Label Co., Inc.

Ground Water Use Restriction

Site Management Plan  
Monitoring Plan  
Landuse Restriction  
O&M Plan  
IC/EC Plan

A sub-slab depressurization system (SSDS) was installed in the existing Site building in 2011. The SSDS is a high vacuum system utilizing fourteen (14) suction points positioned at location shown on Figure 9. Photographs of the system installation are included in Appendix B of this SMP. The fourteen (14) suction points are identified herein, and will be referenced in the future, as S-1, S-2, S-3, and S-4 (clockwise around warehouse starting in the southwest corner); S-5, S-6, and S-7 (south to north along office area wall); S-8 and S-9 (northeastern rooms of building), and S-10, S-11, S-12, S-13, and S-14 (southeastern rooms of building).

Each SSDS suction point consists of a 4 inch hole cored through the existing concrete slab. Each suction riser was constructed of 3 inch diameter schedule 40 polyvinyl chloride (PVC) piping. Each suction riser was connected to a single fan on the roof utilizing a trunk line network consisting of 4 inch diameter PVC piping. Each riser pipe is outfitted with a magnehelic pressure gauge, to allow for monitoring of system performance, and an interior baffle that can be adjusted to regulate airflow. All floor, wall, and roof penetrations were sealed with a VOC compliant urethane sealant. Design details are presented in the Operation and Maintenance Plan (Section 4 of this SMP).

Procedures for monitoring the system, including inspections in the event that an identified severe condition occurs, are included in the Monitoring Plan (Section 3 of this SMP). Procedures for operating and maintaining the SSDS are documented in the Operation and Maintenance Plan (Section 4 of this SMP).

A series of Institutional Controls is required by the RAWP to: (1) implement, maintain and monitor Engineering Control systems; (2) prevent future exposure to remaining contamination by controlling disturbances of the subsurface contamination; and, (3) limit the use and development of the Site to Commercial or Industrial uses only. Adherence to these Institutional Controls on the Site is required by the Environmental Easement and will be implemented under this Site Management Plan. These Institutional Controls are:

- Compliance with the Environmental Easement and this SMP by the Grantor and the Grantor's successors and assigns;
- All Engineering Controls must be operated and maintained as specified in this SMP;
- All Engineering Controls on the Controlled Property must be inspected at a frequency and in a manner defined in the SMP;
- Groundwater and other environmental or public health monitoring must be performed as defined in this SMP; and
- Data and Information pertinent to Site Management of the Controlled Property must be reported at the frequency and in a manner defined in this SMP.

Institutional Controls identified in the Environmental Easement may not be discontinued without an amendment to or extinguishment of the Environmental Easement.

The Site has a series of Institutional Controls in the form of Site restrictions. Adherence to these Institutional Controls is required by the Environmental Easement. Site restrictions that apply to the Controlled Property are:

- The property may only be used for Commercial or Industrial use provided that the long-term Engineering and Institutional Controls included in this SMP are employed;
- The property may not be used for a higher level of use, such as unrestricted, residential, or restricted residential use without additional remediation and amendment of the Environmental Easement, as approved by the NYSDEC;
- All future activities on the property that will disturb remaining contaminated material must be conducted in accordance with this SMP and the Excavation Work Plan (Appendix C);
- The use of the groundwater underlying the property is prohibited without treatment rendering it safe for intended use;
- The potential for vapor intrusion must be evaluated for any buildings developed onsite, and any potential impacts that are identified must be monitored or mitigated;
- Vegetable gardens and farming on the property are prohibited;
- The Site owner or remedial party will submit to NYSDEC a written statement that certifies, under penalty of perjury, that: (1) controls employed at the Controlled Property are unchanged from the previous certification or that any changes to the controls were approved by the NYSDEC; and, (2) nothing has occurred that impairs the ability of the controls to protect public health and environment or that constitute a violation or failure to comply with the SMP. NYSDEC retains the right to access such Controlled Property at any time in order to evaluate the continued maintenance of any and all controls. This certification shall be submitted annually, or an alternate period of time that NYSDEC may allow and will be made by an expert that the NYSDEC finds acceptable; and
- The Site owner is required to monitor whether there is a change in ownership of the adjacent property currently owned by The Brannock Device Company, located at 116 Luther Avenue. If a change in ownership occurs the current owner will need to be notified of the environmental conditions of the 110 Luther Avenue Site and afforded the option to evaluate the potential for soil vapor intrusion into the building. Notification must also be made to the NYSDEC if the adjacent property is sold or ownership is transferred.

#### 2.3.1 Excavation Work Plan

The Site has been remediated for commercial use. Any future intrusive work that will encounter or disturb the remaining contamination, including any modifications or repairs to the existing cover system will be performed in compliance with the Excavation Work Plan (EWP) that is attached as Appendix C to this SMP. Any work conducted pursuant to the EWP must also be conducted in accordance with the procedures defined in a Health and Safety Plan (HASP) and Community Air Monitoring Plan (CAMP) prepared for the Site. A sample HASP and CAMP are attached as Appendix D to this SMP that is in current compliance with DER-10, and 29 CFR 1910, 29 CFR 1926, and all other applicable Federal, State and local regulations. Based on future changes to State and federal health and safety requirements, and specific methods employed by future contractors, the HASP and CAMP will be updated and re-submitted with the notification provided in Section C-1 of the EWP. Any intrusive construction work will be performed in compliance with the EWP, HASP and CAMP, and will

be included in the periodic inspection and certification reports submitted under the Site Management Reporting Plan (See Section 5).

The Site owner and associated parties preparing the remedial documents submitted to the State, and parties performing this work, are completely responsible for the safe performance of all intrusive work, the structural integrity of excavations, proper disposal of excavation de-water, control of runoff from open excavations into remaining contamination, and for structures that may be affected by excavations (such as building foundations and bridge footings). The Site owner will ensure that Site development activities will not interfere with, or otherwise impair or compromise, the engineering controls described in this SMP.

### 2.3.2 Soil Vapor Intrusion Evaluation

Prior to the construction of any enclosed structures at the Site, an SVI evaluation will be performed to determine whether any mitigation measures are necessary to eliminate potential exposure to vapors in the proposed structure. Alternatively, an SVI mitigation system may be installed as an element of the building foundation without first conducting an investigation. This mitigation system will include a vapor barrier and passive sub-slab depressurization system that is capable of being converted to an active system.

Prior to conducting an SVI investigation or installing a mitigation system, a work plan will be developed and submitted to the NYSDEC and NYSDOH for approval. This work plan will be developed in accordance with the most recent NYSDOH "Guidance for Evaluating Vapor Intrusion in the State of New York". Measures to be employed to mitigate potential vapor intrusion will be evaluated, selected, designed, installed, and maintained based on the SVI evaluation, the NYSDOH guidance, and construction details of the proposed structure.

Preliminary (unvalidated) SVI sampling data will be forwarded to the NYSDEC and NYSDOH for initial review and interpretation. Upon validation, the final data will be transmitted to the agencies, along with a recommendation for follow-up action, such as mitigation. If any indoor air test results exceed NYSDOH guidelines, relevant NYSDOH fact sheets will be provided to all tenants and occupants of the property within 15 days of receipt of validated data.

SVI sampling results, evaluations, and follow-up actions will also be summarized in the next Periodic Review Report.

085-12-08.0

Syracuse Label Co., Inc.

IC/EC Plan

Landuse Restriction

Monitoring Plan

O&M Plan

Ground Water Use Restriction

Site Management Plan

A sub-slab depressurization system (SSDS) was installed in the existing Site building in 2011. The SSDS is a high vacuum system utilizing fourteen (14) suction points positioned at location shown on Figure 9. Photographs of the system installation are included in Appendix B of this SMP. The fourteen (14) suction points are identified herein, and will be referenced in the future, as S-1, S-2, S-3, and S-4 (clockwise around warehouse starting in the southwest corner); S-5, S-6, and S-7 (south to north along office area wall); S-8 and S-9 (northeastern rooms of building), and S-10, S-11, S-12, S-13, and S-14 (southeastern rooms of building).

Each SSDS suction point consists of a 4 inch hole cored through the existing concrete slab. Each suction riser was constructed of 3 inch diameter schedule 40 polyvinyl chloride (PVC) piping. Each suction riser was connected to a single fan on the roof utilizing a trunk line network consisting of 4 inch diameter PVC piping. Each riser pipe is outfitted with a magnehelic pressure gauge, to allow for monitoring of system performance, and an interior baffle that can be adjusted to regulate airflow. All floor, wall, and roof penetrations were sealed with a VOC compliant urethane sealant. Design details are presented in the Operation and Maintenance Plan (Section 4 of this SMP).

Procedures for monitoring the system, including inspections in the event that an identified severe condition occurs, are included in the Monitoring Plan (Section 3 of this SMP). Procedures for operating and maintaining the SSDS are documented in the Operation and Maintenance Plan (Section 4 of this SMP).

A series of Institutional Controls is required by the RAWP to: (1) implement, maintain and monitor Engineering Control systems; (2) prevent future exposure to remaining contamination by controlling disturbances of the subsurface contamination; and, (3) limit the use and development of the Site to Commercial or Industrial uses only. Adherence to these Institutional Controls on the Site is required by the Environmental Easement and will be implemented under this Site Management Plan. These Institutional Controls are:

- Compliance with the Environmental Easement and this SMP by the Grantor and the Grantor's successors and assigns;
- All Engineering Controls must be operated and maintained as specified in this SMP;
- All Engineering Controls on the Controlled Property must be inspected at a frequency and in a manner defined in the SMP;
- Groundwater and other environmental or public health monitoring must be performed as defined in this SMP; and
- Data and information pertinent to Site Management of the Controlled Property must be reported at the frequency and in a manner defined in this SMP.

Institutional Controls Identified in the Environmental Easement may not be discontinued without an amendment to or extinguishment of the Environmental Easement.

The Site has a series of Institutional Controls in the form of Site restrictions. Adherence to these Institutional Controls is required by the Environmental Easement. Site restrictions that apply to the Controlled Property are:

- The property may only be used for Commercial or Industrial use provided that the long-term Engineering and Institutional Controls included in this SMP are employed;
- The property may not be used for a higher level of use, such as unrestricted, residential, or restricted residential use without additional remediation and amendment of the Environmental Easement, as approved by the NYSDEC;
- All future activities on the property that will disturb remaining contaminated material must be conducted in accordance with this SMP and the Excavation Work Plan (Appendix C);
- The use of the groundwater underlying the property is prohibited without treatment rendering it safe for intended use;
- The potential for vapor intrusion must be evaluated for any buildings developed onsite, and any potential impacts that are identified must be monitored or mitigated;
- Vegetable gardens and farming on the property are prohibited;
- The Site owner or remedial party will submit to NYSDEC a written statement that certifies, under penalty of perjury, that: (1) controls employed at the Controlled Property are unchanged from the previous certification or that any changes to the controls were approved by the NYSDEC; and, (2) nothing has occurred that impairs the ability of the controls to protect public health and environment or that constitute a violation or failure to comply with the SMP. NYSDEC retains the right to access such Controlled Property at any time in order to evaluate the continued maintenance of any and all controls. This certification shall be submitted annually, or an alternate period of time that NYSDEC may allow and will be made by an expert that the NYSDEC finds acceptable; and
- The Site owner is required to monitor whether there is a change in ownership of the adjacent property currently owned by The Brannock Device Company, located at 116 Luther Avenue. If a change in ownership occurs the current owner will need to be notified of the environmental conditions of the 110 Luther Avenue Site and afforded the option to evaluate the potential for soil vapor intrusion into the building. Notification must also be made to the NYSDEC if the adjacent property is sold or ownership is transferred.

#### 2.3.1 Excavation Work Plan

The Site has been remediated for commercial use. Any future intrusive work that will encounter or disturb the remaining contamination, including any modifications or repairs to the existing cover system will be performed in compliance with the Excavation Work Plan (EWP) that is attached as Appendix C to this SMP. Any work conducted pursuant to the EWP must also be conducted in accordance with the procedures defined in a Health and Safety Plan (HASP) and Community Air Monitoring Plan (CAMP) prepared for the Site. A sample HASP and CAMP are attached as Appendix D to this SMP that is in current compliance with DER-10, and 29 CFR 1910, 29 CFR 1926, and all other applicable Federal, State and local regulations. Based on future changes to State and federal health and safety requirements, and specific methods employed by future contractors, the HASP and CAMP will be updated and re-submitted with the notification provided in Section C-1 of the EWP. Any intrusive construction work will be performed in compliance with the EWP, HASP and CAMP, and will be included in the periodic inspection and certification reports submitted under the Site Management Reporting Plan (See Section 5).

The Site owner and associated parties preparing the remedial documents submitted to the State, and parties performing this work, are completely responsible for the safe performance of all intrusive work, the structural integrity of excavations, proper disposal of excavation de-water, control of runoff from open excavations into remaining contamination, and for structures that may be affected by excavations (such as building foundations and bridge footings). The Site owner will ensure that Site development activities will not interfere with, or otherwise impair or compromise, the engineering controls described in this SMP.

#### 2.3.2 Soil Vapor Intrusion Evaluation

Prior to the construction of any enclosed structures at the Site, an SVI evaluation will be performed to



determine whether any mitigation measures are necessary to eliminate potential exposure to vapors in the proposed structure. Alternatively, an SVI mitigation system may be installed as an element of the building foundation without first conducting an investigation. This mitigation system will include a vapor barrier and passive sub-slab depressurization system that is capable of being converted to an active system.

Prior to conducting an SVI investigation or installing a mitigation system, a work plan will be developed and submitted to the NYSDEC and NYSDOH for approval. This work plan will be developed in accordance with the most recent NYSDOH "Guidance for Evaluating Vapor Intrusion in the State of New York". Measures to be employed to mitigate potential vapor intrusion will be evaluated, selected, designed, installed, and maintained based on the SVI evaluation, the NYSDOH guidance, and construction details of the proposed structure.

Preliminary (unvalidated) SVI sampling data will be forwarded to the NYSDEC and NYSDOH for initial review and interpretation. Upon validation, the final data will be transmitted to the agencies, along with a recommendation for follow-up action, such as mitigation. If any indoor air test results exceed NYSDOH guidelines, relevant NYSDOH fact sheets will be provided to all tenants and occupants of the property within 15 days of receipt of validated data.

SVI sampling results, evaluations, and follow-up actions will also be summarized in the next Periodic Review Report.

085-12-09.0

Syracuse Label Co., Inc.

Ground Water Use Restriction  
Monitoring Plan  
Site Management Plan

Landuse Restriction  
O&M Plan  
IC/EC Plan

A sub-slab depressurization system (SSDS) was installed in the existing Site building in 2011. The SSDS is a high vacuum system utilizing fourteen (14) suction points positioned at location shown on Figure 9. Photographs of the system installation are included in Appendix B of this SMP. The fourteen (14) suction points are identified herein, and will be referenced in the future, as S-1, S-2, S-3, and S-4 (clockwise around warehouse starting in the southwest corner); S-5, S-6, and S-7 (south to north along office area wall); S-8 and S-9 (northeastern rooms of building), and S-10, S-11, S-12, S-13, and S-14 (southeastern rooms of building).

Each SSDS suction point consists of a 4 inch hole cored through the existing concrete slab. Each suction riser was constructed of 3 inch diameter schedule 40 polyvinyl chloride (PVC) piping. Each suction riser was connected to a single fan on the roof utilizing a trunk line network consisting of 4 inch diameter PVC piping. Each riser pipe is outfitted with a magnehelic pressure gauge, to allow for monitoring of system performance, and an interior baffle that can be adjusted to regulate airflow. All floor, wall, and roof penetrations were sealed with a VOC compliant urethane sealant. Design details are presented in the Operation and Maintenance Plan (Section 4 of this SMP).

Procedures for monitoring the system, including inspections in the event that an identified severe condition occurs, are included in the Monitoring Plan (Section 3 of this SMP). Procedures for operating and maintaining the SSDS are documented in the Operation and Maintenance Plan (Section 4 of this SMP).

A series of Institutional Controls is required by the RAWP to: (1) implement, maintain and monitor Engineering Control systems; (2) prevent future exposure to remaining contamination by controlling disturbances of the subsurface contamination; and, (3) limit the use and development of the Site to Commercial or Industrial uses only. Adherence to these Institutional Controls on the Site is required by the Environmental Easement and will be implemented under this Site Management Plan. These Institutional Controls are:

- Compliance with the Environmental Easement and this SMP by the Grantor and the Grantor's successors and assigns;
- All Engineering Controls must be operated and maintained as specified in this SMP;
- All Engineering Controls on the Controlled Property must be inspected at a frequency and in a manner defined in the SMP;
- Groundwater and other environmental or public health monitoring must be performed as defined in this SMP; and
- Data and information pertinent to Site Management of the Controlled Property must be reported at the frequency and in a manner defined in this SMP.

Institutional Controls identified in the Environmental Easement may not be discontinued without an amendment to or extinguishment of the Environmental Easement.

The Site has a series of Institutional Controls in the form of Site restrictions. Adherence to these

Institutional Controls is required by the Environmental Easement. Site restrictions that apply to the Controlled Property are:

- The property may only be used for Commercial or Industrial use provided that the long-term Engineering and Institutional Controls Included in this SMP are employed;
- The property may not be used for a higher level of use, such as unrestricted, residential, or restricted residential use without additional remediation and amendment of the Environmental Easement, as approved by the NYSDEC;
- All future activities on the property that will disturb remaining contaminated material must be conducted in accordance with this SMP and the Excavation Work Plan (Appendix C);
- The use of the groundwater underlying the property is prohibited without treatment rendering it safe for intended use;
- The potential for vapor intrusion must be evaluated for any buildings developed onsite, and any potential impacts that are identified must be monitored or mitigated;
- Vegetable gardens and farming on the property are prohibited;
- The Site owner or remedial party will submit to NYSDEC a written statement that certifies, under penalty of perjury, that: (1) controls employed at the Controlled Property are unchanged from the previous certification or that any changes to the controls were approved by the NYSDEC; and, (2) nothing has occurred that impairs the ability of the controls to protect public health and environment or that constitute a violation or failure to comply with the SMP. NYSDEC retains the right to access such Controlled Property at any time in order to evaluate the continued maintenance of any and all controls. This certification shall be submitted annually, or an alternate period of time that NYSDEC may allow and will be made by an expert that the NYSDEC finds acceptable; and
- The Site owner is required to monitor whether there is a change in ownership of the adjacent property currently owned by The Brannock Device Company, located at 116 Luther Avenue. If a change in ownership occurs the current owner will need to be notified of the environmental conditions of the 110 Luther Avenue Site and afforded the option to evaluate the potential for soil vapor intrusion into the building. Notification must also be made to the NYSDEC if the adjacent property is sold or ownership is transferred.

#### 2.3.1 Excavation Work Plan

The Site has been remediated for commercial use. Any future intrusive work that will encounter or disturb the remaining contamination, including any modifications or repairs to the existing cover system will be performed in compliance with the Excavation Work Plan (EWP) that is attached as Appendix C to this SMP. Any work conducted pursuant to the EWP must also be conducted in accordance with the procedures defined in a Health and Safety Plan (HASP) and Community Air Monitoring Plan (CAMP) prepared for the Site. A sample HASP and CAMP are attached as Appendix D to this SMP that is in current compliance with DER-10, and 29 CFR 1910, 29 CFR 1926, and all other applicable Federal, State and local regulations. Based on future changes to State and federal health and safety requirements, and specific methods employed by future contractors, the HASP and CAMP will be updated and re-submitted with the notification provided in Section C-1 of the EWP. Any intrusive construction work will be performed in compliance with the EWP, HASP and CAMP, and will be included in the periodic inspection and certification reports submitted under the Site Management Reporting Plan (See Section 5).

The Site owner and associated parties preparing the remedial documents submitted to the State, and parties performing this work, are completely responsible for the safe performance of all intrusive work, the structural integrity of excavations, proper disposal of excavation de-water, control of runoff from open excavations into remaining contamination, and for structures that may be affected by excavations (such as building foundations and bridge footings). The Site owner will ensure that Site development activities will not interfere with, or otherwise impair or compromise, the engineering controls described in this SMP.

#### 2.3.2 Soil Vapor Intrusion Evaluation

Prior to the construction of any enclosed structures at the Site, an SVI evaluation will be performed to determine whether any mitigation measures are necessary to eliminate potential exposure to vapors in the proposed structure. Alternatively, an SVI mitigation system may be installed as an element of the building foundation without first conducting an investigation. This mitigation system will include a vapor barrier and passive sub-slab depressurization system that is capable of being converted to an active system.

Prior to conducting an SVI investigation or installing a mitigation system, a work plan will be developed and submitted to the NYSDEC and NYSDOH for approval. This work plan will be developed in accordance with the most recent NYSDOH "Guidance for Evaluating Vapor Intrusion in the State of New York". Measures to be employed to mitigate potential vapor intrusion will be evaluated, selected, designed, installed, and maintained based on the SVI evaluation, the NYSDOH guidance, and construction details of the proposed structure.

Preliminary (unvalidated) SVI sampling data will be forwarded to the NYSDEC and NYSDOH for initial

review and interpretation. Upon validation, the final data will be transmitted to the agencies, along with a recommendation for follow-up action, such as mitigation. If any indoor air test results exceed NYSDOH guidelines, relevant NYSDOH fact sheets will be provided to all tenants and occupants of the property within 15 days of receipt of validated data.

SVI sampling results, evaluations, and follow-up actions will also be summarized in the next Periodic Review Report.

**Box 4**

**Description of Engineering Controls**

<u>Parcel</u>	<u>Engineering Control</u>
085-12-04.1	Vapor Mitigation Cover System
085-12-05.0	Cover System Vapor Mitigation
085-12-06.1	Cover System Vapor Mitigation
085-12-08.0	Cover System Vapor Mitigation
085-12-09.0	Vapor Mitigation Cover System

**Periodic Review Report (PRR) Certification Statements**

1. I certify by checking "YES" below that:

a) the Periodic Review report and all attachments were prepared under the direction of, and reviewed by, the party making the certification;

b) to the best of my knowledge and belief, the work and conclusions described in this certification are in accordance with the requirements of the site remedial program, and generally accepted engineering practices; and the information presented is accurate and complete.

YES NO

☒ ☐

2. If this site has an IC/EC Plan (or equivalent as required in the Decision Document), for each Institutional or Engineering control listed in Boxes 3 and/or 4, I certify by checking "YES" below that all of the following statements are true:

(a) the Institutional Control and/or Engineering Control(s) employed at this site is unchanged since the date that the Control was put in-place, or was last approved by the Department;

(b) nothing has occurred that would impair the ability of such Control, to protect public health and the environment;

(c) access to the site will continue to be provided to the Department, to evaluate the remedy, including access to evaluate the continued maintenance of this Control;

(d) nothing has occurred that would constitute a violation or failure to comply with the Site Management Plan for this Control; and

(e) if a financial assurance mechanism is required by the oversight document for the site, the mechanism remains valid and sufficient for its intended purpose established in the document.

YES NO

☒ ☐

**IF THE ANSWER TO QUESTION 2 IS NO, sign and date below and  
DO NOT COMPLETE THE REST OF THIS FORM. Otherwise continue.**

**A Corrective Measures Work Plan must be submitted along with this form to address these issues.**

\_\_\_\_\_  
Signature of Owner, Remedial Party or Designated Representative

\_\_\_\_\_  
Date

IC CERTIFICATIONS  
SITE NO. C734118

Box 6

**SITE OWNER OR DESIGNATED REPRESENTATIVE SIGNATURE**

I certify that all information and statements in Boxes 1, 2, and 3 are true. I understand that a false statement made herein is punishable as a Class "A" misdemeanor, pursuant to Section 210.45 of the Penal Law.

I Kathleen Alaimo at 110 Luther Ave Liverpool, NY.  
print name print business address

am certifying as Owner (Owner or Remedial Party)

for the Site named in the Site Details Section of this form.

Kathleen Alaimo  
Signature of Owner, Remedial Party, or Designated Representative  
Rendering Certification

4/24/14  
Date

IC/EC CERTIFICATIONS

Box 7


Professional Engineer Signature

I certify that all information in Boxes 4 and 5 are true. I understand that a false statement made herein is punishable as a Class "A" misdemeanor, pursuant to Section 210.45 of the Penal Law.

I Damian Vanetti at GHD, 1 Remington Park Dr.,  
print name print business address Cazenovia, NY 13035

am certifying as a Professional Engineer for the Owner  
(Owner or Remedial Party)

  
Signature of Professional Engineer for the Owner or  
Remedial Party, Rendering Certification



Stamp  
(Required for PE)  
#068011

4-24-14  
Date

## **Appendix B** - Property Ownership Information for Adjoining Property





## Property Description Report For: 116 Luther Ave, Municipality of Town of Salina

*No Photo  
Available*

		<b>Status:</b>	Active
		<b>Roll Section:</b>	Taxable
		<b>Swis:</b>	314889
		<b>Tax Map ID #:</b>	085.-12-10.0
		<b>Property #:</b>	
		<b>Property Class:</b>	710 - Manufacture
		<b>Site:</b>	COM 1
		<b>In Ag. District:</b>	No
		<b>Site Property Class:</b>	710 - Manufacture
		<b>Zoning Code:</b>	06
		<b>Neighborhood Code:</b>	48070
		<b>School District:</b>	Liverpool
		<b>Total Assessment:</b>	2013 - \$116,000
<b>Total Acreage/Size:</b>	90 x 90	<b>Legal Property Desc:</b>	Buckley Gardens Lts 434 435 & 436
<b>Land Assessment:</b>	2013 - \$18,000	<b>Deed Page:</b>	42
<b>Full Market Value:</b>	2013 - \$116,000	<b>Grid North:</b>	1125118
<b>Equalization Rate:</b>	----		
<b>Deed Book:</b>	4013		
<b>Grid East:</b>	610957		

### Owners

Leonardi Salvatore A Jr  
116 Luther Ave  
Liverpool NY 13088-6726

### Sales

<b>Sale Date</b>	<b>Price</b>	<b>Property Class</b>	<b>Sale Type</b>	<b>Prior Owner</b>	<b>Value Usable</b>	<b>Arms Length</b>	<b>Addl. Parcels</b>	<b>Deed Book and Page</b>
7/12/1995	\$125,000	710 - Manufacture	Land & Building	Masterpol Nicholas J	Yes	Yes	No	4013/42
1/4/1995	\$75,000	710 - Manufacture	Land & Building	Krull Duane	Yes	Yes	No	3977/76

## **Appendix C** - Sub-Slab Depressurization System Inspection Checklists

# Sub-Slab Depressurization System

## Inspection Checklist

Syracuse Label, 110 Luther Avenue, Liverpool, NY

Date:

7/23/13

Inspector Name:

Kevin GAGNON

Company:

SYRLSP

Inspector Initials:

KG

### I. Pressure Readings

Suction Riser Identification	Pressure Reading (inWC)
S-1	3.4
S-2	3.1
S-3	5.8
S-4	5.1
S-5	3.6
S-6	3.2
S-7	2.2
S-8	5.0
S-9	2.5
S-10	4.5
S-11	4.5
S-12	4.5
S-13	4.5
S-14	4.5

### II. Fan Inspection

1. Operational? Y 1 N
2. Fan/Controls Clear of obstructions? Y 1 N
3. Repair needs? Y     N 1

#### A. Observations/comments:

Attach photographs as appropriate

#### B. Actions taken:

#### C. Recommended Maintenance/Repairs:

#### Notes:

Locations of suction risers can be found on attached Figure.

System details are included in Appendix B.

### III. Piping/Penetrations

1. Is piping intact? (Y or N) Y
2. Are floor/wall penetrations sealed? (Y or N) Y

If 'No' to either of the above, provide observations and describe corrective actions taken

Do any of the pressure gages require repair or replacement?  
If so, indicate locations, and actions taken:

Y     N 1

### IV. Building Modifications: Have building modifications been made that could affect the operation of the SSD System? (Describe)

None at this time

#### Additional Comments:

Condensation trap - no water

KG

Report all maintenance/repair needs immediately to building facility manager

# Sub-Slab Depressurization System

## Inspection Checklist

Syracuse Label, 110 Luther Avenue, Liverpool, NY

Date:

8-6-13

Inspector Name:

Kevin Gagnon

Company:

SYRL SP

Inspector Initials:

KG

### I. Pressure Readings

Suction Riser Identification	Pressure Reading (inWC)
S-1	2.9
S-2	2.6
S-3	5.4
S-4	4.9
S-5	3.3
S-6	3.1
S-7	2.1
S-8	4.5
S-9	2.1
S-10	2.8
S-11	2.8
S-12	2.7
S-13	3.0
S-14	2.8

### II. Fan Inspection

- Operational? Y ☐ N ☐
- Fan/Controls Clear of obstructions? Y ☐ N ☐
- Repair needs? Y ☐ N ☐

#### A. Observations/comments:

Attach photographs as appropriate

#### B. Actions taken:

#### C. Recommended Maintenance/Repairs:

#### Notes:

Locations of suction risers can be found on attached Figure.

System details are included in Appendix B.

### III. Piping/Penetrations

- Is piping intact? (Y or N) ☒ Y ☐ N
- Are floor/wall penetrations sealed? (Y or N) ☒ Y ☐ N

If 'No' to either of the above, provide observations and describe corrective actions taken

Do any of the pressure gages require repair or replacement?  
If so, indicate locations, and actions taken:

Y ☐ N ☒

### IV. Building Modifications: Have building modifications been made that could affect the operation of the SSD System? (Describe)

None at this time.

#### Additional Comments:

Condensation trap checked - no water - but 2 black fly's on inside of plug + 1 flew out of pipe. (KG)

Report all maintenance/repair needs immediately to building facility manager

# Sub-Slab Depressurization System

## Inspection Checklist

Syracuse Label, 110 Luther Avenue, Liverpool, NY

Date:

9-6-13

Inspectors Name:

Kevin Gagnon

Company:

SYRLSP

Inspector Initials:

KG

### I. Pressure Readings

Suction Riser Identification	Pressure Reading (inWC)
S-1	2.9
S-2	2.6
S-3	5.1
S-4	4.9
S-5	3.3
S-6	3.1
S-7	2.1
S-8	4.5
S-9	2.0
S-10	2.9
S-11	2.8
S-12	2.8
S-13	3.1
S-14	2.9

### II. Fan Inspection

- |  |   |                                     |   |                                     |
|--|---|-------------------------------------|---|-------------------------------------|
| 1. Operational?                        | Y | <input checked="" type="checkbox"/> | N | <input type="checkbox"/>            |
| 2. Fan/Controls Clear of obstructions? | Y | <input checked="" type="checkbox"/> | N | <input type="checkbox"/>            |
| 3. Repair needs?                       | Y | <input type="checkbox"/>            | N | <input checked="" type="checkbox"/> |

#### A. Observations/comments:

Attach photographs as appropriate

#### Notes:

Locations of suction risers can be found on attached Figure.

System details are included in Appendix B.

### III. Piping/Penetrations

1. Is piping intact? (Y or N)
2. Are floor/wall penetrations sealed? (Y or N)

If 'No' to either of the above, provide observations and describe corrective actions taken

#### B. Actions taken:

#### C. Recommended Maintenance/Repairs:

Do any of the pressure gages require repair or replacement?  
If so, indicate locations, and actions taken:

Y ☐ N ☒

### IV. Building Modifications: Have building modifications been made that could affect the operation of the SSD System? (Describe)

None at this time (KG)

#### Additional Comments:

Checked condensation trap no water or fly's (KG)

Report all maintenance/repair needs immediately to building facility manager

# Sub-Slab Depressurization System

## Inspection Checklist

Syracuse Label, 110 Luther Avenue, Liverpool, NY

Date:

10-21-13

Inspector Name:

Kevin Gagnon

Company:

SYRLSP

Inspector Initials:

KG

### I. Pressure Readings

Suction Riser Identification	Pressure Reading (inWC)
S-1	2.9
S-2	2.6
S-3	5.5
S-4	4.9
S-5	3.4
S-6	3.0
S-7	2.1
S-8	(KG) 2.1 + 4.5
S-9	2.1
S-10	3.0
S-11	2.9
S-12	2.7
S-13	3.0
S-14	2.9

### II. Fan Inspection

- Operational? Y X N
- Fan/Controls Clear of obstructions? Y X N
- Repair needs? Y     N X

#### A. Observations/comments:

Attach photographs as appropriate

#### B. Actions taken:

#### C. Recommended Maintenance/Repairs:

#### Notes:

Locations of suction risers can be found on attached Figure.

System details are included in Appendix B.

### III. Piping/Penetrations

- Is piping intact? (Y or N) Y
- Are floor/wall penetrations sealed? (Y or N) Y

If 'No' to either of the above, provide observations and describe corrective actions taken

Do any of the pressure gages require repair or replacement?  
If so, indicate locations, and actions taken:

Y     N X

### IV. Building Modifications: Have building modifications been made that could affect the operation of the SSD System? (Describe)

None

#### Additional Comments:

Checked condensation trap. no water! (KG)

Report all maintenance/repair needs immediately to building facility manager

# Sub-Slab Depressurization System

## Inspection Checklist

Syracuse Label, 110 Luther Avenue, Liverpool, NY

Date:

11/18/13

Inspector Name:

Kevin Gagnon

Company:

SYRLSP

Inspector Initials:

KG

### I. Pressure Readings

Suction Riser Identification	Pressure Reading (inWC)
S-1	2.8
S-2	2.6
S-3	5.3
S-4	4.8
S-5	3.4
S-6	3.1
S-7	2.0
S-8	4.8
S-9	2.4
S-10	3.0
S-11	2.9
S-12	2.7
S-13	3.1
S-14	2.9

### II. Fan Inspection

1. Operational?	Y	X	N	
2. Fan/Controls Clear of obstructions?	Y	X	N	
3. Repair needs?	Y		N	X

#### A. Observations/comments:

Attach photographs as appropriate

#### B. Actions taken:

#### C. Recommended Maintenance/Repairs:

#### Notes:

Locations of suction risers can be found on attached Figure.

System details are included in Appendix B.

### III. Piping/Penetrations

1. Is piping intact? (Y or N)
2. Are floor/wall penetrations sealed? (Y or N)

If 'No' to either of the above, provide observations and describe corrective actions taken

Do any of the pressure gages require repair or replacement?  
If so, indicate locations, and actions taken:

Y \_\_\_ N X

### IV. Building Modifications: Have building modifications been made that could affect the operation of the SSD System? (Describe)

NO - Drilling being done on the weekends. (KG)

#### Additional Comments:

Checked condensation trap. NO water (KG)

Report all maintenance/repair needs immediately to building facility manager

# Sub-Slab Depressurization System

## Inspection Checklist

Syracuse Label, 110 Luther Avenue, Liverpool, NY

Date:

12-17-13

Inspector Name:

Kevin Gagnon

Company:

SYRLSP

Inspector Initials:

Kg

### I. Pressure Readings

Suction Riser Identification	Pressure Reading (inWC)
S-1	2.9
S-2	2.6
S-3	5.9
S-4	4.9
S-5	3.4
S-6	3.1
S-7	2.0
S-8	5.0
S-9	2.2
S-10	2.7
S-11	2.6
S-12	2.5
S-13	2.8
S-14	2.5

### II. Fan Inspection

1. Operational? Y ☒ N ☐
2. Fan/Controls Clear of obstructions? Y ☒ N ☐
3. Repair needs? Y ☐ N ☒

#### A. Observations/comments:

Attach photographs as appropriate

#### B. Actions taken:

#### C. Recommended Maintenance/Repairs:

#### Notes:

Locations of suction risers can be found on attached Figure.

System details are included in Appendix B.

### III. Piping/Penetrations

1. Is piping intact? (Y or N) ☒
2. Are floor/wall penetrations sealed? (Y or N) ☒

If 'No' to either of the above, provide observations and describe corrective actions taken

Do any of the pressure gauges require repair or replacement?  
If so, indicate locations, and actions taken:

Y ☐ N ☒

### IV. Building Modifications: Have building modifications been made that could affect the operation of the SSD System? (Describe)

NO - drilling being done on the weekends (Kg)

#### Additional Comments:

Checked condensation trap - no water. (Kg)

Report all maintenance/repair needs immediately to building facility manager



# Sub-Slab Depressurization System

## Inspection Checklist

Syracuse Label, 110 Luther Avenue, Liverpool, NY

Date:

1/27/14

Inspector Name:

Kevin Gagnon

Company:

SYRLSP

Inspector Initials:

KG

### I. Pressure Readings

Suction Riser Identification	Pressure Reading (inWC)
S-1	3.8
S-2	2.5
S-3	5.5
S-4	5.0
S-5	3.4
S-6	3.1
S-7	2.1
S-8	5.0
S-9	2.6
S-10	2.9
S-11	2.6
S-12	2.6
S-13	2.9
S-14	2.9

### II. Fan Inspection

- Operational? Y ☒ N ☐
- Fan/Controls Clear of obstructions? Y ☒ N ☐
- Repair needs? Y ☐ N ☒

#### A. Observations/comments:

Attach photographs as appropriate

#### B. Actions taken:

#### C. Recommended Maintenance/Repairs:

#### Notes:

Locations of suction risers can be found on attached Figure.

System details are included in Appendix B.

### III. Piping/Penetrations

- Is piping intact? (Y or N) ☒
- Are floor/wall penetrations sealed? (Y or N) ☒

If 'No' to either of the above, provide observations and describe corrective actions taken

Do any of the pressure gages require repair or replacement?  
If so, indicate locations, and actions taken:

Y ☐ N ☒

### IV. Building Modifications: Have building modifications been made that could affect the operation of the SSD System? (Describe)

NONE at this time - (still Drilling)

#### Additional Comments:

Checked condensation trap - a lot of flies - gave to Paul Mumford.

KG

Report all maintenance/repair needs immediately to building facility manager

# Sub-Slab Depressurization System

## Inspection Checklist

Syracuse Label, 110 Luther Avenue, Liverpool, NY

Date:

2-26-14

Inspector Name:

Kevin Fagon

Company:

SYRLSP

Inspector Initials:

KS

### I. Pressure Readings

Suction Riser Identification	Pressure Reading (inWC)
S-1	3.8
S-2	2.6
S-3	5.5
S-4	5.0
S-5	3.4
S-6	3.2
S-7	2.1
S-8	5.0
S-9	2.6
S-10	2.9
S-11	2.6
S-12	2.6
S-13	2.9
S-14	2.9

### II. Fan Inspection

- |  |   |     |   |     |
|--|---|-----|---|-----|
| 1. Operational?                        | Y | X   | N | ___ |
| 2. Fan/Controls Clear of obstructions? | Y | X   | N | ___ |
| 3. Repair needs?                       | Y | ___ | N | X   |

#### A. Observations/comments:

Attach photographs as appropriate

#### Notes:

Locations of suction risers can be found on attached Figure.

System details are included in Appendix B.

### III. Piping/Penetrations

1. Is piping intact? (Y or N)
2. Are floor/wall penetrations sealed? (Y or N)

If 'No' to either of the above, provide observations and describe corrective actions taken

#### B. Actions taken:

#### C. Recommended Maintenance/Repairs:

Do any of the pressure gages require repair or replacement?  
If so, indicate locations, and actions taken:

Y \_\_\_ N X

### IV. Building Modifications: Have building modifications been made that could affect the operation of the SSD System? (Describe)

None at this time

#### Additional Comments:

Check condensation trap o/c (bugs) K1

Report all maintenance/repair needs immediately to building facility manager

# Sub-Slab Depressurization System

## Inspection Checklist

Syracuse Label, 110 Luther Avenue, Liverpool, NY

Date:

3-14-14

Inspector Name:

Kevin Gagnon

Company:

SYRLSP

Inspector Initials:

KG

### I. Pressure Readings

Suction Riser Identification	Pressure Reading (inWC)
S-1	3.2
S-2	3.0
S-3	6.3
S-4	5.6
S-5	4.5
S-6	3.9
S-7	2.6
S-8	6.0
S-9	5.5
S-10	0.2
S-11	0
S-12	0.1
S-13	0
S-14	0

### II. Fan Inspection

- |  |   |          |   |          |
|--|---|----------|---|----------|
| 1. Operational?                        | Y | <u>X</u> | N | ___      |
| 2. Fan/Controls Clear of obstructions? | Y | <u>X</u> | N | ___      |
| 3. Repair needs?                       | Y | ___      | N | <u>X</u> |

#### A. Observations/comments:

The Fan that controls #10-14 is down the motor ~~was~~ bad. on 3/3/14 it was Noticed.

Attach photographs as appropriate

#### Notes:

Locations of suction risers can be found on attached Figure.

System details are included in Appendix B.

### III. Piping/Penetrations

1. Is piping intact? (Y or N)
2. Are floor/wall penetrations sealed? (Y or N)

If 'No' to either of the above, provide observations and describe corrective actions taken

#### B. Actions taken:

The Fan unit was sent to Radon Away on 3-7-14 for evaluation.

#### C. Recommended Maintenance/Repairs:

Do any of the pressure gages require repair or replacement?  
If so, indicate locations, and actions taken:

Y \_\_\_ N X

### IV. Building Modifications: Have building modifications been made that could affect the operation of the SSD System? (Describe)

NONE at this time.

#### Additional Comments:

No water found in Condensation traps

Report all maintenance/repair needs immediately to building facility manager

**APPENDIX H**  
**110 LUTHER AVENUE SITE INSPECTION FORM**

Inspections should be done at a minimum of once a year.

More frequent inspections may be required in accordance with approved work plans in specific areas undergoing construction, and following any construction-related work that may expose site soils or affect the operation of the SSDS.

Inspections must be completed if an incident or accident occurs that may require corrective measures (i.e. damage to the SSDS or emergency actions that require soil removal).

**Inspection Data**

Annually ☒

Construction ☐

Post-Construction ☐

Location: 110 Luther Ave Syracuse NY BCP Site # C734118

Inspection Date: 4-24-14

Inspected By: Damian Vanetti GHD

		Y or N	Comments or Problem Identified/Action Taken
1.	<b>Condition of pavement:</b> Are there areas of pavement where sub-soil is exposed?	N	
2.	<b>Conditions of concrete slab:</b> Is the concrete slab of the manufacturing facility intact? Are there cracks or gaps through which underlying soil is exposed?	Y	INTACT
		N	No exposed soil due to gaps/cracks
3.	<b>Sediment/Erosion Control:</b> Are erosion/storm water control devices in place in accordance with Stormwater Pollution Prevention Plan?	NA	
4.	<b>Excavation/Backfill:</b> Has Excavation been completed in accordance with the site Excavation Work Plan?	NA	
5.	<b>Stockpiled Materials:</b> Are temporary soil stockpiles or construction materials protected from erosion?	NA	
6.	<b>Dust Control:</b> Have dust control measures been implemented as needed during the conduct of construction work?	NA	
7.	<b>CAMP:</b> Has Community Air Monitoring been conducted in accordance with the CAMP?	NA	
8.	<b>SSDS:</b> Has an inspection of the SSDS been completed?	Y	

If current inspection is construction or post-construction, describe the nature of the construction project:  
Has a Work Plan been prepared and approved by NYSDEC? Y\_\_\_\_ N\_\_\_\_

NA

Attach photographs as appropriate

If the current inspection is due to an incident or accident, describe the nature of the incident/accident and the corrective measures being taken.

Note: A Corrective Measure Report will need to be submitted to the NYSDEC.

NA

Attach photographs as appropriate

# Sub-Slab Depressurization System

## Inspection Checklist

Syracuse Label, 110 Luther Avenue, Liverpool, NY

Date:

4-24-14

Inspector's Name:

Damian Vavetti

Company:

GHD

Inspector Initials:

### I. Pressure Readings

Suction Riser Identification	Pressure Reading (inWC)
S-1	3.0
S-2	2.75
S-3	5.5
S-4	5.0
S-5	3.5
S-6	3.25
S-7	2.0
S-8	4.5
S-9	3.0
S-10	2.75
S-11	2.5
S-12	2.75
S-13	3.0
S-14	2.5

### II. Fan Inspection

Two fans

	1	2		
1. Operational?	Y	X	X	N
2. Fan/Controls Clear of obstructions?	Y	X	X	N
3. Repair needs?	Y			N

### A. Observations/comments:

SSDS operating as intended and no repair items noted at this time.  
Fan #2 recently repaired and reinstalled on 4-23-14. Fan is operating and vacuum readings taken from manometer on risers indicate fan is functioning as intended.

Attach photographs as appropriate

### Notes:

Locations of suction risers can be found on attached Figure.

System details are included in Appendix B.

### III. Piping/Penetrations

- Is piping intact? (Y or N) Y
- Are floor/wall penetrations sealed? (Y or N) Y

If 'No' to either of the above, provide observations and describe corrective actions taken

### B. Actions taken:

None at this time.

### C. Recommended Maintenance/Repairs:

None at this time

Do any of the pressure gages require repair or replacement?

Y N X

If so, indicate locations, and actions taken:

### IV. Building Modifications: Have building modifications been made that could affect the operation of the SSD System? (Describe)

former sump adjacent to S-11 filled and finished to floor grade.

### Additional Comments:

Report all maintenance/repair needs immediately to building facility manager

## **Appendix D** - Approval Notifications for EQUIS Database Submittals

**Ian McNamara**

---

**From:** NYENVDATA <NYENVDATA@gw.dec.state.ny.us>  
**Sent:** Thursday, August 01, 2013 3:01 PM  
**To:** Ian McNamara  
**Cc:** Christopher Mannes  
**Subject:** Re: EDDs for BCP Site #C734118

Ian,

TRIP BLANK samples do not get locations. We therefore removed the TRIP BLANK sys loc code reference in the EDD "20130725 1123.C734118.NYSDEC.zip". With this small modification, we were able to successfully load the EDDs "20130725 1029.C734118.NYSDEC.zip" and "20130725 1123.C734118.NYSDEC.zip", and the data is ready for use.

Aaron  
NYSDEC EIMS Team

>>> Ian McNamara <[Ian.McNamara@ghd.com](mailto:Ian.McNamara@ghd.com)> 7/25/2013 11:26 AM >>>  
Hello,

Attached please find 2 EDDs for the above referenced site. These EDDs are related to 2<sup>nd</sup> Quarter 2013 Groundwater Monitoring.

Thanks,  
Ian

**Ian McNamara**  
**Environmental Scientist**

**GHD**

T: 1 315 679 5732 | M: 1 315 368 8432 | V: 865732 | E: [ian.mcnamara@ghd.com](mailto:ian.mcnamara@ghd.com)  
One Remington Park Drive Cazenovia New York 13035 USA | [www.ghd.com](http://www.ghd.com)  
[WATER](#) | [ENERGY & RESOURCES](#) | [ENVIRONMENT](#) | [PROPERTY & BUILDINGS](#) | [TRANSPORTATION](#)

Please consider the environment before printing this email

---

This email and all attachments are confidential. For further important information about emails sent to or from GHD or if you have received this email in error, please refer to <http://www.ghd.com/emaildisclaimer.html> .

---

This e-mail has been scanned for viruses by MessageLabs.

---

This e-mail has been scanned for viruses by MessageLabs.



**Ian McNamara**

---

**From:** NYENVDATA <NYENVDATA@gw.dec.state.ny.us>  
**Sent:** Tuesday, November 05, 2013 4:23 PM  
**To:** Ian McNamara  
**Cc:** Christopher Mannes  
**Subject:** Re: EQuIS EDDs for 110 Luther Avenue BCP Site (BCP Site #C734118)

Ian,

Thank you for your EDD submission. NYSDEC has successfully uploaded the EDD "20131023 0847.C734118.NYSDEC.zip" and "20131023 0909.C734118.NYSDEC.zip" and the data is ready for use.

Aaron  
NYSDEC EIMS Team

>>> Ian McNamara <[Ian.McNamara@ghd.com](mailto:Ian.McNamara@ghd.com)> 10/29/2013 8:09 AM >>>

Hi,  
The EDDs for 3<sup>rd</sup> quarter groundwater monitoring conducted at the above referenced site are attached.  
Thanks,  
Ian

**Ian McNamara**  
**Environmental Scientist**

**GHD**

T: 1 315 679 5732 | M: 1 315 368 8432 | V: 865732 | E: [ian.mcnamara@ghd.com](mailto:ian.mcnamara@ghd.com)  
One Remington Park Drive Cazenovia New York 13035 USA | [www.ghd.com](http://www.ghd.com)  
[WATER](#) | [ENERGY & RESOURCES](#) | [ENVIRONMENT](#) | [PROPERTY & BUILDINGS](#) | [TRANSPORTATION](#)

Please consider the environment before printing this email

---

This email and all attachments are confidential. For further important information about emails sent to or from GHD or if you have received this email in error, please refer to <http://www.ghd.com/emaildisclaimer.html> .

---

This e-mail has been scanned for viruses by MessageLabs.

---

This e-mail has been scanned for viruses by MessageLabs.

**Ian McNamara**

---

**From:** NYENVDATA <NYENVDATA@gw.dec.state.ny.us>  
**Sent:** Tuesday, January 28, 2014 3:45 PM  
**To:** Ian McNamara  
**Cc:** Christopher Mannes  
**Subject:** RE: 110 Luther Avenue BCP Site (BCP Site #C734118) EQUIS EDDs

Ian,

EDDs 20140128 0913.C734118.NYSDEC.zip and 20140128 0914.C734118.NYSDEC.zip were successfully uploaded and the data is ready for use. It is assumed that these were meant to replace EDDs 20140114 1405.C734118.NYSDEC.zip and 20140114 1411.C734118.NYSDEC.zip.

Thank you,

Alison

NYSDEC EIMS Team

>>> Ian McNamara <[Ian.McNamara@ghd.com](mailto:Ian.McNamara@ghd.com)> 1/28/2014 9:16 AM >>>

Hi,

Attached are the updated EDDs referenced below.

Please let me know if they are all set this time.

Thanks,

Ian

**Ian McNamara**  
**Environmental Scientist**

**GHD**

T: 1 315 679 5732 | M: 1 315 368 8432 | V: 865732 | E: [ian.mcnamara@ghd.com](mailto:ian.mcnamara@ghd.com)

One Remington Park Drive Cazenovia New York 13035 USA | [www.ghd.com](http://www.ghd.com)

[WATER](#) | [ENERGY & RESOURCES](#) | [ENVIRONMENT](#) | [PROPERTY & BUILDINGS](#) | [TRANSPORTATION](#)

Please consider the environment before printing this email

---

**From:** NYENVDATA [<mailto:NYENVDATA@gw.dec.state.ny.us>]  
**Sent:** Thursday, January 16, 2014 10:46 AM  
**To:** Ian McNamara  
**Cc:** Christopher Mannes  
**Subject:** Re: 110 Luther Avenue BCP Site (BCP Site #C734118) EQUIS EDDs

Ian,

Thank you for the EDDs for site C734118. We had a question before we proceed with uploading. The sys\_sample\_codes in the FieldResults\_v3 table in EDD 20140114 1405.C734118.NYSDEC.zip are slightly different than those in the Sample\_v3 table in EDD 20140114 1411.C734118.NYSDEC.zip. Are the field and laboratory results supposed to be tied to the same sample? If so, they should have the same sys\_sample\_codes. A few of the samples have different sample dates so maybe this is not the case, but we wanted to make sure before uploading.

Thank you,

Alison

NYSDEC EIMS Team

>>> Ian McNamara <[Ian.McNamara@ghd.com](mailto:Ian.McNamara@ghd.com)> 1/14/2014 2:13 PM >>>

Hi,

Attached are 2 EDDs for the above referenced site for 4<sup>th</sup> Quarter 2013 Groundwater Monitoring activities.  
Please let me know if they are acceptable for upload.

Thanks,  
Ian

**Ian McNamara**  
**Environmental Scientist**

**GHD**

T: 1 315 679 5732 | M: 1 315 368 8432 | V: 865732 | E: [ian.mcnamara@ghd.com](mailto:ian.mcnamara@ghd.com)

One Remington Park Drive Cazenovia New York 13035 USA | [www.ghd.com](http://www.ghd.com)

[WATER](#) | [ENERGY & RESOURCES](#) | [ENVIRONMENT](#) | [PROPERTY & BUILDINGS](#) | [TRANSPORTATION](#)

Please consider the environment before printing this email

---

This email and all attachments are confidential. For further important information about emails sent to or from GHD or if you have received this email in error, please refer to <http://www.ghd.com/emaildisclaimer.html>

---

This e-mail has been scanned for viruses

---

This e-mail has been scanned for viruses

---

This e-mail has been scanned for viruses

## **Appendix E** – Groundwater Sampling and Injection Waste Disposal Manifests

<b>NON-HAZARDOUS WASTE MANIFEST</b>		1. Generator ID Number <b>NYD042350751</b>	2. Page 1 of <b>1</b>	3. Emergency Response Phone <b>800-535-5053</b>	4. Waste Tracking Number <b>15145</b>	
5. Generator's Name and Mailing Address <b>Syracuse Label Company Inc.</b> <b>110 Luther Ave</b> <b>Liverpool, NY 13088</b> Generator's Phone: <b>315-422-1037</b>			Generator's Site Address (if different than mailing address)			
6. Transporter 1 Company Name <b>Environmental Service Group, Inc</b>			716.695.6720		U.S. EPA ID Number <b>NYD986903904</b>	
7. Transporter 2 Company Name					U.S. EPA ID Number	
8. Designated Facility Name and Site Address <b>American Recyclers Inc.</b> <b>177 Wales Ave</b> <b>Tonawanda, NY 14150</b> Facility's Phone:			716.695.6720		U.S. EPA ID Number <b>NYR000030809</b>	
9. Waste Shipping Name and Description			10. Containers		11. Total Quantity	12. Unit Wt./Vol.
			No.	Type		
1. Non RCRA Non DOT Regulated, (Soil Cuttings)			002	DM	0300	P
2. Non RCRA Non DOT Regulated, (Printing Inks)			001	PM	055	G
3.						
4.						
13. Special Handling Instructions and Additional Information <b>ERG: Approval #:</b> 1 - 1-A-6622L 2 - 2-D-874IN 3 - 3- 4 - 4- <b>Handling Codes:</b> 1 - None 2 - None 3 - 4 - <b>24 Hour Emergency Contact:</b> <b>INFOTRAC (Caller Must ID ESG)</b>						
14. GENERATOR'S/OFFEROR'S CERTIFICATION: I hereby declare that the contents of this consignment are fully and accurately described above by the proper shipping name, and are classified, packaged, marked and labeled/placarded, and are in all respects in proper condition for transport according to applicable international and national governmental regulations.						
Generator's/Offor's Printed/Typed Name <b>Mark Howard</b>			Signature <b>Mark Howard</b>		Month <b>01</b>	Day <b>14</b>
15. International Shipments <input type="checkbox"/> Import to U.S. <input type="checkbox"/> Export from U.S.			Port of entry/exit: Date leaving U.S.:		Year <b>14</b>	
16. Transporter Acknowledgment of Receipt of Materials						
Transporter 1 Printed/Typed Name <b>Sean P. Winter</b>			Signature <b>Sean P. Winter</b>		Month <b>01</b>	Day <b>14</b>
Transporter 2 Printed/Typed Name			Signature		Year <b>14</b>	
17. Discrepancy						
17a. Discrepancy Indication Space <input type="checkbox"/> Quantity <input type="checkbox"/> Type <input type="checkbox"/> Residue <input type="checkbox"/> Partial Rejection <input type="checkbox"/> Full Rejection Manifest Reference Number:						
17b. Alternate Facility (or Generator) U.S. EPA ID Number						
Facility's Phone:						
17c. Signature of Alternate Facility (or Generator) Month Day Year						
18. Designated Facility Owner or Operator: Certification of receipt of materials covered by the manifest except as noted in Item 17a						
Printed/Typed Name <b>Sullivan Mastropoli</b>			Signature <b>Sullivan Mastropoli</b>		Month <b>01</b>	Day <b>17</b>
Year <b>14</b>						

DESIGNATED FACILITY TO GENERATOR



177 Wales Ave., Tonawanda, NY, 14150  
NYR 000 030 809

## CERTIFICATE OF DISPOSAL for:


Syracuse Label  
110 Luther Ave., Liverpool, NY 13088  
EPA ID # NYD042350751

MANIFEST NUMBER: 15145

<u>TYPE</u>	<u>QUANTITY</u>	<u>APPROVAL NUMBER</u>
Soil Cuttings	2 Drums	A-6622L

THIS IS TO CERTIFY THAT THE ABOVE DESCRIBED WASTE HAS BEEN DISPOSED OF IN ACCORDANCE TO FEDERAL, STATE, AND LOCAL LAWS.

SIGNED:

  
Julian Mastropoll  
Facility Manager

DATE: 01/14/14

GHD Inc  
One Remington Park Drive  
Cazenovia NY 13035  
T: 1 315 679 5800 F: 1 315 679 5801 E: cazmail@ghd.com

© GHD Inc 2013

This document is and shall remain the property of GHD. The document may only be used for the purpose of assessing our offer of services and for inclusion in documentation for the engagement of GHD. Unauthorized use of this document in any form whatsoever is prohibited.

G:\86\14941\PRRs\PRR June 2013-June 2014\PRR - June.2013 - June.2014.docx

Document Status

Rev No.	Author	Reviewer		Approved for Issue		
		Name	Signature	Name	Signature	Date

[www.ghd.com](http://www.ghd.com)

