Pace Analytical Services, LLC - East Longmeadow, Ma

39 Spruce Street * East Longmeadow, MA 01028 * FAX 413/525-6405 * TEL. 413/525-2332

August 12, 2025

Karen Cahill
NYDEC_WSP - Buffalo, NY
50 Lakefront Boulevard #111
Buffalo, NY 14202

Project Location: Canada Drive, East Syracuse, NY
Client Job Number:
Project Number: C734145A
Laboratory Work Order Number: 25G2026

Enclosed are results of analyses for samples as received by the laboratory on July 30, 2025. If you have any questions concerning this report, please feel free to contact me.

Sincerely,



Raymond J. McCarthy
Project Manager

Table of Contents

Sample Summary 3

Case Narrative 4

Sample Results 5

25G2026-01 5

25G2026-02 7

25G2026-03 9

25G2026-04 11

25G2026-05 13

25G2026-06 15

25G2026-07 17

25G2026-08 19

25G2026-09 21

25G2026-10 23

25G2026-11 25

25G2026-12 27

25G2026-13 29

25G2026-14 31

Sample Preparation Information 33

QC Data 34

Polychlorinated Biphenyls By GC/ECD 34

B410860 34

Dual Column RPD Report 35

Flag/Qualifier Summary 51

Certifications 52

Chain of Custody/Sample Receipt 54

Pace Analytical Services, LLC - East Longmeadow, Ma

39 Spruce Street * East Longmeadow, MA 01028 * FAX 413/525-6405 * TEL. 413/525-2332

NYDEC_WSP - Buffalo, NY
50 Lakefront Boulevard #111
Buffalo, NY 14202
ATTN: Karen Cahill

REPORT DATE: 8/12/2025

PURCHASE ORDER NUMBER: 153133

PROJECT NUMBER: C734145A

ANALYTICAL SUMMARY

WORK ORDER NUMBER: 25G2026

The results of analyses performed on the following samples submitted to Pace Analytical Services, LLC - East Longmeadow, Ma, are found in this report.

PROJECT LOCATION: Canada Drive, East Syracuse, NY

FIELD SAMPLE #	LAB ID:	MATRIX	SAMPLE DESCRIPTION	TEST	SUB LAB
SB80-Z00-12	25G2026-01	Soil		SM 2540G	
				SW-846 8082A	
SB80-Z12-24	25G2026-02	Soil		SM 2540G	
				SW-846 8082A	
SB80-Z24-36	25G2026-03	Soil		SM 2540G	
				SW-846 8082A	
SB80-Z36-48	25G2026-04	Soil		SM 2540G	
				SW-846 8082A	
SB81-Z00-12	25G2026-05	Soil		SM 2540G	
				SW-846 8082A	
SB81-Z12-24	25G2026-06	Soil		SM 2540G	
				SW-846 8082A	
SB81-Z24-36	25G2026-07	Soil		SM 2540G	
				SW-846 8082A	
SB81-Z36-48	25G2026-08	Soil		SM 2540G	
				SW-846 8082A	
SB82-Z00-12	25G2026-09	Soil		SM 2540G	
				SW-846 8082A	
SB82-Z00-12-Q	25G2026-10	Soil		SM 2540G	
				SW-846 8082A	
SB82-Z12-24	25G2026-11	Soil		SM 2540G	
				SW-846 8082A	
SB82-Z24-36	25G2026-12	Soil		SM 2540G	
				SW-846 8082A	
SB82-Z36-48	25G2026-13	Soil		SM 2540G	
				SW-846 8082A	
SB83-Z00-12	25G2026-14	Soil		SM 2540G	
				SW-846 8082A	

Pace Analytical Services, LLC - East Longmeadow, Ma

39 Spruce Street * East Longmeadow, MA 01028 * FAX 413/525-6405 * TEL. 413/525-2332

CASE NARRATIVE SUMMARY

All reported results are within defined laboratory quality control objectives unless listed below or otherwise qualified in this report.

For any Soil analysis, the Method Blank, LCS, and LCSD are reported on a 100% solids basis.

SW-846 8082A

Qualifications:

S-01

The surrogate recovery for this sample is not available due to sample dilution below the surrogate reporting limit required from high analyte concentration and/or matrix interferences.

Analyte & Samples(s) Qualified:


Decachlorobiphenyl
25G2026-01[SB80-Z00-12], 25G2026-02[SB80-Z12-24], 25G2026-03[SB80-Z24-36], 25G2026-04[SB80-Z36-48], 25G2026-05[SB81-Z00-12], 25G2026-06[SB81-Z12-24], 25G2026-07[SB81-Z24-36], 25G2026-08[SB81-Z36-48], 25G2026-09[SB82-Z00-12], 25G2026-10[SB82-Z00-12-Q], 25G2026- 11[SB82-Z12-24], 25G2026-12[SB82-Z24-36]

Decachlorobiphenyl [2C]
25G2026-01[SB80-Z00-12], 25G2026-02[SB80-Z12-24], 25G2026-03[SB80-Z24-36], 25G2026-04[SB80-Z36-48], 25G2026-05[SB81-Z00-12], 25G2026-06[SB81-Z12-24], 25G2026-07[SB81-Z24-36], 25G2026-08[SB81-Z36-48], 25G2026-09[SB82-Z00-12], 25G2026-10[SB82-Z00-12-Q], 25G2026- 11[SB82-Z12-24], 25G2026-12[SB82-Z24-36]

Tetrachloro-m-xylene
25G2026-01[SB80-Z00-12], 25G2026-02[SB80-Z12-24], 25G2026-03[SB80-Z24-36], 25G2026-04[SB80-Z36-48], 25G2026-05[SB81-Z00-12], 25G2026-06[SB81-Z12-24], 25G2026-07[SB81-Z24-36], 25G2026-08[SB81-Z36-48], 25G2026-09[SB82-Z00-12], 25G2026-10[SB82-Z00-12-Q], 25G2026- 11[SB82-Z12-24], 25G2026-12[SB82-Z24-36]

Tetrachloro-m-xylene [2C]
25G2026-01[SB80-Z00-12], 25G2026-02[SB80-Z12-24], 25G2026-03[SB80-Z24-36], 25G2026-04[SB80-Z36-48], 25G2026-05[SB81-Z00-12], 25G2026-06[SB81-Z12-24], 25G2026-07[SB81-Z24-36], 25G2026-08[SB81-Z36-48], 25G2026-09[SB82-Z00-12], 25G2026-10[SB82-Z00-12-Q], 25G2026- 11[SB82-Z12-24], 25G2026-12[SB82-Z24-36]

The results of analyses reported only relate to samples submitted to Pace Analytical Services, LLC - East Longmeadow, Ma, for testing.
I certify that the analyses listed above, unless specifically listed as subcontracted, if any, were performed under my direction according to the approved methodologies listed in this document, and that based upon my inquiry of those individuals immediately responsible for obtaining the information, the material contained in this report is, to the best of my knowledge and belief, accurate and complete.



Meghan E. Kelley
Reporting Specialist

Pace Analytical Services, LLC - East Longmeadow, Ma

39 Spruce Street * East Longmeadow, MA 01028 * FAX 413/525-6405 * TEL. 413/525-2332

Project Location: Canada Drive, East Syracuse, NY Sample Description: Work Order: 25G2026

Date Received: 7/30/2025

Field Sample #: SB80-Z00-12 Sampled: 7/28/2025 12:52

Sample ID: 25G2026-01

Sample Matrix: Soil

Polychlorinated Biphenyls By GC/ECD

Analyte	Results	RL	DL	Units	Dilution	Flag/Qual	Method	Date Prepared	Date/Time Analyzed	Analyst
Aroclor-1016 [2]	ND	4.3	1.2	mg/Kg dry	200		SW-846 8082A	8/7/25	8/11/25 8:09	TG
Aroclor-1221 [2]	ND	4.3	2.0	mg/Kg dry	200		SW-846 8082A	8/7/25	8/11/25 8:09	TG
Aroclor-1232 [2]	ND	4.3	1.2	mg/Kg dry	200		SW-846 8082A	8/7/25	8/11/25 8:09	TG
Aroclor-1242 [2]	ND	4.3	1.3	mg/Kg dry	200		SW-846 8082A	8/7/25	8/11/25 8:09	TG
Aroclor-1248 [2]	49	4.3	1.6	mg/Kg dry	200		SW-846 8082A	8/7/25	8/11/25 8:09	TG
Aroclor-1254 [2]	ND	4.3	2.1	mg/Kg dry	200		SW-846 8082A	8/7/25	8/11/25 8:09	TG
Aroclor-1260 [2]	ND	4.3	1.2	mg/Kg dry	200		SW-846 8082A	8/7/25	8/11/25 8:09	TG
Aroclor-1262 [2]	ND	4.3	1.5	mg/Kg dry	200		SW-846 8082A	8/7/25	8/11/25 8:09	TG
Aroclor-1268 [2]	ND	4.3	1.4	mg/Kg dry	200		SW-846 8082A	8/7/25	8/11/25 8:09	TG

Surrogates	% Recovery	Recovery Limits	Flag/Qual	
Decachlorobiphenyl [1]	*	30-150	S-01	8/11/25 8:09
Decachlorobiphenyl [2]	*	30-150	S-01	8/11/25 8:09
Tetrachloro-m-xylene [1]	*	30-150	S-01	8/11/25 8:09
Tetrachloro-m-xylene [2]	*	30-150	S-01	8/11/25 8:09

Pace Analytical Services, LLC - East Longmeadow, Ma

39 Spruce Street * East Longmeadow, MA 01028 * FAX 413/525-6405 * TEL. 413/525-2332

Project Location: Canada Drive, East Syracuse, NY Sample Description: Work Order: 25G2026

Date Received: 7/30/2025

Field Sample #: SB80-Z00-12 Sampled: 7/28/2025 12:52

Sample ID: 25G2026-01

Sample Matrix: Soil

Conventional Chemistry Parameters by EPA/APHA/SW-846 Methods (Total)

Analyte	Results	RL	Units	Dilution	Flag/Qual	Method	Date Prepared	Date/Time Analyzed	Analyst
% Solids	92.2		% Wt	1		SM 2540G	7/31/25	8/1/25 11:51	DMB

Pace Analytical Services, LLC - East Longmeadow, Ma

39 Spruce Street * East Longmeadow, MA 01028 * FAX 413/525-6405 * TEL. 413/525-2332

Project Location: Canada Drive, East Syracuse, NY Sample Description: Work Order: 25G2026

Date Received: 7/30/2025

Field Sample #: SB80-Z12-24 Sampled: 7/28/2025 12:53

Sample ID: 25G2026-02

Sample Matrix: Soil

Polychlorinated Biphenyls By GC/ECD

Analyte	Results	RL	DL	Units	Dilution	Flag/Qual	Method	Date Prepared	Date/Time Analyzed	Analyst
Aroclor-1016 [2]	ND	4.2	1.1	mg/Kg dry	200		SW-846 8082A	8/7/25	8/11/25 8:26	TG
Aroclor-1221 [2]	ND	4.2	1.9	mg/Kg dry	200		SW-846 8082A	8/7/25	8/11/25 8:26	TG
Aroclor-1232 [2]	ND	4.2	1.2	mg/Kg dry	200		SW-846 8082A	8/7/25	8/11/25 8:26	TG
Aroclor-1242 [2]	ND	4.2	1.3	mg/Kg dry	200		SW-846 8082A	8/7/25	8/11/25 8:26	TG
Aroclor-1248 [2]	71	4.2	1.6	mg/Kg dry	200		SW-846 8082A	8/7/25	8/11/25 8:26	TG
Aroclor-1254 [2]	ND	4.2	2.0	mg/Kg dry	200		SW-846 8082A	8/7/25	8/11/25 8:26	TG
Aroclor-1260 [2]	ND	4.2	1.2	mg/Kg dry	200		SW-846 8082A	8/7/25	8/11/25 8:26	TG
Aroclor-1262 [2]	ND	4.2	1.4	mg/Kg dry	200		SW-846 8082A	8/7/25	8/11/25 8:26	TG
Aroclor-1268 [2]	ND	4.2	1.4	mg/Kg dry	200		SW-846 8082A	8/7/25	8/11/25 8:26	TG

Surrogates	% Recovery	Recovery Limits	Flag/Qual	
Decachlorobiphenyl [1]	*	30-150	S-01	8/11/25 8:26
Decachlorobiphenyl [2]	*	30-150	S-01	8/11/25 8:26
Tetrachloro-m-xylene [1]	*	30-150	S-01	8/11/25 8:26
Tetrachloro-m-xylene [2]	*	30-150	S-01	8/11/25 8:26

Pace Analytical Services, LLC - East Longmeadow, Ma

39 Spruce Street * East Longmeadow, MA 01028 * FAX 413/525-6405 * TEL. 413/525-2332

Project Location: Canada Drive, East Syracuse, NY Sample Description: Work Order: 25G2026

Date Received: 7/30/2025

Field Sample #: SB80-Z12-24 Sampled: 7/28/2025 12:53

Sample ID: 25G2026-02

Sample Matrix: Soil

Conventional Chemistry Parameters by EPA/APHA/SW-846 Methods (Total)

Analyte	Results	RL	Units	Dilution	Flag/Qual	Method	Date Prepared	Date/Time Analyzed	Analyst
% Solids	95.9		% Wt	1		SM 2540G	7/31/25	8/1/25 11:51	DMB

Pace Analytical Services, LLC - East Longmeadow, Ma

39 Spruce Street * East Longmeadow, MA 01028 * FAX 413/525-6405 * TEL. 413/525-2332

Project Location: Canada Drive, East Syracuse, NY Sample Description: Work Order: 25G2026

Date Received: 7/30/2025

Field Sample #: SB80-Z24-36 Sampled: 7/28/2025 12:54

Sample ID: 25G2026-03

Sample Matrix: Soil

Polychlorinated Biphenyls By GC/ECD

Analyte	Results	RL	DL	Units	Dilution	Flag/Qual	Method	Date Prepared	Date/Time Analyzed	Analyst
Aroclor-1016 [2]	ND	8.5	2.3	mg/Kg dry	400		SW-846 8082A	8/7/25	8/11/25 8:44	TG
Aroclor-1221 [2]	ND	8.5	3.9	mg/Kg dry	400		SW-846 8082A	8/7/25	8/11/25 8:44	TG
Aroclor-1232 [2]	ND	8.5	2.4	mg/Kg dry	400		SW-846 8082A	8/7/25	8/11/25 8:44	TG
Aroclor-1242 [2]	ND	8.5	2.6	mg/Kg dry	400		SW-846 8082A	8/7/25	8/11/25 8:44	TG
Aroclor-1248 [2]	90	8.5	3.2	mg/Kg dry	400		SW-846 8082A	8/7/25	8/11/25 8:44	TG
Aroclor-1254 [2]	ND	8.5	4.2	mg/Kg dry	400		SW-846 8082A	8/7/25	8/11/25 8:44	TG
Aroclor-1260 [2]	ND	8.5	2.4	mg/Kg dry	400		SW-846 8082A	8/7/25	8/11/25 8:44	TG
Aroclor-1262 [2]	ND	8.5	2.9	mg/Kg dry	400		SW-846 8082A	8/7/25	8/11/25 8:44	TG
Aroclor-1268 [2]	ND	8.5	2.8	mg/Kg dry	400		SW-846 8082A	8/7/25	8/11/25 8:44	TG

Surrogates	% Recovery	Recovery Limits	Flag/Qual	
Decachlorobiphenyl [1]	*	30-150	S-01	8/11/25 8:44
Decachlorobiphenyl [2]	*	30-150	S-01	8/11/25 8:44
Tetrachloro-m-xylene [1]	*	30-150	S-01	8/11/25 8:44
Tetrachloro-m-xylene [2]	*	30-150	S-01	8/11/25 8:44

Pace Analytical Services, LLC - East Longmeadow, Ma

39 Spruce Street * East Longmeadow, MA 01028 * FAX 413/525-6405 * TEL. 413/525-2332

Project Location: Canada Drive, East Syracuse, NY Sample Description: Work Order: 25G2026

Date Received: 7/30/2025

Field Sample #: SB80-Z24-36 Sampled: 7/28/2025 12:54

Sample ID: 25G2026-03

Sample Matrix: Soil

Conventional Chemistry Parameters by EPA/APHA/SW-846 Methods (Total)

Analyte	Results	RL	Units	Dilution	Flag/Qual	Method	Date Prepared	Date/Time Analyzed	Analyst
% Solids	94.1		% Wt	1		SM 2540G	7/31/25	8/1/25 11:51	DMB

Pace Analytical Services, LLC - East Longmeadow, Ma

39 Spruce Street * East Longmeadow, MA 01028 * FAX 413/525-6405 * TEL. 413/525-2332

Project Location: Canada Drive, East Syracuse, NY Sample Description: Work Order: 25G2026

Date Received: 7/30/2025

Field Sample #: SB80-Z36-48 Sampled: 7/28/2025 12:55

Sample ID: 25G2026-04

Sample Matrix: Soil

Polychlorinated Biphenyls By GC/ECD

Analyte	Results	RL	DL	Units	Dilution	Flag/Qual	Method	Date Prepared	Date/Time Analyzed	Analyst
Aroclor-1016 [2]	ND	8.7	2.4	mg/Kg dry	400		SW-846 8082A	8/7/25	8/11/25 9:02	TG
Aroclor-1221 [2]	ND	8.7	4.0	mg/Kg dry	400		SW-846 8082A	8/7/25	8/11/25 9:02	TG
Aroclor-1232 [2]	ND	8.7	2.5	mg/Kg dry	400		SW-846 8082A	8/7/25	8/11/25 9:02	TG
Aroclor-1242 [2]	ND	8.7	2.7	mg/Kg dry	400		SW-846 8082A	8/7/25	8/11/25 9:02	TG
Aroclor-1248 [2]	52	8.7	3.3	mg/Kg dry	400		SW-846 8082A	8/7/25	8/11/25 9:02	TG
Aroclor-1254 [2]	ND	8.7	4.3	mg/Kg dry	400		SW-846 8082A	8/7/25	8/11/25 9:02	TG
Aroclor-1260 [2]	ND	8.7	2.4	mg/Kg dry	400		SW-846 8082A	8/7/25	8/11/25 9:02	TG
Aroclor-1262 [2]	ND	8.7	3.0	mg/Kg dry	400		SW-846 8082A	8/7/25	8/11/25 9:02	TG
Aroclor-1268 [2]	ND	8.7	2.9	mg/Kg dry	400		SW-846 8082A	8/7/25	8/11/25 9:02	TG

Surrogates	% Recovery	Recovery Limits	Flag/Qual	
Decachlorobiphenyl [1]	*	30-150	S-01	8/11/25 9:02
Decachlorobiphenyl [2]	*	30-150	S-01	8/11/25 9:02
Tetrachloro-m-xylene [1]	*	30-150	S-01	8/11/25 9:02
Tetrachloro-m-xylene [2]	*	30-150	S-01	8/11/25 9:02

Pace Analytical Services, LLC - East Longmeadow, Ma

39 Spruce Street * East Longmeadow, MA 01028 * FAX 413/525-6405 * TEL. 413/525-2332

Project Location: Canada Drive, East Syracuse, NY Sample Description: Work Order: 25G2026

Date Received: 7/30/2025

Field Sample #: SB80-Z36-48 Sampled: 7/28/2025 12:55

Sample ID: 25G2026-04

Sample Matrix: Soil

Conventional Chemistry Parameters by EPA/APHA/SW-846 Methods (Total)

Analyte	Results	RL	Units	Dilution	Flag/Qual	Method	Date Prepared	Date/Time Analyzed	Analyst
% Solids	91.9		% Wt	1		SM 2540G	7/31/25	8/1/25 11:51	DMB

Pace Analytical Services, LLC - East Longmeadow, Ma

39 Spruce Street * East Longmeadow, MA 01028 * FAX 413/525-6405 * TEL. 413/525-2332

Project Location: Canada Drive, East Syracuse, NY Sample Description: Work Order: 25G2026

Date Received: 7/30/2025

Field Sample #: SB81-Z00-12 Sampled: 7/28/2025 12:56

Sample ID: 25G2026-05

Sample Matrix: Soil

Polychlorinated Biphenyls By GC/ECD

Analyte	Results	RL	DL	Units	Dilution	Flag/Qual	Method	Date Prepared	Date/Time Analyzed	Analyst
Aroclor-1016 [2]	ND	4.5	1.2	mg/Kg dry	200		SW-846 8082A	8/7/25	8/11/25 9:19	TG
Aroclor-1221 [2]	ND	4.5	2.1	mg/Kg dry	200		SW-846 8082A	8/7/25	8/11/25 9:19	TG
Aroclor-1232 [2]	ND	4.5	1.3	mg/Kg dry	200		SW-846 8082A	8/7/25	8/11/25 9:19	TG
Aroclor-1242 [2]	ND	4.5	1.4	mg/Kg dry	200		SW-846 8082A	8/7/25	8/11/25 9:19	TG
Aroclor-1248 [2]	28	4.5	1.7	mg/Kg dry	200		SW-846 8082A	8/7/25	8/11/25 9:19	TG
Aroclor-1254 [2]	ND	4.5	2.2	mg/Kg dry	200		SW-846 8082A	8/7/25	8/11/25 9:19	TG
Aroclor-1260 [2]	ND	4.5	1.3	mg/Kg dry	200		SW-846 8082A	8/7/25	8/11/25 9:19	TG
Aroclor-1262 [2]	ND	4.5	1.6	mg/Kg dry	200		SW-846 8082A	8/7/25	8/11/25 9:19	TG
Aroclor-1268 [2]	ND	4.5	1.5	mg/Kg dry	200		SW-846 8082A	8/7/25	8/11/25 9:19	TG

Surrogates	% Recovery	Recovery Limits	Flag/Qual	
Decachlorobiphenyl [1]	*	30-150	S-01	8/11/25 9:19
Decachlorobiphenyl [2]	*	30-150	S-01	8/11/25 9:19
Tetrachloro-m-xylene [1]	*	30-150	S-01	8/11/25 9:19
Tetrachloro-m-xylene [2]	*	30-150	S-01	8/11/25 9:19

Pace Analytical Services, LLC - East Longmeadow, Ma

39 Spruce Street * East Longmeadow, MA 01028 * FAX 413/525-6405 * TEL. 413/525-2332

Project Location: Canada Drive, East Syracuse, NY Sample Description: Work Order: 25G2026

Date Received: 7/30/2025

Field Sample #: SB81-Z00-12 Sampled: 7/28/2025 12:56

Sample ID: 25G2026-05

Sample Matrix: Soil

Conventional Chemistry Parameters by EPA/APHA/SW-846 Methods (Total)

Analyte	Results	RL	Units	Dilution	Flag/Qual	Method	Date Prepared	Date/Time Analyzed	Analyst
% Solids	87.9		% Wt	1		SM 2540G	7/31/25	8/1/25 11:51	DMB

Pace Analytical Services, LLC - East Longmeadow, Ma

39 Spruce Street * East Longmeadow, MA 01028 * FAX 413/525-6405 * TEL. 413/525-2332

Project Location: Canada Drive, East Syracuse, NY Sample Description: Work Order: 25G2026

Date Received: 7/30/2025

Field Sample #: SB81-Z12-24 Sampled: 7/28/2025 12:57

Sample ID: 25G2026-06

Sample Matrix: Soil

Polychlorinated Biphenyls By GC/ECD

Analyte	Results	RL	DL	Units	Dilution	Flag/Qual	Method	Date Prepared	Date/Time Analyzed	Analyst
Aroclor-1016 [2]	ND	4.3	1.1	mg/Kg dry	200		SW-846 8082A	8/7/25	8/11/25 9:37	TG
Aroclor-1221 [2]	ND	4.3	2.0	mg/Kg dry	200		SW-846 8082A	8/7/25	8/11/25 9:37	TG
Aroclor-1232 [2]	ND	4.3	1.2	mg/Kg dry	200		SW-846 8082A	8/7/25	8/11/25 9:37	TG
Aroclor-1242 [2]	ND	4.3	1.3	mg/Kg dry	200		SW-846 8082A	8/7/25	8/11/25 9:37	TG
Aroclor-1248 [2]	32	4.3	1.6	mg/Kg dry	200		SW-846 8082A	8/7/25	8/11/25 9:37	TG
Aroclor-1254 [2]	ND	4.3	2.1	mg/Kg dry	200		SW-846 8082A	8/7/25	8/11/25 9:37	TG
Aroclor-1260 [2]	ND	4.3	1.2	mg/Kg dry	200		SW-846 8082A	8/7/25	8/11/25 9:37	TG
Aroclor-1262 [2]	ND	4.3	1.5	mg/Kg dry	200		SW-846 8082A	8/7/25	8/11/25 9:37	TG
Aroclor-1268 [2]	ND	4.3	1.4	mg/Kg dry	200		SW-846 8082A	8/7/25	8/11/25 9:37	TG

Surrogates	% Recovery	Recovery Limits	Flag/Qual	
Decachlorobiphenyl [1]	*	30-150	S-01	8/11/25 9:37
Decachlorobiphenyl [2]	*	30-150	S-01	8/11/25 9:37
Tetrachloro-m-xylene [1]	*	30-150	S-01	8/11/25 9:37
Tetrachloro-m-xylene [2]	*	30-150	S-01	8/11/25 9:37

Pace Analytical Services, LLC - East Longmeadow, Ma

39 Spruce Street * East Longmeadow, MA 01028 * FAX 413/525-6405 * TEL. 413/525-2332

Project Location: Canada Drive, East Syracuse, NY Sample Description: Work Order: 25G2026

Date Received: 7/30/2025

Field Sample #: SB81-Z12-24 Sampled: 7/28/2025 12:57

Sample ID: 25G2026-06

Sample Matrix: Soil

Conventional Chemistry Parameters by EPA/APHA/SW-846 Methods (Total)

Analyte	Results	RL	Units	Dilution	Flag/Qual	Method	Date Prepared	Date/Time Analyzed	Analyst
% Solids	93.6		% Wt	1		SM 2540G	7/31/25	8/1/25 11:51	DMB

Pace Analytical Services, LLC - East Longmeadow, Ma

39 Spruce Street * East Longmeadow, MA 01028 * FAX 413/525-6405 * TEL. 413/525-2332

Project Location: Canada Drive, East Syracuse, NY Sample Description: Work Order: 25G2026

Date Received: 7/30/2025

Field Sample #: SB81-Z24-36 Sampled: 7/28/2025 12:38

Sample ID: 25G2026-07

Sample Matrix: Soil

Polychlorinated Biphenyls By GC/ECD

Analyte	Results	RL	DL	Units	Dilution	Flag/Qual	Method	Date Prepared	Date/Time Analyzed	Analyst
Aroclor-1016 [2]	ND	8.4	2.3	mg/Kg dry	400		SW-846 8082A	8/7/25	8/11/25 9:54	TG
Aroclor-1221 [2]	ND	8.4	3.9	mg/Kg dry	400		SW-846 8082A	8/7/25	8/11/25 9:54	TG
Aroclor-1232 [2]	ND	8.4	2.4	mg/Kg dry	400		SW-846 8082A	8/7/25	8/11/25 9:54	TG
Aroclor-1242 [2]	ND	8.4	2.6	mg/Kg dry	400		SW-846 8082A	8/7/25	8/11/25 9:54	TG
Aroclor-1248 [2]	68	8.4	3.2	mg/Kg dry	400		SW-846 8082A	8/7/25	8/11/25 9:54	TG
Aroclor-1254 [2]	ND	8.4	4.1	mg/Kg dry	400		SW-846 8082A	8/7/25	8/11/25 9:54	TG
Aroclor-1260 [2]	ND	8.4	2.4	mg/Kg dry	400		SW-846 8082A	8/7/25	8/11/25 9:54	TG
Aroclor-1262 [2]	ND	8.4	2.9	mg/Kg dry	400		SW-846 8082A	8/7/25	8/11/25 9:54	TG
Aroclor-1268 [2]	ND	8.4	2.8	mg/Kg dry	400		SW-846 8082A	8/7/25	8/11/25 9:54	TG

Surrogates	% Recovery	Recovery Limits	Flag/Qual	
Decachlorobiphenyl [1]	*	30-150	S-01	8/11/25 9:54
Decachlorobiphenyl [2]	*	30-150	S-01	8/11/25 9:54
Tetrachloro-m-xylene [1]	*	30-150	S-01	8/11/25 9:54
Tetrachloro-m-xylene [2]	*	30-150	S-01	8/11/25 9:54

Pace Analytical Services, LLC - East Longmeadow, Ma

39 Spruce Street * East Longmeadow, MA 01028 * FAX 413/525-6405 * TEL. 413/525-2332

Project Location: Canada Drive, East Syracuse, NY Sample Description: Work Order: 25G2026

Date Received: 7/30/2025

Field Sample #: SB81-Z24-36 Sampled: 7/28/2025 12:38

Sample ID: 25G2026-07

Sample Matrix: Soil

Conventional Chemistry Parameters by EPA/APHA/SW-846 Methods (Total)

Analyte	Results	RL	Units	Dilution	Flag/Qual	Method	Date Prepared	Date/Time Analyzed	Analyst
% Solids	94.6		% Wt	1		SM 2540G	7/31/25	8/1/25 11:51	DMB

Pace Analytical Services, LLC - East Longmeadow, Ma

39 Spruce Street * East Longmeadow, MA 01028 * FAX 413/525-6405 * TEL. 413/525-2332

Project Location: Canada Drive, East Syracuse, NY Sample Description: Work Order: 25G2026

Date Received: 7/30/2025

Field Sample #: SB81-Z36-48 Sampled: 7/28/2025 12:39

Sample ID: 25G2026-08

Sample Matrix: Soil

Polychlorinated Biphenyls By GC/ECD

Analyte	Results	RL	DL	Units	Dilution	Flag/Qual	Method	Date Prepared	Date/Time Analyzed	Analyst
Aroclor-1016 [2]	ND	18	4.8	mg/Kg dry	800		SW-846 8082A	8/7/25	8/11/25 10:12	TG
Aroclor-1221 [2]	ND	18	8.2	mg/Kg dry	800		SW-846 8082A	8/7/25	8/11/25 10:12	TG
Aroclor-1232 [2]	ND	18	5.0	mg/Kg dry	800		SW-846 8082A	8/7/25	8/11/25 10:12	TG
Aroclor-1242 [2]	ND	18	5.5	mg/Kg dry	800		SW-846 8082A	8/7/25	8/11/25 10:12	TG
Aroclor-1248 [2]	150	18	6.7	mg/Kg dry	800		SW-846 8082A	8/7/25	8/11/25 10:12	TG
Aroclor-1254 [2]	ND	18	8.7	mg/Kg dry	800		SW-846 8082A	8/7/25	8/11/25 10:12	TG
Aroclor-1260 [2]	ND	18	4.9	mg/Kg dry	800		SW-846 8082A	8/7/25	8/11/25 10:12	TG
Aroclor-1262 [2]	ND	18	6.1	mg/Kg dry	800		SW-846 8082A	8/7/25	8/11/25 10:12	TG
Aroclor-1268 [2]	ND	18	5.8	mg/Kg dry	800		SW-846 8082A	8/7/25	8/11/25 10:12	TG

Surrogates	% Recovery	Recovery Limits	Flag/Qual	
Decachlorobiphenyl [1]	*	30-150	S-01	8/11/25 10:12
Decachlorobiphenyl [2]	*	30-150	S-01	8/11/25 10:12
Tetrachloro-m-xylene [1]	*	30-150	S-01	8/11/25 10:12
Tetrachloro-m-xylene [2]	*	30-150	S-01	8/11/25 10:12

Pace Analytical Services, LLC - East Longmeadow, Ma

39 Spruce Street * East Longmeadow, MA 01028 * FAX 413/525-6405 * TEL. 413/525-2332

Project Location: Canada Drive, East Syracuse, NY Sample Description: Work Order: 25G2026

Date Received: 7/30/2025

Field Sample #: SB81-Z36-48 Sampled: 7/28/2025 12:39

Sample ID: 25G2026-08

Sample Matrix: Soil

Conventional Chemistry Parameters by EPA/APHA/SW-846 Methods (Total)

Analyte	Results	RL	Units	Dilution	Flag/Qual	Method	Date Prepared	Date/Time Analyzed	Analyst
% Solids	89.9		% Wt	1		SM 2540G	7/31/25	8/1/25 11:51	DMB

Pace Analytical Services, LLC - East Longmeadow, Ma

39 Spruce Street * East Longmeadow, MA 01028 * FAX 413/525-6405 * TEL. 413/525-2332

Project Location: Canada Drive, East Syracuse, NY Sample Description: Work Order: 25G2026

Date Received: 7/30/2025

Field Sample #: SB82-Z00-12 Sampled: 7/28/2025 12:27

Sample ID: 25G2026-09

Sample Matrix: Soil

Polychlorinated Biphenyls By GC/ECD

Analyte	Results	RL	DL	Units	Dilution	Flag/Qual	Method	Date Prepared	Date/Time Analyzed	Analyst
Aroclor-1016 [2]	ND	4.3	1.2	mg/Kg dry	200		SW-846 8082A	8/7/25	8/11/25 10:30	TG
Aroclor-1221 [2]	ND	4.3	2.0	mg/Kg dry	200		SW-846 8082A	8/7/25	8/11/25 10:30	TG
Aroclor-1232 [2]	ND	4.3	1.2	mg/Kg dry	200		SW-846 8082A	8/7/25	8/11/25 10:30	TG
Aroclor-1242 [2]	ND	4.3	1.3	mg/Kg dry	200		SW-846 8082A	8/7/25	8/11/25 10:30	TG
Aroclor-1248 [2]	15	4.3	1.7	mg/Kg dry	200		SW-846 8082A	8/7/25	8/11/25 10:30	TG
Aroclor-1254 [2]	ND	4.3	2.1	mg/Kg dry	200		SW-846 8082A	8/7/25	8/11/25 10:30	TG
Aroclor-1260 [2]	ND	4.3	1.2	mg/Kg dry	200		SW-846 8082A	8/7/25	8/11/25 10:30	TG
Aroclor-1262 [2]	ND	4.3	1.5	mg/Kg dry	200		SW-846 8082A	8/7/25	8/11/25 10:30	TG
Aroclor-1268 [2]	ND	4.3	1.4	mg/Kg dry	200		SW-846 8082A	8/7/25	8/11/25 10:30	TG

Surrogates	% Recovery	Recovery Limits	Flag/Qual	
Decachlorobiphenyl [1]	*	30-150	S-01	8/11/25 10:30
Decachlorobiphenyl [2]	*	30-150	S-01	8/11/25 10:30
Tetrachloro-m-xylene [1]	*	30-150	S-01	8/11/25 10:30
Tetrachloro-m-xylene [2]	*	30-150	S-01	8/11/25 10:30

Pace Analytical Services, LLC - East Longmeadow, Ma

39 Spruce Street * East Longmeadow, MA 01028 * FAX 413/525-6405 * TEL. 413/525-2332

Project Location: Canada Drive, East Syracuse, NY Sample Description: Work Order: 25G2026

Date Received: 7/30/2025

Field Sample #: SB82-Z00-12 Sampled: 7/28/2025 12:27

Sample ID: 25G2026-09

Sample Matrix: Soil

Conventional Chemistry Parameters by EPA/APHA/SW-846 Methods (Total)

Analyte	Results	RL	Units	Dilution	Flag/Qual	Method	Date Prepared	Date/Time Analyzed	Analyst
% Solids	92.0		% Wt	1		SM 2540G	7/31/25	8/1/25 11:51	DMB

Pace Analytical Services, LLC - East Longmeadow, Ma

39 Spruce Street * East Longmeadow, MA 01028 * FAX 413/525-6405 * TEL. 413/525-2332

Project Location: Canada Drive, East Syracuse, NY Sample Description: Work Order: 25G2026

Date Received: 7/30/2025

Field Sample #: SB82-Z00-12-Q Sampled: 7/28/2025 12:26

Sample ID: 25G2026-10

Sample Matrix: Soil

Polychlorinated Biphenyls By GC/ECD

Analyte	Results	RL	DL	Units	Dilution	Flag/Qual	Method	Date Prepared	Date/Time Analyzed	Analyst
Aroclor-1016 [2]	ND	4.3	1.2	mg/Kg dry	200		SW-846 8082A	8/7/25	8/11/25 10:47	TG
Aroclor-1221 [2]	ND	4.3	2.0	mg/Kg dry	200		SW-846 8082A	8/7/25	8/11/25 10:47	TG
Aroclor-1232 [2]	ND	4.3	1.2	mg/Kg dry	200		SW-846 8082A	8/7/25	8/11/25 10:47	TG
Aroclor-1242 [2]	ND	4.3	1.3	mg/Kg dry	200		SW-846 8082A	8/7/25	8/11/25 10:47	TG
Aroclor-1248 [2]	15	4.3	1.6	mg/Kg dry	200		SW-846 8082A	8/7/25	8/11/25 10:47	TG
Aroclor-1254 [2]	ND	4.3	2.1	mg/Kg dry	200		SW-846 8082A	8/7/25	8/11/25 10:47	TG
Aroclor-1260 [2]	ND	4.3	1.2	mg/Kg dry	200		SW-846 8082A	8/7/25	8/11/25 10:47	TG
Aroclor-1262 [2]	ND	4.3	1.5	mg/Kg dry	200		SW-846 8082A	8/7/25	8/11/25 10:47	TG
Aroclor-1268 [2]	ND	4.3	1.4	mg/Kg dry	200		SW-846 8082A	8/7/25	8/11/25 10:47	TG

Surrogates	% Recovery	Recovery Limits	Flag/Qual	
Decachlorobiphenyl [1]	*	30-150	S-01	8/11/25 10:47
Decachlorobiphenyl [2]	*	30-150	S-01	8/11/25 10:47
Tetrachloro-m-xylene [1]	*	30-150	S-01	8/11/25 10:47
Tetrachloro-m-xylene [2]	*	30-150	S-01	8/11/25 10:47

Pace Analytical Services, LLC - East Longmeadow, Ma

39 Spruce Street * East Longmeadow, MA 01028 * FAX 413/525-6405 * TEL. 413/525-2332

Project Location: Canada Drive, East Syracuse, NY Sample Description: Work Order: 25G2026

Date Received: 7/30/2025

Field Sample #: SB82-Z00-12-Q Sampled: 7/28/2025 12:26

Sample ID: 25G2026-10

Sample Matrix: Soil

Conventional Chemistry Parameters by EPA/APHA/SW-846 Methods (Total)

Analyte	Results	RL	Units	Dilution	Flag/Qual	Method	Date Prepared	Date/Time Analyzed	Analyst
% Solids	92.3		% Wt	1		SM 2540G	7/31/25	8/1/25 11:51	DMB

Pace Analytical Services, LLC - East Longmeadow, Ma

39 Spruce Street * East Longmeadow, MA 01028 * FAX 413/525-6405 * TEL. 413/525-2332

Project Location: Canada Drive, East Syracuse, NY Sample Description: Work Order: 25G2026

Date Received: 7/30/2025

Field Sample #: SB82-Z12-24 Sampled: 7/28/2025 12:28

Sample ID: 25G2026-11

Sample Matrix: Soil

Polychlorinated Biphenyls By GC/ECD

Analyte	Results	RL	DL	Units	Dilution	Flag/Qual	Method	Date Prepared	Date/Time Analyzed	Analyst
Aroclor-1016 [2]	ND	0.86	0.23	mg/Kg dry	40		SW-846 8082A	8/7/25	8/11/25 11:05	TG
Aroclor-1221 [2]	ND	0.86	0.40	mg/Kg dry	40		SW-846 8082A	8/7/25	8/11/25 11:05	TG
Aroclor-1232 [2]	ND	0.86	0.25	mg/Kg dry	40		SW-846 8082A	8/7/25	8/11/25 11:05	TG
Aroclor-1242 [2]	ND	0.86	0.27	mg/Kg dry	40		SW-846 8082A	8/7/25	8/11/25 11:05	TG
Aroclor-1248 [2]	12	0.86	0.33	mg/Kg dry	40		SW-846 8082A	8/7/25	8/11/25 11:05	TG
Aroclor-1254 [2]	ND	0.86	0.42	mg/Kg dry	40		SW-846 8082A	8/7/25	8/11/25 11:05	TG
Aroclor-1260 [2]	ND	0.86	0.24	mg/Kg dry	40		SW-846 8082A	8/7/25	8/11/25 11:05	TG
Aroclor-1262 [2]	ND	0.86	0.30	mg/Kg dry	40		SW-846 8082A	8/7/25	8/11/25 11:05	TG
Aroclor-1268 [2]	ND	0.86	0.28	mg/Kg dry	40		SW-846 8082A	8/7/25	8/11/25 11:05	TG

Surrogates	% Recovery	Recovery Limits	Flag/Qual	
Decachlorobiphenyl [1]	*	30-150	S-01	8/11/25 11:05
Decachlorobiphenyl [2]	*	30-150	S-01	8/11/25 11:05
Tetrachloro-m-xylene [1]	*	30-150	S-01	8/11/25 11:05
Tetrachloro-m-xylene [2]	*	30-150	S-01	8/11/25 11:05

Pace Analytical Services, LLC - East Longmeadow, Ma

39 Spruce Street * East Longmeadow, MA 01028 * FAX 413/525-6405 * TEL. 413/525-2332

Project Location: Canada Drive, East Syracuse, NY Sample Description: Work Order: 25G2026

Date Received: 7/30/2025

Field Sample #: SB82-Z12-24 Sampled: 7/28/2025 12:28

Sample ID: 25G2026-11

Sample Matrix: Soil

Conventional Chemistry Parameters by EPA/APHA/SW-846 Methods (Total)

Analyte	Results	RL	Units	Dilution	Flag/Qual	Method	Date Prepared	Date/Time Analyzed	Analyst
% Solids	93.0		% Wt	1		SM 2540G	7/31/25	8/1/25 11:51	DMB

Pace Analytical Services, LLC - East Longmeadow, Ma

39 Spruce Street * East Longmeadow, MA 01028 * FAX 413/525-6405 * TEL. 413/525-2332

Project Location: Canada Drive, East Syracuse, NY Sample Description: Work Order: 25G2026

Date Received: 7/30/2025

Field Sample #: SB82-Z24-36 Sampled: 7/28/2025 12:29

Sample ID: 25G2026-12

Sample Matrix: Soil

Polychlorinated Biphenyls By GC/ECD

Analyte	Results	RL	DL	Units	Dilution	Flag/Qual	Method	Date Prepared	Date/Time Analyzed	Analyst
Aroclor-1016 [2]	ND	0.89	0.24	mg/Kg dry	40		SW-846 8082A	8/7/25	8/11/25 11:23	TG
Aroclor-1221 [2]	ND	0.89	0.41	mg/Kg dry	40		SW-846 8082A	8/7/25	8/11/25 11:23	TG
Aroclor-1232 [2]	ND	0.89	0.25	mg/Kg dry	40		SW-846 8082A	8/7/25	8/11/25 11:23	TG
Aroclor-1242 [2]	ND	0.89	0.28	mg/Kg dry	40		SW-846 8082A	8/7/25	8/11/25 11:23	TG
Aroclor-1248 [2]	3.7	0.89	0.34	mg/Kg dry	40		SW-846 8082A	8/7/25	8/11/25 11:23	TG
Aroclor-1254 [2]	ND	0.89	0.44	mg/Kg dry	40		SW-846 8082A	8/7/25	8/11/25 11:23	TG
Aroclor-1260 [2]	ND	0.89	0.25	mg/Kg dry	40		SW-846 8082A	8/7/25	8/11/25 11:23	TG
Aroclor-1262 [2]	ND	0.89	0.31	mg/Kg dry	40		SW-846 8082A	8/7/25	8/11/25 11:23	TG
Aroclor-1268 [2]	ND	0.89	0.29	mg/Kg dry	40		SW-846 8082A	8/7/25	8/11/25 11:23	TG

Surrogates	% Recovery	Recovery Limits	Flag/Qual	
Decachlorobiphenyl [1]	*	30-150	S-01	8/11/25 11:23
Decachlorobiphenyl [2]	*	30-150	S-01	8/11/25 11:23
Tetrachloro-m-xylene [1]	*	30-150	S-01	8/11/25 11:23
Tetrachloro-m-xylene [2]	*	30-150	S-01	8/11/25 11:23

Pace Analytical Services, LLC - East Longmeadow, Ma

39 Spruce Street * East Longmeadow, MA 01028 * FAX 413/525-6405 * TEL. 413/525-2332

Project Location: Canada Drive, East Syracuse, NY Sample Description: Work Order: 25G2026

Date Received: 7/30/2025

Field Sample #: SB82-Z24-36 Sampled: 7/28/2025 12:29

Sample ID: 25G2026-12

Sample Matrix: Soil

Conventional Chemistry Parameters by EPA/APHA/SW-846 Methods (Total)

Analyte	Results	RL	Units	Dilution	Flag/Qual	Method	Date Prepared	Date/Time Analyzed	Analyst
% Solids	89.3		% Wt	1		SM 2540G	7/31/25	8/1/25 11:51	DMB

Pace Analytical Services, LLC - East Longmeadow, Ma

39 Spruce Street * East Longmeadow, MA 01028 * FAX 413/525-6405 * TEL. 413/525-2332

Project Location: Canada Drive, East Syracuse, NY Sample Description: Work Order: 25G2026

Date Received: 7/30/2025

Field Sample #: SB82-Z36-48 Sampled: 7/28/2025 12:30

Sample ID: 25G2026-13

Sample Matrix: Soil

Polychlorinated Biphenyls By GC/ECD

Analyte	Results	RL	DL	Units	Dilution	Flag/Qual	Method	Date Prepared	Date/Time Analyzed	Analyst
Aroclor-1016 [1]	ND	0.45	0.12	mg/Kg dry	20		SW-846 8082A	8/7/25	8/11/25 11:40	TG
Aroclor-1221 [1]	ND	0.45	0.21	mg/Kg dry	20		SW-846 8082A	8/7/25	8/11/25 11:40	TG
Aroclor-1232 [1]	ND	0.45	0.12	mg/Kg dry	20		SW-846 8082A	8/7/25	8/11/25 11:40	TG
Aroclor-1242 [1]	ND	0.45	0.12	mg/Kg dry	20		SW-846 8082A	8/7/25	8/11/25 11:40	TG
Aroclor-1248 [1]	1.8	0.45	0.17	mg/Kg dry	20		SW-846 8082A	8/7/25	8/11/25 11:40	TG
Aroclor-1254 [1]	ND	0.45	0.19	mg/Kg dry	20		SW-846 8082A	8/7/25	8/11/25 11:40	TG
Aroclor-1260 [1]	ND	0.45	0.11	mg/Kg dry	20		SW-846 8082A	8/7/25	8/11/25 11:40	TG
Aroclor-1262 [1]	ND	0.45	0.15	mg/Kg dry	20		SW-846 8082A	8/7/25	8/11/25 11:40	TG
Aroclor-1268 [1]	ND	0.45	0.12	mg/Kg dry	20		SW-846 8082A	8/7/25	8/11/25 11:40	TG

Surrogates	% Recovery	Recovery Limits	Flag/Qual	
Decachlorobiphenyl [1]	116	30-150		8/11/25 11:40
Decachlorobiphenyl [2]	109	30-150		8/11/25 11:40
Tetrachloro-m-xylene [1]	89.1	30-150		8/11/25 11:40
Tetrachloro-m-xylene [2]	81.3	30-150		8/11/25 11:40

Pace Analytical Services, LLC - East Longmeadow, Ma

39 Spruce Street * East Longmeadow, MA 01028 * FAX 413/525-6405 * TEL. 413/525-2332

Project Location: Canada Drive, East Syracuse, NY Sample Description: Work Order: 25G2026

Date Received: 7/30/2025

Field Sample #: SB82-Z36-48 Sampled: 7/28/2025 12:30

Sample ID: 25G2026-13

Sample Matrix: Soil

Conventional Chemistry Parameters by EPA/APHA/SW-846 Methods (Total)

Analyte	Results	RL	Units	Dilution	Flag/Qual	Method	Date Prepared	Date/Time Analyzed	Analyst
% Solids	88.7		% Wt	1		SM 2540G	7/31/25	8/1/25 11:51	DMB

Pace Analytical Services, LLC - East Longmeadow, Ma

39 Spruce Street * East Longmeadow, MA 01028 * FAX 413/525-6405 * TEL. 413/525-2332

Project Location: Canada Drive, East Syracuse, NY Sample Description: Work Order: 25G2026

Date Received: 7/30/2025

Field Sample #: SB83-Z00-12 Sampled: 7/28/2025 12:10

Sample ID: 25G2026-14

Sample Matrix: Soil

Polychlorinated Biphenyls By GC/ECD

Analyte	Results	RL	DL	Units	Dilution	Flag/Qual	Method	Date Prepared	Date/Time Analyzed	Analyst
Aroclor-1016 [2]	ND	0.52	0.14	mg/Kg dry	20		SW-846 8082A	8/7/25	8/11/25 11:58	TG
Aroclor-1221 [2]	ND	0.52	0.24	mg/Kg dry	20		SW-846 8082A	8/7/25	8/11/25 11:58	TG
Aroclor-1232 [2]	ND	0.52	0.15	mg/Kg dry	20		SW-846 8082A	8/7/25	8/11/25 11:58	TG
Aroclor-1242 [2]	ND	0.52	0.16	mg/Kg dry	20		SW-846 8082A	8/7/25	8/11/25 11:58	TG
Aroclor-1248 [2]	4.6	0.52	0.20	mg/Kg dry	20		SW-846 8082A	8/7/25	8/11/25 11:58	TG
Aroclor-1254 [2]	ND	0.52	0.26	mg/Kg dry	20		SW-846 8082A	8/7/25	8/11/25 11:58	TG
Aroclor-1260 [2]	ND	0.52	0.15	mg/Kg dry	20		SW-846 8082A	8/7/25	8/11/25 11:58	TG
Aroclor-1262 [2]	ND	0.52	0.18	mg/Kg dry	20		SW-846 8082A	8/7/25	8/11/25 11:58	TG
Aroclor-1268 [2]	ND	0.52	0.17	mg/Kg dry	20		SW-846 8082A	8/7/25	8/11/25 11:58	TG

Surrogates	% Recovery	Recovery Limits	Flag/Qual	
Decachlorobiphenyl [1]	102	30-150		8/11/25 11:58
Decachlorobiphenyl [2]	94.9	30-150		8/11/25 11:58
Tetrachloro-m-xylene [1]	79.2	30-150		8/11/25 11:58
Tetrachloro-m-xylene [2]	69.2	30-150		8/11/25 11:58

Pace Analytical Services, LLC - East Longmeadow, Ma

39 Spruce Street * East Longmeadow, MA 01028 * FAX 413/525-6405 * TEL. 413/525-2332

Project Location: Canada Drive, East Syracuse, NY Sample Description: Work Order: 25G2026

Date Received: 7/30/2025

Field Sample #: SB83-Z00-12 Sampled: 7/28/2025 12:10

Sample ID: 25G2026-14

Sample Matrix: Soil

Conventional Chemistry Parameters by EPA/APHA/SW-846 Methods (Total)

Analyte	Results	RL	Units	Dilution	Flag/Qual	Method	Date Prepared	Date/Time Analyzed	Analyst
% Solids	76.3		% Wt	1		SM 2540G	7/31/25	8/1/25 11:51	DMB

Pace Analytical Services, LLC - East Longmeadow, Ma

39 Spruce Street * East Longmeadow, MA 01028 * FAX 413/525-6405 * TEL. 413/525-2332

Sample Extraction Data

Prep Method:% Solids **Analytical Method:SM 2540G**

Lab Number [Field ID]	Batch	Date
25G2026-01 [SB80-Z00-12]	B410519	07/31/25
25G2026-02 [SB80-Z12-24]	B410519	07/31/25
25G2026-03 [SB80-Z24-36]	B410519	07/31/25
25G2026-04 [SB80-Z36-48]	B410519	07/31/25
25G2026-05 [SB81-Z00-12]	B410519	07/31/25
25G2026-06 [SB81-Z12-24]	B410519	07/31/25
25G2026-07 [SB81-Z24-36]	B410519	07/31/25
25G2026-08 [SB81-Z36-48]	B410519	07/31/25
25G2026-09 [SB82-Z00-12]	B410519	07/31/25
25G2026-10 [SB82-Z00-12-Q]	B410519	07/31/25
25G2026-11 [SB82-Z12-24]	B410519	07/31/25
25G2026-12 [SB82-Z24-36]	B410519	07/31/25
25G2026-13 [SB82-Z36-48]	B410519	07/31/25
25G2026-14 [SB83-Z00-12]	B410519	07/31/25

Prep Method:SW-846 3546 **Analytical Method:SW-846 8082A**

Lab Number [Field ID]	Batch	Initial [g]	Final [mL]	Date
25G2026-01 [SB80-Z00-12]	B410860	10.1	10.0	08/07/25
25G2026-02 [SB80-Z12-24]	B410860	10.0	10.0	08/07/25
25G2026-03 [SB80-Z24-36]	B410860	10.0	10.0	08/07/25
25G2026-04 [SB80-Z36-48]	B410860	10.0	10.0	08/07/25
25G2026-05 [SB81-Z00-12]	B410860	10.1	10.0	08/07/25
25G2026-06 [SB81-Z12-24]	B410860	10.0	10.0	08/07/25
25G2026-07 [SB81-Z24-36]	B410860	10.0	10.0	08/07/25
25G2026-08 [SB81-Z36-48]	B410860	10.1	10.0	08/07/25
25G2026-09 [SB82-Z00-12]	B410860	10.0	10.0	08/07/25
25G2026-10 [SB82-Z00-12-Q]	B410860	10.0	10.0	08/07/25
25G2026-11 [SB82-Z12-24]	B410860	10.0	10.0	08/07/25
25G2026-12 [SB82-Z24-36]	B410860	10.0	10.0	08/07/25
25G2026-13 [SB82-Z36-48]	B410860	10.1	10.0	08/07/25
25G2026-14 [SB83-Z00-12]	B410860	10.0	10.0	08/07/25

Pace Analytical Services, LLC - East Longmeadow, Ma

39 Spruce Street * East Longmeadow, MA 01028 * FAX 413/525-6405 * TEL. 413/525-2332

QUALITY CONTROL

Polychlorinated Biphenyls By GC/ECD - Quality Control

Analyte	Result	Reporting Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes
Batch B410860 - SW-846 3546										
Blank (B410860-BLK1)				Prepared: 08/07/25 Analyzed: 08/10/25						
Aroclor-1016	ND	0.020	mg/Kg wet							
Aroclor-1016 [2C]	ND	0.020	mg/Kg wet							
Aroclor-1221	ND	0.020	mg/Kg wet							
Aroclor-1221 [2C]	ND	0.020	mg/Kg wet							
Aroclor-1232	ND	0.020	mg/Kg wet							
Aroclor-1232 [2C]	ND	0.020	mg/Kg wet							
Aroclor-1242	ND	0.020	mg/Kg wet							
Aroclor-1242 [2C]	ND	0.020	mg/Kg wet							
Aroclor-1248	ND	0.020	mg/Kg wet							
Aroclor-1248 [2C]	ND	0.020	mg/Kg wet							
Aroclor-1254	ND	0.020	mg/Kg wet							
Aroclor-1254 [2C]	ND	0.020	mg/Kg wet							
Aroclor-1260	ND	0.020	mg/Kg wet							
Aroclor-1260 [2C]	ND	0.020	mg/Kg wet							
Aroclor-1262	ND	0.020	mg/Kg wet							
Aroclor-1262 [2C]	ND	0.020	mg/Kg wet							
Aroclor-1268	ND	0.020	mg/Kg wet							
Aroclor-1268 [2C]	ND	0.020	mg/Kg wet							
Surrogate: Decachlorobiphenyl	*0.210*		mg/Kg wet	0.1992		106	30-150			
Surrogate: Decachlorobiphenyl [2C]	*0.220*		mg/Kg wet	0.1992		111	30-150			
Surrogate: Tetrachloro-m-xylene	*0.177*		mg/Kg wet	0.1992		88.6	30-150			
Surrogate: Tetrachloro-m-xylene [2C]	*0.179*		mg/Kg wet	0.1992		90.0	30-150			
LCS (B410860-BS1)				Prepared: 08/07/25 Analyzed: 08/10/25						
Aroclor-1016	0.16	0.020	mg/Kg wet	0.1996		80.4	40-140			
Aroclor-1016 [2C]	0.14	0.020	mg/Kg wet	0.1996		68.7	40-140			
Aroclor-1260	0.19	0.020	mg/Kg wet	0.1996		93.5	40-140			
Aroclor-1260 [2C]	0.18	0.020	mg/Kg wet	0.1996		88.1	40-140			
Surrogate: Decachlorobiphenyl	*0.216*		mg/Kg wet	0.1996		108	30-150			
Surrogate: Decachlorobiphenyl [2C]	*0.226*		mg/Kg wet	0.1996		113	30-150			
Surrogate: Tetrachloro-m-xylene	*0.179*		mg/Kg wet	0.1996		89.5	30-150			
Surrogate: Tetrachloro-m-xylene [2C]	*0.180*		mg/Kg wet	0.1996		90.3	30-150			
LCS Dup (B410860-BSD1)				Prepared: 08/07/25 Analyzed: 08/10/25						
Aroclor-1016	0.16	0.020	mg/Kg wet	0.1992		79.4	40-140	1.36	30	
Aroclor-1016 [2C]	0.14	0.020	mg/Kg wet	0.1992		69.0	40-140	0.505	30	
Aroclor-1260	0.19	0.020	mg/Kg wet	0.1992		93.1	40-140	0.354	30	
Aroclor-1260 [2C]	0.18	0.020	mg/Kg wet	0.1992		88.2	40-140	0.137	30	
Surrogate: Decachlorobiphenyl	*0.213*		mg/Kg wet	0.1992		107	30-150			
Surrogate: Decachlorobiphenyl [2C]	*0.223*		mg/Kg wet	0.1992		112	30-150			
Surrogate: Tetrachloro-m-xylene	*0.174*		mg/Kg wet	0.1992		87.4	30-150			
Surrogate: Tetrachloro-m-xylene [2C]	*0.176*		mg/Kg wet	0.1992		88.6	30-150			

Pace Analytical Services, LLC - East Longmeadow, Ma

39 Spruce Street * East Longmeadow, MA 01028 * FAX 413/525-6405 * TEL. 413/525-2332

IDENTIFICATION SUMMARY FOR SINGLE COMPONENT ANALYTES

SW-846 8082A

SB80-Z00-12

Lab Sample ID: 25G2026-01 Date(s) Analyzed: 08/11/2025 08/11/2025

Instrument ID (1): ECD1 Instrument ID (2): ECD1

GC Column (1): ID: (mm) GC Column (2): ID: (mm)

ANALYTE	COL	RT	RT WINDOW		CONCENTRATION	%RPD
			FROM	TO		
Aroclor-1248	1	0.000	0.000	0.000	37	
	2	0.000	0.000	0.000	49	27.9

Pace Analytical Services, LLC - East Longmeadow, Ma

39 Spruce Street * East Longmeadow, MA 01028 * FAX 413/525-6405 * TEL. 413/525-2332

IDENTIFICATION SUMMARY FOR SINGLE COMPONENT ANALYTES

SW-846 8082A

SB80-Z12-24

Lab Sample ID: 25G2026-02 Date(s) Analyzed: 08/11/2025 08/11/2025

Instrument ID (1): ECD1 Instrument ID (2): ECD1

GC Column (1): ID: (mm) GC Column (2): ID: (mm)

ANALYTE	COL	RT	RT WINDOW		CONCENTRATION	%RPD
			FROM	TO		
Aroclor-1248	1	0.000	0.000	0.000	58	
	2	0.000	0.000	0.000	71	20.2

Pace Analytical Services, LLC - East Longmeadow, Ma

39 Spruce Street * East Longmeadow, MA 01028 * FAX 413/525-6405 * TEL. 413/525-2332

IDENTIFICATION SUMMARY FOR SINGLE COMPONENT ANALYTES

SW-846 8082A

SB80-Z24-36

Lab Sample ID: 25G2026-03 Date(s) Analyzed: 08/11/2025 08/11/2025

Instrument ID (1): ECD1 Instrument ID (2): ECD1

GC Column (1): ID: (mm) GC Column (2): ID: (mm)

ANALYTE	COL	RT	RT WINDOW		CONCENTRATION	%RPD
			FROM	TO		
Aroclor-1248	1	0.000	0.000	0.000	73	
	2	0.000	0.000	0.000	90	20.9

Pace Analytical Services, LLC - East Longmeadow, Ma

39 Spruce Street * East Longmeadow, MA 01028 * FAX 413/525-6405 * TEL. 413/525-2332

IDENTIFICATION SUMMARY FOR SINGLE COMPONENT ANALYTES

SW-846 8082A

SB80-Z36-48

Lab Sample ID: 25G2026-04 Date(s) Analyzed: 08/11/2025 08/11/2025

Instrument ID (1): ECD1 Instrument ID (2): ECD1

GC Column (1): ID: (mm) GC Column (2): ID: (mm)

ANALYTE	COL	RT	RT WINDOW		CONCENTRATION	%RPD
			FROM	TO		
Aroclor-1248	1	0.000	0.000	0.000	42	
	2	0.000	0.000	0.000	52	18.9

Pace Analytical Services, LLC - East Longmeadow, Ma

39 Spruce Street * East Longmeadow, MA 01028 * FAX 413/525-6405 * TEL. 413/525-2332

IDENTIFICATION SUMMARY FOR SINGLE COMPONENT ANALYTES

SW-846 8082A

SB81-Z00-12

Lab Sample ID: 25G2026-05 Date(s) Analyzed: 08/11/2025 08/11/2025

Instrument ID (1): ECD1 Instrument ID (2): ECD1

GC Column (1): ID: (mm) GC Column (2): ID: (mm)

ANALYTE	COL	RT	RT WINDOW		CONCENTRATION	%RPD
			FROM	TO		
Aroclor-1248	1	0.000	0.000	0.000	23	
	2	0.000	0.000	0.000	28	19.6

Pace Analytical Services, LLC - East Longmeadow, Ma

39 Spruce Street * East Longmeadow, MA 01028 * FAX 413/525-6405 * TEL. 413/525-2332

IDENTIFICATION SUMMARY FOR SINGLE COMPONENT ANALYTES

SW-846 8082A

SB81-Z12-24

Lab Sample ID: 25G2026-06 Date(s) Analyzed: 08/11/2025 08/11/2025

Instrument ID (1): ECD1 Instrument ID (2): ECD1

GC Column (1): ID: (mm) GC Column (2): ID: (mm)

ANALYTE	COL	RT	RT WINDOW		CONCENTRATION	%RPD
			FROM	TO		
Aroclor-1248	1	0.000	0.000	0.000	26	
	2	0.000	0.000	0.000	32	20.7

Pace Analytical Services, LLC - East Longmeadow, Ma

39 Spruce Street * East Longmeadow, MA 01028 * FAX 413/525-6405 * TEL. 413/525-2332

IDENTIFICATION SUMMARY FOR SINGLE COMPONENT ANALYTES

SW-846 8082A

SB81-Z24-36

Lab Sample ID: 25G2026-07 Date(s) Analyzed: 08/11/2025 08/11/2025

Instrument ID (1): ECD1 Instrument ID (2): ECD1

GC Column (1): ID: (mm) GC Column (2): ID: (mm)

ANALYTE	COL	RT	RT WINDOW		CONCENTRATION	%RPD
			FROM	TO		
Aroclor-1248	1	0.000	0.000	0.000	56	
	2	0.000	0.000	0.000	68	19.4

Pace Analytical Services, LLC - East Longmeadow, Ma

39 Spruce Street * East Longmeadow, MA 01028 * FAX 413/525-6405 * TEL. 413/525-2332

IDENTIFICATION SUMMARY FOR SINGLE COMPONENT ANALYTES

SW-846 8082A

SB81-Z36-48

Lab Sample ID: 25G2026-08 Date(s) Analyzed: 08/11/2025 08/11/2025

Instrument ID (1): ECD1 Instrument ID (2): ECD1

GC Column (1): ID: (mm) GC Column (2): ID: (mm)

ANALYTE	COL	RT	RT WINDOW		CONCENTRATION	%RPD
			FROM	TO		
Aroclor-1248	1	0.000	0.000	0.000	130	
	2	0.000	0.000	0.000	150	14.3

Pace Analytical Services, LLC - East Longmeadow, Ma

39 Spruce Street * East Longmeadow, MA 01028 * FAX 413/525-6405 * TEL. 413/525-2332

IDENTIFICATION SUMMARY FOR SINGLE COMPONENT ANALYTES

SW-846 8082A

SB82-Z00-12

Lab Sample ID: 25G2026-09 Date(s) Analyzed: 08/11/2025 08/11/2025

Instrument ID (1): ECD1 Instrument ID (2): ECD1

GC Column (1): ID: (mm) GC Column (2): ID: (mm)

ANALYTE	COL	RT	RT WINDOW		CONCENTRATION	%RPD
			FROM	TO		
Aroclor-1248	1	0.000	0.000	0.000	15	
	2	0.000	0.000	0.000	15	0.0

Pace Analytical Services, LLC - East Longmeadow, Ma

39 Spruce Street * East Longmeadow, MA 01028 * FAX 413/525-6405 * TEL. 413/525-2332

IDENTIFICATION SUMMARY FOR SINGLE COMPONENT ANALYTES

SW-846 8082A

SB82-Z00-12-Q

Lab Sample ID: 25G2026-10 Date(s) Analyzed: 08/11/2025 08/11/2025

Instrument ID (1): ECD1 Instrument ID (2): ECD1

GC Column (1): ID: (mm) GC Column (2): ID: (mm)

ANALYTE	COL	RT	RT WINDOW		CONCENTRATION	%RPD
			FROM	TO		
Aroclor-1248	1	0.000	0.000	0.000	14	
	2	0.000	0.000	0.000	15	6.9

Pace Analytical Services, LLC - East Longmeadow, Ma

39 Spruce Street * East Longmeadow, MA 01028 * FAX 413/525-6405 * TEL. 413/525-2332

IDENTIFICATION SUMMARY FOR SINGLE COMPONENT ANALYTES

SW-846 8082A

SB82-Z12-24

Lab Sample ID: 25G2026-11 Date(s) Analyzed: 08/11/2025 08/11/2025

Instrument ID (1): ECD1 Instrument ID (2): ECD1

GC Column (1): ID: (mm) GC Column (2): ID: (mm)

ANALYTE	COL	RT	RT WINDOW		CONCENTRATION	%RPD
			FROM	TO		
Aroclor-1248	1	0.000	0.000	0.000	12	
	2	0.000	0.000	0.000	12	0.0

Pace Analytical Services, LLC - East Longmeadow, Ma

39 Spruce Street * East Longmeadow, MA 01028 * FAX 413/525-6405 * TEL. 413/525-2332

IDENTIFICATION SUMMARY FOR SINGLE COMPONENT ANALYTES

SW-846 8082A

SB82-Z24-36

Lab Sample ID: 25G2026-12 Date(s) Analyzed: 08/11/2025 08/11/2025

Instrument ID (1): ECD1 Instrument ID (2): ECD1

GC Column (1): ID: (mm) GC Column (2): ID: (mm)

ANALYTE	COL	RT	RT WINDOW		CONCENTRATION	%RPD
			FROM	TO		
Aroclor-1248	1	0.000	0.000	0.000	3.2	
	2	0.000	0.000	0.000	3.7	11.4

Pace Analytical Services, LLC - East Longmeadow, Ma

39 Spruce Street * East Longmeadow, MA 01028 * FAX 413/525-6405 * TEL. 413/525-2332

IDENTIFICATION SUMMARY FOR SINGLE COMPONENT ANALYTES

SW-846 8082A

SB82-Z36-48

Lab Sample ID: 25G2026-13 Date(s) Analyzed: 08/11/2025 08/11/2025

Instrument ID (1): ECD1 Instrument ID (2): ECD1

GC Column (1): ID: (mm) GC Column (2): ID: (mm)

ANALYTE	COL	RT	RT WINDOW		CONCENTRATION	%RPD
			FROM	TO		
Aroclor-1248	1	0.000	0.000	0.000	1.8	
	2	0.000	0.000	0.000	1.7	5.7

Pace Analytical Services, LLC - East Longmeadow, Ma

39 Spruce Street * East Longmeadow, MA 01028 * FAX 413/525-6405 * TEL. 413/525-2332

IDENTIFICATION SUMMARY FOR SINGLE COMPONENT ANALYTES

SW-846 8082A

SB83-Z00-12

Lab Sample ID: 25G2026-14 Date(s) Analyzed: 08/11/2025 08/11/2025

Instrument ID (1): ECD1 Instrument ID (2): ECD1

GC Column (1): ID: (mm) GC Column (2): ID: (mm)

ANALYTE	COL	RT	RT WINDOW		CONCENTRATION	%RPD
			FROM	TO		
Aroclor-1248	1	0.000	0.000	0.000	4.0	
	2	0.000	0.000	0.000	4.6	14.0

Pace Analytical Services, LLC - East Longmeadow, Ma

39 Spruce Street * East Longmeadow, MA 01028 * FAX 413/525-6405 * TEL. 413/525-2332

IDENTIFICATION SUMMARY FOR SINGLE COMPONENT ANALYTES

SW-846 8082A

LCS

Lab Sample ID: B410860-BS1 Date(s) Analyzed: 08/10/2025 08/10/2025

Instrument ID (1): ECD1 Instrument ID (2): ECD1

GC Column (1): ID: (mm) GC Column (2): ID: (mm)

ANALYTE	COL	RT	RT WINDOW		CONCENTRATION	%RPD
			FROM	TO		
Aroclor-1016	1	0.000	0.000	0.000	0.16	
	2	0.000	0.000	0.000	0.14	13.3
Aroclor-1260	1	0.000	0.000	0.000	0.19	
	2	0.000	0.000	0.000	0.18	5.4

Pace Analytical Services, LLC - East Longmeadow, Ma

39 Spruce Street * East Longmeadow, MA 01028 * FAX 413/525-6405 * TEL. 413/525-2332

IDENTIFICATION SUMMARY FOR SINGLE COMPONENT ANALYTES

SW-846 8082A

LCS Dup

Lab Sample ID: B410860-BSD1 Date(s) Analyzed: 08/10/2025 08/10/2025

Instrument ID (1): ECD1 Instrument ID (2): ECD1

GC Column (1): ID: (mm) GC Column (2): ID: (mm)

ANALYTE	COL	RT	RT WINDOW		CONCENTRATION	%RPD
			FROM	TO		
Aroclor-1016	1	0.000	0.000	0.000	0.16	
	2	0.000	0.000	0.000	0.14	13.3
Aroclor-1260	1	0.000	0.000	0.000	0.19	
	2	0.000	0.000	0.000	0.18	5.4

Pace Analytical Services, LLC - East Longmeadow, Ma

39 Spruce Street * East Longmeadow, MA 01028 * FAX 413/525-6405 * TEL. 413/525-2332

FLAG/QUALIFIER SUMMARY

*	QC result is outside of established limits.
†	Wide recovery limits established for difficult compound.
‡	Wide RPD limits established for difficult compound.
#	Data exceeded client recommended or regulatory level
ND	Not Detected
RL	Reporting Limit is at the level of quantitation (LOQ)
DL	Detection Limit is the lower limit of detection determined by the MDL study
MCL	Maximum Contaminant Level
	Percent recoveries and relative percent differences (RPDs) are determined by the software using values in the calculation which have not been rounded.
	No results have been blank subtracted unless specified in the case narrative section.
S-01	The surrogate recovery for this sample is not available due to sample dilution below the surrogate reporting limit required from high analyte concentration and/or matrix interferences.

Pace Analytical Services, LLC - East Longmeadow, Ma

39 Spruce Street * East Longmeadow, MA 01028 * FAX 413/525-6405 * TEL. 413/525-2332

CERTIFICATIONS

Certified Analyses included in this Report

Analyte	Certifications
SW-846 8082A in Soil	
Aroclor-1016	CT,NH,NY,NC,ME,VA,PA,NJ
Aroclor-1016 [2C]	CT,NH,NY,NC,ME,VA,PA,NJ
Aroclor-1221	CT,NH,NY,NC,ME,VA,PA,NJ
Aroclor-1221 [2C]	CT,NH,NY,NC,ME,VA,PA,NJ
Aroclor-1232	CT,NH,NY,NC,ME,VA,PA,NJ
Aroclor-1232 [2C]	CT,NH,NY,NC,ME,VA,PA,NJ
Aroclor-1242	CT,NH,NY,NC,ME,VA,PA,NJ
Aroclor-1242 [2C]	CT,NH,NY,NC,ME,VA,PA,NJ
Aroclor-1248	CT,NH,NY,NC,ME,VA,PA,NJ
Aroclor-1248 [2C]	CT,NH,NY,NC,ME,VA,PA,NJ
Aroclor-1254	CT,NH,NY,NC,ME,VA,PA,NJ
Aroclor-1254 [2C]	CT,NH,NY,NC,ME,VA,PA,NJ
Aroclor-1260	CT,NH,NY,NC,ME,VA,PA,NJ
Aroclor-1260 [2C]	CT,NH,NY,NC,ME,VA,PA,NJ
Aroclor-1262	NH,NY,NC,ME,VA,PA,NJ
Aroclor-1262 [2C]	NH,NY,NC,ME,VA,PA,NJ
Aroclor-1268	NH,NY,NC,ME,VA,PA,NJ
Aroclor-1268 [2C]	NH,NY,NC,ME,VA,PA,NJ
SW-846 8082A in Water	
Aroclor-1016	CT,NH,NY,NC,ME,VA,PA,NJ
Aroclor-1016 [2C]	CT,NH,NY,NC,ME,VA,PA,NJ
Aroclor-1221	CT,NH,NY,NC,ME,VA,PA,NJ
Aroclor-1221 [2C]	CT,NH,NY,NC,ME,VA,PA,NJ
Aroclor-1232	CT,NH,NY,NC,ME,VA,PA,NJ
Aroclor-1232 [2C]	CT,NH,NY,NC,ME,VA,PA,NJ
Aroclor-1242	CT,NH,NY,NC,ME,VA,PA,NJ
Aroclor-1242 [2C]	CT,NH,NY,NC,ME,VA,PA,NJ
Aroclor-1248	CT,NH,NY,NC,ME,VA,PA,NJ
Aroclor-1248 [2C]	CT,NH,NY,NC,ME,VA,PA,NJ
Aroclor-1254	CT,NH,NY,NC,ME,VA,PA,NJ
Aroclor-1254 [2C]	CT,NH,NY,NC,ME,VA,PA,NJ
Aroclor-1260	CT,NH,NY,NC,ME,VA,PA,NJ
Aroclor-1260 [2C]	CT,NH,NY,NC,ME,VA,PA,NJ
Aroclor-1262	NH,NY,NC,ME,VA,PA,NJ
Aroclor-1262 [2C]	NH,NY,NC,ME,VA,PA,NJ
Aroclor-1268	NH,NY,NC,ME,VA,PA,NJ
Aroclor-1268 [2C]	NH,NY,NC,ME,VA,PA,NJ

Pace Analytical Services, LLC - East Longmeadow, Ma

39 Spruce Street * East Longmeadow, MA 01028 * FAX 413/525-6405 * TEL. 413/525-2332

Pace Analytical Services, LLC - East Longmeadow, Ma, operates under the following certifications and accreditations:

Code	Description	Number	Expires
CT	Connecticut Department of Public Health	PH-0821	12/31/2026
NY	New York State Department of Health	10899 NELAP	04/1/2026
NH	New Hampshire Environmental Lab	2516 NELAP	02/5/2026
NC	North Carolina Div. of Water Quality	652	12/31/2025
NJ	New Jersey DEP	MA007 NELAP	06/30/2026
ME	State of Maine	MA00100	06/9/2027
VA	Commonwealth of Virginia	460217	12/14/2025
PA	Commonwealth of Pennsylvania DEP	68-05812	06/30/2026

East Long Meadow Facility 25G-02 2026

Pace® Location Requested (City/State):

CHAIN-OF-CUSTODY Analytical Request Document

Chain-of-Custody is a LEGAL DOCUMENT - Complete all relevant fields

LAB USE ONLY- Affix Workorder/Login Label Here

Scan QR Code for instructions

Company Name: WSP USA
Street Address: 46 La Riviere Dr. Suite 320 Buffalo, NY 14202
Customer Project #:
Project Name: Louck Rd Extension
Site Collection Info/Facility ID (as applicable): Site # C734145A
Time Zone Collected: [ ] AK [ ] PT [ ] MT [ ] CT [X] ET

Contact/Report To: Drew Bullinger
Phone #:
E-Mail: Drew.Bullinger@wsp.com
Cc E-Mail:
Invoice to: DEC Lab Callout # 153133
Invoice E-mail: Karen.Cahill@dec.ny.gov
Purchase Order # (if applicable): DEC Lab callout # 153133
Quote #:
County / State origin of sample(s): New York

Data Deliverables: [ ] Level II [ ] Level III [ ] Level IV [X] EQUIS [ ] Other

Regulatory Program (DW, RCRA, etc.) as applicable: NYS DEC
Reportable [ ] Yes [ ] No

Rush (Pre-approval required): [ ] Same Day [ ] 1 Day [ ] 2 Day [ ] 3 Day Other
Date Results Requested:

DW PWSID # or WW Permit # as applicable:
Field Filtered (if applicable): [ ] Yes [ ] No
Analysis:

Specify Container Size **: 4oz
Identify Container Preservative Type***:
Analysis Requested: PCBs

**Container Size: (1) 1L, (2) 500mL, (3) 250mL, (4) 125mL, (5) 100mL, (6) 40mL vial, (7) EnCore, (8) TerraCore, (9) 90mL, (10) Other

*** Preservative Types: (1) None, (2) HNO3, (3) H2SO4, (4) HCl, (5) NaOH, (6) Zn Acetate, (7) NaHSO4, (8) Sod. Thiosulfate, (9) Ascorbic Acid, (10) MeOH, (11) Other

Lab Use Only: Proj. Mgr: / AcctNum / Client ID: / Table #: / Profile / Template: / Prelog / Bottle Ord. ID:

Preservation non-conformance identified for sample.

* Matrix Codes (Insert in Matrix box below): Drinking Water (DW), Ground Water (GW), Wastewater (WW), Product (P), Soil/Solid (SS), Oil (OL), Wipe (WP), Tissue (TS), Bioassay (B), Vapor (V), Surface Water (SW), Sediment (SED), Sludge (SL), Caulk (CK), Leachate (LL), Biosolid (BS), Other (OT)

	Customer Sample ID	Matrix *	Comp / Grab	Composite Start Date	Composite Start Time	Collected or Composite End Date	Collected or Composite End Time	# Cont.	Residual Chlorine Result	Residual Chlorine Units	Sample Comment
	~~SB80-Z00-01~~ dup	S	G			7/28/25	12:52	1			
	~~SB80-Z01-02~~ dup										
1	SB80-Z00-12	S	G			7/28/25	12:52	1			
2	SB80-Z12-24	S	G			7/28/25	12:53	1			
3	SB80-Z24-36	S	G			7/28/25	12:54	1			
4	SB80-Z36-48	S	G			7/28/25	12:55	1			
	SB80-Z48-60	S	G			7/28/25	12:56	1			HOLD
5	SB81-Z00-12	S	G			7.28.25	12:36	1			
6	SB81-Z12-24	S	G			7.28.25	1237	1			
7	SB81-Z24-36	S	G			7.28.25	1238	1			

Additional Instructions from Pace®:

Collected By:
Printed Name: Drew Bullinger
Signature:

Customer Remarks / Special Conditions / Possible Hazards:

Coolers: Thermometer ID: Correction Factor (°C): Obs. Temp. (°C): Corrected Temp. (°C): [ ] On Ice

Relinquished by/Company: (Signature)	Date/Time	Received by/Company: (Signature)	Date/Time	Tracking Number:
Drew Bullinger	7/29/25 1400		7/29/25 1400	
	7/29/25 1700		7/30 12:12	Delivered by: [ ] In-Person [ ] Courier [ ] FedEx [ ] UPS [ ] Other
	7/30 2:40	3.8, 3.9 7/30/25	240	
				Page: 1 of 7

Submitting a sample via this chain of custody constitutes acknowledgment and acceptance of the Pace® Terms and Conditions found at https://www.pacelabs.com/resource-library/resource/pace-terms-and-conditions/

ENV-FRM-CORQ-0019_v02_110123 ©

Table of Contents

east Long meadow facility 25C-2026

Pace® Location Requested (City/State):

CHAIN-OF-CUSTODY Analytical Request Document

Chain-of-Custody is a LEGAL DOCUMENT - Complete all relevant fields

LAB USE ONLY- Affix Workorder/Login Label Here

Scan QR Code for instructions

Company Name: WSP USA
Street Address: 40 Lakeview Drive, Suite 320 Buffalo NY 14202
Customer Project #:
Project Name: Loucks Rd extension
Site Collection Info/Facility ID (as applicable): Site # C734145A
Time Zone Collected: [ ] AK [ ] PT [ ] MT [ ] CT [X] ET

Contact/Report To: Drew.Bullinger@wsp.com
Phone #:
E-Mail:
Cc E-Mail:
Invoice to: Karen Cahill
Invoice E-mail: Karen.Cahill@Dec.ny.gov
Purchase Order # (if applicable): Lab call out # 153133
Quote #:
County / State origin of sample(s): New York

Data Deliverables: [ ] Level II [ ] Level III [ ] Level IV [X] EQUIS [ ] Other
Regulatory Program (DW, RCRA, etc.) as applicable: NYS DEC
Reportable [ ] Yes [ ] No
Rush (Pre-approval required): [ ] Same Day [ ] 1 Day [ ] 2 Day [ ] 3 Day Other
Date Results Requested:
DW PWSID # or WW Permit # as applicable:
Field Filtered (if applicable): [ ] Yes [ ] No
Analysis:

Specify Container Size **: 4oz
Identify Container Preservative Type***:
Analysis Requested: PCBs

**Container Size: (1) 1L, (2) 500mL, (3) 250mL, (4) 125mL, (5) 100mL, (6) 40mL vial, (7) EnCore, (8) TerraCore, (9) 90mL, (10) Other
*** Preservative Types: (1) None, (2) HNO3, (3) H2SO4, (4) HCl, (5) NaOH, (6) Zn Acetate, (7) NaHSO4, (8) Sod. Thiosulfate, (9) Ascorbic Acid, (10) MeOH, (11) Other

Lab Use Only: Proj. Mgr: / AcctNum / Client ID: / Table #: / Profile / Template: / Prelog / Bottle Ord. ID:

* Matrix Codes (Insert in Matrix box below): Drinking Water (DW), Ground Water (GW), Wastewater (WW), Product (P), Soil/Solid (SS), Oil (OL), Wipe (WP), Tissue (TS), Bioassay (B), Vapor (V), Surface Water (SW), Sediment (SED), Sludge (SL), Caulk (CK), Leachate (LL), Biosolid (BS), Other (OT)

	Customer Sample ID	Matrix *	Comp / Grab	Composite Start Date	Composite Start Time	Collected or Composite End Date	Collected or Composite End Time	# Cont.	Residual Chlorine Result	Residual Chlorine Units	Sample Comment	Preservation non-conformance identified for sample.
8	SB81-Z36-48	S	G			7-28-25	1239	1				X
	SB81-Z48-60	S	G			7-28-25	1240	1			HOLD	X
9	SB82-Z00-12	S	G			7-28-25	12:27	1				X
10	SB82-Z00-12-Q	S	G			7-28-25	12:26	1				X
11	SB82-Z12-24	S	G			7-28-25	12:28	1				X
12	SB82-Z24-36	S	G			7-28-25	1229	1				X
13	SB82-Z36-48	S	G			7-28-25	1230	1				X
	SB82-Z48-60	S	G			7-28-25	1231	1			HOLD	X
	SB82-Z60-72	S	G			7-28-25	1232	1			HOLD	X
14	SB83-Z00-12	S	G			7-28-25	1210	1				X

Additional Instructions from Pace®:

Collected By: Printed Name / Signature: Drew Bullinger

Customer Remarks / Special Conditions / Possible Hazards:

Coolers: / Thermometer ID: / Correction Factor (°C): / Obs. Temp. (°C): / Corrected Temp. (°C): / [ ] On Ice

Relinquished by/Company: (Signature)	Date/Time:	Received by/Company: (Signature)	Date/Time:
Drew Bullinger	7/29/25 1400		7/29/25 1400
	7/29/25 1700		7/30 12:12
	7/30 2140	3.8, 3.9 7/30/25	7/30 2:40

Tracking Number:
Delivered by: [ ] In-Person [ ] Courier [ ] FedEx [ ] UPS [ ] Other
Page: 2 of 7

Submitting a sample via this chain of custody constitutes acknowledgment and acceptance of the Pace® Terms and Conditions found at https://www.pacelabs.com/resource-library/resource/pace-terms-and-conditions/

ENV-FRM-CORQ-0019_v02_110123 ©

Table of Contents

Pace	DC#_Title: ENV-FRM-ELON-0001 v08_Sample Receiving Checklist
	Effective Date: 06/11/2024

Log In Back-Sheet

Client WSP NYSDEC

Project Louck Rd Extension

MCP/RCP Required N/A

Deliverable Package Requirement N/A

Location NY

PWSID# (When Applicable) N/A

Arrival Method:

Courier ☒ Fed Ex ☐ Walk In ☐ Other ☐

Received By / Date / Time EGR 4/30/25 0240

Back-Sheet By / Date / Time STM 4/30/25 1705

Temperature Method Gun #6

WV samples: Yes (see note*) / (No) follow normal procedure)

Temp ☒ < 6° C Actual Temperature 3.8-3.9

Rush Samples: Yes / (No) Notify

Short Hold: Yes / (No) Notify

Notes regarding Samples/COC outside of SOP:

Login Sample Receipt Checklist – (Rejection Criteria Listing – Using Acceptance Policy) Any False statement will be brought to the attention of the Client – True or False

	True	False
Received on ice	☒	☐
Received in Cooler	☒	☐
Custody Seal: DATE TIME	☐	☒
COC Relinquished	☒	☐
COC/Samples Labels Agree	☒	☐
All Samples in Good Condition	☒	☐
Samples Received within Holding Time	☒	☐
Is there enough Volume	☒	☐
Proper Media/Container Used	☒	☐
Splitting Samples Required	☐	☒
MS/MSD	☐	☒
Trip Blanks	☐	☒
Lab to Filters	☐	☒
COC Legible	☒	☐

COC Included: (Check all included)

Client	☒	Analysis	☒	Sampler Name	☐
Project	☒	IDs	☐	Collection Date/Time	☒

All Samples Proper pH: (N/A) ☐ ☐

Additional Container Notes

Note: West Virginia requires all samples to have their temperature taken. Note any outliers.

Qualtrax ID: 120836

Quaitrax ID: 120836

Sample	Soils Jars (Circle Amb/Clear)				Ambers							Plastics											VOA Vials						Other / Fill in			
	16oz Amb/Clear	8oz Amb/Clear	4oz Amb/Clear	2oz Amb/Clear	1 Liter			250mL			100mL	1 Liter		500mL		250mL																
					Unpreserved	HCL	Sulfuric	Sulfuric	Phosphoric	HCl	Unpreserved	Unpreserved	Sulfuric	Unpreserved	Sulfuric	Unpreserved	Trizma	Sulfuric	Nitric	NaOH	Ammonium Acetate	NaOH/Zinc	Unpreserved	HCl	MeOH	D.I. Water	Bisulfate	Col/Bact				
1			~																													
2																																
3																																
4																																
5																																
6																																
7																																
8																																
9																																
10																																
11																																
12																																
13																																
14																																
15																																
16																																
17																																
18																																
19																																
20																																

Pace	DC#_Title: ENV-FRM-ELON-0001 v08_Sample Receiving Checklist
	Effective Date: 06/11/2024