Pace Analytical Services, LLC - East Longmeadow, Ma

39 Spruce Street * East Longmeadow, MA 01028 * FAX 413/525-6405 * TEL. 413/525-2332

August 14, 2025

Karen Cahill
NYDEC_WSP - Buffalo, NY
50 Lakefront Boulevard #111
Buffalo, NY 14202

Project Location: Canada Drive, East Syracuse, NY
Client Job Number:
Project Number: C734145A
Laboratory Work Order Number: 25G2029

Enclosed are results of analyses for samples as received by the laboratory on July 30, 2025. If you have any questions concerning this report, please feel free to contact me.

Sincerely,



Raymond J. McCarthy
Project Manager

Table of Contents

Sample Summary 4

Case Narrative 5

Sample Results 6

25G2029-01 6

25G2029-02 8

25G2029-03 10

25G2029-04 12

25G2029-05 14

25G2029-06 16

25G2029-07 18

25G2029-08 20

25G2029-09 22

25G2029-10 24

25G2029-11 26

25G2029-12 28

25G2029-13 30

25G2029-14 32

25G2029-15 34

25G2029-16 36

25G2029-17 38

Sample Preparation Information 40

QC Data 41

Polychlorinated Biphenyls By GC/ECD 41

B411044 41

Conventional Chemistry Parameters by EPA/APHA/SW-846 Methods (Total) 42

Table of Contents (continued)

B410539 42

Dual Column RPD Report 43

Flag/Qualifier Summary 60

Certifications 61

Chain of Custody/Sample Receipt 63

Pace Analytical Services, LLC - East Longmeadow, Ma

39 Spruce Street * East Longmeadow, MA 01028 * FAX 413/525-6405 * TEL. 413/525-2332

NYDEC_WSP - Buffalo, NY
50 Lakefront Boulevard #111
Buffalo, NY 14202
ATTN: Karen Cahill

REPORT DATE: 8/14/2025

PURCHASE ORDER NUMBER: 153133

PROJECT NUMBER: C734145A

ANALYTICAL SUMMARY

WORK ORDER NUMBER: 25G2029

The results of analyses performed on the following samples submitted to Pace Analytical Services, LLC - East Longmeadow, Ma, are found in this report.

PROJECT LOCATION: Canada Drive, East Syracuse, NY

FIELD SAMPLE #	LAB ID:	MATRIX	SAMPLE DESCRIPTION	TEST	SUB LAB
SB88-Z00-12-Q	25G2029-01	Soil		SM 2540G	
				SW-846 8082A	
SB88-Z12-24	25G2029-02	Soil		SM 2540G	
				SW-846 8082A	
SB88-Z24-36	25G2029-03	Soil		SM 2540G	
				SW-846 8082A	
SB88-Z36-48	25G2029-04	Soil		SM 2540G	
				SW-846 8082A	
SB89-Z00-12	25G2029-05	Soil		SM 2540G	
				SW-846 8082A	
SB89-Z12-24	25G2029-06	Soil		SM 2540G	
				SW-846 8082A	
SB89-Z24-36	25G2029-07	Soil		SM 2540G	
				SW-846 8082A	
SB89-Z36-48	25G2029-08	Soil		SM 2540G	
				SW-846 8082A	
SB91-Z00-12	25G2029-09	Soil		SM 2540G	
				SW-846 8082A	
SB91-Z12-24	25G2029-10	Soil		SM 2540G	
				SW-846 8082A	
SB91-Z24-36	25G2029-11	Soil		SM 2540G	
				SW-846 8082A	
SB91-Z36-48	25G2029-12	Soil		SM 2540G	
				SW-846 8082A	
SB91-Z48-60	25G2029-13	Soil		SM 2540G	
				SW-846 8082A	
SB91-Z48-60-Q	25G2029-14	Soil		SM 2540G	
				SW-846 8082A	
SB90-Z00-12	25G2029-15	Soil		SM 2540G	
				SW-846 8082A	
SB90-Z12-24	25G2029-16	Soil		SM 2540G	
				SW-846 8082A	
SB90-Z24-36	25G2029-17	Soil		SM 2540G	
				SW-846 8082A	

Pace Analytical Services, LLC - East Longmeadow, Ma

39 Spruce Street * East Longmeadow, MA 01028 * FAX 413/525-6405 * TEL. 413/525-2332

CASE NARRATIVE SUMMARY

All reported results are within defined laboratory quality control objectives unless listed below or otherwise qualified in this report.

For any Soil analysis, the Method Blank, LCS, and LCSD are reported on a 100% solids basis.

SM 2540G

Qualifications:

R-02

Duplicate RPD is outside of control limits. Outlier can be attributed to sample non-homogeneity encountered during sample prep.

Analyte & Samples(s) Qualified:

% Solids
B410539-DUP2

SW-846 8082A

Qualifications:

O-32

A dilution was performed as part of the standard analytical procedure.

Analyte & Samples(s) Qualified:

25G2029-13[SB91-Z48-60], 25G2029-14[SB91-Z48-60-Q]


S-01

The surrogate recovery for this sample is not available due to sample dilution below the surrogate reporting limit required from high analyte concentration and/or matrix interferences.

Analyte & Samples(s) Qualified:

Decachlorobiphenyl
25G2029-01[SB88-Z00-12-Q], 25G2029-05[SB89-Z00-12], 25G2029-06[SB89-Z12-24], 25G2029-08[SB89-Z36-48], 25G2029-15[SB90-Z00-12], 25G2029-16[SB90-Z12-24]
Decachlorobiphenyl [2C]
25G2029-01[SB88-Z00-12-Q], 25G2029-05[SB89-Z00-12], 25G2029-06[SB89-Z12-24], 25G2029-08[SB89-Z36-48], 25G2029-15[SB90-Z00-12], 25G2029-16[SB90-Z12-24]
Tetrachloro-m-xylene
25G2029-01[SB88-Z00-12-Q], 25G2029-05[SB89-Z00-12], 25G2029-06[SB89-Z12-24], 25G2029-08[SB89-Z36-48], 25G2029-15[SB90-Z00-12], 25G2029-16[SB90-Z12-24]
Tetrachloro-m-xylene [2C]
25G2029-01[SB88-Z00-12-Q], 25G2029-05[SB89-Z00-12], 25G2029-06[SB89-Z12-24], 25G2029-08[SB89-Z36-48], 25G2029-15[SB90-Z00-12], 25G2029-16[SB90-Z12-24]

The results of analyses reported only relate to samples submitted to Pace Analytical Services, LLC - East Longmeadow, Ma, for testing.
I certify that the analyses listed above, unless specifically listed as subcontracted, if any, were performed under my direction according to the approved methodologies listed in this document, and that based upon my inquiry of those individuals immediately responsible for obtaining the information, the material contained in this report is, to the best of my knowledge and belief, accurate and complete.



Meghan E. Kelley
Reporting Specialist

Pace Analytical Services, LLC - East Longmeadow, Ma

39 Spruce Street * East Longmeadow, MA 01028 * FAX 413/525-6405 * TEL. 413/525-2332

Project Location: Canada Drive, East Syracuse, NY Sample Description: Work Order: 25G2029

Date Received: 7/30/2025

Field Sample #: SB88-Z00-12-Q Sampled: 7/28/2025 11:40

Sample ID: 25G2029-01

Sample Matrix: Soil

Polychlorinated Biphenyls By GC/ECD

Analyte	Results	RL	DL	Units	Dilution	Flag/Qual	Method	Date Prepared	Date/Time Analyzed	Analyst
Aroclor-1016 [1]	ND	9.2	2.4	mg/Kg dry	400		SW-846 8082A	8/8/25	8/14/25 11:16	TG
Aroclor-1221 [1]	ND	9.2	4.2	mg/Kg dry	400		SW-846 8082A	8/8/25	8/14/25 11:16	TG
Aroclor-1232 [1]	ND	9.2	2.4	mg/Kg dry	400		SW-846 8082A	8/8/25	8/14/25 11:16	TG
Aroclor-1242 [1]	ND	9.2	2.5	mg/Kg dry	400		SW-846 8082A	8/8/25	8/14/25 11:16	TG
Aroclor-1248 [1]	31	9.2	3.4	mg/Kg dry	400		SW-846 8082A	8/8/25	8/14/25 11:16	TG
Aroclor-1254 [1]	ND	9.2	4.0	mg/Kg dry	400		SW-846 8082A	8/8/25	8/14/25 11:16	TG
Aroclor-1260 [1]	ND	9.2	2.3	mg/Kg dry	400		SW-846 8082A	8/8/25	8/14/25 11:16	TG
Aroclor-1262 [1]	ND	9.2	3.1	mg/Kg dry	400		SW-846 8082A	8/8/25	8/14/25 11:16	TG
Aroclor-1268 [1]	ND	9.2	2.4	mg/Kg dry	400		SW-846 8082A	8/8/25	8/14/25 11:16	TG

Surrogates	% Recovery	Recovery Limits	Flag/Qual	
Decachlorobiphenyl [1]	*	30-150	S-01	8/14/25 11:16
Decachlorobiphenyl [2]	*	30-150	S-01	8/14/25 11:16
Tetrachloro-m-xylene [1]	*	30-150	S-01	8/14/25 11:16
Tetrachloro-m-xylene [2]	*	30-150	S-01	8/14/25 11:16

Pace Analytical Services, LLC - East Longmeadow, Ma

39 Spruce Street * East Longmeadow, MA 01028 * FAX 413/525-6405 * TEL. 413/525-2332

Project Location: Canada Drive, East Syracuse, NY Sample Description: Work Order: 25G2029

Date Received: 7/30/2025

Field Sample #: SB88-Z00-12-Q Sampled: 7/28/2025 11:40

Sample ID: 25G2029-01

Sample Matrix: Soil

Conventional Chemistry Parameters by EPA/APHA/SW-846 Methods (Total)

Analyte	Results	RL	Units	Dilution	Flag/Qual	Method	Date Prepared	Date/Time Analyzed	Analyst
% Solids	86.8		% Wt	1		SM 2540G	8/1/25	8/1/25 13:00	MEF

Pace Analytical Services, LLC - East Longmeadow, Ma

39 Spruce Street * East Longmeadow, MA 01028 * FAX 413/525-6405 * TEL. 413/525-2332

Project Location: Canada Drive, East Syracuse, NY Sample Description: Work Order: 25G2029

Date Received: 7/30/2025

Field Sample #: SB88-Z12-24 Sampled: 7/28/2025 11:42

Sample ID: 25G2029-02

Sample Matrix: Soil

Polychlorinated Biphenyls By GC/ECD

Analyte	Results	RL	DL	Units	Dilution	Flag/Qual	Method	Date Prepared	Date/Time Analyzed	Analyst
Aroclor-1016 [1]	ND	0.088	0.023	mg/Kg dry	4		SW-846 8082A	8/8/25	8/13/25 16:37	TG
Aroclor-1221 [1]	ND	0.088	0.040	mg/Kg dry	4		SW-846 8082A	8/8/25	8/13/25 16:37	TG
Aroclor-1232 [1]	ND	0.088	0.023	mg/Kg dry	4		SW-846 8082A	8/8/25	8/13/25 16:37	TG
Aroclor-1242 [1]	ND	0.088	0.024	mg/Kg dry	4		SW-846 8082A	8/8/25	8/13/25 16:37	TG
Aroclor-1248 [1]	0.80	0.088	0.032	mg/Kg dry	4		SW-846 8082A	8/8/25	8/13/25 16:37	TG
Aroclor-1254 [1]	ND	0.088	0.038	mg/Kg dry	4		SW-846 8082A	8/8/25	8/13/25 16:37	TG
Aroclor-1260 [1]	ND	0.088	0.022	mg/Kg dry	4		SW-846 8082A	8/8/25	8/13/25 16:37	TG
Aroclor-1262 [1]	ND	0.088	0.030	mg/Kg dry	4		SW-846 8082A	8/8/25	8/13/25 16:37	TG
Aroclor-1268 [1]	ND	0.088	0.023	mg/Kg dry	4		SW-846 8082A	8/8/25	8/13/25 16:37	TG

Surrogates	% Recovery	Recovery Limits	Flag/Qual	
Decachlorobiphenyl [1]	95.8	30-150		8/13/25 16:37
Decachlorobiphenyl [2]	98.3	30-150		8/13/25 16:37
Tetrachloro-m-xylene [1]	91.1	30-150		8/13/25 16:37
Tetrachloro-m-xylene [2]	101	30-150		8/13/25 16:37

Pace Analytical Services, LLC - East Longmeadow, Ma

39 Spruce Street * East Longmeadow, MA 01028 * FAX 413/525-6405 * TEL. 413/525-2332

Project Location: Canada Drive, East Syracuse, NY Sample Description: Work Order: 25G2029

Date Received: 7/30/2025

Field Sample #: SB88-Z12-24 Sampled: 7/28/2025 11:42

Sample ID: 25G2029-02

Sample Matrix: Soil

Conventional Chemistry Parameters by EPA/APHA/SW-846 Methods (Total)

Analyte	Results	RL	Units	Dilution	Flag/Qual	Method	Date Prepared	Date/Time Analyzed	Analyst
% Solids	90.8		% Wt	1		SM 2540G	8/1/25	8/1/25 13:00	MEF

Pace Analytical Services, LLC - East Longmeadow, Ma

39 Spruce Street * East Longmeadow, MA 01028 * FAX 413/525-6405 * TEL. 413/525-2332

Project Location: Canada Drive, East Syracuse, NY Sample Description: Work Order: 25G2029

Date Received: 7/30/2025

Field Sample #: SB88-Z24-36 Sampled: 7/28/2025 11:43

Sample ID: 25G2029-03

Sample Matrix: Soil

Polychlorinated Biphenyls By GC/ECD

Analyte	Results	RL	DL	Units	Dilution	Flag/Qual	Method	Date Prepared	Date/Time Analyzed	Analyst
Aroclor-1016 [1]	ND	0.084	0.022	mg/Kg dry	4		SW-846 8082A	8/8/25	8/13/25 16:55	TG
Aroclor-1221 [1]	ND	0.084	0.038	mg/Kg dry	4		SW-846 8082A	8/8/25	8/13/25 16:55	TG
Aroclor-1232 [1]	ND	0.084	0.022	mg/Kg dry	4		SW-846 8082A	8/8/25	8/13/25 16:55	TG
Aroclor-1242 [1]	ND	0.084	0.023	mg/Kg dry	4		SW-846 8082A	8/8/25	8/13/25 16:55	TG
Aroclor-1248 [1]	0.32	0.084	0.031	mg/Kg dry	4		SW-846 8082A	8/8/25	8/13/25 16:55	TG
Aroclor-1254 [1]	ND	0.084	0.036	mg/Kg dry	4		SW-846 8082A	8/8/25	8/13/25 16:55	TG
Aroclor-1260 [1]	ND	0.084	0.021	mg/Kg dry	4		SW-846 8082A	8/8/25	8/13/25 16:55	TG
Aroclor-1262 [1]	ND	0.084	0.028	mg/Kg dry	4		SW-846 8082A	8/8/25	8/13/25 16:55	TG
Aroclor-1268 [1]	ND	0.084	0.022	mg/Kg dry	4		SW-846 8082A	8/8/25	8/13/25 16:55	TG

Surrogates	% Recovery	Recovery Limits	Flag/Qual	
Decachlorobiphenyl [1]	91.7	30-150		8/13/25 16:55
Decachlorobiphenyl [2]	94.1	30-150		8/13/25 16:55
Tetrachloro-m-xylene [1]	84.0	30-150		8/13/25 16:55
Tetrachloro-m-xylene [2]	92.2	30-150		8/13/25 16:55

Pace Analytical Services, LLC - East Longmeadow, Ma

39 Spruce Street * East Longmeadow, MA 01028 * FAX 413/525-6405 * TEL. 413/525-2332

Project Location: Canada Drive, East Syracuse, NY Sample Description: Work Order: 25G2029

Date Received: 7/30/2025

Field Sample #: SB88-Z24-36 Sampled: 7/28/2025 11:43

Sample ID: 25G2029-03

Sample Matrix: Soil

Conventional Chemistry Parameters by EPA/APHA/SW-846 Methods (Total)

Analyte	Results	RL	Units	Dilution	Flag/Qual	Method	Date Prepared	Date/Time Analyzed	Analyst
% Solids	95.6		% Wt	1		SM 2540G	8/1/25	8/1/25 13:00	MEF

Pace Analytical Services, LLC - East Longmeadow, Ma

39 Spruce Street * East Longmeadow, MA 01028 * FAX 413/525-6405 * TEL. 413/525-2332

Project Location: Canada Drive, East Syracuse, NY Sample Description: Work Order: 25G2029

Date Received: 7/30/2025

Field Sample #: SB88-Z36-48 Sampled: 7/28/2025 11:44

Sample ID: 25G2029-04

Sample Matrix: Soil

Polychlorinated Biphenyls By GC/ECD

Analyte	Results	RL	DL	Units	Dilution	Flag/Qual	Method	Date Prepared	Date/Time Analyzed	Analyst
Aroclor-1016 [1]	ND	0.083	0.022	mg/Kg dry	4		SW-846 8082A	8/8/25	8/13/25 17:12	TG
Aroclor-1221 [1]	ND	0.083	0.038	mg/Kg dry	4		SW-846 8082A	8/8/25	8/13/25 17:12	TG
Aroclor-1232 [1]	ND	0.083	0.022	mg/Kg dry	4		SW-846 8082A	8/8/25	8/13/25 17:12	TG
Aroclor-1242 [1]	ND	0.083	0.023	mg/Kg dry	4		SW-846 8082A	8/8/25	8/13/25 17:12	TG
Aroclor-1248 [1]	0.14	0.083	0.031	mg/Kg dry	4		SW-846 8082A	8/8/25	8/13/25 17:12	TG
Aroclor-1254 [1]	ND	0.083	0.036	mg/Kg dry	4		SW-846 8082A	8/8/25	8/13/25 17:12	TG
Aroclor-1260 [1]	ND	0.083	0.021	mg/Kg dry	4		SW-846 8082A	8/8/25	8/13/25 17:12	TG
Aroclor-1262 [1]	ND	0.083	0.028	mg/Kg dry	4		SW-846 8082A	8/8/25	8/13/25 17:12	TG
Aroclor-1268 [1]	ND	0.083	0.022	mg/Kg dry	4		SW-846 8082A	8/8/25	8/13/25 17:12	TG

Surrogates	% Recovery	Recovery Limits	Flag/Qual	
Decachlorobiphenyl [1]	94.3	30-150		8/13/25 17:12
Decachlorobiphenyl [2]	96.5	30-150		8/13/25 17:12
Tetrachloro-m-xylene [1]	93.8	30-150		8/13/25 17:12
Tetrachloro-m-xylene [2]	102	30-150		8/13/25 17:12

Pace Analytical Services, LLC - East Longmeadow, Ma

39 Spruce Street * East Longmeadow, MA 01028 * FAX 413/525-6405 * TEL. 413/525-2332

Project Location: Canada Drive, East Syracuse, NY Sample Description: Work Order: 25G2029

Date Received: 7/30/2025

Field Sample #: SB88-Z36-48 Sampled: 7/28/2025 11:44

Sample ID: 25G2029-04

Sample Matrix: Soil

Conventional Chemistry Parameters by EPA/APHA/SW-846 Methods (Total)

Analyte	Results	RL	Units	Dilution	Flag/Qual	Method	Date Prepared	Date/Time Analyzed	Analyst
% Solids	95.9		% Wt	1		SM 2540G	8/1/25	8/1/25 13:00	MEF

Pace Analytical Services, LLC - East Longmeadow, Ma

39 Spruce Street * East Longmeadow, MA 01028 * FAX 413/525-6405 * TEL. 413/525-2332

Project Location: Canada Drive, East Syracuse, NY Sample Description: Work Order: 25G2029

Date Received: 7/30/2025

Field Sample #: SB89-Z00-12 Sampled: 7/28/2025 11:34

Sample ID: 25G2029-05

Sample Matrix: Soil

Polychlorinated Biphenyls By GC/ECD

Analyte	Results	RL	DL	Units	Dilution	Flag/Qual	Method	Date Prepared	Date/Time Analyzed	Analyst
Aroclor-1016 [1]	ND	8.7	2.3	mg/Kg dry	400		SW-846 8082A	8/8/25	8/14/25 11:28	TG
Aroclor-1221 [1]	ND	8.7	4.0	mg/Kg dry	400		SW-846 8082A	8/8/25	8/14/25 11:28	TG
Aroclor-1232 [1]	ND	8.7	2.3	mg/Kg dry	400		SW-846 8082A	8/8/25	8/14/25 11:28	TG
Aroclor-1242 [1]	ND	8.7	2.4	mg/Kg dry	400		SW-846 8082A	8/8/25	8/14/25 11:28	TG
Aroclor-1248 [1]	44	8.7	3.2	mg/Kg dry	400		SW-846 8082A	8/8/25	8/14/25 11:28	TG
Aroclor-1254 [1]	ND	8.7	3.8	mg/Kg dry	400		SW-846 8082A	8/8/25	8/14/25 11:28	TG
Aroclor-1260 [1]	ND	8.7	2.2	mg/Kg dry	400		SW-846 8082A	8/8/25	8/14/25 11:28	TG
Aroclor-1262 [1]	ND	8.7	3.0	mg/Kg dry	400		SW-846 8082A	8/8/25	8/14/25 11:28	TG
Aroclor-1268 [1]	ND	8.7	2.3	mg/Kg dry	400		SW-846 8082A	8/8/25	8/14/25 11:28	TG

Surrogates	% Recovery	Recovery Limits	Flag/Qual	
Decachlorobiphenyl [1]	*	30-150	S-01	8/14/25 11:28
Decachlorobiphenyl [2]	*	30-150	S-01	8/14/25 11:28
Tetrachloro-m-xylene [1]	*	30-150	S-01	8/14/25 11:28
Tetrachloro-m-xylene [2]	*	30-150	S-01	8/14/25 11:28

Pace Analytical Services, LLC - East Longmeadow, Ma

39 Spruce Street * East Longmeadow, MA 01028 * FAX 413/525-6405 * TEL. 413/525-2332

Project Location: Canada Drive, East Syracuse, NY Sample Description: Work Order: 25G2029

Date Received: 7/30/2025

Field Sample #: SB89-Z00-12 Sampled: 7/28/2025 11:34

Sample ID: 25G2029-05

Sample Matrix: Soil

Conventional Chemistry Parameters by EPA/APHA/SW-846 Methods (Total)

Analyte	Results	RL	Units	Dilution	Flag/Qual	Method	Date Prepared	Date/Time Analyzed	Analyst
% Solids	90.9		% Wt	1		SM 2540G	8/1/25	8/1/25 13:00	MEF

Pace Analytical Services, LLC - East Longmeadow, Ma

39 Spruce Street * East Longmeadow, MA 01028 * FAX 413/525-6405 * TEL. 413/525-2332

Project Location: Canada Drive, East Syracuse, NY Sample Description: Work Order: 25G2029

Date Received: 7/30/2025

Field Sample #: SB89-Z12-24 Sampled: 7/28/2025 11:35

Sample ID: 25G2029-06

Sample Matrix: Soil

Polychlorinated Biphenyls By GC/ECD

Analyte	Results	RL	DL	Units	Dilution	Flag/Qual	Method	Date Prepared	Date/Time Analyzed	Analyst
Aroclor-1016 [1]	ND	2.3	0.62	mg/Kg dry	80		SW-846 8082A	8/8/25	8/14/25 11:41	TG
Aroclor-1221 [1]	ND	2.3	1.1	mg/Kg dry	80		SW-846 8082A	8/8/25	8/14/25 11:41	TG
Aroclor-1232 [1]	ND	2.3	0.60	mg/Kg dry	80		SW-846 8082A	8/8/25	8/14/25 11:41	TG
Aroclor-1242 [1]	ND	2.3	0.64	mg/Kg dry	80		SW-846 8082A	8/8/25	8/14/25 11:41	TG
Aroclor-1248 [1]	22	2.3	0.86	mg/Kg dry	80		SW-846 8082A	8/8/25	8/14/25 11:41	TG
Aroclor-1254 [1]	ND	2.3	1.0	mg/Kg dry	80		SW-846 8082A	8/8/25	8/14/25 11:41	TG
Aroclor-1260 [1]	ND	2.3	0.59	mg/Kg dry	80		SW-846 8082A	8/8/25	8/14/25 11:41	TG
Aroclor-1262 [1]	ND	2.3	0.79	mg/Kg dry	80		SW-846 8082A	8/8/25	8/14/25 11:41	TG
Aroclor-1268 [1]	ND	2.3	0.60	mg/Kg dry	80		SW-846 8082A	8/8/25	8/14/25 11:41	TG

Surrogates	% Recovery	Recovery Limits	Flag/Qual	
Decachlorobiphenyl [1]	*	30-150	S-01	8/14/25 11:41
Decachlorobiphenyl [2]	*	30-150	S-01	8/14/25 11:41
Tetrachloro-m-xylene [1]	*	30-150	S-01	8/14/25 11:41
Tetrachloro-m-xylene [2]	*	30-150	S-01	8/14/25 11:41

Pace Analytical Services, LLC - East Longmeadow, Ma

39 Spruce Street * East Longmeadow, MA 01028 * FAX 413/525-6405 * TEL. 413/525-2332

Project Location: Canada Drive, East Syracuse, NY Sample Description: Work Order: 25G2029

Date Received: 7/30/2025

Field Sample #: SB89-Z12-24 Sampled: 7/28/2025 11:35

Sample ID: 25G2029-06

Sample Matrix: Soil

Conventional Chemistry Parameters by EPA/APHA/SW-846 Methods (Total)

Analyte	Results	RL	Units	Dilution	Flag/Qual	Method	Date Prepared	Date/Time Analyzed	Analyst
% Solids	68.3		% Wt	1		SM 2540G	8/1/25	8/1/25 13:00	MEF

Pace Analytical Services, LLC - East Longmeadow, Ma

39 Spruce Street * East Longmeadow, MA 01028 * FAX 413/525-6405 * TEL. 413/525-2332

Project Location: Canada Drive, East Syracuse, NY Sample Description: Work Order: 25G2029

Date Received: 7/30/2025

Field Sample #: SB89-Z24-36 Sampled: 7/28/2025 11:36

Sample ID: 25G2029-07

Sample Matrix: Soil

Polychlorinated Biphenyls By GC/ECD

Analyte	Results	RL	DL	Units	Dilution	Flag/Qual	Method	Date Prepared	Date/Time Analyzed	Analyst
Aroclor-1016 [1]	ND	0.086	0.023	mg/Kg dry	4		SW-846 8082A	8/8/25	8/13/25 18:05	TG
Aroclor-1221 [1]	ND	0.086	0.040	mg/Kg dry	4		SW-846 8082A	8/8/25	8/13/25 18:05	TG
Aroclor-1232 [1]	ND	0.086	0.022	mg/Kg dry	4		SW-846 8082A	8/8/25	8/13/25 18:05	TG
Aroclor-1242 [1]	ND	0.086	0.024	mg/Kg dry	4		SW-846 8082A	8/8/25	8/13/25 18:05	TG
Aroclor-1248 [1]	0.62	0.086	0.032	mg/Kg dry	4		SW-846 8082A	8/8/25	8/13/25 18:05	TG
Aroclor-1254 [1]	ND	0.086	0.037	mg/Kg dry	4		SW-846 8082A	8/8/25	8/13/25 18:05	TG
Aroclor-1260 [1]	ND	0.086	0.022	mg/Kg dry	4		SW-846 8082A	8/8/25	8/13/25 18:05	TG
Aroclor-1262 [1]	ND	0.086	0.029	mg/Kg dry	4		SW-846 8082A	8/8/25	8/13/25 18:05	TG
Aroclor-1268 [1]	ND	0.086	0.022	mg/Kg dry	4		SW-846 8082A	8/8/25	8/13/25 18:05	TG

Surrogates	% Recovery	Recovery Limits	Flag/Qual	
Decachlorobiphenyl [1]	97.7	30-150		8/13/25 18:05
Decachlorobiphenyl [2]	99.1	30-150		8/13/25 18:05
Tetrachloro-m-xylene [1]	100	30-150		8/13/25 18:05
Tetrachloro-m-xylene [2]	108	30-150		8/13/25 18:05

Pace Analytical Services, LLC - East Longmeadow, Ma

39 Spruce Street * East Longmeadow, MA 01028 * FAX 413/525-6405 * TEL. 413/525-2332

Project Location: Canada Drive, East Syracuse, NY Sample Description: Work Order: 25G2029

Date Received: 7/30/2025

Field Sample #: SB89-Z24-36 Sampled: 7/28/2025 11:36

Sample ID: 25G2029-07

Sample Matrix: Soil

Conventional Chemistry Parameters by EPA/APHA/SW-846 Methods (Total)

Analyte	Results	RL	Units	Dilution	Flag/Qual	Method	Date Prepared	Date/Time Analyzed	Analyst
% Solids	92.8		% Wt	1		SM 2540G	8/1/25	8/1/25 13:00	MEF

Pace Analytical Services, LLC - East Longmeadow, Ma

39 Spruce Street * East Longmeadow, MA 01028 * FAX 413/525-6405 * TEL. 413/525-2332

Project Location: Canada Drive, East Syracuse, NY Sample Description: Work Order: 25G2029

Date Received: 7/30/2025

Field Sample #: SB89-Z36-48 Sampled: 7/28/2025 11:37

Sample ID: 25G2029-08

Sample Matrix: Soil

Polychlorinated Biphenyls By GC/ECD

Analyte	Results	RL	DL	Units	Dilution	Flag/Qual	Method	Date Prepared	Date/Time Analyzed	Analyst
Aroclor-1016 [1]	ND	0.85	0.23	mg/Kg dry	40		SW-846 8082A	8/8/25	8/14/25 11:53	TG
Aroclor-1221 [1]	ND	0.85	0.39	mg/Kg dry	40		SW-846 8082A	8/8/25	8/14/25 11:53	TG
Aroclor-1232 [1]	ND	0.85	0.22	mg/Kg dry	40		SW-846 8082A	8/8/25	8/14/25 11:53	TG
Aroclor-1242 [1]	ND	0.85	0.23	mg/Kg dry	40		SW-846 8082A	8/8/25	8/14/25 11:53	TG
Aroclor-1248 [1]	2.8	0.85	0.32	mg/Kg dry	40		SW-846 8082A	8/8/25	8/14/25 11:53	TG
Aroclor-1254 [1]	ND	0.85	0.37	mg/Kg dry	40		SW-846 8082A	8/8/25	8/14/25 11:53	TG
Aroclor-1260 [1]	ND	0.85	0.22	mg/Kg dry	40		SW-846 8082A	8/8/25	8/14/25 11:53	TG
Aroclor-1262 [1]	ND	0.85	0.29	mg/Kg dry	40		SW-846 8082A	8/8/25	8/14/25 11:53	TG
Aroclor-1268 [1]	ND	0.85	0.22	mg/Kg dry	40		SW-846 8082A	8/8/25	8/14/25 11:53	TG

Surrogates	% Recovery	Recovery Limits	Flag/Qual	
Decachlorobiphenyl [1]	*	30-150	S-01	8/14/25 11:53
Decachlorobiphenyl [2]	*	30-150	S-01	8/14/25 11:53
Tetrachloro-m-xylene [1]	*	30-150	S-01	8/14/25 11:53
Tetrachloro-m-xylene [2]	*	30-150	S-01	8/14/25 11:53

Pace Analytical Services, LLC - East Longmeadow, Ma

39 Spruce Street * East Longmeadow, MA 01028 * FAX 413/525-6405 * TEL. 413/525-2332

Project Location: Canada Drive, East Syracuse, NY Sample Description: Work Order: 25G2029

Date Received: 7/30/2025

Field Sample #: SB89-Z36-48 Sampled: 7/28/2025 11:37

Sample ID: 25G2029-08

Sample Matrix: Soil

Conventional Chemistry Parameters by EPA/APHA/SW-846 Methods (Total)

Analyte	Results	RL	Units	Dilution	Flag/Qual	Method	Date Prepared	Date/Time Analyzed	Analyst
% Solids	93.7		% Wt	1		SM 2540G	8/1/25	8/1/25 13:00	MEF

Pace Analytical Services, LLC - East Longmeadow, Ma

39 Spruce Street * East Longmeadow, MA 01028 * FAX 413/525-6405 * TEL. 413/525-2332

Project Location: Canada Drive, East Syracuse, NY Sample Description: Work Order: 25G2029

Date Received: 7/30/2025

Field Sample #: SB91-Z00-12 Sampled: 7/28/2025 11:03

Sample ID: 25G2029-09

Sample Matrix: Soil

Polychlorinated Biphenyls By GC/ECD

Analyte	Results	RL	DL	Units	Dilution	Flag/Qual	Method	Date Prepared	Date/Time Analyzed	Analyst
Aroclor-1016 [1]	ND	0.088	0.023	mg/Kg dry	4		SW-846 8082A	8/8/25	8/14/25 9:03	TG
Aroclor-1221 [1]	ND	0.088	0.041	mg/Kg dry	4		SW-846 8082A	8/8/25	8/14/25 9:03	TG
Aroclor-1232 [1]	ND	0.088	0.023	mg/Kg dry	4		SW-846 8082A	8/8/25	8/14/25 9:03	TG
Aroclor-1242 [1]	ND	0.088	0.024	mg/Kg dry	4		SW-846 8082A	8/8/25	8/14/25 9:03	TG
Aroclor-1248 [1]	1.3	0.088	0.033	mg/Kg dry	4		SW-846 8082A	8/8/25	8/14/25 9:03	TG
Aroclor-1254 [1]	ND	0.088	0.038	mg/Kg dry	4		SW-846 8082A	8/8/25	8/14/25 9:03	TG
Aroclor-1260 [1]	ND	0.088	0.023	mg/Kg dry	4		SW-846 8082A	8/8/25	8/14/25 9:03	TG
Aroclor-1262 [1]	ND	0.088	0.030	mg/Kg dry	4		SW-846 8082A	8/8/25	8/14/25 9:03	TG
Aroclor-1268 [1]	ND	0.088	0.023	mg/Kg dry	4		SW-846 8082A	8/8/25	8/14/25 9:03	TG

Surrogates	% Recovery	Recovery Limits	Flag/Qual	
Decachlorobiphenyl [1]	102	30-150		8/14/25 9:03
Decachlorobiphenyl [2]	101	30-150		8/14/25 9:03
Tetrachloro-m-xylene [1]	97.4	30-150		8/14/25 9:03
Tetrachloro-m-xylene [2]	108	30-150		8/14/25 9:03

Pace Analytical Services, LLC - East Longmeadow, Ma

39 Spruce Street * East Longmeadow, MA 01028 * FAX 413/525-6405 * TEL. 413/525-2332

Project Location: Canada Drive, East Syracuse, NY Sample Description: Work Order: 25G2029

Date Received: 7/30/2025

Field Sample #: SB91-Z00-12 Sampled: 7/28/2025 11:03

Sample ID: 25G2029-09

Sample Matrix: Soil

Conventional Chemistry Parameters by EPA/APHA/SW-846 Methods (Total)

Analyte	Results	RL	Units	Dilution	Flag/Qual	Method	Date Prepared	Date/Time Analyzed	Analyst
% Solids	89.7		% Wt	1		SM 2540G	8/1/25	8/1/25 13:00	MEF

Pace Analytical Services, LLC - East Longmeadow, Ma

39 Spruce Street * East Longmeadow, MA 01028 * FAX 413/525-6405 * TEL. 413/525-2332

Project Location: Canada Drive, East Syracuse, NY Sample Description: Work Order: 25G2029

Date Received: 7/30/2025

Field Sample #: SB91-Z12-24 Sampled: 7/28/2025 11:04

Sample ID: 25G2029-10

Sample Matrix: Soil

Polychlorinated Biphenyls By GC/ECD

Analyte	Results	RL	DL	Units	Dilution	Flag/Qual	Method	Date Prepared	Date/Time Analyzed	Analyst
Aroclor-1016 [1]	ND	0.084	0.022	mg/Kg dry	4		SW-846 8082A	8/8/25	8/14/25 9:15	TG
Aroclor-1221 [1]	ND	0.084	0.039	mg/Kg dry	4		SW-846 8082A	8/8/25	8/14/25 9:15	TG
Aroclor-1232 [1]	ND	0.084	0.022	mg/Kg dry	4		SW-846 8082A	8/8/25	8/14/25 9:15	TG
Aroclor-1242 [1]	ND	0.084	0.023	mg/Kg dry	4		SW-846 8082A	8/8/25	8/14/25 9:15	TG
Aroclor-1248 [1]	0.28	0.084	0.031	mg/Kg dry	4		SW-846 8082A	8/8/25	8/14/25 9:15	TG
Aroclor-1254 [1]	ND	0.084	0.037	mg/Kg dry	4		SW-846 8082A	8/8/25	8/14/25 9:15	TG
Aroclor-1260 [1]	ND	0.084	0.021	mg/Kg dry	4		SW-846 8082A	8/8/25	8/14/25 9:15	TG
Aroclor-1262 [1]	ND	0.084	0.029	mg/Kg dry	4		SW-846 8082A	8/8/25	8/14/25 9:15	TG
Aroclor-1268 [1]	ND	0.084	0.022	mg/Kg dry	4		SW-846 8082A	8/8/25	8/14/25 9:15	TG

Surrogates	% Recovery	Recovery Limits	Flag/Qual	
Decachlorobiphenyl [1]	98.2	30-150		8/14/25 9:15
Decachlorobiphenyl [2]	97.6	30-150		8/14/25 9:15
Tetrachloro-m-xylene [1]	90.0	30-150		8/14/25 9:15
Tetrachloro-m-xylene [2]	98.7	30-150		8/14/25 9:15

Pace Analytical Services, LLC - East Longmeadow, Ma

39 Spruce Street * East Longmeadow, MA 01028 * FAX 413/525-6405 * TEL. 413/525-2332

Project Location: Canada Drive, East Syracuse, NY Sample Description: Work Order: 25G2029

Date Received: 7/30/2025

Field Sample #: SB91-Z12-24 Sampled: 7/28/2025 11:04

Sample ID: 25G2029-10

Sample Matrix: Soil

Conventional Chemistry Parameters by EPA/APHA/SW-846 Methods (Total)

Analyte	Results	RL	Units	Dilution	Flag/Qual	Method	Date Prepared	Date/Time Analyzed	Analyst
% Solids	94.6		% Wt	1		SM 2540G	8/1/25	8/1/25 13:00	MEF

Pace Analytical Services, LLC - East Longmeadow, Ma

39 Spruce Street * East Longmeadow, MA 01028 * FAX 413/525-6405 * TEL. 413/525-2332

Project Location: Canada Drive, East Syracuse, NY Sample Description: Work Order: 25G2029

Date Received: 7/30/2025

Field Sample #: SB91-Z24-36 Sampled: 7/28/2025 11:05

Sample ID: 25G2029-11

Sample Matrix: Soil

Polychlorinated Biphenyls By GC/ECD

Analyte	Results	RL	DL	Units	Dilution	Flag/Qual	Method	Date Prepared	Date/Time Analyzed	Analyst
Aroclor-1016 [1]	ND	0.087	0.023	mg/Kg dry	4		SW-846 8082A	8/8/25	8/14/25 9:27	TG
Aroclor-1221 [1]	ND	0.087	0.040	mg/Kg dry	4		SW-846 8082A	8/8/25	8/14/25 9:27	TG
Aroclor-1232 [1]	ND	0.087	0.023	mg/Kg dry	4		SW-846 8082A	8/8/25	8/14/25 9:27	TG
Aroclor-1242 [1]	ND	0.087	0.024	mg/Kg dry	4		SW-846 8082A	8/8/25	8/14/25 9:27	TG
Aroclor-1248 [1]	0.39	0.087	0.032	mg/Kg dry	4		SW-846 8082A	8/8/25	8/14/25 9:27	TG
Aroclor-1254 [1]	ND	0.087	0.038	mg/Kg dry	4		SW-846 8082A	8/8/25	8/14/25 9:27	TG
Aroclor-1260 [1]	ND	0.087	0.022	mg/Kg dry	4		SW-846 8082A	8/8/25	8/14/25 9:27	TG
Aroclor-1262 [1]	ND	0.087	0.029	mg/Kg dry	4		SW-846 8082A	8/8/25	8/14/25 9:27	TG
Aroclor-1268 [1]	ND	0.087	0.023	mg/Kg dry	4		SW-846 8082A	8/8/25	8/14/25 9:27	TG

Surrogates	% Recovery	Recovery Limits	Flag/Qual	
Decachlorobiphenyl [1]	104	30-150		8/14/25 9:27
Decachlorobiphenyl [2]	102	30-150		8/14/25 9:27
Tetrachloro-m-xylene [1]	97.4	30-150		8/14/25 9:27
Tetrachloro-m-xylene [2]	106	30-150		8/14/25 9:27

Pace Analytical Services, LLC - East Longmeadow, Ma

39 Spruce Street * East Longmeadow, MA 01028 * FAX 413/525-6405 * TEL. 413/525-2332

Project Location: Canada Drive, East Syracuse, NY Sample Description: Work Order: 25G2029

Date Received: 7/30/2025

Field Sample #: SB91-Z24-36 Sampled: 7/28/2025 11:05

Sample ID: 25G2029-11

Sample Matrix: Soil

Conventional Chemistry Parameters by EPA/APHA/SW-846 Methods (Total)

Analyte	Results	RL	Units	Dilution	Flag/Qual	Method	Date Prepared	Date/Time Analyzed	Analyst
% Solids	91.9		% Wt	1		SM 2540G	8/1/25	8/1/25 13:00	MEF

Pace Analytical Services, LLC - East Longmeadow, Ma

39 Spruce Street * East Longmeadow, MA 01028 * FAX 413/525-6405 * TEL. 413/525-2332

Project Location: Canada Drive, East Syracuse, NY Sample Description: Work Order: 25G2029

Date Received: 7/30/2025

Field Sample #: SB91-Z36-48 Sampled: 7/28/2025 11:06

Sample ID: 25G2029-12

Sample Matrix: Soil

Polychlorinated Biphenyls By GC/ECD

Analyte	Results	RL	DL	Units	Dilution	Flag/Qual	Method	Date Prepared	Date/Time Analyzed	Analyst
Aroclor-1016 [2]	ND	0.095	0.026	mg/Kg dry	4		SW-846 8082A	8/8/25	8/14/25 9:39	TG
Aroclor-1221 [2]	ND	0.095	0.044	mg/Kg dry	4		SW-846 8082A	8/8/25	8/14/25 9:39	TG
Aroclor-1232 [2]	ND	0.095	0.027	mg/Kg dry	4		SW-846 8082A	8/8/25	8/14/25 9:39	TG
Aroclor-1242 [2]	ND	0.095	0.029	mg/Kg dry	4		SW-846 8082A	8/8/25	8/14/25 9:39	TG
Aroclor-1248 [2]	0.078	0.095	0.036	mg/Kg dry	4	J	SW-846 8082A	8/8/25	8/14/25 9:39	TG
Aroclor-1254 [2]	ND	0.095	0.046	mg/Kg dry	4		SW-846 8082A	8/8/25	8/14/25 9:39	TG
Aroclor-1260 [2]	ND	0.095	0.027	mg/Kg dry	4		SW-846 8082A	8/8/25	8/14/25 9:39	TG
Aroclor-1262 [2]	ND	0.095	0.033	mg/Kg dry	4		SW-846 8082A	8/8/25	8/14/25 9:39	TG
Aroclor-1268 [2]	ND	0.095	0.031	mg/Kg dry	4		SW-846 8082A	8/8/25	8/14/25 9:39	TG

Surrogates	% Recovery	Recovery Limits	Flag/Qual	
Decachlorobiphenyl [1]	102	30-150		8/14/25 9:39
Decachlorobiphenyl [2]	100	30-150		8/14/25 9:39
Tetrachloro-m-xylene [1]	100	30-150		8/14/25 9:39
Tetrachloro-m-xylene [2]	106	30-150		8/14/25 9:39

Pace Analytical Services, LLC - East Longmeadow, Ma

39 Spruce Street * East Longmeadow, MA 01028 * FAX 413/525-6405 * TEL. 413/525-2332

Project Location: Canada Drive, East Syracuse, NY Sample Description: Work Order: 25G2029

Date Received: 7/30/2025

Field Sample #: SB91-Z36-48 Sampled: 7/28/2025 11:06

Sample ID: 25G2029-12

Sample Matrix: Soil

Conventional Chemistry Parameters by EPA/APHA/SW-846 Methods (Total)

Analyte	Results	RL	Units	Dilution	Flag/Qual	Method	Date Prepared	Date/Time Analyzed	Analyst
% Solids	84.1		% Wt	1		SM 2540G	8/1/25	8/1/25 13:00	MEF

Pace Analytical Services, LLC - East Longmeadow, Ma

39 Spruce Street * East Longmeadow, MA 01028 * FAX 413/525-6405 * TEL. 413/525-2332

Project Location: Canada Drive, East Syracuse, NY Sample Description: Work Order: 25G2029

Date Received: 7/30/2025

Field Sample #: SB91-Z48-60 Sampled: 7/28/2025 11:07

Sample ID: 25G2029-13

Sample Matrix: Soil

Sample Flags: O-32

Polychlorinated Biphenyls By GC/ECD

Analyte	Results	RL	DL	Units	Dilution	Flag/Qual	Method	Date Prepared	Date/Time Analyzed	Analyst
Aroclor-1016 [1]	ND	0.083	0.022	mg/Kg dry	4		SW-846 8082A	8/8/25	8/14/25 9:52	TG
Aroclor-1221 [1]	ND	0.083	0.038	mg/Kg dry	4		SW-846 8082A	8/8/25	8/14/25 9:52	TG
Aroclor-1232 [1]	ND	0.083	0.022	mg/Kg dry	4		SW-846 8082A	8/8/25	8/14/25 9:52	TG
Aroclor-1242 [1]	ND	0.083	0.023	mg/Kg dry	4		SW-846 8082A	8/8/25	8/14/25 9:52	TG
Aroclor-1248 [1]	ND	0.083	0.031	mg/Kg dry	4		SW-846 8082A	8/8/25	8/14/25 9:52	TG
Aroclor-1254 [1]	ND	0.083	0.036	mg/Kg dry	4		SW-846 8082A	8/8/25	8/14/25 9:52	TG
Aroclor-1260 [1]	ND	0.083	0.021	mg/Kg dry	4		SW-846 8082A	8/8/25	8/14/25 9:52	TG
Aroclor-1262 [1]	ND	0.083	0.028	mg/Kg dry	4		SW-846 8082A	8/8/25	8/14/25 9:52	TG
Aroclor-1268 [1]	ND	0.083	0.022	mg/Kg dry	4		SW-846 8082A	8/8/25	8/14/25 9:52	TG

Surrogates	% Recovery	Recovery Limits	Flag/Qual	
Decachlorobiphenyl [1]	99.2	30-150		8/14/25 9:52
Decachlorobiphenyl [2]	96.9	30-150		8/14/25 9:52
Tetrachloro-m-xylene [1]	94.8	30-150		8/14/25 9:52
Tetrachloro-m-xylene [2]	101	30-150		8/14/25 9:52

Pace Analytical Services, LLC - East Longmeadow, Ma

39 Spruce Street * East Longmeadow, MA 01028 * FAX 413/525-6405 * TEL. 413/525-2332

Project Location: Canada Drive, East Syracuse, NY Sample Description: Work Order: 25G2029

Date Received: 7/30/2025

Field Sample #: SB91-Z48-60 Sampled: 7/28/2025 11:07

Sample ID: 25G2029-13

Sample Matrix: Soil

Conventional Chemistry Parameters by EPA/APHA/SW-846 Methods (Total)

Analyte	Results	RL	Units	Dilution	Flag/Qual	Method	Date Prepared	Date/Time Analyzed	Analyst
% Solids	95.8		% Wt	1		SM 2540G	8/1/25	8/1/25 13:00	MEF

Pace Analytical Services, LLC - East Longmeadow, Ma

39 Spruce Street * East Longmeadow, MA 01028 * FAX 413/525-6405 * TEL. 413/525-2332

Project Location: Canada Drive, East Syracuse, NY Sample Description: Work Order: 25G2029

Date Received: 7/30/2025

Field Sample #: SB91-Z48-60-Q Sampled: 7/28/2025 11:09

Sample ID: 25G2029-14

Sample Matrix: Soil

Sample Flags: O-32

Polychlorinated Biphenyls By GC/ECD

Analyte	Results	RL	DL	Units	Dilution	Flag/Qual	Method	Date Prepared	Date/Time Analyzed	Analyst
Aroclor-1016 [1]	ND	0.085	0.022	mg/Kg dry	4		SW-846 8082A	8/8/25	8/14/25 10:04	TG
Aroclor-1221 [1]	ND	0.085	0.039	mg/Kg dry	4		SW-846 8082A	8/8/25	8/14/25 10:04	TG
Aroclor-1232 [1]	ND	0.085	0.022	mg/Kg dry	4		SW-846 8082A	8/8/25	8/14/25 10:04	TG
Aroclor-1242 [1]	ND	0.085	0.023	mg/Kg dry	4		SW-846 8082A	8/8/25	8/14/25 10:04	TG
Aroclor-1248 [1]	ND	0.085	0.031	mg/Kg dry	4		SW-846 8082A	8/8/25	8/14/25 10:04	TG
Aroclor-1254 [1]	ND	0.085	0.037	mg/Kg dry	4		SW-846 8082A	8/8/25	8/14/25 10:04	TG
Aroclor-1260 [1]	ND	0.085	0.022	mg/Kg dry	4		SW-846 8082A	8/8/25	8/14/25 10:04	TG
Aroclor-1262 [1]	ND	0.085	0.029	mg/Kg dry	4		SW-846 8082A	8/8/25	8/14/25 10:04	TG
Aroclor-1268 [1]	ND	0.085	0.022	mg/Kg dry	4		SW-846 8082A	8/8/25	8/14/25 10:04	TG

Surrogates	% Recovery	Recovery Limits	Flag/Qual	
Decachlorobiphenyl [1]	102	30-150		8/14/25 10:04
Decachlorobiphenyl [2]	99.4	30-150		8/14/25 10:04
Tetrachloro-m-xylene [1]	105	30-150		8/14/25 10:04
Tetrachloro-m-xylene [2]	110	30-150		8/14/25 10:04

Pace Analytical Services, LLC - East Longmeadow, Ma

39 Spruce Street * East Longmeadow, MA 01028 * FAX 413/525-6405 * TEL. 413/525-2332

Project Location: Canada Drive, East Syracuse, NY Sample Description: Work Order: 25G2029

Date Received: 7/30/2025

Field Sample #: SB91-Z48-60-Q Sampled: 7/28/2025 11:09

Sample ID: 25G2029-14

Sample Matrix: Soil

Conventional Chemistry Parameters by EPA/APHA/SW-846 Methods (Total)

Analyte	Results	RL	Units	Dilution	Flag/Qual	Method	Date Prepared	Date/Time Analyzed	Analyst
% Solids	94.3		% Wt	1		SM 2540G	8/1/25	8/1/25 13:00	MEF

Pace Analytical Services, LLC - East Longmeadow, Ma

39 Spruce Street * East Longmeadow, MA 01028 * FAX 413/525-6405 * TEL. 413/525-2332

Project Location: Canada Drive, East Syracuse, NY Sample Description: Work Order: 25G2029

Date Received: 7/30/2025

Field Sample #: SB90-Z00-12 Sampled: 7/28/2025 11:26

Sample ID: 25G2029-15

Sample Matrix: Soil

Polychlorinated Biphenyls By GC/ECD

Analyte	Results	RL	DL	Units	Dilution	Flag/Qual	Method	Date Prepared	Date/Time Analyzed	Analyst
Aroclor-1016 [1]	ND	9.5	2.5	mg/Kg dry	400		SW-846 8082A	8/8/25	8/14/25 12:05	TG
Aroclor-1221 [1]	ND	9.5	4.4	mg/Kg dry	400		SW-846 8082A	8/8/25	8/14/25 12:05	TG
Aroclor-1232 [1]	ND	9.5	2.5	mg/Kg dry	400		SW-846 8082A	8/8/25	8/14/25 12:05	TG
Aroclor-1242 [1]	ND	9.5	2.6	mg/Kg dry	400		SW-846 8082A	8/8/25	8/14/25 12:05	TG
Aroclor-1248 [1]	58	9.5	3.5	mg/Kg dry	400		SW-846 8082A	8/8/25	8/14/25 12:05	TG
Aroclor-1254 [1]	ND	9.5	4.1	mg/Kg dry	400		SW-846 8082A	8/8/25	8/14/25 12:05	TG
Aroclor-1260 [1]	ND	9.5	2.4	mg/Kg dry	400		SW-846 8082A	8/8/25	8/14/25 12:05	TG
Aroclor-1262 [1]	ND	9.5	3.2	mg/Kg dry	400		SW-846 8082A	8/8/25	8/14/25 12:05	TG
Aroclor-1268 [1]	ND	9.5	2.5	mg/Kg dry	400		SW-846 8082A	8/8/25	8/14/25 12:05	TG

Surrogates	% Recovery	Recovery Limits	Flag/Qual	
Decachlorobiphenyl [1]	*	30-150	S-01	8/14/25 12:05
Decachlorobiphenyl [2]	*	30-150	S-01	8/14/25 12:05
Tetrachloro-m-xylene [1]	*	30-150	S-01	8/14/25 12:05
Tetrachloro-m-xylene [2]	*	30-150	S-01	8/14/25 12:05

Pace Analytical Services, LLC - East Longmeadow, Ma

39 Spruce Street * East Longmeadow, MA 01028 * FAX 413/525-6405 * TEL. 413/525-2332

Project Location: Canada Drive, East Syracuse, NY Sample Description: Work Order: 25G2029

Date Received: 7/30/2025

Field Sample #: SB90-Z00-12 Sampled: 7/28/2025 11:26

Sample ID: 25G2029-15

Sample Matrix: Soil

Conventional Chemistry Parameters by EPA/APHA/SW-846 Methods (Total)

Analyte	Results	RL	Units	Dilution	Flag/Qual	Method	Date Prepared	Date/Time Analyzed	Analyst
% Solids	83.9		% Wt	1		SM 2540G	8/1/25	8/1/25 13:00	MEF

Pace Analytical Services, LLC - East Longmeadow, Ma

39 Spruce Street * East Longmeadow, MA 01028 * FAX 413/525-6405 * TEL. 413/525-2332

Project Location: Canada Drive, East Syracuse, NY Sample Description: Work Order: 25G2029

Date Received: 7/30/2025

Field Sample #: SB90-Z12-24 Sampled: 7/28/2025 11:27

Sample ID: 25G2029-16

Sample Matrix: Soil

Polychlorinated Biphenyls By GC/ECD

Analyte	Results	RL	DL	Units	Dilution	Flag/Qual	Method	Date Prepared	Date/Time Analyzed	Analyst
Aroclor-1016 [1]	ND	4.5	1.2	mg/Kg dry	200		SW-846 8082A	8/8/25	8/14/25 12:17	TG
Aroclor-1221 [1]	ND	4.5	2.1	mg/Kg dry	200		SW-846 8082A	8/8/25	8/14/25 12:17	TG
Aroclor-1232 [1]	ND	4.5	1.2	mg/Kg dry	200		SW-846 8082A	8/8/25	8/14/25 12:17	TG
Aroclor-1242 [1]	ND	4.5	1.2	mg/Kg dry	200		SW-846 8082A	8/8/25	8/14/25 12:17	TG
Aroclor-1248 [1]	26	4.5	1.7	mg/Kg dry	200		SW-846 8082A	8/8/25	8/14/25 12:17	TG
Aroclor-1254 [1]	ND	4.5	2.0	mg/Kg dry	200		SW-846 8082A	8/8/25	8/14/25 12:17	TG
Aroclor-1260 [1]	ND	4.5	1.1	mg/Kg dry	200		SW-846 8082A	8/8/25	8/14/25 12:17	TG
Aroclor-1262 [1]	ND	4.5	1.5	mg/Kg dry	200		SW-846 8082A	8/8/25	8/14/25 12:17	TG
Aroclor-1268 [1]	ND	4.5	1.2	mg/Kg dry	200		SW-846 8082A	8/8/25	8/14/25 12:17	TG

Surrogates	% Recovery	Recovery Limits	Flag/Qual	
Decachlorobiphenyl [1]	*	30-150	S-01	8/14/25 12:17
Decachlorobiphenyl [2]	*	30-150	S-01	8/14/25 12:17
Tetrachloro-m-xylene [1]	*	30-150	S-01	8/14/25 12:17
Tetrachloro-m-xylene [2]	*	30-150	S-01	8/14/25 12:17

Pace Analytical Services, LLC - East Longmeadow, Ma

39 Spruce Street * East Longmeadow, MA 01028 * FAX 413/525-6405 * TEL. 413/525-2332

Project Location: Canada Drive, East Syracuse, NY Sample Description: Work Order: 25G2029

Date Received: 7/30/2025

Field Sample #: SB90-Z12-24 Sampled: 7/28/2025 11:27

Sample ID: 25G2029-16

Sample Matrix: Soil

Conventional Chemistry Parameters by EPA/APHA/SW-846 Methods (Total)

Analyte	Results	RL	Units	Dilution	Flag/Qual	Method	Date Prepared	Date/Time Analyzed	Analyst
% Solids	88.8		% Wt	1		SM 2540G	8/1/25	8/1/25 13:00	MEF

Pace Analytical Services, LLC - East Longmeadow, Ma

39 Spruce Street * East Longmeadow, MA 01028 * FAX 413/525-6405 * TEL. 413/525-2332

Project Location: Canada Drive, East Syracuse, NY Sample Description: Work Order: 25G2029

Date Received: 7/30/2025

Field Sample #: SB90-Z24-36 Sampled: 7/28/2025 11:28

Sample ID: 25G2029-17

Sample Matrix: Soil

Polychlorinated Biphenyls By GC/ECD

Analyte	Results	RL	DL	Units	Dilution	Flag/Qual	Method	Date Prepared	Date/Time Analyzed	Analyst
Aroclor-1016 [1]	ND	0.44	0.12	mg/Kg dry	20		SW-846 8082A	8/8/25	8/14/25 12:29	TG
Aroclor-1221 [1]	ND	0.44	0.20	mg/Kg dry	20		SW-846 8082A	8/8/25	8/14/25 12:29	TG
Aroclor-1232 [1]	ND	0.44	0.12	mg/Kg dry	20		SW-846 8082A	8/8/25	8/14/25 12:29	TG
Aroclor-1242 [1]	ND	0.44	0.12	mg/Kg dry	20		SW-846 8082A	8/8/25	8/14/25 12:29	TG
Aroclor-1248 [1]	2.7	0.44	0.16	mg/Kg dry	20		SW-846 8082A	8/8/25	8/14/25 12:29	TG
Aroclor-1254 [1]	ND	0.44	0.19	mg/Kg dry	20		SW-846 8082A	8/8/25	8/14/25 12:29	TG
Aroclor-1260 [1]	ND	0.44	0.11	mg/Kg dry	20		SW-846 8082A	8/8/25	8/14/25 12:29	TG
Aroclor-1262 [1]	ND	0.44	0.15	mg/Kg dry	20		SW-846 8082A	8/8/25	8/14/25 12:29	TG
Aroclor-1268 [1]	ND	0.44	0.12	mg/Kg dry	20		SW-846 8082A	8/8/25	8/14/25 12:29	TG

Surrogates	% Recovery	Recovery Limits	Flag/Qual	
Decachlorobiphenyl [1]	102	30-150		8/14/25 12:29
Decachlorobiphenyl [2]	96.0	30-150		8/14/25 12:29
Tetrachloro-m-xylene [1]	101	30-150		8/14/25 12:29
Tetrachloro-m-xylene [2]	101	30-150		8/14/25 12:29

Pace Analytical Services, LLC - East Longmeadow, Ma

39 Spruce Street * East Longmeadow, MA 01028 * FAX 413/525-6405 * TEL. 413/525-2332

Project Location: Canada Drive, East Syracuse, NY Sample Description: Work Order: 25G2029

Date Received: 7/30/2025

Field Sample #: SB90-Z24-36 Sampled: 7/28/2025 11:28

Sample ID: 25G2029-17

Sample Matrix: Soil

Conventional Chemistry Parameters by EPA/APHA/SW-846 Methods (Total)

Analyte	Results	RL	Units	Dilution	Flag/Qual	Method	Date Prepared	Date/Time Analyzed	Analyst
% Solids	90.2		% Wt	1		SM 2540G	8/1/25	8/1/25 13:00	MEF

Pace Analytical Services, LLC - East Longmeadow, Ma

39 Spruce Street * East Longmeadow, MA 01028 * FAX 413/525-6405 * TEL. 413/525-2332

Sample Extraction Data

Prep Method:% Solids **Analytical Method:SM 2540G**

Lab Number [Field ID]	Batch	Date
25G2029-01 [SB88-Z00-12-Q]	B410539	08/01/25
25G2029-02 [SB88-Z12-24]	B410539	08/01/25
25G2029-03 [SB88-Z24-36]	B410539	08/01/25
25G2029-04 [SB88-Z36-48]	B410539	08/01/25
25G2029-05 [SB89-Z00-12]	B410539	08/01/25
25G2029-06 [SB89-Z12-24]	B410539	08/01/25
25G2029-07 [SB89-Z24-36]	B410539	08/01/25
25G2029-08 [SB89-Z36-48]	B410539	08/01/25
25G2029-09 [SB91-Z00-12]	B410539	08/01/25
25G2029-10 [SB91-Z12-24]	B410539	08/01/25
25G2029-11 [SB91-Z24-36]	B410539	08/01/25
25G2029-12 [SB91-Z36-48]	B410539	08/01/25
25G2029-13 [SB91-Z48-60]	B410539	08/01/25
25G2029-14 [SB91-Z48-60-Q]	B410539	08/01/25
25G2029-15 [SB90-Z00-12]	B410539	08/01/25
25G2029-16 [SB90-Z12-24]	B410539	08/01/25
25G2029-17 [SB90-Z24-36]	B410539	08/01/25

Prep Method:SW-846 3546 **Analytical Method:SW-846 8082A**

Lab Number [Field ID]	Batch	Initial [g]	Final [mL]	Date
25G2029-01 [SB88-Z00-12-Q]	B411044	10.0	10.0	08/08/25
25G2029-02 [SB88-Z12-24]	B411044	10.1	10.0	08/08/25
25G2029-03 [SB88-Z24-36]	B411044	10.0	10.0	08/08/25
25G2029-04 [SB88-Z36-48]	B411044	10.0	10.0	08/08/25
25G2029-05 [SB89-Z00-12]	B411044	10.1	10.0	08/08/25
25G2029-06 [SB89-Z12-24]	B411044	10.1	10.0	08/08/25
25G2029-07 [SB89-Z24-36]	B411044	10.0	10.0	08/08/25
25G2029-08 [SB89-Z36-48]	B411044	10.0	10.0	08/08/25
25G2029-09 [SB91-Z00-12]	B411044	10.1	10.0	08/08/25
25G2029-10 [SB91-Z12-24]	B411044	10.0	10.0	08/08/25
25G2029-11 [SB91-Z24-36]	B411044	10.0	10.0	08/08/25
25G2029-12 [SB91-Z36-48]	B411044	10.0	10.0	08/08/25
25G2029-13 [SB91-Z48-60]	B411044	10.0	10.0	08/08/25
25G2029-14 [SB91-Z48-60-Q]	B411044	10.0	10.0	08/08/25
25G2029-15 [SB90-Z00-12]	B411044	10.0	10.0	08/08/25
25G2029-16 [SB90-Z12-24]	B411044	10.0	10.0	08/08/25
25G2029-17 [SB90-Z24-36]	B411044	10.0	10.0	08/08/25

Pace Analytical Services, LLC - East Longmeadow, Ma

39 Spruce Street * East Longmeadow, MA 01028 * FAX 413/525-6405 * TEL. 413/525-2332

QUALITY CONTROL

Polychlorinated Biphenyls By GC/ECD - Quality Control

Analyte	Result	Reporting Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes
Batch B411044 - SW-846 3546										
Blank (B411044-BLK1)				Prepared: 08/08/25 Analyzed: 08/13/25						
Aroclor-1016	ND	0.020	mg/Kg wet							
Aroclor-1016 [2C]	ND	0.020	mg/Kg wet							
Aroclor-1221	ND	0.020	mg/Kg wet							
Aroclor-1221 [2C]	ND	0.020	mg/Kg wet							
Aroclor-1232	ND	0.020	mg/Kg wet							
Aroclor-1232 [2C]	ND	0.020	mg/Kg wet							
Aroclor-1242	ND	0.020	mg/Kg wet							
Aroclor-1242 [2C]	ND	0.020	mg/Kg wet							
Aroclor-1248	ND	0.020	mg/Kg wet							
Aroclor-1248 [2C]	ND	0.020	mg/Kg wet							
Aroclor-1254	ND	0.020	mg/Kg wet							
Aroclor-1254 [2C]	ND	0.020	mg/Kg wet							
Aroclor-1260	ND	0.020	mg/Kg wet							
Aroclor-1260 [2C]	ND	0.020	mg/Kg wet							
Aroclor-1262	ND	0.020	mg/Kg wet							
Aroclor-1262 [2C]	ND	0.020	mg/Kg wet							
Aroclor-1268	ND	0.020	mg/Kg wet							
Aroclor-1268 [2C]	ND	0.020	mg/Kg wet							
Surrogate: Decachlorobiphenyl	*0.210*		mg/Kg wet	0.2000		105	30-150			
Surrogate: Decachlorobiphenyl [2C]	*0.212*		mg/Kg wet	0.2000		106	30-150			
Surrogate: Tetrachloro-m-xylene	*0.199*		mg/Kg wet	0.2000		99.6	30-150			
Surrogate: Tetrachloro-m-xylene [2C]	*0.218*		mg/Kg wet	0.2000		109	30-150			
LCS (B411044-BS1)				Prepared: 08/08/25 Analyzed: 08/13/25						
Aroclor-1016	0.17	0.020	mg/Kg wet	0.1996		87.4	40-140			
Aroclor-1016 [2C]	0.19	0.020	mg/Kg wet	0.1996		95.7	40-140			
Aroclor-1260	0.19	0.020	mg/Kg wet	0.1996		97.1	40-140			
Aroclor-1260 [2C]	0.20	0.020	mg/Kg wet	0.1996		99.8	40-140			
Surrogate: Decachlorobiphenyl	*0.210*		mg/Kg wet	0.1996		105	30-150			
Surrogate: Decachlorobiphenyl [2C]	*0.210*		mg/Kg wet	0.1996		105	30-150			
Surrogate: Tetrachloro-m-xylene	*0.205*		mg/Kg wet	0.1996		103	30-150			
Surrogate: Tetrachloro-m-xylene [2C]	*0.224*		mg/Kg wet	0.1996		112	30-150			
LCS Dup (B411044-BSD1)				Prepared: 08/08/25 Analyzed: 08/13/25						
Aroclor-1016	0.17	0.020	mg/Kg wet	0.1994		86.0	40-140	1.64	30	
Aroclor-1016 [2C]	0.19	0.020	mg/Kg wet	0.1994		94.0	40-140	1.83	30	
Aroclor-1260	0.19	0.020	mg/Kg wet	0.1994		97.2	40-140	0.111	30	
Aroclor-1260 [2C]	0.20	0.020	mg/Kg wet	0.1994		99.5	40-140	0.312	30	
Surrogate: Decachlorobiphenyl	*0.209*		mg/Kg wet	0.1994		105	30-150			
Surrogate: Decachlorobiphenyl [2C]	*0.210*		mg/Kg wet	0.1994		105	30-150			
Surrogate: Tetrachloro-m-xylene	*0.199*		mg/Kg wet	0.1994		99.8	30-150			
Surrogate: Tetrachloro-m-xylene [2C]	*0.216*		mg/Kg wet	0.1994		108	30-150			

Pace Analytical Services, LLC - East Longmeadow, Ma

39 Spruce Street * East Longmeadow, MA 01028 * FAX 413/525-6405 * TEL. 413/525-2332

QUALITY CONTROL

Conventional Chemistry Parameters by EPA/APHA/SW-846 Methods (Total) - Quality Control

Analyte	Result	Reporting Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD		RPD Limit	Notes
Batch B410539 - % Solids											
Duplicate (B410539-DUP2)	**Source: 25G2029-01**			Prepared & Analyzed: 08/01/25							
% Solids	96.9		% Wt		86.8			**10.9**	*	10	R-02

Pace Analytical Services, LLC - East Longmeadow, Ma

39 Spruce Street * East Longmeadow, MA 01028 * FAX 413/525-6405 * TEL. 413/525-2332

IDENTIFICATION SUMMARY FOR SINGLE COMPONENT ANALYTES

SW-846 8082A

SB88-Z00-12-Q

Lab Sample ID: 25G2029-01 Date(s) Analyzed: 08/14/2025 08/14/2025

Instrument ID (1): ECD3 Instrument ID (2): ECD3

GC Column (1): ID: (mm) GC Column (2): ID: (mm)

ANALYTE	COL	RT	RT WINDOW		CONCENTRATION	%RPD
			FROM	TO		
Aroclor-1248	1	0.000	0.000	0.000	31	
	2	0.000	0.000	0.000	28	10.2

Pace Analytical Services, LLC - East Longmeadow, Ma

39 Spruce Street * East Longmeadow, MA 01028 * FAX 413/525-6405 * TEL. 413/525-2332

IDENTIFICATION SUMMARY FOR SINGLE COMPONENT ANALYTES

SW-846 8082A

SB88-Z12-24

Lab Sample ID: 25G2029-02 Date(s) Analyzed: 08/13/2025 08/13/2025

Instrument ID (1): ECD3 Instrument ID (2): ECD3

GC Column (1): ID: (mm) GC Column (2): ID: (mm)

ANALYTE	COL	RT	RT WINDOW		CONCENTRATION	%RPD
			FROM	TO		
Aroclor-1248	1	0.000	0.000	0.000	0.80	
	2	0.000	0.000	0.000	0.75	6.5

Pace Analytical Services, LLC - East Longmeadow, Ma

39 Spruce Street * East Longmeadow, MA 01028 * FAX 413/525-6405 * TEL. 413/525-2332

IDENTIFICATION SUMMARY FOR SINGLE COMPONENT ANALYTES

SW-846 8082A

SB88-Z24-36

Lab Sample ID: 25G2029-03 Date(s) Analyzed: 08/13/2025 08/13/2025

Instrument ID (1): ECD3 Instrument ID (2): ECD3

GC Column (1): ID: (mm) GC Column (2): ID: (mm)

ANALYTE	COL	RT	RT WINDOW		CONCENTRATION	%RPD
			FROM	TO		
Aroclor-1248	1	0.000	0.000	0.000	0.32	
	2	0.000	0.000	0.000	0.30	6.5

Pace Analytical Services, LLC - East Longmeadow, Ma

39 Spruce Street * East Longmeadow, MA 01028 * FAX 413/525-6405 * TEL. 413/525-2332

IDENTIFICATION SUMMARY FOR SINGLE COMPONENT ANALYTES

SW-846 8082A

SB88-Z36-48

Lab Sample ID: 25G2029-04 Date(s) Analyzed: 08/13/2025 08/13/2025

Instrument ID (1): ECD3 Instrument ID (2): ECD3

GC Column (1): ID: (mm) GC Column (2): ID: (mm)

ANALYTE	COL	RT	RT WINDOW		CONCENTRATION	%RPD
			FROM	TO		
Aroclor-1248	1	0.000	0.000	0.000	0.14	
	2	0.000	0.000	0.000	0.14	0.0

Pace Analytical Services, LLC - East Longmeadow, Ma

39 Spruce Street * East Longmeadow, MA 01028 * FAX 413/525-6405 * TEL. 413/525-2332

IDENTIFICATION SUMMARY FOR SINGLE COMPONENT ANALYTES

SW-846 8082A

SB89-Z00-12

Lab Sample ID: 25G2029-05 Date(s) Analyzed: 08/14/2025 08/14/2025

Instrument ID (1): ECD3 Instrument ID (2): ECD3

GC Column (1): ID: (mm) GC Column (2): ID: (mm)

ANALYTE	COL	RT	RT WINDOW		CONCENTRATION	%RPD
			FROM	TO		
Aroclor-1248	1	0.000	0.000	0.000	44	
	2	0.000	0.000	0.000	40	9.5

Pace Analytical Services, LLC - East Longmeadow, Ma

39 Spruce Street * East Longmeadow, MA 01028 * FAX 413/525-6405 * TEL. 413/525-2332

IDENTIFICATION SUMMARY FOR SINGLE COMPONENT ANALYTES

SW-846 8082A

SB89-Z12-24

Lab Sample ID: 25G2029-06 Date(s) Analyzed: 08/14/2025 08/14/2025

Instrument ID (1): ECD3 Instrument ID (2): ECD3

GC Column (1): ID: (mm) GC Column (2): ID: (mm)

ANALYTE	COL	RT	RT WINDOW		CONCENTRATION	%RPD
			FROM	TO		
Aroclor-1248	1	0.000	0.000	0.000	22	
	2	0.000	0.000	0.000	21	4.7

Pace Analytical Services, LLC - East Longmeadow, Ma

39 Spruce Street * East Longmeadow, MA 01028 * FAX 413/525-6405 * TEL. 413/525-2332

IDENTIFICATION SUMMARY FOR SINGLE COMPONENT ANALYTES

SW-846 8082A

SB89-Z24-36

Lab Sample ID: 25G2029-07 Date(s) Analyzed: 08/13/2025 08/13/2025

Instrument ID (1): ECD3 Instrument ID (2): ECD3

GC Column (1): ID: (mm) GC Column (2): ID: (mm)

ANALYTE	COL	RT	RT WINDOW		CONCENTRATION	%RPD
			FROM	TO		
Aroclor-1248	1	0.000	0.000	0.000	0.62	
	2	0.000	0.000	0.000	0.59	5.0

Pace Analytical Services, LLC - East Longmeadow, Ma

39 Spruce Street * East Longmeadow, MA 01028 * FAX 413/525-6405 * TEL. 413/525-2332

IDENTIFICATION SUMMARY FOR SINGLE COMPONENT ANALYTES

SW-846 8082A

SB89-Z36-48

Lab Sample ID: 25G2029-08 Date(s) Analyzed: 08/14/2025 08/14/2025

Instrument ID (1): ECD3 Instrument ID (2): ECD3

GC Column (1): ID: (mm) GC Column (2): ID: (mm)

ANALYTE	COL	RT	RT WINDOW		CONCENTRATION	%RPD
			FROM	TO		
Aroclor-1248	1	0.000	0.000	0.000	2.8	
	2	0.000	0.000	0.000	2.6	7.4

Pace Analytical Services, LLC - East Longmeadow, Ma

39 Spruce Street * East Longmeadow, MA 01028 * FAX 413/525-6405 * TEL. 413/525-2332

IDENTIFICATION SUMMARY FOR SINGLE COMPONENT ANALYTES

SW-846 8082A

SB91-Z00-12

Lab Sample ID: 25G2029-09 Date(s) Analyzed: 08/14/2025 08/14/2025

Instrument ID (1): ECD3 Instrument ID (2): ECD3

GC Column (1): ID: (mm) GC Column (2): ID: (mm)

ANALYTE	COL	RT	RT WINDOW		CONCENTRATION	%RPD
			FROM	TO		
Aroclor-1248	1	0.000	0.000	0.000	1.3	
	2	0.000	0.000	0.000	1.2	8.0

Pace Analytical Services, LLC - East Longmeadow, Ma

39 Spruce Street * East Longmeadow, MA 01028 * FAX 413/525-6405 * TEL. 413/525-2332

IDENTIFICATION SUMMARY FOR SINGLE COMPONENT ANALYTES

SW-846 8082A

SB91-Z12-24

Lab Sample ID: 25G2029-10 Date(s) Analyzed: 08/14/2025 08/14/2025

Instrument ID (1): ECD3 Instrument ID (2): ECD3

GC Column (1): ID: (mm) GC Column (2): ID: (mm)

ANALYTE	COL	RT	RT WINDOW		CONCENTRATION	%RPD
			FROM	TO		
Aroclor-1248	1	0.000	0.000	0.000	0.28	
	2	0.000	0.000	0.000	0.26	7.4

Pace Analytical Services, LLC - East Longmeadow, Ma

39 Spruce Street * East Longmeadow, MA 01028 * FAX 413/525-6405 * TEL. 413/525-2332

IDENTIFICATION SUMMARY FOR SINGLE COMPONENT ANALYTES

SW-846 8082A

SB91-Z24-36

Lab Sample ID: 25G2029-11 Date(s) Analyzed: 08/14/2025 08/14/2025

Instrument ID (1): ECD3 Instrument ID (2): ECD3

GC Column (1): ID: (mm) GC Column (2): ID: (mm)

ANALYTE	COL	RT	RT WINDOW		CONCENTRATION	%RPD
			FROM	TO		
Aroclor-1248	1	0.000	0.000	0.000	0.39	
	2	0.000	0.000	0.000	0.37	5.3

Pace Analytical Services, LLC - East Longmeadow, Ma

39 Spruce Street * East Longmeadow, MA 01028 * FAX 413/525-6405 * TEL. 413/525-2332

IDENTIFICATION SUMMARY FOR SINGLE COMPONENT ANALYTES

SW-846 8082A

SB91-Z36-48

Lab Sample ID: 25G2029-12 Date(s) Analyzed: 08/14/2025 08/14/2025

Instrument ID (1): ECD3 Instrument ID (2): ECD3

GC Column (1): ID: (mm) GC Column (2): ID: (mm)

ANALYTE	COL	RT	RT WINDOW		CONCENTRATION	%RPD
			FROM	TO		
Aroclor-1248	1	0.000	0.000	0.000	0.075	
	2	0.000	0.000	0.000	0.078	3.9

Pace Analytical Services, LLC - East Longmeadow, Ma

39 Spruce Street * East Longmeadow, MA 01028 * FAX 413/525-6405 * TEL. 413/525-2332

IDENTIFICATION SUMMARY FOR SINGLE COMPONENT ANALYTES

SW-846 8082A

SB90-Z00-12

Lab Sample ID: 25G2029-15 Date(s) Analyzed: 08/14/2025 08/14/2025

Instrument ID (1): ECD3 Instrument ID (2): ECD3

GC Column (1): ID: (mm) GC Column (2): ID: (mm)

ANALYTE	COL	RT	RT WINDOW		CONCENTRATION	%RPD
			FROM	TO		
Aroclor-1248	1	0.000	0.000	0.000	58	
	2	0.000	0.000	0.000	53	9.0

Pace Analytical Services, LLC - East Longmeadow, Ma

39 Spruce Street * East Longmeadow, MA 01028 * FAX 413/525-6405 * TEL. 413/525-2332

IDENTIFICATION SUMMARY FOR SINGLE COMPONENT ANALYTES

SW-846 8082A

SB90-Z12-24

Lab Sample ID: 25G2029-16 Date(s) Analyzed: 08/14/2025 08/14/2025

Instrument ID (1): ECD3 Instrument ID (2): ECD3

GC Column (1): ID: (mm) GC Column (2): ID: (mm)

ANALYTE	COL	RT	RT WINDOW		CONCENTRATION	%RPD
			FROM	TO		
Aroclor-1248	1	0.000	0.000	0.000	26	
	2	0.000	0.000	0.000	23	12.2

Pace Analytical Services, LLC - East Longmeadow, Ma

39 Spruce Street * East Longmeadow, MA 01028 * FAX 413/525-6405 * TEL. 413/525-2332

IDENTIFICATION SUMMARY FOR SINGLE COMPONENT ANALYTES

SW-846 8082A

SB90-Z24-36

Lab Sample ID: 25G2029-17 Date(s) Analyzed: 08/14/2025 08/14/2025

Instrument ID (1): ECD3 Instrument ID (2): ECD3

GC Column (1): ID: (mm) GC Column (2): ID: (mm)

ANALYTE	COL	RT	RT WINDOW		CONCENTRATION	%RPD
			FROM	TO		
Aroclor-1248	1	0.000	0.000	0.000	2.7	
	2	0.000	0.000	0.000	2.5	7.7

Pace Analytical Services, LLC - East Longmeadow, Ma

39 Spruce Street * East Longmeadow, MA 01028 * FAX 413/525-6405 * TEL. 413/525-2332

IDENTIFICATION SUMMARY FOR SINGLE COMPONENT ANALYTES

SW-846 8082A

LCS

Lab Sample ID: B411044-BS1 Date(s) Analyzed: 08/13/2025 08/13/2025

Instrument ID (1): ECD3 Instrument ID (2): ECD3

GC Column (1): ID: (mm) GC Column (2): ID: (mm)

ANALYTE	COL	RT	RT WINDOW		CONCENTRATION	%RPD
			FROM	TO		
Aroclor-1016	1	0.000	0.000	0.000	0.17	
	2	0.000	0.000	0.000	0.19	11.1
Aroclor-1260	1	0.000	0.000	0.000	0.19	
	2	0.000	0.000	0.000	0.20	5.1

Pace Analytical Services, LLC - East Longmeadow, Ma

39 Spruce Street * East Longmeadow, MA 01028 * FAX 413/525-6405 * TEL. 413/525-2332

IDENTIFICATION SUMMARY FOR SINGLE COMPONENT ANALYTES

SW-846 8082A

LCS Dup

Lab Sample ID: B411044-BSD1 Date(s) Analyzed: 08/13/2025 08/13/2025

Instrument ID (1): ECD3 Instrument ID (2): ECD3

GC Column (1): ID: (mm) GC Column (2): ID: (mm)

ANALYTE	COL	RT	RT WINDOW		CONCENTRATION	%RPD
			FROM	TO		
Aroclor-1016	1	0.000	0.000	0.000	0.17	
	2	0.000	0.000	0.000	0.19	11.1
Aroclor-1260	1	0.000	0.000	0.000	0.19	
	2	0.000	0.000	0.000	0.20	5.1

Pace Analytical Services, LLC - East Longmeadow, Ma

39 Spruce Street * East Longmeadow, MA 01028 * FAX 413/525-6405 * TEL. 413/525-2332

FLAG/QUALIFIER SUMMARY

*	QC result is outside of established limits.
†	Wide recovery limits established for difficult compound.
‡	Wide RPD limits established for difficult compound.
#	Data exceeded client recommended or regulatory level
ND	Not Detected
RL	Reporting Limit is at the level of quantitation (LOQ)
DL	Detection Limit is the lower limit of detection determined by the MDL study
MCL	Maximum Contaminant Level
	Percent recoveries and relative percent differences (RPDs) are determined by the software using values in the calculation which have not been rounded.
	No results have been blank subtracted unless specified in the case narrative section.
J	Detected but below the Reporting Limit (lowest calibration standard); therefore, result is an estimated concentration (CLP J-Flag).
O-32	A dilution was performed as part of the standard analytical procedure.
R-02	Duplicate RPD is outside of control limits. Outlier can be attributed to sample non-homogeneity encountered during sample prep.
S-01	The surrogate recovery for this sample is not available due to sample dilution below the surrogate reporting limit required from high analyte concentration and/or matrix interferences.

Pace Analytical Services, LLC - East Longmeadow, Ma

39 Spruce Street * East Longmeadow, MA 01028 * FAX 413/525-6405 * TEL. 413/525-2332

CERTIFICATIONS

Certified Analyses included in this Report

Analyte	Certifications
SW-846 8082A in Soil	
Aroclor-1016	CT,NH,NY,NC,ME,VA,PA,NJ
Aroclor-1016 [2C]	CT,NH,NY,NC,ME,VA,PA,NJ
Aroclor-1221	CT,NH,NY,NC,ME,VA,PA,NJ
Aroclor-1221 [2C]	CT,NH,NY,NC,ME,VA,PA,NJ
Aroclor-1232	CT,NH,NY,NC,ME,VA,PA,NJ
Aroclor-1232 [2C]	CT,NH,NY,NC,ME,VA,PA,NJ
Aroclor-1242	CT,NH,NY,NC,ME,VA,PA,NJ
Aroclor-1242 [2C]	CT,NH,NY,NC,ME,VA,PA,NJ
Aroclor-1248	CT,NH,NY,NC,ME,VA,PA,NJ
Aroclor-1248 [2C]	CT,NH,NY,NC,ME,VA,PA,NJ
Aroclor-1254	CT,NH,NY,NC,ME,VA,PA,NJ
Aroclor-1254 [2C]	CT,NH,NY,NC,ME,VA,PA,NJ
Aroclor-1260	CT,NH,NY,NC,ME,VA,PA,NJ
Aroclor-1260 [2C]	CT,NH,NY,NC,ME,VA,PA,NJ
Aroclor-1262	NH,NY,NC,ME,VA,PA,NJ
Aroclor-1262 [2C]	NH,NY,NC,ME,VA,PA,NJ
Aroclor-1268	NH,NY,NC,ME,VA,PA,NJ
Aroclor-1268 [2C]	NH,NY,NC,ME,VA,PA,NJ
SW-846 8082A in Water	
Aroclor-1016	CT,NH,NY,NC,ME,VA,PA,NJ
Aroclor-1016 [2C]	CT,NH,NY,NC,ME,VA,PA,NJ
Aroclor-1221	CT,NH,NY,NC,ME,VA,PA,NJ
Aroclor-1221 [2C]	CT,NH,NY,NC,ME,VA,PA,NJ
Aroclor-1232	CT,NH,NY,NC,ME,VA,PA,NJ
Aroclor-1232 [2C]	CT,NH,NY,NC,ME,VA,PA,NJ
Aroclor-1242	CT,NH,NY,NC,ME,VA,PA,NJ
Aroclor-1242 [2C]	CT,NH,NY,NC,ME,VA,PA,NJ
Aroclor-1248	CT,NH,NY,NC,ME,VA,PA,NJ
Aroclor-1248 [2C]	CT,NH,NY,NC,ME,VA,PA,NJ
Aroclor-1254	CT,NH,NY,NC,ME,VA,PA,NJ
Aroclor-1254 [2C]	CT,NH,NY,NC,ME,VA,PA,NJ
Aroclor-1260	CT,NH,NY,NC,ME,VA,PA,NJ
Aroclor-1260 [2C]	CT,NH,NY,NC,ME,VA,PA,NJ
Aroclor-1262	NH,NY,NC,ME,VA,PA,NJ
Aroclor-1262 [2C]	NH,NY,NC,ME,VA,PA,NJ
Aroclor-1268	NH,NY,NC,ME,VA,PA,NJ
Aroclor-1268 [2C]	NH,NY,NC,ME,VA,PA,NJ

Pace Analytical Services, LLC - East Longmeadow, Ma

39 Spruce Street * East Longmeadow, MA 01028 * FAX 413/525-6405 * TEL. 413/525-2332

Pace Analytical Services, LLC - East Longmeadow, Ma, operates under the following certifications and accreditations:

Code	Description	Number	Expires
CT	Connecticut Department of Public Health	PH-0821	12/31/2026
NY	New York State Department of Health	10899 NELAP	04/1/2026
NH	New Hampshire Environmental Lab	2516 NELAP	02/5/2026
NC	North Carolina Div. of Water Quality	652	12/31/2025
NJ	New Jersey DEP	MA007 NELAP	06/30/2026
ME	State of Maine	MA00100	06/9/2027
VA	Commonwealth of Virginia	460217	12/14/2025
PA	Commonwealth of Pennsylvania DEP	68-05812	06/30/2026

east Lay Meadow facility 25G2029

Pace® Location Requested (City/State):

CHAIN-OF-CUSTODY Analytical Request Document

Chain-of-Custody is a LEGAL DOCUMENT - Complete all relevant fields

LAB USE ONLY- Affix Workorder/Login Label Here

Scan QR Code for instructions

Company Name: WSP USA	Contact/Report To: Drew Bullinger
Street Address: 40 La Riviere Dr Suite 300 Buffalo, NY 14202	Phone #:
Customer Project #:	E-Mail: Drew.Bullinger@wsp.com
Project Name: Lovck Rd extension	Cc E-Mail:
Site Collection Info/Facility ID (as applicable): Site # C734145A	Invoice to: DEC Lab Callout #: 153133
	Invoice E-mail: kateh.caHill@dec.ny.gov
	Purchase Order # (if applicable): DEC Lab Callout # 153133
	Quote #:
Time Zone Collected: [ ] AK [ ] PT [ ] MT [ ] CT [X] ET	County / State origin of sample(s): New York
Data Deliverables: [ ] Level II [ ] Level III [ ] Level IV [X] EQUIS [ ] Other	Regulatory Program (DW, RCRA, etc.) as applicable: NYS DEC Reportable [ ] Yes [ ] No
	Rush (Pre-approval required): [ ] Same Day [ ] 1 Day [ ] 2 Day [ ] 3 Day Other Date Results Requested:
	DW PWSID # or WW Permit # as applicable:
	Field Filtered (if applicable): [ ] Yes [ ] No
	Analysis:

* Matrix Codes (Insert in Matrix box below): Drinking Water (DW), Ground Water (GW), Wastewater (WW), Product (P), Soil/Solid (SS), Oil (OL), Wipe (WP), Tissue (TS), Bioassay (B), Vapor (V), Surface Water (SW), Sediment (SED), Sludge (SL), Caulk (CK), Leachate (LL), Biosolid (BS), Other (OT)

Specify Container Size **: 4oz

**Container Size: (1) 1L, (2) 500mL, (3) 250mL, (4) 125mL, (5) 100mL, (6) 40mL vial, (7) EnCore, (8) TerraCore, (9) 90mL, (10) Other

Identify Container Preservative Type***:

*** Preservative Types: (1) None, (2) HNO3, (3) H2SO4, (4) HCl, (5) NaOH, (6) Zn Acetate, (7) NaHSO4, (8) Sod. Thiosulfate, (9) Ascorbic Acid, (10) MeOH, (11) Other

Analysis Requested: PCBs

Lab Use Only: Proj. Mgr: / AcctNum / Client ID: / Table #: / Profile / Template: / Prelog / Bottle Ord. ID:

Preservation non-conformance identified for sample.

	Customer Sample ID	Matrix *	Comp / Grab	Composite Start Date	Composite Start Time	Collected or Composite End Date	Collected or Composite End Time	# Cont.	Residual Chlorine Result	Residual Chlorine Units	PCBs	Sample Comment
1	SB88-Z00-12-Q	S	G			7.28.25	1140	1			X	
2	SB88-Z12-24	S	G			7.28.25	1142	1			X	
3	SB88-Z24-36	S	G			7.28.25	1143	1			X	
4	SB88-Z36-48	S	G			7.28.25	1144	1			X	
5	SB89-Z00-12	S	G			7.28.25	1134	1			X	
6	SB89-Z12-24	S	G			7.28.25	1135	1			X	
7	SB89-Z24-36	S	G			7.28.25	1136	1			X	
8	SB89-Z36-48	S	G			7.28.25	1137	1			X	
~~9~~	~~SB89-Z48-60~~	~~S~~	~~G~~			~~7.28.25~~	~~1130~~	~~1~~			~~X~~	~~480 7.28~~
~~10~~	~~SB89-Z60-72~~	~~S~~	~~G~~			~~7.28.25~~	~~1131~~	~~1~~			~~X~~	~~d 7.28~~

Additional Instructions from Pace® :

Collected By: Printed Name: Drew Bullinger Signature:

Customer Remarks / Special Conditions / Possible Hazards:

# Coolers:	Thermometer ID:	Correction Factor (°C):	Obs. Temp. (°C):	Corrected Temp. (°C):	[ ] On Ice

	Relinquished by/Company: (Signature)	Date/Time:	Received by/Company: (Signature)	Date/Time:
1	Drew Bullin	7/29/25 1400		7/29/25 1400
2		7/29/25 1700		7/30 1212
3		7/30 2:00	3.8, 3.9	7-30-25 240
4				

Tracking Number:

Delivered by: [ ] In-Person [ ] Courier [ ] FedEX [ ] UPS [ ] Other

Page: 5 of 7

Submitting a sample via this chain of custody constitutes acknowledgment and acceptance of the Pace® Terms and Conditions found at https://www.pacelabs.com/resource-library/resource/pace-terms-and-conditions/

ENV-FRM-CORQ-0019_v02_110123 ©

Table of Contents

East Long Meadow facility 25G-209

Pace® Location Requested (City/State):

CHAIN-OF-CUSTODY Analytical Request Document

Chain-of-Custody is a LEGAL DOCUMENT - Complete all relevant fields

LAB USE ONLY- Affix Workorder/Login Label Here

Scan QR Code for instructions

Company Name: WSP USA
Street Address: 40 La Riviere Dr Suite 320 Buffalo, NY 14202
Customer Project #:
Project Name: Louck Rd Extension
Site Collection Info/Facility ID (as applicable): Site # C734145A

Contact/Report To: Drew Bullinger
Phone #:
E-Mail: Drew.Bullinger@wsp.com
Cc E-Mail:
Invoice to: DEC Lab Callout #: 153133
Invoice E-mail: Karen.Caltill@dec.ny.gov
Purchase Order # (if applicable): DEC Lab Callout # 153133
Quote #:

Time Zone Collected: [ ] AK [ ] PT [ ] MT [ ] CT [X] ET
County / State origin of sample(s): New York

Data Deliverables: [ ] Level II [ ] Level III [ ] Level IV [X] EQUIS [ ] Other
Regulatory Program (DW, RCRA, etc.) as applicable: NYS DEC
Reportable [ ] Yes [ ] No
Rush (Pre-approval required): [ ] Same Day [ ] 1 Day [ ] 2 Day [ ] 3 Day Other
Date Results Requested:
DW PWSID # or WW Permit # as applicable:
Field Filtered (if applicable): [ ] Yes [ ] No
Analysis:

Specify Container Size **: 4oz
**Container Size: (1) 1L, (2) 500mL, (3) 250mL, (4) 125mL, (5) 100mL, (6) 40mL vial, (7) EnCore, (8) TerraCore, (9) 90mL, (10) Other
Identify Container Preservative Type***:
*** Preservative Types: (1) None, (2) HNO3, (3) H2SO4, (4) HCl, (5) NaOH, (6) Zn Acetate, (7) NaHSO4, (8) Sod. Thiosulfate, (9) Ascorbic Acid, (10) MeOH, (11) Other
Analysis Requested: PCBs

Lab Use Only: Proj. Mgr: / AcctNum / Client ID: / Table #: / Profile / Template: / Prelog / Bottle Ord. ID:
Preservation non-conformance identified for sample.

* Matrix Codes (Insert in Matrix box below): Drinking Water (DW), Ground Water (GW), Wastewater (WW), Product (P), Soil/Solid (SS), Oil (OL), Wipe (WP), Tissue (TS), Bioassay (B), Vapor (V), Surface Water (SW), Sediment (SED), Sludge (SL), Caulk (CK), Leachate (LL), Biosolid (BS), Other (OT)

	Customer Sample ID	Matrix *	Comp / Grab	Composite Start Date	Composite Start Time	Collected or Composite End Date	Collected or Composite End Time	# Cont.	Residual Chlorine Result	Residual Chlorine Units	Sample Comment
9	SB91-Z00-12	S	G			7-28-25	1103	1			
10	SB91-Z12-24	S	G			7-28-25	1104	1			
11	SB91-Z24-36	S	G			7-28-25	1105	1			
12	SB91-Z36-48	S	G			7-28-25	1106	1			
13	SB91-Z48-60	S	G			7-28-25	1107	1			
14	SB91-Z48-60-Q	S	G			7-28-25	1109	1			
	SB91-Z60-60.4	S	G			7-28-25	1108	1			HOLD
15	SB90-Z00-12	S	G			7-28-25	1126	1			
16	SB90-Z12-24	S	G			7-28-25	1127	1			
17	SB90-Z24-36	S	G			7-28-25	1128	1			

Additional Instructions from Pace®:

Collected By: Printed Name: Drew Bullinger Signature:

Customer Remarks / Special Conditions / Possible Hazards:

# Coolers:	Thermometer ID:	Correction Factor (°C):	Obs. Temp. (°C):	Corrected Temp. (°C):	[ ] On Ice

Relinquished by/Company: (Signature)	Date/Time:	Received by/Company: (Signature)	Date/Time:
Drew Bullinger	7/29/25 1400		7/29/25 1400
	7/29/25 1700		7/30 1212
	7/30 2:00	3.8, 3.9 7/30/25	7/30 2410
	Date/Time:	Received by/Company: (Signature)	Date/Time:

Tracking Number:
Delivered by: [ ] In-Person [ ] Courier [ ] FedEx [ ] UPS [ ] Other

Page: 6 of 7

Submitting a sample via this chain of custody constitutes acknowledgment and acceptance of the Pace® Terms and Conditions found at https://www.pacelabs.com/resource-library/resource/pace-terms-and-conditions/

ENV-FRM-CORQ-0019_v02_110123 ©

Table of Contents

Pace	DC#_Title: ENV-FRM-ELON-0001 v08_Sample Receiving Checklist
	Effective Date: 06/11/2024

Log In Back-Sheet

Client WSP NYSDEC

Project Louck Rd Extension

MCP/RCP Required N/A

Deliverable Package Requirement N/A

Location NY

PWSID# (When Applicable) N/A

Arrival Method:

Courier ☒ Fed Ex ☐ Walk In ☐ Other ☐

Received By / Date / Time EGR 4/30/25 0240

Back-Sheet By / Date / Time STM 4/30/25 1705

Temperature Method Gun #6

WV samples: Yes (see note*) / (No) follow normal procedure)

Temp ☒ < 6° C Actual Temperature 3.8, 3.9

Rush Samples: Yes / (No) Notify

Short Hold: Yes / (No) Notify

Notes regarding Samples/COC outside of SOP:

Login Sample Receipt Checklist – (Rejection Criteria Listing – Using Acceptance Policy) Any False statement will be brought to the attention of the Client – True or False

	True	False
Received on Ice	☒	☐
Received in Cooler	☒	☐
Custody Seal: DATE TIME	☐	☒
COC Relinquished	☒	☐
COC/Samples Labels Agree	☒	☐
All Samples in Good Condition	☒	☐
Samples Received within Holding Time	☒	☐
Is there enough Volume	☒	☐
Proper Media/Container Used	☒	☐
Splitting Samples Required	☐	☒
MS/MSD	☐	☒
Trip Blanks	☐	☒
Lab to Filters	☐	☒
COC Legible	☒	☐

COC Included: (Check all included)

Client ☒ Analysis ☒ Sampler Name ☐

Project ☒ IDs ☐ Collection Date/Time ☒

All Samples Proper pH: (N/A) ☐ ☐

Additional Container Notes

**Note: West Virginia requires all samples to have their temperature taken. Note any outliers.*

Qualtrax ID: 120836

Quaitrax ID: 120836

Sample	Soils Jars (Circle Amb/Clear)				Ambers						Plastics											VOA Vials					Other / Fill in				
	16oz Amb/Clear	8oz Amb/Clear	4oz Amb/Clear	2oz Amb/Clear	1 Liter		250mL			100mL	1 Liter		500mL		250mL																
					Unpreserved	HCL	Sulfuric	Sulfuric	Phosphoric	HCl	Unpreserved	Unpreserved	Sulfuric	Unpreserved	Sulfuric	Unpreserved	Trizma	Sulfuric	Nitric	NaOH	Ammonium Acetate	NaOH/Zinc	Unpreserved	HCl	MeOH	D.I. Water	Bisulfate	Col/Bact				
1																															
2																															
3																															
4																															
5																															
6																															
7																															
8																															
9																															
10																															
11																															
12																															
13																															
14																															
15																															
16																															
17																															
18																															
19																															
20																															

Pace	DC#_Title: ENV-FRM-ELON-0001 v08_Sample Receiving Checklist
	Effective Date: 06/11/2024