

Periodic Review Report: August 6, 2016 to August 6, 2017 NYSDEC BCP Site No. C828134

Location:

Former Steve Joy's Sunoco
3865 & 3875 West Henrietta Road
Town of Henrietta, New York

Prepared for:

RJ Dorschel Corporation
3817 West Henrietta Road
Rochester, New York 14623

LaBella Project No. 209395

August 2017

Periodic Review Report:
August 6, 2016 to August 6, 2017
NYSDEC BCP Site No. C828134

Location:

Former Steve Joy's Sunoco
3865 & 3875 West Henrietta Road
Town of Henrietta, New York

Prepared for:

RJ Dorschel Corporation
3817 West Henrietta Road
Rochester, New York 14623

LaBella Project No. 209395

August 2017

Table of Contents

	Page
1.0 INTRODUCTION.....	1
1.1 Environmental History.....	1
2.0 PURPOSE AND SCOPE OF WORK.....	3
3.0 ANNUAL MONITORING.....	3
3.1 Groundwater Monitoring.....	4
3.2 Sub-Slab Depressurization System Monitoring.....	5
3.3 Deviations from SMP.....	6
4.0 GROUNDWATER FLOW CONTOURS.....	7
5.0 SUMMARY OF GROUNDWATER MONITORING.....	7
6.0 SITE EVALUATION.....	7
7.0 INSTITUTIONAL AND ENGINEERING CONTROLS CERTIFICATION.....	8

FIGURES

Figure 1	Site Location Map
Figure 2	Site Plan and Surrounding Properties
Figure 3	Groundwater Monitoring Well Locations and Location of Sub-Slab Depressurization Fan
Figure 4A	October 2011 Groundwater Contours
Figure 4B	July 2012 Groundwater Contours

TABLES

Table 1	Groundwater Monitoring Results - VOCs
----------------	---------------------------------------

APPENDICES

Appendix A	Groundwater Sampling Logs
Appendix B	Data Usability Summary Report (DUSR)
Appendix C	August 4, 2017 Site Inspection Form and Photograph
Appendix D	As-Built Drawings of SSDS at 3865 & 3875 West Henrietta Road Buildings
Appendix E	Graphs of Total VOCs over Time
Appendix F	Institutional Controls/Engineering Controls Certification Form

1.0 INTRODUCTION

LaBella Associates, D.P.C. (LaBella) is pleased to submit this Periodic Review Report (PRR) for the Former Steve Joy's Sunoco property located at 3865 and 3875 West Henrietta Road (NYS Route 15) (hereinafter referred to as the "Site") under the New York State (NYS) Brownfield Cleanup Program (BCP) Site #C828134 administered by New York State Department of Environmental Conservation (NYSDEC). The Site was remediated in accordance with Brownfield Cleanup Agreement (BCA) Index #B8-0719-06-06, Site # C828134. A Site Location Map is included as Figure 1.

The Site is located in the Town of Henrietta, County of Monroe, New York and is comprised of the following two (2) parcels of land:

- 3865 West Henrietta Road, an approximate 1-acre parcel identified as Block 161.15-1 and Lot 20.1; and
- 3875 West Henrietta Road, an approximate 1.5-acre parcel identified as Block 161.19-1 and Lot 9.

The Site is improved with the following structures:

- A 4,692[±] square foot building on the 3865 West Henrietta Road parcel; and
- A 12,468 [±] square foot building on the 3875 West Henrietta Road parcel.

The properties surrounding the Site are commercial properties. The properties directly adjacent to the Site and their current occupants are as follows:

- North – 3861 West Henrietta Road, Pizza Hut Restaurant;
- East – West Henrietta Road Right-of-way (ROW), then 3870 West Henrietta Road, Lewis General Tire, Inc.;
- South – 3883 West Henrietta Road, an auto dealership; and
- West – overflow parking lots associated with the 3883 West Henrietta Road property.

A Site Plan (included as Figure 2), illustrates the Site boundaries and the adjacent properties.

1.1 Environmental History

Previous environmental investigations (Pre-BCP work) at the Site identified the nature and extent of contamination to be limited to petroleum contamination in soil, groundwater, and soil vapor. The apparent source of the petroleum impacts was from six (6) petroleum underground storage tanks (USTs) and five hydraulic lifts.

The Pre-BCP and BCP Investigation work at the Site included: advancing 73 soil borings; excavating nine (9) test pits; installing 16 groundwater monitoring wells; the installation of sub-slab soil vapor sampling points; and collecting samples of soil, groundwater, sub-slab vapor, and indoor/outdoor air. Based on the work completed, it was determined that the predominant contaminants at the Site were petroleum-related volatile organic compounds (VOCs) in soil and groundwater.

Petroleum-related semi-volatile organic compounds (SVOCs), chlorinated solvents, and metals were also detected in groundwater, along with a limited area of metals in surface soils. Based on these findings, the following specific areas of contamination were identified:

- Petroleum impacted soil and groundwater between the 3865 Parcel Building and West Henrietta Road, in the area of the former pump islands, was identified at concentrations above the NYSDEC Part 375-6 Restricted Commercial Use Soil Cleanup Objectives and the NYSDEC Part 703 Groundwater Standards;
- Petroleum impacted soil directly north of the central portion of the 3875 Building associated with a UST was identified in the field as impacted;
- Petroleum impacts in soil around hydraulic lifts within the western portion of the 3875 Building was identified in field observations;
- An area of surface soils along West Henrietta Road impacted with the metals (arsenic and barium) was identified at concentrations above the NYSDEC Part 375-6 Restricted Commercial Use Soil Cleanup Objectives;
- Concentrations of VOCs in the sub-slab soil vapor and indoor air at both buildings at the Site were identified; and
- VOCs and metals in groundwater on the 3875 Parcel were identified at concentrations above the NYSDEC Part 703 Groundwater Standards.

The Remedial Measures completed at the Site have included two (2) Interim Remedial Measures (IRMs) consisting of the removal of USTs and soil. The soil removed during the IRM was transported to an off-site location for treatment in a bio-cell. In addition, a final remedy at the Site consisted of the removing hydraulic lifts, soil and groundwater. The remedies and Areas of Concern (AOC) designation from the Remedial Action Work Plan (RAWP) are summarized below:

- Removal and bioremediation of approximately 1,740 cubic yards of petroleum-impacted soils from AOC #1. This resulted in removing all soils above the NYSDEC Part 375-6.8(b) Protection of Groundwater SCOs with the exception of two areas due to underground utilities, the West Henrietta Road ROW and the on-site building.
- Removal and disposal of six underground storage tanks and their contents, which consisted of approximately 8,000 gallons of petroleum impacted waters and 600 gallons of waste oil.
- Removal and disposal of five hydraulic lifts (AOC #2) and removal and off-site disposal of approximately 85 tons of petroleum impacted soil from seven hydraulic lift locations (i.e., 2 former locations and the 5 lifts removed as part of this project).
- Removal and disposal of a 5-ft. by 5-ft. area to 1-ft. in depth of surface soils impacted with heavy metals. The heavy metals were identified during the RI in surface soil sample SS-1 located along the eastern edge of the 3865 West Henrietta property boundary and was identified as AOC #5.
- Installation of a sub-slab depressurization system (SSDS) to mitigate the potential for vapor intrusion within (AOC #3) the existing building at the 3865 West Henrietta Road parcel. Pressure field extension testing was completed on each of the monitoring points after the installation of the SSDS, and confirmed the system influences the entire slab area. An SSDS was also installed at the 3875 Parcel building during redevelopment of the Mini Cooper dealership in 2012.

- An Environmental Easement was executed and recorded to restrict land use and prevent future exposure to any contamination remaining at the Site.
- Development and implementation of a Site Management Plan (SMP) for long term management of remaining contamination as required by the Environmental Easement, which includes plans for: (1) Institutional and Engineering Controls, (2) monitoring, (3) operation and maintenance and (4) reporting.

2.0 PURPOSE AND SCOPE OF WORK

The purpose of this report is to present the monitoring work completed at the Site during the time period of August 6, 2016 to August 6, 2017. This work was completed in general accordance with the provisions identified in the SMP. As required in the SMP, this report includes the following information:

- Identification, assessment and certification of all Engineering Controls/Institutional Controls (ECs/ICs) required by the remedy for the Site;
- Results of the required annual site inspections and severe condition inspections, if applicable;
- All applicable inspection forms and other records generated for the Site during the reporting period in electronic format (included in report);
- A summary of any discharge monitoring data and/or information generated during the reporting period with comments and conclusions;
- Data summary tables and graphical representations of contaminants of concern by media, including: a list of all compounds analyzed; applicable regulatory standards, with all exceedances highlighted; and a presentation of past data as part of an evaluation of contaminant concentration trends;
- Results of all analyses, copies of all laboratory data sheets, and the required laboratory data deliverables for all samples collected during the reporting period will be submitted electronically in a NYSDEC-approved format;
- A Site evaluation, which includes the following:
 - The compliance of the remedy with the requirements of the Site-specific RAWP;
 - Any new conclusions or observations regarding Site contamination based on inspections or data generated by the Monitoring Plan for the media being monitored;
 - Recommendations regarding any necessary changes to the remedy and/or Monitoring Plan; and
 - The overall performance and effectiveness of the remedy.

3.0 ANNUAL MONITORING

The original SMP identified the ongoing monitoring of the performance of the remedy, via semi-annual sampling of two (2) existing groundwater monitoring wells (3865 Parcel: MW-7 and 3875 Parcel: MW-3R). The original SMP indicated that monitoring the overall reduction in contamination on-site would be conducted for the first two (2) years, with the frequency thereafter to be determined by NYSDEC. The NYSDEC approved annual monitoring of the two (2) wells for VOCs only in a letter dated July 22, 2013. Trends in contaminant levels in groundwater in the affected areas will be evaluated to determine if the remedy continues to be effective in achieving remedial goals.

The original SMP also required a semi-annual inspection of the SSDS and semi-annual monitoring of the biocell soils. In their July 22, 2013 letter, the NYSDEC also approved discontinuing monitoring of the biocell soils.

The current monitoring program is summarized in the following table and was included in the June 2014 SMP update.

Schedule of Monitoring/Inspections

Monitoring Program	Frequency*	Matrix	Analysis
Groundwater Monitoring	Annual	Groundwater	1) VOCs using USEPA Method 8260 (NYSDEC STARS-list for 3865 parcel wells and TCL VOCs for 3875 parcel wells)
Sub-Slab Depressurization System Inspection	Annual	Sub-Slab Vapor	None

* The frequency of events will be conducted as specified until otherwise approved by NYSDEC and NYSDOH

3.1 Groundwater Monitoring

Groundwater monitoring for this PRR was conducted in June 2017. Monitoring wells MW-3R (replacement well) and MW-7 were sampled on June 16, 2017 and June 17, 2016, respectively. The locations of these wells are shown on Figure 3.

Static water levels (SWLs) were collected during the June 2017 groundwater sampling event. The groundwater samples were collected using a modified low-flow sampling procedure with a peristaltic pump. During the sampling event, disposable tubing was utilized between wells, and, as such, decontamination of equipment was not required.

During the sampling event, field measurements of water quality parameters were collected using a Horiba U-52-2 water quality meter equipped with an in-line flow cell. During the sampling event, the following field measurements were collected:

- pH
- Conductivity
- Temperature
- Oxygen Reduction Potential (ORP)
- Turbidity
- Dissolved Oxygen (DO)

During the sampling event, water quality parameter readings were recorded at regular time intervals prior to the collection of groundwater samples. Water quality stabilization criteria are summarized in the following table.

Measurement	Maximum Variability for 3 Consecutive Readings
pH	+/- 0.1 standard units
Conductivity	+/- 3 %
Oxidation Reduction Potential	+/- 10 mV
Turbidity	+/- 10 %
Dissolved Oxygen	+/- 10 %

During the sampling event, the required criteria were met prior to sample collection at MW-3R. In addition, the SWL in MW-3R was monitored during the sampling event to confirm that drawdown in the well was minimized.

Due to limited water volume in MW-7, on June 16, 2017 MW-7 was purged “dry”, and the well was allowed to recharge overnight. A groundwater sample was collected from MW-7 on the afternoon of June 17, 2017.

Groundwater sampling logs that include the in-field parameter measurements are included as Appendix A.

Environmental Science Corporation of Mt. Juliet, Tennessee (ESC) analyzed the groundwater samples collected during the groundwater monitoring event. ESC is a New York State Department of Health (NYSDOH) Environmental Laboratory Approval Program (ELAP) certified laboratory. The samples were analyzed for NYSDEC CP-51-list and United States Environmental Protection Agency (USEPA) Target Compound List (TCL) VOCs using USEPA Method 8260.

The laboratory data from the groundwater monitoring event were reported in an Analytical Services Protocol (ASP) Category B Deliverable and a Data Usability Summary Report (DUSR) was prepared for the data. The DUSR is included as Appendix B. As previously requested by the NYSDEC, the ASP Category B laboratory analytical report will be provided separately.

3.2 Sub-Slab Depressurization System (SSDS) Monitoring

This section discusses the SSDS monitoring performed on August 4, 2017 in the two (2) on-site buildings.

3865 West Henrietta Road Building

The SSDS in the 3865 West Henrietta Road building was monitored on August 4, 2017 in order to verify proper operation of the system. Because the manometer installed on this SSDS is now located within the wall of the women’s restroom and is accessible via a removable wall panel, NYSDEC requested in October 2015 that an alarm be installed on the SSDS. The purpose of the alarm is to monitor proper operation of the SSDS; this alarm was installed in late 2015.

The location of the SSDS venting point/fan that operates the SSDS for the 3865 Building is shown on

Figure 3, and an as-built drawing of the SSDS is included in Appendix D. At the fan location, the following inspections were made:

- the in-line U-tube manometer on the suction side of the piping system was observed to determine a pressure differential of approximately 2.5 inches of water column which is consistent with historic readings and indicates the SSDS is operating properly;
- the condition of the piping was observed to determine if any portion of the piping required repair;
- the fan was working properly; and
- labeling of the system was intact.

Based upon the inspections, the SSDS appeared to be in good working order (i.e., the manometer indicated the SSDS was working, the fan was observed to be working, and the piping appeared in good condition). Copies of the inspection form and a photograph from the inspection are included in Appendix C.

3875 West Henrietta Road Building

The SSDS in the 3875 West Henrietta Road building was monitored on August 4, 2017 in order to verify proper operation of the system. The SSDS for the 3875 Building is shown in the as-built drawings included in Appendix D. At the fan location, the following inspections were made:

- the sub-slab monitoring points were measured with a digital micro-manometer to determine a pressure differential between the sub-slab and indoor air. The results of this monitoring are summarized in the following table;

Location	August 4, 2017 Monitoring Event	
	Valve 1 Measurement (inches of H ₂ O)	Valve 2 Measurement (inches of H ₂ O)
Northern Point (customer reception)	- 0.612	- 0.060
Southern Point (service area)	- 0.171	- 0.007

- the condition of the piping was observed to determine if any portion of the piping required repair;
- the fan was working properly; and
- labeling of the system was intact.

Based upon the inspections, the SSDS appeared to be in good working order (i.e., the micro-manometer readings indicated the SSDS was working, the fan was observed to be working, and the piping appeared in good condition). A copy of the inspection form is included in Appendix C.

3.3 Deviations from SMP

No deviations were encountered during this monitoring period.

4.0 GROUNDWATER FLOW CONTOURS

Although static water level measurements were collected during the June 2017 groundwater monitoring event, this sampling event included only two (2) monitoring wells. Historic monitoring information previously presented to the NYSDEC describes the groundwater flow regime at the Site. For informational purposes, groundwater contour maps from October 2011 and July 2012 are included as Figures 4A and 4B, respectively.

5.0 SUMMARY OF GROUNDWATER MONITORING

Groundwater monitoring was performed in June 2017 and included two (2) existing groundwater monitoring wells (3865 Parcel: MW-7 and 3875 Parcel: MW-3R), as shown on Figure 3.

The results of the groundwater monitoring are summarized in Table 1 (VOCs) and are compared to the NYSDEC Part 703 groundwater standards. As summarized in the attached Table 1 and the following table, VOCs were reported above NYSDEC Part 703 groundwater standards in the groundwater samples collected during the June 2017 groundwater monitoring event.

Well ID	Site Parcel	VOC(s) above Part 703 Groundwater Standards
MW-7	3865 Parcel	Benzene; Ethylbenzene; n-Propylbenzene; Isopropylbenzene; Naphthalene; Toluene; 1,2,4-Trimethylbenzene; 1,3,5-Trimethylbenzene; Xylenes; Chlorobenzene; and Cyclohexane
MW-3R	3875 Parcel	Chlorobenzene

6.0 SITE EVALUATION

The annual monitoring work conducted from August 6, 2016 to August 6, 2017 was completed in accordance with the SMP, with any exceptions noted in Section 3.3.

Groundwater Monitoring

Most of the previously existing groundwater monitoring wells at the Site have been destroyed or paved over during the redevelopment activities at the Site.

The analytical results from the June 2017 groundwater sampling event indicates that VOC concentrations appear stable in MW-7 and MW-3R, as shown in the graphs included in Appendix E. In addition, with regard to MW-3R, the reported VOC concentrations are relatively low-level, and only Chlorobenzene exceeds its associated Part 703 Groundwater Standard.

Based on the above, no changes to the current monitoring program are proposed.

The remedial program outlined in the SMP has effectively achieved progress toward meeting the remedial


objectives for the Site. Continued monitoring of the SSDS and the implementation of the SMP should ultimately achieve the remedial objectives for the Site. The next groundwater sampling event is scheduled for Spring 2018.

7.0 INSTITUTIONAL AND ENGINEERING CONTROLS CERTIFICATION

The completed NYSDEC Institutional and Engineering Controls Certification Form is included in Appendix F.

J:\RJ DORSCHER CORP\209395 - 3865 3875 W HENRIETTA RD REM ACT\REPORTS\2017 PRR\RPT_2017_08_14_ Periodic Review Report_RJ Dorschel.docx

FIGURES



PROJECT DRAWING NUMBER [209395] [FIGURE 1]	SITE LOCATION MAP 1:24,000 <table border="1"> <tr> <td>DESIGNED FOR</td> <td>DESIGNED BY</td> <td>RCN</td> </tr> <tr> <td>REVIEW</td> <td>DRAWN BY</td> <td>RCN</td> </tr> <tr> <td>DATE: 8/28/09</td> <td>DATE: 8/28/09</td> <td>DPN</td> </tr> </table>	DESIGNED FOR	DESIGNED BY	RCN	REVIEW	DRAWN BY	RCN	DATE: 8/28/09	DATE: 8/28/09	DPN	SITE MANAGEMENT PLAN BCP SITE #C8281324 3865 & 3875 WEST HENRIETTA RD ROCHESTER, NY 14623	LABELLA Associates, P.C. 300 STATE STREET ROCHESTER, NY 14614 P: (585) 454-6110 F: (585) 454-3066 www.labellappc.com COPYRIGHT 2010
DESIGNED FOR	DESIGNED BY	RCN										
REVIEW	DRAWN BY	RCN										
DATE: 8/28/09	DATE: 8/28/09	DPN										

Y:\R\J Dorschel Corp\209395\Drawings\PRR 2011\Fig2 Site Area Map.mxd




LABELLA
Associates, P.C.

200 STATE STREET
ROCHESTER, NY 14614
P: (585) 454-6110
F: (585) 454-3086
www.labellacorp.com
C0191012221

Periodic Review Report
NYSDEC BCP Site #C8281324
3865 & 3875 West Henrietta Rd
Henrietta, New York

R.J. Dorschel Corporation

Site Plan and Surrounding
Properties



[209395]



[FIGURE 2]




Periodic Review Report
NYSDEC BCP Site #C8281324
3865 & 3875 West Henrietta Rd
Henrietta, New York

R.J. Dorschel Corporation

Groundwater Monitoring Well Locations and Location of Sub-Slab Depressurization Fan




Y:\RJ Dorschel Corp\209395\Drawings\PRR 2011\Fig5B Groundwater Contour Oct 2010.mxd



**Periodic Review Report
NYSDEC BCP Site #C8281324
3865 & 3875 West Henrietta Rd
Henrietta, New York**

R.J. Dorschel Corporation

**July 2012
Groundwater Contours
and Site Location Plan**



0 510 20
1 inch = 40 feet

209395
FIGURE 4B

TABLE 1

Groundwater Monitoring Results - VOCs

Table 1

Groundwater Monitoring
3865 & 3875 West Henrietta Road, Henrietta, New York
NYSDEC Brownfield Cleanup Program ID No. C828134

Summary of Detected Volatile Organic Compounds (VOCs) in Groundwater
Test Results in Micrograms per Liter (µg/L) or Parts Per Billion (ppb)

Constituent	3865 Parcel												3875 Parcel										NYSDEC Part 703: Groundwater Standard
	MW-7												MW-3R										
	September 2006	May 2007	June 2010	October 2010	May 2011	October 2011	July 2012	March 2014	May 2015	October 2015	June 2016	June 2017	May 2007	June 2010	October 2010	May 2011	October 2011	April 2014	May 2015	October 2015	June 2016	June 2017	
Petroleum-Related Volatile Organic Compounds																							
Benzene	370	410	740 E	750 D	ND<5.0	730	870	1,150	1,200	816	848	675	ND<5.0	2.3 J	2.8 J	3.1 J	31.7	ND<0.7	ND<50	ND<1.00	ND<1.00	ND<1.00	1
Ethyl ether	---	---	---	---	---	---	---	---	---	---	---	---	---	---	---	---	ND<1.0	---	ND<1.0	---	---	---	Not Available
Ethylbenzene	880	790 E	250 E	620 D	ND<5.0	266	610	1050	950	786	258	332	ND<5.0	ND<5.0	ND<5.0	ND<5.0	5.2	ND<2.0	ND<1.0	ND<1.00	ND<1.00	ND<1.00	5
sec-Butylbenzene	ND <50	23	3 J	5.6	ND<5.0	ND<100	11	ND<40.0	7.7	7.89	6.29	ND<10.0	ND<5.0	ND<5.0	ND<5.0	ND<5.0	ND<1.0	ND<2.0	ND<1.0	ND<1.00	ND<1.00	ND<1.00	5
n-Propylbenzene	ND <50	260 E	13	36	ND<5.0	ND<100	86	108	110	89.1	18.2	22.0	ND<5.0	ND<5.0	ND<5.0	ND<5.0	ND<1.0	ND<2.0	ND<1.0	ND<1.00	ND<1.00	ND<1.00	5
Isopropylbenzene	78	91	13	33	ND<5.0	ND<100	44	49.9	49	43.0	21.0	18.3	ND<5.0	ND<5.0	ND<5.0	ND<5.0	ND<1.0	ND<2.0	ND<1.0	ND<1.00	ND<1.00	ND<1.00	5
p-Isopropyltoluene	ND <50	22	ND<5.0	---	ND<5.0	ND<100	ND<5.0	ND<40.0	7.1	7.27	6.71	ND<10.0	ND<5.0	ND<5.0	ND<5.0	ND<5.0	ND<1.0	ND<2.0	ND<1.0	ND<1.00	ND<1.00	ND<1.00	5
n-Butylbenzene	---	---	---	---	---	ND<100	32	28.8 J	12	11.0	4.16	ND<10.0	---	---	---	---	---	ND<2.0	ND<1.0	ND<1.00	ND<1.00	ND<1.00	5
Napthalene	ND <50	1,100 E	240 BE	330 DJ	ND<5.0	419	480	478	600	423	620	642	ND<5.0	1.4 BJ	ND<5.0	ND<5.0	ND<1.0	ND<5.0	ND<5.0	ND<5.00	ND<5.00	ND<5.00	10
Toluene	980 D	690 E	260 E	180	ND<5.0	106	35	156	120	73.9	71.9	67.6	ND<5.0	ND<5.0	ND<5.0	ND<5.0	1.7	ND<2.0	ND<5.0	ND<5.00	ND<5.00	ND<1.00	5
1,2,4-Trimethylbenzene	ND <50	1,100 E	620 E	730 D	ND<5.0	1,400	1,200	1,390	1,300	1,380	1,540	1,750	ND<5.0	ND<5.0	ND<5.0	ND<5.0	ND<1.0	ND<2.0	1.3	ND<1.00	ND<1.00	ND<1.00	5
1,3,5-Trimethylbenzene	ND <50	630 E	210 E	190 DJ	ND<5.0	422	320	322	200	196	197	290	ND<5.0	ND<5.0	ND<5.0	ND<5.0	ND<1.0	ND<2.0	ND<1.0	ND<1.00	ND<1.00	ND<1.00	5
m,p-Xylene	ND <50	2,100 E	2,300 E	4,700 D	ND<5.0	6,190	2,800	4,190	2,900	2,620	3,220	3,610	ND<5.0	ND<5.0	ND<5.0	ND<5.0	2.2	ND<2.0	2.1	ND<2.00	ND<2.00	ND<2.00	5
o-Xylene	ND <50	760 E	450 E	690 D	ND<5.0	502	35	363	230	143	332	319	ND<5.0	ND<5.0	ND<5.0	ND<5.0	3.9	ND<2.0	ND<1.0	ND<1.00	ND<1.00	ND<1.00	5
Tert-amyl methyl ether	---	---	---	---	---	---	---	---	---	---	---	---	---	---	---	---	3.4	---	---	---	---	---	Not Available
Tert-butanol / butyl alcohol	---	---	---	---	---	---	---	---	---	---	---	---	---	---	---	---	12.8	---	---	---	---	---	Not Available
Methyl-tert-Butyl Ether	ND <10	ND<5	2.4 J	2.4 J	5.6	ND<100	18	ND<40.0	ND<1.0	ND<1.0 U	ND<1.00	ND<10.0	2 J	ND<5.0	ND<5.0	1.2 J	22.5	2.97	2.5	1.56	2.25 J	1.35	10
Solvent-Related Volatile Organic Compounds																							
Acetone	40 J	ND<5	Not Tested	Not Tested	Not Tested	Not Tested	Not Tested	ND<200	140	ND <50.0	ND <50.0	ND <500	ND<5.0	42	Not Tested	ND<5.0	ND<10.0	ND<10.0	ND<50	ND <50.0	ND <50.0	ND <50.0	50
2-Butanone	ND<50	ND<5						ND<200	ND<10	ND <10.0	ND <10.0	ND <100	ND<5.0	8.1		ND<5.0	ND<10.0	ND<10.0	ND<10	ND <10.0	ND <10.0 R	ND <10.0	50
Cyclohexane	140	ND<5						190 J	100	113	82.3 R	79.5	ND<5.0	ND<5.0		ND<5.0	Not Tested	ND<10.0	ND<1.0	ND<1.00	ND<1.00	ND<1.00	5
Chlorobenzene	ND<50	ND<5						ND<40.0	ND<1.0	ND<1.00	ND<1.00	ND<10.0	11 J	3.9 J		---	ND<1.0	67.3	120	106	103 J	130	5
Dichlorodifluorormethane	---	---						ND<40.0	ND<5.0	ND<5.00	ND<5.00	ND<50.0	---	---		---	ND<2.0	ND<2.0	ND<5.0	ND<5.00	ND<5.00 J0	ND<5.00	5
1,2-Dichlorobenzene	ND<50	ND<5						ND<40.0	ND<1.0	ND<1.00	ND<1.00	ND<10.0	ND<5.0	ND<5.0		ND<5.0	ND<10.0	1.4	2.7	2.42	2.41 J	2.80	5
cis-1,2-Dichloroethene	ND<50	ND<5						ND<40.0	ND<1.0	ND<1.00	ND<1.00	ND<10.0	1 J	ND<5.0		4.4 J	ND<1.0	ND<2.0	ND<1.0	ND<1.00	ND<1.00	ND<1.00	5
1,1-Dichloroethane	ND<50	ND<5						ND<40.0	ND<1.0	ND<1.00	ND<1.00	ND<10.0	1 J	ND<5.0		ND<5.0	1.2	ND<2.0	1.2	ND<1.00	1.24 J	ND<1.00	5
Methylcyclohexane	59	ND<5						63.2	120	ND<20 U	27.6 R	44.8 U	ND<5.0	ND<5.0		ND<5.0	Not Tested	ND<2.0	ND<1.0	ND<1.00	ND<1.00 R	ND<1.00	5
Methylene Chloride	ND<36	ND<5						ND<100	ND<5.0	ND<5.00	ND<5.00	ND<50.0	ND<5.0	ND<5.0		ND<5.0	ND<2.0	ND<5.0	ND<5.0	ND<5.00	ND<5.00	ND<5.00	5
trans-1,2-Dichloroethene	ND<50	ND<5						ND<40.0	ND<1.0	ND<1.00	ND<1.00	ND<10.0	ND<5.0	ND<5.0		ND<5.0	ND<1.0	ND<2.0	ND<1.0	ND<1.00	ND<1.00	ND<1.00	5
Vinyl Chloride	ND<50	ND<5						ND<40.0	ND<1.0	ND<1.00	ND<1.00	ND<10.0	3 J	ND<5.0		---	1.8	ND<2.0	ND<1.0	ND<1.00	ND<1.00	ND<1.00	2
Total VOCs	2,547	7,976	5,101	8,267 D,J	5.6	10,035	6,541	9,286	8,046	6,709	7,143.26	7,805.40	18	57.7	2.8 J	24.1 J	86.4	71.67	129.8	109.98	108.90	134.15	Not Available
Total VOC TICs	9,980	5,795	Not Tested	Not Tested	Not Tested	Not Tested	Not Tested	Not Tested	Not Tested	Not Tested	Not Tested	Not Tested	ND	ND	Not Tested	Not Tested	Not Tested	Not Tested	Not Tested	Not Tested	Not Tested	Not Tested	
Total VOCs and VOC TICs	12,527	13,771	5,101	8,267	5.6	10,035	6,541	9,286	8,046	6,709	7,143.26	7,805.40	18	57.7	2.8	24.1	86.4	71.7	129.8	109.98	108.9	134.15	

Notes:
VOC analysis by USEPA Method 8260B TCL.
Bold Type denotes that the detected value exceeds its associated NYSDEC Part 703 Groundwater Standard.
ND<5.0 denotes compound not detected above the method detection limits.
J denotes an estimated value; the analyte was positively identified, but the associated numerical value is the approximate concentration of the analyte in the sample.
J0 denotes that the laboratory's calibration verification was outside of acceptance limits. Result is estimal
D denotes that the compound was identified in a secondary dilution performed on the sample.
E denotes that the concentration of the compound was found to exceed the calibration range for the instrument.
U is a data qualifier indicating that during data validation, it was determined that the concentration reported by the laboratory should be "interpreted as undetected."
R is a data qualifier indicating that during data validation, it was determined that the concentration reported by the laboratory should be "rejected".

APPENDIX A

Groundwater Sampling Logs



300 State Street
Rochester, New York 14614

Telephone: (585) 454-6110

Facsimile: (585) 454-3066

WELL I.D.: MW-3R

Project Name: RJ Dorschel Groundwater Monitoring

Location: 3865 & 3875 West Henrietta Road

Project No.: 209395

Sampled By: K R Miller

Date: 6/16/2017

Weather: Sunny 80° F

WELL SAMPLING INFORMATION

Well Diameter: 2-inch

Depth of Well: 15 feet

Measuring Point: Top of Casing (TOC)

Pump Type: Geopump – Peristaltic

Static Water Level: 2.38 feet Below Top of Casing (BTOC)

Length of Well Screen: 5 feet

Depth to Top of Pump: Tubing inlet ±12.5 BTOC

Tubing Type: Poly

FIELD PARAMETER MEASUREMENT

Time	Pump Rate (L/min)	Gallons Purged	pH	Temp °C	Conductivity (μS/cm)	Turbidity (NTU)	Dissolved O ₂ (mg/L)	Redox (mV)	Depth to Water (ft. BTOC)	Comments
			+/- 0.1		+/- 3%		+ 10%	+/- 10 mV		
										Flow thru cell filling
16:50	<0.2		6.51	24.68	3.31	28.7	4.42	11		
16:55			6.48	22.96	3.36	19.9	6.23	17	4.06	
17:00			6.46	22.39	3.44	20.5	6.01	21		
17:05			6.46	22.24	3.44	18.3	5.91	-7	5.05	
17:10			6.45	22.28	3.44	15.3	5.74	27	5.50	
17:15			6.45	22.71	3.41	14.4	5.59	29	5.50	
17:20			6.46	22.37	3.37	11.2	5.69	26	5.55	

Total ±1.5 Gallons Purged

Purge Time Start: 16:48

Purge Time End: 17:20

Final Static Water Level: 5.55 feet BTOC

OBSERVATIONS

No odor or sheen observed in connection with purged groundwater.

Groundwater sample collected 6/16/2017 at 17:25; two (2) 40-mL, HCl-preserved VOA containers filled and submitted for laboratory analysis.



300 State Street
Rochester, New York 14614

Telephone: (585) 454-6110

Facsimile: (585) 454-3066

WELL I.D.: MW-7

Project Name: RJ Dorschel Groundwater Monitoring

Location: 3865 & 3875 West Henrietta Road

Project No.: 209395

Sampled By: K R Miller

Date: 6/16/2017 & 6/17/2017

Weather: Sunny 80° F

WELL SAMPLING INFORMATION

Well Diameter: 1 inch

Depth of Well: 7.5 feet

Measuring Point: Top of Casing (TOC)

Pump Type: Geopump - Peristaltic

Static Water Level: 1.80 feet Below Top of Casing (BTOC)

Length of Well Screen: 5 feet

Depth to Top of Pump: Tubing inlet ±6 BTOC

Tubing Type: Poly

FIELD PARAMETER MEASUREMENT

Time	Pump Rate (L/min)	Gallons Purged	pH	Temp °C	Conductivity (µS/cm)	Turbidity (NTU)	Dissolved O ₂ (mg/L)	Redox (mV)	Depth to Water (ft. BTOC)	Comments
			+/- 0.1		+/- 3%		+ 10%	+/- 10 mV		
19:10	<0.2									Flow thru cell filling
19:13			6.71	26.04	1.16	78.4	1.54	-80		Cannot measure depth to water, well diameter is too small.
19:18			6.57	19.36	1.32	63.4	0.98	-72		

Total ±0.1 Gallons Purged

Purge Time Start: 19:10

Purge Time End: 19:21

Final Static Water Level: N/A

OBSERVATIONS

Slight petroleum odor noted in connection with purged groundwater. Well purged "dry" on 6/16/2017, and was allowed to recharge overnight. Groundwater sample was collected on 6/17/2017 at 14:00; two (2) 40-mL, HCl-preserved VOA containers filled and submitted for laboratory analysis.

APPENDIX B

Data Usability Summary Report (DUSR)

DATA USABILITY SUMMARY REPORT

for

LABELLA ASSOCIATES, P.C.

300 State Street

Rochester, NY 14614

3865 & 3875 WEST HENRIETTA ROAD

Project 209395

SDG: L917097

Sampled 6/16/2017 and 6/17/17

VOLATILE ORGANICS

MW-3R (L917097-01)

MW-7 (L917097-02)

DATA ASSESSMENT

An ASP Category B data package containing analytical results for two groundwater samples was received from Labella Associates, P.C. on 04Aug17. The deliverables package included formal reports, raw data, the necessary QC, and supporting information. The samples, taken from the 3865 and 3875 West Henrietta Road site, were identified by Chain of Custody documents and traceable through the work of ESC Lab Sciences, the laboratory contracted for analysis. Analyses, performed according to SW-846 Method 8260C, addressed determinations of volatile organics. Laboratory data was evaluated according to the quality assurance / quality control requirements of the New York State Department of Environmental Conservation's Analytical Services Protocol (ASP), September 1989, Rev. 07/2005. When the required protocol was not followed, the current EPA Region II Functional Guidelines (SOP NO. HW-33, Rev. #3, March 2013, Low/Medium Volatile Data Validation) was used as a technical reference.

The trichloroethene and bromomethane results from this group of samples have been qualified as estimations due to poor calibration performance.

The presence of methylcyclohexane in MW-7 could not be verified based on the mass spectra references included in the raw data. Methylcyclohexane should be interpreted as undetected in this sample.

CORRECTNESS AND USABILITY

Reported data should be considered technically defensible and completely usable in its present form. Results presenting a usable estimation of the conditions at the time of sampling have been flagged "U" or "UJ". Estimated data should be used with caution. A detailed discussion of the review process follows.

Two facts should be considered by all data users. No compound concentration, even if it has passed strict QC testing, can be guaranteed to be accurate. Strict QC serves to increase confidence in data, but any value potentially contains error. Secondly, DATAVAL, Inc. guarantees the quality of this data assessment. However, DATAVAL, Inc. does not warrant any interpretation or utilization of this data by a third party.

Reviewer's signature:


James B. Baldwin
DATAVAL Inc.

Date: 09Aug17

SAMPLE HISTORY

Analyte concentrations can deteriorate with time due to chemical instability, bacterial degradation, or volatility. Samples that are not properly preserved or are not analyzed within established holding times may no longer be considered representative. Holding times are calculated from the time of sample collection. Samples must remain chilled to $4 \pm 2^\circ\text{C}$ between the time of collection and the time of analysis. Acid preserved VOC samples must be analyzed within 14 days, unpreserved VOC samples within 7 days. The holding time for VOC soils is 14 days. Aqueous semivolatile organics, pesticide and PCB samples must be extracted within seven days of collection. Soils must be extracted within 14 days. The extracts must then be analyzed within forty days of extraction. The holding times for cyanide and mercury samples are 14 and 28 days, respectively. Metals samples must be analyzed within six months.

This delivery group contained two groundwater samples that were collected from the 3865 and 3875 West Henrietta Road Site on 16Jun17 and 17Jun17. The samples were shipped to the laboratory, via FedEx, on 19Jun17 and were received the following morning. At the time of receipt, the sample cooler was found to be intact and properly chilled, with custody seals in place. A cooler temperature of 2.3°C was recorded at the time of receipt. Proper sample preservation was documented in the field custody record and verified at the time of analysis. These checks verified that both program samples were properly stabilized at a $\text{pH} < 2$.

VOLATILE ORGANICS

This group of samples was analyzed for VOC 25Jun17. The SW-846 holding time requirements were satisfied.

Blanks

Blanks are analyzed to evaluate various sources of sample contamination. Field blanks monitor sampling activities. Method blanks are analyzed to verify instrument integrity. Samples are considered compromised by conditions causing contamination in any blank.

One method blank was analyzed with this group of samples. This blank demonstrated acceptable chromatography and was free of targeted analyte contamination exceeding the laboratory's reporting limit.

MS Tuning

Mass spectrometer tuning and performance criteria are established to ensure sufficient mass resolution and sensitivity to accurately detect and identify targeted analytes. Verification is accomplished using a certified standard.

An Instrument Performance Check Standard of BFB was analyzed prior to each analytical sequence that included samples from this program. An Instrument Performance Check Form is present for each BFB evaluation. The BFB tunes associated with the analysis of this group of samples satisfied the program acceptance criteria.

Calibrations

Requirements for instrument calibration are established to ensure that laboratory equipment is capable of producing accurate, quantitative data. Initial calibrations demonstrate a range through which measurements may be made. Continuing calibration check standards verify instrument stability.

The initial instrument calibration was performed on 19Jun17. Calibration standards of 0.25, 0.50, 1.0, 2.0, 5.0, 10, 25, 40, 75, 100 and 200 µg/l were included. With the exception of trichloroethene, each targeted analyte produced the required levels of instrument response and demonstrated an acceptable degree of linearity during this calibration. Trichloroethene standards, however, failed to produce the required levels of instrument response. The trichloroethene (TCE) results from MW-3R and MW-7 have been qualified as estimations based on this performance.

A calibration check standard was analyzed on 25Jun17, prior to the 12-hour period of instrument operation that included samples from this program. When compared to the initial calibration, an unacceptable shift was observed in the instrument response of bromomethane (27%). The bromomethane results from both program samples have been qualified as estimations based on this performance. It is noted that the response of trichloroethene remained low.

Surrogates

Each sample, blank and standard is spiked with surrogate compounds prior to analysis. The structures of surrogates are similar to analytes of interest, but they are not normally found in environmental samples. Surrogate recoveries are monitored to evaluate overall laboratory performance and the efficiency of laboratory technique.

Surrogate Summary Sheets were properly prepared, based on the laboratory's statistical acceptance criteria. When compared to the ASP requirements, however, an acceptable recovery was reported for each surrogate addition to this group of samples.

Internal Standards

Internal standards are added to each sample, blank and standard just prior to injection. Analyte concentrations are calculated relative to the response of a specific internal standard. Internal standard performance criteria ensure that GC/MS sensitivity and response are stable during the analysis of each sample. The area of internal standard peaks may not vary by more than a factor of

two. When compared to the preceding calibration check, retention times may not vary by more than 30 seconds.

The laboratory correctly calculated control limits for internal standard response and retention times. When compared to this criteria, acceptable performance was demonstrated by each internal standard addition to this group of samples.

Matrix Spikes

Matrix spiking refers to the addition of known analyte concentrations to a sample, prior to analysis. Analyte recoveries provide an indication of laboratory accuracy. The analysis of a duplicate spiked aliquot provides a measurement of precision.

Although a sample from this project was not selected for matrix spiking, a pair of spiked blanks (LCS/LCSD) was analyzed with this group of samples. The recoveries reported from this LCS pair demonstrated acceptable levels of measurement precision and accuracy.

Duplicates

Two aliquots of the same sample are processed separately through all aspects of sample preparation and analysis. The results produced by the analysis of this pair of samples are compared as a measurement of precision. Poor precision may be indicative of sample non-homogeneity, method defects, or poor laboratory technique.

A duplicate sample was not included in this delivery group. It is noted, however, that the previously addressed LCS/LCSD samples demonstrated an acceptable level of measurement precision.

Reported Analytes

Formal reports were provided for each sample. The data package also included total ion chromatograms and raw instrument printouts. Reference mass spectra were provided to confirm the identification of each analyte that was found in this group of samples. Tentatively Identified Compounds (TIC) were not reported.

The presence of methylcyclohexane in MW-7 could not be confirmed, based on the mass spectra references included in the raw data. Methylcyclohexane should be considered undetected in this sample.

SUMMARY OF QUALIFIED DATA

3865/3875 HENRIETTA STREET

SAMPLED: 6/16/2017 and 6/17/2017

		CALIBRATE TRICHLOROETHENE	CALIBRATE BROMOMETHANE	MASS SPECTRA ID METHYL CYCLOHEXANE	.
MW-3R	(L917097-01)	1.00UJ	5.00UJ		
MW-7	(L917097-02)	10.0UJ	50.0UJ	44.8U	

SAMPLE RESULT SUMMARY ORGANIC ANALYSIS DATA SHEET

ESC Sample ID: L917097-01
 Client Sample ID: MW-3R
 Lab File ID: 0625_09
 Instrument ID: VOCMS6
 Analytical Batch: WG992821
 Dilution Factor: 1
 Analytical Method: 8260C
 Matrix: GW
 Total Solids (%):

SDG: L917097
 Collected Date/Time: 06/16/17 17:25
 Received Date/Time: 06/20/17 08:45
 Preparation Date/Time: 06/25/17 18:27
 Analysis Date/Time: 06/25/17 18:27
 Prep Method: 8260C
 Sample Vol Used: 5 mL
 Initial Wt/Vol:
 Final Wt/Vol: 5 mL

Analyte	CAS	RT	Result	Qualifier	MDL	RDL
			ug/l		ug/l	ug/l
Acetone	67-64-1	3.02	ND		10.0	50.0
Benzene	71-43-2	0	ND		0.331	1.00
Bromochloromethane	74-97-5	0	ND		0.520	1.00
Bromodichloromethane	75-27-4	0	ND		0.380	1.00
Bromoform	75-25-2	0	ND		0.469	1.00
Bromomethane	74-83-9	0	ND		0.866	5.00
Carbon disulfide	75-15-0	0	ND		0.275	1.00
Carbon tetrachloride	56-23-5	0	ND		0.379	1.00
Chlorobenzene	108-90-7	6.35	130		0.348	1.00
Chlorodibromomethane	124-48-1	0	ND		0.327	1.00
Chloroethane	75-00-3	0	ND		0.453	5.00
Chloroform	67-66-3	0	ND		0.324	5.00
Chloromethane	74-87-3	0	ND		0.276	2.50
Cyclohexane	110-82-7	0	ND		0.390	1.00
1,2-Dibromo-3-Chloropropane	96-12-8	0	ND		1.33	5.00
1,2-Dibromoethane	106-93-4	0	ND		0.381	1.00
1,2-Dichlorobenzene	95-50-1	8.36	2.80		0.349	1.00
1,3-Dichlorobenzene	541-73-1	0	ND		0.220	1.00
1,4-Dichlorobenzene	106-46-7	0	ND		0.274	1.00
Dichlorodifluoromethane	75-71-8	1.67	ND	JO	0.551	5.00
1,1-Dichloroethane	75-34-3	3.43	ND		0.259	1.00
1,2-Dichloroethane	107-06-2	0	ND		0.361	1.00
1,1-Dichloroethene	75-35-4	0	ND		0.398	1.00
cis-1,2-Dichloroethene	156-59-2	3.72	ND		0.260	1.00
trans-1,2-Dichloroethene	156-60-5	0	ND		0.396	1.00
1,2-Dichloropropane	78-87-5	0	ND		0.306	1.00
cis-1,3-Dichloropropene	10061-01-5	0	ND		0.418	1.00
trans-1,3-Dichloropropene	10061-02-6	0	ND		0.419	1.00
Ethylbenzene	100-41-4	0	ND		0.384	1.00
2-Hexanone	591-78-6	0	ND		3.82	10.0
Isopropylbenzene	98-82-8	0	ND		0.326	1.00
2-Butanone (MEK)	78-93-3	0	ND		3.93	10.0
Methyl Acetate	79-20-9	0	ND		4.30	20.0
Methyl Cyclohexane	108-87-2	0	ND		0.380	1.00
Methylene Chloride	75-09-2	0	ND		1.00	5.00
4-Methyl-2-pentanone (MIBK)	108-10-1	0	ND		2.14	10.0
Methyl tert-butyl ether	1634-04-4	3.13	1.35		0.367	1.00
Naphthalene	91-20-3	0	ND		1.00	5.00
Styrene	100-42-5	0	ND		0.307	1.00
1,1,2,2-Tetrachloroethane	79-34-5	0	ND		0.130	1.00
Tetrachloroethene	127-18-4	0	ND		0.372	1.00
Toluene	108-88-3	0	ND		0.412	1.00
1,2,3-Trichlorobenzene	87-61-6	0	ND		0.230	1.00

SAMPLE RESULT SUMMARY ORGANIC ANALYSIS DATA SHEET

ESC Sample ID: L917097-01
Client Sample ID: MW-3R
Lab File ID: 0625_09
Instrument ID: VOCMS6
Analytical Batch: WG992821
Dilution Factor: 1
Analytical Method: 8260C
Matrix: GW
Total Solids (%):

SDG: L917097
Collected Date/Time: 06/16/17 17:25
Received Date/Time: 06/20/17 08:45
Preparation Date/Time: 06/25/17 18:27
Analysis Date/Time: 06/25/17 18:27
Prep Method: 8260C
Sample Vol Used: 5 mL
Initial Wt/Vol:
Final Wt/Vol: 5 mL

Analyte	CAS	RT	Result	Qualifier	MDL	RDL
			ug/l		ug/l	ug/l
1,2,4-Trichlorobenzene	120-82-1	0	ND		0.355	1.00
1,1,1-Trichloroethane	71-55-6	0	ND		0.319	1.00
1,1,2-Trichloroethane	79-00-5	0	ND		0.383	1.00
Trichloroethene	79-01-6	0	1.0 ND UJ		0.398	1.00
Trichlorofluoromethane	75-69-4	0	ND		1.20	5.00
1,1,2-Trichlorotrifluoroethane	76-13-1	0	ND		0.303	1.00
Vinyl chloride	75-01-4	0	ND		0.259	1.00
o-Xylene	95-47-6	0	ND		0.341	1.00
m&p-Xylenes	1330-20-7	0	ND		0.719	2.00
n-Butylbenzene	104-51-8	0	ND		0.361	1.00
sec-Butylbenzene	135-98-8	0	ND		0.365	1.00
tert-Butylbenzene	98-06-6	0	ND		0.399	1.00
1,2,4-Trimethylbenzene	95-63-6	0	ND		0.373	1.00
1,3,5-Trimethylbenzene	108-67-8	0	ND		0.387	1.00
n-Propylbenzene	103-65-1	0	ND		0.349	1.00
p-Isopropyltoluene	99-87-6	0	ND		0.350	1.00

114

SAMPLE RESULT SUMMARY ORGANIC ANALYSIS DATA SHEET

ESC Sample ID: L917097-02
 Client Sample ID: MW-7
 Lab File ID: 0625_10
 Instrument ID: VOCMS6
 Analytical Batch: WG992821
 Dilution Factor: 10
 Analytical Method: 8260C
 Matrix: GW
 Total Solids (%):

SDG: L917097
 Collected Date/Time: 06/16/17 14:00
 Received Date/Time: 06/20/17 08:45
 Preparation Date/Time: 06/25/17 18:45
 Analysis Date/Time: 06/25/17 18:45
 Prep Method: 8260C
 Sample Vol Used: 5 mL
 Initial Wt/Vol: _____
 Final Wt/Vol: 5 mL

Analyte	CAS	RT	Result	Qualifier	MDL	RDL
			ug/l		ug/l	ug/l
Acetone	67-64-1	0	ND		100	500
Benzene	71-43-2	4.19	675		3.31	10.0
Bromochloromethane	74-97-5	0	ND		5.20	10.0
Bromodichloromethane	75-27-4	0	ND		3.80	10.0
Bromoform	75-25-2	0	ND		4.69	10.0
Bromomethane	74-83-9	0	50 ND UJ		8.66	50.0
Carbon disulfide	75-15-0	0	ND		2.75	10.0
Carbon tetrachloride	56-23-5	0	ND		3.79	10.0
Chlorobenzene	108-90-7	0	ND		3.48	10.0
Chlorodibromomethane	124-48-1	0	ND		3.27	10.0
Chloroethane	75-00-3	0	ND		4.53	50.0
Chloroform	67-66-3	0	ND		3.24	50.0
Chloromethane	74-87-3	0	ND		2.76	25.0
Cyclohexane	110-82-7	3.85	79.5		3.90	10.0
1,2-Dibromo-3-Chloropropane	96-12-8	0	ND		13.3	50.0
1,2-Dibromoethane	106-93-4	0	ND		3.81	10.0
1,2-Dichlorobenzene	95-50-1	0	ND		3.49	10.0
1,3-Dichlorobenzene	541-73-1	0	ND		2.20	10.0
1,4-Dichlorobenzene	106-46-7	0	ND		2.74	10.0
Dichlorodifluoromethane	75-71-8	0	ND		5.51	50.0
1,1-Dichloroethane	75-34-3	0	ND		2.59	10.0
1,2-Dichloroethane	107-06-2	0	ND		3.61	10.0
1,1-Dichloroethene	75-35-4	0	ND		3.98	10.0
cis-1,2-Dichloroethene	156-59-2	0	ND		2.60	10.0
trans-1,2-Dichloroethene	156-60-5	0	ND		3.96	10.0
1,2-Dichloropropane	78-87-5	0	ND		3.06	10.0
cis-1,3-Dichloropropene	10061-01-5	0	ND		4.18	10.0
trans-1,3-Dichloropropene	10061-02-6	0	ND		4.19	10.0
Ethylbenzene	100-41-4	6.34	332		3.84	10.0
2-Hexanone	591-78-6	0	ND		38.2	100
Isopropylbenzene	98-82-8	6.96	18.3		3.26	10.0
2-Butanone (MEK)	78-93-3	0	ND		39.3	100
Methyl Acetate	79-20-9	0	ND		43.0	200
Methyl Cyclohexane	108-87-2	4.52	44.8 U		3.80	10.0
Methylene Chloride	75-09-2	0	ND		10.0	50.0
4-Methyl-2-pentanone (MIBK)	108-10-1	0	ND		21.4	100
Methyl tert-butyl ether	1634-04-4	0	ND		3.67	10.0
Naphthalene	91-20-3	9.81	642		10.0	50.0
Styrene	100-42-5	0	ND		3.07	10.0
1,1,2,2-Tetrachloroethane	79-34-5	0	ND		1.30	10.0
Tetrachloroethene	127-18-4	0	ND		3.72	10.0
Toluene	108-88-3	5.36	67.6		4.12	10.0
1,2,3-Trichlorobenzene	87-61-6	0	ND		2.30	10.0

SAMPLE RESULT SUMMARY
ORGANIC ANALYSIS DATA SHEET

ESC Sample ID: L917097-02
Client Sample ID: MW-7
Lab File ID: 0625_10
Instrument ID: VOCMS6
Analytical Batch: WG992821
Dilution Factor: 10
Analytical Method: 8260C
Matrix: GW
Total Solids (%):

SDG: L917097
Collected Date/Time: 06/16/17 14:00
Received Date/Time: 06/20/17 08:45
Preparation Date/Time: 06/25/17 18:45
Analysis Date/Time: 06/25/17 18:45
Prep Method: 8260C
Sample Vol Used: 5 mL
Initial Wt/Vol:
Final Wt/Vol: 5 mL

Analyte	CAS	RT	Result	Qualifier	MDL	RDL
			ug/l		ug/l	ug/l
1,2,4-Trichlorobenzene	120-82-1	0	ND		3.55	10.0
1,1,1-Trichloroethane	71-55-6	0	ND		3.19	10.0
1,1,2-Trichloroethane	79-00-5	0	ND		3.83	10.0
Trichloroethene	79-01-6	0	10 ND UJ		3.98	10.0
Trichlorofluoromethane	75-69-4	0	ND		12.0	50.0
1,1,2-Trichlorotrifluoroethane	76-13-1	0	ND		3.03	10.0
Vinyl chloride	75-01-4	0	ND		2.59	10.0
o-Xylene	95-47-6	6.74	319		3.41	10.0
m&p-Xylenes	1330-20-7	6.44	3610		7.19	20.0
n-Butylbenzene	104-51-8	8.21	ND		3.61	10.0
sec-Butylbenzene	135-98-8	7.78	ND		3.65	10.0
tert-Butylbenzene	98-06-6	0	ND		3.99	10.0
1,2,4-Trimethylbenzene	95-63-6	7.69	1750		3.73	10.0
1,3,5-Trimethylbenzene	108-67-8	7.39	290		3.87	10.0
n-Propylbenzene	103-65-1	7.26	22.0		3.49	10.0
p-Isopropyltoluene	99-87-6	7.88	ND		3.50	10.0

7/14/17



Analytical Method: 8260C
Matrix: GW

SDG: L917097

Sample ID	ESC Sample ID	Instrument	File ID	DMC-1	DMC-2	DMC-3	DMC-4	TOT Out
				% Rec. ✓	% Rec. ✓	% Rec. ✓	% Rec. ✓	
MW-3R	L917097-01	VOCMS6	0625_09	107	95.3	98.7	98.2	0
MW-7	L917097-02	VOCMS6	0625_10	104	96.3	100	98.5	0
BLANK	R3228636-3	VOCMS6	0625_05	104	97.9	100	99.0	0
LCS	R3228636-1	VOCMS6	0625_02a	104	97.3	98.3	100	0
LCSD	R3228636-2	VOCMS6	0625_03	103	96.2	99.2	99.5	0

Parm Abbreviation

DMC-1

DMC-2

DMC-3

DMC-4

Parameter

Toluene-d8

Dibromofluoromethane

a,a,a-Trifluorotoluene

4-Bromofluorobenzene

QC LIMITS

80.0 - 120

76.0 - 123

80.0 - 120

80.0 - 120

†: Value outside the established quality control limits.

D: Surrogate recovery cannot be used for control limit evaluation due to dilution.

LABORATORY CONTROL SAMPLE
LABORATORY CONTROL SAMPLE DUPLICATE
RECOVERY
L917097-01,02

LCS Sample / File ID: R3228636-1 / 0625_02a

LCSD Sample / File ID: R3228636-2 / 0625_03

Instrument ID: VOCMS6

Analytical Method: 8260C

SDG: L917097

Analytical Batch: WG992821

Dilution Factor: 1

Matrix: GW

Analyte	Spike Amount ug/l	LCS Result ug/l	LCSD Result ug/l	LCS Rec. %	LCSD Rec. %	Rec. Limits %	RPD %	RPD Limit %
Acetone	125	112	109	89.4	87.3	10.0 - 160	2.27	23
Benzene	25.0	22.7	22.5	90.6 ✓	89.9 ✓	69.0 - 123	0.840	20
Bromochloromethane	25.0	24.9	24.8	99.4	99.1	76.0 - 122	0.310	20
Bromodichloromethane	25.0	22.1	22.0	88.4	88.2	76.0 - 120	0.190	20
Bromoform	25.0	23.2	24.0	93.0	96.0	67.0 - 132	3.24	20
Bromomethane	25.0	31.8	32.3	127	129	18.0 - 160	1.65	20
n-Butylbenzene	25.0	23.8	24.3	95.1	97.0	72.0 - 126	1.97	20
sec-Butylbenzene	25.0	23.5	24.0	93.9	96.1	74.0 - 121	2.31	20
Carbon disulfide	25.0	20.6	20.1	82.4	80.5	55.0 - 127	2.37	20
tert-Butylbenzene	25.0	23.6	23.8	94.2	95.2	75.0 - 122	1.06	20
Carbon tetrachloride	25.0	23.2	22.9	92.8	91.6	63.0 - 122	1.35	20
Chlorobenzene	25.0	24.5	24.4	98.0 ✓	97.4 ✓	79.0 - 121	0.640	20
Chlorodibromomethane	25.0	23.7	24.1	94.9	96.5	75.0 - 125	1.61	20
Chloroethane	25.0	25.8	25.9	103	104	47.0 - 152	0.630	20
Chloroform	25.0	21.9	21.6	87.8	86.4	72.0 - 121	1.55	20
Cyclohexane	25.0	23.3	22.8	93.4	91.3	70.0 - 130	2.26	20
Chloromethane	25.0	24.5	24.4	98.0	97.5	48.0 - 139	0.560	20
1,2-Dibromo-3-Chloropropane	25.0	23.2	24.2	92.9	96.7	64.0 - 127	4.05	20
1,2-Dibromoethane	25.0	24.5	24.4	97.9	97.7	77.0 - 123	0.160	20
1,2-Dichlorobenzene	25.0	23.4	24.0	93.4	96.0	80.0 - 120	2.72	20
1,3-Dichlorobenzene	25.0	23.6	24.1	94.4	96.5	72.0 - 123	2.25	20
1,4-Dichlorobenzene	25.0	23.2	23.3	92.7	93.1	77.0 - 120	0.500	20
Dichlorodifluoromethane	25.0	31.3	30.1	125	121	49.0 - 155	3.63	20
1,1-Dichloroethane	25.0	23.1	22.9	92.3	91.7	70.0 - 126	0.740	20
1,2-Dichloroethane	25.0	23.7	23.3	94.8	93.1	67.0 - 126	1.75	20
1,1-Dichloroethene	25.0	23.1	22.9	92.4 ✓	91.8 ✓	64.0 - 129	0.650	20
cis-1,2-Dichloroethene	25.0	22.7	22.2	90.7	88.6	73.0 - 120	2.28	20
trans-1,2-Dichloroethene	25.0	22.2	21.8	88.7	87.2	71.0 - 121	1.71	20
1,2-Dichloropropane	25.0	23.2	23.0	92.6	91.9	75.0 - 125	0.740	20
cis-1,3-Dichloropropene	25.0	24.1	24.0	96.5	95.9	79.0 - 123	0.580	20
trans-1,3-Dichloropropene	25.0	25.7	25.2	103	101	74.0 - 127	1.98	20
Ethylbenzene	25.0	24.6	24.5	98.5	97.8	77.0 - 120	0.700	20
2-Hexanone	125	119	120	95.5	95.7	58.0 - 147	0.200	20
Isopropylbenzene	25.0	23.1	23.6	92.5	94.2	75.0 - 120	1.84	20
p-Isopropyltoluene	25.0	23.8	24.5	95.4	98.0	74.0 - 126	2.77	20
Methyl Acetate	125	113	114	90.6	91.6	70.0 - 130	1.11	20
Methyl Cyclohexane	25.0	21.1	20.7	84.5	82.7	70.0 - 130	2.15	20
2-Butanone (MEK)	125	109	109	87.3	87.4	37.0 - 158	0.0700	20
Methylene Chloride	25.0	21.6	21.7	86.5	86.6	66.0 - 121	0.190	20
4-Methyl-2-pentanone (MIBK)	125	117	119	93.7	95.2	59.0 - 143	1.54	20
Methyl tert-butyl ether	25.0	22.6	21.9	90.4	87.7	64.0 - 123	3.10	20
Naphthalene	25.0	22.8	24.0	91.1	95.8	62.0 - 128	5.03	20
n-Propylbenzene	25.0	24.0	24.3	95.8	97.2	79.0 - 120	1.49	20

*: Value outside the established quality control limits.

D: Surrogate recovery cannot be used for control limit evaluation due to dilution.

LABORATORY CONTROL SAMPLE
LABORATORY CONTROL SAMPLE DUPLICATE
RECOVERY
L917097-01,02

SAMPLE NO.:

R3228636-1

R3228636-2

LCS Sample / File ID: R3228636-1 / 0625_02a

LCSD Sample / File ID: R3228636-2 / 0625_03

Instrument ID: VOCMS6

Analytical Method: 8260C

SDG: L917097

Analytical Batch: WG992821

Dilution Factor: 1

Matrix: GW

Analyte	Spike Amount ug/l	LCS Result ug/l	LCSD Result ug/l	LCS Rec. %	LCSD Rec. %	Rec. Limits %	RPD %	RPD Limit %
Styrene	25.0	24.0	24.1	95.9	96.3	78.0 - 124	0.470	20
1,1,2,2-Tetrachloroethane	25.0	22.3	22.5	89.3	89.8	71.0 - 122	0.570	20
Tetrachloroethene	25.0	25.2	24.5	101	98.2	70.0 - 127	2.51	20
Toluene	25.0	23.2	22.9	92.7 ✓	91.4 ✓	77.0 - 120	1.32	20
1,1,2-Trichlorotrifluoroethane	25.0	23.6	22.8	94.6	91.1	61.0 - 136	3.79	20
1,2,3-Trichlorobenzene	25.0	23.0	23.8	92.0	95.2	61.0 - 133	3.44	20
1,2,4-Trichlorobenzene	25.0	22.7	24.3	90.9	97.2	69.0 - 129	6.67	20
1,1,1-Trichloroethane	25.0	22.8	22.7	91.3	90.6	68.0 - 122	0.740	20
1,1,2-Trichloroethane	25.0	23.4	22.6	93.5	90.5	78.0 - 120	3.25	20
Trichloroethene	25.0	24.9	25.0	99.6 ✓	99.8 ✓	78.0 - 120	0.230	20
Trichlorofluoromethane	25.0	24.5	23.8	98.1	95.0	56.0 - 137	3.16	20
1,2,4-Trimethylbenzene	25.0	22.8	23.4	91.4	93.4	75.0 - 120	2.22	20
1,3,5-Trimethylbenzene	25.0	23.4	23.6	93.7	94.4	75.0 - 120	0.660	20
Vinyl chloride	25.0	28.8	27.9	115	112	64.0 - 133	3.03	20
o-Xylene	25.0	23.8	23.8	95.0	95.0	78.0 - 120	0.0100	20
m&p-Xylenes	50.0	48.9	48.6	97.7	97.1	77.0 - 120	0.600	20

*: Value outside the established quality control limits.

D: Surrogate recovery cannot be used for control limit evaluation due to dilution.



ESC Sample ID: R3228636-3
Lab File ID: 0625_05
Instrument ID: VOCMS6
Analytical Batch: WG992821
Analytical Method: 8260C

SDG: L917097
Preparation Date/Time: 06/25/17 16:58
Analysis Date/Time: 06/25/17 16:58
Dilution Factor: 1
Matrix: GW

Sample ID	ESC Sample ID	Instrument	File ID	Analysis date/time
LC5	R3228636-1	VOCMS6	0625_02a	06/25/17 16:04
LCSD	R3228636-2	VOCMS6	0625_03	06/25/17 16:22
MW-3R	L917097-01	VOCMS6	0625_09	06/25/17 18:27
MW-7	L917097-02	VOCMS6	0625_10	06/25/17 18:45

GC/MS INSTRUMENT
PERFORMANCE CHECK

Lab File ID: 0619_01T
Instrument ID: VOCMS6
Analysis Date/Time: 06/19/17 18:42

SDG: L917097
Analytical Method: 8260C



Target Mass (m/e)	Relative Mass	Low Limit	High Limit	% Relative Abundance
173	174	0	2	0 ✓
174	95	50	100	71 ✓
175	174	5	9	8 ✓
176	174	95	101	97 ✓
177	176	5	9	6 ✓
50	95	15	40	17 ✓
75	95	30	60	45 ✓
95	95	100	100	100 ✓
96	95	5	9	6 ✓

Sample ID	ESC Sample ID	File ID	Analysis date/time
STD-0.25	0.25	0619_03	06/19/17 19:17
STD-0.5	0.5	0619_04	06/19/17 19:36
STD-1	1	0619_05	06/19/17 19:54
STD-2	2	0619_06	06/19/17 20:12
STD-5.0	5.0	0619_07	06/19/17 20:30
STD-10	10	0619_08	06/19/17 20:49
STD-25	25	0619_09	06/19/17 21:07
STD-40	40	0619_10	06/19/17 21:25
STD-75	75	0619_11	06/19/17 21:43
STD-100	100	0619_12	06/19/17 22:01
STD-200	200	0619_13	06/19/17 22:19 ✓

Data Path : C:\msdchem\1\data\061917\
 Data File : 0619_01.D
 Acq On : 19 Jun 2017 6:42 pm
 Operator : 605
 Sample : INSTBLK
 Misc : water IS/SURR 17F11411
 ALS Vial : 1 Sample Multiplier: 1

Integration File: RTEINTLRH.P

Method : C:\msdchem\1\methods\V806F27Q.M
 Title : Env. Science Corp. 8260B/6210D/624 - VOCMS06
 Last Update : Sun Jun 25 12:37:07 2017



AutoFind: Scans 2204, 2205, 2206; Background Corrected with Scan 2188

Target Mass	Rel. to Mass	Lower Limit%	Upper Limit%	Rel. Abn%	Raw Abn	Result Pass/Fail
50	95	15	40	16.7	46187	PASS
75	95	30	60	45.3	125189	PASS
95	95	100	100	100.0	276416	PASS
96	95	5	9	6.3	17386	PASS
173	174	0.00	2	0.0	0	PASS
174	95	50	100	71.3	197120	PASS
175	174	5	9	7.5	14840	PASS
176	174	95	101	96.7	190677	PASS
177	176	5	9	6.3	11919	PASS

GC/MS INSTRUMENT
PERFORMANCE CHECK

Lab File ID: 0625_01T-3
Instrument ID: VOCMS6
Analysis Date/Time: 06/25/17 15:46

SDG: L917097
Analytical Method: 8260C



Target Mass (m/e)	Relative Mass	Low Limit	High Limit	% Relative Abundance
173	174	0	2	0
174	95	50	100	68
175	174	5	9	7
176	174	95	101	98
177	176	5	9	7
50	95	15	40	17
75	95	30	60	47
95	95	100	100	100
96	95	5	9	6

Sample ID	ESC Sample ID	File ID	Analysis date/time
LCS	R3228636-1	0625_02a	06/25/17 16:04
LCSD	R3228636-2	0625_03	06/25/17 16:22
BLANK	R3228636-3	0625_05	06/25/17 16:58
MW-3R	L917097-01	0625_09	06/25/17 18:27
MW-7	L917097-02	0625_10	06/25/17 18:45

Data Path : C:\msdchem\1\data\062517\
 Data File : 0625_01.D
 Acq On : 25 Jun 2017 3:46 pm
 Operator : 605
 Sample : INSTBLK
 Misc : water
 ALS Vial : 1 Sample Multiplier: 1

Integration File: RTEINTLRH.P

Method : C:\msdchem\1\methods\V806F24Q.M
 Title : Env. Science Corp. 8260B/6210D/624 - VOCMS06
 Last Update : Sun Jun 25 12:37:07 2017



AutoFind: Scans 2201, 2202, 2203; Background Corrected with Scan 2190

Target Mass	Rel. to Mass	Lower Limit%	Upper Limit%	Rel. Abn%	Raw Abn	Result Pass/Fail
50	95	15	40	17.0	43288	PASS
75	95	30	60	47.0	119851	PASS
95	95	100	100	100.0	254891	PASS
96	95	5	9	6.5	16509	PASS
173	174	0.00	2	0.0	0	PASS
174	95	50	100	68.2	173845	PASS
175	174	5	9	7.4	12863	PASS
176	174	95	101	98.4	171115	PASS
177	176	5	9	6.6	11251	PASS

INTERNAL STANDARD
AND RETENTION TIME

SDG: L917097
Instrument ID: VOCMS6
Std File: 0625_02-3

Analytical Method: 8260C
Calibration Start Date: 06/19/17 19:17
Calibration End Date: 06/25/17 11:03
Std Analysis Date: 06/25/17 16:04

Sample ID	File ID	1,4-DCB		DFB		BCP		PFB	
		Response	RT	Response	RT	Response	RT	Response	RT
STANDARD		341782	8.01	830371	4.51	140042	5.65	440709	4.19
UPPER LIMIT		684000		1660000		280000		881000	
LOWER LIMIT		171000		415000		70000		220000	
LCS R3228636-1 WG992821 1x	0625_02a	341782	✓ 8.01	830371	✓ 4.51	140042	✓ 5.65	440709	✓ 4.19
LCSD R3228636-2 WG992821 1x	0625_03	336927	8.02	814656	4.51	139085	5.65	438643	4.19
BLANK R3228636-3 WG992821 1x	0625_05	316954	8.02	777602	4.51	131421	5.66	422176	4.19
L917097-01 WG992821 1x	0625_09	302375	8.02	749680	4.51	122206	5.65	404954	4.19
L917097-02 WG992821 10x	0625_10	322040	8.02	760148	4.52	127812	5.66	410786	4.19

1,4-DCB - 8260-1,4-DICHLOROBENZENE-D4
BCP - 8260-2-BROMO-1-CHLOROPROPANE

DFB - 8260-1,4-DIFLUOROBENZENE
PFB - 8260-PENTAFLUOROBENZENE

*: Value outside the established quality control limits.

D: Surrogate recovery cannot be used for control limit evaluation due to dilution.

APPENDIX C

Site Inspection Form and Photograph

LABELLA

Associates, P.C.

300 State Street
Rochester, New York 14614
Phone: (585) 454-6110
Fax: (585) 454-3066**SITE-WIDE INSPECTION FORM**

Project Name: NYSDEC BCP Site No. C828134

Location: 3865 & 3875 West Henrietta Road, Rochester, New York

Project No.: 209395

Inspected By:

K R Miller

Date of Inspection:

6/4/2017

Weather Conditions:

Sunny +/- 75°F

INSPECTION FINDINGS

3865 Building SSDS VENT FAN & GENERAL LOCATION	FAN OPERATING PROPERLY (YES/NO) and MANOMETER READING (H ₂ O"):	PIPING and LABELLING IN GOOD CONDITION (YES/NO)	COMMENTS AND/OR ACTIONS TAKEN
Women's Restroom, behind wall panel	2.5" H ₂ O	YES	NONE
3875 Building SSDS VENT FAN & GENERAL LOCATION	FAN OPERATING PROPERLY (YES/NO) and MANOMETER READING (H ₂ O"):	PIPING and LABELLING IN GOOD CONDITION (YES/NO)	COMMENTS AND/OR ACTIONS TAKEN
customer reception	-0.612 -0.060	YES	NONE
service area	-0.171 -0.007	YES	NONE
GENERAL SITE CONDITIONS	CURRENT USE OF SITE (COMMERCIAL/ RESIDENTIAL/ETC.)	SITE RECORDS UP TO DATE (YES/NO)	COMMENTS AND/OR ACTIONS TAKEN
Similar to previous years.	commercial auto service and sales	YES	Small demolition/construction work area on west end of 3875 Bldg.

NOTICE
Radon System Monitor
Do not alter or disconnect
Green light indicates vacuum pressure in ventline
(system operating). A red light and audible alarm
indicates a loss of vacuum pressure.
If red light appears/alarm sounds disconnect
power from alarm unit and call system installer
for service.
The EPA recommends testing radon levels at least every 2 years.
Checkpoint IIa Alarm
EPA 2008-2
RadonAway
Mfg by RadonAway, Ward Hill, MA
www.radonaway.com
15094-1 B

vacuum pressure,
pressure provides on
operating.
needed for Radon at
as required or
local agencies
COLUMNS ARE AT ZERO
CHANGES SUBSTANTIALY

EC4
100722
1-7430
2.5"



Easy Read
Dynamometer
RadonAway
Rev C

APPENDIX D

**As-Built Drawings of SSDSs at
3865 & 3875 West Henrietta Road Buildings**


PROPOSED SUB-SLAB DEPRESSURIZATION SYSTEM

SCALE: 1"=20'



SYMBOL LEGEND

-  SUB-SLAB VAPOR PIPE TRENCHING (REFER TO FIGURE 2 DETAILS)
 VALVE (REFER TO FIGURE 2 DETAILS)
 1/4" STAINLESS STEEL VACUUM PIPE
 #1 MONITORING LOCATION



NOTE:
BASE DRAWING ADAPTED FROM TY LIN INTERNATIONAL
DRAWING TITLED "SANITARY SEWER PLUMBING PLAN"
DATED NOVEMBER 8, 2011.

[illegible]

LABELLA
Associates, P.C.

300 STATE STREET
ROCHESTER, NY 14614
P: (585) 454-6110
F: (585) 454-3066
www.labelapc.com
Copyright © 2010

PROJECT/CLIENT

3875 West Henrietta Road
Henrietta, New York

R.J. Dorschel Corp.

DRAWING TITLE


AS-BUILT PLAN FOR SUB-SLAB DEPRESSURIZATION SYSTEM

ISSUED FOR:	SCALE:	NO SCALE
	DRAWN BY:	HMS/PCN
DATE:	REVIEWED BY:	DPI
MAR 2013	REVIEWED BY:	###

PROJECT/DRAWING NUMBER

209395

FIG 1



300 STATE STREET
ROCHESTER, NY 14614
P: (585) 454-6110
F: (585) 454-3066
WWW.LABELLA.PC.COM
COPYRIGHT © 2003

LABELLA
Associates, P.C.

PROJECT/CLIENT
BROWNFIELD CLEANUP PROGRAM
SITE MANAGEMENT PLAN
BCP Site # C828134
3865 WEST HENRIETTA RD
ROCHESTER, NY 14623

DRAWING TITLE	
SUBSLAB DEPRESSURIZATION DETAILS	
ISSUED FOR	DESIGNED BY: EPD
	DRAWN BY: EPD
	REVIEWED BY: DPN
	AUGUST 2009

DRAFT

PROJECT/DRAWING NUMBER


209395

FIGURE 9

APPENDIX E

Graphs of Total VOCs Over Time


MW-3R



Date

MW-7

[without outlier (May 2011 sample results)]



	Sep-06	May-07	Jun-10	Oct-10	Oct-11	Jul-12	Mar-14	May-15	Oct-15	Jun-16	Jun-17
MW-7	2,547	7,976	5,101	8,267	10,035	6,541	9,286	8,046	6,709	7,143.26	7805.4

Date

APPENDIX F

Institutional Controls/Engineering Controls Certification Form



Enclosure 2
NEW YORK STATE DEPARTMENT OF ENVIRONMENTAL CONSERVATION
Site Management Periodic Review Report Notice
Institutional and Engineering Controls Certification Form



Site Details		Box 1
Site No.	C828134	
Site Name Former Steve Joy's Sunoco		
Site Address: 3865 West Henrietta Road Zip Code: 14623		
City/Town: Rochester		
County: Monroe		
Site Acreage: 2.5		
Reporting Period: August 06, 2016 to August 06, 2017		
		YES NO
1. Is the information above correct?		☒ ☐
If NO, include handwritten above or on a separate sheet.		
2. Has some or all of the site property been sold, subdivided, merged, or undergone a tax map amendment during this Reporting Period?		☐ ☒
3. Has there been any change of use at the site during this Reporting Period (see 6NYCRR 375-1.11(d))?		☐ ☒
4. Have any federal, state, and/or local permits (e.g., building, discharge) been issued for or at the property during this Reporting Period?		☒ ☐
<i>See Addendum for more information.</i>		
If you answered YES to questions 2 thru 4, include documentation or evidence that documentation has been previously submitted with this certification form.		
5. Is the site currently undergoing development?		☒ ☐
<i>See Addendum for more information.</i>		

Box 2	
YES NO	
6. Is the current site use consistent with the use(s) listed below? Commercial and Industrial	☒ ☐
7. Are all ICs/ECs in place and functioning as designed?	☒ ☐
IF THE ANSWER TO EITHER QUESTION 6 OR 7 IS NO, sign and date below and DO NOT COMPLETE THE REST OF THIS FORM. Otherwise continue.	
A Corrective Measures Work Plan must be submitted along with this form to address these issues.	
_____ Signature of Owner, Remedial Party or Designated Representative	_____ Date

Box 2A

YES NO

8. Has any new information revealed that assumptions made in the Qualitative Exposure Assessment regarding offsite contamination are no longer valid?

☐

If you answered YES to question 8, include documentation or evidence that documentation has been previously submitted with this certification form.

9. Are the assumptions in the Qualitative Exposure Assessment still valid?
(The Qualitative Exposure Assessment must be certified every five years)

☐

If you answered NO to question 9, the Periodic Review Report must include an updated Qualitative Exposure Assessment based on the new assumptions.

SITE NO. C828134**Box 3****Description of Institutional Controls**

<u>Parcel</u>	<u>Owner</u>	<u>Institutional Control</u>
161.15-1-20.1	R.J. Dorschel Corp.	Soil Management Plan Landuse Restriction Monitoring Plan Site Management Plan O&M Plan IC/EC Plan Ground Water Use Restriction
The property may only be used for commercial or industrial use, provided that the long-term Engineering and Institutional Controls included in this SMP are employed. • The property may not be used for a higher level of use (e.g., unrestricted, residential, etc.) use without additional remediation and amendment of the Environmental Easement, as approved by the NYSDEC; • All future activities on the property that will disturb remaining contaminated material must be conducted in accordance with the SMP; • The existing sub-slab depressurization system at the 3865 West Henrietta Road property will be monitored and maintained in accordance with the SMP; • The existing biocell will be monitored and maintained in accordance with the SMP; • The use of the groundwater underlying the property is prohibited without treatment restricting the use of groundwater as a source of potable or process water, without necessary water quality treatment as determined by NYSDOH; • Prior to occupancy of any newly constructed buildings at this site a soil vapor intrusion evaluation will be performed in accordance with the State's most recent guidance on evaluation soil vapor intrusion. Alternatively, a SSDS can be designed and installed/started prior to occupancy of any newly constructed building. The SSDS will be designed and installed in accordance with the State's most recent guidance on evaluating soil vapor intrusion and will require approval by NYSDEC and NYSDOH prior to installation; • Vegetable gardens and farming on the Site are prohibited; and • The Site owner or remedial party will submit to NYSDEC a written statement that certifies, under penalty of perjury, that: (1) controls employed at the Controlled Property are unchanged from the previous certification or that any changes to the controls were approved by the NYSDEC; and, (2) nothing has occurred that impairs the ability of the controls to protect public health and environment or that constitute a violation or failure to comply with the SMP. NYSDEC retains the right to access the Site at any time in order to evaluate the continued maintenance of any and all controls. This certification shall be submitted annually, or an alternate period of time that NYSDEC may allow and will be made by an expert that the NYSDEC finds acceptable.		
161.19-1-9	R.J. Dorschel Corp.	Ground Water Use Restriction Soil Management Plan Landuse Restriction Monitoring Plan Site Management Plan IC/EC Plan
The property may only be used for commercial or industrial use, provided that the long-term Engineering and Institutional Controls included in this SMP are employed. • The property may not be used for a higher level of use (e.g., unrestricted, residential, etc.) use without additional remediation and amendment of the Environmental Easement, as approved by the NYSDEC; • All future activities on the property that will disturb remaining contaminated material must be conducted in accordance with the SMP; • The existing biocell will be monitored and maintained in accordance with the SMP; • The use of the groundwater underlying the property is prohibited without treatment restricting the use of groundwater as a source of potable or process water, without necessary water quality treatment as determined by NYSDOH; • Prior to occupancy of any newly constructed buildings at this site a soil vapor intrusion evaluation will be performed in accordance with the State's most recent guidance on evaluation soil vapor intrusion. Alternatively, a SSDS can be designed and installed/started prior to occupancy of any newly constructed building. The SSDS will be designed and installed in accordance with the State's most recent guidance on evaluating soil vapor intrusion and will require approval by NYSDEC and NYSDOH prior		

to installation;

- A SSDS will be designed and installed/started prior to occupancy of the existing 3875 West Henrietta Road building. The SSDS will be designed and installed in accordance with the State's most recent guidance on evaluating soil vapor intrusion and will require approval by NYSDEC and NYSDOH prior to installation;

- Vegetable gardens and farming on the Site are prohibited; and

- The Site owner or remedial party will submit to NYSDEC a written statement that certifies, under penalty of perjury, that: (1) controls employed at the Controlled

Property are unchanged from the previous certification or that any changes to the controls were approved by the NYSDEC; and, (2) nothing has occurred that impairs

the ability of the controls to protect public health and environment or that constitute a violation or failure to comply with the SMP. NYSDEC retains the right to access the

Site at any time in order to evaluate the continued maintenance of any and all controls. This certification shall be submitted annually, or an alternate period of time

that NYSDEC may allow and will be made by an expert that the NYSDEC finds acceptable.

Box 4

Description of Engineering Controls

Parcel

Engineering Control

161.15-1-20.1

Vapor Mitigation

161.19-1-9

Vapor Mitigation

Periodic Review Report (PRR) Certification Statements

1. I certify by checking "YES" below that:

a) the Periodic Review report and all attachments were prepared under the direction of, and reviewed by, the party making the certification;

b) to the best of my knowledge and belief, the work and conclusions described in this certification are in accordance with the requirements of the site remedial program, and generally accepted engineering practices; and the information presented is accurate and complete.

YES NO



2. If this site has an IC/EC Plan (or equivalent as required in the Decision Document), for each Institutional or Engineering control listed in Boxes 3 and/or 4, I certify by checking "YES" below that all of the following statements are true:

(a) the Institutional Control and/or Engineering Control(s) employed at this site is unchanged since the date that the Control was put in-place, or was last approved by the Department;

(b) nothing has occurred that would impair the ability of such Control, to protect public health and the environment;

(c) access to the site will continue to be provided to the Department, to evaluate the remedy, including access to evaluate the continued maintenance of this Control;

(d) nothing has occurred that would constitute a violation or failure to comply with the Site Management Plan for this Control; and

(e) if a financial assurance mechanism is required by the oversight document for the site, the mechanism remains valid and sufficient for its intended purpose established in the document.

YES NO



**IF THE ANSWER TO QUESTION 2 IS NO, sign and date below and
DO NOT COMPLETE THE REST OF THIS FORM. Otherwise continue.**

A Corrective Measures Work Plan must be submitted along with this form to address these issues.

Signature of Owner, Remedial Party or Designated Representative

Date

IC CERTIFICATIONS
SITE NO. C828134

Box 6


SITE OWNER OR DESIGNATED REPRESENTATIVE SIGNATURE

I certify that all information and statements in Boxes 1, 2, and 3 are true. I understand that a false statement made herein is punishable as a Class "A" misdemeanor, pursuant to Section 210.45 of the Penal Law.

I Albert J. Baronas at 3817 W Henrietta Rd Rochester NY 14623
print name print business address

am certifying as Owner's Representative (Owner or Remedial Party)

for the Site named in the Site Details Section of this form.

 Corp. Sec'ty. RJ Dorschel Corp.
Signature of Owner, Remedial Party, or Designated Representative
Rendering Certification

7.24.17
Date

IC/EC CERTIFICATIONS

Box 7


Qualified Environmental Professional Signature

I certify that all information in Boxes 4 and 5 are true. I understand that a false statement made herein is punishable as a Class "A" misdemeanor, pursuant to Section 210.45 of the Penal Law.

I DANIEL P NOLL at LaBella Associates
print name 300 STATE ST Rochester NY
print business address

am certifying as a Qualified Environmental Professional for the _____
(Owner or Remedial Party)

D. P. Noll
Signature of Qualified Environmental Professional, for
the Owner or Remedial Party, Rendering Certification



Stamp
(Required for PE)

8/21/17
Date

ADDENDUM

**To Enclosure 2
NYSDEC Site Management Plan PRR Notice
August 6, 2016 to August 6, 2017 Reporting Period**

ADDENDUM TO PERIODIC REVIEW REPORT; AUGUST 6, 2016 TO AUGUST 6, 2017 REPORTING PERIOD

FROM: Kyle R. Miller, LaBella Associates, DPC

DATE: August 21, 2017

RE: NYSDEC Site No. C828134, Former Steve Joy's Sunoco BCP Site
Town of Henrietta, Monroe County (i.e., the "Site")

This memorandum and the following pages in this Addendum to *Enclosure 2, NYSDEC Site Management Periodic Review Report Notice Institutional and Engineering Controls Certification Form* are intended to provide additional information to the affirmative responses to questions number 4 and 5 in Box 1 of the form.

The owner of the 3875 West Henrietta Road parcel, are proposing to construct a ±500 Square Foot Building Addition to an existing auto service area. A copy of the receipt from the Town of Henrietta regarding the building permit for this project is included as part of this Addendum.

The scope of work for this project includes the partial demolition and reconstruction of the extreme western portion of the existing 3875 West Henrietta Road building. This area of the Site is currently used as an automotive service area and the future use will be the same. It is understood that minor site work (excavation activities) will be completed at the 3875 West Henrietta Road portion of the Site during the demolition and reconstruction of the ±500 Square Foot Building Addition, including the following:

- excavations for new foundations;
- an excavation for a storm drainage tie-in to an existing storm sewer;
- shallow excavations for concrete sidewalks and floor slabs ; and
- a shallow excavation to facilitate the installation of new wheel alignment equipment in the new building addition

A Change of Use Notification Form regarding this partial demolition and reconstruction project was submitted to the NYSDEC Site Control Section in Albany on August 1, 2017. Construction drawings and specifications were also included with the submittal of the Change of Use Notification Form.

A 15-Day Advance Notice of Excavation Activities letter was submitted to the NYSDEC Region 8 Project Manager for this BCP Site on August 11, 2017. A copy of this letter, which includes a copy of the Change of Use Notification Form submittal, is included as part of this Addendum.



Town of Henrietta
Office of Building and Fire Prevention
475 Calkins Road, Henrietta, New York 14467
(585) 359-7060 Office (585) 321-6093 Fax

Receipt

DATE: 07/20/2017

Permit Number: C2017-0083

Invoice Number: 00011617

Tax ID #: 161.19-1-9.1

Property Name/Address:

The Dorschel Group
3875 West Henrietta Rd
Rochester, NY 14623-3703

Permit Type: Com: Addition

Permit Information

Com: Addition	225.00
Professional Services	75.00
Com: Plumbing	109.00
Com: Plan Review	110.00
Com: Inspections	125.00
Com: C of O	150.00

TOTAL PERMIT FEE: 794.00

Payment Type: Check **Check #** 405730

Payor: The Dorschel Group

August 11, 2017

Mr. Frank Sowers, P.E.
New York State Department of Environmental Conservation, Region 8
Division of Environmental Remediation
6274 East Avon-Lima Road
Avon, New York 14414

RE: 15-Day Advance Notice of Excavation Activities
±500 Square Foot Building Addition
3875 West Henrietta Road Parcel
BCP Site #C828134
Former Steve Joy's Sunoco
Town of Henrietta, Monroe County
LaBella Project Number 209395

Dear Mr. Sowers,

LaBella Associates, D.P.C. (LaBella) is submitting this letter on behalf of RJ Dorschel Corporation in order to provide notification of the anticipated excavation activities that will be taking place at the Former Steve Joy's Sunoco property located at 3865 and 3875 West Henrietta Road (hereinafter referred to as the "Site"). The Site is New York State (NYS) Brownfield Cleanup Program (BCP) Site #C828134 administered by New York State Department of Environmental Conservation (NYSDEC) and was remediated in accordance with Brownfield Cleanup Agreement (BCA) Index #B8-0719-06-06, Site # C828134.

A Change of Use Notification Form regarding the planned construction of a ±500 Square Foot Building Addition on the 3875 West Henrietta Road portion of the Site was submitted to the NYSDEC Site Control Section. Construction drawings and specifications were also included with the submittal of the Change of Use Notification Form. A copy of this submittal is included as Attachment 1. The owner of the Site would like to proceed with the construction of the ±500 Square Foot Building Addition as soon as possible.

Description of the Work

The scope of work for this project includes the partial demolition and reconstruction of the extreme western portion of the existing 3875 West Henrietta Road building. This area of the Site is currently used as an automotive service area and the future use will be the same. It is understood that minor site work (excavation activities) will be completed at the 3875 West Henrietta Road portion of the Site during the demolition and reconstruction of the ±500 Square Foot Building Addition, including the following:

- excavations for new foundations;
- an excavation for a storm drainage tie-in to an existing storm sewer;
- shallow excavations for concrete sidewalks and floor slabs ; and
- a shallow excavation to facilitate the installation of new wheel alignment equipment in the new building addition.

According to the owner's construction contractor (Spoleta Construction of Rochester, New York), the deepest of the proposed excavations will be four (4) feet deep (for new foundation footers) and overall estimated volumes of materials to be excavated are identified in the following table.

Material Type	Excavated [Cubic Yards (CY)]	Re-Used On-Site (CY)	Off-Site Disposal (CY)
Total	60	45	15

Based upon the on the relatively small quantity of material proposed for excavation during this project, and the previously existing subsurface data from the Remedial Investigation, no sampling and laboratory analysis is planned for the 45 cubic yards of material proposed for on-site re-use, unless the material exhibits evidence of impairment. If this material is observed to exhibit evidence of impairment, then it would be sampled, analyzed, and re-used as outlined in the Excavation Work Plan (EWP) [Appendix B of the Site Management Plan (SMP)].

Given the relatively shallow excavations (4-foot maximum depth), significant amounts of groundwater are not expected to be encountered during construction. However, if groundwater accumulates in excavations and requires removal, it will be containerized. All such liquids to be removed from the excavations will be handled, transported and disposed in accordance with applicable local, State, and Federal regulations. It is anticipated that groundwater will be sampled, treated if necessary, and discharged to the sanitary sewer system with prior approval from the local sewer authority.

A sub-slab depressurization system (SSDS) was installed within the 3875 West Henrietta Road building during redevelopment of this structure in 2012. In order to expand the SSDS during this project, additional sub-slab perforated piping and vapor barrier are proposed for inclusion beneath the building in areas where floor slab will be replaced during construction of the ±500 Square Foot Building Addition. The new sub-slab perforated piping is proposed for connection to existing sub-slab piping in the southwestern portion of the building.

Summary of Environmental Conditions Anticipated to be Encountered

Soil and Fill Materials – on-site subsurface characteristics are based primarily on information obtained from the advancement soil borings and the excavation test pits completed as part of the BCP Remedial Investigation. Soils encountered beneath the asphalt pavement, concrete

slabs or topsoil layer within the soil borings and test pits completed at the Site generally revealed a Fill Material layer consisting primarily of coarse to fine-grained Sand and coarse to fine-grained Gravel with little or no Silt. The Fill Material deposit generally ranged in thickness from 0.6 to 4 feet, but was found to be up to 8 feet thick in some borings.

The following investigation locations were completed during the Remedial Investigation and are situated nearest the proposed work area:

- soil boring "RITB-4";
- soil boring "RITB-9"; and
- test pit "RITP-4".

For your reference, copies of the logs for the above investigation locations and a figure are included in Attachment 2. The subsurface findings at the above investigation locations found sandy and gravelly fill material extending to depths of approximately 4 feet below existing grade.

A shallow (0.5 to 1.8 feet below existing grade) soil sample was collected from soil boring RITB-4 was collected and submitted for laboratory analysis of volatile organic compounds (VOCs) and semi-volatile organic compounds (SVOCs). As shown on the attached (see Attachment 2) Figure 3 from the BCP Remedial Investigation Report, no VOCs and SVOCs were reported at concentrations above their respective NYCRR Subpart 375-6 Restricted Use Soil Cleanup objectives for the Protection of Groundwater.

Schedule

As noted previously, the owner of the Site would like to proceed with the construction of the ±500 Square Foot Building Addition as soon as possible. The estimated duration of the proposed work is approximately 90 days. The estimated duration of the on-site excavation work is approximately three (3) weeks.

Applicable EWP Components

The SMP and EWP will be followed for completing the excavation work. As noted previously, based upon the on the relatively small quantity of material proposed for excavation during this project, and the previously existing subsurface data from the Remedial Investigation, no sampling and laboratory analysis is planned with regard to the 45 cubic yards of material proposed for on-site re-use, unless the material exhibits evidence of impairment. If this material is observed to exhibit evidence of impairment, then it would be sampled, analyzed, and re-used as outlined in the EWP. The following components of the EWP are the most significant/relevant to this project:

- Section B-2: Soil-Screening Methods
- Section B-3: Stockpile Methods
- Section B-4: Excavation and Load Out of Material
- Section B-5: Transport of Material Off-Site

- Section B-6: Off-Site Disposal of Material
- Section B-7: Reuse of Materials On-Site
- Section B-9: Cover System Restoration
- Section B-10: Backfill From Off-Site Sources
- Section B-11: Stormwater Pollution Prevention
- Section B-13: Community Air Monitoring Plan
- Section B-15: Dust Control Plan

During all soil/fill disturbances, soils will be assessed for visible and olfactory indications of impairment, including the presence of fill material, and indications of detectable VOCs with a photoionization detector (PID) by a LaBella representative. Types of fill materials and depths of such materials, if encountered, will be documented by a LaBella representative.

The New York State Department of Health (NYSDOH) Generic Community Air Monitoring Plan (CAMP) will be followed during all ground intrusive work. Two (2) air monitoring locations, one (1) upwind and one (1) downwind from the excavation activities will be set up preceding any ground intrusive work. Due to the variability of the wind direction these locations may change on a daily, or more frequent, basis. The location(s) of the air sampling stations, based upon generally prevailing wind conditions, will be recorded in a daily log of activities by a LaBella representative. Exceedances of action levels listed in the CAMP will be recorded. Dust suppression will be completed as necessary, as defined in the SMP and EWP.

Compliance with EWP and 29 CFR 1910.120

All parties working at the Site are aware of and have been provided a copy of the EWP and the requirements of 29 CFR 1910.120. All work will be completed in accordance with these requirements.

Disposal Facilities

As noted previously, it is anticipated that approximately 15 cubic yards of excavated material cannot be reused on-Site, so these excess spoils will be disposed of at Mill Seat Landfill operated by Waste Management, or an equivalent NYSDEC-permitted landfill. All transport of regulated materials and characterized wastes will be performed by licensed haulers in properly placarded trucks in accordance with appropriate local, State, and Federal regulations, including 6 NYCRR Part 364. It is anticipated that construction vehicles will enter and leave the Site via West Henrietta Road.

Backfill Materials

A Request to Import/ Reuse Fill or Soil form will be completed and provided to the NYSDEC for material is to be imported on the Site for use as backfill.

Mr. Frank Sowers, P.E.
NYS Department of Environmental Conservation
August 11, 2017
Page 5

If you have any questions, please do not hesitate to contact me at (585) 295-6295.

Sincerely,

LABELLA ASSOCIATES, D.P.C.



Kyle R. Miller
Sr. Environmental Analyst

Attachment 1: Change of Use Form, Construction Drawings and Specifications

Attachment 2: Pertinent Subsurface Investigation Logs and Figures

Attachment 3: Excavation Work Plan (Appendix B to Site Management Plan)

cc: Mr. Al Baronas, RJ Dorschel Corporation (w/o Attachment 1)
Mr. Kirk Olsen, Spoleta Construction (w/o Attachment 1)

J:\RJ Dorschel Corp\209395 - 3865 3875 W Henrietta Rd Rem Act\2017 MINI Bldg. Change of Use\2017_08_11_Excavation Notice C828134.doc

ATTACHMENT 1

Change of Use Form, Construction Drawings and Specifications

**60-Day Advance Notification of Site Change of Use, Transfer of
Certificate of Completion, and/or Ownership**

Required by 6NYCRR Part 375-1.11(d) and 375-1.9(f)

To be submitted at least 60 days prior to change of use to:

Chief, Site Control Section
New York State Department of Environmental Conservation
Division of Environmental Remediation, 625 Broadway
Albany NY 12233-7020

I. Site Name: Former Steve Joy's Sunoco **DEC Site ID No.** C828134

II. Contact Information of Person Submitting Notification:

Name: Al Baronas - RJ Dorschel Corporation
Address1: 3817 West Henrietta Road Rochester, NY 14623
Address2: _____
Phone: (585) 321-2403 E-mail: abaronas@dorschel.com

III. Type of Change and Date: Indicate the Type of Change(s) (check all that apply):

- ☐ Change in Ownership or Change in Remedial Party(ies)
☐ Transfer of Certificate of Completion (CoC)
☒ Other (e.g., any physical alteration or other change of use)

Proposed Date of Change (mm/dd/yyyy): 08/2017**IV. Description:** Describe proposed change(s) indicated above and attach maps, drawings, and/or parcel information.

Construct a +/- 500 sq. ft. building addition to an existing auto service area. Minor site work required for new foundations, storm drainage tie-in, and concrete walkways. Please refer to attached construction drawings for additional information.

If "Other," the description must explain and advise the Department how such change may or may not affect the site's proposed, ongoing, or completed remedial program (attach additional sheets if needed).

The proposed construction of a +/- 500 sq. ft. building addition to an existing auto service area should not substantively impact the site's operations or the status of the site's completed remedial program.

V. Certification Statement: Where the change of use results in a change in ownership or in responsibility for the proposed, ongoing, or completed remedial program for the site, the following certification must be completed (by owner or designated representative; see §375-1.11(d)(3)(i)):

I hereby certify that the prospective purchaser and/or remedial party has been provided a copy of any order, agreement, Site Management Plan, or State Assistance Contract regarding the Site's remedial program as well as a copy of all approved remedial work plans and reports.

Name: _____
(Signature)

(Date)

(Print Name)

Address1:

Address2:

Phone: _____ E-mail: _____

VI. Contact Information for New Owner, Remedial Party, or CoC Holder: If the site will be sold or there will be a new remedial party, identify the prospective owner(s) or party(ies) along with contact information. If the site is subject to an Environmental Easement, Deed Restriction, or Site Management Plan requiring periodic certification of institutional controls/engineering controls (IC/ECs), indicate who will be the certifying party (attach additional sheets if needed).

☐ Prospective Owner ☐ Prospective Remedial Party ☐ Prospective Owner Representative

Name: _____

Address1:

Address2:

Phone: _____ E-mail: _____

Certifying Party Name:

Address1:

Address2:

Phone: _____ E-mail: _____

VII. Agreement to Notify DEC after Transfer: If Section VI applies, and all or part of the site will be sold, a letter to notify the DEC of the completion of the transfer must be provided. If the current owner is also the holder of the CoC for the site, the CoC should be transferred to the new owner using DEC's form found at <http://www.dec.ny.gov/chemical/54736.html>. This form has its own filing requirements (see 6NYCRR Part 375-1.9(f)).

Signing below indicates that these notices will be provided to the DEC within the specified time frames. If the sale of the site also includes the transfer of a CoC, the DEC agrees to accept the notice given in VII.3 below in satisfaction of the notice required by VII.1 below (which normally must be submitted within 15 days of the sale of the site).

Within 30 days of the sale of the site, I agree to submit to the DEC:

1. the name and contact information for the new owner(s) (see §375-1.11(d)(3)(ii));
2. the name and contact information for any owner representative; and
3. a notice of transfer using the DEC's form found at <http://www.dec.ny.gov/chemical/54736.html> (see §375-1.9(f)).

Name: _____
(Signature)

(Date)

(Print Name)

Address1: _____

Address2: _____

Phone: _____ E-mail: _____

Continuation Sheet

☐ Prospective Owner/Holder ☐ Prospective Remedial Party ☐ Prospective Owner Representative
Name: _____

Address1: _____

Address2: _____

Phone: _____ E-mail: _____

☐ Prospective Owner/Holder ☐ Prospective Remedial Party ☐ Prospective Owner Representative
Name: _____

Address1: _____

Address2: _____

Phone: _____ E-mail: _____

☐ Prospective Owner/Holder ☐ Prospective Remedial Party ☐ Prospective Owner Representative
Name: _____

Address1: _____

Address2: _____

Phone: _____ E-mail: _____

☐ Prospective Owner/Holder ☐ Prospective Remedial Party ☐ Prospective Owner Representative
Name: _____

Address1: _____

Address2: _____

Phone: _____ E-mail: _____

☐ Prospective Owner/Holder ☐ Prospective Remedial Party ☐ Prospective Owner Representative
Name: _____

Address1: _____

Address2: _____

Phone: _____ E-mail: _____

☐ Prospective Owner/Holder ☐ Prospective Remedial Party ☐ Prospective Owner Representative
Name: _____

Address1: _____

Address2: _____

Phone: _____ E-mail: _____



Instructions for Completing the 60-Day Advance Notification of Site Change of Use, Transfer of Certificate of Completion (CoC), and/or Ownership Form

Submit to: Chief, Site Control Section, New York State Department of Environmental Conservation, Division of Environmental Remediation, 625 Broadway, Albany NY 12233-7020

Section I

Description

Site Name

Official DEC site name.
(see <http://www.dec.ny.gov/cfm/externalapps/derexternal/index.cfm?pageid=3>)

DEC Site ID No.

DEC site identification number.

Section II

Contact Information of Person Submitting Notification

Name

Name of person submitting notification of site change of use, transfer of certificate of completion and/or ownership form.

Address1

Street address or P.O. box number of the person submitting notification.

Address2

City, state and zip code of the person submitting notification.

Phone

Phone number of the person submitting notification.

E-mail

E-mail address of the person submitting notification.

Section III

Type of Change and Date

Check Boxes

Check the appropriate box(s) for the type(s) of change about which you are notifying the Department. Check all that apply.

Proposed Date of Change

Date on which the change in ownership or remedial party, transfer of CoC, or other change is expected to occur.

Section IV

Description

Description

For each change checked in Section III, describe the proposed change.
Provide all applicable maps, drawings, and/or parcel information.
If "Other" is checked in Section III, explain how the change may affect the site's proposed, ongoing, or completed remedial program at the site.
Please attach additional sheets, if needed.

Section V Certification Statement

This section must be filled out if the change of use results in a change of ownership or responsibility for the proposed, ongoing, or completed remedial program for the site. When completed, it provides DEC with a certification that the prospective purchaser has been provided a copy of any order, agreement, or State assistance contract as well as a copy of all approved remedial work plans and reports.

Name	The owner of the site property or their designated representative must sign and date the certification statement. Print owner or designated representative's name on the line provided below the signature.
Address1	Owner or designated representative's street address or P.O. Box number.
Address2	Owner or designated representative's city, state and zip code.
Phone	Owner or designated representative's phone number.
E-Mail	Owner or designated representative's E-mail.

Section VI Contact Information for New Owner, Remedial Party, and CoC Holder (if a CoC was issued)

Fill out this section only if the site is to be sold or there will be a new remedial party. Check the appropriate box to indicate whether the information being provided is for a Prospective Owner, CoC Holder (if site was ever issued a COC), Prospective Remedial Party, or Prospective Owner Representative. Identify the prospective owner or party and include contact information. A Continuation Sheet is provided at the end of this form for additional owner/party information.

Name	Name of Prospective Owner, Prospective Remedial Party or Prospective Owner Representative.
Address1	Street address or P.O. Box number for the Prospective Owner, Prospective Remedial Party, or Prospective Owner Representative.
Address2	City, state and zip code for the Prospective Owner, Prospective Remedial Party, or Prospective Owner Representative.
Phone	Phone number for the Prospective Owner, Prospective Remedial Party or Prospective Owner Representative.
E-Mail	E-mail address of the Prospective Owner, Prospective Remedial Party or Prospective Owner Representative.

If the site is subject to an Environmental Easement, Deed Restriction, or Site Management Plan requiring periodic certification of institutional controls/engineering controls (IC/EC), indicate who will be the certifying party(ies). Attach additional sheets, if needed.

Certifying Party

Name Name of Certifying Party.

Address1 Certifying Party's street address or P.O. Box number.

Address2 Certifying Party's city, state and zip code.

Phone Certifying Party's Phone number.

E-Mail Certifying Party's E-mail address.

Section VII Agreement to Notify DEC After Property Transfer/Sale

This section must be filled out for all property transfers of all or part of the site. If the site also has a CoC, then the CoC shall be transferred using DEC's form found at <http://www.dec.ny.gov/chemical/54736.html>

Filling out and signing this section of the form indicates you will comply with the post transfer notifications within the required timeframes specified on the form. If a CoC has been issued for the site, the DEC will allow 30 days for the post transfer notification so that the "Notice of CoC Transfer Form" and proof of it's filing can be included. Normally the required post transfer notification must be submitted within 15 day (per 375-1.11(d)(3)(ii)) when no CoC is involved.

Name Current property owner must sign and date the form on the designated lines. Print owner's name on the line provided.

Address1 Current owner's street address.


Address2 Current owner's city, state and zip code.

DORSCHEL MINI OF ROCHESTER SERVICE BAY ADDITION & ALTERATION

RJ DORSCHEL CORP.

3875 W.HENRITETTA ROAD, ROCHESTER, NY 14623

LABELLA PROJECT NO. 2171059
CONSTRUCTION DOCUMENTS
05/17/2017



DORSCHEL
clear. simple. different.



GENERAL NOTES

- * THE ARCHITECT'S CERTIFICATION ON THIS PROJECT IS ONLY FOR THE CONSTRUCTION WORK SHOWN TO BE DONE. IT DOES NOT CONSTITUTE APPROVAL OF ANY PREEXISTING CONDITIONS OR REVIEW OF THOSE CONDITIONS FOR CODE COMPLIANCE.
- * REFER TO OUTLINE SPECIFICATIONS OR PROJECT MANUAL FOR SPECIFICATIONS AND ADDITIONAL INFORMATION.
- * CONSTRUCTION SHALL CONFORM TO CURRENT EDITIONS OF THE 2015 BUILDING CODE OF NEW YORK STATE, THE 2015 EXISTING BUILDING CODE OF NEW YORK STATE, THE 2015 ENERGY CONSERVATION CONSTRUCTION CODE OF NEW YORK STATE, THE NATIONAL ELECTRICAL CODE 1999 (NEC), THE 2015 PLUMBING CODE OF NEW YORK STATE, THE 2015 MECHANICAL CODE OF NEW YORK STATE, THE 2015 FUEL GAS CODE OF NEW YORK STATE, THE 2015 FIRE CODE OF NEW YORK STATE, NFPA 101 LIFE SAFETY CODE 2012, NFPA 99 STANDARD FOR HEALTHCARE FACILITIES 1999, NEW YORK STATE HEALTH CODE (10NYCRR), GUIDELINES FOR DESIGN AND CONSTRUCTION OF HOSPITAL AND HEALTHCARE FACILITIES 2010 EDITION (NYS DOH) AND 2001 EDITION (JCAHO), (ARTICLE 28 HEALTHCARE ONLY) ADAAG AMERICANS WITH DISABILITIES ACT ACCESSIBILITY GUIDELINES 2004 ED., STANDARDS FOR ACCESSIBLE DESIGN (28 CFR PART 35 & 36, 2004), AND AMERICAN NATIONAL STANDARD FOR ACCESSIBLE AND USABLE BUILDINGS AND FACILITIES (ICC/ANSI A117.1-2003), AS WELL AS ALL OTHER CURRENT LOCAL, STATE AND FEDERAL CODES AND REGULATIONS APPLICABLE TO THIS PROJECT.
- * COMPLY WITH ALL OTHER CURRENT AND IN-FORCE LOCAL, STATE AND FEDERAL CODES AND REGULATIONS APPLICABLE TO THIS PROJECT.
- * GENERAL CONTRACTOR IS RESPONSIBLE FOR ALL MATERIALS, CONSTRUCTION METHODS AND CRAFTSMANSHIP.
- * GENERAL CONTRACTOR TO VERIFY ALL REQUIREMENTS, NOTES AND DIMENSIONS PRIOR TO THE START OF CONSTRUCTION. REPORT ALL DISCREPANCIES TO THE ARCHITECT IMMEDIATELY.
- * GENERAL CONTRACTOR SHALL BE RESPONSIBLE FOR ALL CHANGES TO THESE DOCUMENTS. SITE VISITS MIGHT NOT BE MADE BY THIS ARCHITECT TO VERIFY CONFORMANCE.
- * DUE TO REPRODUCTION QUALITY AND REVISIONS MADE DURING THE DEVELOPMENT OF THESE PLANS THEY MAY NOT REFLECT THE DIMENSIONS NOTED. DO NOT SCALE THE DRAWINGS.
- * THE QUALITY OF CONSTRUCTION IS TO MATCH SURROUNDING AREAS UNLESS OTHERWISE SPECIFIED OR NOTED.
- * ALL MATERIALS ARE TO MATCH EXISTING UNLESS NOTED OTHERWISE. WHEN IN QUESTION, THE CONTRACTOR SHALL CONSULT THE OWNER TO DETERMINE WHAT THE BUILDING'S "STANDARD" IS.
- * IN THE EVENT OF A MATERIAL CONFLICT SPECIFICATIONS SHALL TAKE PRECEDENT OVER DRAWINGS. IN EVENT OF A DIMENSIONAL CONFLICT DRAWINGS TAKE PRECEDENT OVER SPECIFICATIONS.
- * GENERAL CONTRACTOR SHALL SET ALL GRADES.
- * CALL BEFORE YOU DIG. 1-800-962-7962
- * NO PART OF THESE DOCUMENTS MAY BE REPRODUCED WITHOUT WRITTEN PERMISSION FROM LABELLA ASSOCIATES
- * THE DRAWINGS AND SPECIFICATIONS PREPARED BY THE ARCHITECT FOR THIS PROJECT ARE INSTRUMENTS OF THE ARCHITECT'S SERVICE FOR USE SOLELY WITH RESPECT TO THIS PROJECT AND, UNLESS OTHERWISE PROVIDED, LABELLA ASSOCIATES SHALL BE DEEMED THE AUTHOR OF THESE DOCUMENTS AND SHALL RETAIN ALL COMMON LAW, STATUTORY AND OTHER RESERVED RIGHTS, INCLUDING THE COPYRIGHT. THE OWNER SHALL BE PERMITTED TO RETAIN COPIES OF THE DOCUMENTS FOR INFORMATION AND REFERENCE IN CONNECTION WITH THE OWNER'S USE AND OCCUPANCY OF THE PROJECT. THE ARCHITECT'S DOCUMENTS SHALL NOT BE USED BY THE OWNER OR OTHERS FOR ANOTHER PROJECT OR FOR ADDITIONS TO THIS PROJECT EXCEPT AS AGREED TO IN WRITING BY THE ARCHITECT AND WITH APPROPRIATE COMPENSATION TO THIS ARCHITECT.
- * THE FOLLOWING IS AN EXCERPT FROM THE NEW YORK EDUCATION LAW ARTICLE 145 SECTION 7209 AND APPLIES TO THESE DRAWINGS: "IT IS A VIOLATION OF THIS LAW FOR ANY PERSON UNLESS HE IS ACTING UNDER THE DIRECT SUPERVISION OF A LICENSED ARCHITECT TO ALTER AN ITEM IN ANY WAY". IF AN ITEM BEARING THE SEAL OF AN ARCHITECT IS ALTERED, THE ALTERING ARCHITECT SHALL AFFIX HIS SEAL AND NOTATION "ALTERED BY" FOLLOWED BY HIS SIGNATURE AND DATE OF SUCH ALTERATION AND SPECIFIC DESCRIPTION OF THE ALTERATION.

INDEX OF DRAWINGS

ARCHITECTURAL DRAWINGS:

COVER SHEET

- D100 - DEMOLITION FLOOR PLAN
- A001 - SYMBOLS & ABBREVIATIONS
A100 - GROUND FLOOR PLAN
A101 - MEP SCHEMATIC PLAN
A200 - ROOF PLAN & DETAILS
A300 - EXTERIOR ELEVATIONS
A400 - WALL SECTIONS & SECTION DETAILS

STRUCTURAL DRAWINGS:

- S001 - GENERAL NOTES
S002 - SPECIAL INSPECTIONS
S003 - 3D ISOMETRIC VIEW
S101 - FOUNDATION PLAN
S102 - SLAB-ON-GRADE PLAN
S103 - ROOF FRAMING PLAN
S201 - TYPICAL SLAB-ON-GRADE & FOUNDATION DETAILS
S202 - FOUNDATION SECTIONS & DETAILS
S301 - TYPICAL STEEL DETAILS
S302 - FRAMING SECTIONS & DETAILS
S401 - TYPICAL MASONRY DETAILS


NYS BUILDING CODE DATA

CODE REVIEW INFORMATION			
2015 BUILDING CODE OF NEW YORK STATE			
BUILDING DATA		FIRE RESISTANCE RATINGS	
USE DESCRIPTION	NYS REQD.	PROVIDED	
SPECIAL REQUIREMENTS	N/A	N/A	
OCCUPANCY	S-1		
MIXED OCCUPANCY	N/A	N/A	
CLASSIFICATION OF WORK	EBC NYS CHAPTER 5	ADDITION & ALT. LVL 2	COMPLIES
CONSTRUCTION TYPE	NYS CHAPTER 6	2B	COMPLIES
NO. OF STORIES	NYS BC504	55'	1-STORY
BUILDING HEIGHT	NYS BC506	2 STORIES	COMPLIES
ALLOWABLE BUILDING AREA	NYS BC506.3	17,500	
INCREASE FOR FRONTAGE	NYS BC506.2	NR	
INCREASE FOR SPRINKLERS (1 STORY)	TABLE BC506.2	NR	
TOTAL MAXIMUM ALLOWABLE BLDG AREA	NYS BC506	17,500	
EXISTING BUILDING GROSS AREA		3,330 SF	S-1 OCC.
BUILDING ADDITION GROSS AREA		462 SF	S-1 OCC.
TOTAL S-1 BUILDING GROSS AREA		3,792 SF	COMPLIES
NUMBER OF OCCUPANTS	NYS BC1004.1	200 SF PER OCC.	3,792 SF / 200 SF = 18 OCC.
EXIT WIDTH PER OCCUPANT	NYS BC1005.3	0.2" PER OCC.	19 * 0.2" = 3.8" (COMPLIES)
EXIT WIDTH	NYS BC1005.3	0.2" PER OCC.	19 * 0.2" = 3.8" (COMPLIES)
MIN. NO. OF EXITS	NYS BC1006	1-EXIT <29 OCC.	COMPLIES
ONE EXIT RULES	NYS BC1006.2 & BC1006.3.1	1-EXIT <29 OCC.	COMPLIES
DOORS	NYS BC1010.1.1	32" CLEAR	36" COMPLIES
STAIRWAY WIDTH	NYS BC1011.2	N/A	N/A
CORRIDOR WIDTH	NYS BC1005.1 & BC1020.2	N/A	N/A
MAXIMUM TRAVEL DISTANCE	NYS TABLE BC1017.2	200'	COMPLIES
MAXIMUM COMMON PATH OF TRAVEL	NYS TABLE BC1006.2.1	100'	COMPLIES
MAXIMUM DEAD END CORRIDOR	NYS BC1020.4	N/A	N/A
CONCEALED SPACE DRAFTSTOPPING	NYS BC718	N/A	N/A
SMOKE COMPARTMENT	NYS CHAPTER 4	NR	NR
INTERIOR FINISHES CLASS @ EXITS & VERT. EXITS		B	COMPLIES
INTERIOR FINISHES CLASS @ EXITS ACCESS	T-B0803.1.1	C	COMPLIES
INTERIOR FINISHES CLASS @ ROOMS	T-B0803.1.1	C	COMPLIES
FIRE EXTINGUISHER SPACING	FIRE CODE OF NYS FC906	75'	1/3,000 SF
AUTOMATIC SPRINKLER SYSTEM	NYS BC903.2.9	YES	YES
STANDPIPE SYSTEM	NYS SECTION BC905	YES	YES
SMOKE & FIRE DETECTION	NYS SECTION BC907	YES	YES
FIRE ALARM SYSTEM	NYS SECTION BC907	YES	YES
ACCESSIBILITY DESIGN	BC NYS CHAPTER 11		
VERTICAL ACCESS REQUIRED	NYS BC1104.4	YES	NO
ACCESSIBLE ENTRANCE	NYS BC1105	YES	NO
PASSENGER LOADING ZONES	NYS BC1106.7	YES	NO


SCOPE OF WORK

- CONSTRUCT A BUILDING ADDITION APPROXIMATELY 500 SF TO AN EXISTING SERVICE WING TO PROVIDE FOR A RECONFIGURED SPACE THAT WILL INCLUDE A WASH BAY, CAR LIFT, STORAGE, AND MISCELLANEOUS SERVICE WORK SPACE. EXISTING EQUIPMENT TO BE RELOCATED. MINOR SITE WORK REQUIRED FOR NEW FOUNDATIONS, STORM DRAINAGE TIE-IN AND CONCRETE WALKWAYS.


SITE PLAN



Date & Time: 5/17/2017 11:17 AM Bc.2
Path: C:\RD Dorschel Corp\2171059 - Mini Cooper Dealer Addition\Drawings\Arch\3-2D\0100 - Demo Plan\2171059.dwg



1
D100
DEMOLITION PLAN
SCALE: 1/4" = 1'-0"



SYMBOLS

EXISTING CONSTRUCTION TO REMAIN

EXISTING CONSTRUCTION TO BE REMOVED

EXISTING DOOR TO REMAIN

EXISTING DOOR AND FRAME TO BE REMOVED

NOT IN SCOPE OF WORK (EXISTING CONSTRUCTION)

TEMPORARY WALL

SYMBOLS

1

REMOVE EXISTING MASONRY WALL TO DEPTH SHOWN ON STRUCTURAL DRAWINGS

2

REMOVE & SALVAGE EXISTING DOOR, FRAME TO BE REMOVED. PREPARE DOOR FOR INSTALLATION

2A

REMOVE DOOR, FRAME, AND HARDWARE

2B

REMOVE OVERHEAD DOOR, FRAME, AND OPENER FOR RELOCATION

3

REMOVE EXISTING TRENCH DRAIN ASSEMBLY, CUT & CAP SANITARY LINE AS REQUIRED.

4

REMOVE & SALVAGE SECURITY PANEL AND ALL ACCESSORIES. PREPARE FOR REINSTALLATION

5

DISCONNECT & SALVAGE SERVICE EQUIPMENT. EQUIPMENT TO BE STORED UNTIL ADDITION IS COMPLETE. COORDINATE W/OWNER

6

REMOVE AND SALVAGE ALL LIFT EQUIPMENT & ACCESSORIES

7

REMOVE GUTTER AND DOWNSPOUT DOWN TO STORM DRAIN TIE-IN. EXCAVATE STORM LINE AS REQUIRED AND REMOVE UNDER BUILDING FOOTPRINT PREPARE STORM LINE FOR RECONNECTION

8

REMOVE PORTION OF EXTERIOR WALL ASSEMBLY TO ACCOMMODATE LOUVER VENT. PREPARE OPENING AS REQUIRED.

9

GRIND AND/OR REMOVE IN ENTIRETY TILE FLOOR FINISH. PREPARE SLAB FOR NEW EPOXY FINISH

10

REMOVE EXISTING MEZZANINE, RAILINGS, AND MEZZANINE STRUCTURE

11

SAW-CUT & EXCAVATE AS REQUIRED EXISTING ASPHALT DRIVEWAY WITHIN BUILDING ADDITION FOOTPRINT. REMOVE ANY ORGANIC FILL. PREPARE FOR NEW POURED CONCRETE APRON. PATCH IN TO EXISTING ASPHALT.

12

REMOVE EXISTING ROOFING JOISTS, DECKING, AND MEMBRANE

13

REMOVE EXISTING ALUMINUM COPING & BLOCKING DOWN TO MASONRY BLOCK WALL. PREPARE TOP OF MASONRY FOR NEW COURSING. REFER TO EXTERIOR ELEVATIONS & ROOF PLAN FOR MORE INFORMATION

14

REMOVE EXISTING SLAB ON GRADE AS REQUIRED FOR NEW TRENCH DRAINS AND LIFT EQUIPMENT PIT. REMOVE SUB-BASE IF INADEQUATE. PREPARE FOR NEW SLAB POUR

15

SAW-CUT AND REMOVE EXISTING CONC. SLAB AS REQUIRED & PREPARE FOR NEW SLAB POUR

16

REMOVE AND RELOCATE EXISTING WALL PACKS. COORDINATE NEW LOCATIONS WITH OWNER

17

REMOVE AND RELOCATE EXISTING BATTERY CHARGING SYSTEM

18

REMOVE AND RELOCATE EXISTING SECURITY CAMERA SYSTEM

19

REMOVE EXISTING FURNACE VENT

20

CUT AND CAP EXISTING HOSE BIB

It is a violation of New York Education Law Article 145 Sec.7209, for any person, unless acting under the direction of a licensed architect, professional engineer, or land surveyor, to alter an item in any way. If an item bearing the seal of an architect, engineer, or land surveyor is altered; the altering architect, engineer, or land surveyor shall affix to the item their seal and notation "altered by" followed by their signature and date of such alteration, and a specific description of the alteration.

© 2017 LaBella Associates

DORSCHEL MINI OF ROCHESTER

3875 WEST HENRIETTA ROAD
ROCHESTER, NY 14623

**SERVICE BAY ADDITION
& ALTERATION**



--	--	--
--	--	--
--	--	--
--	--	--
--	--	--

NO:	DATE:	DESCRIPTION:
-----	-------	--------------

REVISIONS:	
PROJECT NUMBER:	2171059

DRAWN BY:	CD
-----------	----

REVIEWED BY:	SM
--------------	----

ISSUED FOR:	CONSTRUCTION
-------------	--------------

ISSUED DATE:	5/17/2017
--------------	-----------

DRAWING NAME:	
---------------	--

**DEMOLITION
FLOOR PLAN**

DRAWING NUMBER:

ABBREVIATIONS

THIS LIST REPRESENTS COMMON ABBREVIATIONS WHICH MAY BE USED IN GARDNER PLUS ARCHITECTS CONSTRUCTION DOCUMENTS. OTHER INDUSTRY ACCEPTED ABBREVIATIONS MAY ALSO BE USED.

A

AB ANCHOR BOLT
ABV ABOVE
A/C AIR CONDITIONING
ACoust ACOUSTICAL
ACT ACOUSTICAL CEILING TILE
ACR ACRYLIC
AD AREA DRAIN
ADH ADHESIVE
ADJ ADJUSTABLE
ADTN ADDITION
A.F.F. ABOVE FINISH FLOOR
AGGR AGGREGATE
AHU AIR HANDLING UNIT
ALUM ALUMINUM
ALT ALTERNATE
ANCH ANCHOR
ANOD ANODIZED
ANSI AMERICAN NATIONAL STANDARDS INSTITUTE
AP ACCESS PANEL
APA AMERICAN PLYWOOD ASSOCIATION
APPL APPLICABLE
APROX APPROXIMATE
ARCH ARCHITECTURAL
ASB ASBESTOS
ASPH ASPHALT
AUTO AUTOMATIC
A/V AUDIO/VISUAL ALARM
AWI WOODWORK INSTITUTE

B

BC BOTTOM OF CURB
BD BOARD
BITUM BITUMINOUS
BLDG BUILDING
BLK BLOCK
BLKGBLOCKING
BM BEAM
BOS BOTTOM OF STEEL
BOTTBOTTOM
BSMTBASEMENT
BR BUMPER RAIL
BRDG BRIDGING
BTWN BETWEEN

C

CAB CABINET
CB CARPET BASE
CB CATCH BASIN
CEM CEMENT
CF CUBIC FEET
CFCI CONTRACTOR FURNISHED, CONTRACTOR INSTALLED
CFMFCOLD FORMED METAL FRAMING
CG CORNER GUARD
CH COAT HOOK
CI CAST IRON
CJ CONTROL JOINT
CKBD CHALKBOARD
CL CENTERLINE
CLG CEILING
CLK CAULKING
CLR CLEAR
CLSTCLOSET
CMT CERAMIC MOSAIC TILE
CMU CONCRETE MASONRY UNIT
CNTRCOUNTER
CO CLEAN OUT
COL COLUMN
CONC CONCRETE
CONN CONNECTION
CONST CONSTRUCTION
CONTCONTINUOUS
CONTR CONTRACTOR
COORD COORDINATE
CORR CORRIDOR
CPT CARPET
CR CARD READER
CT CERAMIC TILE
CTB CERAMIC TILE BASE
CRS COURSGING
CTR CENTER
CTSKCOUNTERSUNK
CW COLD WATER
CY CUBIC YARD

D

DBL DOUBLE
DEPTDEPARTMENT
DET DETAIL
DF DRINKING FOUNTAIN
DIA DIAMETER
DIM DIMENSION
DISP DISPENSER
DN DOWN
DR DOOR
DSP DOWNSPOUT
DSP DRY STANDPIPE
DWG DRAWING
DWR DRAWER

E

EA EAST
EACH EACH
EB EXPANSION BOLT
EC ELECTRICAL CONTRACTOR
EF EXHAUST FAN
EHF EXTERIOR INSULATION & FINISH SYSTEM
EJ EXPANSION JOINT
ELEV ELEVATION
ELEC ELECTRICAL
EL ELEVATOR
EMERG EMERGENCY
ENC ENCLOSURE
ENT ENTRANCE
EP ELECTRICAL PANEL
EPY EPOXY PAINT

E (CONT'D)

EQ EQUAL
EQUIP EQUIPMENT
ESC ESCALATOR
ETR EXISTING TO REMAIN
EW EACH WAY
EWC ELECTRIC WATER COOLER
EXH EXHAUST
EXIST EXISTING
EXP EXPOSED
EXT EXPANSION EXTERIOR

F

FA FIRE ALARM
FCU FAN COIL UNIT
FD FLOOR DRAIN
FDN FOUNDATION
FE FIRE EXTINGUISHER
FEC FIRE EXTING. CABINET
FF FINISH FLOOR
FG FIBERGLASS
FHC FIRE HOSE CABINET
FHV FIRE HOSE VALVE
FIN FINISH
FL FIRE-LITE SAFETY GLASS
FLASH FLASHING
FLR FLOOR
FLUOR FLUORESCENT
FOC FACE OF CONCRETE
FOF FACE OF FINISH
FOS FACE OF STUDS
FRP FIBERGLASS REINFORCED PANEL
FP FIREPROOF
FS FULL SIZE
FT FOOT OR FEET
FTG FOOTING
FTWDFIRE TREATED WOOD
FURRFURRING

G

GA GAUGE
GALV GALVANIZED
GB GRAB BAR
GC GENERAL CONTRACTOR
GFI GROUND FAULT INTERRUPTER
QL GND
GR GRADE
GT GLAZED TILE
GTB GLAZED TILE BASE
GWT GLAZED WALL TILE
GWB GYPSUM WALL BOARD

H

HB HOSE BIB
HC HANDICAPPED
HCC HOLLOW CORE
HDBD HARD BOARD
HDWD HARDWOOD
HDR HEADER
HDWR HARDWARE
HI HIGH IMPACT
HM HOLLOW METAL
HRZ HORIZONTAL
HR HOUR
HT HAND RAIL
HT HUMIDIFIER
HVAC HEATING/VENTILATION/AIR CONDITIONING
HWP HIGH IMPACT WALL PROTECTION
HYD HYDRANT
HW HOT WATER
HWH HOT WATER HEATER

I

ID INSIDE DIAMETER
ILO IN LIEU OF
IN INCH
INSUL INSULATION
INT INTERIOR
INV INVERT
IVH IV HOOK

J

JAN JANITOR
JC JANITOR CLOSET
JST JOIST
JT JOINT

K

KD KNOCK DOWN
KIT KITCHEN
KOP KICK OUT PANEL
KP KICK PLATE
KYN KYNAR

L

LAB LABORATORY
LAM LAMINATE
LAV LAVATORY
LC/M LEAD CORE/METAL
LC/W LEAD CORE/WOOD
LG LEAD GLASS
LGMFLIGHT GA. MTL. FRAMING
LH LEFT HAND
LIN LINEN
LHR LEFT HAND REVERSE
LKR LOCKER
LLH LONG LEG HORIZONTAL
LLV LONG LEG VERTICAL
LMG LAMINATED GLASS
LT LIGHT
LV LOUVER
LVL LAMINATED VENEER LUMBER

M

MAX MAXIMUM
MC MEDICINE CABINET
MC MECHANICAL CONTRACTOR
MDO MEDIUM DENSITY OVERLAY
ME MATCH EXISTING
ME MECHANICAL
MEMB MEMBRANE
MTL METAL
MFR MANUFACTURER
MH MANHOLE
MIN MINIMUM
MIR MIRROR
MISC MISCELLANEOUS
MO MASONRY OPENING
MTD MOUNTED
MTC MOUNTING
MTRL MATERIAL
MUL MULLION

N

N NORTH
NAT NATURAL
NEC NATIONAL ELECTRIC CODE
NEC NECESSARY
NIC NOT IN CONTRACT
NLC NIGHT LIGHT
NO NUMBER
NOM NOMINAL
NTS NOT TO SCALE

O

OBS OBSCURE
OC ON CENTER
OD OUTSIDE DIAMETER
OFF OFFICE
OHD OVERHEAD DOOR
OFCI OWNER FURNISHED, CONTRACTOR INSTALLED
OFOW OWNER FURNISHED, OWNER INSTALLED
OPNG OPENING
OPP OPPOSITE
OSB ORIENTED STRAND BOARD

P

PARTPARTITION
PART.BD PARTICLE BOARD
PC PLUMBING CONTRACTOR
PC PRE-CAST
PD PENCIL DRAWER
PG PLEXIGLASS
PL PLATE
P. LAM PLASTIC LAMINATE
PLASPLASTER
PLYWD PLYWOOD
PP POWER POLE
PR PAIR
PSF POUNDS PER SQUARE FOOT
PSI POUNDS PER SQUARE INCH
PSL PARALLEL STRAND LUMBER
PT PAINT
PTD PAPER TOWEL DISPENSER
PTD/R COMBO PAPER TOWEL DISPENSER & RECEPTACLE
PTM PATCH TO MATCH
PTWD PRESSURE TREATED WOOD

Q

QT QUARRY TILE
QTB QUARRY TILE BASE

R

R RISER
RAD RADIUS
RAF RAISED ACCESS FLOOR
RB RESILIENT BASE
RD ROOF DRAIN
REF REFRIGERATOR
REF REFERENCE
REG REGISTER
REIN REINFORCE
REQ REQUIRE(MENT)
REQ'D REQUIRED
RESIL RESILIENT
REV REVISION / REVISE
RH RIGHT HAND
RHR RIGHT HAND REVERSE
RL ROOF LEADER
RM ROOM
RO ROUGH OPENING
RUB RUB RAIL
RT RADIAL TILE
RTU ROOF TOP UNIT

S

S SOUTH
SC SOLID CORE
SCD SEAT COVER DISPENSER
SCH SCHEDULE
SD SOAP DISPENSER
SF SQUARE FOOT
SH SHELF
SHR SHOWER
SHT SHEET
SIM SIMILAR
SLR SEALER
SLR SHEET METAL
SM SANITARY NAPKIN DISP.
SND SANITARY NAPKIN DISP. & RECEPTACLE
SND/R SOLID SURFACE
SOL SPECIFICATION
SQ SQUARE
SS STAINLESS STEEL
ST STAIN
STA STATION
STD STANDARD
STL STEEL
STORSTORAGE
STR STRETCHER
STRUCT STRUCTURAL
SUSP SUSPENDED
SV SHEET VINYL
SY SQUARE YARD
SYM SYMMETRICAL

T

T TREAD
TB TOWEL BAR
TEL TELEPHONE
TEMPTEMPORARY
TG TEMPERED GLASS
T & G TONGUE & GROOVE
THK THICK
TKBDTACK BOARD
TOB TOP OF BEAM
TOC TOP OF CURB
TOPL TOP OF PLATE
TOS TOP OF STEEL
TP TOP OF PAVEMENT
TPD TOILET PAPER DISPENSER
TREAT TREATMENT
TRZ TERRAZZO
TOW TOP OF WALL
TV TELEVISION
TYP TYPICAL

U

UC UNDER COUNTER
UL UNDERWRITER'S LABORATORY
UNF UNFINISHED
UNO UNLESS NOTED OTHERWISE
URN URNINAL

V

VB VAPOR BARRIER
VCT VINYL COMPOSITION TILE
VERT VERTICAL
VEST VESTIBULE
VIF VERIFY IN FIELD
VWC VINYL WALL COVERING
VWF VINYL WALL FABRIC

W

W WEST
W WITH
WC WATER CLOSET
WD WOOD
WDW WINDOW
WIC WALK IN CLOSET
WG WIRE GLASS
W/O WITHOUT
WP WATERPROOF
WT WEIGHT

Y

YD YARD
YD YARD DRAIN


Z

N/A


MISCELLANEOUS

PERPENDICULAR
DIAMETER
NUMBER
ANGLE
AT
CENTER LINE
PROPERTY LINE
PLUS / MINUS
SQUARE FEET
DEGREE

MATERIAL SYMBOLS




DRAWING SYMBOLS



TYPICAL MOUNTING HEIGHTS


(UNLESS NOTED OTHERWISE ELSEWHERE IN DRAWINGS; CONTACT ARCHITECT REGARDING ANY DISCREPANCIES IN CONFLICT WITH ALL APPLICABLE CODES)




MEP/FP SYMBOLS

(UNLESS NOTED OTHERWISE PER DRAWINGS BY OTHERS)

MECHANICAL



ELECTRICAL



It is a violation of New York Education Law Article 145 Sec.7209, for any person, unless acting under the direction of a licensed architect, professional engineer, or land surveyor, to alter an item in any way. If an item bearing the seal of an architect, engineer, or land surveyor is altered; the altering architect, engineer, or land surveyor shall affix to the item their seal and notation "altered by" followed by their signature and date of such alteration, and a specific description of the alteration.

DORSCHEL MINI OF ROCHESTER

3875 WEST HENRIETTA ROAD
ROCHESTER, NY 14623

SERVICE BAY ADDITION & ALTERATION



--	--	--	--
--	--	--	--
--	--	--	--
--	--	--	--

NO:	DATE:	DESCRIPTION:
-----	-------	--------------

REVISIONS:
PROJECT NUMBER: 2171059

DRAWN BY: CD

REVIEWED BY: SM

ISSUED FOR: CONSTRUCTION

ISSUED DATE: 5/17/2017

DRAWING NAME:

SYMBOLS & ABBREVIATIONS

DRAWING NUMBER:


DOOR SCHEDULE

DOOR MARK	DOOR					GLASS	LOUVER	RATING	FRAME			HARDWARE COMPONENTS	DETAIL NO.	NOTE NO.
	OPENING SIZE	TYPE	THICK.	CONST.	FINISH				TYPE	CONST.	FINISH			
DOOR-1	ETR 3'-0" X 7'-0"	EX	EX	EX	PT	---	---	---	1	HM	PT	B, CL, L-S, T, WS	---	1
DOOR-2	ETR 10'-0" X 10'-0"	EX	EX	EX	PT	---	---	---	EX	EX	EX	EXISTING	---	2
DOOR-3	(2) 3'-0" X 7'-0"	HM	1-3/4"	HM	PT	---	---	45 MIN.	2	HM	PT	(2)B, (2) CL, L-S, FL-IM, A, P	---	3


DOOR ABBREV.

CONSTRUCTION:	HARDWARE:
HM HOLLOW METAL	A ASTRAGAL
ALUM. ALUMINUM	B BUTTS
	CL CLOSER (COORDINATED)
	FL-IM FLUSH BOLTS - MANUAL
PT PAINT	L-S LOCKSET - STORAGE
AN. ANODIZED	P PULL
	T THRESHOLD
	WS WEATHERSTRIPPING

FRAME TYPE




LOUVER TYPE



DOOR NOTES

- DOOR TO BE SALVAGED AND RELOCATED. PROVIDE NEW ANODIZED, ALUMINUM FRAME WITH FINISH TO MATCH EXISTING. VERIFY IN FIELD
- EXISTING OVERHEAD DOOR TO BE RELOCATED. COORDINATE OPENING REQUIREMENTS WITH VENDOR AND OWNER. INSTALL OVERHEAD DOOR PER MANUFACTURERS RECOMMENDATIONS.
- REUSE HARDWARE FROM EXISTING DOUBLE DOOR IF POSSIBLE. PROVIDE HARDWARE AS SCHEDULED IF NEW HARDWARE IS REQUIRED



2 CONTROL JOINT DETAIL
SCALE: 1-1/2" = 1'-0"

SYMBOLS


	EXISTING CONSTRUCTION TO REMAIN
	NEW CONSTRUCTION
	NEW DOOR OPENING WITH DOOR SYMBOL
	EXISTING DOOR TO REMAIN
	ROOM NUMBER - SEE ROOM FINISH SCHEDULE SHEET AX.XX
	DETAIL REFERENCE: DETAIL NUMBER (TOP) SHEET NUMBER (BOTTOM)
	ELEVATION REFERENCE: ELEVATION NUMBER (TOP) SHEET NUMBER (BOTTOM)
	LOUVER - (SEE SCHEDULES FOR MORE INFO)
	NEW FLOOR DRAIN
	NEW TRENCH DRAIN ASSEMBLY (COMPOSITE MATERIAL)
	OVERHEAD WATERPROOF SCREEN SYSTEM (BY OWNER) INSTALLED (BY G.C.)
	WALL MTD. FIRE EXTINGUISHER
	12" CMU (60-MIN. FIRE RATING) - PAINTED
	NOT IN SCOPE OF WORK

KEYNOTES


- PROVIDE IN-SLAB DOOR OPENING SENSOR. COORDINATE WITH VENDOR. COORDINATE POWER / CONDUIT REQUIREMENTS WITH VENDOR
- COORDINATE LIFT PIT CONSTRUCTION, LOCATION, AND POWER REQUIREMENTS WITH VENDOR. COORDINATE CONTROL-HUB LOCATION WITH OWNER. REFER TO STRUCTURAL DRAWINGS FOR PIT DIMENSIONS AND CONSTRUCTION. INSTALL PER MANUFACTURERS RECOMMENDATIONS. FLOAT SLAB FOR POSITIVE DRAINAGE
- PROVIDE BOND BEAM PER STRUCTURAL DWGS
- NEW SLAB TO BE SEALED AND COATED WITH APPROPRIATE EPOXY FLOORING PRODUCT. INSTALL PER MANUFACTURERS RECOMMENDATIONS
- SLOPE NEW SITE WORK / ASPHALT FOR POSITIVE DRAINAGE TO EXISTING STORM SYSTEM

ARCHITECTURAL NOTES

- ALL DIMENSIONS TO BE TAKEN FROM FINISHED FACE OF MASONRY OF WALL UNLESS INDICATED OTHERWISE
- COORDINATE NEW DATA & POWER LOCATIONS WITH OWNER
- CONTRACTOR SHALL PROVIDE BLOCKING AS REQUIRED FOR ALL EQUIPMENT INSTALLATION
- FURNITURE AND EQUIPMENT TO BE PROVIDED BY OWNER. VERIFY FINAL LOCATION AND REQUIREMENTS OF ALL EQUIPMENT WITH OWNER
- PATCH ALL EXISTING WALLS AS REQUIRED; PREPARE ALL WALLS FOR PAINT
- REPAINT ALL EXISTING WALLS WITHIN SERVICE BAY. COORDINATE PAINT TYPE & COLOR SELECTION WITH OWNER



1 GROUND FLOOR PLAN
SCALE: 1/4" = 1'-0"



LABELLA

300 State Street | Engineering
Suite 201 | Architecture
Rochester, NY 14614
P: (585) 454-6110 | Environmental
Planning

www.labellapc.com



It is a violation of New York Education Law Article 145 Sec.7209, for any person, unless acting under the direction of a licensed architect, professional engineer, or land surveyor, to alter an item in any way. If an item bearing the seal of an architect, engineer, or land surveyor is altered; the altering architect, engineer, or land surveyor shall affix to the item their seal and notation "altered by" followed by their signature and date of such alteration, and a specific description of the alteration.

© 2017 LaBella Associates

DORSCHEL MINI OF ROCHESTER

3875 WEST HENRIETTA ROAD
ROCHESTER, NY 14623

SERVICE BAY ADDITION & ALTERATION



--	--	--
--	--	--
--	--	--
--	--	--
--	--	--

NO:	DATE:	DESCRIPTION:
-----	-------	--------------

REVISIONS:	
PROJECT NUMBER:	2171059

DRAWN BY:	CD
-----------	----

REVIEWED BY:	SM
--------------	----

ISSUED FOR:	CONSTRUCTION
-------------	--------------



ISSUED DATE:	5/17/2017
--------------	-----------

DRAWING NAME:	
---------------	--

GROUND FLOOR PLAN

DRAWING NUMBER:	
-----------------	--

A100



SYMBOLS	
	TWO-WAY SWITCH
	THREE-WAY SWITCH
	110v RECEPTACLE (MIN. 36" A.F.F.) UNLESS NOTED OTHERWISE COORDINATE HEIGHT A.F.F. W/ OWNER
	GROUND FAULT CIRCUIT INTERRUPTER (MIN. 36" A.F.F.) UNLESS OTHERWISE NOTED OTHERWISE COORDINATE HEIGHT A.F.F. W/ OWNER
	110v CEILING MOUNTED QUAD RECEPTACLE (MIN. 36" A.F.F.) UNLESS OTHERWISE NOTED OTHERWISE COORDINATE HEIGHT A.F.F. W/ OWNER
	EXHAUST FAN FULLY DUCTED TO EXTERIOR
	WALL MOUNTED EXIT LIGHT
	BATTERY POWERED EMERGENCY LIGHT
	LIGHT FIXTURES TO MATCH EXISTING COORDINATE W/ OWNER
	WALL MOUNTED FIXTURE - COORDINATE W/ OWNER
	FLOOR CLEANOUT
	AUDIBLE VISUAL FIRE ALARM DEVICE
	FIRE ALARM PULL STATION
	EXIT SIGNAGE

- KEYNOTES**
- RELOCATE OPERABLE LOUVER SYSTEM AND HUMIDISTAT
 - PROVIDE NEW LOUVER SYSTEM TO MATCH EXISTING. PROVIDE IN-LINE DUCT FAN SUFFICIENT TO EXHAUST ROOM. WIRE FAN TO THERMOSTAT
 - RELOCATE BATTERY CHARGING SYSTEM. CONSULT OWNER ON EXACT LOCATION
 - RELOCATE ONE OF THE TWO HEATING SYSTEMS IN THE EXISTING SERVICE BAY. RELOCATE ALL CONTROLS, WIRING, AND ACCESSORIES.
 - RELOCATE TIRE CHANGER AND TIRE BALANCER. COORDINATE WITH OWNER ON EXACT LOCATION
 - TIE INTO EXISTING AIR SYSTEM. COORDINATE WITH OWNER ON ALL AIR DROP LOCATIONS
 - PROVIDE NECESSARY CONTROL CONDUIT / WIRING FOR ALIGNMENT PIT CONTROLS
 - PROVIDE NECESSARY CONTROL CONDUIT / WIRING FOR ALIGNMENT PIT CONTROLS
 - CONTRACTOR TO COORDINATE WITH DOOR OPENING SENSOR VENDOR PRIOR TO SLAB POUR
 - TIE INTO EXISTING STORM DRAIN (ENSURE PIPING LEADS TO OIL SEPARATOR)
 - TIE ROOF DRAINS INTO EXISTING STORM DRAINS
 - PROVIDE AND INSTALL CATCH BASIN / CLEANOUT AND TIE-INTO EXISTING FCO.
 - PROVIDE HOSE BIB AT THIS LOCATION. MATCH HOSE BIB STYLE AND PLUMBING REQUIREMENTS WITH EXISTING

- HVAC NOTES**
- RELOCATE AND INSTALL ALL HVAC EQUIPMENT PER CODE. CONSULT OWNER ON HVAC EQUIPMENT TO BE RELOCATED
- PLUMBING NOTES**
- ALL UNDER SLAB SANITARY LINES TO BE CAST IRON, OR SCHEDULE 80 PVC
 - CONTRACTOR TO VERIFY COMPLIANT VENTING IS INSTALLED IN PLUMBING SYSTEM. VENTING SHALL BE INSTALLED IN (2) REMOTE LOCATIONS OF NEW PLUMBING WORK AS REQUIRED.

- ELECTRICAL NOTES**
- ALL ELECTRICAL DEVICES SHALL BE WIRED PER APPLICABLE CODE & INSPECTED
 - RECEPTACLE AND SWITCH LOCATIONS SHOWN AS REFERENCE ONLY. COORDINATE W/ OWNER & TENANT
 - INSTALL ALL DEVICES PER MANUFACTURERS RECOMMENDATIONS
 - COORDINATE DATA DROP LOCATIONS W/ OWNER & TENANT

LABELLA

300 State Street | Suite 201 | Rochester, NY 14614 | P: (585) 454-6110 | www.labellapc.com

It is a violation of New York Education Law Article 145 Sec.7209, for any person, unless acting under the direction of a licensed architect, professional engineer, or land surveyor, to alter an item in any way. If an item bearing the seal of an architect, engineer, or land surveyor is altered; the altering architect, engineer, or land surveyor shall affix to the item their seal and notation "altered by" followed by their signature and date of such alteration, and a specific description of the alteration.

© 2017 LaBella Associates

DORSCHEL MINI OF ROCHESTER
3875 WEST HENRIETTA ROAD
ROCHESTER, NY 14623

SERVICE BAY ADDITION & ALTERATION

DORSCHEL
clear. simple. different.


NO.	DATE:	DESCRIPTION:
1		
2		
3		
4		
5		
6		
7		
8		
9		
10		
11		
12		
13		
REVISIONS:		
PROJECT NUMBER: 2171059		
DRAWN BY: CD		
REVIEWED BY: SM		
ISSUED FOR: CONSTRUCTION		
ISSUED DATE: 5/17/2017		
DRAWING NAME:		

**MEP SCHEMATIC PLANS
(REFERENCE ONLY)**


DRAWING NUMBER:

A101


Date & Time: 5/17/2017 11:15 AM Bx:2
Path: C:\R\Dorschel Corp\2171059 - Mini Cooper Dealer Addition\Drawings\Arch\3-CD\A200 - Roof Plan.2171059.dwg




7 ROOFING TRANSITION DETAIL
A200 SCALE: NTS




6 MEMBRANE TERMINATION DETAIL
A200 SCALE: NTS



4 ROOF DRAIN DETAIL
A200 SCALE: NTS




5 GRAVEL STOP DETAIL
A200 SCALE: NTS



3 SCUPPER DRAIN DETAIL
A200 SCALE: NTS

SYMBOLS	
	DETAIL REFERENCE: DETAIL NUMBER (TOP) SHEET NUMBER (BOTTOM)




2 DEMO ROOF PLAN
A200 SCALE: 1/4" = 1'-0"

SYMBOLS

- REMOVE EXISTING ROOFING JOISTS, DECKING, AND MEMBRANE
- REMOVE EXISTING ALUMINUM COPING & BLOCKING DOWN TO MASONRY BLOCK WALL. PREPARE TOP OF MASONRY FOR NEW COURSING. REFER TO EXTERIOR ELEVATIONS & ROOF PLAN FOR MORE INFORMATION
- REMOVE EXISTING FURNACE VENT

GENERAL NOTES

- PROVIDE TAPERED INSULATION TO DIRECT WATER TO NEW ROOF DRAIN (MIN. 1/2" PER 1'-0" SLOPE)
- PROVIDE TAPERED INSULATION INFILL BETWEEN NEW AND EXISTING ROOFING SURFACES TO ALIGN ROOFING MEMBRANES. REFER TO 7/A200 FOR MORE INFORMATION
- PROVIDE NEW WHITE MEMBRANE ROOFING SYSTEM. REFER TO SPECIFICATION FOR MORE INFORMATION
- PROVIDE NEW ALUMINUM THOUGH WALL SCUPPER, COLLECTION BOX, AND DOWNSPOUT. FINISH TO MATCH EXISTING BUILDING COPING. REFER TO 1/A400 AND 3/A200 FOR MORE INFORMATION
- PROVIDE ROOF DRAIN. REFER TO DETAILS FOR MORE INFORMATION
- PROVIDE NEW ALUMINUM COPING TO MATCH EXISTING BUILDING. NOTE THAT THE SOUTH ELEVATION COULD BE A GRAVEL STOP CONDITION BASED ON EXISTING STRUCTURE HEIGHTS. CONTRACTOR TO COORDINATE COPING REQUIREMENTS



1 ROOF PLAN
A200 SCALE: 1/4" = 1'-0"

LABELLA

300 State Street | Engineering
Suite 201 | Architecture
Rochester, NY 14614
P: (585) 454-6110 | Planning

www.labellapc.com



It is a violation of New York Education Law Article 145 Sec.7209, for any person, unless acting under the direction of a licensed architect, professional engineer, or land surveyor, to alter an item in any way. If an item bearing the seal of an architect, engineer, or land surveyor is altered; the altering architect, engineer, or land surveyor shall affix to the item their seal and notation "altered by" followed by their signature and date of such alteration, and a specific description of the alteration.

© 2017 LaBella Associates

DORSCHEL MINI OF ROCHESTER

3875 WEST HENRIETTA ROAD
ROCHESTER, NY 14623

SERVICE BAY ADDITION & ALTERATION



DORSCHEL
clear. simple. different.

--	--	--
--	--	--
--	--	--
--	--	--
--	--	--
NO:	DATE:	DESCRIPTION:
REVISIONS		
PROJECT NUMBER: 2171059		
DRAWN BY: CD		
REVIEWED BY: SM		
ISSUED FOR: CONSTRUCTION		
ISSUED DATE: 5/17/2017		
DRAWING NAME:		
DRAWING NUMBER:		

ROOF PLANS & DETAILS

A200



It is a violation of New York Education Law Article 145 Sec.7209, for any person, unless acting under the direction of a licensed architect, professional engineer, or land surveyor, to alter an item in any way. If an item bearing the seal of an architect, engineer, or land surveyor is altered; the altering architect, engineer, or land surveyor shall affix to the item their seal and notation "altered by" followed by their signature and date of such alteration, and a specific description of the alteration.

© 2017 LaBella Associates

**DORSCHER MINI OF
ROCHESTER**

3875 WEST HENRIETTA ROAD
ROCHESTER, NY 14623

SERVICE BAY ADDITION & ALTERATION



DORSCH
clear. simple. different

000	000	000
000	000	000
000	000	000
000	000	000
000	000	000

NO:	DATE:	DESCRIPTION:
REVISIONS		

PROJECT NUMBER: 2171059

DRAWN BY: CD

REVIEWED BY: SM

ISSUED FOR: CONSTRUCTION


ISSUED DATE: 5/17/2017

DRAWING NAME: _____

EXTERIOR ELEVATIONS


DRAWING NUMBER:

A300




EXTERIOR ELEVATION - SOUTH

SCALE: 1/4" = 1'-0"



EXTERIOR ELEVATION - WEST

SCALE: 1/4" = 1'-0"



EXTERIOR ELEVATION - WEST

SCALE: 1/4" = 1'-0"



It is a violation of New York Education Law Article 145 Sec.7209, for any person, unless acting under the direction of a licensed architect, professional engineer, or land surveyor, to alter an item in any way. If an item bearing the seal of an architect, engineer, or land surveyor is altered; the altering architect, engineer, or land surveyor shall affix to the item their seal and notation "altered by" followed by their signature and date of such alteration, and a specific description of the alteration.

© 2017 LaBella Associates

DORSCHEL MINI OF ROCHESTER

3875 WEST HENRIETTA ROAD
ROCHESTER, NY 14623

**SERVICE BAY ADDITION
& ALTERATION**



--	--	--
--	--	--
--	--	--
--	--	--
--	--	--

NO.	DATE:	DESCRIPTION:
-----	-------	--------------

REVISIONS:	
------------	--

PROJECT NUMBER:	2171059
-----------------	---------

DRAWN BY:	CD
-----------	----

REVIEWED BY:	SM
--------------	----

ISSUED FOR:	CONSTRUCTION
-------------	--------------


ISSUED DATE:	5/17/2017
--------------	-----------

DRAWING NAME:	TBD
---------------	-----


**BUILDING SECTIONS &
SECTION DETAILS**

DRAWING NUMBER:


A400




2 BUILDING SECTION
A400 SCALE: 1/4" = 1'-0"




3 TRENCH DRAIN DETAIL
A400 SCALE: 1-1/2" = 1'-0"




4 STANDARD DRAIN DETAIL (IN SLAB)
A400 SCALE: 1-1/2" = 1'-0"




5 DOOR THRESHOLD DETAIL
A400 SCALE: 1-1/2" = 1'-0"



6 DOOR HEAD DETAIL
A400 SCALE: 1-1/2" = 1'-0"



7 DOOR JAMB DETAIL
A400 SCALE: 1-1/2" = 1'-0"



1 WALL SECTION
A400 SCALE: 3/4" = 1'-0"

- GENERAL STRUCTURAL NOTES:**
1. BUILDING CODE: APPLICABLE BUILDING CODE. SEE DESIGN CHART.
 2. CONSTRUCTION LOADING: DURING CONSTRUCTION, THE GENERAL CONTRACTOR SHALL LIMIT AND CONTROL CONSTRUCTION LOADING, INCLUDING BUT NOT LIMITED TO:
 - a. MATERIAL STOCKPILING AND EQUIPMENT TO PRECLUDE OVERSTRESSING, CONSTRUCTION LIVE LOAD IN EXCESS OF 20 PSF, OR DAMAGE TO ANY STRUCTURAL ELEMENT.
 3. COORDINATION WITH OTHER DISCIPLINES: THE CONTRACTOR SHALL COORDINATE ALL STRUCTURAL WORK WITH THE ARCHITECTURAL, ELECTRICAL, MECHANICAL, PLUMBING AND FIRE PROTECTION DRAWINGS AND SPECIFICATIONS.
 4. EXISTING CONDITIONS: THE INFORMATION SHOWN ON THESE DOCUMENTS IS THE BEST REPRESENTATION OF EXISTING CONDITIONS AVAILABLE TO THE ENGINEER. IT IS THE CONTRACTOR'S RESPONSIBILITY TO FIELD VERIFY AND BRING TO THE ENGINEERS AND CONSTRUCTION MANAGERS ATTENTION ANY DISCREPANCIES PRIOR TO COMMENCING WORK.
 5. EXISTING STRUCTURES: ALL EXISTING STRUCTURES ADJACENT TO NEW WORK ARE TO BE ADEQUATELY PROTECTED AND/OR SUPPORTED DURING CONSTRUCTION. THE CONTRACTOR SHALL BE RESPONSIBLE FOR REPAIRING ANY NEW OR EXISTING CONSTRUCTION DAMAGED WHILE WORK IS IN PROGRESS.
 6. OPENINGS: THE CONTRACTOR SHALL BE RESPONSIBLE FOR COORDINATING SIZE AND LOCATION OF ALL OPENINGS IN NEW AND EXISTING CONSTRUCTION WITH THE DISCIPLINE REQUIRING THEM.

- FOUNDATION NOTES:**
1. GEOTECHNICAL INFORMATION USE PER RECORD DOCUMENTS. ALLOWABLE BEARING PRESSURE = 3,000 PSF.
 2. TAKE ALL NECESSARY PRECAUTIONS WHEN EXCAVATING OR DRILLING ADJACENT TO EXISTING STRUCTURES TO AVOID DISTURBING EXISTING FOUNDATIONS. DO NOT EXCAVATE BELOW EXISTING FOUNDATIONS. CONTACT THE ENGINEER IF EXISTING CONDITIONS DIFFER FROM THOSE SHOWN ON THE DRAWING.
 3. ALL EXCAVATIONS SHALL FULLY CONFORM TO LOCAL, STATE AND FEDERAL SAFETY REGULATIONS.
 4. DO NOT BACKFILL AGAINST CONCRETE ELEMENTS UNTIL PLACED CONCRETE HAS REACHED 75% OF ITS SPECIFIED 28-DAY COMPRESSIVE STRENGTH.
 5. BACKFILL BOTH SIDES OF FOUNDATION WALLS IN EQUAL, ALTERNATE LIFTS IN ORDER TO AVOID IMPOSING UNBALANCED LATERAL PRESSURE ON THE WALLS.
 6. ALLOW TESTING AGENCY TO INSPECT AND APPROVE ALL COMPACTED SUBGRADE AND FILL LAYERS PRIOR TO FURTHER BACKFILL AND/OR PLACEMENT OF CONCRETE. TESTING AND INSPECTION RESULTS SHALL BE APPROVED BY THE GEOTECHNICAL ENGINEER.
 7. THE SUITABILITY AND STABILITY OF EXISTING SOILS AND FILL, THE DEPTHS AND LATERAL LIMITS OF UNSUITABLE MATERIAL, TO BE REMOVED, AND ADEQUACY OF FOUNDATION BEARING GRADES SHALL BE DETERMINED BY THE PROJECT GEOTECHNICAL ENGINEER.
 8. BACKFILL AND FILL MATERIALS SHALL BE COMPACTED TO 95% OF MAXIMUM DRY DENSITY ACCORDING TO THE MODIFIED PROCTOR TEST (ASTM D-1557). ALL EXISTING BACKFILL SHALL BE RECOMPACTED AS SUCH.
 9. EXCAVATION AND BACKFILL OPERATIONS SHALL BE MAINTAINED IN A DRY CONDITION. SURFACE AND INFILTRATING WATER SHALL BE REMOVED BY SITE GRADING AND/OR BY PUMPING FROM PUMPS AS REQUIRED.

- CONCRETE NOTES:**
1. PROVIDE THE FOLLOWING MINIMUM CONCRETE CLEAR COVER FOR REINFORCING STEEL, UNLESS OTHERWISE NOTED:
 - a. CONCRETE PLACED AGAINST EARTH: 3.0 IN.
 - b. FORMED SURFACES IN CONTACT WITH EARTH OR EXPOSED TO WEATHER: #6 THROUGH #18 BARS: 2.0 IN.
#5 BARS AND SMALLER: 1.5 IN.
 - c. FORMED SURFACES NOT IN CONTACT WITH EARTH OR EXPOSED TO WEATHER: #14 AND #18 BARS: 1.5 IN.
#11 BARS AND SMALLER: 1.0 IN.
 2. ALL CONCRETE WORK, CONSTRUCTION, AND REINFORCING DETAILS SHALL CONFORM TO THE APPLICABLE BUILDING CODE.
 3. ALL REINFORCING STEEL SHALL BE DETAILED, FABRICATED AND PLACED IN ACCORDANCE WITH ACI 318.
 4. ALL REINFORCING BARS SHALL CONFORM TO ASTM A615 GRADE 60.
 5. ALL REINFORCING SHALL BE LAPPED OR EMBEDDED IN ACCORDANCE WITH ACI 318, UNLESS OTHERWISE NOTED.
 6. PROVIDE CORNER BARS TO MATCH ALL HORIZONTAL REINFORCING AT CORNERS OR INTERSECTIONS.
 7. CHAMFER EXTERIOR CORNERS AND EDGES OF PERMANENTLY EXPOSED CONCRETE.
 8. PRIOR TO PLACEMENT OF CONCRETE, A FIELD REPRESENTATIVE SHALL BE INFORMED A MINIMUM OF 24 HOURS IN ADVANCE OF PLACEMENT, TO ALLOW INSPECTION OF REINFORCING STEEL, AND PREPARATION FOR TAKING CONCRETE SAMPLES. INDEPENDENT TESTS ARE REQUIRED FOR ALL CONCRETE PLACEMENTS.
 9. INSTALLATION OF REINFORCEMENT SHALL BE COMPLETED AT LEAST 24 HOURS PRIOR TO THE SCHEDULED CONCRETE PLACEMENT.
 10. VAPOR BARRIER, POLYETHYLENE SHEET, ASTM D 4397, NOT LESS THAN 15-MIL, LOCATED BELOW INTERIOR SLABS-ON-GRADE.
 11. SYNTHETIC MACRO-FIBER-POLYPROPYLENE MACRO-FIBERS ENGINEERED AND DESIGNED FOR USE IN CONCRETE, COMPLYING WITH ASTM C 1116/C 1116M, TYPE III.
 12. PROTECT CONCRETE FROM PREMATURE DRYING IMMEDIATELY AFTER PLACEMENT. CURING OF CONCRETE SLABS MUST START WITHIN 2 HOURS AFTER FINISHING OPERATIONS ARE COMPLETE. SLABS-ON-GRADE SHALL BE WET CURED FOR 7 DAYS. CURING COMPOUNDS ARE PROHIBITED.
 13. SLABS-ON-GRADE SHALL HAVE CONTROL JOINTS AS SHOWN ON PLANS. SAW CUT JOINTS SHALL BE MADE WITHIN 12 HOURS OF PLACING SLAB. AFTER CONCRETE IS CURED AND READY FOR PLACEMENT OF FLOOR FINISH, ALL SLABS INSIDE THE BUILDING SHALL HAVE CONTROL JOINTS FILLED WITH APPROVED JOINT FILLER.
 14. CONCRETE SHALL BE CONTROLLED, PROPORTIONED, MIXED AND PLACED IN THE PRESENCE OF A REPRESENTATIVE OF AN APPROVED TESTING AGENCY.
 15. CONDUIT OR PIPES SHALL BE PLACED UNDER SLABS-ON-GRADE.
 16. ALUMINUM CONDUITS OR PIPES SHALL NOT BE PLACED IN CONCRETE.

- CONCRETE MIX NOTES:**
1. SUBMIT MIX DESIGNS FOR REVIEW AND APPROVAL.
 2. FOOTINGS: PROPORTION NORMAL-WEIGHT CONCRETE MIXTURE AS FOLLOWS:
 - a. MINIMUM COMPRESSIVE STRENGTH: 4500 PSI AT 28 DAYS.
 - b. MAXIMUM WATER-CEMENTITIOUS MATERIALS RATIO: 0.45.
 - c. SLUMP LIMIT: 4 INCHES PLUS OR MINUS 1 INCH. IF ADMIXTURES ARE USED TO IMPROVE WORKABILITY, THE MAXIMUM SLUMP LIMITS MAY BE RELAXED WITH ENGINEER'S APPROVAL.
 - d. AIR CONTENT: 4.5 PERCENT PLUS OR MINUS 1.5 PERCENT, AT POINT OF DELIVERY.
 - e. COURSE AGGREGATE: 1-INCH NOMINAL MAXIMUM AGGREGATE SIZE.
 3. INTERIOR SLABS-ON-GRADE: PROPORTION NORMAL-WEIGHT CONCRETE MIXTURE AS FOLLOWS:
 - a. MINIMUM COMPRESSIVE STRENGTH: 3500 PSI AT 28 DAYS.
 - b. MINIMUM CEMENTITIOUS MATERIALS CONTENT: 470 LB/CU. YD.
 - c. SLUMP LIMIT: 4 INCHES PLUS OR MINUS 1 INCH. IF ADMIXTURES ARE USED TO IMPROVE WORKABILITY, THE MAXIMUM SLUMP LIMITS MAY BE RELAXED WITH ENGINEER'S APPROVAL.
 - d. AIR CONTENT: DO NOT ALLOW AIR CONTENT OF TROWELED FINISHED FLOORS TO EXCEED 3 PERCENT.
 - e. COURSE AGGREGATE: 1.5 INCH NOMINAL MAXIMUM AGGREGATE SIZE.
 - f. SYNTHETIC MACRO-FIBER: UNIFORMLY DISPERSE IN CONCRETE MIXTURE AT MANUFACTURER'S RECOMMENDED RATE, BUT NOT LESS THAN A RATE OF 5.0 LB/CU. YD.
 4. EXTERIOR CONCRETE: PROPORTION NORMAL-WEIGHT CONCRETE MIXTURE AS FOLLOWS:
 - a. MINIMUM COMPRESSIVE STRENGTH: 5000 PSI AT 28 DAYS.
 - b. MAXIMUM WATER-CEMENTITIOUS MATERIALS RATIO: 0.40.
 - c. SLUMP LIMIT: 4 INCHES PLUS OR MINUS 1 INCH. IF ADMIXTURES ARE USED TO IMPROVE WORKABILITY, THE MAXIMUM SLUMP LIMITS MAY BE RELAXED WITH ENGINEER'S APPROVAL.
 - d. AIR CONTENT: 6 PERCENT PLUS OR MINUS 1.5 PERCENT, AT POINT OF DELIVERY.
 - e. COURSE AGGREGATE: 1-INCH NOMINAL MAXIMUM AGGREGATE SIZE.
 - f. SYNTHETIC MACRO-FIBER: UNIFORMLY DISPERSE IN CONCRETE MIXTURE AT MANUFACTURER'S RECOMMENDED RATE, BUT NOT LESS THAN A RATE OF 5.0 LB/CU. YD.


- MASONRY NOTES:**
1. MASONRY CONSTRUCTION SHALL CONFORM TO THE LATEST EDITION OF THE "BUILDING CODE REQUIREMENTS FOR CONCRETE MASONRY STRUCTURES" (ACI-530).
 2. ALL CONCRETE BLOCK SHALL CONFORM TO ASTM-C90. PROVIDE NORMAL WEIGHT UNITS WITH MINIMUM AVERAGE NET-AREA COMPRESSIVE STRENGTH OF 2800 PSI.
 3. MORTAR FOR UNIT MASONRY: COMPLY WITH ASTM C 270. PROVIDE THE FOLLOWING TYPES OF MORTAR FOR APPLICATIONS BELOW:
 - a. FOR REINFORCED MASONRY, USE TYPE M.
 - b. FOR MASONRY BELOW GRADE OR IN CONTACT WITH EARTH, USE TYPE M.
 - c. FOR INTERIOR NONLOAD-BEARING PARTITIONS, USE TYPE N.
 4. PLACE GROUT IN ALL REINFORCED CELLS. GROUT SHALL BE PLACED IN LIFTS NOT TO EXCEED 5'-0" FOR LOW LIFT GROUTING.
 5. REINFORCING STEEL SHALL CONFORM TO ASTM A615, GRADE 60. REINFORCING BARS MARKED "CONTINUOUS" SHALL BE LAPPED PER ACI 530. CONSTRUCT LAP SPLICES AND EMBEDMENT LENGTHS PER ACI 530. MAINTAIN A MINIMUM OF 1/2" CLEARANCE BETWEEN REINFORCING BARS AND MASONRY. PROVIDE #5 BARS UNLESS OTHERWISE NOTED.
 6. JOINT REINFORCEMENT FACTORY FABRICATED FROM COLD-DRAWN STEEL WIRE, ASTM A 82, LADDER DESIGN, WITH 9 GAGE DEFORMED STEEL WIRE LONGITUDINAL RODS WELDED TO 9 GAGE STEEL WIRE CROSS TIES SPACED 16 INCHES ON CENTER MAXIMUM, WIDTH 1-1/2 TO 2 INCHES LESS THAN TOTAL WALL THICKNESS. FURNISH FACTORY FABRICATED CORNER AND TEE SECTIONS FOR CORNERS AND WALL INTERSECTIONS.
 7. DESIGN AND PROVIDE TEMPORARY BRACING OF MASONRY WALLS DURING CONSTRUCTION. BRACING SHALL REMAIN IN PLACE UNTIL PERMANENT SUPPORTING ELEMENTS OF THE STRUCTURE HAVE BEEN CONSTRUCTED. BRACING SHALL FULLY CONFORM TO ALL OSHA REQUIREMENTS.
 8. GROUT ALL CELLS OF MASONRY UNITS FOR THE FIRST TWO COURSES ABOVE ALL FOUNDATION WALLS AND SLABS.
 9. PROVIDE CORNER BARS WHERE HORIZONTAL REINFORCING MEETS AT A CORNER OR INTERSECTION.
 10. PROVIDE REINFORCING BARS AROUND ALL MASONRY OPENINGS. SEE TYPICAL MASONRY DETAILS.
 11. ALL MASONRY COURSING SHOWN IN SECTION AND ELEVATION IS SCHEMATIC. MASONRY MAY NEED TO BE CUT AS REQUIRED.
 12. CONDUITS, PIPES, AND SLEEVES IN MASONRY SHALL BE NO CLOSER THAN 3 DIAMETERS ON CENTER. ALUMINUM SHALL NOT BE USED.

- STRUCTURAL STEEL NOTES:**
1. STRUCTURAL STEEL SHAPES SHALL CONFORM TO THE FOLLOWING:
 - a. WIDE FLANGE SHAPES: ASTM A992
 - b. PLATES, BARS AND ANGLES: ASTM A36
 - c. HOLLOW STRUCTURAL SECTIONS (HSS) - SQUARE OR RECTANGULAR: ASTM A500, GRADE B, Fy = 46 KSI
 - d. HOLLOW STRUCTURAL SECTIONS (HSS) - ROUND: ASTM A500, GRADE B, Fy = 42 KSI
 2. BOLTED CONNECTIONS SHALL CONFORM TO THE FOLLOWING:
 - a. HIGH-STRENGTH BOLTS (AS INDICATED ON PLANS): ASTM A325, ASTM A490
 3. ANCHOR RODS SHALL CONFORM TO THE FOLLOWING:
 - a. ANCHOR RODS (U.O.N.): ASTM F1554, GRADE 36, WELDABLE (S1)
 4. WELDING ELECTRODES SHALL CONFORM TO THE FOLLOWING:
 - a. AWS SPECIFICATIONS FOR ELECTRODES BASED ON WELDING PROCESS AND THE TYPE AND GRADE OF STEEL. E70XX ELECTRODES (MIN.) FOR FILLET WELDS.
 5. ALL STRUCTURAL STEEL SHALL BE DETAILED, FABRICATED AND ERECTED IN STRICT ACCORDANCE WITH THE LATEST AISC SPECIFICATIONS.
 6. SHOP FABRICATE TO THE GREATEST EXTENT POSSIBLE BY WELDING INCLUDING BEAM STIFFENERS, COLUMN CAPS AND BASES, HOLES AND CONNECTIONS.
 7. FRAMING SHALL BE EQUALLY SPACED BETWEEN COLUMN LINES UNLESS OTHERWISE NOTED.
 8. ERECT ALL STEEL IN ACCORDANCE WITH THE LATEST AISC SPECIFICATIONS.
 9. PROVIDE MOMENT AND SHEAR CONNECTIONS AS SHOWN SCHEMATICALLY IN THE DRAWINGS. ALL CONNECTIONS SHALL BE DESIGNED BY THE FABRICATOR FOR LOADS SHOWN ON THE PLANS AND SHALL MEET THE CRITERIA SHOWN IN THE TYPICAL DETAILS.
 10. PROVIDE TEMPORARY BRACING FOR ALL ERECTED STEEL FRAMING UNTIL ALL CONNECTIONS HAVE BEEN FULLY TIGHTENED OR WELDED.
 11. CUTS, HOLES, COPELS, ETC., REQUIRED FOR WORK OF THE OTHER TRADES SHALL BE SHOWN ON SHOP DRAWINGS AND MADE IN THE SHOP. FIELD CUTTING OR BURNING WILL NOT BE PERMITTED.
 12. ALL WELDING BOTH SHOP AND FIELD SHALL BE PERFORMED BY CERTIFIED WELDERS IN ACCORDANCE WITH AWS SPECIFICATIONS. WELDING ELECTRODES SHALL CONFORM TO ASTM A233, E70-XX. MINIMUM WELD SIZE SHALL BE 1/4 INCHES (FILLET) UNLESS OTHERWISE NOTED.
 13. BITUMINOUS COAT ALL STRUCTURAL STEEL LOCATED BELOW GRADE.
 14. ALL EXTERIOR MEMBERS, LINTELS, ASSEMBLIES OR COMPONENTS SHALL BE GALVANIZED AND PAINTED.
 15. FINISH: PAINTED: MANUFACTURERS STANDARD PRIMER, SEE SPECIFICATION. GALVANIZED: IN ACCORDANCE WITH ASTM A780.
 16. AFTER ERECTION, ALL DAMAGED AREAS IN THE SHOP COAT AND AT ALL FIELD WELD LOCATIONS, SHALL BE TOUCHED UP WITH THE SAME PAINT USED FOR THE PRIMER AND SHOP COAT. PREPARE SURFACES IN ACCORDANCE WITH SSPC-SP3, FOR PAINTED FINISH, OR IN ACCORDANCE WITH ASTM A780 IF FINISH IS GALVANIZED.

- STEEL DECK NOTES:**
1. PROVIDE GALVANIZED STEEL DECK IN ACCORDANCE WITH ASTM A653. GALVANIZED WITH A MINIMUM YIELD STRENGTH OF 33 KSI.
 2. PLACE STEEL DECK OVER A MINIMUM OF 3 SPANS IN THE DIRECTION INDICATED IN THE PLANS, UNLESS OTHERWISE NOTED.
 3. WELD DECKING TO STRUCTURAL STEEL BY CERTIFIED WELDERS USING PREQUALIFIED PROCEDURES. THE ERECTOR SHALL ESTABLISH A WELDING PROCEDURE FOR THE PUDDLE WELDING OF STEEL DECKING TO THE STRUCTURAL STEEL FOR THE PARTICULAR GAGES USED. PRIOR TO THE START OF ERECTION OF THE STEEL DECK, QUALIFY EACH WELDER USING THIS PROCEDURE AS WITNESSED BY THE OWNERS' TESTING LABORATORY.
 4. POWER-ACTUATED MECHANICAL FASTENERS APPROVED BY THE ENGINEER OF RECORD MAY BE USED IN LIEU OF WELDING THE DECKING TO THE STRUCTURAL STEEL.
 5. DO NOT HANG LOADS EXCEEDING 50 LBS. FROM ANY METAL DECKING. HANG ALL DUCTWORK, PIPING, ETC. DIRECTLY FROM STRUCTURAL STEEL.

- SPECIAL INSPECTION NOTES:**
1. ALL PREFABRICATED ITEMS SHALL BE MANUFACTURED BY APPROVED AND CERTIFIED SHOPS.
 2. SPECIAL INSPECTIONS WILL BE REQUIRED FOR THIS PROJECT. THE CONTRACTOR SHALL COORDINATE ALL WORK WITH THE OWNERS' TESTING AND SPECIAL INSPECTION REPRESENTATIVES.
 3. SEE CHARTS ON S-002 AND SPECIFICATIONS FOR STRUCTURAL SPECIAL INSPECTIONS AND ADDITIONAL INFORMATION.

- MISCELLANEOUS NOTES:**
1. ALL ELEVATIONS ARE REFERENCED FROM FINISHED MAIN FLOOR ELEVATION [0' - 0']
 2. BEAM LEGEND



COLUMN SCHEDULE				
T.O STEEL				
15' - 11"				15' - 11"
	HSS30X30X16		HSS30X30X16	
FOUNDATION PLAN				FOUNDATION PLAN
0"	-9 1/4"		-9 1/4"	0"
COLUMN STIFFENERS &/OR DOUBLER PLATES REQUIRED				
BASE PLATE TYPE	BP1		BP1	
AXIAL LOAD				
Column Locations	A-11		A*-11	
NOTES: 1. ELEVATIONS ARE REFERENCED FROM THE NEAREST LEVEL. 2. PROVIDE 1/4" CAP PLATES FOR ALL HSS COLUMNS. U.N.O.				

BASE PLATE SCHEDULE						
TYPE	BASE PLATE DIMENSIONS			ANCHOR BOLT PROPERTIES		
	LENGTH	WIDTH	THICKNESS	NO. OF BOLTS	BOLT DIAMETER	MIN. EMBEDMENT
BP1	1' - 4"	1' - 4"	3/4"	4	3/4"	9"
COMMENTS -						

FOOTING SCHEDULE					
MARK	FOOTING DIMENSIONS			FOOTING REINFORCEMENT	
	LENGTH	WIDTH	THICKNESS	BOTTOM REINFORCEMENT LONGITUDINAL REINF.	TOP REINFORCEMENT TRANSVERSE REINF.
F1	4' - 0"	4' - 0"	1' - 0"	(5) #5 BARS	(5) #5 BARS
COMMENTS (5) #5 BARS E.W.					

STRUCTURAL ABBREVIATIONS LEGEND

ACI	AMERICAN CONCRETE INSTITUTE
AISC	AMERICAN INSTITUTE OF STEEL CONSTRUCTION
ASTM	AMERICAN SOCIETY FOR TESTING AND MATERIALS
AWS	AMERICAN WELDING SOCIETY
APPROX.	APPROXIMATE
ARCH.	ARCHITECT/ARCHITECTURAL
B.F.	BOTTOM FACE
B.O.	BOTTOM OF
CIP	CAST-IN-PLACE
CONC.	CONCRETE
C.J.	CONSTRUCTION JOINT
CONT.	CONTINUOUS
COV.	COVER
DIA.	DIAMETER
E.F.	EACH FACE
E.S.	EACH SIDE
E.W.	EACH WAY
ELEV.	ELEVATION
EQ.	EQUAL
EXIST.	EXISTING
(E)	EXISTING
F.F.E.	FINISHED FLOOR ELEVATION
FW	FLATWISE
F.D.	FLOOR DRAIN
F	FOOTING
FTG.	FOOTING
FNDR.	FOUNDATION
GA.	GAGE
GALV.	GALVANIZED
H.P.	HIGH POINT
H.S.	HIGH STRENGTH


STRUCTURAL ABBREVIATIONS LEGEND

HORIZ.	HORIZONTAL
I.F.	INSIDE FACE
LLH	LONG LEG HORIZONTAL
LLV	LONG LEG VERTICAL
MANUF.	MANUFACTURER
MAX.	MAXIMUM
MECH.	MECHANICAL
MIN.	MINIMUM
(N)	NEW
O.C.	ON CENTER
O.F.	OUTSIDE FACE
P	PIER (SEE SCHEDULE)
PLF	POUNDS PER LINEAR FOOT
REINF.	REINFORCING REINFORCEMENT
S.J.	SAW-CUT CONTROL JOINT
S.P.A., SP.	SPACE OR SPACING
STD.	STANDARD
SDI	STEEL DECK INSTITUTE
TSF	TON PER SQUARE FOOT
T&B	TOP & BOTTOM
T.F.	TOP FACE
T.O.	TOP OF
T.O.S.	TOP OF STEEL
TYP.	TYPICAL
U.O.N.	UNLESS OTHERWISE NOTED
V.I.F.	VERIFY IN FIELD
VERT.	VERTICAL
W.W.R.	WELDED WIRE REINFORCEMENT
W/	WITH
W.P.	WORKING POINT

STRUCTURAL DESIGN TABLE


(IN ACCORDANCE WITH APPLICABLE BUILDING CODE)

BUILDING DATA:		LOCATION		ROCHESTER, NEW YORK		IBC 2015 TABLE 1604.5	
BUILDING OCCUPANCY RISK CATEGORY		APPLICABLE BUILDING CODE		INTERNATIONAL BUILDING CODE 2015 WITH NEW YORK STATE AMENDMENTS			
GEOTECHNICAL INFORMATION:		ALLOWABLE BEARING PRESSURE		3000 PSF			
DEAD LOAD:		ROOF		DL1		20 PSF	
FLOOR LIVE LOAD:		GARAGES		LL1		40 PSF	
ROOF LIVE LOAD:		ROOF		LLr		20 PSF	
SNOW LOAD:		SNOW LOAD IMPORTANCE FACTOR		Is		1.00	
		GROUND SNOW LOAD		Pg		40.0 PSF	
		SNOW EXPOSURE FACTOR		Ce		1.00	
		THERMAL FACTOR		Ct		1.00	
		FLAT ROOF SNOW DRIFTING SNOW		Pf		28.0 PSF	
				AS REQ. PER ASCE 7-10			
WIND LOAD (MAIN WIND-FORCE RESISTING SYSTEM):		ANALYSIS PROCEDURE		DIRECTIONAL PROCEDURE		ASCE 7-10 CHAPTER 27	
		ULTIMATE DESIGN WIND SPEED (3-SECOND GUST)		Vult		115 mph	
		NOMINAL DESIGN WIND SPEED (3-SECOND GUST)		Vasd		89.0 mph	
		WIND DIRECTIONALITY FACTOR		Kd		0.85	
		EXPOSURE CATEGORY		Is		B	
		TOPOGRAPHIC FACTOR		Kzt		1.00	
		GUST-EFFECT FACTOR		G		0.85	
		ENCLOSURE CLASSIFICATION		GCp1		+0.55/-0.55	
		INTERNAL PRESSURE COEFFICIENT		q		0.62	
		VELOCITY PRESSURE EXPOSURE COEFFICIENT		Kz		17.84 PSF	
		VELOCITY PRESSURE		Prin		16 PSF	
		MINIMUM WALL WIND PRESSURE		Pmin		8 PSF	
		MINIMUM ROOF WIND PRESSURE		NOTES		WIND LOADS ARE CALCULATED FROM THESE PARAMETERS FOR EACH SURFACE OF THE MAIN WIND-FORCE RESISTING SYSTEM.	
EARTHQUAKE LOAD:		SEISMIC - FORCE RESISTING SYSTEM		A.9 ORDINARY REINFORCED MASONRY SHEAR WALLS		ASCE 7-10 TABLE 12.2-1	
		SOIL SITE CLASSIFICATION		C		ASCE 7-10 SECTION 20.3	
		SPECTRAL RESPONSE ACCELERATION AT 0.2 SEC		Ss		0.168g	
		SPECTRAL RESPONSE ACCELERATION AT 1.0 SEC		S1		0.060g	
		SEISMIC IMPORTANCE FACTOR		Ie		1.00	
		DESIGN SPECTRAL RESPONSE COEFFICIENT		SDS		0.134g	
		DESIGN SPECTRAL RESPONSE COEFFICIENT		SD1		0.068g	
		SEISMIC DESIGN CATEGORY		B		ASCE 7-10 SECTION 11.4.4	
		ANALYSIS PROCEDURE		EQUIV. LATERAL FORCE		ASCE 7-10 SECTION 12.8	
		SEISMIC RESPONSE COEFFICIENT		Cs		0.0672	
		RESPONSE MODIFICATION FACTOR		R		2	
		SEISMIC BASE SHEAR		V		5.8 KIPS	



SLAB-ON-GRADE SCHEDULE				
MARK	TYPE	SLAB THICKNESS	SLAB REINFORCEMENT	COMMENTS
S.O.G. 1	SLAB-ON-GRADE	6"	FIBERMESH 650 MACROSYNTHETIC FIBERS OR APPROVED EQUAL	SEE PLANS & SECTIONS FOR ADDITIONAL REINF.
S.O.G. 2	CIVIL/SITE SLAB	6"	FIBERMESH 650 MACROSYNTHETIC FIBERS OR APPROVED EQUAL	SEE PLANS & SECTIONS FOR ADDITIONAL REINF.

5/16/2017 5:45:34 PM
E:\Users\skender\Documents\Draw\Local\Phd\2171059 - STR - MINI COOPER ROCHESTER_kender.rvt




1
S-003

3D ISOMETRIC VIEW

NOT TO SCALE

3D ISOMETRIC PLAN NOTES:

1. FOR REFERENCE PURPOSES ONLY. NOT FOR CONSTRUCTION.
2. ISOMETRIC VIEW MAY NOT BE AN ACCURATE REPRESENTATION OF FRAMING CONDITIONS. SEE PLANS AND SECTIONS FOR ALL CONDITIONS.



LaBella

300 State Street
Suite 201
Rochester, NY 14614
P: (585) 454-6110

Engineering
Architecture
Environmental
Planning

www.labellapc.com



It is a violation of New York Education Law Article 145 Sec.7209, for any person, unless acting under the direction of a licensed architect, professional engineer, or land surveyor, to alter an item in any way. If an item bearing the seal of an architect, engineer, or land surveyor is altered; the altering architect, engineer, or land surveyor shall affix to the item their seal and notation "altered by" followed by their signature and date of such alteration, and a specific description of the alteration.

© 2017 LaBella Associates

DORSCHEL MINI OF ROCHESTER

3875 WEST HENRIETTA ROAD
ROCHESTER, NY 14623

SERVICE BAY ADDITION & ALTERATION




NO.	DATE:	DESCRIPTION:
REVISIONS		
PROJECT NUMBER:		
2171059		
DRAWN BY:		
KRD		
REVIEWED BY:		
JDL		
ISSUED FOR:		
CONSTRUCTION		
DATE:		
5/16/2017		
DRAWING NAME:		

3D VIEWS

DRAWING NUMBER:

S-003

5/16/2017 5:45:35 PM
C:\Users\skender\Documents\Draw Local\Plan\2171059 - STR - MINI COOPER ROCHESTER_kender.rvt



FOUNDATION LEGEND						
1.	<table><tr><th>P#</th><th>F#</th></tr><tr><th>#'-#"</th><th>-#'-#"</th></tr></table>	P#	F#	#'-#"	-#'-#"	P# - INDICATES PIER TYPE (SEE PIER SCHEDULE) F# - INDICATES COLUMN FOOTING TYPE (SEE FOOTING SCHEDULE) [-#'-#"] - BELOW COLUMN FOOTING TYPE INDICATES BOTTOM OF FOOTING ELEVATION WITH RESPECT TO DATUM ELEVATION = 0'-0" [-#'-#"] - BELOW PIER TYPE INDICATES TOP OF PIER ELEVATION WITH RESPECT TO DATUM ELEVATION = 0'-0"
P#	F#					
#'-#"	-#'-#"					
2.	<table><tr><th>W#</th></tr></table>	W#	## - INDICATES WALL TYPE (SEE FOUNDATION WALL &/OR WALL SCHEDULE)			
W#						
3.	<table><tr><th>WF#</th></tr></table>	WF#	WF# - INDICATES WALL FOOTING TYPE (SEE WALL FOOTING SCHEDULE)			
WF#						
4.	<table><tr><th>#'-#"</th></tr></table>	#'-#"	#'-#"- BOTTOM OF FOOTING ELEV. FOR WALL FOOTING W/ RESPECT TO DATUM ELEVATION = 0'-0"			
#'-#"						
5.	<table><tr><th>[##'-##"]</th></tr></table>	[##'-##"]	TOP OF WALL ELEVATION W/ RESPECT TO DATUM ELEVATION = 0'-0"			
[##'-##"]						
6.		SPOT ELEVATION INDICTES DEPTH BELOW F.F.E. (DATUM ELEVATION 0'-0")				

1 S-101 FOUNDATION PLAN


- 1/4" = 1'-0"
- FOUNDATION PLAN NOTES:
1. BOTTOM OF FOOTING ELEVATIONS ARE REFERENCED FROM FINISHED FLOOR ELEVATION (DATUM ELEV. 0'-0") AND ARE NOTED ON PLAN.
 2. CENTER ISOLATED FOOTINGS UNDER COLUMNS AND/OR AT COLUMN LINE INTERSECTIONS. U.O.N..
 3. DO NOT SCALE DRAWINGS. SEE ARCHITECTURAL FLOOR PLANS FOR DIMENSIONS NOT INDICATED ON STRUCTURAL DRAWINGS.
 4. SECTIONS INDICATED ON PLAN ARE TYPICAL FOR SIMILAR CONDITIONS.
 5. EXISTING ELEVATIONS AND DIMENSIONS ARE DERIVED FROM RECORD CONSTRUCTION DRAWINGS AND SHALL BE VERIFIED IN THE FIELD. NOTIFY ENGINEER OF RECORD OF ANY DISCREPANCIES.
 6. LIMITS OF DEMOLITION SHOWN ARE APPROXIMATE AND SHALL BE VERIFIED IN THE FIELD. ADJUST LIMITS AS NECESSARY SO THAT NEW CONSTRUCTION DOES NOT INTERFERE WITH EXISTING CONSTRUCTION.
 7. REMOVE EXISTING FOUNDATION WALLS AND FOOTINGS TO BE DEMOLISHED DOWN A MINIMUM OF 8" FROM BOTTOM OF SLABS-ON-GRADE AND INTERIOR FOOTINGS.

LABELLA

300 State Street
Suite 201
Rochester, NY 14614
P: (585) 454-6110

Engineering
Architecture
Environmental
Planning

www.labellapc.com



It is a violation of New York Education Law Article 145 Sec.7209, for any person, unless acting under the direction of a licensed architect, professional engineer, or land surveyor, to alter an item in any way. If an item bearing the seal of an architect, engineer, or land surveyor is altered; the altering architect, engineer, or land surveyor shall affix to the item their seal and notation "altered by" followed by their signature and date of such alteration, and a specific description of the alteration.

© 2017 LaBella Associates

DORSCHEL MINI OF ROCHESTER

3875 WEST HENRIETTA ROAD
ROCHESTER, NY 14623

SERVICE BAY ADDITION & ALTERATION



DORSCHEL
clear. simple. different.

NO.	DATE:	DESCRIPTION:
REVISIONS		
PROJECT NUMBER:		
2171059		
DRAWN BY:		
KRD		
REVIEWED BY:		
JDL		
ISSUED FOR:		
CONSTRUCTION		
DATE:		
5/16/2017		
DRAWING NAME:		

FOUNDATION PLAN

DRAWING NUMBER:

S-101



It is a violation of New York Education Law Article 145 Sec.7209, for any person, unless acting under the direction of a licensed architect, professional engineer, or land surveyor, to alter an item in any way. If an item bearing the seal of an architect, engineer, or land surveyor is altered; the altering architect, engineer, or land surveyor shall affix to the item their seal and notation "altered by" followed by their signature and date of such alteration, and a specific description of the alteration.

DORSCHEL MINI OF ROCHESTER

3875 WEST HENRIETTA ROAD
ROCHESTER, NY 14623

SERVICE BAY ADDITION & ALTERATION



NO.	DATE:	DESCRIPTION:
REVISIONS		
PROJECT NUMBER: 2171059		
DRAWN BY: KRD		
REVIEWED BY: JDL		
ISSUED FOR: CONSTRUCTION		
DATE: 5/16/2017		
DRAWING NAME:		


SLAB-ON-GRADE PLAN

DRAWING NUMBER:

S-102

SLAB-ON-GRADE LEGEND


1. SLAB-ON-GRADE: ARROWS INDICATE LIMITS
= SLAB MARK
2. SPOT ELEVATION INDICTES DEPTH BELOW F.F.E. (DATUM ELEVATION 0'-0")
3. CONTROL/CONSTRUCTION JOINT
4. WALL MARK: SEE WALL SCHEDULE
5. F.D. = FLOOR DRAIN (SEE MECH. & ARCH.)
6. C.O. = CLEAN OUT (SEE MECH. & ARCH.)
7. DENOTES STEP IN SLAB
8. DENOTES SLOPE IN SLAB
9. DENOTES STEP TO SLOPE IN SLAB
10. TOP OF WALL ELEVATION W/ RESPECT TO DATUM ELEVATION = 0' - 0".



1 SLAB-ON-GRADE PLAN

- 1/4" = 1'-0"
- SLAB PLAN NOTES:
1. ALL ELEVATIONS ARE REFERENCED FROM FINISHED FLOOR (DATUM ELEV. 0' - 0") AND ARE NOTED ON PLAN. U.N.O.
 2. DO NOT SCALE DRAWINGS. SEE ARCHITECTURAL FLOOR PLANS FOR DIMENSIONS NOT INDICATED ON STRUCTURAL DRAWINGS.
 3. SECTIONS INDICATED ON PLAN ARE TYPICAL FOR SIMILAR CONDITIONS.
 4. SEE M.E.P. DRAWINGS FOR THE BALANCE OF ALL EQUIPMENT, HOUSEKEEPING PADS, FLOOR PENETRATIONS, ETC. REQUIRED AT THIS LEVEL.
 5. BALANCE OF SLAB REINF. FOR REINFRANT CORNERS AND OPENINGS NOT SHOWN FOR CLARITY. SEE TYPICAL DETAILS.
 6. EXISTING ELEVATIONS AND DIMENSIONS ARE DERIVED FROM RECORD CONSTRUCTION DRAWINGS AND SHALL BE VERIFIED IN THE FIELD. NOTIFY ENGINEER OF RECORD OF ANY DISCREPANCIES.
 7. LIMITS OF DEMOLITION SHOWN ARE APPROXIMATE AND SHALL BE VERIFIED IN THE FIELD. ADJUST LIMITS AS NECESSARY SO THAT NEW CONSTRUCTION DOES NOT INTERFERE WITH EXISTING CONSTRUCTION.

5/16/2017 5:45:36 PM
C:\Users\skender\Documents\Revit Local File\2171059 - STR - MINI COOPER ROCHESTER.kendall.rvt



1 S-103

ROOF FRAMING PLAN


1/4" = 1'-0"

ROOF FRAMING PLAN NOTES:

1. TOP OF STEEL ELEVATIONS SHALL BE (+/- 15' - 11") ABOVE FIRST FLOOR DATUM ELEVATION (DATUM ELEV. 0' - 0"). DEVIATIONS FROM THIS ELEVATION ARE NOTED ON PLAN.
2. BEAM REACTIONS SHOWN ON PLANS ARE FACTORED LOAD FORCES. THE MINIMUM BEAM SHEAR REACTION IS 10 KIPS, OR 25% MAXIMUM TOTAL UNIFORM LOAD FOR ALL STEEL MEMBERS, WHICHEVER IS GREATER.
3. SEE MECHANICAL/ELECTRICAL DRAWINGS FOR THE BALANCE OF ALL EQUIPMENT, FLOOR PENETRATIONS, ETC. REQUIRED AT THIS LEVEL.
4. DO NOT SCALE DRAWINGS. SEE ARCHITECTURAL FLOOR PLANS FOR DIMENSIONS NOT INDICATED ON STRUCTURAL DRAWINGS.
5. SECTIONS INDICATED ON PLAN ARE TYPICAL FOR SIMILAR CONDITIONS.
6. EXISTING ELEVATIONS AND DIMENSIONS ARE DERIVED FROM RECORD CONSTRUCTION DRAWINGS AND SHALL BE VERIFIED IN THE FIELD. NOTIFY ENGINEER OF RECORD OF ANY DISCREPANCIES.
7. LIMITS OF DEMOLITION SHOWN ARE APPROXIMATE AND SHALL BE VERIFIED IN THE FIELD. ADJUST LIMITS AS NECESSARY SO THAT NEW CONSTRUCTION DOES NOT INTERFERE WITH EXISTING CONSTRUCTION.

FRAMING LEGEND

1. (#' - #') TOP OF BEAM ELEV.
W/ RESPECT TO DATUM ELEVATION = 0' - 0'.
2. (BELOW) BEAM LOCATED BELOW ANOTHER BEAM IN PLAN
3. S#
SPAN ELEVATED SLAB; ARROWS INDICATE SPAN DIRECTION
= SLAB MARK (SEE ELEVATED SLAB SCHEDULE)
4. R#
SPAN ROOF DECK; ARROWS INDICATE SPAN DIRECTION
= DECK MARK (SEE ROOF DECK SCHEDULE)
5. W#
WALL MARK; SEE WALL SCHEDULE
6. F.D.
F.D. = FLOOR DRAIN (SEE MECH. & ARCH.)
7. C.O.
C.O. = CLEAN OUT (SEE MECH. & ARCH.)
8. R.D.
R.D. = ROOF DRAIN (SEE MECH. & ARCH.)
9. [##'-##'] TOP OF WALL ELEVATION
W/ RESPECT TO DATUM ELEVATION = 0' - 0'.



LaBella

300 State Street
Suite 201
Rochester, NY 14614
P: (585) 454-6110

Engineering
Architecture
Environmental
Planning

www.labellapc.com



It is a violation of New York Education Law Article 145 Sec.7209, for any person, unless acting under the direction of a licensed architect, professional engineer, or land surveyor, to alter an item in any way. If an item bearing the seal of an architect, engineer, or land surveyor is altered; the altering architect, engineer, or land surveyor shall affix to the item their seal and notation "altered by" followed by their signature and date of such alteration, and a specific description of the alteration.

© 2017 LaBella Associates

DORSCHEL MINI OF ROCHESTER

3875 WEST HENRIETTA ROAD
ROCHESTER, NY 14623

SERVICE BAY ADDITION & ALTERATION




NO.	DATE:	DESCRIPTION:
REVISIONS		
PROJECT NUMBER:		2171059
DRAWN BY:		KRD
REVIEWED BY:		JDL
ISSUED FOR:		CONSTRUCTION
DATE:		5/16/2017
DRAWING NAME:		

ROOF FRAMING PLAN


DRAWING NUMBER:

S-103


5/16/2017 5:43:37 PM
C:\Users\skender\Documents\Draw Local File\2171059 - STR - MINI COOPER ROCHESTER_kender.rvt




8
S-201
TYPICAL RECESSED SLAB DETAIL
NOT TO SCALE




7
S-201
TYPICAL DEEPEINED FOOTINGS AT PIPES
NOT TO SCALE




6
S-201
TYPICAL PIPE SLEEVE THRU FOUNDATION WALL
NOT TO SCALE




5
S-201
TYPICAL PIPES AT FOUNDATION
NOT TO SCALE




4
S-201
TYPICAL SLAB-ON-GRADE PATCH DETAIL
NOT TO SCALE



3
S-201
TYPICAL SLAB-ON-GRADE RE-ENTRANT CORNER
NOT TO SCALE



2
S-201
TYPICAL SLAB-ON-GRADE JOINT
NOT TO SCALE



1
S-201
TYPICAL SLAB-ON-GRADE WITH VAPOR BARRIER
NOT TO SCALE

LaBella

300 State Street
Suite 201
Rochester, NY 14614
P: (585) 454-6110

Engineering
Architecture
Environmental
Planning

www.labellapc.com



It is a violation of New York Education Law Article 145 Sec.7209, for any person, unless acting under the direction of a licensed architect, professional engineer, or land surveyor, to alter an item in any way. If an item bearing the seal of an architect, engineer, or land surveyor is altered; the altering architect, engineer, or land surveyor shall affix to the item their seal and notation "altered by" followed by their signature and date of such alteration, and a specific description of the alteration.

© 2017 LaBella Associates

DORSCHEL MINI OF ROCHESTER

3875 WEST HENRIETTA ROAD
ROCHESTER, NY 14623

SERVICE BAY ADDITION & ALTERATION



DORSCHEL
clear. simple. different.

NO.	DATE:	DESCRIPTION:
REVISIONS		
PROJECT NUMBER: 2171059		
DRAWN BY: KRD		
REVIEWED BY: JDL		
ISSUED FOR: CONSTRUCTION		
DATE: 5/16/2017		
DRAWING NAME:		

TYPICAL SLAB-ON-GRADE & FOUNDATION DETAILS

DRAWING NUMBER:

S-201

SPLICE & DEVELOPMENT LENGTHS											
BAR SIZE	LAP SPLICE LENGTHS (IN.)					DEVELOPMENT LENGTHS (IN.)			TENSION	COMP.	HOOKED
	TENSION LAP LENGTH				COMP.						
	TOP BARS	OTHER									
CLASS	A	B	A	B							
#3	20	26	16	20	12	SAME AS CLASS A TENSION LAP SLICE	8	8			
#4	27	35	21	27	15		11	11			
#5	33	43	26	33	19		13	13			
#6	40	52	31	40	23		16	16			
#7	58	75	45	58	27		18	18			
#8	66	86	51	66	30		21	21			
#9	75	97	58	75	34		23	23			
#10	84	109	65	84	39		26	26			
#11	93	121	72	93	43		29	29			
f _c = 3,500 psi	LAP SPLICE LENGTHS (IN.)						DEVELOPMENT LENGTHS (IN.)			TENSION	COMP.
	TENSION LAP LENGTH				COMP.						
	TOP BARS	OTHER									
	CLASS	A	B	A	B						
	#3	18	23	14	18	12	8	7			
	#4	24	31	18	24	15	9	9			
	#5	30	38	23	30	19	12	12			
	#6	35	46	27	35	23	14	14			
	#7	51	67	40	51	27	16	16			
	#8	59	76	45	59	30	18	18			
	#9	66	86	51	66	34	21	21			
#10	74	96	57	74	39	23	23				
#11	82	107	64	82	43	26	26				
f _c = 4,500 psi	LAP SPLICE LENGTHS (IN.)					DEVELOPMENT LENGTHS (IN.)			TENSION	COMP.	HOOKED
	TENSION LAP LENGTH				COMP.						
	TOP BARS	OTHER									
	CLASS	A	B	A	B						
	#3	17	22	13	17	12	8	7			
	#4	23	29	17	23	15	9	9			
	#5	28	36	22	28	19	12	12			
	#6	34	43	26	34	23	14	13			
	#7	49	63	38	49	27	16	15			
	#8	56	72	43	56	30	18	17			
	#9	63	81	48	63	34	21	20			
#10	70	92	54	70	39	23	22				
#11	78	102	60	78	43	26	24				
NOTES:											
1. TOP BARS ARE HORIZONTAL BARS, PLACED SO THAT MORE THAN 12 INCHES OF FRESH CONCRETE IS PLACED BELOW THE BAR.											
2. ALL LAP SPLICES SHALL BE CLASS "B" UNLESS OTHERWISE NOTED.											
3. LENGTHS IN THE TABLE ARE FOR UNCOATED OR ZINC-COATED (GALVANIZED) BARS.											
4. CLEAR SPACING OF BARS BEING DEVELOPED OR SPliced NOT LESS THAN 20d AND CLEAR COVER NOT LESS THAN Dd.											
5. VALUES IN TABLE ARE FOR NORMAL WEIGHT CONCRETE.											
6. SPACING REQUIREMENTS AND END ANCHORAGE SHALL BE SPACED PER THE REQUIREMENTS OF ACI-318.											



It is a violation of New York Education Law Article 145 Sec. 7209, for any person, unless acting under the direction of a licensed architect, professional engineer, or land surveyor, to alter an item in any way. If an item bearing the seal of an architect, engineer, or land surveyor is altered; the altering architect, engineer, or land surveyor shall affix to the item their seal and notation "altered by" followed by their signature and date of such alteration, and a specific description of the alteration.

© 2017 LaBella Associates

DORSCHER MINI OF ROCHESTER

3875 WEST HENRIETTA ROAD
ROCHESTER, NY 14623

SERVICE BAY ADDITION & ALTERATION




NO:	DATE:	DESCRIPTION:
REVISIONS		
PROJECT NUMBER: 2171059		
DRAWN BY: KRD		
REVIEWED BY: JDL		
ISSUED FOR: CONSTRUCTION		
DATE: 5/16/2017		
DRAWING NAME:		


TYPICAL STEEL DETAILS

DRAWING NUMBER: _____


S-301



3 TYPICAL DECK SUPPORT AT HSS-COLUMNS
S-301 NOT TO SCALE




2 TYPICAL METAL DECK FASTENING LAYOUT




RECOMMENDED SIZES FOR ANCHOR ROD HOLES IN BASE PLATES			
ANCHOR ROD DIAMETER (INCH.)	HOLE DIAMETER (INCH.)	MIN. WASHER DIMENSION (INCH.)	MIN WASHER THICKNESS (INCH.)
3/4	1 5/16	2	1/4
7/8	1 1/6	2 1/2	5/16
1	1 13/16	3	3/8
1 1/4	2 1/16	3	1/2
1 1/2	2 5/16	3 1/2	1/2
1 3/4	2 3/4	4	5/8
2	3 1/4	5	3/4
2 1/2	3 1/4	5 1/2	7/8

NOTES:

1. CIRCULAR OR SQUARE WASHERS MEETING THE SIZE SHOWN ARE ACCEPTABLE.
2. ADEQUATE CLEARANCE MUST BE PROVIDED FOR THE WASHER SIZE SELECTED.




1 TYPICAL BASE PLATE HSS-SECTION




5 TYPICAL W-BEAM TO HSS-COLUMN SHEAR CONNECTION

S-301 NOT TO SCALE




4 TYPICAL MECHANICAL UNIT SUPPORT


5/16/2017 5:45:39 PM
C:\Users\skender\Documents\Draw Local\2171059 - STR - MINI COOPER ROCHESTER_kender.rvt



11
S-302
SECTION AT EXTERIOR WALL
3/4" = 1'-0"




8
S-302
SECTION AT INTERIOR WALL
3/4" = 1'-0"




4
S-302
SECTION AT EXTERIOR WALL
3/4" = 1'-0"


5
S-302
SECTION AT DECK TRANSITION
3/4" = 1'-0"




6
S-302
SECTION AT INTERIOR SUPPORT
3/4" = 1'-0"




7
S-302
SECTION AT INTERIOR SUPPORT
3/4" = 1'-0"



10
S-302
SECTION AT INTERIOR WALL
3/4" = 1'-0"




9
S-302
SECTION AT DECK TRANSITION
3/4" = 1'-0"





1
S-302
SECTION AT EXTERIOR WALL
3/4" = 1'-0"

2
S-302
SECTION AT EXTERIOR WALL
3/4" = 1'-0"



3
S-302
SECTION AT ROOF - OVERHEAD DOOR
3/4" = 1'-0"



11
S-302
SECTION AT EXTERIOR WALL
3/4" = 1'-0"

LaBella

300 State Street
Suite 201
Rochester, NY 14614
P: (585) 454-6110

Engineering
Architecture
Environmental
Planning

www.labellapc.com



It is a violation of New York Education Law Article 145 Sec.7209, for any person, unless acting under the direction of a licensed architect, professional engineer, or land surveyor, to alter an item in any way. If an item bearing the seal of an architect, engineer, or land surveyor is altered; the altering architect, engineer, or land surveyor shall affix to the item their seal and notation "altered by" followed by their signature and date of such alteration, and a specific description of the alteration.

© 2017 LaBella Associates

DORSCHEL MINI OF ROCHESTER

3875 WEST HENRIETTA ROAD
ROCHESTER, NY 14623

SERVICE BAY ADDITION & ALTERATION



NO.	DATE:	DESCRIPTION:
REVISIONS		
PROJECT NUMBER:		2171059
DRAWN BY:		KRD
REVIEWED BY:		JDL
ISSUED FOR:		CONSTRUCTION
DATE:		5/16/2017
DRAWING NAME:		

FRAMING SECTIONS & DETAILS

DRAWING NUMBER:

S-302



It is a violation of New York Education Law Article 145 Sec.7209, for any person, unless acting under the direction of a licensed architect, professional engineer, or land surveyor, to alter an item in any way. If an item bearing the seal of an architect, engineer, or land surveyor is altered; the altering architect, engineer, or land surveyor shall affix to the item their seal and notation "altered by" followed by their signature and date of such alteration, and a specific description of the alteration.

DORSCHEL MINI OF ROCHESTER

3875 WEST HENRIETTA ROAD
ROCHESTER, NY 14623

SERVICE BAY ADDITION & ALTERATION




DORSCHEL
clear. simple. different.

NO.	DATE:	DESCRIPTION:
REVISIONS		
PROJECT NUMBER: 2171059		
DRAWN BY: KRD		
REVIEWED BY: JDL		
ISSUED FOR: CONSTRUCTION		
DATE: 5/16/2017		
DRAWING NAME:		


TYPICAL MASONRY DETAILS

DRAWING NUMBER:


S-401




5 TYPICAL NON-STRUCTURAL TO STRUCTURAL MASONRY WALL
S-401 NOT TO SCALE



HORIZONTAL JOINT REINF. LAP




HORIZONTAL JOINT REINF.




BOND BEAM REINF.

- NOTES:
- THESE DETAILS ARE FOR MASONRY WALLS SUPPORTED ON A CONTINUOUS FOUNDATION WALL OR FOOTING.
 - AT LEAST 50% OF THE MASONRY UNITS AT THE CORNER OR INTERSECTION INTERFACE SHALL INTERLOCK.
 - BALANCE OF VERTICAL WALL REINFORCEMENT NOT SHOWN FOR CLARITY. SEE MASONRY WALL SCHEDULE FOR SIZE AND SPACING.
 - ADDITIONAL VERTICAL BARS TO MATCH WALL REINFORCEMENT. RUN FULL HEIGHT OF WALL & DOWEL INTO FOUNDATION. ADDITIONAL BARS SHALL BE LOCATED WITHIN 8 INCHES OF CORNER OR WALL END.
 - USE PREFABRICATED CORNER AND INTERSECTION JOINT REINFORCEMENT.
 - USE PREFABRICATED CORNER AND INTERSECTION BOND BEAM UNITS OR REMOVE FACESHELL TO ACCOMMODATE REINFORCEMENT BARS & GROUT.




6 TYPICAL BEAM BEARING ON MASONRY WALL
S-401 NOT TO SCALE



- NOTES:
- SEE MASONRY WALL SCHEDULE FOR BLOCK SIZE, REINFORCEMENT SIZE AND SPACING.
 - GROUT REINFORCING SOLID IN BLOCK CORES.
 - PROVIDE BOND BEAMS AT SPACING NOTED IN MASONRY WALL SCHEDULE. AT STRUCTURALLY CONNECTED ROOFS AND FLOOR LEVELS, AND WITHIN 16 INCHES OF THE TOP OF WALLS.
 - RUN BOND BEAMS WITH REINFORCEMENT THROUGH CONTROL JOINTS. SEE TYPICAL CONTROL JOINT DETAIL.
 - LAP SPlice REINFORCEMENT PER ACI 530.
 - AT ALL VERTICAL REINFORCEMENT PROVIDE DOWEL TO FOUNDATION. DOWEL TO MATCH VERTICAL REINFORCEMENT SIZE AND SPACING, UNLESS OTHERWISE NOTED.


4 TYPICAL MASONRY WALL REINF.
S-401 NOT TO SCALE

2 TYPICAL MASONRY WALL CORNER, INTERSECTION, & END
S-401 NOT TO SCALE



3 TYPICAL MASONRY WALL CONTROL JOINT DETAILS
S-401 NOT TO SCALE

- CONTROL JOINT SPACING CRITERIA:
- USE THE LESSER OF THE FOLLOWING:
- 25' - 0" ON CENTER MAXIMUM.
 - 1.5 MAXIMUM LENGTH TO HEIGHT RATIO.
 - AT LOCATIONS INDICATED ON STRUCTURAL AND/OR ARCHITECTURAL DRAWINGS.
- ADDITIONAL LOCATIONS:
- AT CHANGES IN WALL HEIGHT.
 - AT CHANGES IN WALL THICKNESS.
 - LOCATED ABOVE MOVEMENT JOINTS IN FOUNDATIONS OR FLOORS.
 - LOCATED ABOVE AND BELOW MOVEMENT JOINTS IN ROOFS OR FLOORS THAT BEAR ON WALL.
 - ADJACENT TO CORNER OF INTERSECTIONS WITHIN A DISTANCE EQUAL TO HALF THE CONTROL JOINT SPACING.
 - 2' - 0" MINIMUM AWAY FROM FACE OF OPENINGS.
 - COORDINATE WITH VENEER LOCATIONS.



- NOTES:
- SEE MASONRY WALL SCHEDULE FOR REINFORCEMENT SIZE & SPACING. REINFORCEMENT NOTED IN THIS DETAIL IS IN ADDITION TO THAT NOTED IN THE SCHEDULE.
 - GROUT REINFORCING SOLID IN BLOCK CORES.
 - PLACE CONTROL JOINTS AWAY FROM THE OPENING. SEE MASONRY CONTROL JOINT DETAIL.
 - COORDINATE HEIGHTS, OPENINGS, AND LENGTHS OF WALLS WITH ARCHITECTURAL DRAWINGS.
 - PROVIDE HORIZONTAL JOINT REINFORCEMENT IN FIRST OR SECOND MORTAR JOINT BELOW BOTTOM OF OPENING FROM CONTROL JOINT TO CONTROL JOINT.
 - USE ONLY LINTEL BLOCKS FOR BOTTOM COURSE OF LINTEL OVER OPENINGS. UNLESS OTHERWISE NOTED.
 - PROVIDE JAMB BARS FOR FULL HEIGHT TO MATCH VERT. REINFORCING. JAMB BARS NOT REQUIRED FOR OPENINGS SMALLER THAN 16 INCHES UNLESS DISTRIBUTED VERTICAL REINFORCEMENT IS INTERRUPTED BY SUCH OPENING.
 - EXTEND BOND BEAM AND/OR LINTEL WITH REINFORCEMENT A MINIMUM OF 2' - 0" BUT NO LESS THAN 40 BAR DIAMETERS BEYOND EACH SIDE OF OPENING.
 - AT ALL VERTICAL REINFORCEMENT PROVIDE DOWEL TO FOUNDATION. DOWEL TO MATCH VERTICAL REINFORCEMENT SIZE AND SPACING, UNLESS OTHERWISE NOTED.

1 TYPICAL MASONRY WALL OPENINGS
S-401 NOT TO SCALE

DORSCHEL MINI OF ROCHESTER



Service Bay Addition & Alteration

3875 West Henrietta, NY 14623



DORSCHEL
clear. simple. different.



OUTLINE SPECIFICATIONS



Architect

LaBella Associates, D.P.C.
300 State Street
Rochester, NY 14614
585-454-6110

Contractor

Spoleta Construc
7 Van Auker Street
Rochester, NY 14608
585-436-2701

ISSUED FOR PERMIT:

May 17, 2017

OUTLINE SPECIFICATIONS

DORSCHEL MINI OF ROCHESTER SERVICE BAY ADDITION & ALTERATION
3875 W. Henrietta Road, Rochester, NY 14623
PROJECT NO: 2171059

DESCRIPTION:

Construct a building addition approximately 500 s.f. to an existing service wing to provide for a reconfigured space that will include a wash bay, car lift, storage and miscellaneous service work space. Existing equipment to be relocated, minor site work required for new foundations, storm drainage tie-in and concrete walkways.

DIVISION 1 - GENERAL REQUIREMENTS:

Construction shall conform to current editions of the 2015 Building Code of New York State, the 2015 Existing Building Code of New York State, the 2015 Energy Conservation Construction Code of New York State, The 2017 National Electrical Code (NEC), the 2015 Plumbing Code of New York State, the 2015 Mechanical Code of New York State, the 2010 Fuel Gas Code of New York State, the 2015 Fire Code of New York State, and American National Standard for Accessible and Usable Buildings and Facilities (ICC/ANSI A117.1-2003), as well as with all other current local, state and federal codes and regulations applicable to this project.

Manage construction to complete scope of work on time and on budget. Coordinate schedule with Owner and Project Manager.

References to "Owner" shall mean RJ Dorschel Corp., unless otherwise noted.

Contractor is responsible for all materials, construction methods and craftsmanship.

Contractor shall review existing conditions, prior to starting any work.

Contractor to verify all requirements, notes and dimensions prior to the start of construction. Report all discrepancies to the Architect immediately.

Contractor shall be responsible for all changes to these documents. Site visits made by the Architect will not be to verify conformance.

In the event of a dimensional conflict, drawings take precedent over specifications. In the event of a material conflict, specifications shall take precedent over drawings.

Scope of work shall include patch to match (PTM) of any existing areas above, below or beside which are disturbed as a result of construction. The quality of PTM construction shall be equivalent to new. All PTM materials are to match existing unless noted otherwise. When in question, the Contractor shall consult the Owner to determine what the building's "standard" is.

Contractor is responsible for all required temporary protection required to maintain ongoing operations, exiting paths, dust control and occupant safety. It is the Contractor's responsibility to identify the requirements for temporary protection and project phasing and incorporate that cost into



their base bid. Coordinate with the Owner for other requirements.

Finish material and color selections will be made by the Owner and Architect unless otherwise specified or noted.

Submittals: Submit Shop Drawings, Product Data, and Samples for products to be furnished for this project. If submitting as specified clearly state on submittal AS-SPECIFIED:

Doors, Frames and Hardware

Refer to Mechanical/Electrical Specifications for other requirements.

DIVISION 1 – GENERAL REQUIREMENTS:

014000: QUALITY REQUIREMENTS:

A. CONSTRUCTION PHASE TESTING:

B. SCHEDULE OF STRUCTURAL TESTS AND SPECIAL INSPECTIONS: The following tests are to be managed by the General Contractor and paid for by the Owner. Testing to conform to Section 1704 of the Building Code of New York State. Contractor is to provide a copy of the inspection report and/or certification to the Architect upon completion of the test or inspection.

1. 1704.4: Concrete Construction 1704.3.3 High-Strength Bolting & Steel

017700: CLOSE OUT PROCEDURES:

A. REQUIREMENTS AT SUBSTANTIAL COMPLETION: Before requesting inspection for determining date of Substantial Completion, complete the following. List items below that are incomplete in request.

1. Prepare a list of items to be completed and corrected (punch list), and reasons why the Work is not complete.
2. Advise Owner of pending insurance changeover requirements.
3. Submit specific warranties, workmanship bonds, maintenance service agreements, final certifications, and similar documents.
4. Obtain and submit releases permitting Owner unrestricted use of the Work and access to services and utilities. Include occupancy permits, operating certificates, and similar releases.
5. Deliver tools, spare parts, extra materials, and similar items to location designated by Owner. Label with manufacturer's name and model number where applicable.
6. Make final changeover of permanent locks and deliver keys to Owner. Advise Owner's personnel of changeover in security provisions.
7. Complete startup testing of systems.
8. Terminate and remove temporary facilities from Project site, along with mockups, construction tools, and similar elements.
9. Advise Owner of changeover in heat and other utilities.
10. Submit changeover information related to Owner's occupancy, use, operation, and maintenance.
11. Complete final cleaning requirements, including touchup painting.
12. Touch up and otherwise repair and restore marred exposed finishes to eliminate visual defects.

13. Inspection: Submit a written request for inspection for Substantial Completion. On receipt of request, Architect will either proceed with inspection or notify Contractor of unfulfilled requirements. Architect will prepare the Certificate of Substantial Completion after inspection or will notify Contractor of items, either on Contractor's list or additional items identified by Architect, that must be completed or corrected before certificate will be issued.

B. REQUIREMENTS AT CLOSE OUT: Before requesting final inspection for determining date of Final Completion, complete the following:

1. Submit a final Application for Payment.
2. Submit evidence of final, continuing insurance coverage complying with insurance requirements.
3. Instruct Owner's personnel in operation, adjustment, and maintenance of products, equipment, and systems.
4. Inspection: Submit a written request for final inspection for acceptance. On receipt of request, Architect will either proceed with inspection or notify Contractor of unfulfilled requirements. Architect will prepare a final Certificate for Payment after inspection or will notify Contractor of construction that must be completed or corrected before certificate will be issued.

DIVISION 2 – EXISTING CONDITIONS:

024116: SHORING AND BRACING: Extent of shoring and bracing work includes, but is not limited to, shoring and bracing necessary to protect existing building and structure and the removal of bracing, as required. Provide suitable shoring and bracing materials, which will support loads imposed. Contractor shall review all related material and coordinate with rigger as required. Shoring materials need not be new, but should be in serviceable condition. Repair or replace, as acceptable to Architect, adjacent work damaged or displaced through the installation or removal of shoring and bracing work.

024119: SELECTIVE STRUCTURE DEMOLITION: Removal of certain exterior items as required for replacement or repair. Removal of certain existing interior construction including HVAC, plumbing and electrical. Salvage of designated items for relocation. Review all salvage and reuse items with the Owner.

DIVISION 3 - CONCRETE:

033000: CAST-IN-PLACE CONCRETE:

1.1 PRODUCTS

A. Concrete General: ACI 301 and ACI 117.

B. Form facing materials.

C. Steel Reinforcement:



1. Reinforcing Bars: Deformed.
2. Welded-Wire Reinforcement: Plain.

D. Concrete Materials:

1. Portland Cement: ASTM C 150, Type I/II.
2. Fly ash.
3. Slag cement.
4. Blended Hydraulic Cement.
5. Silica fume.
6. Aggregate: Normal weight.
7. Water.

E. Mixing: Ready mixed.

1.2 CONCRETE MIXTURES

A. Portland Cement Replacement: Use fly ash, slag cement, and silica fume to reduce portland cement by 20-45 percent.

B. Compressive Strength (28 Days):

1. Footings: 4500 psi.
2. Slabs-on-Grade: 3500 psi.
3. Exterior Concrete: 5000 psi.

1.3 INSTALLATION

A. Formed Finishes: Rubbed.

B. Floor and Slab Finishes:

1. Scratch: Surfaces to receive concrete floor toppings.
2. Float: Surfaces to receive trowel.
3. Trowel: Surfaces exposed to view or to be covered with epoxy paint.
4. Broom: Exterior concrete slabs.

1.4 FIELD QUALITY CONTROL

A. Testing: By Owner-engaged agency.

B. Special Inspections: By Owner-engaged special inspector.

END OF SECTION 033000

033001: CONCRETE SEALER: Curing and Sealing Compound: Apply uniformly to floors and slabs indicated in a continuous operation by power spray or roller according to manufacturer's written instructions. Repeat process within 24 hours after initial application and apply a second coat. Maintain continuity of coating and repair damage during curing period.

036000: GROUTS: Non-shrink grout shall be Quikrete Fast Set or equal. Grout shall meet or exceed the requirements in testing standards ASTM C939, C143, C191, C928, C939, C1090 & C1107. Minimum compressive strength at 28 days 6,500 psi. Install per manufacturers specifications.

DIVISION 4 - MASONRY:

0422000: CONCRETE UNIT MASONRY:

1.1 PERFORMANCE REQUIREMENTS

- A. Net-Area Compressive Strengths of Structural Unit Masonry: As indicated.
- B. Determine net-area compressive strength of masonry by unit-strength method.

1.2 MATERIALS

- A. Concrete Masonry Units (CMUs):
 - 1. Units made with integral water repellent where indicated.
 - 2. CMUs: Normal weight.
 - 3. Insulated CMUs- R-20.
- B. Masonry Lintels: prefabricated or built-in-place CMU lintels.
- C. Reinforcing Steel: Uncoated-steel reinforcing bars.
- D. Masonry-Joint Reinforcement:
 - 1. Interior Walls: Hot-dip galvanized, carbon steel.
 - 2. Exterior Walls: Hot-dip galvanized, carbon steel.
- E. Ties and Anchors: Galvanized steel.
 - 1. Adjustable anchors for connecting to structural steel framing.
 - 2. Adjustable anchors for connecting to concrete.
 - 3. Partition top anchors.
 - 4. Rigid anchors.



F. Reinforcing bar positioners.

G. Mortar:

1. Portland cement-lime, masonry cement or mortar cement mortar unless otherwise indicated.

1.3 FIELD QUALITY CONTROL

- A. Testing Agency: Owner engaged.
- B. Inspections: Special inspections according to Level B in TMS 402/ACI 530/ASCE 5.
- C. Testing: One set of tests for each 5000 sq. ft. of wall area.

END OF SECTION 042200

DIVISION 5 - METALS:

051200: STRUCTURAL STEEL FRAMING:

1.1 SUMMARY

- A. Structural steel as classified by AISC 303.
- B. Grout.

1.2 QUALITY ASSURANCE

- A. Fabricator Qualifications: AISC-Certified Plant, Category STD.
- B. Shop-Painting Applicator Qualifications: AISC's Sophisticated Paint endorsement or SSPC-QP 3.
- C. Quality Standards: AISC 303 and AISC 360.

1.3 PERFORMANCE REQUIREMENTS

- A. Fabricator to select or complete simple shear connections, including engineering analysis by a qualified professional engineer, to withstand design loads.

1.4 MATERIALS

- A. Structural-Steel Shapes: W-shapes, channels, angles, plate, and bar cold-formed hollow structural sections.
- B. Steel castings.
- C. Steel forgings.
- D. Bolts, Nuts, and Washers: High strength.
- E. Anchor Rods: Unheaded rods, nuts, plate washers, and washers.
- F. Connectors: threaded rods.
- G. Primer: Fabricator's standard, nonasphaltic.
- H. Grout: Nonmetallic, shrinkage resistant.

1.5 FABRICATION

- A. Shop Connections:
 - 1. High-Strength Bolts: Snug tightened.
 - 2. Welded connections.
- B. Galvanize: Lintels, shelf angles and welded door frames located in exterior walls.

1.6 SOURCE QUALITY CONTROL

- A. Testing Agency: Owner engaged.

1.7 INSTALLATION

- A. Field Connections:
 - 1. High-Strength Bolts: Snug tightened.
 - 2. Welded connections.

1.8 FIELD QUALITY CONTROL

- A. Special Inspector: Owner engaged.
- B. Testing Agency: Owner engaged.



END OF SECTION 051200

053100: STEEL DECKING:

1.1 MATERIALS

A. Roof Deck: Galvanized- steel sheet.

1. Profile Depth: As indicated.

B. Accessories: girder fillers, end closures, Z-closures, and cover plates recessed sump pans and flat sump plates.

1.2 INSTALLATION

A. Roof Deck: Welded or Mechanically fastened.

1.3 FIELD QUALITY CONTROL

A. Testing Agency: Owner engaged.

END OF SECTION 053100

055000: METAL FABRICATIONS:

1. Provide loose bearing and leveling plates, loose steel lintels, shelf and relieving angles and miscellaneous framing and supports. Provide ferrous materials as follows:
 - (a) Steel Plates, Shapes and Bars: ASTM A 36.
 - (b) Brackets, Flanges, and Anchors: Cast or formed metal.
 - (c) Zinc-Coating: Hot-dip galvanized coating for materials in exterior assemblies or exterior walls.
2. Structural steel shall conform to 1989 American Institute of Steel Construction (AISC) specifications and code of standard practice. The length of framed beam connections shall be approximately equal to the at@ distance of the smaller beam unless otherwise noted. Structural steel shall be shop painted with an alkyd primer paint. Touch up all field welds and exposed or rusted areas after fabrication complete with same primer paint. Connections shall be designed for 1.0 times the end reactions computed from the table "uniform load constants" in the AISC manual unless otherwise noted. Bolts shall be ASTM A325 unless otherwise noted. Anchor bolts shall be ASTM A307 or ASTM A36. Welding shall conform to AWS D1.1. Electrodes shall be E70xx. Weld continuously, grind flush and make smooth on exposed surfaces. Contractor shall take field measurements prior to preparation of shop drawings and fabrication. Do not delay job; allow for cutting and fitting if field measurement not practical. Install work plumb and level with hairline joints and ground flush welds. Lintels: Provide sizes indicated with 8" (minimum) bearing at each end.

DIVISION 6 - WOOD & PLASTICS:

061053: MISCELLANEOUS ROUGH CARPENTRY: fire treated wood blocking as required for equipment etc. DANBACK or approved. Coordinate locations for all equipment with Owner prior to installing gypsum board on framing. No. 2 hem fir or better with minimums of: Fb = 1,150 psi.; Fv = 75 psi.; E = 1,400,000 psi.

DIVISION 7 - THERMAL & MOISTURE PROTECTION:

072100: THERMAL INSULATION

- A. Rigid Board Insulation (for below grade):
 - 1. Type: Extruded polystyrene, rigid, ASTM C 578, Type IV.
 - 2. Dow Square Edge or approved equal by Owens Corning or Tenneco.
- B. Foil-Faced, Polyisocyanurate Board Insulation (for roof):
 - 1. Type I, Class 2, ASTM C 1289, with maximum flame-spread and smoke-developed index of 450
 - 2. Atlas Roofing Corporation, Dow Chemical Company, R-max, Inc, Hunter Panel Insert
- C. Vapor Barrier (where not Integral with Insulation):
 - 1. Type: Polyethylene, ASTM D 4397, 6 mils, 0.13 perm vapor transmission rating.
 - 2. Vapor barrier tape as recommended by the manufacturer.
- D. Accessories.
 - 1. Adhesives and mechanical anchors.
 - 2. Crack / joint sealers and tapes.

075323: EPDM MEMBRANE ROOFING:

- A. Fully Adhered System. ASTM D 4637, Type II, fabric internally reinforced uniform, flexible sheet made from EPDM, and as follows:
- B. Manufacturers: Subject to compliance with requirements, provide products by the manufacturers specified or approved equal.
 - 1. Carlisle SynTec Incorporated.
 - 2. Firestone Building Products Company.
- C. Thickness: 60 mils(1.5 mm), nominal.
- D. Exposed Face Color: White.
- E. Roof Board: 5/8" Dens Deck Prime.
- F. Provide all required fasteners and accessories for a complete installation. Provide standard. manufacturer's 10 year warranty. Product shall be installed by a certified installer with a minimum of 3 years of experience with approved product.

076200: SHEET METAL FLASHINGS AND ROOF TRIM:

Prefinished .040" aluminum drip edge, gravel stop, flashing, coping and other shapes as shown on drawings. Aluminum Sheet: ASTM B 209(ASTM B 209M), Alloy 3003, 3004, 3105, or 5005, Temper suitable for forming and structural performance required, but not less than H14, finished as follows:

Siliconized-Polyester Coating: Epoxy primer and silicone-modified, polyester-enamel topcoat. Color: As selected by Architect from manufacturer's full range to match existing.

078413: PENETRATION FIRESTOPPING: Review cover sheet "Code Review Information" and Code Plan for fire separation requirements. Consult with Architect if unsure about locations or required rating.

A. One-Part Fire-Stopping Sealant: For sealing openings around cables, conduit, pipes and similar penetrations through fire rated walls and floors and at joints between partitions and roof or floor decks. Sealant must be red in color. Use only at penetrations in fire rated walls and floors.

1. "3M Fire Barrier Caulk CP-25WB+"; Electrical Products Div./3M.
2. "FS-One", Hilti
3. "TPS Type I", Isolatek
4. "TPS Type C", Isolatek
5. "Series 100 Sealant", Specified Technologies, Inc.
6. "2000 Series Sealant", 3M
7. Or approved equal.

B. Fire-Stopping Systems: Where elastomeric sealants are not applicable to conditions encountered, provide UL listed fire-stopping systems including putty, mortar, foam, intumescent pillows or rigid board. Materials must be red in color or must consist of devices and hardware that are readily identifiable as being a part of a UL listed assembly. Manufacturers: 3M Fire Protection Products, Hilti, Isolatek International, Nelson Firestop Products, Specified Technologies, Inc., United States Gypsum Co.

079200: JOINT SEALANTS: Install appropriate sealant and foam backer rod where shown and at all joints exposed to weather.

A. ONE-PART NONACID-CURING SILICONE SEALANT: For exterior vertical applications, Type S; Grade NS; Class 25. Uses NT, M, G, A, and, as applicable to joint substrates indicated.

1. "Chem-Calk 1200"; Bostik Construction Products Div.
2. "Dow Corning 790"; Dow Corning Corp.
3. "864"; Pecora Corp.
4. "Spectrem 2"; Tremco, Inc.

B. ONE-PART POURABLE URETHANE SEALANT: for Horizontal surfaces, use T: Type S, Grade P, Class 25:

1. "Chem-Calk 950"; Bostik Construction Products Div.
2. "Vulkem 45"; Mameco International, Inc.
3. "NR-201 Urexpand"; Pecora Corp.
4. "Sonolastic SL-1"; Sonneborn Building Products Div, Rexnord Chemical Products Inc.

C. SILICONE LATEX JOINT SEALANTS: For exposed interior use. Pecora AC-20+Silicone"

D. INTERIOR ACOUSTICAL SEALANTS FOR CONCEALED JOINTS:

1. "BA-98"; Pecora Corp.
2. "Tremco Acoustical Sealant"; Tremco Inc.

E. TRAFFIC GRADE SEALANT: for exterior use at concrete aprons. Tremco Spectrum 800 Highway and Parking Structure Sealant. Low-modulus, self-leveling silicone, high-performance, one-part, gun grade.

DIVISION 8 - DOORS:

081113: HOLLOW METAL DOORS AND FRAMES:

- A. MANUFACTURERS: Steelcraft, Ceco, Fleming, Curries, Pioneer or approved equal.
- B. FRAMES: 14 gauge galvanized welded frames at exterior locations. 16 gauge primed all interior locations: knock down typically except welded at: double doors, cross corridor doors, doors with automatic operators, doors 42" or more wide.
- C. DOORS: 18 gauge flush steel seamless doors (HMMA861). UL labeled fire rating as shown or required. LIGHT FRAMES: Standard 18 gauge frames matching Marshfield #115 at rated doors. Marshfield W-6 at unrated and 20 minute rated doors.

087100: DOOR HARDWARE:

- A. HINGES: Reuse existing to be relocated as noted.
- B. LOCK CYLINDERS AND KEYING: Reuse existing to be relocated as noted.
- C. FINISHES: Existing

DIVISION 9 - FINISHES:

09671: RESILIENT RESINOUS (Epoxy EX-1) FLOORING

GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

1.2 SUMMARY

A. This Section includes the following:

- 1. General-use epoxy flooring for service bay.
- 2. Work of this Section includes all labor, materials, equipment and services necessary to prepare the new slab and complete multi-layered troweled waterproof floor surfacing as scheduled on the drawings and/or specified herein.

B. Related Sections include the following:

- 1. Concrete - Section 03300.
 - a. Concrete slab should be either water cured or cured using sodium silicate curing compounds only. Other types of curing compounds are generally not acceptable. Concrete should be cured for a minimum of 28 days.
- 2. Floor drains - Division 15.
 - a. Floor drains, clean-outs, etc. should match existing and be installed per manufacturers recommendations.
- 3. Joint Sealants – Division 7

1.3 SUBMITTALS

- A. Maintenance Data: For resilient products to include in maintenance manuals.
- B. General: Submit the following in accordance with Conditions of Contract and Division 1 Specification Sections.
- C. Product Data: Submit manufacturer's technical data, application instructions and general recommendations for multi-layered troweled waterproof flooring surfacing specified herein.
- D. Samples for initial selection purposes in form of manufacturer's color charts showing full range of colors and finishes available.
Submit 2-1/2" x 4" samples in color as selected.
- E. Material certificates signed by manufacturer certifying that the multi-layered troweled waterproof flooring surfacing complies with requirement specified herein.
- F. Maintenance Instructions: Submit manufacturer's written instructions for recommended maintenance practices.

PRODUCTS

2.1 MANUFACTURERS

- A. Available products: Subject to compliance with requirements, products that may be incorporated into the work include:
 - 1. NDex-O-Tex M-E Flooring or approved equal.
 - 2. General Polymers Corp.

END OF SECTION 09651

099100: PAINTING: Prepare existing surfaces as required to receive new finishes: clean, remove adhesives, patch and spackle, and sand. Colors to be selected by Owner and Architect. Provide the following paint systems for the various substrates, as indicated.

- A. MANUFACTURERS: Pratt and Lambert or approved equal.
- B. INTERIOR METAL:
 - 1. Semi-Gloss Emulsion Finish: 3 Coats.
 - a. First Coat: P&L Suprime "3"
 - b. Second and Third Coats: P&L Accolade Interior Semi-Gloss
- C. EXTERIOR METAL (UNGALVANIZED IRON OR STEEL, ALUMINUM):
 - 1. Gloss Alkyd Enamel Finish: 3 coats.
 - a. First Coat: P&L Suprime "9"
 - b. Second and Third Coats: P&L RedSeal Interior/Exterior Oil Gloss
- D. CONCRETE MASONRY UNITS & DIRECT APPLIED FINISH SYSTEM:
 - 1. Eggshell Emulsion Finish: 3 Coats.



- a. First Coat: P&L Pro-hide Silver Heavy Duty Block Filler
- b. Second and Third Coat: P&L Pro-Hide Gold Low Odor Eggshell

DIVISION 10 – SPECIALTIES:

102123: AUTO-GUARD WASH BAY CURTAIN:

- A. Manufacturer: To be selected by Owner
- B. Track: Heavy gauge galvanized steel
- C. Curtain: Durable 18 oz vinyl reinforced with clear vinyl vision panel, hemmed edges and resistant to wash down chemicals. Curtains to be Owner Furnished, Contractor Installed
- D. Carriers to be roller type
- E. Provide system with all necessary accessories for complete installation and proper operation including adequate carriers for the installation, end stops, splices, clips and fasteners.

104400: FIRE PROTECTION SPECIALTIES: Relocate existing fire extinguisher as indicated on drawing.

DIVISION 11 - EQUIPMENT: Reuse existing to be relocated as noted.

DIVISION 12 - FURNISHINGS: (NOT NEEDED FOR THIS PROJECT)

DIVISION 13 - SPECIAL CONSTRUCTION: (NOT NEEDED FOR THIS PROJECT)

DIVISION 14 - CONVEYING SYSTEMS:

14450: VEHICLE LIFTS:

- A. Owner Furnished, Contractor installed.
- B. Manufacturer: Hunter Engineering Company – model RX10FT-ISBLK FLUSH MOUNT SCISSOR LIFT RACK and 20-2766-1 RX Lift LED Lighting Kit – See attachment.

DIVISION 15 - MECHANICAL:

Mechanical systems are existing to remain unless otherwise as noted on plans. All mechanical work in accordance w/ federal, state, and local codes. Contractor shall deliver to the Owner complete and legal systems, tested in all respects and ready for operation. Contractor shall pay all fees, secure all permits and arrange for all testing required for mechanical system.

All mechanical equipment shall be warranted for a period of one year from the Date of Substantial Completion. The contractor shall guarantee, in writing, all equipment installed under this contract.



During the guarantee period, all defects shall be remedied without cost to the Owner. The contractor shall at the time of closeout instruct the owner in the proper operation of the systems, and supply the owner with all maintenance and operating instructions, along with his written guarantee and manufacturer's warranties, all bound in folders.

All gas piping in conformance with local utility company requirements.

All HVAC work shall be as designed. All HVAC work shall be new and complete in all respects. Coordinate installation and placement of utility connections to ensure proper equipment operation. Balance system to CFM's shown on drawings.

DIVISION 16 - ELECTRICAL:

Electrical systems are existing to remain unless otherwise as noted on plans. All electrical work in conformance w/ latest edition of National Electric Code (N.E.C). Furnish all materials, accessories, fittings, fixtures and equipment; perform work required to deliver electrical systems in a complete, proper and legal working order.

The total electrical system must be inspected by the New York Board of Fire Underwriters. The contractor secure a rough and final inspection and furnish certificates of final approval from the Underwriters Inspection Bureau. All materials, equipment and devices shall be new, installed in a workmanlike manner and clearly marked to identify manufacturer, model and UL Rating.

All electrical systems shall be warranted for a period of one year from the date of project Date of Substantial Completion. The contractor shall guarantee, in writing, all equipment installed under this contract. During the guarantee period, all defects shall be remedied without cost to the Owner. The contractor shall, at the time of closeout, instruct the Owner in the proper operation of the systems, and supply the owner with all maintenance and operating instructions, along with his written guarantee and manufacturer's warranties, all bound in folders.

All conduit and wiring shall be concealed from view. Support all wiring as per N.E.C. Wire all circuits. Clean all lighting fixtures, provide and install lamps, bulbs or tubes at completion of job. Provide typed panel schedules to properly fit panel schedule holder in box. Mark all circuit breaker schedules. Duplex outlet and switch covers to be stainless steel. All devices shall be as required by Code.

Smoke detectors system shall be installed in accordance w/ U.L., N.E.C., NYS Bldg. Code and Town requirements. System shall be tested prior to acceptance.

Relocate existing exit signs, fire alarm pull stations, strobe devices, audio devices, that are in project scope of work.

Refer to scopes of work for all cutting and patching regarding this work.

DIVISION 22 – PLUMBING



Existing Plumbing to remain unless otherwise as noted on plans. All plumbing work in accordance w/ federal, state, and local codes. Contractor shall deliver to the Owner complete and legal systems, tested in all respects and ready for operation. Contractor shall pay all fees, secure all permits and arrange for all testing required for plumbing system. All water, waste and vent lines, and plumbing fixtures are to be securely supported with proper hangers from structure or equipment carriers. All valves are to be tagged. Test and disinfect water lines per local water department requirements. All wall hung fixtures shall be on floor mounted arm-type carriers.

Perform all excavation, backfilling, compaction in accordance with Village/City/Town requirements.

221301: FACILITY WASTE WATER SYSTEMS:

- A. Manufacturer: Zurn Trench Drain System - model Z884 with composite grate.
- B. Floor Drain at lift pit to match existing floor drains and installed per manufacturers recommendations.

DIVISION 31 – EARTHWORK

312000: EARTHWORK: Provide gravel or crushed stone for sub-base materials. Provide mineral soil substantially free from organic and unsuitable materials, and free from rock or gravel larger than 2" in diameter for common fill materials. Place fill in 6"-8" lifts and compact each lift to at least 95% of maximum density as determined by the Modified Proctor Method. Slope all grades away from building.

DIVISION 32 – EXTERIOR IMPROVEMENTS

321216: ASPHALT PAVING: Patch to match at areas disturbed by new work. Saw cut areas of pavement to be removed. Tack coat edges of pavement repair before paving. Perform work in accordance with NYSDOT, Section No. 401 – Plant Mix Pavements – General.

031313: CEMENT CONCRETE PAVING: Portland cement concrete for sidewalks and aprons, structures

END OF SPECIFICATION

RX10FT-IS (RX LIFT RACK WITH INFLATION STATION) FLUSH-MOUNT SCISSOR LIFT RACK SITE REQUIREMENTS

RX10FT-IS lift racks are installed in a shallow pit to place the surface of the runways flush with the floor when the lift is in the fully lowered position. All flush-mount scissor lift racks have ramps on both ends to allow for drive-thru shop configuration.

IMPORTANT: Use *attached Pit Construction Drawings* to determine if the selected site is suitable.

NOTE: For RX10JFT and RX10FT-PS (RX with NO inflation Station), refer to Form 6187-T.

Pit Construction

- ☐ Choose the *Pit Construction Drawing* that best suits the shop's desired layout:
 - Page 3 Console located at rear (approach-end) of lift rack
 - Page 4 Console located at front (turnplate-end) of lift rack
 - Page 5 Console located at alternative front location (at aligner console in front of rack)
- ☐ The Hunter representative and shop owner are to work together to complete *Pit Construction Drawing* by determining dimensions and details for topics A, B and C.
 - A. Bay door clearance and space for alignment sensors.
 - B. Console's location, distance from pit and side of pit.
 - C. Additional in-ground conduit beyond the required console-to-pit conduit.
- ☐ Provide contractor with completed *Pit Construction Drawing*.
 - Additional details of runway anchoring and console is also available (pages 6 and 7).

Site

Bay Length

- Hawkeye (HS) Series Sensors require a specified amount of space at the front of the lift. *Refer to the appropriate Hawkeye Site Requirements.*
- The rear overhang of longer vehicles may prevent the closure of bay door. A distance of 39 inches (991 mm) from the garage entrance to the back edge of the pit will accommodate most vehicles.

Bay Height

- Minimum ceiling height of lift area is 13 feet (3962 mm). Lift elevates 72 inches (1829 mm) above pit floor.

Power Requirements

- 208/230 VAC, single phase power, 60 Hz
- Wiring and circuit breakers should be sized according to local electrical codes to provide 25 Amp draw available at motor.
- Availability of specified power is necessary to install lift rack. Temporary power connection is acceptable.


Air Requirements

- 125-150 PSI (8.6-10.3 bar)
- Rack only requires 90 PSI (6.2 bar), but jacks require 125 PSI (8.6 bar) for full capacity operation.

Pit Requirements

- 3 inches (76 mm) thick with a 3000 PSI (20,700 kPa) rated concrete
- Drain or sump must be included in pit. Flooding will void product warranty.
- Approach and exit ramps require a smooth floor for best function. Tile or other irregularities may cause ramps to hang-up
- Ideal bay for pit installation would have a level floor (no floor slope over the length of pit).

- Significant slope of the bay floor toward the bay entrance will result in the approach end of rack setting above grade when the lift is in the lowered positioned. The approach ramps will elevate an amount that is equal to the amount the bay floor lowered over the length of pit. 3 in. (76 mm) maximum recommended.




Pit Installation into a Bay with Floor Slope toward Entrance

- Elevated ramps will clatter when vehicle is driven onto rack. This condition will not hurt vehicle. Depending on the amount of height difference due to bay floor slope and weight of vehicles serviced, the approach ramp may begin to deform over time. Building-up approach edge of pit will alleviate condition.


Simplified Plan View and Elevation View

* Longer vehicles will need to be serviced with the bay door open. To accommodate most vehicles, increase the space behind the pit to 39 in. (991 mm) or greater.

** Hawkeye series sensors and Pronto systems have space requirements in front of lift that must be met, refer to appropriate site requirements.




⚠ WARNING: Pit-to-lift gap of 2 inches all the way around the lift is important for safety.




SECTION B-B

CONSOLE CONDUIT DETAIL



CONSOLE OPENINGS

PRIOR TO INSTALL



- 208-230 VAC, 1 phase, 60 HZ for 26 Amp draw is required near control console location.
- 125-150 psi (8.6-10.3 bar) shop air is required near control console location.

INDIVIDUAL SHOP LAYOUT

Owner needs to decide the best location for the lift rack, console and in-ground conduit to accommodate their facility plan.

A PIT PLACEMENT WITHIN BAY: Space in front of the lift rack for alignment equipment should be considered. Sensor space requirements are flexible to accommodate a variety of bays. Refer to the sensor's site requirements.

Example: 64 1/4 in. (1632 mm) in front of the pit (A₂) is needed for a floor-mount, Hawkeye sensor.

Accommodations behind the lift rack (A₁) for the overhang of large vehicle should also be considered.

B CONSOLE LOCATION / CONDUIT: 4-inch (100 mm) conduit is required from rack to console. Location of console is to be determined by owner.

This drawing shows rear console location.

Console can be located on opposite side of pit; same distance limitations and requirements apply.

Various console locations are specified on separate drawings.

C ADDITIONAL IN-GROUND CONDUIT: Optional below-ground conduits may be needed to complete desired installation.

Power and shop air are required at console. Openings within console base are shown to accommodate plans to have conduit come-up within console.

Optional conduit for FIA communication between console and alignment console is another consideration.

Abide by all local codes for in-ground conduits. General conduit recommendation is large diameter with bends no greater than 45°.

OPTIONAL FIA CONDUIT

CONSTRUCTION NOTES

- Bay floor slope is allowed. For the typical slope (towards door), The rack will be above floor level at the approach end by slope amount.
- Pit floor is to be overall level with a slope towards central drain. Drain is 1/2 in. (13 mm) below the pit floor's perimeter elevation.
- Entire pit (floor and walls) must be hard trowel finished.
- Dimensions are for finished pit. Adjust pit dimensions for tile thickness, if applicable.
- Workspace about pit perimeter is needed for automotive service. (36 in.(914mm) typical workspace)
- BEFORE POURING CONCRETE,** contact your Hunter sales or service representative to verify pit. <http://www.hunter.com/find-a-rep>
- Four 14 x 5 in. (356 x 127 mm) cutouts are required for inflation station (-IS) feature. Pit edging is not required for IS cutouts.

SPACE FOR ALIGNMENT SENSORS


A₂=

See sensor site requirements.


FRONT BAY WALL (Example of bay wall location shown)

SECTION C-C


EDGE DETAIL



SECTION A-A PIT CONSTRUCTION DETAIL





REAR CONSOLE



RX10FT-IS

WITH CONSOLE AT REAR OF PIT

PRIOR TO INSTALL



Abide by all local codes for in-ground conduits. General conduit recommendation is large diameter with bends no greater than 45°.

Finished floor ①
zero elevation reference is at
high end of floor (typically front)



SECTION B-B

CONSOLE CONDUIT DETAIL

CONSOLE OPENINGS

PRIOR TO INSTALL

INDIVIDUAL SHOP LAYOUT

Owner needs to decide the best location for the lift rack, console and in-ground conduit to accommodate their facility plan.

A PIT PLACEMENT WITHIN BAY: Space in front of the lift rack for alignment equipment should be considered. Sensor space requirements are flexible to accommodate a variety of bays. Refer to the sensor's site requirements.

Example: 64 1/4 in. (1632 mm) in front of the pit (A₂) is needed for a floor-mount, Hawkeye sensor. Accommodations behind the lift rack (A₁) for the overhang of large vehicle should also be considered.

B CONSOLE LOCATION / CONDUIT: 4-inch (100 mm) conduit is required from rack to console. Location of console is to be determined by owner.

This drawing shows near-aligner location. Console can be located on opposite side of pit; same distance limitations and requirements apply.

Various console locations are specified on separate drawings.

C ADDITIONAL IN-GROUND CONDUIT: Optional below-ground conduits may be needed to complete desired installation.

Power and shop air are required at console. Openings within console base are shown to accommodate plans to have conduit come-up within console.


Optional conduit for FIA communication between console and alignment console is another consideration.

Abide by all local codes for in-ground conduits. General conduit recommendation is large diameter with bends no greater than 45°.

CONSTRUCTION NOTES

- 1 Bay floor slope is allowed. For the typical slope (towards door), The rack will be above floor level at the approach end by slope amount.
- 2 Pit floor is to be overall level with a slope towards central drain. Drain is 1/2 in. (13 mm) below the pit floor's perimeter elevation.
3. Entire pit (floor and walls) must be hard trowel finished.
4. Dimensions are for finished pit. Adjust pit dimensions for tile thickness, if applicable.
5. Workspace about pit perimeter is needed for automotive service. (36 in.(914mm) typical workspace)
6. **BEFORE POURING CONCRETE**, contact your Hunter sales or service representative to verify pit. <http://www.hunter.com/find-a-rep>
- 7 Four 14 x 5 in. (356 x 127 mm) cutouts are required for inflation station (-IS) feature. Pit edging is not require for IS cutouts.

- 4 in. (100 mm) diameter conduit
- Maximum bend 45° (no 90°'s)
- Maximum run 198 in. (5029 mm)
- Exit into pit at floor level and at threshold centerline



- 208-230 VAC, 1 phase, 60 HZ for 26 Amp draw is required near control console location.
- 125-150 psi (8.6-10.3 bar) shop air is required near control console location.


ALT. FRONT CONDUIT: Maximum run is 198 in. (5029 mm)

- 1 Bay floor slope is allowed. For the typical slope (towards door), The rack will be above floor level at the approach end by slope amount.
- 2 Pit floor is to be overall level with a slope towards central drain. Drain is 1/2 in. (13 mm) below the pit floor's perimeter elevation.
3. Entire pit (floor and walls) must be hard trowel finished.
4. Dimensions are for finished pit. Adjust pit dimensions for tile thickness, if applicable.
5. Workspace about pit perimeter is needed for automotive service. (36 in.(914mm) typical workspace)
6. **BEFORE POURING CONCRETE**, contact your Hunter sales or service representative to verify pit. <http://www.hunter.com/find-a-rep>
- 7 Four 14 x 5 in. (356 x 127 mm) cutouts are required for inflation station (-IS) feature. Pit edging is not require for IS cutouts.


SECTION C-C EDGE DETAIL

- Anchors welded at approx. 12 in. (305 mm) apart
- 2 x 2 x 1/4 in. ANGLE (typ.)
- Painted safety yellow
 - Contractor supplied
 - Breaks at "IS" cutouts 7

SECTION A-A PIT CONSTRUCTION DETAIL



ALTERNATIVE FRONT CONSOLE




RX10FT-IS

WITH CONSOLE NEAR ALIGNER


REFERENCE A - Runway Base Plate Anchor Locations

- Using lift / pit centerline and indicated threshold location to determine the approximate location of each anchor to secure runway base plates
- In-floor heating lines need to avoid anchor locations.
- In some instances reinforcing bars within concrete have interfered with anchors.
- Typical installation has an anchor at each corner of base plates. Optional (OPT) anchor locations are only use in unique circumstances, such as meeting seismic requirements.



REFERENCE B - Rack Console Details

- Use these additional consoles to possibly fine tune a rack installation plan.



ATTACHMENT 2

Pertinent Subsurface Investigation Logs and Figures



300 STATE STREET, ROCHESTER, NY
ENVIRONMENTAL ENGINEERING CONSULTANTS

TEST PIT LOG PROJECT

Remedial Investigation: Test Pit Soil Sampling
3875 West Henrietta Road
Henrietta, New York

BORING: RITP-4

SHEET 1 OF 1

JOB: 206139.02

CHKD BY:

CONTRACTOR: TREC Environmental TEST PIT LOCATION: TIME: 1124 TO ###
EXCAVATOR: Kubota KX121-3 Super S₁ GROUND SURFACE ELEVATION: NA DATUM: NA
LABELLA REPRESENTATIVE: C. A. Stiles START DATE: 27-Apr-07 END DATE: 27-Apr-07

TYPE OF DRILL RIG: DRIVE SAMPLER TYPE: 4-foot Macrocore
AUGER SIZE AND TYPE: NA INSIDE DIAMETER: ~1.8-Inch
OVERBURDEN SAMPLING METHOD: Direct Push OTHER:

DEPTH	SAMPLE		VISUAL CLASSIFICATION	PID FIELD SCREEN (PPM)	REMARKS
	SAMPLE NO AND DEPTH	STRATA CHANGE			
0		0.0-ft.	<u>FILL MATERIAL</u> Asphalt Pavement Brown cmf SAND, some(+) cmf subrounded Gravel, Also includes boulders, damp to wet, no odors.	0.0	
		0.3 to 0.4-ft.		0.1	
2		1.0-ft.	Gray to dark gray cmf ⁽⁺⁾ SAND. some cmf angular to subrounded Gravel, trace(+) Clayey Silt, damp, no odors.	0.0	
		2.1-ft.	Gray cmf subround to subangular GRAVEL and cmf SAND, trace Clayey Silt, damp to saturated @ ~3.4-ft., no odors.	0.1	
4		3.5-ft.	<u>GLACIAL TILL</u> Brown Clayey SILT to Silty CLAY, little(-) cmf subangular to subrounded Gravel, trace cmf Sand, saturated, no odors.	0.0	
				0.0	
6			Total Depth of Test Pit = 5.1-feet Below Ground Surface		
8					
10					
12					

WATER LEVEL DATA			BOTTOM OF CASING	BOTTOM OF BORING	GROUNDWATER ENCOUNTERED	NOTES: No metal or other man-made debris observed within soils excavated from the test pit.
DATE	TIME	ELAPSED TIME		5.1-Ft.	Approx. 3.4-ft. BGS	

GENERAL NOTES

- STRATIFICATION LINES REPRESENT APPROXIMATE BOUNDARY BETWEEN SOIL TYPES, TRANSITIONS MAY BE GRADUAL.
 - WATER LEVEL READINGS HAVE BEEN MADE AT TIMES AND UNDER CONDITIONS STATED, FLUCTUATIONS OF GROUNDWATER
 - Abbreviations
and = 35 to 50 %
some = 20 to 35%
little = 10 to 20%
trace = 1 to 10%
c = coarse
m = medium
f = fine
vf = very fine
- BGS = Below the Ground Surface
NA = Not Applicable

BORING: RITP-4



300 STATE STREET, ROCHESTER, NY
ENVIRONMENTAL ENGINEERING CONSULTANTS

PROJECT

Remedial Investigation
3865 & 3875 West Henrietta Road
Henrietta, New York

BORING: RITB-9

SHEET 1 OF 1

JOB: 206139.02

CHKD BY:

CONTRACTOR: Trec Environmental Services

DRILLER: Paul Wiley

LABELLA REPRESENTATIVE: C. A. Stiles

BORING LOCATION:

GROUND SURFACE ELEVATION: NA

START DATE: 08-May-07

END DATE: 08-May-07

TIME: 1137 TO

DATUM: NA

TYPE OF DRILL RIG: Truck/Track Mounted Geoprobe Model 54LT

AUGER SIZE AND TYPE: NA

OVERBURDEN SAMPLING METHOD: Direct Push

DRIVE SAMPLER TYPE: 4-foot Macrocore

INSIDE DIAMETER: ~1.8-Inch

OTHER:

DEPTH	SAMPLE			VISUAL CLASSIFICATION	PID FIELD SCREEN (PPM)	REMARKS			
	SAMPLE NO. AND DEPTH	SAMPLE RECOVERY	STRATA CHANGE						
0	S-1 0' to 4'	1.3-ft.	0.0-ft. 0.5-ft.	<u>FILL MATERIAL</u> Concrete Slab - Not sampled. Gray cm ⁽⁺⁾ SAND, some(-) cmf subangular to angular Gravel, slightly moist, slight weathered petroleum odor.	6.1				
2					8.4				
4									
6	S-2 4' - 8'	2.6-ft.	4.0-ft. 4.6-ft. 5.6-ft.		<u>LACUSTRINE</u> Grayish-brown Clayey SILT, trace mf(+) Sand, saturated, no odors. Brown SILT, trace(+) vf Sand, with black staining (due to organic matter) at bedding partings, saturated, no odors. Brown CLAY & SILT, saturated, no odors.		1.3		
							0.5		
							0.1		
8	S-3 8' - 11'	2.8-ft.	8.0-ft.				As above, saturated, no odors.	0.6	
0.2									
0.0									
10								Bottom of Boring @ 11.0-feet BGS	
12									
14									
16									
18									
WATER LEVEL DATA			BOTTOM OF CASING	BOTTOM OF BORING	GROUNDWATER ENCOUNTERED	NOTES: 			
DATE	TIME	ELAPSED TIME							
			11.0-Ft.	Less than 4.0-ft. BGS					

GENERAL NOTES

- STRATIFICATION LINES REPRESENT APPROXIMATE BOUNDARY BETWEEN SOIL TYPES, TRANSITIONS MAY BE GRADUAL.
 - WATER LEVEL READINGS HAVE BEEN MADE AT TIMES AND UNDER CONDITIONS STATED, FLUCTUATIONS OF GROUNDWATER
 - Abbreviations
 - and = 35 to 50 %
 - some = 20 to 35%
 - little = 10 to 20%
 - trace = 1 to 10%
 - c = coarse
 - m = medium
 - f = fine
 - vf = very fine
- BGS = Below the Ground Surface
NA = Not Applicable

BORING: RITB-9



300 STATE STREET, ROCHESTER, NY
ENVIRONMENTAL ENGINEERING CONSULTANTS

PROJECT

Remedial Investigation
3865 & 3875 West Henrietta Road
Henrietta, New York

BORING: RITB-4

SHEET 1 OF 1

JOB: 206139.02

CHKD BY:

CONTRACTOR: Trec Environmental Services

DRILLER: Paul Wiley

LABELLA REPRESENTATIVE: C. A. Stiles

BORING LOCATION:

GROUND SURFACE ELEVATION: NA

START DATE: 07-May-07

END DATE: 07-May-07

TIME: 1427 TO

DATUM: NA

TYPE OF DRILL RIG: Truck/Track Mounted Geoprobe Model 54LT

AUGER SIZE AND TYPE: NA

OVERBURDEN SAMPLING METHOD: Direct Push

DRIVE SAMPLER TYPE: 4-foot Macrocore

INSIDE DIAMETER: ~1.8-Inch


OTHER:

DEPTH	SAMPLE			VISUAL CLASSIFICATION	PID FIELD SCREEN (PPM)	REMARKS	
	SAMPLE NO. AND DEPTH	SAMPLE RECOVERY	STRATA CHANGE				
0	S-1 0' to 4'	1.2-ft.	0.0-ft. 0.5-ft.	<u>FILL MATERIAL</u> Concrete Slab - Not sampled. Gray cm ⁽⁺⁾ f SAND, some(-) cmf angular to subrounded Gravel, trace Silt, moist to damp, slight weathered petroleum odor.	17.4		
2							
4	S-2 4' - 8'	2.8-ft.	4.0-ft.		<u>LACUSTRINE</u> Grayish-brown to brown CLAY & SILT, trace f Sand, trace(-) f subrounded Gravel, saturated, no odors.		6.0
6							6.4
8	S-3 8' - 11'	2.4-ft.	8.0-ft.	As above, saturated, no odors.	5.6		
10					0.2		
					0.2		
12				<i>Bottom of Boring @ 11.0-feet BGS</i>			
14							
16							
18							
WATER LEVEL DATA			BOTTOM OF CASING	BOTTOM OF BORING	GROUNDWATER ENCOUNTERED	NOTES: _____ _____	
DATE	TIME	ELAPSED TIME					
				11.0-Ft.	Less than 4.0-ft. BGS		

GENERAL NOTES

- STRATIFICATION LINES REPRESENT APPROXIMATE BOUNDARY BETWEEN SOIL TYPES, TRANSITIONS MAY BE GRADUAL.
 - WATER LEVEL READINGS HAVE BEEN MADE AT TIMES AND UNDER CONDITIONS STATED, FLUCTUATIONS OF GROUNDWATER
 - Abbreviations
 - and = 35 to 50 %
 - some = 20 to 35%
 - little = 10 to 20%
 - trace = 1 to 10%
 - c = coarse
 - m = medium
 - f = fine
 - vf = very fine
- BGS = Below the Ground Surface
NA = Not Applicable

BORING: RITB-4



ATTACHMENT 3

Excavation Work Plan (Appendix B to Site Management Plan)

APPENDIX B – EXCAVATION WORK PLAN

B-1 NOTIFICATION

At least 15 days prior to the start of any activity that is anticipated to encounter remaining contamination (refer to Figure 8), the Site owner or their representative will notify the Department. Currently, this notification will be made to:

Matthew Gillete, P.E.

Division of Environmental Remediation

New York State Department of Environmental Conservation

6274 East Avon-Lima Road

Avon, New York 14414

This notification will include:

- A detailed description of the work to be performed, including the location and areal extent, plans for Site re-grading, intrusive elements or utilities to be installed below the soil cover, estimated volumes of contaminated soil to be excavated and any work that may impact an engineering control;
- A summary of environmental conditions anticipated in the work areas, including the nature and concentration levels of contaminants of concern, potential presence of grossly contaminated media, and plans for any pre-construction sampling;
- A schedule for the work, detailing the start and completion of all intrusive work;
- A summary of the applicable components of this EWP;

NOTE: Simple excavations may only require compliance with a portion of the EWP (e.g., excavation of a small volume of soil from above the water table that is directly loaded for off-site disposal would not require the stockpiling or fluids management provisions of the EWP).

- A statement that the work will be performed in compliance with this EWP and 29 CFR 1910.120;
- A copy of the Contractor's Health and Safety Plan;
- Identification of disposal facilities for potential waste streams; and
- Identification of sources of any anticipated backfill, along with all required chemical testing results.

B-2 SOIL-SCREENING METHODS

Visual, olfactory and instrument-based (i.e., PID) soil screening will be performed by a qualified environmental professional during all remedial and development excavations into known or potentially contaminated material (remaining contamination). Soil screening will be performed regardless of when the invasive work is done and will include all excavation and invasive work performed during development, such as excavations for foundations and utility work, after issuance of the COC.

Soils will be segregated based upon previous environmental data and in-field soil screening results into material that requires off-site disposal, material that requires testing, material that can be returned to the subsurface, and material that can be used as "cover" soil.

Petroleum-impacted soils at the Site exhibit a moderate gasoline-like odor and are typically stained a dark gray color. The petroleum-impacted soils at the Site will also register elevated readings on a properly calibrated PID meter.

Two (2) classes of soil have been defined for the Site. These Classes of material will be managed and handled in a manner dictated soil-screening observations. These two (2) classes of material are described in the following table.

EWP Soil Classifications

Class of Material	Physical Description	Screening Parameter	Management/ Re-use of Material
Class 1 Material	Soil without obvious impacts	No discernable odor; No staining; No elevated PID readings (i.e., < 10 ppm).	Unrestricted use anywhere on the Site; Off-site disposal, if required, only after waste characterization testing; Use on Site to cover Class 2 Materials.
Class 2 Material	Soil with petroleum impacts.	Petroleum odor; Staining; PID readings > 10 ppm.	Sample in accordance with NYSDEC Spill Technology and Remediation Series (STARS) Memo #1. The following actions would be undertaken depending on the sampling results: 1) unrestricted use (on-site) if results meet Part 375-6.8 Restricted Commercial Use Soil Cleanup Objectives criteria (i.e., reclassify as Class 1 Material); 2) use on Site as non-structural backfill and buried under at least 1 foot of Class 1 Materials if results fail Part 375 Restricted Commercial Use Soil Cleanup Objectives; or, 3) Off-Site disposal per 6 NYCRR Part 360 requirements.

B-3 STOCKPILE METHODS

Construction and maintenance of staging/stockpiling areas are described as follows:

- **Class 1 Material** - will be staged for later use as cover material on-site. In the event these materials cannot be reused on-site, these materials will be staged on a minimum two (2) layers of 6-mil polyethylene sheeting and covered with one (1) layer of polyethylene sheeting until sampled and a determination of unrestricted use, restricted on-site reuse, or off-site disposal is made.

- **Class 2 Material** - will be staged on a minimum two (2) layers of 6-mil polyethylene sheeting and covered with one (1) layer of polyethylene sheeting until sampled and a determination of unrestricted use, restricted on-site reuse, or off-site disposal is made. Soil stockpiles will be continuously encircled with a berm and/or silt fence. Hay bales will be used as needed near catch basins, surface waters, and other discharge points.

All soil stockpiles will be continuously encircled with a berm and/or silt fence. Hay bales will be used as needed near catch basins, surface waters and other discharge points.

Stockpiles will be kept covered at all times with appropriately anchored tarps. Stockpiles will be routinely inspected and damaged tarp covers will be promptly replaced.

Stockpiles will be inspected at a minimum once each week and after every storm event. Results of inspections will be recorded in a logbook and maintained at the site and available for inspection by NYSDEC.

B-4 EXCAVATION AND LOAD OUT OF MATERIAL

The owner of the Site and its contractors are solely responsible for safe execution of all invasive and other work performed under this SMP.

The presence of utilities and easements on the Site will be investigated by the contractor. It will be determined whether a risk or impediment to the planned work under this SMP is posed by utilities or easements on the Site.

Loaded vehicles leaving the Site with impacted media will be appropriately lined, tarped, securely covered, manifested, and placarded in accordance with appropriate Federal, State, local, and NYSDOT requirements (and all other applicable transportation requirements).

A truck wash will be operated on-site for any loading of remaining contamination. The contractor will be responsible for ensuring that all outbound trucks will be washed at the truck wash before leaving the Site until the activities performed under this section are complete.

Locations where vehicles enter or exit the Site shall be inspected daily for evidence of off-site soil tracking.

The contractor will be responsible for ensuring that all egress points for truck and equipment transport from the Site are clean of dirt and other materials derived from the Site during intrusive excavation activities. Cleaning of the adjacent streets will be performed, as needed, to maintain a clean condition with respect to Site-derived materials.

Any soils proposed for re-use off-site should be tested for TCL VOCs by USEPA Method 8260 and for STARS-list SVOCs by USEPA Method 8270. These analytical results must meet Part 375 Unrestricted Use Soil Cleanup Objectives.

A qualified environmental professional or person under their supervision will oversee all invasive work in the area of remaining contamination and the excavation and load-out of all excavated material from the area of remaining contamination (refer to Figure 8).

B-5 TRANSPORT OF MATERIAL OFF-SITE

All transport of materials will be performed by licensed haulers in accordance with appropriate local, State, and Federal regulations, including 6 NYCRR Part 364. Haulers will be appropriately licensed, and trucks shall be properly placarded.

Material transported by trucks exiting the Site will be secured with tight-fitting covers. Loose-fitting canvas-type truck covers will be prohibited. If loads contain wet material capable of producing free liquid, truck liners will be used.

All trucks transporting impacted media will be washed prior to leaving the Site. Truck wash waters will be collected and disposed of off-site in an appropriate manner.

Truck transport routes will take into account: (a) limiting transport through residential areas and past sensitive sites; (b) use of city mapped truck routes; (c) prohibiting off-site queuing of trucks entering the facility; (d) limiting total distance to major highways; (e) promoting safety in access to highways; and (f) overall safety in transport.

Trucks will be prohibited from stopping and idling in the neighborhood outside the Site.

Egress points for truck and equipment transport from the Site will be kept clean of dirt and other materials during on-site remediation and development.

Queuing of trucks will be performed on-site in order to minimize off-site disturbance.

Off-site queuing will be prohibited.

B-6 OFF-SITE DISPOSAL OF MATERIAL

All soil/fill/solid waste excavated and removed from the site will be treated as contaminated and regulated material and will be transported and disposed in accordance with all local, State (including 6NYCRR Part 360), and Federal regulations.

If disposal of soil/fill from the Site is proposed for unregulated off-site disposal (i.e., clean soil removed for development purposes), a formal request with an associated plan will be made to the NYSDEC. Unregulated off-site management of materials from this Site will not occur without formal NYSDEC approval.

Off-site disposal locations for excavated soils will be identified in the pre-excavation notification. This will include estimated quantities and an appropriate solid waste landfill disposal facility. Actual disposal quantities and associated documentation will be reported to the NYSDEC in the Periodic Review Report. This documentation will include: waste profiles, test results, facility acceptance letters, manifests, bills of lading, and disposal facility receipts.

Non-hazardous historic fill and contaminated soils taken off-site will be handled, at minimum, as a Municipal Solid Waste per 6NYCRR Part 360-1.2. Material that does not meet Track 1 unrestricted SCOs is prohibited from being taken to a New York State recycling facility (6NYCRR Part 360-16 Registration Facility).

B-7 REUSE OF MATERIALS ON-SITE

‘Reuse on-site’ means reuse on-site of material that originates at the Site and which does not leave the Site during the excavation. Excavated material determined to be Class 1 Material may be re-used on-site with no restrictions.

Excavated material staged as apparent Class 2 Material will be sampled for NYSDEC STARS-list VOCs and STARS-list SVOCs in order to determine appropriate reuse. The following criteria/reuse will be implemented:

- if contaminant concentrations are less than Part 375-6 Restricted Commercial Use Soil Cleanup Objectives then the material can be reused on-site anywhere or NYSDEC could be petitioned for off-site reuse (subject to NYSDEC approval);

- if contaminant concentrations are above the Part 375-6 Restricted Commercial Use Soil Cleanup Objectives then the material can be reused on-site if covered by one foot of Class 1 material or imported clean fill (refer to B-10: Backfill From Off-Site Sources for requirements of backfill);

All waste streams will be staged separately.

A qualified environmental professional will ensure that procedures defined for materials reuse in this SMP are followed and that unacceptable material does not remain on-site. Contaminated on-site material, including historic fill and contaminated soil, that is acceptable for re-use on-site will be placed below the demarcation layer (if present) or impervious surface, and will not be reused within a cover soil layer, within landscaping berms, or as backfill for subsurface utility lines.

Any demolition material proposed for reuse on-site will be sampled for asbestos and the results will be reported to the NYSDEC for acceptance. Concrete crushing or processing on-site will not be performed without prior NYSDEC approval. Organic matter (wood, roots, stumps, etc.) or other solid waste derived from clearing and grubbing of the Site will not be reused on-site.

B-8 FLUIDS MANAGEMENT

All liquids to be removed from the Site, including excavation dewatering and groundwater monitoring well purge and development waters, will be handled, transported and disposed in accordance with applicable local, State, and Federal regulations. Dewatering, purge and development fluids will not be recharged back to the land surface or subsurface of the Site, but will be properly handled and disposed off-site.

If impacted groundwater is discovered in an on-site excavation, contractors will follow their company's Health and Safety Plan(s).

Since elevated levels of contaminants may be encountered in water entering on-site excavations, the following apply:

1. If impacted excavation waters are encountered, an appropriately sized container will be mobilized to the Site and staged at a location close to the excavation. Ideally, this tank should be located in a level area that is protected from vehicle traffic, yet remains accessible to trucks and the sewer system. The contractor will need to supply the appropriate number and size of pumps to effectively de-water the excavation. The pumps will need to be able to generate enough head to pump the water to the temporary containment tank(s), or a water truck could be utilized to transport the water from the excavation to the tank(s). The contractor will be responsible for reducing the turbidity of the water during pumping (i.e., removing/filtering suspended solids/sediments).
2. When the container becomes full, a sample of water from the tank will be collected and submitted to a NYSDOH ELAP-certified laboratory. The water sample will be sampled in accordance with MCPW guidelines for TCL VOCs by USEPA Method 8260. *[Note: Based upon field observations and/or Monroe County Pure Waters (MCPW) requirements, additional testing may be required.]*
3. The laboratory analytical results will be compared to the applicable MCPW discharge criteria. In the event that contaminant concentrations exceed the MCPW discharge criteria, the water will be treated using an appropriate system (e.g., additional filtering, carbon treatment, air stripping, etc.) to remove contaminants and discharged to a second tank, or circulated through the same tank. A second sample of the treated water will then be collected and analyzed, in order to confirm that contaminants were removed to concentrations below the MCPW discharge criteria. This process will be repeated if necessary. Subsequent to receiving results in compliance with MCPW discharge criteria, the test results will be submitted with a sewer use permit application to MCPW, in order to obtain a sewer use permit for discharge of the treated water.

[Note: In the event that treatment of the excavation waters is unable to meet the discharge criteria, the waters will be disposed off-site at an approved facility.]

B-9 COVER SYSTEM RESTORATION

Any soil removals and any other invasive activities will be backfilled with at least 1-ft. of clean materials over any areas of Remaining Contamination (the zone that requires adherence to special conditions for disturbance of remaining contaminated soils defined in this SMP) or covered with an impervious surface (e.g., asphalt pavement, concrete, etc.). If the type of cover system changes from that which existed prior to the excavation (i.e., a soil cover is replaced by asphalt), this will constitute a modification of the cover element of the remedy and the upper surface of the 'Remaining Contamination'. A figure showing the modified surface will be included in the subsequent Periodic Review Report and in any updates to the SMP.

B-10 BACKFILL FROM OFF-SITE SOURCES

All materials proposed for import onto the site will be approved by a qualified environmental professional and will be in compliance with provisions in the SMP, applicable regulations [6NYCRR 375-6.7(d)] and guidance (DER-10) prior to receipt at the Site.

Material from industrial sites, spill sites, or other environmental remediation sites or potentially contaminated sites will not be imported to the Site. All imported soils will meet the backfill and cover soil quality standards established in 6NYCRR 375-6.7(d).

Soils that meet 'exempt' fill requirements under 6 NYCRR Part 360, but do not meet backfill or cover soil objectives for this site, will not be imported onto the site without prior approval by NYSDEC. Solid waste will not be imported onto the site. Trucks entering the site with imported soils will be securely covered with tight fitting covers. Imported soils will be stockpiled separately from excavated materials and covered to prevent dust releases.

In the event that imported backfill material is needed at the Site, the following procedures will be followed for the use of backfill from other sources at the Site:

- All imported backfill will be from NYSDEC-permitted source, and written documentation regarding the nature of the material will be obtained from the source, OR
- Representative samples of the imported backfill will be collected at the frequency specified in the NYSDEC Spill Technology and Remediation Series (STARS) Memo #1 guidance document. The representative samples of imported backfill will be submitted

for laboratory analysis of the following: VOCs, SVOCs, USEPA RCRA metals; PCBs; and pesticides. Laboratory analytical results associated with the samples of imported backfill will be compared to NYSDEC Part 375 Soil Cleanup Objectives (SCOs) for the Protection of Groundwater Sample. Samples that meet these SCOs will be deemed suitable for use as backfill at the Site.

B-11 STORMWATER POLLUTION PREVENTION

With regard to larger excavations that may be proposed at the Site, procedures for stormwater pollution prevention shall be specified in a project-specific Stormwater Pollution Prevention Plan that conforms to the requirements of NYSDEC Division of Water guidelines and NYS regulations. If not covered in the project-specific Stormwater Pollution Prevention Plan, the following will also apply:

- Barriers and hay bale checks will be installed and inspected once a week and after every storm event. Results of inspections will be recorded in a logbook and maintained at the Site and available for inspection by NYSDEC. All necessary repairs shall be made immediately.
- Accumulated sediments will be removed as required to keep the barrier and hay bale check functional.
- All undercutting or erosion of the silt fence toe anchor shall be repaired immediately with appropriate backfill materials.
- Manufacturer's recommendations will be followed for replacing silt fencing damaged due to weathering.

- Erosion and sediment control measures identified in the SMP shall be observed to ensure that they are operating correctly. Where discharge locations or points are accessible, they shall be inspected to ascertain whether erosion control measures are effective in preventing significant impacts to receiving waters.
- Silt fencing or hay bales will be installed around the entire perimeter of the excavation/construction area.

B-12 CONTINGENCY PLAN

If USTs or other previously unidentified contaminant sources (e.g., stained soil, drums, etc.) are found during post-remedial subsurface excavations or development related construction, then excavation activities will be suspended until sufficient equipment and personnel are mobilized to the Site to address the condition.

Sampling will be performed on product, sediment and surrounding soils, etc. as necessary to determine the nature of the material and proper disposal method. Chemical analysis will be performed for petroleum-related compounds (i.e., STARS-list VOCs and SVOCs), unless field observations suggest the need for more comprehensive analyses or at the discretion of the NYSDEC.

Identification of unknown or unexpected contaminated media identified by screening during invasive Site work will be promptly communicated by phone to NYSDEC's Project Manager. Reportable quantities of petroleum product will also be reported to the NYSDEC Spills Hotline. These findings will also be included in the periodic reports prepared pursuant to Section 5 of the SMP.

B-13 COMMUNITY AIR MONITORING PLAN

A copy of the Community Air Monitoring Plan (CAMP) component of the EWP, obtained from Appendix 1A of NYSDEC Draft DER-10 Technical Guidance for Site Investigation and Remediation, dated December 2002, is included as Appendix C of this SMP. The provisions of this CAMP will be followed during all future ground-intrusive activities performed at the Site.

B-14 ODOR CONTROL PLAN

This Odor Control Plan component of the EWP is intended to control emissions of nuisance odors off-site and into on-site tenant spaces. If nuisance odors are identified at the Site boundary, or if odor complaints are received, work will be halted and the source of odors will be identified and corrected. Work will not resume until all nuisance odors have been abated. NYSDEC and NYSDOH will be notified of all odor events and of any other complaints about the project. Implementation of all odor controls, including the halt of work, is the responsibility of the property owner's Remediation Engineer, and any measures that are implemented will be discussed in the Periodic Review Report.

All necessary means will be employed to prevent on- and off-site nuisances. At a minimum, these measures will include: (a) limiting the area of open excavations and size of soil stockpiles; (b) shrouding open excavations with tarps and other covers; and (c) using foams or other additives to cover or "seal" exposed odorous soils. If odors develop and cannot be otherwise controlled, additional means to eliminate odor nuisances will include: (d) direct load-out of soils to trucks for off-site disposal; (e) use of chemical odorants in spray or misting systems; and, (f) use of staff to monitor odors in surrounding neighborhoods.

If nuisance odors develop during intrusive work that cannot be corrected, or where the control of nuisance odors cannot otherwise be achieved due to on-site conditions or close proximity to sensitive receptors, odor control will be achieved by sheltering the excavation and handling areas in a temporary containment structure equipped with appropriate air venting/filtering systems.

B-15 DUST CONTROL PLAN

A dust suppression plan that addresses dust management during invasive on-site work will include, at a minimum, the items listed below:

- Dust suppression will be achieved through the use of a dedicated on-site water truck for road wetting. The truck will be equipped with a water cannon capable of spraying water directly onto off-road areas including excavations and stockpiles.
- Gravel will be used on roadways to provide a clean and dust-free road surface.

- On-site roads will be limited in total area to minimize the area required for water truck sprinkling.

B-16 OTHER NUISANCES

A plan for rodent control, if required by the City of Rochester, will be developed and utilized by the Contractor prior to and during all on-site demolition or remedial work.

If required by the City of Rochester, a plan will be developed and utilized by the Contractor for all demolition or remedial work to ensure compliance with all applicable City of Rochester noise control ordinances.

Y:\RJ DORSCHER CORP\209395\REPORTS\SMP\REVISED SMP (BASED ON DEC 11-13-09 COMMENT LETTER).DOC