

Periodic Review Report

*Tecumseh Phase III Business Park
Sites III-5 & III-6*

2303 Hamburg Turnpike

April 2017

B0397-017-001

Prepared For:

Steel Sun, LLC

Prepared By:



PERIODIC REVIEW REPORT

**TECUMSEH PHASE III BUSINESS PARK
SITES III-5 & III-6
(BCP SITE NO.s C915199E & C915199F)**

**2303 HAMBURG TURNPIKE
LACKAWANNA, NEW YORK**

April 2017

B0397-017-001

Prepared for:

Steel Sun, LLC

Prepared By:



Benchmark Environmental Engineering & Science, PLLC
2558 Hamburg Turnpike, Suite 300
Buffalo, NY 14218
(716)856-0599

PERIODIC REVIEW REPORT
Sites III-5 & III-6: C915199E & C915199F
Table of Contents

1.0	INTRODUCTION.....	1
1.1	Site Background.....	1
1.2	Remedial History	2
1.2.1	<i>Phase III Business Park.....</i>	<i>2</i>
1.2.2	<i>Sites III-5 & III-6.....</i>	<i>3</i>
1.2.3	<i>IRM Activities: August – December 2013.....</i>	<i>3</i>
1.2.4	<i>IRM Activities: September 2014.....</i>	<i>4</i>
1.3	Compliance	5
1.4	Recommendations.....	5
2.0	SITE OVERVIEW.....	6
2.1	Final Remedial Measures.....	6
3.0	REMEDY PERFORMANCE	7
4.0	SITE MANAGEMENT PLAN	8
4.1	Engineering and Institutional Control (IC/EC) Plan.....	8
4.1.1	<i>Institutional Controls</i>	<i>8</i>
4.1.2	<i>Engineering Controls.....</i>	<i>8</i>
4.2	Excavation Work Plan	9
4.3	Annual Inspection and Certification Program	10
4.4	Operation, Monitoring and Maintenance Plan.....	11
5.0	GROUNDWATER MONITORING	12
6.0	CONCLUSIONS AND RECOMMENDATIONS	13
7.0	DECLARATION/LIMITATION	14
8.0	REFERENCES	15

PERIODIC REVIEW REPORT
Sites III-5 & III-6: C915199E & C915199F
Table of Contents

FIGURES

Figure 1	Site Location and Vicinity Map
Figure 2	Business Park III Site Plan
Figure 3	III-5 & III-6 Remedial Actions
Figure 4	III-5 & III-6 Site Plan (Post-Remediation)

TABLES

Table 1	Summary of Groundwater Analytical Results
---------	---

APPENDICIES

Appendix A	CAMP Data
Appendix B	Fill Disposal Documentation
Appendix C	Stone Import Documentation
Appendix D	Institutional & Engineering Controls Certification Forms
Appendix D1	Site III-5
Appendix D2	Site III-6
Appendix E	Site Photolog
Appendix F	Groundwater Monitoring Data

1.0 INTRODUCTION

Benchmark Environmental Engineering and Science, PLLC (Benchmark) has prepared this Periodic Review Report (PRR) to summarize the post-remedial status of New York State Department of Environmental Conservation (NYSDEC) Brownfield Cleanup Program (BCP) Site No.s C915199E and C915199F, located at 2303 Hamburg Turnpike in the City of Lackawanna, Erie County, New York.

This PRR has been prepared for the Subject BCP Sites in accordance with NYSDEC DER-10 *Technical Guidance for Site Investigation and Remediation* (Ref 1). Institutional and Engineering Control (IC/EC) Certification Forms have been completed for the Sites and are included in Appendix A.

This PRR and the associated certifications have been completed on behalf of the BCP Site operator, Steel Sun, LLC, to document post-remedial activities covered by the Site Management Plan (Ref. 2). The post remedial period covered by this PRR is: January 15, 2016 – March 15, 2017.

1.1 Site Background

In March of 2007 Tecumseh Redevelopment Inc. (Tecumseh) entered into a Brownfield Cleanup Agreement (BCA) with the New York State Department of Environmental Conservation (NYSDEC) to investigate and remediate an approximate 150-acre property located in Lackawanna, New York. The property, deemed the “Phase III Business Park Site” is located in the County of Erie, New York and encompasses tax parcel numbers 141.15-1-1, 141.15-1-2, and part of tax parcel number 141.11-1-50 per Erie County Tax Map records. The Phase III Business Park Site is bounded by Gateway Metroport Ship Canal and property owned by Gateway Trade Center to the north; the South Buffalo Railroad Company to the south; Phase II Business Park Site and the South Return Water Trench (SRWT) to the east; and other Tecumseh property to the west (see Figures 1 and 2). The 150-acre Phase III Business Park was originally deemed Brownfield Cleanup Program (BCP) Site No. C915199, but was subsequently subdivided into ten smaller parcels to facilitate remediation and redevelopment (see Figure 2). On August 20, 2012, the original BCA for Site C915199 was amended to cover the smaller Site III-1, with separate BCAs

issued and executed for the remaining nine BCP Sites (i.e., Sites III-2 through III-10, having BCP Site Nos. C915199b through C915199j).

In July 2014 Steel Sun, LLC arranged to lease from Tecumseh Sub-parcels III-5 (Site No. C915199e) and III-6 (Site No. C915199f), encompassing 22.6 acres of property, for construction and operation of a commercial-scale solar electricity generation system. Sub-parcels III-5 and III-6 were subsequently remediated to Track 4 restricted (commercial) use with site specific soil cleanup objectives (SCOs) consistent with the approved Remedial Action Work Plan. The final remedial measures implemented by Steel Sun included placement of acceptable cover material in areas not otherwise covered by asphalt roadway, pavement, etc.

1.2 Remedial History

1.2.1 Phase III Business Park

The approximate 150-acre Phase III Business Park was formerly part of the Bethlehem Steel Corporation (BSC) Lackawanna Works and housed several facilities used in BSC's steel manufacturing processes. Specific processes and steel making facilities performed on or proximate to the subject BCP Sites included:

- Open Hearth Furnaces
- Basic Oxygen Furnace
- Mold Warming and Preparation
- Electrical Substations
- Wastewater Treatment

Remedial Investigation (RI) activities on the Phase III Business Park were initiated in August 2008, with additional activities undertaken in late 2009 through early 2010. Some supplemental investigation work was also completed in April 2012.

The RI identified several Constituents of Concern (COCs) that were generally present across widespread areas of the Phase III Business Park site, primarily in site soils and to a lesser extent in groundwater. These included polyaromatic hydrocarbons (PAHs), arsenic,

lead, and mercury. Isolated areas of petroleum impact were also encountered. The Remedial Investigation/Alternatives Analysis (RI/AA) Report (Ref. 3) recommended remediation of “hotspot” slag/fill (characterized by more pronounced levels of COCs) and isolated groundwater/saturated soil impacts (affecting only select sites in the Phase III Business Park), with cover placement recommended as the final remedial measure under a Track 4 Cleanup approach. Additional requirements included development and adherence to a Site Management Plan (SMP) and filing of an Environmental Easement to restrict use of the Phase III Business Park property to commercial and industrial applications and to place other limitations on post-redevelopment activities.

1.2.2 Sites III-5 & III-6

In accordance with the May 2008 RI/AA Work Plan, 86 test pits were completed across the Phase III Business Park including approximately 27 test pits on Sites III-5 and III-6. The investigation identified evidence of potentially significant soil/fill impacts associated with Test Pit BP3-TP-42 within Sub-parcel III-6. At this location, which was subsequently deemed “Hotspot A,” a PID reading of 400 ppm was measured and suspected red paint was observed at 0.5- 1.5 feet below ground surface (fbgs). A soil sample was collected and submitted for laboratory analysis. An elevated estimated concentration of lead (4,550 mg/kg) was detected within the sample, consistent with the observed red paint. The test pit was expanded with similar observations recorded across an isolated area having dimensions of approximately 10 feet x 10 feet x 2.5 feet deep. These results are summarized in the RI/AA Report.

1.2.3 IRM Activities: August – December 2013

Based on the findings of the RI/AA Report, an interim remedial measure (IRM) in the form of soil/fill excavation and offsite disposal was undertaken to address Hotspot A in 2013. TurnKey Environmental Restoration, LLC (TurnKey) implemented IRM work on Site III-6 on behalf of Tecumseh Redevelopment, Inc. The work was performed on a design-build basis in accordance with an NYSDEC-approved IRM Work Plan (Ref. 4). Hotspot excavation activities were performed in August 2013, with offsite disposal of the impacted

slag/fill was performed in December 2013. The IRM activities, fully described in the January 2014 Construction Completion Report for the Phase III Business Park (Ref. 5), included:

- Excavating approximately 9.3 cubic yards of lead-impacted slag/fill surrounding Hotspot A (i.e., Remedial Investigation Test pit BPA3-TP-42 on Sub-Parcel III-6 -see Figure 3), with off-site disposal of these materials at the Chautauqua County Landfill (CCLF) in Ellery, NY.
- Collecting post-excavation documentation samples from the lead-impacted hotspot excavation area. One representative sidewall sample was collected from each of the four sides of each excavation area and one bottom sample was collected from the base of each excavation area. The samples were submitted to a New York State Department of Health (NYSDOH)-ELAP certified laboratory for analysis of lead in accordance with USEPA SW-846 Method 6010. The samples were compared to the site-specific action level (SSAL) of 3,900 parts per million. All detections fell below the SSAL and no further excavation work was completed at Hotspot A. Based on the shallow nature of the excavation no backfill work was performed.

1.2.4 IRM Activities: September 2014

During subgrade work on other Phase III Business Park property in 2013 an abandoned 30" diameter pipeline was encountered. The line, which contained a heel of materials exhibiting visual and olfactory evidence of impact, was identified through review of historical drawings to be part of a network of aboveground and subsurface piping used to convey coke oven gas for heating applications in the former steel manufacturing and support buildings. A 14" diameter branch off the 30" gas line, which extended west into Sub-parcel III-5, was identified on the drawings as well (see Figure 3).

Due to the presence of the impacted heel within the piping (believed to be residual scale and sediment resulting from gas condensate), the NYSDEC determined that the line represented a potential source area requiring remediation. Tecumseh subsequently prepared an Interim Remedial Work Plan (Ref 6) to address the piping on the Brownfield areas of its Lackawanna property. The 14" branch extending into Site III-5 was remediated by Turnkey on behalf of Tecumseh on September 4-5, 2014. The work involved exposing the pipe along its length followed by excavating and removing the cast iron piping in sections. Overlying clean overburden material was staged adjacent to the excavation. Minor quantities

of scale/sediment within the piping were removed and stockpiled on poly sheeting. An estimated 3.76 tons of non-hazardous slag/fill and piping residuals were disposed at the CCLF. The cleaned piping was staged on poly sheeting in Business Park III for offsite transport and recycling.

The excavation for the 14-inch diameter piping was backfilled with the overlying clean overburden material and supplemented with imported BUD-approved (BUD #555-9-15) slag from a commercial stockpile operated by Iron City Recovery.

1.3 Compliance

At the time of the Site inspection, the Site was fully compliant with the NYSDEC-approved SMP (Ref 2).

1.4 Recommendations

Based on observations recorded during the annual inspection and IC/EC certification, no modifications are recommended at this time.

2.0 SITE OVERVIEW

Final remedial activities undertaken on Sites III-5 and III-6 are described below. All of the remediated properties within the Phase III Business Park are subject to a comprehensive, site-wide SMP which identifies requirements for monitoring and maintenance of engineering and institutional controls and procedures for post-remedial excavation and related activities. Specific requirements affecting individual Sites within Phase III Business Park are included as appendices to the comprehensive plan. The SMP is updated as additional Sites within the Phase III Business Park are remediated.

2.1 Final Remedial Measures

Final (post-IRM) remedial activities on Sites III-5 and III-6 were performed by Steel Sun, LLC with oversight provided by the New York State Department of Environmental Conservation (NYSDEC). Benchmark performed the remedial work on a design-build basis with assistance from Zoladz Construction Company, Inc., the designated remedial subcontractor, in accordance with an NYSDEC-approved Remedial Action Work Plan (Ref. 7). The final remedial measures incorporated the following activities:

- Railroad ties (approx. six loads) were removed from the Site by the subcontractor and transported to Iron City Recovery, LLC for disposal.
- All areas of the Site not covered by existing competent asphalt were covered with approximately 73,249 tons imported beneficial use determination (BUD)-approved slag over a demarcation layer. Imported slag was placed to a minimum compacted thickness of 1 foot (see Figure 4).
- An addendum to the previously-approved Business Park III SMP was prepared to summarize the remedial measures on Sites III-5 and III-6 and describe site-specific monitoring and maintenance requirements for those parcels. (An Environmental Easement restricting end use of the Site and enforcing adherence to the SMP was filed in November 2013).

The remedial program was successful in achieving the remedial objectives for the Site. The Final Engineering Report (FER) was approved in December 2014 (Ref 8). A

Certificate of Completion (COC) was issued for Site III-5 and III-6 by the NYSDEC in December 2014.

3.0 REMEDY PERFORMANCE

A post-remedial site inspection involving a walk-over of the Sites covered by this PRR was performed to visually observe and document the use of the Site for commercial/industrial use, confirm absence of site groundwater use, inspect the cover system integrity, and verify conformance with other requirements under the SMP. The site inspection completed during this reporting period indicates that the controls are in-place and functioning as intended in accordance with the SMP.

The completed IC/EC Certification forms and site photographs are included in Appendices A and B, respectively.

4.0 SITE MANAGEMENT PLAN

A site-wide SMP was prepared for the Phase III Business Park and approved by the Department in December 2013. Parcel-specific SMP requirements for Sites III-5 and III-6 were added by Addenda in November 2014 and are presented in SMP appendices H5 and H6. Key components of the SMP are described below.

4.1 Engineering and Institutional Control (IC/EC) Plan

Since remaining contaminated soil/fill and groundwater exists beneath the Phase III Business Park, Engineering Controls and Institutional Controls (EC/ICs) are required to protect human health and the environment. The Engineering and Institutional Control Plan describes the procedures for the implementation and management of all EC/ICs on the Sites within the Phase III Business Park.

4.1.1 *Institutional Controls*

The following institutional controls apply to all Sites within the Phase III Business Park:

- The use and development of the property is restricted to commercial and industrial uses as defined by Part 375-1.8(g), although land use is subject to local zoning laws;
- Groundwater cannot be used as a source of potable or process water, without necessary water quality treatment as determined by the New York State Department of Health (NYSDOH) or County DOH;
- All Sites must comply with the Department approved Site Management Plan; and
- The remedial party or site owner must complete and submit to the Department a periodic certification of institutional and engineering controls in accordance with Part 375-1.8(h)(3.)

4.1.2 *Engineering Controls*

Engineering controls covering Sites within the Phase III Business Park include:

- Cover System – The cover system, including building foundations, concrete sidewalks, concrete or asphalt driveways, parking areas, and landscaped vegetated areas must be maintained in compliance with the SMP.
- Vapor Barrier (specific to Sites with buildings) - A poly vapor barrier must be installed and remain in-place beneath building concrete floor slab.

At the time of the site inspection, the Sites covered by this PRR were fully compliant with all engineering and institutional control requirements.

4.2 Excavation Work Plan

An Excavation Work Plan (EWP) was included in the approved-SMP for the Phase III Business Park. The Excavation Work Plan provides guidelines for the management of soil and fill material during any future intrusive activities. Any intrusive work that will penetrate the cover or cap, or encounter or disturb the remaining contamination, including any modifications or repairs to the existing cover system, must be performed in compliance with the EWP and must also be conducted in accordance with a site-specific Health and Safety Plan (HASP) and Community Air Monitoring Plan (CAMP) meeting the minimum requirements of the sample HASP and CAMP included with the SMP.

For the Subject Sites III-5 and III-6 certain intrusive activities requiring disturbance of the cover system, management of on-Site soil/fill material, and placement of backfill materials occurred in 2016 coincidental with build-out of the site as a commercial solar power generation facility. These included:

- Excavation of approximately 538.39 tons of fill materials to allow installation of two 6-inch underground power conduits and one 5 ft. x 5ft. concrete vault leading to metering poles in the southern areas of the site.
- Surface placement of four (4) floating concrete pads approximately 6 ft. x 6 ft. and 6 ft. x 12 ft. housing inverter and related equipment fed by the solar panels.

Remaining activities involved de-minimis disturbance of cover materials for security fence installation (poles were driven through cover) and placement of trays and racking for surface power lines and panels, respectively.

Benchmark was onsite to document the intrusive work. Community air monitoring was performed during excavation of fill materials displaced by the conduits. The work was performed in accordance with the Community Air Monitoring Plan (CAMP) included in the SMP. Appendix A contains the CAMP data; no exceedance of CAMP thresholds occurred during the work.

Excavated soils were sent to the Chautauqua County Ellery Landfill under profile 041416S1, which was previously approved for slag spoils originating on the Tecumseh Site. Scale receipts and copies of manifests are included in Appendix B. The excavations were fitted with steel conduits and the remaining space was backfilled with clean stone material from the Buffalo Crushed Stone Division of New Enterprise Stone and Lime Company, a commercial aggregate provider. The clean stone materials, totaling 280.26 tons, specifically originated from the company's Wehrle Drive facility. Stone backfill documentation is provided in Appendix C.

4.3 Annual Inspection and Certification Program

The Annual Inspection and Certification Program outlines requirements for certifying and attesting that the institutional controls and engineering controls employed on the Sites are unchanged from the original design and/or previous certification. The Annual Certification includes a Site Inspection and completion of the NYSDEC's IC/EC Certification Form. The Site inspection is intended to verify that the IC/ECs:

- Are in place and effective.
- Are performing as designed.
- That nothing has occurred that would impair the ability of the controls to protect the public health and environment.

- That nothing has occurred that would constitute a violation or failure to comply with any operation and maintenance plan for such controls.
- Access is available to the Site to evaluate continued maintenance of such controls.

Inspection of Sites III-5 and III-6 was conducted by Richard Dubisz of Benchmark on March 23, 2017. Mr. Dubisz meets the requirements of a Qualified Environmental Professional (QEP) per 6NYCRR Part 375.12. At the time of the inspection, the Sites were vacant. No observable indication of intrusive activities was noted during the Site inspection.

The completed Site Management Periodic Review Report Notice – Institutional and Engineering Controls Certification Forms are included in Appendix D. A PRR photo log is included in Appendix E.

4.4 Operation, Monitoring and Maintenance Plan

The remedy for Sites III-5 and III-6 does not rely on any mechanical systems such as sub-slab depressurization or soil vapor extraction, to protect public health and the environment. Therefore, an Operation and Maintenance Plan is not required.

5.0 GROUNDWATER MONITORING

Appendices H5/H6 of the SMP require groundwater monitoring at wells MWN-58A, MWN-59A, and MWN-60A on an annual basis for a period of approximately 2 years, after which the need for continued monitoring or a revision to the monitoring program will be discussed with the NYSDEC. During the first two years the SMP requires that groundwater sampled from all three wells be analyzed for VOCs, SVOCs (base neutrals only), site-specific metals (i.e., arsenic, chromium, lead, and mercury), and field parameters (i.e., pH, temperature, specific conductance, turbidity, dissolved oxygen, and oxidation-reduction potential).

TurnKey Environmental Restoration performed the first annual monitoring event at MWN-58A, MWN-59A, and MWN-60A on February 2, 2016 as part of a comprehensive groundwater monitoring event requested by the NYSDEC for all of the Tecumseh Business Parks. A summary of the analytical results and laboratory data from this event were provided to the NYSDEC in the February 2016 PRR.

A second semi-annual monitoring event was conducted by Steel Sun, LLC on March 13, 2017. Laboratory results are included in Appendix F along with field data sheets. Table 1 summarizes the monitoring results, as well as groundwater monitoring data from the February 2016 event and prior events completed during the Phase II Business Park Remedial Investigation (RI). NYSDEC Class GA groundwater quality standards (GWQS) per NYSDEC Division of Water Technical and Operational Guidance Series (TOGS) 1.1.1 are presented for comparison. As indicated, data are generally consistent with those collected during the RI and February 2016 event.

6.0 CONCLUSIONS AND RECOMMENDATIONS

Conclusions and recommendations are as follows:

- At the time of the Site inspection, Sites III-5 and III-6 were in compliance with the SMP.
- Groundwater data have been consistent throughout the 2 year monitoring period and prior RI, with no significant exceedances of the standards. Accordingly, Steel Sun, LLC requests termination of annual groundwater monitoring.

7.0 DECLARATION/LIMITATION


This report has been prepared for the exclusive use of Steel Sun, LLC. The contents of this report are limited to information available at the time of the site inspection. The findings herein may be relied upon only at the discretion of Steel Sun, LLC. Use of or reliance upon this report or its findings by any other person or entity is prohibited without written permission of Benchmark Environmental Engineering and Science, PLLC.

8.0 REFERENCES

1. 2013. New York State Department of Environmental Conservation. *DER-10/Technical Guidance for Site Investigation and Remediation*. May 3.
2. 2013. TurnKey Environmental Restoration, LLC. *Site Management Plan for Tecumseh Phase III Business Park*. Revised July 2015.
3. 2012. TurnKey Environmental Restoration, LLC. *Remedial Investigation/Alternatives Analysis Report for Phase III Business Park, Lackawanna, New York*. Revised July.
4. 2013. TurnKey Environmental Restoration, LLC and Benchmark Environmental Engineering & Science, PLLC. *Interim Remedial Measures (IRM) Work Plan, Phase III Business Park, Sub-Parcels III-4, III-6 and III-10, Lackawanna, New York, BCP Site Nos. 915199D, C915199F, and C915199J*. July.
5. 2014. TurnKey Environmental Restoration, LLC and Benchmark Environmental Engineering & Science, PLLC. *Construction Completion Report, Metal-Impacted Hotspots, Business Park Sub-parcels III-4, III-6 & III-10, Lackawanna, New York, BCP Sites C915199D, C915199F & C915199J*. January
6. 2014. TurnKey Environmental Restoration, LLC and Benchmark Environmental Engineering & Science, PLLC. *Interim Remedial Measures (IRM) Work Plan for BCP Business Parks II & III: Decommissioning of Former Coke Oven Gas Lines, Tecumseh Redevelopment Site, Lackawanna, New York*. April.
7. 2014. Benchmark Environmental Engineering & Science, PLLC. *Remedial Action Work Plan, Steel Sun Site, Lackawanna, New York, BCP Site Nos. C915199E & C915199F*. July
8. 2014. Benchmark Environmental Engineering & Science, PLLC. *Final Engineering Report, Tecumseh Phase III-5 & 6 Business Park Sites, NYSDEC Site Nos. C915199E/C915199F, Lackawanna, New York*. November.

FIGURES

FIGURE 1



2558 HAMBURG TURNPIKE
 SUITE 300
 BUFFALO, NY 14218
 (716) 856-0599

PROJECT NO.: 0302-016-001

DATE: JANUARY 2016

DRAFTED BY: RPL

REGIONAL MAP

PERIODIC REVIEW REPORT

TECUMSEH PHASE III BUSINESS PARK

SITES III-5 AND III-6

LACKAWANNA, NY


PREPARED FOR

STEEL SUN, LLC

DISCLAIMER:

PROPERTY OF BENCHMARK EES, PLLC. IMPORTANT: THIS DRAWING PRINT IS LOANED FOR MUTUAL ASSISTANCE AND AS SUCH IS SUBJECT TO RECALL AT ANY TIME. INFORMATION CONTAINED HEREON IS NOT TO BE DISCLOSED OR REPRODUCED IN ANY FORM FOR THE BENEFIT OF PARTIES OTHER THAN NECESSARY SUBCONTRACTORS & SUPPLIERS WITHOUT THE WRITTEN CONSENT OF BENCHMARK EES, PLLC.

DATE: JANUARY 2016
DRAFTED BY: RPL



VICINITY MAP


PERIODIC REVIEW REPORT
STEEL SUN PHOTOVOLTAIC SOLAR SYSTEM
TECUMSEH REDEVELOPMENT AREA
LACKAWANNA, NY
PREPARED FOR
STEEL SUN, LLC

BENCHMARK
ENVIRONMENTAL
ENGINEERING &
SCIENCE, PLLC

2558 HAMBURG TURNPIKE
SUITE 300
BUFFALO, NY 14218
(716) 856-0599

JOB NO.: B0302-016-001

FIGURE 2




REMEDIAL ACTIONS ON PARCELS III-5 & III-6

FINAL ENGINEERING REPORT
TECUMSEH PARCEL III-5&6 BUSINESS PARK SITE
BCP SITE NOS. C915199E & C915199F
LACKAWANNA, NY
PREPARED FOR
STEEL SUN, LLC

FIGURE 3

DATE: SEPTEMBER 2014
DRAFTED BY: JCT



SITE-WIDE COVER SYSTEM

TECUMSEH PHASE III BUSINESS PARK
SITE III-5 AND III-6
LACKAWANNA, NY
PREPARED FOR
STEEL SUN, LLC

BENCHMARK
ENVIRONMENTAL
ENGINEERING &
SCIENCE, PLLC

2558 HAMBURG TURNPIKE
SUITE 300
BUFFALO, NY 14218
(716) 856-0599

JOB NO.: B0302-016-001

FIGURE 4

TABLE

TABLE 1
SUMMARY OF GROUNDWATER ANALYTICAL RESULTS

PERIODIC REVIEW REPORT

Tecumseh Phase III Business Park: Sites III-5 & III-6
Lackawanna, New York

Parameter ^{1,2,3}	Sample Location																		GWQS ⁴
	MWN-58A 1/14/09		MWN-58A 2/3/16		MWN-58A 3/13/17		MWN-59A 1/14/09		MWN-59A 2/3/16		MWN-59A 3/13/17		MWN-60A 1/14/09		MWN-60A 2/3/16		MWN-60A 3/13/17		
Field Measurements ⁵ :																			
Sample No.	Initial	Final	Initial	Final	Initial	Final	Initial	Final	Initial	Final	Initial	Final	Initial	Final	Initial	Final	Initial	Final	--
pH (units)	7.71	7.71	7.16	7.17	7.18	7.18	7.55	7.60	7.47	7.51	7.32	7.36	8.28	8.29	8.19	8.18	7.62	7.87	6.5 - 8.5
Temperature (°C)	10.3	9.3	12.1	12.1	9.0	8.5	9.1	8.8	12.4	12.1	9.2	8.7	9.6	9.6	12.20	12.30	7.1	6.4	NA
Sp. Conductance (mS)	412.4	411.5	559.8	558.9	523.3	526.1	704.3	700.8	823.7	824.2	729.5	722.4	614.8	619.0	663.2	660.3	672.4	666.7	NA
Turbidity (NTU)	31.30	22.60	26	7.97	29.6	28.3	24.40	11.10	13.4	24.8	6.38	5.31	5.57	4.54	7.47	4.02	1.33	1.29	NA
DO (ppm)	1.61	1.91	1.96	1.87	1.25	X	1.78	1.96	1.37	1.28	2.55	2.65	1.33	1.63	1.50	1.38	2.15	3.54	NA
Eh (mV)	-128	-120	-53	-65	31	42	-142	-142	-118	-123	74	75	-197	-189	176	152	7	43	NA
Metals (mg/L): ⁶																			
Arsenic - Total	0.0164		0.035		0.1405		ND		ND		0.00343		ND		0.0064 J		0.00225		0.025
Barium - Total	--		0.043		--		--		0.056		--		--		0.03		--		1
Chromium - Total	ND		ND		0.00067 J		ND		ND		0.0009 J		ND		ND		0.00029 J		0.05
Lead - Total	ND		0.0031 J		0.00077 J		ND		0.004 J		ND		ND		ND		ND		0.025
Manganese - Total	--		0.15		--		--		0.29		--		--		0.38		--		0.3
Cyanide - Total	--		ND		--		--		0.011		--		--		0.01		--		0.2
Volatile Organic Compounds (ug/L):																			
Acetone	ND		ND		ND		ND		ND		ND		ND		ND		0.02		50
Benzene	ND		ND		ND		ND		ND		ND		0.034 J		ND		ND		1
2-Butanone	ND		ND		ND		ND		ND		ND		ND		ND		0.013		50
Semi-Volatile Organic Compounds (ug/L):																			
4-Chlorophenyl phenyl ether	ND		ND		ND		ND		0.39 J*		ND		ND		ND		ND		--
Benzaldehyde	ND		0.55 JHB		--		ND		0.54 JHB		--		ND		0.52 JHB		--		--
Butyl benzyl phthalate	ND		0.52 JHB		ND		ND		0.49 JHB		ND		ND		0.46 JHB		ND		50
Di-n-butyl phthalate	ND		ND		ND		0.3 BJ		ND		ND		ND		ND		ND		50
Di-n-octyl phthalate	ND		0.58 J		ND		ND		0.57 J		ND		ND		0.57 J		ND		50
Fluoranthene	ND		ND		ND		ND		ND		ND		0.23 J		ND		ND		50*
Hexachlorocyclopentadiene	ND		ND		ND		ND		0.75 JB		ND		ND		ND		ND		5***
Phenanthrene	ND		ND		ND		ND		ND		ND		0.74 J		ND		ND		50*
Pyrene	ND		ND		ND		ND		ND		ND		0.21 J		ND		ND		50*

- Notes:**
- Only those compounds detected above the method detection limit at a minimum of one sample location are reported in this table.
 - Shaded and bolded values represent exceedances of the GWQS/GV.
 - For summary purposes only detected parameters are shown on this table.
 - NYSDEC Class "GA" Groundwater Quality Standards (GWQS) as per 6 NYCRR Part 703.
 - Field measurements were collected immediately before and after groundwater sample collection.
 - COPC metals Per the 2016 periodic review report include arsenic, total chromium, lead, and mercury.
 - "J" = Estimated Value
 - "H" = Sample was prepped or analyzed beyond specified holding time.
 - "B" = Analyte was present in the blank.
 - "ND" indicates parameter was not detected above laboratory reporting limit and is reported herein as not detected (ND).
 - "NA" = not applicable.
 - "*" = The Guidance Value was used where a Standard has not been established.
 - "-" = Not analyzed for.

APPENDIX A

CAMP DATA



COMMUNITY AIR MONITORING

PERIODIC REVIEW REPORT

Tecumseh Phase III Business Park: Sites III-5 & III-6
Lackawanna, New York

Timestamp (GMT-4)	Batt. Voltage (V)	Current (mA)	Low (ppm)	Peak (ppm)	STEL (ppm)	TWA (ppm)	VOC (ppm)	VOC (Avg15) (ppm)	Mass Conc. Total (mg/m³)	Memory (%)	Sensor Batt. (%)	TWA (mg/m³)	Mass Conc. Total (Avg15) (mg/m³)	Latitude	Longitude
8/25/2016 9:01	12.6	77.78	0	0	0	0	0	0	0.031	100	9	0.004	0.0308	42.8114	-78.8498
8/25/2016 9:00	12.58	94.44	0	0	0	0	0	0	0.031	100	10	0.004	0.0307	42.8114	-78.8498
8/25/2016 8:59	12.6	64.99	0	0	0	0	0	0	0.031	100	10	0.004	0.0309	42.8114	-78.8498
8/25/2016 8:58	12.6	75.19	0	0	0	0	0	0	0.029	100	10	0.004	0.0308	42.8114	-78.8498
8/25/2016 8:57	12.6	68.6	0	0	0	0	0	0	0.032	100	10	0.004	0.0309	42.8114	-78.8498
8/25/2016 8:56	12.59	102.45	0	0	0	0	0	0	0.031	100	10	0.004	0.0305	42.8114	-78.8498
8/25/2016 8:55	12.6	74.81	0	0	0	0	0	0	0.031	100	10	0.004	0.0304	42.8114	-78.8498
8/25/2016 8:54	12.56	100.9	0	0	0	0	0	0	0.031	100	10	0.004	0.0304	42.8114	-78.8498
8/25/2016 8:53	12.59	71.32	0	0	0	0	0	0	0.03	100	10	0.004	0.0307	42.8114	-78.8498
8/25/2016 8:52	12.56	111.5	0	0	0	0	0	0	0.032	100	10	0.004	0.0306	42.8114	-78.8498
8/25/2016 8:51	12.6	66.67	0	0	0	0	0	0	0.032	100	10	0.003	0.0306	42.8114	-78.8498
8/25/2016 8:50	12.6	73.77	0	0	0	0	0	0	0.03	100	10	0.003	0.0305	42.8114	-78.8498
8/25/2016 8:49	12.6	104.26	0	0	0	0	0	0	0.032	100	10	0.003	0.0304	42.8114	-78.8498
8/25/2016 8:48	12.6	68.09	0	0	0	0	0	0	0.03	100	10	0.003	0.0302	42.8114	-78.8498
8/25/2016 8:47	12.6	66.93	0	0	0	0	0	0	0.029	100	10	0.003	0.0302	42.8114	-78.8498
8/25/2016 8:46	12.59	67.05	0	0	0	0	0	0	0.03	100	10	0.003	0.0303	42.8114	-78.8498
8/25/2016 8:45	12.6	76.87	0	0	0	0	0	0	0.033	100	11	0.003	0.0302	42.8114	-78.8498
8/25/2016 8:44	12.58	122.35	0	0	0	0	0	0	0.03	100	11	0.003	0.0299	42.8114	-78.8498
8/25/2016 8:43	12.59	67.96	0	0	0	0	0	0	0.03	100	11	0.003	0.0299	42.8114	-78.8498
8/25/2016 8:42	12.58	84.24	0	0	0	0	0	0	0.027	100	11	0.003	0.0299	42.8114	-78.8498
8/25/2016 8:41	12.59	72.35	0	0	0	0	0	0	0.029	100	11	0.003	0.0299	42.8114	-78.8498
8/25/2016 8:40	12.55	117.57	0	0	0	0	0	0	0.031	100	11	0.003	0.0299	42.8114	-78.8498
8/25/2016 8:39	12.59	61.63	0	0	0	0	0	0	0.035	100	11	0.003	0.0296	42.8114	-78.8498
8/25/2016 8:38	12.59	71.83	0	0	0	0	0	0	0.029	100	11	0.003	0.0291	42.8114	-78.8498
8/25/2016 8:37	12.6	73.39	0	0	0	0	0	0	0.032	100	11	0.003	0.0289	42.8114	-78.8498
8/25/2016 8:36	12.56	99.22	0	0	0	0	0	0	0.03	100	11	0.003	0.0286	42.8114	-78.8498
8/25/2016 8:35	12.59	73.26	0	0	0	0	0	0	0.029	100	11	0.002	0.0284	42.8114	-78.8498
8/25/2016 8:34	12.61	85.66	0	0	0	0	0	0	0.029	100	11	0.002	0.0284	42.8114	-78.8498
8/25/2016 8:33	12.59	69.12	0	0	0	0	0	0	0.03	100	11	0.002	0.0283	42.8114	-78.8498
8/25/2016 8:32	12.55	108.79	0	0	0	0	0	0	0.03	100	13	0.002	0.0282	42.8114	-78.8498
8/25/2016 8:31	12.58	73.77	0	0	0	0	0	0	0.029	100	12	0.002	0.0281	42.8114	-78.8498
8/25/2016 8:30	12.58	63.82	0	0	0	0	0	0	0.029	100	12	0.002	0.0281	42.8114	-78.8498
8/25/2016 8:29	12.58	92.25	0	0	0	0	0	0	0.03	100	12	0.002	0.0281	42.8114	-78.8498
8/25/2016 8:28	12.57	98.58	0	0	0	0	0	0	0.029	100	12	0.002	0.0283	42.8114	-78.8497
8/25/2016 8:27	12.6	93.28	0	0	0	0	0	0	0.027	100	12	0.002	0.0285	42.8114	-78.8498
8/25/2016 8:26	12.55	103.88	0	0	0	0	0	0	0.029	100	12	0.002	0.0286	42.8114	-78.8498
8/25/2016 8:25	12.59	66.8	0	0	0	0	0	0	0.027	100	12	0.002	0.0285	42.8114	-78.8498
8/25/2016 8:24	12.55	122.74	0	0	0	0	0	0	0.027	100	12	0.002	0.0288	42.8114	-78.8498
8/25/2016 8:23	12.58	58.01	0	0	0	0	0	0	0.026	100	12	0.002	0.0292	42.8114	-78.8498
8/25/2016 8:22	12.57	82.43	0	0	0	0	0	0	0.028	100	12	0.002	0.0305	42.8114	-78.8498
8/25/2016 8:21	12.57	84.5	0	0	0	0	0	0	0.027	100	12	0.002	0.0311	42.8114	-78.8498
8/25/2016 8:20	12.58	109.04	0	0	0	0	0	0	0.029	100	12	0.002	0.0318	42.8114	-78.8498
8/25/2016 8:19	12.59	89.15	0	0	0	0	0	0	0.027	100	12	0.002	0.0323	42.8114	-78.8498
8/25/2016 8:18	12.57	75.71	0	0	0	0	0	0	0.029	100	12	0.001	0.0333	42.8114	-78.8498
8/25/2016 8:17	12.57	67.83	0	0	0	0	0	0	0.028	100	12	0.001	0.0341	42.8114	-78.8498
8/25/2016 8:16	12.54	79.59	0	0	0	0	0	0	0.029	100	13	0.001	0.0356	42.8114	-78.8498
8/25/2016 8:15	12.56	55.68	0	0	0	0	0	0	0.03	100	13	0.001	0.0366	42.8114	-78.8498
8/25/2016 8:14	12.55	64.86	0	0	0	0	0	0	0.032	100	13	0.001	0.0369	42.8114	-78.8499
8/25/2016 8:13	12.55	75.97	0	0	0	0	0	0	0.032	100	13	0.001	0.0374	42.8114	-78.8499
8/25/2016 8:10									0.031	100	13	0	0.034		
8/25/2016 8:09	12.62	82.17	0	0	0	0	0	0	0.031	100	13	0	0.0322	42.8108	-78.8506
8/25/2016 8:08	12.61	109.43	0	0	0	0	0	0	0.043	100	13	0	0.0323	42.8108	-78.8507
8/25/2016 8:07	12.64	91.99	0	0	0	0	0	0	0.036	100	13	0	0.0315	42.8108	-78.8506
8/25/2016 8:06	12.63	71.19	0	0	0	0	0	0	0.037	100	13	0	0.0311	42.8108	-78.8507
8/25/2016 8:05	12.61	79.72	0	0	0	0	0	0	0.035	100	13	0	0.0305	42.8108	-78.8506
8/25/2016 8:04	12.61	108.53	0	0	0	0	0	0	0.04	100	13	0	0.0301	42.8108	-78.8506
8/25/2016 8:03	12.63	81.52	0	0	0	0	0	0	0.039	100	13	0	0.029	42.8108	-78.8506
8/25/2016 8:02	12.62	83.85	0	0	0	0	0	0	0.048	100	13	0	0.0278	42.8108	-78.8506
8/25/2016 8:01	12.63	81.52	0	0	0	0	0	0	0.042	100	13	0	0.0249	42.8108	-78.8506
8/25/2016 8:00	12.62	58.27	0	0	0	0	0	0	0.034	100	14	0	0.022	42.8108	-78.8506
8/25/2016 7:59	12.6	79.59	0	0	0	0	0	0	0.038	100	14	0	0.0196	42.8108	-78.8506
8/25/2016 7:58	12.59	109.82	0	0	0	0	0	0	0.048	100	14	0	0.015	42.8108	-78.8507
8/25/2016 7:57	12.61	80.88	0	0	0	0	0	0	0.004	100	14	0.006	0.004	42.8108	-78.8506
8/25/2016 7:56	12.61	87.73	0	0	0	0	0	0	0.004	100	14	0.006	0.004	42.8108	-78.8507
8/25/2016 7:55	12.61	103.23	0	0	0	0	0	0	0.004	100	14	0.006	0.004	42.8108	-78.8507



COMMUNITY AIR MONITORING

PERIODIC REVIEW REPORT

Tecumseh Phase III Business Park: Sites III-5 & III-6
Lackawanna, New York

Timestamp (GMT-4)	Low (ppm)	Peak (ppm)	STEL (ppm)	TWA (ppm)	VOC (ppm)	VOC (Avg15) (ppm)	Mass Conc. Total (mg/m³)	TWA (mg/m³)	Mass Conc. Total (Avg15) (mg/m³)	Latitude	Longitude
9/30/2016 15:20										42.8153	-78.845
9/30/2016 15:19										42.8153	-78.845
9/30/2016 15:18										42.8153	-78.845
9/30/2016 15:17										42.8153	-78.845
9/30/2016 15:16										42.8153	-78.845
9/30/2016 15:15										42.8153	-78.845
9/30/2016 15:14										42.8153	-78.845
9/30/2016 15:13										42.8153	-78.845
9/30/2016 15:12										42.8153	-78.845
9/30/2016 15:11										42.8152	-78.845
9/30/2016 15:10										42.8152	-78.845
9/30/2016 15:09										42.8151	-78.845
9/30/2016 15:08										42.8151	-78.845
9/30/2016 15:07										42.8151	-78.845
9/30/2016 15:06										42.8151	-78.845
9/30/2016 15:05										42.8151	-78.845
9/30/2016 15:04										42.8152	-78.845
9/30/2016 15:03										42.8152	-78.845
9/30/2016 15:02										42.8152	-78.845
9/30/2016 15:01										42.8152	-78.845
9/30/2016 15:00										42.8152	-78.845
9/30/2016 14:59										42.8152	-78.845
9/30/2016 14:58										42.8152	-78.845
9/30/2016 14:57										42.8234	-78.8497
9/30/2016 14:56										42.8249	-78.8509
9/30/2016 14:55										42.8213	-78.8522
9/30/2016 14:54										42.8173	-78.8524
9/30/2016 14:53										42.8131	-78.8505
9/30/2016 14:52										42.8109	-78.8499
9/30/2016 14:51										42.8112	-78.8519
9/30/2016 14:50										42.8112	-78.8519
9/30/2016 14:49										42.8111	-78.8518
9/30/2016 14:48										42.8111	-78.8518
9/30/2016 14:47										42.8111	-78.8519
9/30/2016 14:46										42.8111	-78.8519
9/30/2016 14:45										42.8111	-78.8518
9/30/2016 14:44										42.8111	-78.8519
9/30/2016 14:43										42.8112	-78.8519
9/30/2016 14:42	0	0	0	0	0	0	0.675	0.002	0.0492	42.8112	-78.8519
9/30/2016 14:41	0	0	0	0	0	0	0	0.002	0.0039	42.8112	-78.8519

COMMUNITY AIR MONITORING

PERIODIC REVIEW REPORT

Tecumseh Phase III Business Park: Sites III-5 & III-6
Lackawanna, New York

Timestamp (GMT-4)	Low (ppm)	Peak (ppm)	STEL (ppm)	TWA (ppm)	VOC (ppm)	VOC (Avg15) (ppm)	Mass Conc. Total (mg/m³)	TWA (mg/m³)	Mass Conc. Total (Avg15) (mg/m³)	Latitude	Longitude
9/30/2016 14:40	0	0	0	0	0	0	0.001	0.002	0.0043	42.8112	-78.8519
9/30/2016 14:39	0	0	0	0	0	0	-0.004	0.002	0.0043	42.8111	-78.8519
9/30/2016 14:38	0	0	0	0	0	0	0.034	0.002	0.0069	42.8111	-78.8519
9/30/2016 14:37	0	0	0	0	0	0	-0.002	0.002	0.0043	42.8111	-78.8519
9/30/2016 14:36	0	0	0	0	0	0	0.008	0.002	0.0041	42.8112	-78.8519
9/30/2016 14:35	0	0	0	0	0	0	-0.002	0.002	0.0049	42.8112	-78.8519
9/30/2016 14:34	0	0	0	0	0	0	-0.001	0.002	0.0048	42.8111	-78.8519
9/30/2016 14:33	0	0	0	0	0	0	-0.002	0.002	0.0047	42.8112	-78.8519
9/30/2016 14:32	0	0	0	0	0	0	0	0.002	0.0046	42.8112	-78.8519
9/30/2016 14:31	0	0	0	0	0	0	0.01	0.002	0.0043	42.8112	-78.8519
9/30/2016 14:30	0	0	0	0	0	0	0.008	0.002	0.0034	42.8112	-78.8519
9/30/2016 14:29	0	0	0	0	0	0	0.003	0.002	0.0027	42.8112	-78.8519
9/30/2016 14:28	0	0	0	0	0	0	0.01	0.002	0.0023	42.8111	-78.8519
9/30/2016 14:27	0	0	0	0	0	0	-0.004	0.002	0.0033	42.8112	-78.8519
9/30/2016 14:26	0	0	0	0	0	0	0.006	0.002	0.0035	42.8112	-78.8519
9/30/2016 14:25	0	0	0	0	0	0	0	0.002	0.0046	42.8112	-78.8519
9/30/2016 14:24	0	0	0	0	0	0	0.036	0.002	0.0044	42.8112	-78.8519
9/30/2016 14:23	0	0	0	0	0	0	-0.005	0.002	0.002	42.8112	-78.8519
9/30/2016 14:22	0	0	0	0	0	0	-0.005	0.002	0.002	42.8112	-78.8519
9/30/2016 14:21	0	0	0	0	0	0	0.02	0.002	0.0021	42.8112	-78.8519
9/30/2016 14:20	0	0	0	0	0	0	-0.004	0.002	0.0008	42.8112	-78.8519
9/30/2016 14:19	0	0	0	0	0	0	-0.003	0.002	0.0008	42.8112	-78.8519
9/30/2016 14:18	0	0	0	0	0	0	-0.003	0.002	0.0007	42.8112	-78.8519
9/30/2016 14:17	0	0	0	0	0	0	-0.004	0.002	0.0009	42.8112	-78.8519
9/30/2016 14:16	0	0	0	0	0	0	-0.004	0.002	0.0009	42.8112	-78.8519
9/30/2016 14:15	0	0	0	0	0	0	-0.003	0.002	0.0009	42.8112	-78.8519
9/30/2016 14:14	0	0	0	0	0	0	-0.002	0.002	0.0009	42.8112	-78.8519
9/30/2016 14:13	0	0	0	0	0	0	0.024	0.002	0.0023	42.8112	-78.8519
9/30/2016 14:12	0	0	0	0	0	0	-0.001	0.002	0.0008	42.8112	-78.8519
9/30/2016 14:11	0	0	0	0	0	0	0.023	0.002	0.0007	42.8112	-78.8519
9/30/2016 14:10	0	0	0	0	0	0	-0.003	0.002	-0.0011	42.8112	-78.8519
9/30/2016 14:09	0	0	0	0	0	0	0	0.002	-0.0009	42.8112	-78.8519
9/30/2016 14:08	0	0	0	0	0	0	-0.005	0.002	-0.0006	42.8112	-78.8519
9/30/2016 14:07	0	0	0	0	0	0	-0.003	0.002	0.0001	42.8112	-78.8519
9/30/2016 14:06	0	0	0	0	0	0	0	0.002	0.0002	42.8112	-78.8519
9/30/2016 14:05	0	0	0	0	0	0	-0.004	0.002	-0.0001	42.8112	-78.8519
9/30/2016 14:04	0	0	0	0	0	0	-0.004	0.002	0.0001	42.8112	-78.8519
9/30/2016 14:03	0	0	0	0	0	0	0	0.002	0.0002	42.8112	-78.8519
9/30/2016 14:02	0	0	0	0	0	0	-0.004	0.002	-0.0001	42.8112	-78.8519
9/30/2016 14:01	0	0	0	0	0	0	-0.004	0.002	0.0024	42.8112	-78.8519
9/30/2016 14:00	0	0	0	0	0	0	-0.003	0.002	0.0031	42.8112	-78.8519
9/30/2016 13:59	0	0	0	0	0	0	0.019	0.002	0.0041		
9/30/2016 13:58											
9/30/2016 13:57	0	0	0	0	0	0	-0.002	0.002	0.0029	42.8112	-78.8519
9/30/2016 13:56	0	0	0	0	0	0	-0.003	0.002	0.0028	42.8112	-78.8519
9/30/2016 13:55	0	0	0	0	0	0	0	0.002	0.0029	42.8112	-78.8519
9/30/2016 13:54	0	0	0	0	0	0	0.004	0.002	0.0033	42.8112	-78.8519
9/30/2016 13:53	0	0	0	0	0	0	0.006	0.002	0.0028	42.8112	-78.8519
9/30/2016 13:52	0	0	0	0	0	0	-0.002	0.002	0.0023	42.8112	-78.8519

COMMUNITY AIR MONITORING

PERIODIC REVIEW REPORT

Tecumseh Phase III Business Park: Sites III-5 & III-6
Lackawanna, New York

Timestamp (GMT-4)	Low (ppm)	Peak (ppm)	STEL (ppm)	TWA (ppm)	VOC (ppm)	VOC (Avg15) (ppm)	Mass Conc. Total (mg/m³)	TWA (mg/m³)	Mass Conc. Total (Avg15) (mg/m³)	Latitude	Longitude
9/30/2016 13:51	0	0	0	0	0	0	-0.004	0.002	0.0023	42.8112	-78.8519
9/30/2016 13:50	0	0	0	0	0	0	-0.001	0.002	0.0027	42.8112	-78.8519
9/30/2016 13:49	0	0	0	0	0	0	-0.003	0.002	0.0025	42.8112	-78.8519
9/30/2016 13:48	0	0	0	0	0	0	-0.004	0.002	0.0025	42.8112	-78.8519
9/30/2016 13:47	0	0	0	0	0	0	0.031	0.002	0.0025	42.8112	-78.8519
9/30/2016 13:46	0	0	0	0	0	0	0.005	0.002	0.0001	42.8112	-78.8519
9/30/2016 13:45	0	0	0	0	0	0	0.012	0.002	-0.0004	42.8112	-78.8519
9/30/2016 13:44	0	0	0	0	0	0	0.001	0.002	-0.0014	42.8112	-78.8519
9/30/2016 13:43	0	0	0	0	0	0	0.004	0.002	-0.001	42.8112	-78.8519
9/30/2016 13:42	0	0	0	0	0	0	-0.004	0.002	-0.0001	42.8112	-78.8519
9/30/2016 13:41	0	0	0	0	0	0	-0.002	0.002	0.0002	42.8112	-78.8519
9/30/2016 13:40	0	0	0	0	0	0	0.007	0.002	0.0003	42.8112	-78.8519
9/30/2016 13:39	0	0	0	0	0	0	-0.004	0.002	-0.0003	42.8112	-78.8519
9/30/2016 13:38	0	0	0	0	0	0	-0.002	0.002	-0.0001	42.8112	-78.8519
9/30/2016 13:37	0	0	0	0	0	0	-0.001	0.002	-0.0001	42.8112	-78.8519
9/30/2016 13:36	0	0	0	0	0	0	0.001	0.002	0	42.8112	-78.8519
9/30/2016 13:35	0	0	0	0	0	0	-0.003	0.002	0.0001	42.8112	-78.8519
9/30/2016 13:34	0	0	0	0	0	0	-0.004	0.002	0.0003	42.8112	-78.8519
9/30/2016 13:33	0	0	0	0	0	0	-0.004	0.002	0.0015	42.8112	-78.8519
9/30/2016 13:32	0	0	0	0	0	0	-0.004	0.002	0.0018	42.8112	-78.8519
9/30/2016 13:31	0	0	0	0	0	0	-0.003	0.002	0.0057	42.8112	-78.8519
9/30/2016 13:30	0	0	0	0	0	0	-0.003	0.002	0.0062	42.8112	-78.8519
9/30/2016 13:29	0	0	0	0	0	0	0.007	0.002	0.0277	42.8112	-78.8519
9/30/2016 13:28	0	0	0	0	0	0	0.017	0.002	0.0273	42.8112	-78.8519
9/30/2016 13:27	0	0	0	0	0	0	0.001	0.002	0.0261	42.8112	-78.8519
9/30/2016 13:26	0	0	0	0	0	0	0	0.002	0.026	42.8112	-78.8519
9/30/2016 13:25	0	0	0	0	0	0	-0.003	0.002	0.0258	42.8112	-78.8519
9/30/2016 13:24	0	0	0	0	0	0	-0.001	0	0.0259	42.8112	-78.8519
9/30/2016 13:23	0	0	0	0	0	0	-0.001	0.002	0.0259	42.8112	-78.8519
9/30/2016 13:22	0	0	0	0	0	0	0	0.002	0.0257	42.8112	-78.8519
9/30/2016 13:21	0	0	0	0	0	0	0.003	0.002	0.0257	42.8112	-78.8519
9/30/2016 13:20	0	0	0	0	0	0	0	0.002	0.0256	42.8112	-78.8519
9/30/2016 13:19	0	0	0	0	0	0	0.014	0.002	0.0255	42.8112	-78.8519
9/30/2016 13:18	0	0	0	0	0	0	0	0.002	0.0245	42.8112	-78.8519
9/30/2016 13:17	0	0	0	0	0	0	0.054	0.002	0.0243	42.8112	-78.8519
9/30/2016 13:16	0	0	0	0	0	0	0.005	0.002	0.0207	42.8112	-78.8519
9/30/2016 13:15	0	0	0	0	0	0	0.32	0.002	0.0205	42.8112	-78.8519
9/30/2016 13:14	0	0	0	0	0	0	0	0.002	-0.0009	42.8112	-78.8519
9/30/2016 13:13	0	0	0	0	0	0	-0.001	0.002	-0.0009	42.8112	-78.8519
9/30/2016 13:12	0	0	0	0	0	0	0	0.002	-0.0009	42.8112	-78.8519
9/30/2016 13:11	0	0	0	0	0	0	-0.003	0.002	-0.0011	42.8112	-78.8519
9/30/2016 13:10	0	0	0	0	0	0	-0.001	0.002	-0.0011	42.8112	-78.8519
9/30/2016 13:09	0	0	0	0	0	0	-0.002	0.002	-0.0012	42.8112	-78.8519
9/30/2016 13:08	0	0	0	0	0	0	-0.003	0.002	-0.0012	42.8112	-78.8519
9/30/2016 13:07	0	0	0	0	0	0	0	0.002	-0.0012	42.8112	-78.8519
9/30/2016 13:06	0	0	0	0	0	0	0.001	0.002	-0.0012	42.8112	-78.8519
9/30/2016 13:05	0	0	0	0	0	0	-0.001	0.002	-0.0014	42.8112	-78.8519
9/30/2016 13:04	0	0	0	0	0	0	-0.001	0.002	-0.0013	42.8112	-78.8519
9/30/2016 13:03	0	0	0	0	0	0	-0.003	0.002	-0.0012	42.8112	-78.8519
9/30/2016 13:02	0	0	0	0	0	0	0	0.002	-0.0011	42.8112	-78.8519
9/30/2016 13:01	0	0	0	0	0	0	0.001	0.002	-0.0013	42.8112	-78.8519
9/30/2016 13:00	0	0	0	0	0	0	0	0.002	-0.0016	42.8112	-78.8519
9/30/2016 12:59	0	0	0	0	0	0	0	0.002	-0.0017	42.8112	-78.8519

COMMUNITY AIR MONITORING

PERIODIC REVIEW REPORT

Tecumseh Phase III Business Park: Sites III-5 & III-6
Lackawanna, New York

Timestamp (GMT-4)	Low (ppm)	Peak (ppm)	STEL (ppm)	TWA (ppm)	VOC (ppm)	VOC (Avg15) (ppm)	Mass Conc. Total (mg/m³)	TWA (mg/m³)	Mass Conc. Total (Avg15) (mg/m³)	Latitude	Longitude
9/30/2016 12:58	0	0	0	0	0	0	-0.001	0.002	-0.002	42.8112	-78.8519
9/30/2016 12:57	0	0	0	0	0	0	-0.004	0.002	-0.0019	42.8112	-78.8519
9/30/2016 12:56	0	0	0	0	0	0	-0.002	0.002	-0.0017	42.8112	-78.8519
9/30/2016 12:55	0	0	0	0	0	0	-0.003	0.002	-0.0016	42.8112	-78.8519
9/30/2016 12:54	0	0	0	0	0	0	-0.002	0.002	-0.0014	42.8112	-78.8519
9/30/2016 12:53	0	0	0	0	0	0	-0.003	0.002	-0.0011	42.8112	-78.8519
9/30/2016 12:52	0	0	0	0	0	0	0	0.002	-0.001	42.8112	-78.8519
9/30/2016 12:51	0	0	0	0	0	0	-0.002	0.002	-0.0013	42.8112	-78.8519
9/30/2016 12:50	0	0	0	0	0	0	0	0.002	-0.0013	42.8112	-78.8519
9/30/2016 12:49	0	0	0	0	0	0	0.001	0.001	-0.0011	42.8112	-78.8519
9/30/2016 12:48	0	0	0	0	0	0	-0.001	0.001	0.0011	42.8112	-78.8519
9/30/2016 12:47	0	0	0	0	0	0	-0.004	0.001	0.0056	42.8112	-78.8519
9/30/2016 12:46	0	0	0	0	0	0	-0.003	0.001	0.0057	42.8112	-78.8519
9/30/2016 12:45	0	0	0	0	0	0	-0.002	0.001	0.0062	42.8112	-78.8519
9/30/2016 12:44	0	0	0	0	0	0	-0.004	0.001	0.0066	42.8112	-78.8519
9/30/2016 12:43	0	0	0	0	0	0	0	0.001	0.0078	42.8112	-78.8519
9/30/2016 12:42	0	0	0	0	0	0	-0.001	0.001	0.0076	42.8112	-78.8519
9/30/2016 12:41	0	0	0	0	0	0	0	0.001	0.0075	42.8112	-78.8519
9/30/2016 12:40	0	0	0	0	0	0	0	0.001	0.0073	42.8112	-78.8519
9/30/2016 12:39	0	0	0	0	0	0	0.003	0.001	0.0084	42.8112	-78.8519
9/30/2016 12:38	0	0	0	0	0	0	-0.002	0.001	0.0082	42.8112	-78.8519
9/30/2016 12:37	0	0	0	0	0	0	-0.004	0.001	0.0083	42.8112	-78.8519
9/30/2016 12:36	0	0	0	0	0	0	-0.002	0.001	0.0084	42.8112	-78.8519
9/30/2016 12:35	0	0	0	0	0	0	0.002	0.001	0.0086	42.8112	-78.8519
9/30/2016 12:34	0	0	0	0	0	0	0.034	0.001	0.0084	42.8112	-78.8519
9/30/2016 12:33	0	0	0	0	0	0	0.067	0.001	0.0061	42.8112	-78.8519
9/30/2016 12:32	0	0	0	0	0	0	-0.002	0.001	0.0016	42.8111	-78.8519
9/30/2016 12:31	0	0	0	0	0	0	0.004	0.001	0.0035	42.8112	-78.8519
9/30/2016 12:30	0	0	0	0	0	0	0.004	0.001	0.0033	42.8112	-78.8519
9/30/2016 12:29	0	0	0	0	0	0	0.014	0.001	0.0029	42.8112	-78.8519
9/30/2016 12:28	0	0	0	0	0	0	-0.003	0.001	0.0019	42.8112	-78.8519
9/30/2016 12:27	0	0	0	0	0	0	-0.002	0.001	0.0021	42.8112	-78.8519
9/30/2016 12:26	0	0	0	0	0	0	-0.003	0.001	0.0022	42.8112	-78.8519
9/30/2016 12:25	0	0	0	0	0	0	0.016	0.001	0.0022	42.8112	-78.8519
9/30/2016 12:24	0	0	0	0	0	0	0	0.001	0.0011	42.8112	-78.8519
9/30/2016 12:23	0	0	0	0	0	0	-0.001	0.001	0.0012	42.8112	-78.8519
9/30/2016 12:22	0	0	0	0	0	0	-0.002	0.001	0.0011	42.8112	-78.8519
9/30/2016 12:21	0	0	0	0	0	0	0.001	0.001	0.0015	42.8112	-78.8519
9/30/2016 12:20	0	0	0	0	0	0	-0.001	0.001	0.0013	42.8112	-78.8519
9/30/2016 12:19	0	0	0	0	0	0	-0.001	0.001	0.0014	42.8112	-78.8519
9/30/2016 12:18	0	0	0	0	0	0	0	0.001	0.0014	42.8112	-78.8519
9/30/2016 12:17	0	0	0	0	0	0	0.027	0.001	0.0014	42.8112	-78.8519
9/30/2016 12:16	0	0	0	0	0	0	0	0.001	-0.0006	42.8112	-78.8519
9/30/2016 12:15	0	0	0	0	0	0	-0.002	0.001	-0.0006	42.8112	-78.8519
9/30/2016 12:14	0	0	0	0	0	0	-0.001	0.001	-0.0005	42.8112	-78.8519
9/30/2016 12:13	0	0	0	0	0	0	0	0.001	0.0022	42.8112	-78.8519
9/30/2016 12:12	0	0	0	0	0	0	0	0.001	0.0026	42.8112	-78.8519
9/30/2016 12:11	0	0	0	0	0	0	-0.003	0.001	0.0026	42.8112	-78.8519
9/30/2016 12:10	0	0	0	0	0	0	0	0.001	0.0029	42.8112	-78.8519
9/30/2016 12:09	0	0	0	0	0	0				42.8112	-78.8519
9/30/2016 12:08	0	0	0	0	0	0	-0.003	0.001	0.0026	42.8112	-78.8519
9/30/2016 12:07	0	0	0	0	0	0	0.004	0.001	0.0029	42.8112	-78.8519
9/30/2016 12:06	0	0	0	0	0	0	-0.002	0.001	0.0041	42.8112	-78.8519

COMMUNITY AIR MONITORING

PERIODIC REVIEW REPORT

Tecumseh Phase III Business Park: Sites III-5 & III-6
Lackawanna, New York

Timestamp (GMT-4)	Low (ppm)	Peak (ppm)	STEL (ppm)	TWA (ppm)	VOC (ppm)	VOC (Avg15) (ppm)	Mass Conc. Total (mg/m³)	TWA (mg/m³)	Mass Conc. Total (Avg15) (mg/m³)	Latitude	Longitude
9/30/2016 12:05	0	0	0	0	0	0	0	0.001	0.0067	42.8112	-78.8519
9/30/2016 12:04	0	0	0	0	0	0	0	0.001	0.0067	42.8111	-78.8519
9/30/2016 12:03	0	0	0	0	0	0	0	0.001	0.0067	42.8111	-78.8519
9/30/2016 12:02	0	0	0	0	0	0	-0.001	0.001	0.0066	42.8111	-78.8519
9/30/2016 12:01	0	0	0	0	0	0	-0.001	0.001	0.0068	42.8112	-78.8519
9/30/2016 12:00	0	0	0	0	0	0	0	0.001	0.0069	42.8112	-78.8519
9/30/2016 11:59	0	0	0	0	0	0	0.037	0.001	0.0067	42.8112	-78.8519
9/30/2016 11:58	0	0	0	0	0	0	0.006	0.001	0.0043	42.8112	-78.8519
9/30/2016 11:57	0	0	0	0	0	0	0	0.001	0.0038	42.8112	-78.8519
9/30/2016 11:56	0	0	0	0	0	0	0	0.001	0.0037	42.8112	-78.8519
9/30/2016 11:55	0	0	0	0	0	0	-0.001	0.001	0.0041	42.8112	-78.8519
9/30/2016 11:54	0	0	0	0	0	0	0	0.001	0.0041	42.8112	-78.8519
9/30/2016 11:53	0	0	0	0	0	0	0.001	0.001	0.0041	42.8112	-78.8519
9/30/2016 11:52	0	0	0	0	0	0	0.023	0.001	0.0039	42.8112	-78.8519
9/30/2016 11:51	0	0	0	0	0	0	0.036	0.001	0.0025	42.8112	-78.8519
9/30/2016 11:50	0	0	0	0	0	0	0	0.001	0	42.8112	-78.8519
9/30/2016 11:49	0	0	0	0	0	0	0	0.001	0	42.8112	-78.8519
9/30/2016 11:48	0	0	0	0	0	0	-0.001	0.001	-0.0001	42.8112	-78.8519
9/30/2016 11:47	0	0	0	0	0	0	0.002	0.001	0	42.8112	-78.8519
9/30/2016 11:46	0	0	0	0	0	0	0	0.001	-0.0002	42.8112	-78.8519
9/30/2016 11:45	0	0	0	0	0	0	-0.002	0.001	-0.0002	42.8112	-78.8519
9/30/2016 11:44	0	0	0	0	0	0	0	0.001	-0.0001	42.8112	-78.8519
9/30/2016 11:43	0	0	0	0	0	0	-0.001	0.001	0.001	42.8112	-78.8519
9/30/2016 11:42	0	0	0	0	0	0	-0.001	0.001	0.0011	42.8112	-78.8519
9/30/2016 11:41	0	0	0	0	0	0	0.005	0.001	0.001	42.8112	-78.8519
9/30/2016 11:40	0	0	0	0	0	0	0	0.001	0.0006	42.8112	-78.8519
9/30/2016 11:39	0	0	0	0	0	0	0	0.001	0.0006	42.8112	-78.8519
9/30/2016 11:38	0	0	0	0	0	0	-0.002	0.001	0.0005	42.8112	-78.8519
9/30/2016 11:37	0	0	0	0	0	0	0.001	0.001	0.0007	42.8112	-78.8519
9/30/2016 11:36	0	0	0	0	0	0	-0.001	0.001	0.0006	42.8112	-78.8519
9/30/2016 11:35	0	0	0	0	0	0	0	0.001	0.0007	42.8112	-78.8519
9/30/2016 11:34	0	0	0	0	0	0	-0.001	0.001	0.0006	42.8112	-78.8519
9/30/2016 11:33	0	0	0	0	0	0	0	0.001	0.0009	42.8112	-78.8519
9/30/2016 11:32	0	0	0	0	0	0	-0.001	0.001	0.0011	42.8112	-78.8519
9/30/2016 11:31	0	0	0	0	0	0	0	0.001	0.0011	42.8112	-78.8519
9/30/2016 11:30	0	0	0	0	0	0	0	0.001	0.0011	42.8112	-78.8519
9/30/2016 11:29	0	0	0	0	0	0	0.016	0.001	0.0011	42.8112	-78.8519
9/30/2016 11:28	0	0	0	0	0	0	0	0.001	-0.0001	42.8112	-78.8519
9/30/2016 11:27	0	0	0	0	0	0	-0.002	0.001	-0.0001	42.8112	-78.8519
9/30/2016 11:26	0	0	0	0	0	0	-0.001	0.001	0.0001	42.8112	-78.8519
9/30/2016 11:25	0	0	0	0	0	0	0	0.001	0.0001	42.8112	-78.8519
9/30/2016 11:24	0	0	0	0	0	0	-0.001	0.001	0.0001	42.8112	-78.8519
9/30/2016 11:23	0	0	0	0	0	0	0	0.001	0.0012	42.8112	-78.8519
9/30/2016 11:22	0	0	0	0	0	0	0	0.001	0.0012	42.8112	-78.8519
9/30/2016 11:21	0	0	0	0	0	0	0	0.001	0.0013	42.8112	-78.8519
9/30/2016 11:20	0	0	0	0	0	0	-0.001	0.001	0.0013	42.8112	-78.8519
9/30/2016 11:19	0	0	0	0	0	0	0.003	0.001	0.0013	42.8112	-78.8519
9/30/2016 11:18	0	0	0	0	0	0	0.003	0.001	0.0011	42.8112	-78.8519
9/30/2016 11:17	0	0	0	0	0	0	-0.001	0.001	0.0009	42.8112	-78.8519
9/30/2016 11:16	0	0	0	0	0	0	0	0.001	0.001	42.8112	-78.8519
9/30/2016 11:15	0	0	0	0	0	0	0	0.001	0.0013	42.8112	-78.8519
9/30/2016 11:14	0	0	0	0	0	0	-0.001	0.001	0.0012	42.8112	-78.8519
9/30/2016 11:13	0	0	0	0	0	0	0	0.001	0.0013	42.8112	-78.8519

COMMUNITY AIR MONITORING

PERIODIC REVIEW REPORT

Tecumseh Phase III Business Park: Sites III-5 & III-6
Lackawanna, New York

Timestamp (GMT-4)	Low (ppm)	Peak (ppm)	STEL (ppm)	TWA (ppm)	VOC (ppm)	VOC (Avg15) (ppm)	Mass Conc. Total (mg/m³)	TWA (mg/m³)	Mass Conc. Total (Avg15) (mg/m³)	Latitude	Longitude
9/30/2016 11:12	0	0	0	0	0	0	0	0.001	0.0013	42.8112	-78.8519
9/30/2016 11:11	0	0	0	0	0	0	0	0.001	0.0013	42.8112	-78.8519
9/30/2016 11:10	0	0	0	0	0	0	0	0.001	0.0012	42.8112	-78.8519
9/30/2016 11:09	0	0	0	0	0	0	0.015	0.001	0.0012	42.8112	-78.8519
9/30/2016 11:08	0	0	0	0	0	0	0	0.001	0.0001	42.8112	-78.8519
9/30/2016 11:07	0	0	0	0	0	0	0.001	0.001	0.0001	42.8112	-78.8519
9/30/2016 11:06	0	0	0	0	0	0	0.001	0.001	0	42.8112	-78.8519
9/30/2016 11:05	0	0	0	0	0	0	-0.001	0.001	-0.0001	42.8112	-78.8519
9/30/2016 11:04	0	0	0	0	0	0	0	0.001	0	42.8112	-78.8519
9/30/2016 11:03	0	0	0	0	0	0	0	0.001	0	42.8112	-78.8519
9/30/2016 11:02	0	0	0	0	0	0	0	0.001	-0.0001	42.8112	-78.8519
9/30/2016 11:01	0	0	0	0	0	0	0.004	0.001	-0.0001	42.8112	-78.8519
9/30/2016 11:00	0	0	0	0	0	0	-0.001	0.001	-0.0003	42.8112	-78.8519
9/30/2016 10:59	0	0	0	0	0	0	0	0.001	-0.0003	42.8112	-78.8519
9/30/2016 10:58	0	0	0	0	0	0	0	0.001	-0.0003	42.8112	-78.8519
9/30/2016 10:57	0	0	0	0	0	0	0	0.001	-0.0001	42.8112	-78.8519
9/30/2016 10:56	0	0	0	0	0	0	-0.001	0.001	-0.0001	42.8112	-78.8519
9/30/2016 10:55	0	0	0	0	0	0	0	0.001	0.0003	42.8112	-78.8519
9/30/2016 10:54	0	0	0	0	0	0	-0.001	0.001	0.0003	42.8112	-78.8519
9/30/2016 10:53	0	0	0	0	0	0	0	0.001	0.0006	42.8112	-78.8519
9/30/2016 10:52	0	0	0	0	0	0	-0.001	0.001	0.0006	42.8112	-78.8519
9/30/2016 10:51	0	0	0	0	0	0	0	0.001	0.0015	42.8112	-78.8519
9/30/2016 10:50	0	0	0	0	0	0	0	0.001	0.0018	42.8112	-78.8519
9/30/2016 10:49	0	0	0	0	0	0	0	0.001	0.0018	42.8112	-78.8519
9/30/2016 10:48	0	0	0	0	0	0	-0.001	0.001	0.0019	42.8112	-78.8519
9/30/2016 10:47	0	0	0	0	0	0	0	0.001	0.0019	42.8112	-78.8519
9/30/2016 10:46	0	0	0	0	0	0	0	0.001	0.0019	42.8112	-78.8519
9/30/2016 10:45	0	0	0	0	0	0	0	0.001	0.0019	42.8112	-78.8519
9/30/2016 10:44	0	0	0	0	0	0	0	0.001	0.0019	42.8112	-78.8519
9/30/2016 10:43	0	0	0	0	0	0	0.002	0.001	0.0019	42.8112	-78.8519
9/30/2016 10:42	0	0	0	0	0	0	0.001	0.001	0.0019	42.8112	-78.8519
9/30/2016 10:41	0	0	0	0	0	0	0.004	0.001	0.0018	42.8112	-78.8519
9/30/2016 10:40	0	0	0	0	0	0	0	0.001	0.0018	42.8112	-78.8519
9/30/2016 10:39	0	0	0	0	0	0	0.004	0.001	0.0018	42.8112	-78.8519
9/30/2016 10:38	0	0	0	0	0	0	0	0.001	0.0015	42.8112	-78.8519
9/30/2016 10:37	0	0	0	0	0	0	0.013	0.001	0.0015	42.8112	-78.8519
9/30/2016 10:36	0	0	0	0	0	0	0.004	0.001	0.0005	42.8112	-78.8519
9/30/2016 10:35	0	0	0	0	0	0	0	0.001	0.0003	42.8112	-78.8519
9/30/2016 10:34	0	0	0	0	0	0	0.001	0.001	0.0003	42.8112	-78.8519
9/30/2016 10:33	0	0	0	0	0	0	0	0.001	0.0019	42.8112	-78.8519
9/30/2016 10:32	0	0	0	0	0	0	0	0.001	0.0019	42.8112	-78.8519
9/30/2016 10:31	0	0	0	0	0	0	0	0.001	0.0019	42.8112	-78.8519
9/30/2016 10:30	0	0	0	0	0	0	0	0.001	0.0019	42.8112	-78.8519
9/30/2016 10:29	0	0	0	0	0	0	-0.001	0.001	0.0019	42.8112	-78.8519
9/30/2016 10:28	0	0	0	0	0	0	0.002	0.001	0.0019	42.8112	-78.8519
9/30/2016 10:27	0	0	0	0	0	0	0	0.001	0.0017	42.8112	-78.8519
9/30/2016 10:26	0	0	0	0	0	0	0.004	0.001	0.0017	42.8112	-78.8519
9/30/2016 10:25	0	0	0	0	0	0	0	0.001	0.0014	42.8112	-78.8519
9/30/2016 10:24	0	0	0	0	0	0	0	0.001	0.0014	42.8112	-78.8519
9/30/2016 10:23	0	0	0	0	0	0	-0.001	0.001	0.0014	42.8112	-78.8519
9/30/2016 10:22	0	0	0	0	0	0	-0.001	0.001	0.0014	42.8112	-78.8519
9/30/2016 10:21	0	0	0	0	0	0	0	0.001	0.0014	42.8112	-78.8519
9/30/2016 10:20	0	0	0	0	0	0	0	0.001	0.0014	42.8112	-78.8519

COMMUNITY AIR MONITORING

PERIODIC REVIEW REPORT

Tecumseh Phase III Business Park: Sites III-5 & III-6
Lackawanna, New York

Timestamp (GMT-4)	Low (ppm)	Peak (ppm)	STEL (ppm)	TWA (ppm)	VOC (ppm)	VOC (Avg15) (ppm)	Mass Conc. Total (mg/m³)	TWA (mg/m³)	Mass Conc. Total (Avg15) (mg/m³)	Latitude	Longitude
9/30/2016 10:19	0	0	0	0	0	0	0.025	0.001	0.0013	42.8112	-78.8519
9/30/2016 10:18	0	0	0	0	0	0	0.001	0.001	-0.0003	42.8112	-78.8519
9/30/2016 10:17	0	0	0	0	0	0	0	0.001	-0.0004	42.8112	-78.8519
9/30/2016 10:16	0	0	0	0	0	0	0	0.001	-0.0003	42.8112	-78.8519
9/30/2016 10:15	0	0	0	0	0	0	-0.001	0.001	-0.0003	42.8112	-78.8519
9/30/2016 10:14	0	0	0	0	0	0	0	0.001	-0.0002	42.8112	-78.8519
9/30/2016 10:13	0	0	0	0	0	0	-0.001	0.001	-0.0002	42.8112	-78.8519
9/30/2016 10:12	0	0	0	0	0	0	-0.001	0.001	-0.0002	42.8112	-78.8519
9/30/2016 10:11	0	0	0	0	0	0	0	0.001	-0.0001	42.8112	-78.8519
9/30/2016 10:10	0	0	0	0	0	0	0	0.001	-0.0001	42.8112	-78.8519
9/30/2016 10:09	0	0	0	0	0	0	0	0.001	-0.0002	42.8112	-78.8519
9/30/2016 10:08	0	0	0	0	0	0	-0.001	0.001	-0.0002	42.8112	-78.8519
9/30/2016 10:07	0	0	0	0	0	0	-0.001	0.001	-0.0001	42.8112	-78.8519
9/30/2016 10:06	0	0	0	0	0	0	0	0.001	-0.0001	42.8112	-78.8519
9/30/2016 10:05	0	0	0	0	0	0	-0.001	0.001	-0.0001	42.8112	-78.8519
9/30/2016 10:04	0	0	0	0	0	0	0	0.001	0	42.8112	-78.8519
9/30/2016 10:03	0	0	0	0	0	0	0	0	-0.0001	42.8112	-78.8519
9/30/2016 10:02	0	0	0	0	0	0	0.002	0.001	-0.0001	42.8112	-78.8519
9/30/2016 10:01	0	0	0	0	0	0	0	0.001	-0.0001	42.8112	-78.8519
9/30/2016 10:00	0	0	0	0	0	0	0	0.001	0.0006	42.8112	-78.8519
9/30/2016 9:59	0	0	0	0	0	0	0	0.001	0.0005	42.8112	-78.8519
9/30/2016 9:58	0	0	0	0	0	0	-0.001	0.001	0.0005	42.8112	-78.8519
9/30/2016 9:57	0	0	0	0	0	0	0	0.001	0.0006	42.8112	-78.8519
9/30/2016 9:54	0	0	0	0	0	0	0	0.001	0.0006	42.8112	-78.8519
9/30/2016 9:53	0	0	0	0	0	0	0	0.001	0.0006	42.8112	-78.8519
9/30/2016 9:52	0	0	0	0	0	0	-0.001	0.001	0.0007	42.8112	-78.8519
9/30/2016 9:51	0	0	0	0	0	0	0	0.001	0.0012	42.8112	-78.8519
9/30/2016 9:50	0	0	0	0	0	0	0	0.001	0.002	42.8112	-78.8519
9/30/2016 9:49	0	0	0	0	0	0	-0.001	0.001	0.0023	42.8112	-78.8519
9/30/2016 9:48	0	0	0	0	0	0	0	0.001	0.0023	42.8112	-78.8519
9/30/2016 9:47	0	0	0	0	0	0	0.002	0.001	0.0023	42.8112	-78.8519
9/30/2016 9:46	0	0	0	0	0	0	0.009	0.001	0.0022	42.8112	-78.8519
9/30/2016 9:45	0	0	0	0	0	0	-0.001	0.001	0.0051	42.8112	-78.8519
9/30/2016 9:44	0	0	0	0	0	0	0	0.001	0.0051	42.8112	-78.8519
9/30/2016 9:43	0	0	0	0	0	0	0	0.001	0.0051	42.8112	-78.8519
9/30/2016 9:42	0	0	0	0	0	0	0	0.001	0.0051	42.8112	-78.8519
9/30/2016 9:41	0	0	0	0	0	0	0.001	0.001	0.0068	42.8112	-78.8519
9/30/2016 9:40	0	0	0	0	0	0	0	0.001	0.0067	42.8112	-78.8519
9/30/2016 9:39	0	0	0	0	0	0	0	0.001	0.0068	42.8112	-78.8519
9/30/2016 9:38	0	0	0	0	0	0	0.002	0.001	0.0068	42.8112	-78.8519
9/30/2016 9:37	0	0	0	0	0	0	0.006	0.001	0.0067	42.8112	-78.8519
9/30/2016 9:36	0	0	0	0	0	0	0.012	0.001	0.0063	42.8112	-78.8519
9/30/2016 9:35	0	0	0	0	0	0	0.004	0.001	0.0055	42.8112	-78.8519
9/30/2016 9:34	0	0	0	0	0	0	0	0.001	0.0052	42.8112	-78.8519
9/30/2016 9:33	0	0	0	0	0	0	0	0.001	0.0052	42.8112	-78.8519
9/30/2016 9:32	0	0	0	0	0	0	0	0.001	0.0052	42.8112	-78.8519
9/30/2016 9:31	0	0	0	0	0	0	0.052	0	0.0052	42.8112	-78.8519
9/30/2016 9:30	0	0	0	0	0	0	0	0	0.0017	42.8112	-78.8519
9/30/2016 9:29	0	0	0	0	0	0	0	0	0.0017	42.8112	-78.8519
9/30/2016 9:28	0	0	0	0	0	0	0	0	0.0017	42.8112	-78.8519
9/30/2016 9:27	0	0	0	0	0	0	0.025	0	0.0017	42.8112	-78.8519
9/30/2016 9:26	0	0	0	0	0	0	0	0	0	42.8112	-78.8519
9/30/2016 9:25	0	0	0	0	0	0	0.001	0	0.0001	42.8112	-78.8519

COMMUNITY AIR MONITORING

PERIODIC REVIEW REPORT

Tecumseh Phase III Business Park: Sites III-5 & III-6
Lackawanna, New York

Timestamp (GMT-4)	Low (ppm)	Peak (ppm)	STEL (ppm)	TWA (ppm)	VOC (ppm)	VOC (Avg15) (ppm)	Mass Conc. Total (mg/m³)	TWA (mg/m³)	Mass Conc. Total (Avg15) (mg/m³)	Latitude	Longitude
9/30/2016 9:24	0	0	0	0	0	0	0	0	0	42.8112	-78.8519
9/30/2016 9:23	0	0	0	0	0	0	0	0	0	42.8112	-78.8519
9/30/2016 9:22	0	0	0	0	0	0	0	0	0	42.8112	-78.8519
9/30/2016 9:21	0	0	0	0	0	0	0	0	0	42.8112	-78.8519
9/30/2016 9:20	0	0	0	0	0	0	0	0	0	42.8112	-78.8519
9/30/2016 9:19	0	0	0	0	0	0	0	0	0	42.8112	-78.8519
9/30/2016 9:18	0	0	0	0	0	0	0	0	0	42.8112	-78.8519
9/30/2016 9:17	0	0	0	0	0	0	0	0	0	42.8112	-78.8519
9/30/2016 9:16	0	0	0	0	0	0	0	0	0.0004	42.8112	-78.8519
9/30/2016 9:15	0	0	0	0	0	0	-0.001	0	0.0004	42.8112	-78.8519
9/30/2016 9:14	0	0	0	0	0	0	0	0	0.0005	42.8112	-78.8519
9/30/2016 9:13	0	0	0	0	0	0	0	0	0.0005	42.8112	-78.8519
9/30/2016 9:12	0	0	0	0	0	0	0	0	0.0005	42.8112	-78.8519
9/30/2016 9:11	0	0	0	0	0	0	0.001	0	0.0005	42.8113	-78.8519
9/30/2016 9:10	0	0	0	0	0	0	0	0	0.0005	42.8112	-78.8519
9/30/2016 9:09	0	0	0	0	0	0	0	0	0.0005	42.8112	-78.8519
9/30/2016 9:08	0	0	0	0	0	0	0	0	0.0005	42.8112	-78.8519
9/30/2016 9:07	0	0	0	0	0	0	0	0	0.0005	42.8112	-78.8519
9/30/2016 9:06	0	0	0	0	0	0	0	0	0.0005	42.8112	-78.8519
9/30/2016 9:05	0	0	0	0	0	0	0	0	0.0005	42.8112	-78.8519
9/30/2016 9:04	0	0	0	0	0	0	0	0	0.0005	42.8112	-78.8519
9/30/2016 9:03	0	0	0	0	0	0	0	0	0.0005	42.8112	-78.8519
9/30/2016 9:02	0	0	0	0	0	0	0.006	0	0.0005	42.8112	-78.8519
9/30/2016 9:01	0	0	0	0	0	0	0	0	0.0002	42.8112	-78.8519
9/30/2016 9:00	0	0	0	0	0	0	0	0	0.0003	42.8112	-78.8519
9/30/2016 8:59	0	0	0	0	0	0	0	0	0.0005	42.8112	-78.8519
9/30/2016 8:58	0	0	0	0	0	0	0	0	0.0006	42.8112	-78.8519
9/30/2016 8:57	0	0	0	0	0	0	0	0	0.0006	42.8112	-78.8519
9/30/2016 8:56	0	0	0	0	0	0	0.001	0	0.0006	42.8112	-78.8519
9/30/2016 8:55	0	0	0	0	0	0	0	0	0.0005	42.8112	-78.8519
9/30/2016 8:54	0	0	0	0	0	0	0	0	0.0005	42.8112	-78.8519
9/30/2016 8:53	0	0	0	0	0	0	0.001	0	0.0008	42.8112	-78.8519
9/30/2016 8:52	0	0	0	0	0	0	0	0	0.0007	42.8112	-78.8519
9/30/2016 8:51	0	0	0	0	0	0	0	0	0.0008	42.8112	-78.8519
9/30/2016 8:50	0	0	0	0	0	0	0	0	0.0008	42.8112	-78.8519
9/30/2016 8:49	0	0	0	0	0	0	0	0	0.0009	42.8112	-78.8519
9/30/2016 8:48	0	0	0	0	0	0	0	0	0.0009	42.8112	-78.8519
9/30/2016 8:47	0	0	0	0	0	0	0.001	0	0.001	42.8112	-78.8519
9/30/2016 8:46	0	0	0	0	0	0	0.002	0	0.0009	42.8112	-78.8519
9/30/2016 8:45	0	0	0	0	0	0	0.002	0	0.0008	42.8112	-78.8519
9/30/2016 8:44	0	0	0	0	0	0	0.002	0	0.0007	42.8112	-78.8519
9/30/2016 8:43	0	0	0	0	0	0	0	0	0.0005	42.8112	-78.8519
9/30/2016 8:42	0	0	0	0	0	0	0	0	0.0008	42.8112	-78.8519
9/30/2016 8:41	0	0	0	0	0	0	0	0	0.0008	42.8112	-78.8519
9/30/2016 8:40	0	0	0	0	0	0	0	0	0.0008	42.8112	-78.8519
9/30/2016 8:39	0	0	0	0	0	0	0.004	0	0.001	42.8112	-78.8519
9/30/2016 8:38	0	0	0	0	0	0	0	0	0.0007	42.8112	-78.8519
9/30/2016 8:37	0	0	0	0	0	0	0.001	0	0.0008	42.8112	-78.8519
9/30/2016 8:36	0	0	0	0	0	0	0	0	0.0008	42.8112	-78.8519
9/30/2016 8:35	0	0	0	0	0	0	0.001	0	0.0008	42.8112	-78.8519
9/30/2016 8:33											
9/30/2016 8:32	0	0	0	0	0	0	0	0	0.0007	42.8112	-78.8519
9/30/2016 8:31	0	0	0	0	0	0	0.001	0	0.0008	42.8112	-78.8519

COMMUNITY AIR MONITORING

PERIODIC REVIEW REPORT

Tecumseh Phase III Business Park: Sites III-5 & III-6
Lackawanna, New York

Timestamp (GMT-4)	Low (ppm)	Peak (ppm)	STEL (ppm)	TWA (ppm)	VOC (ppm)	VOC (Avg15) (ppm)	Mass Conc. Total (mg/m³)	TWA (mg/m³)	Mass Conc. Total (Avg15) (mg/m³)	Latitude	Longitude
9/30/2016 8:30	0	0	0	0	0	0	0	0	0.0007	42.8112	-78.8519
9/30/2016 8:29	0	0	0	0	0	0	0	0	0.0011	42.8112	-78.8519
9/30/2016 8:28	0	0	0	0	0	0	0.004	0	0.0011	42.8112	-78.8519
9/30/2016 8:27	0	0	0	0	0	0	0	0	0.001	42.8112	-78.8519
9/30/2016 8:26	0	0	0	0	0	0	0	0	0.0013	42.8112	-78.8519
9/30/2016 8:25	0	0	0	0	0	0	0.002	0	0.0017	42.8112	-78.8519
9/30/2016 8:24	0	0	0	0	0	0	0	0	0.0018	42.8112	-78.8519
9/30/2016 8:23	0	0	0	0	0	0	0.001	0	0.0021	42.8112	-78.8519
9/30/2016 8:22	0	0	0	0	0	0	0.001	0	0.0021	42.8112	-78.8519
9/30/2016 8:21	0	0	0	0	0	0	0	0	0.002	42.8112	-78.8519
9/30/2016 8:20	0	0	0	0	0	0	0.001	0	0.002	42.8112	-78.8519
9/30/2016 8:19	0	0	0	0	0	0	0	0	0.0019	42.8112	-78.8519
9/30/2016 8:18	0	0	0	0	0	0	0	0	0.0019	42.8112	-78.8519
9/30/2016 8:17	0	0	0	0	0	0	0.002	0	0.0019	42.8112	-78.8519
9/30/2016 8:16	0	0	0	0	0	0	0	0	0.0019	42.8112	-78.8519
9/30/2016 8:15	0	0	0	0	0	0	0.005	0	0.0019	42.8112	-78.8519
9/30/2016 8:14	0	0	0	0	0	0	0	0	0.0019	42.8112	-78.8519
9/30/2016 8:13	0	0	0	0	0	0	0.003	0	0.0022	42.8112	-78.8519
9/30/2016 8:12	0	0	0	0	0	0	0.004	0	0.0023	42.8112	-78.8519
9/30/2016 8:11	0	0	0	0	0	0	0.006	0	0.0021	42.8112	-78.8519
9/30/2016 8:10	0	0	0	0	0	0	0.004	0	0.003	42.8112	-78.8519
9/30/2016 8:09	0	0	0	0	0	0	0.005	0	0.0027	42.8112	-78.8519
9/30/2016 8:08	0	0	0	0	0	0	0	0	0.0027	42.8112	-78.8519
9/30/2016 8:07	0	0	0	0	0	0	0	0	0.0031	42.8112	-78.8519
9/30/2016 8:06	0	0	0	0	0	0	0	0	0.0032	42.8112	-78.8519
9/30/2016 8:05	0	0	0	0	0	0	0	0	0.0035	42.8112	-78.8519
9/30/2016 8:04	0	0	0	0	0	0	0	0	0.0037	42.8112	-78.8519
9/30/2016 8:03	0	0	0	0	0	0	0	0	0.0037	42.8112	-78.8519
9/30/2016 8:02	0	0	0	0	0	0	0.002	0	0.0037	42.8112	-78.8519
9/30/2016 8:01	0	0	0	0	0	0	0	0	0.0035	42.8112	-78.8519
9/30/2016 8:00	0	0	0	0	0	0	0.005	0	0.0038	42.8112	-78.8519
9/30/2016 7:59	0	0	0	0	0	0	0.004	0	0.0035	42.8112	-78.8519
9/30/2016 7:58	0	0	0	0	0	0	0.004	0	0.0034	42.8112	-78.8519
9/30/2016 7:57	0	0	0	0	0	0	0.001	0	0.0031	42.8112	-78.852
9/30/2016 7:56	0	0	0	0	0	0	0.02	0	0.0031	42.8112	-78.8519
9/30/2016 7:55	0	0	0	0	0	0	0	0	0.0019	42.8112	-78.8519
9/30/2016 7:54	0	0	0	0	0	0	0.005	0	0.0019	42.8112	-78.8519
9/30/2016 7:53	0	0	0	0	0	0	0.006	0	0.0016	42.8112	-78.8519
9/30/2016 7:52	0	0	0	0	0	0	0.001	0	0.0011	42.8112	-78.8519
9/30/2016 7:51	0	0	0	0	0	0	0.004	0	0.0013	42.8112	-78.8519
9/30/2016 7:50	0	0	0	0	0	0	0.003	0	0.001	42.8112	-78.8519
9/30/2016 7:49	0	0	0	0	0	0	0	0	0.0008	42.8112	-78.8519
9/30/2016 7:48	0	0	0	0	0	0	0	0	0.0008	42.8112	-78.8519
9/30/2016 7:47	0	0	0	0	0	0	0	0	0.0009	42.8112	-78.8519
9/30/2016 7:46	0	0	0	0	0	0	0.004	0	0.0009	42.8112	-78.8519
9/30/2016 7:45	0	0	0	0	0	0	0.001	0	0.0006	42.8112	-78.852
9/30/2016 7:44	0	0	0	0	0	0	0.002	0	0.0005	42.8112	-78.8519
9/30/2016 7:43	0	0	0	0	0	0	0	0	0.0004	42.8112	-78.8519
9/30/2016 7:42	0	0	0	0	0	0	0	0	0.0004	42.8112	-78.852
9/30/2016 7:40	0	0	0	0	0	0	0	0	0.0003	42.8112	-78.852
9/30/2016 7:39	0	0	0	0	0	0	0.001	0	0.0003	42.8112	-78.852
9/30/2016 7:38	0	0	0	0	0	0	0	0	0.0002	42.8112	-78.852
9/30/2016 7:37	0	0	0	0	0	0	0.003	0	0.0002	42.8112	-78.852

COMMUNITY AIR MONITORING

PERIODIC REVIEW REPORT

Tecumseh Phase III Business Park: Sites III-5 & III-6
Lackawanna, New York

Timestamp (GMT-4)	Low (ppm)	Peak (ppm)	STEL (ppm)	TWA (ppm)	VOC (ppm)	VOC (Avg15) (ppm)	Mass Conc. Total (mg/m³)	TWA (mg/m³)	Mass Conc. Total (Avg15) (mg/m³)	Latitude	Longitude
9/30/2016 7:36	0	0	0	0	0	0	0	0	0	42.8112	-78.852
9/30/2016 7:35	0	0	0	0	0	0	0	0	0	42.8112	-78.852
9/30/2016 7:34	0	0	0	0	0	0	0	0	0	42.8112	-78.852
9/30/2016 7:33	0	0	0	0	0	0	0.001	0	0	42.8112	-78.852
9/30/2016 7:32	0	0	0	0	0	0	0	0	-0.0001	42.8112	-78.852
9/30/2016 7:31	0	0	0	0	0	0	0	0	-0.0001	42.8112	-78.852
9/30/2016 7:30	0	0	0	0	0	0	0	0	-0.0001	42.8112	-78.852
9/30/2016 7:29	0	0	0	0	0	0	0	0	-0.0001	42.8112	-78.852
9/30/2016 7:28	0	0	0	0	0	0	0.001	0	-0.0001	42.8112	-78.852
9/30/2016 7:27	0	0	0	0	0	0	0	0	-0.0002	42.8112	-78.852
9/30/2016 7:26	0	0	0	0	0	0	-0.001	0	-0.0002	42.8112	-78.852
9/30/2016 7:25	0	0	0	0	0	0	-0.001	0	-0.0001	42.8112	-78.852
9/30/2016 7:24	0	0	0	0	0	0	0	0	0	42.8112	-78.852
9/30/2016 7:23	0	0	0	0	0	0	0	0	0	42.8112	-78.852
9/30/2016 7:22	0	0	0	0	0	0	0	0	0	42.8112	-78.852
9/30/2016 7:21	0	0	0	0	0	0	0	0	0	42.8112	-78.8519
9/30/2016 7:20	0	0	0	0	0	0	0	0	0	42.8112	-78.852
9/30/2016 7:19	0	0	0	0	0	0	0	0	0	42.8112	-78.852
9/30/2016 7:18	0	0	0	0	0	0	0	0	0	42.8112	-78.852
9/30/2016 7:17	0	0	0	0	0	0	0	0	0	42.8112	-78.852
9/30/2016 7:16	0	0	0	0	0	0	0	0	0	42.8112	-78.852
9/30/2016 7:15							0	0	0		
9/29/2016 14:49	0	0	0	0	0	0	0.003	0	0.0018	42.8115	-78.8521
9/29/2016 14:48	0	0	0	0	0	0	0.002	0	0.0017	42.8115	-78.8522
9/29/2016 14:47	0	0	0	0	0	0	0.002	0	0.0016	42.8115	-78.8522
9/29/2016 14:46	0	0	0	0	0	0	0.002	0	0.0015	42.8115	-78.8521
9/29/2016 14:45	0	0	0	0	0	0	0.001	0	0.0014	42.8115	-78.8521
9/29/2016 14:44	0	0	0	0	0	0	0.001	0	0.0013	42.8115	-78.8521
9/29/2016 14:43	0	0	0	0	0	0	0.001	0	0.0015	42.8115	-78.8521
9/29/2016 14:42	0	0	0	0	0	0	0.007	0	0.0014	42.8115	-78.8522
9/29/2016 14:41	0	0	0	0	0	0	0.002	0	0.0009	42.8115	-78.8522
9/29/2016 14:40	0	0	0	0	0	0	0.002	0	0.0009	42.8115	-78.8521
9/29/2016 14:39	0	0	0	0	0	0	0.001	0	0.0008	42.8115	-78.8521
9/29/2016 14:38	0	0	0	0	0	0	0.001	0	0.0007	42.8115	-78.8522
9/29/2016 14:37	0	0	0	0	0	0	0	0	0.0007	42.8115	-78.8521
9/29/2016 14:36	0	0	0	0	0	0	0	0	0.0007	42.8115	-78.8521
9/29/2016 14:35	0	0	0	0	0	0	0.002	0	0.0007	42.8115	-78.8521
9/29/2016 14:34	0	0	0	0	0	0	0.002	0	0.0005	42.8115	-78.8521
9/29/2016 14:33	0	0	0	0	0	0	0	0	0.0004	42.8115	-78.8521
9/29/2016 14:32	0	0	0	0	0	0	0.001	0	0.0004	42.8115	-78.8522
9/29/2016 14:31	0	0	0	0	0	0	0	0	0.0005	42.8115	-78.8521
9/29/2016 14:30	0	0	0	0	0	0	0	0	0.0005	42.8115	-78.8521
9/29/2016 14:29	0	0	0	0	0	0	0.003	0	0.0005	42.8115	-78.8521
9/29/2016 14:28	0	0	0	0	0	0	0	0	0.0003	42.8115	-78.8522
9/29/2016 14:27	0	0	0	0	0	0	0	0	0.0004	42.8115	-78.8522
9/29/2016 14:26	0	0	0	0	0	0	0.002	0	0.0004	42.8115	-78.8521
9/29/2016 14:25	0	0	0	0	0	0	0	0	0.0003	42.8115	-78.8521
9/29/2016 14:24	0	0	0	0	0	0	0	0	0.0003	42.8115	-78.8521
9/29/2016 14:23	0	0	0	0	0	0	0	0	0.0003	42.8115	-78.8521
9/29/2016 14:22	0	0	0	0	0	0	0	0	0.0003	42.8115	-78.8521
9/29/2016 14:21	0	0	0	0	0	0	0	0	0.0003	42.8115	-78.8522
9/29/2016 14:20	0	0	0	0	0	0	0	0	0.0003	42.8115	-78.8521
9/29/2016 14:19	0	0	0	0	0	0	0	0	0.0003	42.8115	-78.8522

COMMUNITY AIR MONITORING

PERIODIC REVIEW REPORT

Tecumseh Phase III Business Park: Sites III-5 & III-6
Lackawanna, New York

Timestamp (GMT-4)	Low (ppm)	Peak (ppm)	STEL (ppm)	TWA (ppm)	VOC (ppm)	VOC (Avg15) (ppm)	Mass Conc. Total (mg/m³)	TWA (mg/m³)	Mass Conc. Total (Avg15) (mg/m³)	Latitude	Longitude
9/29/2016 14:18	0	0	0	0	0	0	0	0	0.0004	42.8115	-78.8522
9/29/2016 14:17	0	0	0	0	0	0	0.002	0	0.0004	42.8115	-78.8522
9/29/2016 14:16	0	0	0	0	0	0	0.001	0	0.0003	42.8115	-78.8522
9/29/2016 14:15	0	0	0	0	0	0	0	0	0.0002	42.8115	-78.8522
9/29/2016 14:14	0	0	0	0	0	0	0	0	0.0002	42.8115	-78.8522
9/29/2016 14:13	0	0	0	0	0	0	0.001	0	0.0002	42.8115	-78.8522
9/29/2016 14:12	0	0	0	0	0	0	0	0	0.0008	42.8115	-78.8522
9/29/2016 14:11	0	0	0	0	0	0	0	0	0.0008	42.8115	-78.8522
9/29/2016 14:10	0	0	0	0	0	0	0	0	0.0008	42.8115	-78.8522
9/29/2016 14:09	0	0	0	0	0	0	0	0	0.0008	42.8115	-78.8522
9/29/2016 14:08	0	0	0	0	0	0	0	0	0.0008	42.8115	-78.8522
9/29/2016 14:07	0	0	0	0	0	0	0	0	0.0008	42.8116	-78.8522
9/29/2016 14:06	0	0	0	0	0	0	0	0	0.0008	42.8115	-78.8522
9/29/2016 14:05	0	0	0	0	0	0	0	0	0.0008	42.8115	-78.8521
9/29/2016 14:04	0	0	0	0	0	0	0.002	0	0.0008	42.8115	-78.8521
9/29/2016 14:03	0	0	0	0	0	0	0	0	0.001	42.8115	-78.8521
9/29/2016 14:02	0	0	0	0	0	0	0	0	0.001	42.8115	-78.8522
9/29/2016 14:01	0	0	0	0	0	0	0	0	0.001	42.8115	-78.8521
9/29/2016 14:00	0	0	0	0	0	0	0	0	0.001	42.8115	-78.8521
9/29/2016 13:59	0	0	0	0	0	0	0	0	0.001	42.8115	-78.8522
9/29/2016 13:58	0	0	0	0	0	0	0.01	0	0.001	42.8115	-78.8522
9/29/2016 13:57	0	0	0	0	0	0	0	0	0	42.8115	-78.8522
9/29/2016 13:56	0	0	0	0	0	0	0	0	0	42.8115	-78.8522
9/29/2016 13:55	0	0	0	0	0	0	0	0	0	42.8115	-78.8522
9/29/2016 13:54	0	0	0	0	0	0	0	0	0	42.8115	-78.8522
9/29/2016 13:53	0	0	0	0	0	0	0	0	0	42.8115	-78.8522
9/29/2016 13:52	0	0	0	0	0	0	0	0	0	42.8115	-78.8522
9/29/2016 13:51	0	0	0	0	0	0	0	0	0	42.8115	-78.8521
9/29/2016 13:50	0	0	0	0	0	0	0	0	0	42.8115	-78.8522
9/29/2016 13:49	0	0	0	0	0	0	0	0	0	42.8115	-78.8522
9/29/2016 13:48	0	0	0	0	0	0	0	0	0	42.8115	-78.8522
9/29/2016 13:47	0	0	0	0	0	0	0	0	0	42.8115	-78.8522
9/29/2016 13:46	0	0	0	0	0	0	0	0	0	42.8115	-78.8522
9/29/2016 13:45	0	0	0	0	0	0	0	0	0	42.8115	-78.8521
9/29/2016 13:44	0	0	0	0	0	0	0	0	0	42.8115	-78.8522
9/29/2016 13:43	0	0	0	0	0	0	0	0	0	42.8115	-78.8522
9/29/2016 13:42	0	0	0	0	0	0	0	0	0	42.8115	-78.8522
9/29/2016 13:41	0	0	0	0	0	0	0	0	0	42.8115	-78.8522
9/29/2016 13:40	0	0	0	0	0	0	0	0	0	42.8115	-78.8522
9/29/2016 13:39	0	0	0	0	0	0	0	0	0	42.8115	-78.8522
9/29/2016 13:38	0	0	0	0	0	0	0	0	0	42.8115	-78.8522
9/29/2016 13:37	0	0	0	0	0	0	0	0	0	42.8115	-78.8522
9/29/2016 13:36	0	0	0	0	0	0	0	0	0	42.8115	-78.8521
9/29/2016 13:35	0	0	0	0	0	0	0	0	0.0002	42.8115	-78.8522
9/29/2016 13:34	0	0	0	0	0	0	0	0	0.0002	42.8115	-78.8522
9/29/2016 13:33	0	0	0	0	0	0	0	0	0.0002	42.8115	-78.8522
9/29/2016 13:32	0	0	0	0	0	0	0	0	0.0004	42.8115	-78.8521
9/29/2016 13:31	0	0	0	0	0	0	0	0	0.0005	42.8115	-78.8522
9/29/2016 13:30	0	0	0	0	0	0	0	0	0.0012	42.8115	-78.8522
9/29/2016 13:29	0	0	0	0	0	0	0	0	0.0013	42.8115	-78.8522
9/29/2016 13:28	0	0	0	0	0	0	0	0	0.0013	42.8115	-78.8522
9/29/2016 13:25	0	0	0	0	0	0	0	0	0.0011	42.8115	-78.8522
9/29/2016 13:24	0	0	0	0	0	0	0	0	0.0011	42.8115	-78.8522

PERIODIC REVIEW REPORT

**Tecumseh Phase III Business Park: Sites III-5 & III-6
Lackawanna, New York**

[illegible]

COMMUNITY AIR MONITORING

PERIODIC REVIEW REPORT

Tecumseh Phase III Business Park: Sites III-5 & III-6
Lackawanna, New York

Timestamp (GMT-4)	Low (ppm)	Peak (ppm)	STEL (ppm)	TWA (ppm)	VOC (ppm)	VOC (Avg15) (ppm)	Mass Conc. Total (mg/m³)	TWA (mg/m³)	Mass Conc. Total (Avg15) (mg/m³)	Latitude	Longitude
9/29/2016 12:26	0	0	0	0	0	0	0	0	0	42.8115	-78.8522
9/29/2016 12:25	0	0	0	0	0	0	0	0	0	42.8115	-78.8522
9/29/2016 12:24	0	0	0	0	0	0	0	0	0	42.8115	-78.8522
9/29/2016 12:23	0	0	0	0	0	0	0	0	0	42.8115	-78.8522
9/29/2016 12:22	0	0	0	0	0	0	0	0	0	42.8115	-78.8522
9/29/2016 12:21	0	0	0	0	0	0	0	0	0	42.8115	-78.8522
9/29/2016 12:20	0	0	0	0	0	0	0	0	0	42.8115	-78.8522
9/29/2016 12:19	0	0	0	0	0	0	0	0	0	42.8115	-78.8521
9/29/2016 12:18	0	0	0	0	0	0	0	0	0	42.8115	-78.8522
9/29/2016 12:17	0	0	0	0	0	0	0	0	0.0001	42.8115	-78.8521
9/29/2016 12:16	0	0	0	0	0	0	0	0	0.0001	42.8115	-78.8521
9/29/2016 12:15	0	0	0	0	0	0	0	0	0.0001	42.8115	-78.8521
9/29/2016 12:14	0	0	0	0	0	0	0	0	0.0003	42.8115	-78.8521
9/29/2016 12:13	0	0	0	0	0	0	0	0	0.0003	42.8115	-78.8521
9/29/2016 12:12	0	0	0	0	0	0	0	0	0.0003	42.8115	-78.8521
9/29/2016 12:11	0	0	0	0	0	0	0	0	0.0003	42.8115	-78.8522
9/29/2016 12:10	0	0	0	0	0	0	0	0	0.0004	42.8115	-78.8521
9/29/2016 12:09	0	0	0	0	0	0	0	0	0.0004	42.8115	-78.8521
9/29/2016 12:08	0	0	0	0	0	0	0	0	0.0004	42.8115	-78.8521
9/29/2016 12:07	0	0	0	0	0	0	0	0	0.0005	42.8115	-78.8521
9/29/2016 12:06	0	0	0	0	0	0	0	0	0.0008	42.8115	-78.8521
9/29/2016 12:05	0	0	0	0	0	0	0	0	0.001	42.8115	-78.8521
9/29/2016 12:04	0	0	0	0	0	0	0	0	0.001	42.8115	-78.8521
9/29/2016 12:03	0	0	0	0	0	0	0.002	0	0.001	42.8115	-78.8521
9/29/2016 12:02	0	0	0	0	0	0	0	0	0.0011	42.8115	-78.8522
9/29/2016 12:01	0	0	0	0	0	0	0	0	0.0011	42.8115	-78.8522
9/29/2016 12:00	0	0	0	0	0	0	0.002	0	0.0011	42.8115	-78.8522
9/29/2016 11:59	0	0	0	0	0	0	0	0	0.001	42.8115	-78.8522
9/29/2016 11:58	0	0	0	0	0	0	0	0	0.001	42.8115	-78.8521
9/29/2016 11:57	0	0	0	0	0	0	0	0	0.001	42.8115	-78.8522
9/29/2016 11:56	0	0	0	0	0	0	0.002	0	0.001	42.8115	-78.8522
9/29/2016 11:55	0	0	0	0	0	0	0	0	0.0009	42.8115	-78.8522
9/29/2016 11:54	0	0	0	0	0	0	0	0	0.0009	42.8115	-78.8522
9/29/2016 11:53	0	0	0	0	0	0	0.001	0	0.0009	42.8115	-78.8522
9/29/2016 11:52	0	0	0	0	0	0	0.005	0	0.0008	42.8115	-78.8522
9/29/2016 11:51	0	0	0	0	0	0	0.003	0	0.0005	42.8115	-78.8521
9/29/2016 11:50	0	0	0	0	0	0	0	0	0.0003	42.8115	-78.8521
9/29/2016 11:49	0	0	0	0	0	0	0	0	0.0003	42.8115	-78.8521
9/29/2016 11:48	0	0	0	0	0	0	0.004	0	0.0003	42.8115	-78.8521
9/29/2016 11:47	0	0	0	0	0	0	0	0	0	42.8115	-78.8522
9/29/2016 11:46	0	0	0	0	0	0	0	0	0.0002	42.8115	-78.8522
9/29/2016 11:45	0	0	0	0	0	0	0	0	0.0002	42.8115	-78.8522
9/29/2016 11:44	0	0	0	0	0	0	0	0	0.0002	42.8115	-78.8522
9/29/2016 11:43	0	0	0	0	0	0	0	0	0.0002	42.8115	-78.8522
9/29/2016 11:42	0	0	0	0	0	0	0	0	0.0002	42.8115	-78.8522
9/29/2016 11:41	0	0	0	0	0	0	0	0	0.0002	42.8115	-78.8521
9/29/2016 11:40	0	0	0	0	0	0	0	0	0.0002	42.8115	-78.8521
9/29/2016 11:39	0	0	0	0	0	0	0	0	0.0003	42.8115	-78.8521
9/29/2016 11:38	0	0	0	0	0	0	0	0	0.0003	42.8115	-78.8521
9/29/2016 11:37	0	0	0	0	0	0	0	0	0.0004	42.8115	-78.8521
9/29/2016 11:36	0	0	0	0	0	0	0	-0.001	0.0004	42.8115	-78.8521
9/29/2016 11:35	0	0	0	0	0	0	0	-0.001	0.0005	42.8115	-78.8521
9/29/2016 11:34	0	0	0	0	0	0	0	-0.001	0.0005	42.8115	-78.8521

COMMUNITY AIR MONITORING

PERIODIC REVIEW REPORT

Tecumseh Phase III Business Park: Sites III-5 & III-6
Lackawanna, New York

Timestamp (GMT-4)	Low (ppm)	Peak (ppm)	STEL (ppm)	TWA (ppm)	VOC (ppm)	VOC (Avg15) (ppm)	Mass Conc. Total (mg/m³)	TWA (mg/m³)	Mass Conc. Total (Avg15) (mg/m³)	Latitude	Longitude
9/29/2016 11:33	0	0	0	0	0	0	0	-0.001	0.0005	42.8115	-78.8522
9/29/2016 11:32	0	0	0	0	0	0	0.003	-0.001	0.0005	42.8115	-78.8522
9/29/2016 11:31	0	0	0	0	0	0	0	-0.001	0.0003	42.8115	-78.8522
9/29/2016 11:30	0	0	0	0	0	0	0	-0.001	0.0003	42.8115	-78.8522
9/29/2016 11:29	0	0	0	0	0	0	0	-0.001	0.0003	42.8115	-78.8522
9/29/2016 11:28	0	0	0	0	0	0	0	-0.001	0.0004	42.8115	-78.8522
9/29/2016 11:27	0	0	0	0	0	0	0	-0.001	0.0004	42.8115	-78.8522
9/29/2016 11:26	0	0	0	0	0	0	0	-0.001	0.0004	42.8115	-78.8521
9/29/2016 11:25	0	0	0	0	0	0	0.001	-0.001	0.0004	42.8115	-78.8521
9/29/2016 11:24	0	0	0	0	0	0	0	-0.001	0.0003	42.8115	-78.8522
9/29/2016 11:23	0	0	0	0	0	0	0.002	-0.001	0.001	42.8115	-78.8522
9/29/2016 11:22	0	0	0	0	0	0	0	-0.001	0.0008	42.8115	-78.8522
9/29/2016 11:21	0	0	0	0	0	0	0.002	-0.001	0.0008	42.8115	-78.8522
9/29/2016 11:20	0	0	0	0	0	0	0	-0.001	0.0007	42.8115	-78.8522
9/29/2016 11:19	0	0	0	0	0	0	0	-0.001	0.0007	42.8115	-78.8522
9/29/2016 11:18	0	0	0	0	0	0	0	-0.001	0.0008	42.8115	-78.8521
9/29/2016 11:17	0	0	0	0	0	0	0	-0.001	0.0008	42.8115	-78.8521
9/29/2016 11:16	0	0	0	0	0	0	0	-0.001	0.0008	42.8115	-78.8521
9/29/2016 11:15	0	0	0	0	0	0	0	-0.001	0.001	42.8115	-78.8521
9/29/2016 11:12	0	0	0	0	0	0	0	-0.001	0.0011	42.8115	-78.8522
9/29/2016 11:11	0	0	0	0	0	0	0	-0.001	0.0011	42.8115	-78.8522
9/29/2016 11:10	0	0	0	0	0	0	0	-0.001	0.0012	42.8115	-78.8521
9/29/2016 11:09	0	0	0	0	0	0	0.009	-0.001	0.0013	42.8115	-78.8522
9/29/2016 11:08	0	0	0	0	0	0	0	-0.001	0.0007	42.8115	-78.8522
9/29/2016 11:07	0	0	0	0	0	0	0	-0.001	0.0007	42.8115	-78.8522
9/29/2016 11:06	0	0	0	0	0	0	0	-0.001	0.0007	42.8115	-78.8521
9/29/2016 11:05	0	0	0	0	0	0	0	-0.001	0.0007	42.8115	-78.8521
9/29/2016 11:04	0	0	0	0	0	0	0.001	-0.001	0.0007	42.8115	-78.8522
9/29/2016 11:03	0	0	0	0	0	0	0	-0.001	0.0006	42.8115	-78.8521
9/29/2016 11:02	0	0	0	0	0	0	0	-0.001	0.0006	42.8115	-78.8521
9/29/2016 11:01	0	0	0	0	0	0	0.003	-0.001	0.0006	42.8115	-78.8521
9/29/2016 11:00	0	0	0	0	0	0	0.002	-0.001	0.0004	42.8115	-78.8521
9/29/2016 10:59	0	0	0	0	0	0	0	-0.001	0.0003	42.8115	-78.8521
9/29/2016 10:58	0	0	0	0	0	0	0.001	-0.001	0.0003	42.8115	-78.8522
9/29/2016 10:57	0	0	0	0	0	0	0	-0.001	0.0005	42.8115	-78.8522
9/29/2016 10:56	0	0	0	0	0	0	0.002	-0.001	0.0005	42.8115	-78.8522
9/29/2016 10:55	0	0	0	0	0	0	0.001	-0.001	0.0003	42.8115	-78.8522
9/29/2016 10:54	0	0	0	0	0	0	0	-0.001	0.0003	42.8115	-78.8521
9/29/2016 10:53	0	0	0	0	0	0	0	-0.001	0.0005	42.8115	-78.8521
9/29/2016 10:52	0	0	0	0	0	0	0	-0.001	0.0005	42.8115	-78.8521
9/29/2016 10:51	0	0	0	0	0	0	0	-0.001	0.0005	42.8115	-78.8522
9/29/2016 10:50	0	0	0	0	0	0	0	-0.001	0.0005	42.8115	-78.8522
9/29/2016 10:49	0	0	0	0	0	0	0	-0.001	0.0005	42.8115	-78.8522
9/29/2016 10:48	0	0	0	0	0	0	0	-0.001	0.0005	42.8115	-78.8522
9/29/2016 10:47	0	0	0	0	0	0	0	-0.001	0.0005	42.8115	-78.8522
9/29/2016 10:46	0	0	0	0	0	0	0	-0.001	0.0007	42.8115	-78.8521
9/29/2016 10:45	0	0	0	0	0	0	0	-0.001	0.0007	42.8115	-78.8521
9/29/2016 10:44	0	0	0	0	0	0	0	-0.001	0.0007	42.8115	-78.8521
9/29/2016 10:43	0	0	0	0	0	0	0.004	-0.001	0.0007	42.8115	-78.8521
9/29/2016 10:42	0	0	0	0	0	0	0	-0.001	0.0012	42.8115	-78.8522
9/29/2016 10:41	0	0	0	0	0	0	0	-0.001	0.0011	42.8115	-78.8522
9/29/2016 10:40	0	0	0	0	0	0	0.001	-0.001	0.0011	42.8115	-78.8522
9/29/2016 10:39	0	0	0	0	0	0	0.002	-0.001	0.001	42.8115	-78.8521

COMMUNITY AIR MONITORING

PERIODIC REVIEW REPORT

Tecumseh Phase III Business Park: Sites III-5 & III-6
Lackawanna, New York

Timestamp (GMT-4)	Low (ppm)	Peak (ppm)	STEL (ppm)	TWA (ppm)	VOC (ppm)	VOC (Avg15) (ppm)	Mass Conc. Total (mg/m³)	TWA (mg/m³)	Mass Conc. Total (Avg15) (mg/m³)	Latitude	Longitude
9/29/2016 10:38	0	0	0	0	0	0	0	-0.001	0.0008	42.8115	-78.8521
9/29/2016 10:37	0	0	0	0	0	0	0	-0.001	0.0008	42.8115	-78.8521
9/29/2016 10:36	0	0	0	0	0	0	0	-0.001	0.0008	42.8115	-78.8521
9/29/2016 10:35	0	0	0	0	0	0	0	-0.001	0.0008	42.8115	-78.8521
9/29/2016 10:34	0	0	0	0	0	0	0	-0.001	0.0008	42.8115	-78.8521
9/29/2016 10:33	0	0	0	0	0	0	0	-0.001	0.0008	42.8115	-78.8521
9/29/2016 10:32	0	0	0	0	0	0	0.004	-0.001	0.0008	42.8115	-78.8521
9/29/2016 10:31	0	0	0	0	0	0	0	-0.001	0.0005	42.8115	-78.8521
9/29/2016 10:30	0	0	0	0	0	0	0	-0.001	0.0005	42.8115	-78.8521
9/29/2016 10:29	0	0	0	0	0	0	-0.001	-0.001	0.0005	42.8115	-78.8521
9/29/2016 10:28	0	0	0	0	0	0	0.012	-0.001	0.0005	42.8115	-78.8522
9/29/2016 10:27	0	0	0	0	0	0	-0.001	-0.001	-0.0003	42.8115	-78.8522
9/29/2016 10:26	0	0	0	0	0	0	-0.001	-0.001	0.0002	42.8115	-78.8521
9/29/2016 10:25	0	0	0	0	0	0	0	-0.001	0.0002	42.8115	-78.8522
9/29/2016 10:24	0	0	0	0	0	0	-0.001	-0.001	0.0001	42.8115	-78.8521
9/29/2016 10:23	0	0	0	0	0	0	0	-0.001	0.0007	42.8115	-78.8522
9/29/2016 10:22	0	0	0	0	0	0	0	-0.001	0.0007	42.8115	-78.8522
9/29/2016 10:21	0	0	0	0	0	0	0	-0.001	0.0006	42.8115	-78.8522
9/29/2016 10:20	0	0	0	0	0	0	0	-0.001	0.0005	42.8115	-78.8522
9/29/2016 10:19	0	0	0	0	0	0	0	-0.001	0.0004	42.8115	-78.8521
9/29/2016 10:18	0	0	0	0	0	0	0	-0.001	0.0004	42.8115	-78.8521
9/29/2016 10:17	0	0	0	0	0	0	0	-0.001	0.0004	42.8115	-78.8521
9/29/2016 10:16	0	0	0	0	0	0	-0.001	-0.001	0.0004	42.8115	-78.8521
9/29/2016 10:15	0	0	0	0	0	0	0	-0.001	0.0005	42.8115	-78.8521
9/29/2016 10:14	0	0	0	0	0	0	0	-0.001	0.0005	42.8115	-78.8522
9/29/2016 10:13	0	0	0	0	0	0	-0.001	-0.001	0.0005	42.8115	-78.8522
9/29/2016 10:12	0	0	0	0	0	0	0.007	-0.001	0.0016	42.8115	-78.8522
9/29/2016 10:11	0	0	0	0	0	0	-0.001	-0.001	0.0011	42.8115	-78.8522
9/29/2016 10:10	0	0	0	0	0	0	-0.002	-0.001	0.0012	42.8115	-78.8522
9/29/2016 10:09	0	0	0	0	0	0	0.009	-0.001	0.0013	42.8115	-78.8521
9/29/2016 10:08	0	0	0	0	0	0	-0.001	-0.001	0.0007	42.8115	-78.8521
9/29/2016 10:07	0	0	0	0	0	0	-0.001	-0.001	0.0008	42.8115	-78.8521
9/29/2016 10:06	0	0	0	0	0	0	-0.002	-0.001	0.0009	42.8115	-78.8521
9/29/2016 10:05	0	0	0	0	0	0	-0.001	-0.001	0.001	42.8115	-78.8521
9/29/2016 10:04	0	0	0	0	0	0	0	-0.001	0.001	42.8115	-78.8521
9/29/2016 10:03	0	0	0	0	0	0	0	-0.001	0.0009	42.8115	-78.8521
9/29/2016 10:02	0	0	0	0	0	0	0	-0.001	0.0009	42.8115	-78.8521
9/29/2016 10:01	0	0	0	0	0	0	0	-0.001	0.0009	42.8115	-78.8521
9/29/2016 10:00	0	0	0	0	0	0	0	-0.001	0.0009	42.8115	-78.8521
9/29/2016 9:59	0	0	0	0	0	0	0	-0.001	0.0007	42.8115	-78.8521
9/29/2016 9:58	0	0	0	0	0	0	0.016	-0.001	0.0007	42.8115	-78.8521
9/29/2016 9:57	0	0	0	0	0	0	0	-0.001	-0.0005	42.8115	-78.8521
9/29/2016 9:56	0	0	0	0	0	0	0	-0.001	-0.0006	42.8115	-78.8521
9/29/2016 9:55	0	0	0	0	0	0	0	-0.001	-0.0007	42.8115	-78.8521
9/29/2016 9:54	0	0	0	0	0	0	0	-0.001	-0.0007	42.8115	-78.8521
9/29/2016 9:53	0	0	0	0	0	0	0	-0.001	-0.0009	42.8115	-78.8521
9/29/2016 9:52	0	0	0	0	0	0	0	-0.001	-0.0009	42.8115	-78.8521
9/29/2016 9:51	0	0	0	0	0	0	0	-0.001	-0.0009	42.8115	-78.8521
9/29/2016 9:50	0	0	0	0	0	0	-0.001	-0.001	-0.0011	42.8115	-78.8521
9/29/2016 9:49	0	0	0	0	0	0	-0.002	-0.001	-0.0011	42.8115	-78.8521
9/29/2016 9:48	0	0	0	0	0	0	0	-0.001	-0.0012	42.8115	-78.8521
9/29/2016 9:47	0	0	0	0	0	0	0	-0.001	-0.0014	42.8115	-78.8521
9/29/2016 9:46	0	0	0	0	0	0	0	-0.001	-0.0015	42.8115	-78.8521

COMMUNITY AIR MONITORING

PERIODIC REVIEW REPORT

Tecumseh Phase III Business Park: Sites III-5 & III-6
Lackawanna, New York

Timestamp (GMT-4)	Low (ppm)	Peak (ppm)	STEL (ppm)	TWA (ppm)	VOC (ppm)	VOC (Avg15) (ppm)	Mass Conc. Total (mg/m³)	TWA (mg/m³)	Mass Conc. Total (Avg15) (mg/m³)	Latitude	Longitude
9/29/2016 9:45	0	0	0	0	0	0	-0.002	-0.001	-0.0017	42.8115	-78.8521
9/29/2016 9:44	0	0	0	0	0	0	-0.001	-0.001	-0.0017	42.8115	-78.8521
9/29/2016 9:43	0	0	0	0	0	0	-0.002	-0.001	-0.0017	42.8115	-78.8521
9/29/2016 9:42	0	0	0	0	0	0	-0.001	-0.001	-0.0017	42.8115	-78.8522
9/29/2016 9:41	0	0	0	0	0	0	-0.001	-0.001	-0.0018	42.8115	-78.8522
9/29/2016 9:40	0	0	0	0	0	0	-0.001	-0.001	-0.0018	42.8115	-78.8522
9/29/2016 9:39	0	0	0	0	0	0	-0.002	-0.001	-0.002	42.8115	-78.8522
9/29/2016 9:38	0	0	0	0	0	0	-0.001	-0.001	-0.002	42.8115	-78.8521
9/29/2016 9:37	0	0	0	0	0	0	0	-0.001	-0.0021	42.8115	-78.8522
9/29/2016 9:36	0	0	0	0	0	0	-0.002	-0.001	-0.0023	42.8115	-78.8522
9/29/2016 9:35	0	0	0	0	0	0	-0.002	-0.001	-0.0024	42.8115	-78.8522
9/29/2016 9:34	0	0	0	0	0	0	-0.003	-0.001	-0.0023	42.8115	-78.8522
9/29/2016 9:33	0	0	0	0	0	0	-0.003	-0.001	-0.0023	42.8115	-78.8522
9/29/2016 9:32	0	0	0	0	0	0	-0.001	-0.001	-0.0022	42.8115	-78.8522
9/29/2016 9:31	0	0	0	0	0	0	-0.003	-0.001	-0.0023	42.8115	-78.8522
9/29/2016 9:30	0	0	0	0	0	0	-0.003	-0.001	-0.0023	42.8115	-78.8522
9/29/2016 9:29	0	0	0	0	0	0	-0.001	-0.001	-0.0023	42.8115	-78.8522
9/29/2016 9:25	0	0	0	0	0	0	-0.003	-0.001	-0.0025	42.8115	-78.8522
9/29/2016 9:24	0	0	0	0	0	0	-0.002	-0.001	-0.0024	42.8115	-78.8522
9/29/2016 9:23	0	0	0	0	0	0	-0.002	-0.001	-0.0023	42.8115	-78.8522
9/29/2016 9:22	0	0	0	0	0	0	-0.003	-0.001	-0.0023	42.8115	-78.8522
9/29/2016 9:21	0	0	0	0	0	0	-0.003	-0.001	-0.0024	42.8115	-78.8521
9/29/2016 9:20	0	0	0	0	0	0	0	-0.001	-0.0024	42.8115	-78.8522
9/29/2016 9:19	0	0	0	0	0	0	-0.003	-0.001	-0.0026	42.8115	-78.8521
9/29/2016 9:18	0	0	0	0	0	0	-0.002	-0.001	-0.0025	42.8115	-78.8521
9/29/2016 9:17	0	0	0	0	0	0	-0.003	-0.001	-0.0026	42.8115	-78.8521
9/29/2016 9:16	0	0	0	0	0	0	-0.003	-0.001	-0.0027	42.8115	-78.8522
9/29/2016 9:15	0	0	0	0	0	0	-0.003	-0.001	-0.0027	42.8115	-78.8522
9/29/2016 9:14	0	0	0	0	0	0	-0.003	-0.001	-0.0026	42.8115	-78.8522
9/29/2016 9:13	0	0	0	0	0	0	-0.002	-0.001	-0.0026	42.8116	-78.8522
9/29/2016 9:12	0	0	0	0	0	0	-0.003	-0.001	-0.0025	42.8115	-78.8522
9/29/2016 9:11	0	0	0	0	0	0	-0.003	-0.001	-0.0015	42.8115	-78.8522
9/29/2016 9:10	0	0	0	0	0	0	-0.001	-0.001	-0.0013	42.8115	-78.8522
9/29/2016 9:09	0	0	0	0	0	0	0	-0.001	-0.0015	42.8115	-78.8522
9/29/2016 9:08	0	0	0	0	0	0	-0.003	-0.001	-0.0015	42.8115	-78.8522
9/29/2016 9:07	0	0	0	0	0	0	-0.004	-0.001	-0.0015	42.8115	-78.8522
9/29/2016 9:06	0	0	0	0	0	0	-0.003	-0.001	-0.0014	42.8115	-78.8521
9/29/2016 9:05	0	0	0	0	0	0	-0.003	-0.001	-0.0013	42.8115	-78.8522
9/29/2016 9:04	0	0	0	0	0	0	-0.001	-0.001	-0.0013	42.8115	-78.8521
9/29/2016 9:03	0	0	0	0	0	0	-0.004	-0.001	-0.0013	42.8115	-78.8521
9/29/2016 9:02	0	0	0	0	0	0	-0.004	-0.001	-0.0013	42.8115	-78.8521
9/29/2016 9:01	0	0	0	0	0	0	-0.003	-0.001	-0.0012	42.8115	-78.8522
9/29/2016 9:00	0	0	0	0	0	0	-0.002	-0.001	-0.0012	42.8115	-78.8522
9/29/2016 8:59	0	0	0	0	0	0	-0.003	-0.001	-0.0013	42.8115	-78.8521
9/29/2016 8:58	0	0	0	0	0	0	0	-0.001	-0.0013	42.8115	-78.8522
9/29/2016 8:57	0	0	0	0	0	0	0.011	-0.001	-0.0014	42.8115	-78.8522
9/29/2016 8:56	0	0	0	0	0	0	0	-0.001	-0.0024	42.8115	-78.8522
9/29/2016 8:55	0	0	0	0	0	0	-0.003	-0.001	-0.0026	42.8115	-78.8522
9/29/2016 8:54	0	0	0	0	0	0	-0.001	-0.001	-0.0027	42.8115	-78.8522
9/29/2016 8:53	0	0	0	0	0	0	-0.002	-0.001	-0.0029	42.8115	-78.8522
9/29/2016 8:52	0	0	0	0	0	0	-0.003	-0.001	-0.0029	42.8115	-78.8522
9/29/2016 8:51	0	0	0	0	0	0	-0.001	-0.001	-0.0029	42.8115	-78.8522
9/29/2016 8:50	0	0	0	0	0	0	-0.003	-0.001	-0.0031	42.8115	-78.8522

COMMUNITY AIR MONITORING

PERIODIC REVIEW REPORT

Tecumseh Phase III Business Park: Sites III-5 & III-6
Lackawanna, New York

Timestamp (GMT-4)	Low (ppm)	Peak (ppm)	STEL (ppm)	TWA (ppm)	VOC (ppm)	VOC (Avg15) (ppm)	Mass Conc. Total (mg/m³)	TWA (mg/m³)	Mass Conc. Total (Avg15) (mg/m³)	Latitude	Longitude
9/29/2016 8:49	0	0	0	0	0	0	-0.002	-0.001	-0.0031	42.8115	-78.8522
9/29/2016 8:48	0	0	0	0	0	0	-0.003	-0.001	-0.0033	42.8115	-78.8522
9/29/2016 8:47	0	0	0	0	0	0	-0.003	-0.001	-0.0031	42.8115	-78.8522
9/29/2016 8:46	0	0	0	0	0	0	-0.003	-0.001	-0.003	42.8115	-78.8522
9/29/2016 8:45	0	0	0	0	0	0	-0.003	-0.001	-0.0029	42.8115	-78.8522
9/29/2016 8:44	0	0	0	0	0	0	-0.003	-0.001	-0.0029	42.8115	-78.8522
9/29/2016 8:43	0	0	0	0	0	0	-0.002	-0.001	-0.0027	42.8115	-78.8522
9/29/2016 8:42	0	0	0	0	0	0	-0.004	-0.001	-0.0029	42.8115	-78.8522
9/29/2016 8:41	0	0	0	0	0	0	-0.003	-0.001	-0.0031	42.8115	-78.8522
9/29/2016 8:40	0	0	0	0	0	0	-0.004	-0.001	-0.0032	42.8115	-78.8522
9/29/2016 8:39	0	0	0	0	0	0	-0.004	-0.001	-0.0033	42.8115	-78.8522
9/29/2016 8:38	0	0	0	0	0	0	-0.002	-0.001	-0.0033	42.8115	-78.8522
9/29/2016 8:37	0	0	0	0	0	0	-0.003	-0.001	-0.0035	42.8115	-78.8522
9/29/2016 8:36	0	0	0	0	0	0	-0.004	-0.001	-0.0037	42.8115	-78.8522
9/29/2016 8:35	0	0	0	0	0	0	-0.004	-0.001	-0.0037	42.8115	-78.8522
9/29/2016 8:34	0	0	0	0	0	0	-0.004	-0.001	-0.0037	42.8115	-78.8522
9/29/2016 8:33	0	0	0	0	0	0	0	-0.001	-0.0037	42.8115	-78.8522
9/29/2016 8:32	0	0	0	0	0	0	-0.002	-0.001	-0.004	42.8115	-78.8522
9/29/2016 8:31	0	0	0	0	0	0	-0.001	-0.001	-0.0042	42.8115	-78.8522
9/29/2016 8:30	0	0	0	0	0	0	-0.004	-0.001	-0.0042	42.8115	-78.8522
9/29/2016 8:29	0	0	0	0	0	0	0	-0.001	-0.0039	42.8115	-78.8522
9/29/2016 8:28	0	0	0	0	0	0	-0.005	0	-0.0039	42.8115	-78.8522
9/29/2016 8:27	0	0	0	0	0	0	-0.006	0	-0.0039	42.8115	-78.8522
9/29/2016 8:26	0	0	0	0	0	0	-0.005	0	-0.0039	42.8115	-78.8522
9/29/2016 8:25	0	0	0	0	0	0	-0.005	0	-0.0039	42.8115	-78.8522
9/29/2016 8:24	0	0	0	0	0	0	-0.005	0	-0.0038	42.8115	-78.8522
9/29/2016 8:23	0	0	0	0	0	0	-0.005	0	-0.0036	42.8115	-78.8522
9/29/2016 8:22	0	0	0	0	0	0	-0.005	0	-0.0036	42.8115	-78.8522
9/29/2016 8:21	0	0	0	0	0	0	-0.004	0	-0.0036	42.8115	-78.8522
9/29/2016 8:20	0	0	0	0	0	0	-0.004	0	-0.0037	42.8115	-78.8522
9/29/2016 8:19	0	0	0	0	0	0	-0.004	0	-0.0038	42.8115	-78.8522
9/29/2016 8:18	0	0	0	0	0	0	-0.005	0	-0.0039	42.8115	-78.8522
9/29/2016 8:17	0	0	0	0	0	0	-0.005	0	-0.0039	42.8115	-78.8522
9/29/2016 8:16	0	0	0	0	0	0	-0.001	0	-0.0039	42.8115	-78.8522
9/29/2016 8:15	0	0	0	0	0	0	0	0	-0.0043	42.8115	-78.8522
9/29/2016 8:14	0	0	0	0	0	0	0	0	-0.0047	42.8115	-78.8522
9/29/2016 8:13	0	0	0	0	0	0	-0.005	0	-0.0051	42.8115	-78.8522
9/29/2016 8:12	0	0	0	0	0	0	-0.005	0	-0.0051	42.8115	-78.8522
9/29/2016 8:11	0	0	0	0	0	0	-0.005	0	-0.0051	42.8115	-78.8522
9/29/2016 8:10	0	0	0	0	0	0	-0.004	0	-0.0052	42.8115	-78.8522
9/29/2016 8:09	0	0	0	0	0	0	-0.002	0	-0.0053	42.8115	-78.8522
9/29/2016 8:08	0	0	0	0	0	0	-0.005	0	-0.0055	42.8115	-78.8522
9/29/2016 8:07	0	0	0	0	0	0	-0.005	0	-0.0055	42.8115	-78.8522
9/29/2016 8:06	0	0	0	0	0	0	-0.006	0	-0.0053	42.8115	-78.8522
9/29/2016 8:05	0	0	0	0	0	0	-0.005	0	-0.0053	42.8115	-78.8522
9/29/2016 8:04	0	0	0	0	0	0	-0.006	0	-0.0053	42.8115	-78.8522
9/29/2016 8:03	0	0	0	0	0	0	-0.005	0	-0.0053	42.8115	-78.8522
9/29/2016 8:02	0	0	0	0	0	0	-0.005	0	-0.0054	42.8115	-78.8522
9/29/2016 8:01	0	0	0	0	0	0	-0.006	0	-0.0054	42.8115	-78.8522
9/29/2016 8:00	0	0	0	0	0	0	-0.006	0	-0.0054	42.8115	-78.8522
9/29/2016 7:59	0	0	0	0	0	0	-0.006	0	-0.0055	42.8115	-78.8522
9/29/2016 7:58	0	0	0	0	0	0	-0.006	0	-0.0055	42.8115	-78.8522
9/29/2016 7:57	0	0	0	0	0	0	-0.005	0	-0.0055	42.8115	-78.8522

COMMUNITY AIR MONITORING

PERIODIC REVIEW REPORT

Tecumseh Phase III Business Park: Sites III-5 & III-6
Lackawanna, New York

Timestamp (GMT-4)	Low (ppm)	Peak (ppm)	STEL (ppm)	TWA (ppm)	VOC (ppm)	VOC (Avg15) (ppm)	Mass Conc. Total (mg/m³)	TWA (mg/m³)	Mass Conc. Total (Avg15) (mg/m³)	Latitude	Longitude
9/29/2016 7:56	0	0	0	0	0	0	-0.006	0	-0.0056	42.8115	-78.8522
9/29/2016 7:55	0	0	0	0	0	0	-0.006	0	-0.0055	42.8115	-78.8522
9/29/2016 7:54	0	0	0	0	0	0	-0.005	0	-0.0055	42.8115	-78.8522
9/29/2016 7:53	0	0	0	0	0	0	-0.005	0	-0.0055	42.8115	-78.8522
9/29/2016 7:52	0	0	0	0	0	0	-0.002	0	-0.0054	42.8115	-78.8522
9/29/2016 7:51	0	0	0	0	0	0	-0.005	0	-0.0055	42.8115	-78.8522
9/29/2016 7:50	0	0	0	0	0	0	-0.006	0	-0.0051	42.8115	-78.8522
9/29/2016 7:49	0	0	0	0	0	0	-0.006	0	-0.0049	42.8115	-78.8522
9/29/2016 7:48	0	0	0	0	0	0	-0.006	0	-0.0048	42.8115	-78.8522
9/29/2016 7:47	0	0	0	0	0	0	-0.005	0	-0.0048	42.8115	-78.8522
9/29/2016 7:46	0	0	0	0	0	0	-0.006	0	-0.0049	42.8115	-78.8522
9/29/2016 7:45	0	0	0	0	0	0	-0.007	0	-0.0048	42.8115	-78.8522
9/29/2016 7:44	0	0	0	0	0	0	-0.006	0	-0.0048	42.8115	-78.8522
9/29/2016 7:43	0	0	0	0	0	0	-0.006	0	-0.0045	42.8115	-78.8522
9/29/2016 7:42	0	0	0	0	0	0	-0.007	0	-0.0045	42.8115	-78.8522
9/29/2016 7:41	0	0	0	0	0	0	-0.005	0	-0.0045	42.8115	-78.8522
9/29/2016 7:38							-0.003	0	-0.0045	42.8115	-78.8522
9/29/2016 7:37	0	0	0	0	0	0	-0.003	0	-0.0048	42.8115	-78.8522
9/29/2016 7:36	0	0	0	0	0	0	0	0	-0.0049	42.8115	-78.8522
9/29/2016 7:35	0	0	0	0	0	0	-0.004	0	-0.0053	42.8115	-78.8522
9/29/2016 7:34	0	0	0	0	0	0	-0.004	0	-0.0054	42.8115	-78.8522
9/29/2016 7:33	0	0	0	0	0	0	-0.007	0	-0.0055	42.8115	-78.8522
9/29/2016 7:32	0	0	0	0	0	0	-0.006	0	-0.0054	42.8115	-78.8522
9/29/2016 7:31	0	0	0	0	0	0	-0.005	0	-0.0053	42.8115	-78.8522
9/29/2016 7:30	0	0	0	0	0	0	-0.006	0	-0.0054	42.8115	-78.8522
9/29/2016 7:29	0	0	0	0	0	0	-0.002	0	-0.0053	42.8115	-78.8522
9/29/2016 7:28	0	0	0	0	0	0	-0.007	0	-0.0058	42.8115	-78.8522
9/29/2016 7:27	0	0	0	0	0	0	-0.007	0	-0.0056	42.8115	-78.8522
9/29/2016 7:26	0	0	0	0	0	0	-0.007	0	-0.0053	42.8115	-78.8522
9/29/2016 7:25	0	0	0	0	0	0	-0.007	0	-0.0047	42.8115	-78.8522
9/29/2016 7:24	0	0	0	0	0	0	0	0	-0.0035	42.8115	-78.8522
9/29/2016 7:23	0	0	0	0	0	0	-0.007	0	-0.007	42.8115	-78.8522
9/28/2016 13:49										42.8112	-78.8504
9/28/2016 13:48	0	0	0	0	0	0	0.012	0.002	0.001	42.8112	-78.8503
9/28/2016 13:47	0	0	0	0	0	0	0	0.002	0.0001	42.8112	-78.8503
9/28/2016 13:46	0	0	0	0	0	0	-0.001	0.002	0.0001	42.8112	-78.8503
9/28/2016 13:45	0	0	0	0	0	0	-0.001	0.002	0.0002	42.8112	-78.8503
9/28/2016 13:44	0	0	0	0	0	0	0	0.002	0.0004	42.8112	-78.8504
9/28/2016 13:43	0	0	0	0	0	0	0.001	0.002	0.0004	42.8112	-78.8504
9/28/2016 13:42	0	0	0	0	0	0	0	0.002	0.0003	42.8112	-78.8504
9/28/2016 13:41	0	0	0	0	0	0	-0.001	0.002	0.0003	42.8112	-78.8504
9/28/2016 13:40	0	0	0	0	0	0	0.003	0.002	0.0004	42.8111	-78.8503
9/28/2016 13:39	0	0	0	0	0	0				42.8112	-78.8503
9/28/2016 13:38	0	0	0	0	0	0	0.001	0.002	0.0001	42.8112	-78.8504
9/28/2016 13:37	0	0	0	0	0	0	0	0.002	0.0001	42.8111	-78.8503
9/28/2016 13:36	0	0	0	0	0	0	0	0.002	0.0005	42.8111	-78.8503
9/28/2016 13:35	0	0	0	0	0	0	0	0.002	0.0005	42.8111	-78.8503
9/28/2016 13:34	0	0	0	0	0	0	0	0.002	0.0004	42.8111	-78.8503
9/28/2016 13:33	0	0	0	0	0	0	0	0.002	0.0003	42.8111	-78.8503
9/28/2016 13:32	0	0	0	0	0	0	0	0.002	0.0003	42.8112	-78.8503
9/28/2016 13:31	0	0	0	0	0	0	0	0.002	0.0003	42.8111	-78.8503
9/28/2016 13:30	0	0	0	0	0	0	0.001	0.002	0.0003	42.8111	-78.8503
9/28/2016 13:29	0	0	0	0	0	0	0	0.002	0.0003	42.8112	-78.8503

COMMUNITY AIR MONITORING

PERIODIC REVIEW REPORT

Tecumseh Phase III Business Park: Sites III-5 & III-6
Lackawanna, New York

Timestamp (GMT-4)	Low (ppm)	Peak (ppm)	STEL (ppm)	TWA (ppm)	VOC (ppm)	VOC (Avg15) (ppm)	Mass Conc. Total (mg/m³)	TWA (mg/m³)	Mass Conc. Total (Avg15) (mg/m³)	Latitude	Longitude
9/28/2016 13:28	0	0	0	0	0	0	0	0.002	0.0003	42.8111	-78.8503
9/28/2016 13:27	0	0	0	0	0	0	0	0.002	0.0007	42.8111	-78.8503
9/28/2016 13:26	0	0	0	0	0	0	0	0.002	0.0007	42.8111	-78.8503
9/28/2016 13:25	0	0	0	0	0	0	-0.001	0.002	0.0007	42.8111	-78.8503
9/28/2016 13:24	0	0	0	0	0	0	0.001	0.002	0.0007	42.8112	-78.8503
9/28/2016 13:23	0	0	0	0	0	0	0	0.002	0.0005	42.8112	-78.8503
9/28/2016 13:22	0	0	0	0	0	0	0.007	0.002	0.0005	42.8111	-78.8503
9/28/2016 13:21	0	0	0	0	0	0	-0.001	0.002	0.0001	42.8111	-78.8503
9/28/2016 13:20	0	0	0	0	0	0	-0.001	0.002	0.0001	42.8111	-78.8503
9/28/2016 13:19	0	0	0	0	0	0	-0.001	0.002	0.0017	42.8112	-78.8503
9/28/2016 13:18	0	0	0	0	0	0	0	0.002	0.0021	42.8111	-78.8503
9/28/2016 13:17	0	0	0	0	0	0	-0.001	0.002	0.0021	42.8111	-78.8503
9/28/2016 13:16	0	0	0	0	0	0	0	0.002	0.002	42.8112	-78.8503
9/28/2016 13:15	0	0	0	0	0	0	0.001	0.002	0.0019	42.8111	-78.8503
9/28/2016 13:14							0	0.002	0.0017		
9/28/2016 13:13	0	0	0	0	0	0	0.006	0.002	0.0017	42.8112	-78.8503
9/28/2016 13:12	0	0	0	0	0	0	0	0.002	0.0013	42.8112	-78.8503
9/28/2016 13:11	0	0	0	0	0	0	0	0.002	0.0013	42.8111	-78.8503
9/28/2016 13:10	0	0	0	0	0	0	0	0.002	0.0013	42.8112	-78.8503
9/28/2016 13:09	0	0	0	0	0	0	-0.002	0.002	0.0014	42.8111	-78.8503
9/28/2016 13:08	0	0	0	0	0	0	0	0.002	0.0015	42.8111	-78.8503
9/28/2016 13:07	0	0	0	0	0	0	0	0.002	0.0045	42.8112	-78.8503
9/28/2016 13:06	0	0	0	0	0	0	0	0.002	0.0044	42.8111	-78.8503
9/28/2016 13:05	0	0	0	0	0	0	0.023	0.002	0.0043	42.8111	-78.8503
9/28/2016 13:04	0	0	0	0	0	0	0.004	0.002	0.0027	42.8111	-78.8503
9/28/2016 13:03	0	0	0	0	0	0	0	0.002	0.0025	42.8111	-78.8503
9/28/2016 13:02	0	0	0	0	0	0	-0.002	0.002	0.0024	42.8111	-78.8503
9/28/2016 13:01	0	0	0	0	0	0	-0.002	0.002	0.0024	42.8111	-78.8503
9/28/2016 13:00	0	0	0	0	0	0	-0.002	0.002	0.0025	42.8111	-78.8503
9/28/2016 12:59	0	0	0	0	0	0	0	0.002	0.0026	42.8111	-78.8503
9/28/2016 12:58	0	0	0	0	0	0	0	0.002	0.0026	42.8111	-78.8503
9/28/2016 12:57	0	0	0	0	0	0	0	0.002	0.0025	42.8111	-78.8503
9/28/2016 12:56	0	0	0	0	0	0	0	0.002	0.0025	42.8111	-78.8503
9/28/2016 12:55	0	0	0	0	0	0	0.002	0.002	0.0031	42.8111	-78.8503
9/28/2016 12:54	0	0	0	0	0	0	-0.001	0.002	0.0039	42.8111	-78.8503
9/28/2016 12:53	0	0	0	0	0	0	0.046	0.002	0.0038	42.8111	-78.8503
9/28/2016 12:52	0	0	0	0	0	0	-0.002	0.002	0.0007	42.8111	-78.8503
9/28/2016 12:51	0	0	0	0	0	0	-0.001	0.002	0.0009	42.8111	-78.8503
9/28/2016 12:50	0	0	0	0	0	0	-0.001	0.002	0.0009	42.8111	-78.8503
9/28/2016 12:49	0	0	0	0	0	0	0.001	0.002	0.001	42.8112	-78.8503
9/28/2016 12:48	0	0	0	0	0	0	-0.002	0.002	0.0009	42.8112	-78.8503
9/28/2016 12:47	0	0	0	0	0	0	-0.002	0.002	0.0008	42.8112	-78.8503
9/28/2016 12:46	0	0	0	0	0	0	0	0.002	0.0011	42.8112	-78.8503
9/28/2016 12:45	0	0	0	0	0	0	-0.001	0.002	0.0009	42.8112	-78.8503
9/28/2016 12:44	0	0	0	0	0	0	0	0.002	0.001	42.8112	-78.8503
9/28/2016 12:43	0	0	0	0	0	0	-0.001	0.002	0.0016	42.8112	-78.8503
9/28/2016 12:42	0	0	0	0	0	0	-0.001	0.002	0.0023	42.8112	-78.8503
9/28/2016 12:41	0	0	0	0	0	0	0.009	0.002	0.0023	42.8111	-78.8503
9/28/2016 12:40	0	0	0	0	0	0	0.014	0.002	0.0015	42.8111	-78.8503
9/28/2016 12:39	0	0	0	0	0	0	-0.002	0.002	0.0003	42.8112	-78.8503
9/28/2016 12:38	0	0	0	0	0	0	0	0.002	0.0005	42.8111	-78.8503
9/28/2016 12:37	0	0	0	0	0	0	0	0.002	0.0008	42.8111	-78.8503
9/28/2016 12:36	0	0	0	0	0	0	0	0.002	0.0007	42.8111	-78.8503

COMMUNITY AIR MONITORING

PERIODIC REVIEW REPORT

Tecumseh Phase III Business Park: Sites III-5 & III-6
Lackawanna, New York

Timestamp (GMT-4)	Low (ppm)	Peak (ppm)	STEL (ppm)	TWA (ppm)	VOC (ppm)	VOC (Avg15) (ppm)	Mass Conc. Total (mg/m³)	TWA (mg/m³)	Mass Conc. Total (Avg15) (mg/m³)	Latitude	Longitude
9/28/2016 12:35	0	0	0	0	0	0	0	0.002	0.0008	42.8111	-78.8503
9/28/2016 12:34	0	0	0	0	0	0	-0.001	0.002	0.0006	42.8112	-78.8503
9/28/2016 12:33	0	0	0	0	0	0	-0.003	0.002	0.0005	42.8111	-78.8503
9/28/2016 12:32	0	0	0	0	0	0	0.002	0.002	0.0026	42.8111	-78.8503
9/28/2016 12:31	0	0	0	0	0	0	-0.002	0.002	0.0025	42.8112	-78.8503
9/28/2016 12:30	0	0	0	0	0	0	0	0.002	0.0025	42.8111	-78.8503
9/28/2016 12:29	0	0	0	0	0	0	0.009	0.002	0.0031	42.8111	-78.8503
9/28/2016 12:28	0	0	0	0	0	0	0.009	0.002	0.0025	42.8112	-78.8503
9/28/2016 12:27	0	0	0	0	0	0	-0.001	0.002	0.0019	42.8112	-78.8503
9/28/2016 12:26	0	0	0	0	0	0	-0.003	0.002	0.0026	42.8112	-78.8503
9/28/2016 12:25	0	0	0	0	0	0	-0.003	0.002	0.0031	42.8111	-78.8503
9/28/2016 12:24	0	0	0	0	0	0	0	0.002	0.0032	42.8111	-78.8503
9/28/2016 12:23	0	0	0	0	0	0	0.005	0.002	0.0033	42.8111	-78.8503
9/28/2016 12:22	0	0	0	0	0	0	-0.001	0.002	0.0027	42.8111	-78.8503
9/28/2016 12:21	0	0	0	0	0	0	0.001	0.002	0.0032	42.8112	-78.8503
9/28/2016 12:20	0	0	0	0	0	0	-0.003	0.002	0.0029	42.8111	-78.8503
9/28/2016 12:19	0	0	0	0	0	0	-0.002	0.002	0.0031	42.8111	-78.8503
9/28/2016 12:18	0	0	0	0	0	0	0.028	0.002	0.0037	42.8112	-78.8503
9/28/2016 12:17	0	0	0	0	0	0	0	0.002	0.0018	42.8112	-78.8503
9/28/2016 12:16	0	0	0	0	0	0	-0.001	0.002	0.0016	42.8112	-78.8503
9/28/2016 12:15	0	0	0	0	0	0	0.009	0.002	0.0019	42.8111	-78.8503
9/28/2016 12:14	0	0	0	0	0	0	-0.001	0.002	0.002	42.8112	-78.8503
9/28/2016 12:13	0	0	0	0	0	0	0	0.002	0.0019	42.8111	-78.8503
9/28/2016 12:12	0	0	0	0	0	0	0.01	0.002	0.0019	42.8111	-78.8503
9/28/2016 12:11	0	0	0	0	0	0	0.005	0.002	0.0011	42.8111	-78.8503
9/28/2016 12:10	0	0	0	0	0	0	-0.002	0.002	0.0008	42.8111	-78.8503
9/28/2016 12:09	0	0	0	0	0	0	0.001	0.002	0.0009	42.8112	-78.8504
9/28/2016 12:08	0	0	0	0	0	0	-0.004	0.002	0.0009	42.8111	-78.8503
9/28/2016 12:07	0	0	0	0	0	0	0.007	0.002	0.0013	42.8111	-78.8503
9/28/2016 12:06	0	0	0	0	0	0	-0.003	0.002	0.0008	42.8112	-78.8503
9/28/2016 12:05	0	0	0	0	0	0	0	0.002	0.0008	42.8112	-78.8503
9/28/2016 12:04	0	0	0	0	0	0	0.006	0.002	0.0007	42.8111	-78.8503
9/28/2016 12:03	0	0	0	0	0	0	0	0.002	-0.0002	42.8111	-78.8503
9/28/2016 12:02	0	0	0	0	0	0	-0.003	0.002	-0.0002	42.8112	-78.8503
9/28/2016 12:01	0	0	0	0	0	0	0.003	0.002	-0.0001	42.8112	-78.8503
9/28/2016 12:00	0	0	0	0	0	0	0.011	0.002	-0.0003	42.8112	-78.8503
9/28/2016 11:59	0	0	0	0	0	0	-0.002	0.002	-0.0013	42.8112	-78.8503
9/28/2016 11:58	0	0	0	0	0	0	-0.001	0.002	-0.0013	42.8111	-78.8503
9/28/2016 11:57	0	0	0	0	0	0	-0.001	0.002	-0.0013	42.8111	-78.8503
9/28/2016 11:56	0	0	0	0	0	0	0	0.002	-0.0012	42.8112	-78.8503
9/28/2016 11:55	0	0	0	0	0	0	0	0.002	-0.0001	42.8111	-78.8503
9/28/2016 11:51	0	0	0	0	0	0	-0.003	0.002	-0.0005	42.8111	-78.8503
9/28/2016 11:50	0	0	0	0	0	0	-0.002	0.002	-0.0003	42.8111	-78.8503
9/28/2016 11:49	0	0	0	0	0	0	-0.004	0.002	0	42.8111	-78.8503
9/28/2016 11:48	0	0	0	0	0	0	0	0.002	0.0001	42.8111	-78.8503
9/28/2016 11:47	0	0	0	0	0	0	-0.002	0.002	0.0001	42.8111	-78.8503
9/28/2016 11:46	0	0	0	0	0	0	0	0.002	0.0003	42.8112	-78.8503
9/28/2016 11:45	0	0	0	0	0	0	0	0.002	0.0003	42.8112	-78.8503
9/28/2016 11:44	0	0	0	0	0	0	-0.003	0.002	0.0003	42.8112	-78.8503
9/28/2016 11:43	0	0	0	0	0	0	0	0.002	0.0003	42.8112	-78.8503
9/28/2016 11:42	0	0	0	0	0	0	0	0.002	0.0007	42.8111	-78.8503
9/28/2016 11:41	0	0	0	0	0	0	0.013	0.002	0.001	42.8111	-78.8503
9/28/2016 11:40	0	0	0	0	0	0	-0.002	0.002	0.0001	42.8112	-78.8503

COMMUNITY AIR MONITORING

PERIODIC REVIEW REPORT

Tecumseh Phase III Business Park: Sites III-5 & III-6
Lackawanna, New York

Timestamp (GMT-4)	Low (ppm)	Peak (ppm)	STEL (ppm)	TWA (ppm)	VOC (ppm)	VOC (Avg15) (ppm)	Mass Conc. Total (mg/m³)	TWA (mg/m³)	Mass Conc. Total (Avg15) (mg/m³)	Latitude	Longitude
9/28/2016 11:39	0	0	0	0	0	0	-0.001	0.002	0.0014	42.8112	-78.8503
9/28/2016 11:38	0	0	0	0	0	0	-0.001	0.002	0.0014	42.8112	-78.8503
9/28/2016 11:37	0	0	0	0	0	0	-0.002	0.002	0.0013	42.8112	-78.8503
9/28/2016 11:36	0	0	0	0	0	0	0	0.002	0.0014	42.8111	-78.8503
9/28/2016 11:35	0	0	0	0	0	0	0.002	0.002	0.0014	42.8111	-78.8503
9/28/2016 11:34	0	0	0	0	0	0	-0.003	0.002	0.0009	42.8111	-78.8503
9/28/2016 11:33	0	0	0	0	0	0	0	0.002	0.0017	42.8112	-78.8503
9/28/2016 11:32	0	0	0	0	0	0	0.001	0.002	0.0017	42.8111	-78.8503
9/28/2016 11:31	0	0	0	0	0	0	0	0.002	0.0018	42.8112	-78.8503
9/28/2016 11:30	0	0	0	0	0	0	0	0.002	0.0024	42.8112	-78.8503
9/28/2016 11:29	0	0	0	0	0	0	-0.002	0.002	0.0022	42.8111	-78.8503
9/28/2016 11:28	0	0	0	0	0	0	0.006	0.002	0.0042	42.8111	-78.8503
9/28/2016 11:27	0	0	0	0	0	0	0.004	0.002	0.0036	42.8112	-78.8503
9/28/2016 11:26										42.8111	-78.8503
9/28/2016 11:25	0	0	0	0	0	0	0.016	0.002	0.0033	42.8112	-78.8503
9/28/2016 11:24	0	0	0	0	0	0	-0.002	0.002	0.0022	42.8112	-78.8503
9/28/2016 11:23	0	0	0	0	0	0	-0.002	0.002	0.0021	42.8111	-78.8503
9/28/2016 11:22	0	0	0	0	0	0	-0.001	0.002	0.0021	42.8112	-78.8503
9/28/2016 11:21	0	0	0	0	0	0	0	0.002	0.0041	42.8112	-78.8503
9/28/2016 11:20	0	0	0	0	0	0	-0.004	0.002	0.0041	42.8112	-78.8503
9/28/2016 11:19	0	0	0	0	0	0	0.008	0.002	0.0042	42.8112	-78.8503
9/28/2016 11:18	0	0	0	0	0	0	0	0.002	0.0036	42.8111	-78.8503
9/28/2016 11:17	0	0	0	0	0	0	0.002	0.002	0.0036	42.8112	-78.8503
9/28/2016 11:16	0	0	0	0	0	0	0.008	0.002	0.0033	42.8112	-78.8503
9/28/2016 11:15	0	0	0	0	0	0	-0.002	0.002	0.0029	42.8112	-78.8503
9/28/2016 11:14	0	0	0	0	0	0	0.026	0.002	0.0033	42.8111	-78.8503
9/28/2016 11:13	0	0	0	0	0	0	-0.002	0.002	0.0011	42.8111	-78.8503
9/28/2016 11:12	0	0	0	0	0	0	0	0.002	0.0011	42.8112	-78.8503
9/28/2016 11:11	0	0	0	0	0	0	0.002	0.002	0.0009	42.8112	-78.8503
9/28/2016 11:10	0	0	0	0	0	0	0	0.002	0.0019	42.8112	-78.8503
9/28/2016 11:09	0	0	0	0	0	0	-0.003	0.002	0.0018	42.8112	-78.8503
9/28/2016 11:08	0	0	0	0	0	0	-0.002	0.002	0.0021	42.8111	-78.8503
9/28/2016 11:07	0	0	0	0	0	0	0.028	0.002	0.0019	42.8112	-78.8503
9/28/2016 11:06	0	0	0	0	0	0	0	0.002	-0.0005	42.8112	-78.8503
9/28/2016 11:05	0	0	0	0	0	0	-0.002	0.002	-0.0007	42.8112	-78.8503
9/28/2016 11:04	0	0	0	0	0	0	-0.001	0.002	-0.0008	42.8112	-78.8503
9/28/2016 11:03	0	0	0	0	0	0	0	0.002	-0.001	42.8112	-78.8503
9/28/2016 11:02	0	0	0	0	0	0	-0.003	0.002	-0.0012	42.8112	-78.8503
9/28/2016 11:00	0	0	0	0	0	0				42.8111	-78.8503
9/28/2016 10:59	0	0	0	0	0	0	-0.003	0.002	-0.0013	42.8112	-78.8503
9/28/2016 10:58	0	0	0	0	0	0	-0.002	0.002	-0.0013	42.8111	-78.8503
9/28/2016 10:57	0	0	0	0	0	0	-0.002	0.002	-0.0013	42.8111	-78.8503
9/28/2016 10:56	0	0	0	0	0	0	0.015	0.002	-0.0013	42.8112	-78.8503
9/28/2016 10:55	0	0	0	0	0	0	-0.001	0.002	-0.0025	42.8112	-78.8503
9/28/2016 10:54	0	0	0	0	0	0	0	0.002	-0.0027	42.8111	-78.8503
9/28/2016 10:53	0	0	0	0	0	0	-0.004	0.002	-0.0029	42.8112	-78.8503
9/28/2016 10:52	0	0	0	0	0	0	-0.004	0.002	-0.0028	42.8112	-78.8503
9/28/2016 10:51	0	0	0	0	0	0	-0.002	0.002	-0.0027	42.8112	-78.8503
9/28/2016 10:50	0	0	0	0	0	0	-0.004	0.002	-0.0028	42.8111	-78.8503
9/28/2016 10:49	0	0	0	0	0	0	-0.003	0.002	-0.0027	42.8111	-78.8503
9/28/2016 10:48	0	0	0	0	0	0	-0.002	0.002	-0.0026	42.8112	-78.8503
9/28/2016 10:47	0	0	0	0	0	0	-0.003	0.002	-0.0027	42.8112	-78.8503
9/28/2016 10:46	0	0	0	0	0	0	-0.002	0.002	-0.0025	42.8112	-78.8503

COMMUNITY AIR MONITORING

PERIODIC REVIEW REPORT

Tecumseh Phase III Business Park: Sites III-5 & III-6
Lackawanna, New York

Timestamp (GMT-4)	Low (ppm)	Peak (ppm)	STEL (ppm)	TWA (ppm)	VOC (ppm)	VOC (Avg15) (ppm)	Mass Conc. Total (mg/m³)	TWA (mg/m³)	Mass Conc. Total (Avg15) (mg/m³)	Latitude	Longitude
9/28/2016 10:45	0	0	0	0	0	0	-0.002	0.002	-0.0025	42.8111	-78.8503
9/28/2016 10:44	0	0	0	0	0	0	-0.003	0.002	-0.0026	42.8111	-78.8503
9/28/2016 10:43	0	0	0	0	0	0	-0.003	0.002	-0.0024	42.8112	-78.8503
9/28/2016 10:42	0	0	0	0	0	0	-0.001	0.002	-0.0023	42.8112	-78.8503
9/28/2016 10:41	0	0	0	0	0	0	-0.003	0.002	-0.0023	42.8112	-78.8503
9/28/2016 10:40	0	0	0	0	0	0	-0.004	0.002	-0.0013	42.8112	-78.8503
9/28/2016 10:39	0	0	0	0	0	0	-0.003	0.002	-0.0013	42.8112	-78.8503
9/28/2016 10:38	0	0	0	0	0	0	-0.003	0.002	-0.0013	42.8111	-78.8503
9/28/2016 10:37	0	0	0	0	0	0	-0.002	0.002	-0.0013	42.8111	-78.8503
9/28/2016 10:36	0	0	0	0	0	0	-0.004	0.002	-0.0013	42.8112	-78.8503
9/28/2016 10:35	0	0	0	0	0	0	-0.003	0.002	-0.0012	42.8111	-78.8504
9/28/2016 10:34	0	0	0	0	0	0	-0.001	0.002	-0.0013	42.8111	-78.8503
9/28/2016 10:33	0	0	0	0	0	0	-0.003	0.002	-0.001	42.8112	-78.8503
9/28/2016 10:32	0	0	0	0	0	0	0	0.002	-0.0006	42.8112	-78.8503
9/28/2016 10:31	0	0	0	0	0	0	-0.002	0.002	-0.0002	42.8111	-78.8503
9/28/2016 10:30	0	0	0	0	0	0	-0.004	0.002	-0.0004	42.8112	-78.8503
9/28/2016 10:29	0	0	0	0	0	0	0	0.002	-0.0003	42.8112	-78.8503
9/28/2016 10:28	0	0	0	0	0	0	-0.002	0.002	-0.0006	42.8112	-78.8503
9/28/2016 10:27	0	0	0	0	0	0	0	0.002	-0.0007	42.8112	-78.8503
9/28/2016 10:26	0	0	0	0	0	0	0.011	0.002	-0.0007	42.8111	-78.8503
9/28/2016 10:25	0	0	0	0	0	0	-0.003	0.002	-0.0017	42.8111	-78.8503
9/28/2016 10:24	0	0	0	0	0	0	-0.004	0.002	-0.0015	42.8111	-78.8503
9/28/2016 10:23	0	0	0	0	0	0	-0.002	0.002	-0.0009	42.8112	-78.8503
9/28/2016 10:22	0	0	0	0	0	0	-0.003	0.002	-0.0009	42.8111	-78.8503
9/28/2016 10:21	0	0	0	0	0	0	-0.002	0.002	0.0023	42.8112	-78.8503
9/28/2016 10:20	0	0	0	0	0	0	-0.004	0.002	0.0022	42.8112	-78.8503
9/28/2016 10:19	0	0	0	0	0	0	0	0.002	0.0026	42.8112	-78.8503
9/28/2016 10:18	0	0	0	0	0	0	0.003	0.002	0.0028	42.8111	-78.8503
9/28/2016 10:17	0	0	0	0	0	0	0.005	0.002	0.0025	42.8112	-78.8503
9/28/2016 10:16	0	0	0	0	0	0	-0.001	0.002	0.0018	42.8112	-78.8503
9/28/2016 10:15	0	0	0	0	0	0	-0.002	0.002	0.0018	42.8111	-78.8503
9/28/2016 10:14	0	0	0	0	0	0	-0.005	0.002	0.0033	42.8112	-78.8504
9/28/2016 10:13	0	0	0	0	0	0	-0.003	0.002	0.0041	42.8112	-78.8504
9/28/2016 10:12	0	0	0	0	0	0	0	0.002	0.0042	42.8112	-78.8504
9/28/2016 10:11	0	0	0	0	0	0	-0.004	0.002	0.004	42.8112	-78.8503
9/28/2016 10:10	0	0	0	0	0	0	0	0.002	0.0041	42.8112	-78.8503
9/28/2016 10:09	0	0	0	0	0	0	0.004	0.002	0.0038	42.8112	-78.8504
9/28/2016 10:08	0	0	0	0	0	0	-0.002	0.002	0.0034	42.8112	-78.8503
9/28/2016 10:07	0	0	0	0	0	0	0.046	0.002	0.0035	42.8112	-78.8503
9/28/2016 10:06	0	0	0	0	0	0	-0.004	0.002	-0.0002	42.8112	-78.8504
9/28/2016 10:03	0	0	0	0	0	0	-0.002	0.001	-0.0002	42.8112	-78.8503
9/28/2016 10:02	0	0	0	0	0	0	-0.003	0.001	-0.0001	42.8112	-78.8503
9/28/2016 10:01	0	0	0	0	0	0	-0.001	0.001	0.0007	42.8112	-78.8503
9/28/2016 10:00	0	0	0	0	0	0	0.017	0.001	0.001	42.8112	-78.8503
9/28/2016 9:59	0	0	0	0	0	0	0.005	0.001	-0.0003	42.8112	-78.8503
9/28/2016 9:58	0	0	0	0	0	0	-0.002	0.001	-0.0007	42.8112	-78.8503
9/28/2016 9:57	0	0	0	0	0	0	-0.002	0.001	-0.0007	42.8112	-78.8503
9/28/2016 9:56	0	0	0	0	0	0	-0.003	0.001	-0.0007	42.8112	-78.8503
9/28/2016 9:55	0	0	0	0	0	0	-0.004	0.001	-0.0007	42.8112	-78.8503
9/28/2016 9:54	0	0	0	0	0	0	-0.001	0.001	-0.0005	42.8112	-78.8503
9/28/2016 9:53	0	0	0	0	0	0	0	0.001	-0.0006	42.8112	-78.8503
9/28/2016 9:52	0	0	0	0	0	0	-0.002	0.001	-0.0006	42.8112	-78.8503
9/28/2016 9:51	0	0	0	0	0	0	0	0.001	-0.0005	42.8112	-78.8503

COMMUNITY AIR MONITORING

PERIODIC REVIEW REPORT

Tecumseh Phase III Business Park: Sites III-5 & III-6
Lackawanna, New York

Timestamp (GMT-4)	Low (ppm)	Peak (ppm)	STEL (ppm)	TWA (ppm)	VOC (ppm)	VOC (Avg15) (ppm)	Mass Conc. Total (mg/m³)	TWA (mg/m³)	Mass Conc. Total (Avg15) (mg/m³)	Latitude	Longitude
9/28/2016 9:50	0	0	0	0	0	0	-0.002	0.001	0.0039	42.8112	-78.8503
9/28/2016 9:49	0	0	0	0	0	0	-0.003	0.001	0.0053	42.8112	-78.8503
9/28/2016 9:48	0	0	0	0	0	0	-0.001	0.001	0.0055	42.8112	-78.8503
9/28/2016 9:47	0	0	0	0	0	0	0.009	0.001	0.0056	42.8112	-78.8503
9/28/2016 9:46	0	0	0	0	0	0	0.004	0.001	0.005	42.8112	-78.8503
9/28/2016 9:45	0	0	0	0	0	0	-0.002	0.001	0.0046	42.8112	-78.8503
9/28/2016 9:44	0	0	0	0	0	0	-0.002	0.001	0.0046	42.8112	-78.8503
9/28/2016 9:43	0	0	0	0	0	0	-0.002	0.001	0.0047	42.8112	-78.8503
9/28/2016 9:42	0	0	0	0	0	0	-0.002	0.001	0.0049	42.8112	-78.8503
9/28/2016 9:41	0	0	0	0	0	0	-0.003	0.001	0.0049	42.8112	-78.8503
9/28/2016 9:40	0	0	0	0	0	0	0	0.001	0.0055	42.8112	-78.8503
9/28/2016 9:39	0	0	0	0	0	0	-0.003	0.001	0.0059	42.8112	-78.8503
9/28/2016 9:38	0	0	0	0	0	0	0	0.001	0.0115	42.8112	-78.8503
9/28/2016 9:37	0	0	0	0	0	0	0	0.001	0.0115	42.8112	-78.8504
9/28/2016 9:36	0	0	0	0	0	0	0.066	0.001	0.0115	42.8112	-78.8504
9/28/2016 9:35	0	0	0	0	0	0	0.019	0.001	0.0071	42.8112	-78.8503
9/28/2016 9:34	0	0	0	0	0	0	0	0.001	0.0058	42.8112	-78.8503
9/28/2016 9:33	0	0	0	0	0	0	0	0.001	0.0062	42.8112	-78.8503
9/28/2016 9:32	0	0	0	0	0	0	0	0.001	0.0062	42.8112	-78.8503
9/28/2016 9:31	0	0	0	0	0	0	-0.002	0.001	0.0061	42.8112	-78.8503
9/28/2016 9:30	0	0	0	0	0	0	-0.002	0.001	0.0062	42.8112	-78.8504
9/28/2016 9:29	0	0	0	0	0	0	0	0.001	0.0063	42.8112	-78.8503
9/28/2016 9:28	0	0	0	0	0	0	0	0.001	0.0073	42.8112	-78.8503
9/28/2016 9:27	0	0	0	0	0	0	-0.001	0.001	0.0073	42.8112	-78.8504
9/28/2016 9:26	0	0	0	0	0	0	0.006	0.001	0.0076	42.8112	-78.8503
9/28/2016 9:25	0	0	0	0	0	0	0.006	0.001	0.0081	42.8112	-78.8503
9/28/2016 9:24	0	0	0	0	0	0	0.081	0.001	0.0084	42.8112	-78.8503
9/28/2016 9:23	0	0	0	0	0	0	0	0.001	0.0029	42.8112	-78.8503
9/28/2016 9:22	0	0	0	0	0	0	-0.001	0.001	0.0029	42.8112	-78.8503
9/28/2016 9:21	0	0	0	0	0	0	0	0.001	0.0041	42.8112	-78.8504
9/28/2016 9:20	0	0	0	0	0	0	0	0.001	0.0041	42.8112	-78.8503
9/28/2016 9:19	0	0	0	0	0	0	0.006	0.001	0.0042	42.8112	-78.8504
9/28/2016 9:18	0	0	0	0	0	0	0	0.001	0.0038	42.8112	-78.8503
9/28/2016 9:17	0	0	0	0	0	0	-0.001	0.001	0.0038	42.8112	-78.8503
9/28/2016 9:16	0	0	0	0	0	0	-0.001	0.001	0.004	42.8112	-78.8503
9/28/2016 9:15	0	0	0	0	0	0	0	0.001	0.0042	42.8112	-78.8503
9/28/2016 9:14	0	0	0	0	0	0	0.015	0.001	0.0043	42.8112	-78.8503
9/28/2016 9:13	0	0	0	0	0	0	0	0.001	0.0033	42.8112	-78.8503
9/28/2016 9:12	0	0	0	0	0	0	0.003	0.001	0.0041	42.8112	-78.8504
9/28/2016 9:11	0	0	0	0	0	0	0.013	0.001	0.0053	42.8112	-78.8503
9/28/2016 9:10	0	0	0	0	0	0	0.011	0.001	0.0044	42.8112	-78.8504
9/28/2016 9:09	0	0	0	0	0	0	-0.001	0.001	0.0049	42.8112	-78.8504
9/28/2016 9:08	0	0	0	0	0	0	0	0.001	0.0065	42.8112	-78.8504
9/28/2016 9:07	0	0	0	0	0	0	0.017	0.001	0.0065	42.8112	-78.8504
9/28/2016 9:06	0	0	0	0	0	0	0	0.001	0.0054	42.8111	-78.8503
9/28/2016 9:05	0	0	0	0	0	0	0.001	0.001	0.0055	42.8112	-78.8503
9/28/2016 9:04	0	0	0	0	0	0	0	0.001	0.0055	42.8112	-78.8503
9/28/2016 9:03	0	0	0	0	0	0	0	0.001	0.0055	42.8112	-78.8503
9/28/2016 9:02	0	0	0	0	0	0	0.002	0.001	0.0054	42.8112	-78.8503
9/28/2016 9:01	0	0	0	0	0	0	0.002	0.001	0.0051	42.8112	-78.8503
9/28/2016 9:00	0	0	0	0	0	0	0.002	0.001	0.0049	42.8112	-78.8504
9/28/2016 8:59	0	0	0	0	0	0	0	0.001	0.0048	42.8112	-78.8504
9/28/2016 8:58	0	0	0	0	0	0	0.011	0.001	0.0048	42.8112	-78.8504

COMMUNITY AIR MONITORING

PERIODIC REVIEW REPORT

Tecumseh Phase III Business Park: Sites III-5 & III-6
Lackawanna, New York

Timestamp (GMT-4)	Low (ppm)	Peak (ppm)	STEL (ppm)	TWA (ppm)	VOC (ppm)	VOC (Avg15) (ppm)	Mass Conc. Total (mg/m³)	TWA (mg/m³)	Mass Conc. Total (Avg15) (mg/m³)	Latitude	Longitude
9/28/2016 8:57	0	0	0	0	0	0	0.021	0.001	0.0061	42.8112	-78.8504
9/28/2016 8:56	0	0	0	0	0	0	0	0.001	0.0055	42.8112	-78.8504
9/28/2016 8:55	0	0	0	0	0	0	0.018	0.001	0.0076	42.8112	-78.8503
9/28/2016 8:54	0	0	0	0	0	0	0.024	0.001	0.0067	42.8112	-78.8504
9/28/2016 8:53	0	0	0	0	0	0	0	0.001	0.0055	42.8112	-78.8504
9/28/2016 8:52	0	0	0	0	0	0	0	0.001	0.0067	42.8112	-78.8503
9/28/2016 8:51	0	0	0	0	0	0	0.002	0.001	0.0079	42.8112	-78.8504
9/28/2016 8:50	0	0	0	0	0	0	0	0.001	0.0089	42.8111	-78.8504
9/28/2016 8:49	0	0	0	0	0	0	0	0.001	0.0091	42.8112	-78.8504
9/28/2016 8:48	0	0	0	0	0	0	-0.001	0.001	0.0091	42.8112	-78.8504
9/28/2016 8:47	0	0	0	0	0	0	-0.002	0.001	0.0093	42.8112	-78.8504
9/28/2016 8:46	0	0	0	0	0	0	-0.001	0.001	0.0094	42.8112	-78.8504
9/28/2016 8:45	0	0	0	0	0	0	0	0.001	0.0095	42.8112	-78.8504
9/28/2016 8:44	0	0	0	0	0	0	0	0.001	0.0095	42.8112	-78.8504
9/28/2016 8:43	0	0	0	0	0	0	0.031	0.001	0.0095	42.8112	-78.8504
9/28/2016 8:42	0	0	0	0	0	0	0.011	0.001	0.0074	42.8111	-78.8503
9/28/2016 8:41	0	0	0	0	0	0	0.032	0.001	0.0067	42.8112	-78.8504
9/28/2016 8:40	0	0	0	0	0	0	0.005	0.001	0.0046	42.8112	-78.8504
9/28/2016 8:39	0	0	0	0	0	0	0.006	0.001	0.0043	42.8112	-78.8503
9/28/2016 8:38	0	0	0	0	0	0	0.018	0.001	0.0039	42.8112	-78.8504
9/28/2016 8:37	0	0	0	0	0	0	0.018	0.001	0.0027	42.8112	-78.8503
9/28/2016 8:36	0	0	0	0	0	0	0.016	0.001	0.0017	42.8112	-78.8504
9/28/2016 8:35	0	0	0	0	0	0	0.003	0.001	0.0008	42.8112	-78.8504
9/28/2016 8:34	0	0	0	0	0	0	0	0.001	0.0007	42.8112	-78.8504
9/28/2016 8:33	0	0	0	0	0	0	0.002	0.001	0.0009	42.8112	-78.8504
9/28/2016 8:32	0	0	0	0	0	0	0	0.001	0.0008	42.8112	-78.8503
9/28/2016 8:31	0	0	0	0	0	0	0	0.001	0.0008	42.8112	-78.8504
9/28/2016 8:30	0	0	0	0	0	0	0	0.001	0.0008	42.8112	-78.8503
9/28/2016 8:29	0	0	0	0	0	0	0	0.001	0.0009	42.8112	-78.8503
9/28/2016 8:28	0	0	0	0	0	0	0	0.001	0.001	42.8112	-78.8504
9/28/2016 8:27	0	0	0	0	0	0	0	0.001	0.0011	42.8112	-78.8504
9/28/2016 8:26	0	0	0	0	0	0	0.001	0.001	0.0012	42.8112	-78.8504
9/28/2016 8:25	0	0	0	0	0	0	0	0.001	0.0011	42.8112	-78.8504
9/28/2016 8:24	0	0	0	0	0	0	0	0.001	0.0013	42.8112	-78.8503
9/28/2016 8:23	0	0	0	0	0	0	0.001	0.001	0.0013	42.8112	-78.8504
9/28/2016 8:22	0	0	0	0	0	0	0.002	0.001	0.0013	42.8112	-78.8504
9/28/2016 8:21	0	0	0	0	0	0	0.003	0.001	0.0013	42.8112	-78.8504
9/28/2016 8:20	0	0	0	0	0	0	0.001	0.001	0.0011	42.8112	-78.8503
9/28/2016 8:19	0	0	0	0	0	0	0.004	0.001	0.0013	42.8112	-78.8504
9/28/2016 8:18	0	0	0	0	0	0	0	0.001	0.0012	42.8112	-78.8504
9/28/2016 8:17	0	0	0	0	0	0	0	0.001	0.0016	42.8112	-78.8504
9/28/2016 8:16	0	0	0	0	0	0	0	0.001	0.0019	42.8112	-78.8504
9/28/2016 8:15							0.002	0.001	0.0022	42.8112	-78.8504
9/28/2016 8:14	0	0	0	0	0	0	0.001	0.001	0.0023	42.8112	-78.8504
9/28/2016 8:13	0	0	0	0	0	0	0.001	0.001	0.0025	42.8112	-78.8504
9/28/2016 8:12	0	0	0	0	0	0	0.002	0.001	0.0026	42.8112	-78.8504
9/28/2016 8:11	0	0	0	0	0	0	0	0.001	0.0026	42.8112	-78.8504
9/28/2016 8:10	0	0	0	0	0	0	0.002	0.001	0.003	42.8112	-78.8504
9/28/2016 8:09	0	0	0	0	0	0	0.001	0.001	0.0032	42.8112	-78.8504
9/28/2016 8:08	0	0	0	0	0	0	0.001	0.001	0.0034	42.8112	-78.8504
9/28/2016 8:07	0	0	0	0	0	0	0.002	0.001	0.0037	42.8112	-78.8504
9/28/2016 8:06	0	0	0	0	0	0	0	0.001	0.0042	42.8112	-78.8504
9/28/2016 8:05	0	0	0	0	0	0	0.003	0.001	0.0043	42.8112	-78.8504

COMMUNITY AIR MONITORING

PERIODIC REVIEW REPORT

Tecumseh Phase III Business Park: Sites III-5 & III-6
Lackawanna, New York

Timestamp (GMT-4)	Low (ppm)	Peak (ppm)	STEL (ppm)	TWA (ppm)	VOC (ppm)	VOC (Avg15) (ppm)	Mass Conc. Total (mg/m³)	TWA (mg/m³)	Mass Conc. Total (Avg15) (mg/m³)	Latitude	Longitude
9/28/2016 8:04	0	0	0	0	0	0	0.003	0.001	0.0044	42.8112	-78.8504
9/28/2016 8:03	0	0	0	0	0	0	0.006	0.001	0.0075	42.8112	-78.8504
9/28/2016 8:02	0	0	0	0	0	0	0.005	0.001	0.008	42.8112	-78.8504
9/28/2016 8:01	0	0	0	0	0	0	0.004	0.001	0.0077	42.8112	-78.8503
9/28/2016 8:00	0	0	0	0	0	0	0.004	0.001	0.0075	42.8112	-78.8503
9/28/2016 7:59	0	0	0	0	0	0	0.003	0.001	0.0075	42.8112	-78.8504
9/28/2016 7:58	0	0	0	0	0	0	0.003	0.001	0.0075	42.8112	-78.8503
9/28/2016 7:57	0	0	0	0	0	0	0.002	0.001	0.0079	42.8112	-78.8504
9/28/2016 7:56	0	0	0	0	0	0	0.006	0	0.0081	42.8112	-78.8503
9/28/2016 7:55	0	0	0	0	0	0	0.005	0	0.0083	42.8112	-78.8504
9/28/2016 7:54	0	0	0	0	0	0	0.004	0	0.0086	42.8112	-78.8504
9/28/2016 7:53	0	0	0	0	0	0	0.006	0	0.0088	42.8112	-78.8504
9/28/2016 7:52	0	0	0	0	0	0	0.009	0	0.009	42.8112	-78.8504
9/28/2016 7:51	0	0	0	0	0	0	0.002	0	0.0097	42.8112	-78.8504
9/28/2016 7:50	0	0	0	0	0	0	0.004	0	0.0107	42.8112	-78.8504
9/28/2016 7:49	0	0	0	0	0	0	0.05	0	0.0111	42.8112	-78.8504
9/28/2016 7:48	0	0	0	0	0	0	0.013	0	0.0082	42.8112	-78.8504
9/28/2016 7:47	0	0	0	0	0	0	0	0	0.0077	42.8112	-78.8504
9/28/2016 7:46	0	0	0	0	0	0	0.002	0	0.0085	42.8112	-78.8504
9/28/2016 7:45	0	0	0	0	0	0	0.004	0	0.0091	42.8112	-78.8504
9/28/2016 7:44	0	0	0	0	0	0	0.003	0	0.0097	42.8112	-78.8504
9/28/2016 7:43	0	0	0	0	0	0	0.009	0	0.0105	42.8112	-78.8504
9/28/2016 7:42	0	0	0	0	0	0	0.004	0	0.0107	42.8112	-78.8504
9/28/2016 7:41	0	0	0	0	0	0	0.01	0	0.0118	42.8112	-78.8504
9/28/2016 7:40	0	0	0	0	0	0	0.009	0	0.0122	42.8112	-78.8504
9/28/2016 7:39	0	0	0	0	0	0	0.007	0	0.013	42.8112	-78.8504
9/28/2016 7:38	0	0	0	0	0	0	0.009	0	0.015	42.8112	-78.8504
9/28/2016 7:37	0	0	0	0	0	0	0.019	0	0.018	42.8112	-78.8504
9/28/2016 7:36	0	0	0	0	0	0	0.017	0	0.017	42.8112	-78.8504
9/28/2016 7:35										42.8112	-78.8504
9/27/2016 15:02										42.8111	-78.8503
9/27/2016 15:01	0	0	0	0	0	0	0.005	0.002	0.0104	42.8111	-78.8503
9/27/2016 15:00	0	0	0	0	0	0	-0.001	0.002	0.0111	42.8111	-78.8503
9/27/2016 14:59	0	0	0	0	0	0	0.014	0.002	0.0112	42.8111	-78.8503
9/27/2016 14:58	0	0	0	0	0	0	0.009	0.001	0.0103	42.8111	-78.8503
9/27/2016 14:57	0	0	0	0	0	0	0	0.001	0.0094	42.8111	-78.8503
9/27/2016 14:56	0	0	0	0	0	0	-0.005	0.001	0.0101	42.8111	-78.8503
9/27/2016 14:55	0	0	0	0	0	0	0.03	0.001	0.0102	42.8111	-78.8503
9/27/2016 14:54	0	0	0	0	0	0	0.009	0.001	0.0081	42.8111	-78.8503
9/27/2016 14:53	0	0	0	0	0	0	-0.002	0.001	0.0075	42.8111	-78.8503
9/27/2016 14:52	0	0	0	0	0	0	-0.001	0.001	0.0075	42.8111	-78.8503
9/27/2016 14:51	0	0	0	0	0	0	0	0.001	0.0071	42.8111	-78.8503
9/27/2016 14:50	0	0	0	0	0	0	-0.006	0.001	0.0068	42.8111	-78.8503
9/27/2016 14:49	0	0	0	0	0	0	0.007	0.001	0.0072	42.8111	-78.8503
9/27/2016 14:48	0	0	0	0	0	0	0	0.001	0.0067	42.8111	-78.8503
9/27/2016 14:47	0	0	0	0	0	0	0.097	0.001	0.0076	42.8111	-78.8503
9/27/2016 14:46	0	0	0	0	0	0	0.016	0.001	0.0023	42.8111	-78.8503
9/27/2016 14:45	0	0	0	0	0	0	0	0.001	0.0017	42.8111	-78.8503
9/27/2016 14:44	0	0	0	0	0	0	0	0.001	0.0017	42.8111	-78.8503
9/27/2016 14:43	0	0	0	0	0	0	-0.004	0.001	0.0015	42.8111	-78.8503
9/27/2016 14:42	0	0	0	0	0	0	0.011	0.001	0.0021	42.8111	-78.8503
9/27/2016 14:41	0	0	0	0	0	0	-0.004	0.001	0.0017	42.8111	-78.8503
9/27/2016 14:40	0	0	0	0	0	0	-0.001	0.001	0.0019	42.8111	-78.8503

COMMUNITY AIR MONITORING

PERIODIC REVIEW REPORT

Tecumseh Phase III Business Park: Sites III-5 & III-6
Lackawanna, New York

Timestamp (GMT-4)	Low (ppm)	Peak (ppm)	STEL (ppm)	TWA (ppm)	VOC (ppm)	VOC (Avg15) (ppm)	Mass Conc. Total (mg/m³)	TWA (mg/m³)	Mass Conc. Total (Avg15) (mg/m³)	Latitude	Longitude
9/27/2016 14:39	0	0	0	0	0	0	-0.001	0.001	0.0019	42.8111	-78.8503
9/27/2016 14:38	0	0	0	0	0	0	-0.002	0.001	0.0017	42.8111	-78.8503
9/27/2016 14:37	0	0	0	0	0	0	-0.006	0.001	0.0023	42.8111	-78.8503
9/27/2016 14:36	0	0	0	0	0	0	-0.005	0.001	0.0041	42.8111	-78.8503
9/27/2016 14:35	0	0	0	0	0	0	0	0.001	0.0049	42.8111	-78.8503
9/27/2016 14:34	0	0	0	0	0	0	0	0.001	0.0047	42.8111	-78.8503
9/27/2016 14:33	0	0	0	0	0	0	0.013	0.001	0.005	42.8111	-78.8503
9/27/2016 14:32	0	0	0	0	0	0	0.018	0.001	0.0039	42.8111	-78.8503
9/27/2016 14:31	0	0	0	0	0	0	0.006	0.001	0.0028	42.8111	-78.8503
9/27/2016 14:30	0	0	0	0	0	0	0	0.001	0.0024	42.8111	-78.8503
9/27/2016 14:29	0	0	0	0	0	0	-0.002	0.001	0.0023	42.8111	-78.8503
9/27/2016 14:28	0	0	0	0	0	0	0.005	0.001	0.0023	42.8111	-78.8503
9/27/2016 14:27	0	0	0	0	0	0	0.004	0.001	0.0017	42.8111	-78.8503
9/27/2016 14:26	0	0	0	0	0	0	0	0.001	0.0013	42.8111	-78.8503
9/27/2016 14:25	0	0	0	0	0	0	-0.001	0.001	0.0027	42.8111	-78.8503
9/27/2016 14:24	0	0	0	0	0	0	-0.004	0.001	0.0025	42.8111	-78.8503
9/27/2016 14:23	0	0	0	0	0	0	0.006	0.001	0.0027	42.8111	-78.8503
9/27/2016 14:22	0	0	0	0	0	0	0.022	0.001	0.0098	42.8111	-78.8503
9/27/2016 14:21	0	0	0	0	0	0	0.006	0.001	0.0081	42.8111	-78.8503
9/27/2016 14:20	0	0	0	0	0	0	-0.003	0.001	0.0075	42.8111	-78.8503
9/27/2016 14:19	0	0	0	0	0	0	0.005	0.001	0.0074	42.8111	-78.8503
9/27/2016 14:18	0	0	0	0	0	0	-0.004	0.001	0.0069	42.8111	-78.8503
9/27/2016 14:17	0	0	0	0	0	0	0.002	0.001	0.0069	42.8111	-78.8503
9/27/2016 14:16	0	0	0	0	0	0	0	0.001	0.0064	42.8111	-78.8503
9/27/2016 14:15	0	0	0	0	0	0	-0.002	0.001	0.0062	42.8111	-78.8503
9/27/2016 14:14	0	0	0	0	0	0	-0.001	0.001	0.0061	42.8111	-78.8503
9/27/2016 14:13	0	0	0	0	0	0	-0.005	0.001	0.006	42.8111	-78.8503
9/27/2016 14:12	0	0	0	0	0	0	-0.001	0.001	0.011	42.8111	-78.8503
9/27/2016 14:11	0	0	0	0	0	0	0.021	0.001	0.0114	42.8111	-78.8503
9/27/2016 14:10	0	0	0	0	0	0	-0.005	0.001	0.0107	42.8111	-78.8503
9/27/2016 14:09	0	0	0	0	0	0	0	0.001	0.0119	42.8111	-78.8503
9/27/2016 14:08	0	0	0	0	0	0	0.112	0.001	0.0117	42.8111	-78.8503
9/27/2016 14:07	0	0	0	0	0	0	-0.003	0.001	0.0028	42.8111	-78.8503
9/27/2016 14:06	0	0	0	0	0	0	-0.004	0.001	0.0029	42.8111	-78.8503
9/27/2016 14:05	0	0	0	0	0	0	-0.004	0.001	0.0032	42.8111	-78.8503
9/27/2016 14:04	0	0	0	0	0	0	-0.002	0.001	0.0037	42.8111	-78.8503
9/27/2016 14:03	0	0	0	0	0	0	-0.005	0.001	0.0071	42.8111	-78.8503
9/27/2016 14:02	0	0	0	0	0	0	-0.005	0.001	0.0079	42.8111	-78.8503
9/27/2016 14:01	0	0	0	0	0	0	-0.003	0.001	0.008	42.8111	-78.8503
9/27/2016 14:00	0	0	0	0	0	0	-0.003	0.001	0.0079	42.8111	-78.8503
9/27/2016 13:59	0	0	0	0	0	0	-0.003	0.001	0.0078	42.8111	-78.8503
9/27/2016 13:58	0	0	0	0	0	0	0.07	0.001	0.0077	42.8111	-78.8503
9/27/2016 13:57	0	0	0	0	0	0	0.005	0.001	0.0021	42.8111	-78.8503
9/27/2016 13:54	0	0	0	0	0	0	-0.003	0.001	0.0011	42.8111	-78.8503
9/27/2016 13:53	0	0	0	0	0	0	-0.003	0.001	0.0011	42.8111	-78.8503
9/27/2016 13:52	0	0	0	0	0	0	-0.002	0.001	0.0011	42.8111	-78.8503
9/27/2016 13:51	0	0	0	0	0	0	0	0.001	0.0011	42.8111	-78.8503
9/27/2016 13:50	0	0	0	0	0	0	0.002	0.001	0.0007	42.8111	-78.8503
9/27/2016 13:49	0	0	0	0	0	0	0.042	0.001	0.0002	42.8111	-78.8503
9/27/2016 13:48	0	0	0	0	0	0	0.006	0.001	-0.0027	42.8111	-78.8503
9/27/2016 13:47	0	0	0	0	0	0	-0.004	0.001	-0.0035	42.8111	-78.8503
9/27/2016 13:46	0	0	0	0	0	0	-0.004	0.001	-0.0036	42.8111	-78.8503
9/27/2016 13:45	0	0	0	0	0	0	-0.005	0.001	-0.0036	42.8111	-78.8503

COMMUNITY AIR MONITORING

PERIODIC REVIEW REPORT

Tecumseh Phase III Business Park: Sites III-5 & III-6
Lackawanna, New York

Timestamp (GMT-4)	Low (ppm)	Peak (ppm)	STEL (ppm)	TWA (ppm)	VOC (ppm)	VOC (Avg15) (ppm)	Mass Conc. Total (mg/m³)	TWA (mg/m³)	Mass Conc. Total (Avg15) (mg/m³)	Latitude	Longitude
9/27/2016 13:44	0	0	0	0	0	0	-0.004	0.001	-0.0036	42.8111	-78.8503
9/27/2016 13:43	0	0	0	0	0	0	-0.003	0.001	-0.0037	42.8111	-78.8503
9/27/2016 13:42	0	0	0	0	0	0	0.005	0.001	-0.0035	42.8111	-78.8503
9/27/2016 13:41	0	0	0	0	0	0	-0.005	0.001	-0.0042	42.8111	-78.8503
9/27/2016 13:40	0	0	0	0	0	0	-0.006	0.001	-0.0043	42.8111	-78.8503
9/27/2016 13:39	0	0	0	0	0	0	-0.002	0.001	-0.0041	42.8111	-78.8503
9/27/2016 13:38	0	0	0	0	0	0	-0.003	0.001	-0.0043	42.8111	-78.8503
9/27/2016 13:37	0	0	0	0	0	0	-0.003	0.001	-0.0041	42.8111	-78.8503
9/27/2016 13:36	0	0	0	0	0	0	-0.006	0.001	-0.004	42.8111	-78.8503
9/27/2016 13:35	0	0	0	0	0	0	-0.005	0.001	-0.0039	42.8111	-78.8503
9/27/2016 13:34	0	0	0	0	0	0	-0.002	0.001	-0.0035	42.8111	-78.8503
9/27/2016 13:33	0	0	0	0	0	0	-0.005	0.001	-0.0034	42.8111	-78.8503
9/27/2016 13:32	0	0	0	0	0	0	-0.006	0.001	-0.0034	42.8111	-78.8503
9/27/2016 13:31	0	0	0	0	0	0	-0.004	0.001	-0.003	42.8111	-78.8503
9/27/2016 13:30	0	0	0	0	0	0	-0.005	0.001	-0.002	42.8111	-78.8503
9/27/2016 13:29	0	0	0	0	0	0	-0.005	0.001	-0.0019	42.8111	-78.8503
9/27/2016 13:28	0	0	0	0	0	0	0	0.001	-0.0015	42.8111	-78.8503
9/27/2016 13:27	0	0	0	0	0	0	-0.006	0.001	-0.002	42.8111	-78.8503
9/27/2016 13:26	0	0	0	0	0	0	-0.006	0.001	-0.0019	42.8111	-78.8503
9/27/2016 13:25	0	0	0	0	0	0	-0.004	0.001	-0.0015	42.8111	-78.8503
9/27/2016 13:24	0	0	0	0	0	0	-0.004	0.001	-0.0013	42.8111	-78.8503
9/27/2016 13:23	0	0	0	0	0	0	0	0.001	-0.0014	42.8111	-78.8503
9/27/2016 13:22	0	0	0	0	0	0	-0.002	0.001	-0.0015	42.8111	-78.8503
9/27/2016 13:21	0	0	0	0	0	0	-0.004	0.001	-0.0017	42.8111	-78.8503
9/27/2016 13:20	0	0	0	0	0	0	0	0.001	-0.0017	42.8111	-78.8503
9/27/2016 13:19	0	0	0	0	0	0	0	0.001	-0.0017	42.8111	-78.8503
9/27/2016 13:18	0	0	0	0	0	0	-0.005	0.001	-0.0019	42.8111	-78.8503
9/27/2016 13:17	0	0	0	0	0	0	0	0.001	-0.0019	42.8111	-78.8503
9/27/2016 13:16	0	0	0	0	0	0	0.011	0.001	-0.0022	42.8111	-78.8503
9/27/2016 13:15	0	0	0	0	0	0	-0.003	0.001	-0.0032	42.8111	-78.8503
9/27/2016 13:14	0	0	0	0	0	0	0	0.001	-0.0031	42.8111	-78.8503
9/27/2016 13:13	0	0	0	0	0	0	-0.007	0.001	-0.0032	42.8111	-78.8503
9/27/2016 13:12	0	0	0	0	0	0	-0.004	0.001	-0.0031	42.8111	-78.8503
9/27/2016 13:11	0	0	0	0	0	0	0	0.001	-0.003	42.8111	-78.8503
9/27/2016 13:10	0	0	0	0	0	0	-0.002	0.001	-0.0034	42.8111	-78.8503
9/27/2016 13:09	0	0	0	0	0	0	-0.005	0.001	-0.0032	42.8111	-78.8503
9/27/2016 13:08	0	0	0	0	0	0	-0.002	0.001	-0.0031	42.8111	-78.8503
9/27/2016 13:07	0	0	0	0	0	0	-0.005	0.001	-0.0032	42.8111	-78.8503
9/27/2016 13:06	0	0	0	0	0	0	-0.004	0.001	-0.0031	42.8111	-78.8503
9/27/2016 13:05	0	0	0	0	0	0	0	0.001	-0.0031	42.8111	-78.8503
9/27/2016 13:03							-0.006	0.001	-0.0034	42.8111	-78.8503
9/27/2016 13:02	0	0	0	0	0	0	-0.004	0.001	-0.0033	42.8111	-78.8503
9/27/2016 13:01	0	0	0	0	0	0	-0.003	0.001	-0.0033	42.8111	-78.8503
9/27/2016 13:00	0	0	0	0	0	0	-0.002	0.001	-0.0032	42.8111	-78.8503
9/27/2016 12:59	0	0	0	0	0	0	-0.001	0.001	-0.0032	42.8111	-78.8503
9/27/2016 12:58	0	0	0	0	0	0	-0.005	0.001	-0.0029	42.8111	-78.8503
9/27/2016 12:57	0	0	0	0	0	0	-0.003	0.001	-0.0027	42.8111	-78.8503
9/27/2016 12:56	0	0	0	0	0	0	-0.005	0.001	-0.0027	42.8111	-78.8503
9/27/2016 12:55	0	0	0	0	0	0	0	0.001	-0.0026	42.8111	-78.8503
9/27/2016 12:54	0	0	0	0	0	0	-0.004	0.001	-0.003	42.8111	-78.8503
9/27/2016 12:53	0	0	0	0	0	0	-0.003	0.001	-0.0029	42.8111	-78.8503
9/27/2016 12:52	0	0	0	0	0	0	-0.003	0.001	-0.0029	42.8111	-78.8503
9/27/2016 12:51	0	0	0	0	0	0	-0.004	0.001	-0.0027	42.8111	-78.8503

COMMUNITY AIR MONITORING

PERIODIC REVIEW REPORT

Tecumseh Phase III Business Park: Sites III-5 & III-6
Lackawanna, New York

Timestamp (GMT-4)	Low (ppm)	Peak (ppm)	STEL (ppm)	TWA (ppm)	VOC (ppm)	VOC (Avg15) (ppm)	Mass Conc. Total (mg/m³)	TWA (mg/m³)	Mass Conc. Total (Avg15) (mg/m³)	Latitude	Longitude
9/27/2016 12:50	0	0	0	0	0	0	-0.006	0.001	-0.002	42.8111	-78.8503
9/27/2016 12:49	0	0	0	0	0	0	-0.002	0.001	-0.0017	42.8111	-78.8503
9/27/2016 12:48	0	0	0	0	0	0	-0.005	0.001	-0.0019	42.8111	-78.8503
9/27/2016 12:47	0	0	0	0	0	0	-0.003	0.001	-0.0016	42.8111	-78.8503
9/27/2016 12:46	0	0	0	0	0	0	-0.002	0.001	-0.0015	42.8111	-78.8503
9/27/2016 12:45	0	0	0	0	0	0	-0.002	0.001	-0.0016	42.8111	-78.8503
9/27/2016 12:44	0	0	0	0	0	0	0.004	0.001	-0.0015	42.8111	-78.8503
9/27/2016 12:43	0	0	0	0	0	0	-0.002	0.001	-0.0017	42.8111	-78.8503
9/27/2016 12:42	0	0	0	0	0	0	-0.003	0.001	-0.0017	42.8111	-78.8503
9/27/2016 12:41	0	0	0	0	0	0	-0.004	0.001	-0.0017	42.8111	-78.8503
9/27/2016 12:40	0	0	0	0	0	0	-0.006	0.001	-0.0017	42.8111	-78.8503
9/27/2016 12:39	0	0	0	0	0	0	-0.003	0.001	-0.0016	42.8111	-78.8503
9/27/2016 12:38	0	0	0	0	0	0	-0.002	0.001	-0.0015	42.8111	-78.8503
9/27/2016 12:37	0	0	0	0	0	0	0	0.001	-0.0015	42.8111	-78.8503
9/27/2016 12:36	0	0	0	0	0	0	0.006	0.001	-0.0017	42.8111	-78.8503
9/27/2016 12:35	0	0	0	0	0	0	-0.001	0.001	-0.0025	42.8111	-78.8503
9/27/2016 12:34	0	0	0	0	0	0	-0.005	0.001	-0.0025	42.8111	-78.8503
9/27/2016 12:33	0	0	0	0	0	0	-0.001	0.001	-0.0025	42.8111	-78.8503
9/27/2016 12:32	0	0	0	0	0	0	-0.002	0.001	-0.0026	42.8111	-78.8503
9/27/2016 12:31	0	0	0	0	0	0	-0.003	0.001	-0.0028	42.8112	-78.8503
9/27/2016 12:30	0	0	0	0	0	0	0	0.001	-0.003	42.8112	-78.8503
9/27/2016 12:29	0	0	0	0	0	0	0.001	0.001	-0.0031	42.8111	-78.8503
9/27/2016 12:28	0	0	0	0	0	0	-0.003	0.001	-0.0032	42.8111	-78.8503
9/27/2016 12:27	0	0	0	0	0	0	-0.003	0.001	-0.0033	42.8111	-78.8503
9/27/2016 12:26	0	0	0	0	0	0	-0.004	0.001	-0.0035	42.8111	-78.8503
9/27/2016 12:25	0	0	0	0	0	0	-0.004	0.001	-0.0032	42.8111	-78.8503
9/27/2016 12:24	0	0	0	0	0	0	-0.001	0.001	-0.0032	42.8111	-78.8503
9/27/2016 12:23	0	0	0	0	0	0	-0.003	0.001	-0.0033	42.8111	-78.8503
9/27/2016 12:22	0	0	0	0	0	0	-0.003	0.001	-0.0034	42.8111	-78.8503
9/27/2016 12:21	0	0	0	0	0	0	-0.005	0.001	-0.0033	42.8111	-78.8503
9/27/2016 12:20	0	0	0	0	0	0	-0.001	0.001	-0.0029	42.8111	-78.8503
9/27/2016 12:19	0	0	0	0	0	0	-0.005	0.001	-0.0019	42.8111	-78.8503
9/27/2016 12:18	0	0	0	0	0	0	-0.003	0.001	-0.0017	42.8111	-78.8503
9/27/2016 12:17	0	0	0	0	0	0	-0.005	0.001	-0.0019	42.8111	-78.8503
9/27/2016 12:16	0	0	0	0	0	0	-0.006	0.001	-0.0017	42.8111	-78.8503
9/27/2016 12:15	0	0	0	0	0	0	-0.002	0.001	-0.0015	42.8111	-78.8503
9/27/2016 12:14	0	0	0	0	0	0	0	0.001	-0.0017	42.8111	-78.8503
9/27/2016 12:13	0	0	0	0	0	0	-0.005	0.001	-0.0019	42.8111	-78.8503
9/27/2016 12:12	0	0	0	0	0	0	-0.005	0.001	-0.0019	42.8111	-78.8503
9/27/2016 12:11	0	0	0	0	0	0	0	0.001	-0.0017	42.8111	-78.8503
9/27/2016 12:10	0	0	0	0	0	0	-0.004	0.001	-0.0019	42.8111	-78.8503
9/27/2016 12:09	0	0	0	0	0	0	-0.003	0.001	-0.0019	42.8111	-78.8503
9/27/2016 12:08	0	0	0	0	0	0	-0.004	0.001	-0.0021	42.8111	-78.8503
9/27/2016 12:07	0	0	0	0	0	0	-0.001	0.001	-0.0021	42.8111	-78.8503
9/27/2016 12:06	0	0	0	0	0	0	0	0.001	-0.0023	42.8111	-78.8503
9/27/2016 12:05	0	0	0	0	0	0	0.015	0.001	-0.0025	42.8111	-78.8503
9/27/2016 12:04	0	0	0	0	0	0	-0.003	0.001	-0.0039	42.8111	-78.8503
9/27/2016 12:03	0	0	0	0	0	0	-0.005	0.001	-0.0035	42.8111	-78.8503
9/27/2016 12:02	0	0	0	0	0	0	-0.003	0.001	-0.0032	42.8111	-78.8503
9/27/2016 12:01	0	0	0	0	0	0	-0.003	0.001	-0.003	42.8112	-78.8503
9/27/2016 12:00	0	0	0	0	0	0	-0.005	0.001	-0.003	42.8111	-78.8503
9/27/2016 11:59	0	0	0	0	0	0	-0.003	0.001	-0.0028	42.8111	-78.8503
9/27/2016 11:58	0	0	0	0	0	0	-0.005	0.001	-0.0028	42.8111	-78.8503

COMMUNITY AIR MONITORING

PERIODIC REVIEW REPORT

Tecumseh Phase III Business Park: Sites III-5 & III-6
Lackawanna, New York

Timestamp (GMT-4)	Low (ppm)	Peak (ppm)	STEL (ppm)	TWA (ppm)	VOC (ppm)	VOC (Avg15) (ppm)	Mass Conc. Total (mg/m³)	TWA (mg/m³)	Mass Conc. Total (Avg15) (mg/m³)	Latitude	Longitude
9/27/2016 11:57	0	0	0	0	0	0	-0.002	0.001	-0.0026	42.8111	-78.8503
9/27/2016 11:56	0	0	0	0	0	0	-0.002	0.001	-0.0027	42.8111	-78.8503
9/27/2016 11:55	0	0	0	0	0	0	-0.004	0.001	-0.0029	42.8111	-78.8503
9/27/2016 11:54	0	0	0	0	0	0	-0.006	0.001	-0.003	42.8111	-78.8503
9/27/2016 11:53	0	0	0	0	0	0	-0.004	0.001	-0.0028	42.8111	-78.8503
9/27/2016 11:52	0	0	0	0	0	0	-0.004	0.001	-0.0026	42.8111	-78.8503
9/27/2016 11:51	0	0	0	0	0	0	-0.004	0.001	-0.0027	42.8111	-78.8503
9/27/2016 11:50	0	0	0	0	0	0	-0.005	0.001	-0.0023	42.8111	-78.8503
9/27/2016 11:49	0	0	0	0	0	0	0.002	0.001	-0.0022	42.8111	-78.8503
9/27/2016 11:48	0	0	0	0	0	0	0	0.001	-0.0027	42.8111	-78.8503
9/27/2016 11:47	0	0	0	0	0	0	0	0.001	-0.0028	42.8111	-78.8503
9/27/2016 11:46	0	0	0	0	0	0	-0.003	0.001	-0.0032	42.8111	-78.8503
9/27/2016 11:45	0	0	0	0	0	0	-0.002	0.001	-0.0027	42.8111	-78.8503
9/27/2016 11:41	0	0	0	0	0	0	-0.005	0.001	-0.0024	42.8111	-78.8503
9/27/2016 11:40	0	0	0	0	0	0	-0.005	0.001	-0.0022	42.8111	-78.8503
9/27/2016 11:39	0	0	0	0	0	0	-0.003	0.001	-0.0015	42.8111	-78.8503
9/27/2016 11:38	0	0	0	0	0	0	-0.002	0.001	-0.0013	42.8111	-78.8503
9/27/2016 11:37	0	0	0	0	0	0	-0.005	0.001	-0.0015	42.8111	-78.8503
9/27/2016 11:36	0	0	0	0	0	0	0	0.001	-0.0011	42.8111	-78.8503
9/27/2016 11:35	0	0	0	0	0	0	-0.003	0.001	-0.0013	42.8111	-78.8503
9/27/2016 11:34	0	0	0	0	0	0	-0.004	0.001	-0.0009	42.8111	-78.8503
9/27/2016 11:33	0	0	0	0	0	0	-0.002	0.001	-0.0007	42.8111	-78.8503
9/27/2016 11:32	0	0	0	0	0	0	-0.004	0.001	-0.0008	42.8111	-78.8503
9/27/2016 11:31	0	0	0	0	0	0	0.003	0.001	-0.0007	42.8111	-78.8503
9/27/2016 11:30	0	0	0	0	0	0	-0.003	0.001	-0.001	42.8111	-78.8503
9/27/2016 11:29	0	0	0	0	0	0	-0.002	0.001	-0.0009	42.8111	-78.8503
9/27/2016 11:28	0	0	0	0	0	0	0	0.001	-0.0004	42.8111	-78.8503
9/27/2016 11:27	0	0	0	0	0	0	-0.003	0.001	-0.0005	42.8111	-78.8503
9/27/2016 11:26	0	0	0	0	0	0	0	0.001	-0.0005	42.8111	-78.8503
9/27/2016 11:25	0	0	0	0	0	0	0.006	0.001	-0.0005	42.8111	-78.8503
9/27/2016 11:24	0	0	0	0	0	0	-0.001	0.001	-0.0011	42.8111	-78.8503
9/27/2016 11:23	0	0	0	0	0	0	-0.004	0.001	-0.0012	42.8111	-78.8503
9/27/2016 11:22	0	0	0	0	0	0	0	0.001	-0.0011	42.8111	-78.8503
9/27/2016 11:21	0	0	0	0	0	0	-0.002	0.001	-0.0012	42.8111	-78.8503
9/27/2016 11:20	0	0	0	0	0	0	0.003	0.001	-0.0012	42.8111	-78.8503
9/27/2016 11:19	0	0	0	0	0	0	-0.001	0.001	-0.0015	42.8111	-78.8503
9/27/2016 11:18	0	0	0	0	0	0	-0.004	0.001	-0.0014	42.8111	-78.8503
9/27/2016 11:17	0	0	0	0	0	0	-0.003	0.001	-0.0012	42.8111	-78.8503
9/27/2016 11:16							-0.001	0.001	-0.0011	42.8111	-78.8503
9/27/2016 11:15	0	0	0	0	0	0	-0.002	0.001	-0.001	42.8111	-78.8503
9/27/2016 11:14	0	0	0	0	0	0	0.006	0.001	-0.001	42.8111	-78.8503
9/27/2016 11:13	0	0	0	0	0	0	-0.002	0.001	-0.0015	42.8111	-78.8503
9/27/2016 11:12	0	0	0	0	0	0	-0.003	0.001	-0.0009	42.8111	-78.8503
9/27/2016 11:11	0	0	0	0	0	0	0	0.001	-0.0008	42.8111	-78.8503
9/27/2016 11:10	0	0	0	0	0	0	-0.002	0.001	-0.001	42.8111	-78.8503
9/27/2016 11:09	0	0	0	0	0	0	-0.003	0.001	-0.0011	42.8111	-78.8503
9/27/2016 11:08	0	0	0	0	0	0	-0.002	0.001	-0.001	42.8111	-78.8503
9/27/2016 11:07	0	0	0	0	0	0	-0.002	0.001	-0.0009	42.8111	-78.8503
9/27/2016 11:06	0	0	0	0	0	0	-0.002	0.001	-0.0009	42.8111	-78.8503
9/27/2016 11:05	0	0	0	0	0	0	-0.001	0.001	-0.0008	42.8111	-78.8503
9/27/2016 11:04	0	0	0	0	0	0	0	0.001	-0.0007	42.8111	-78.8503
9/27/2016 11:03	0	0	0	0	0	0	-0.001	0.001	-0.0009	42.8111	-78.8503
9/27/2016 11:02	0	0	0	0	0	0	-0.001	0.001	-0.0009	42.8111	-78.8503

COMMUNITY AIR MONITORING

PERIODIC REVIEW REPORT

Tecumseh Phase III Business Park: Sites III-5 & III-6
Lackawanna, New York

Timestamp (GMT-4)	Low (ppm)	Peak (ppm)	STEL (ppm)	TWA (ppm)	VOC (ppm)	VOC (Avg15) (ppm)	Mass Conc. Total (mg/m³)	TWA (mg/m³)	Mass Conc. Total (Avg15) (mg/m³)	Latitude	Longitude
9/27/2016 11:01	0	0	0	0	0	0	0	0.001	-0.0009	42.8111	-78.8503
9/27/2016 11:00	0	0	0	0	0	0	-0.002	0.001	-0.0009	42.8111	-78.8503
9/27/2016 10:59	0	0	0	0	0	0	-0.002	0.001	-0.0007	42.8111	-78.8503
9/27/2016 10:58	0	0	0	0	0	0	0.008	0.001	-0.0007	42.8111	-78.8503
9/27/2016 10:57	0	0	0	0	0	0	-0.002	0.001	-0.0013	42.8111	-78.8503
9/27/2016 10:56	0	0	0	0	0	0	-0.003	0.001	-0.0013	42.8111	-78.8503
9/27/2016 10:55	0	0	0	0	0	0	-0.004	0.001	-0.0011	42.8111	-78.8503
9/27/2016 10:54	0	0	0	0	0	0	-0.001	0.001	-0.0008	42.8111	-78.8503
9/27/2016 10:53	0	0	0	0	0	0	-0.001	0.001	-0.0009	42.8111	-78.8503
9/27/2016 10:52	0	0	0	0	0	0	-0.001	0.001	-0.0007	42.8111	-78.8503
9/27/2016 10:51	0	0	0	0	0	0	-0.001	0.001	-0.0006	42.8111	-78.8503
9/27/2016 10:50	0	0	0	0	0	0	0	0.001	-0.0005	42.8111	-78.8503
9/27/2016 10:49	0	0	0	0	0	0	-0.002	0.001	-0.0007	42.8111	-78.8503
9/27/2016 10:48	0	0	0	0	0	0	-0.001	0.001	-0.0006	42.8111	-78.8503
9/27/2016 10:47	0	0	0	0	0	0	-0.001	0.001	-0.0005	42.8111	-78.8503
9/27/2016 10:46	0	0	0	0	0	0	0	0.001	-0.0004	42.8111	-78.8503
9/27/2016 10:45	0	0	0	0	0	0	0	0.001	-0.0004	42.8111	-78.8503
9/27/2016 10:44	0	0	0	0	0	0	-0.001	0.001	-0.0004	42.8111	-78.8503
9/27/2016 10:43	0	0	0	0	0	0	-0.001	0.001	-0.0003	42.8111	-78.8503
9/27/2016 10:42	0	0	0	0	0	0	-0.002	0.001	-0.0001	42.8111	-78.8503
9/27/2016 10:41	0	0	0	0	0	0	0	0.001	0.0004	42.8111	-78.8503
9/27/2016 10:40	0	0	0	0	0	0	0	0.001	0.0005	42.8111	-78.8503
9/27/2016 10:39	0	0	0	0	0	0	-0.002	0.001	0.0005	42.8111	-78.8503
9/27/2016 10:38	0	0	0	0	0	0	0.002	0.001	0.0007	42.8111	-78.8503
9/27/2016 10:37	0	0	0	0	0	0	0	0.001	0.0007	42.8111	-78.8503
9/27/2016 10:36	0	0	0	0	0	0	0	0.001	0.0007	42.8111	-78.8503
9/27/2016 10:35	0	0	0	0	0	0	-0.002	0.001	0.0011	42.8111	-78.8503
9/27/2016 10:34	0	0	0	0	0	0	-0.001	0.001	0.0012	42.8111	-78.8503
9/27/2016 10:33	0	0	0	0	0	0	0	0.001	0.0013	42.8111	-78.8503
9/27/2016 10:32	0	0	0	0	0	0	0.001	0.001	0.0023	42.8111	-78.8503
9/27/2016 10:31	0	0	0	0	0	0	0	0.001	0.0023	42.8111	-78.8503
9/27/2016 10:30	0	0	0	0	0	0	0	0.001	0.0023	42.8111	-78.8503
9/27/2016 10:29	0	0	0	0	0	0	0	0.001	0.0027	42.8111	-78.8503
9/27/2016 10:28	0	0	0	0	0	0	0.003	0.001	0.0029	42.8111	-78.8503
9/27/2016 10:27	0	0	0	0	0	0	0.005	0.001	0.0037	42.8111	-78.8503
9/27/2016 10:26	0	0	0	0	0	0	0.002	0.001	0.0035	42.8111	-78.8503
9/27/2016 10:25	0	0	0	0	0	0	0	0.001	0.0035	42.8111	-78.8503
9/27/2016 10:24	0	0	0	0	0	0	0.001	0.001	0.0039	42.8111	-78.8503
9/27/2016 10:23	0	0	0	0	0	0	0.001	0.001	0.0038	42.8111	-78.8503
9/27/2016 10:22	0	0	0	0	0	0	0	0.001	0.0037	42.8111	-78.8503
9/27/2016 10:21	0	0	0	0	0	0	0.006	0.001	0.0037	42.8112	-78.8503
9/27/2016 10:20	0	0	0	0	0	0	0	0.001	0.0033	42.8111	-78.8503
9/27/2016 10:19	0	0	0	0	0	0	0.001	0.001	0.0035	42.8111	-78.8503
9/27/2016 10:18	0	0	0	0	0	0	0.015	0.001	0.0037	42.8111	-78.8503
9/27/2016 10:17	0	0	0	0	0	0	0	0.001	0.0027	42.8111	-78.8503
9/27/2016 10:16	0	0	0	0	0	0	0	0.001	0.0031	42.8111	-78.8503
9/27/2016 10:15	0	0	0	0	0	0	0.007	0.001	0.0032	42.8111	-78.8503
9/27/2016 10:14	0	0	0	0	0	0	0.002	0.001	0.0027	42.8111	-78.8503
9/27/2016 10:13	0	0	0	0	0	0	0.015	0.001	0.0027	42.8111	-78.8503
9/27/2016 10:12	0	0	0	0	0	0	0.003	0.001	0.0017	42.8111	-78.8503
9/27/2016 10:11	0	0	0	0	0	0	0.001	0.001	0.0015	42.8111	-78.8503
9/27/2016 10:10	0	0	0	0	0	0	0.006	0.001	0.0015	42.8111	-78.8503
9/27/2016 10:09	0	0	0	0	0	0	0	0.001	0.0011	42.8111	-78.8503

COMMUNITY AIR MONITORING

PERIODIC REVIEW REPORT

Tecumseh Phase III Business Park: Sites III-5 & III-6
Lackawanna, New York

Timestamp (GMT-4)	Low (ppm)	Peak (ppm)	STEL (ppm)	TWA (ppm)	VOC (ppm)	VOC (Avg15) (ppm)	Mass Conc. Total (mg/m³)	TWA (mg/m³)	Mass Conc. Total (Avg15) (mg/m³)	Latitude	Longitude
9/27/2016 10:08	0	0	0	0	0	0	0	0.001	0.0012	42.8111	-78.8503
9/27/2016 10:07	0	0	0	0	0	0	0	0.001	0.0013	42.8111	-78.8503
9/27/2016 10:06	0	0	0	0	0	0	0	0.001	0.0013	42.8112	-78.8503
9/27/2016 10:05	0	0	0	0	0	0	0.003	0.001	0.0013	42.8111	-78.8503
9/27/2016 10:04	0	0	0	0	0	0	0.003	0.001	0.0011	42.8111	-78.8503
9/27/2016 10:03	0	0	0	0	0	0	0.001	0.001	0.0008	42.8111	-78.8503
9/27/2016 10:02	0	0	0	0	0	0	0.005	0.001	0.0012	42.8112	-78.8503
9/27/2016 10:01	0	0	0	0	0	0	0.002	0.001	0.0036	42.8111	-78.8503
9/27/2016 10:00	0	0	0	0	0	0	0	0.001	0.0038	42.8111	-78.8503
9/27/2016 9:59	0	0	0	0	0	0	0.002	0.001	0.0038	42.8111	-78.8503
9/27/2016 9:58	0	0	0	0	0	0	0	0.001	0.0037	42.8112	-78.8503
9/27/2016 9:57	0	0	0	0	0	0	0	0.001	0.0037	42.8111	-78.8503
9/27/2016 9:56	0	0	0	0	0	0	0.001	0.001	0.0037	42.8112	-78.8503
9/27/2016 9:55	0	0	0	0	0	0	0	0.001	0.0036	42.8111	-78.8503
9/27/2016 9:53	0	0	0	0	0	0					
9/27/2016 9:52	0	0	0	0	0	0	0	0.001	0.0037	42.8111	-78.8503
9/27/2016 9:51	0	0	0	0	0	0	0	0.001	0.0037	42.8111	-78.8503
9/27/2016 9:50	0	0	0	0	0	0	0	0.001	0.0037	42.8112	-78.8503
9/27/2016 9:49	0	0	0	0	0	0	0	0.001	0.0037	42.8111	-78.8503
9/27/2016 9:48	0	0	0	0	0	0	0.005	0.001	0.0037	42.8111	-78.8503
9/27/2016 9:47	0	0	0	0	0	0	0.037	0.001	0.0033	42.8111	-78.8503
9/27/2016 9:46	0	0	0	0	0	0	0.004	0.001	0.0008	42.8111	-78.8503
9/27/2016 9:45	0	0	0	0	0	0	0	0.001	0.0005	42.8111	-78.8503
9/27/2016 9:44	0	0	0	0	0	0	0.001	0.001	0.0005	42.8111	-78.8503
9/27/2016 9:43	0	0	0	0	0	0	0	0.001	0.0006	42.8111	-78.8503
9/27/2016 9:42	0	0	0	0	0	0	0	0.001	0.0006	42.8111	-78.8503
9/27/2016 9:41	0	0	0	0	0	0	0	0.001	0.0006	42.8111	-78.8503
9/27/2016 9:40	0	0	0	0	0	0	0.006	0.001	0.0009	42.8111	-78.8503
9/27/2016 9:39	0	0	0	0	0	0	0.003	0.001	0.0005	42.8111	-78.8503
9/27/2016 9:38	0	0	0	0	0	0	0	0.001	0.0008	42.8111	-78.8503
9/27/2016 9:37	0	0	0	0	0	0	-0.001	0.001	0.0008	42.8111	-78.8503
9/27/2016 9:36	0	0	0	0	0	0	0	0.001	0.0009	42.8111	-78.8503
9/27/2016 9:35	0	0	0	0	0	0	0	0.001	0.0018	42.8112	-78.8503
9/27/2016 9:34	0	0	0	0	0	0	0	0.001	0.002	42.8111	-78.8503
9/27/2016 9:33	0	0	0	0	0	0	-0.001	0.001	0.002	42.8111	-78.8503
9/27/2016 9:32	0	0	0	0	0	0	0	0.001	0.0021	42.8112	-78.8503
9/27/2016 9:31	0	0	0	0	0	0	0	0.001	0.0021	42.8111	-78.8503
9/27/2016 9:30	0	0	0	0	0	0	0	0.001	0.0021	42.8111	-78.8503
9/27/2016 9:29	0	0	0	0	0	0	0.002	0.001	0.0023	42.8112	-78.8503
9/27/2016 9:28	0	0	0	0	0	0	0	0.001	0.0023	42.8111	-78.8503
9/27/2016 9:27	0	0	0	0	0	0	0	0.001	0.0023	42.8111	-78.8503
9/27/2016 9:26	0	0	0	0	0	0	0.004	0.001	0.0024	42.8111	-78.8503
9/27/2016 9:25	0	0	0	0	0	0	0.001	0.001	0.0021	42.8112	-78.8503
9/27/2016 9:24	0	0	0	0	0	0	0.007	0.001	0.0021	42.8111	-78.8503
9/27/2016 9:23	0	0	0	0	0	0	0	0.001	0.0016	42.8111	-78.8503
9/27/2016 9:22	0	0	0	0	0	0	0	0.001	0.0016	42.8111	-78.8503
9/27/2016 9:21	0	0	0	0	0	0	0.014	0	0.0016	42.8111	-78.8503
9/27/2016 9:20	0	0	0	0	0	0	0.003	0	0.0008	42.8112	-78.8503
9/27/2016 9:19	0	0	0	0	0	0	0	0	0.0011	42.8111	-78.8503
9/27/2016 9:18	0	0	0	0	0	0	0	0	0.0011	42.8111	-78.8503
9/27/2016 9:17	0	0	0	0	0	0	0.001	0	0.0013	42.8111	-78.8503
9/27/2016 9:16	0	0	0	0	0	0	0	0	0.0012	42.8112	-78.8503
9/27/2016 9:15	0	0	0	0	0	0	0.003	0	0.0015	42.8111	-78.8503

COMMUNITY AIR MONITORING

PERIODIC REVIEW REPORT

Tecumseh Phase III Business Park: Sites III-5 & III-6
Lackawanna, New York

Timestamp (GMT-4)	Low (ppm)	Peak (ppm)	STEL (ppm)	TWA (ppm)	VOC (ppm)	VOC (Avg15) (ppm)	Mass Conc. Total (mg/m³)	TWA (mg/m³)	Mass Conc. Total (Avg15) (mg/m³)	Latitude	Longitude
9/27/2016 9:14	0	0	0	0	0	0	0.002	0	0.0013	42.8111	-78.8503
9/27/2016 9:13	0	0	0	0	0	0	0	0	0.0012	42.8112	-78.8503
9/27/2016 9:12	0	0	0	0	0	0	0.001	0	0.0012	42.8111	-78.8503
9/27/2016 9:11	0	0	0	0	0	0	0	0	0.0011	42.8111	-78.8503
9/27/2016 9:10	0	0	0	0	0	0	0	0	0.0011	42.8112	-78.8503
9/27/2016 9:09	0	0	0	0	0	0	0	0	0.0011	42.8111	-78.8503
9/27/2016 9:08	0	0	0	0	0	0	0	0	0.0013	42.8111	-78.8503
9/27/2016 9:07	0	0	0	0	0	0	0	0	0.0015	42.8112	-78.8503
9/27/2016 9:06	0	0	0	0	0	0	0.002	0	0.0017	42.8111	-78.8503
9/27/2016 9:05	0	0	0	0	0	0	0.008	0	0.0017	42.8112	-78.8503
9/27/2016 9:04	0	0	0	0	0	0	0	0	0.0012	42.8112	-78.8503
9/27/2016 9:03	0	0	0	0	0	0	0.002	0	0.0013	42.8112	-78.8503
9/27/2016 9:02	0	0	0	0	0	0	0	0	0.0011	42.8112	-78.8503
9/27/2016 9:01	0	0	0	0	0	0	0.004	0	0.0011	42.8112	-78.8503
9/27/2016 9:00	0	0	0	0	0	0	0.001	0	0.0009	42.8111	-78.8503
9/27/2016 8:59	0	0	0	0	0	0	0	0	0.001	42.8111	-78.8503
9/27/2016 8:58	0	0	0	0	0	0	0	0	0.0012	42.8111	-78.8503
9/27/2016 8:57	0	0	0	0	0	0	0	0	0.0013	42.8111	-78.8503
9/27/2016 8:56	0	0	0	0	0	0	0	0	0.0019	42.8112	-78.8503
9/27/2016 8:55	0	0	0	0	0	0	0	0	0.0024	42.8112	-78.8503
9/27/2016 8:54	0	0	0	0	0	0	0.003	0	0.0027	42.8112	-78.8503
9/27/2016 8:53	0	0	0	0	0	0	0.002	0	0.0025	42.8111	-78.8503
9/27/2016 8:52	0	0	0	0	0	0	0.004	0	0.0026	42.8111	-78.8503
9/27/2016 8:51	0	0	0	0	0	0	0.002	0	0.0024	42.8112	-78.8503
9/27/2016 8:50	0	0	0	0	0	0	0	0	0.0024	42.8112	-78.8503
9/27/2016 8:49	0	0	0	0	0	0	0.001	0	0.0025	42.8112	-78.8503
9/27/2016 8:48	0	0	0	0	0	0	0	0	0.0029	42.8112	-78.8503
9/27/2016 8:47	0	0	0	0	0	0	0	0	0.003	42.8111	-78.8503
9/27/2016 8:46	0	0	0	0	0	0	0.001	0	0.0031	42.8111	-78.8503
9/27/2016 8:45	0	0	0	0	0	0	0.002	0	0.0036	42.8111	-78.8503
9/27/2016 8:44	0	0	0	0	0	0	0.003	0	0.0037	42.8111	-78.8503
9/27/2016 8:43	0	0	0	0	0	0	0.001	0	0.0037	42.8111	-78.8503
9/27/2016 8:42	0	0	0	0	0	0	0.01	0	0.0037	42.8111	-78.8503
9/27/2016 8:41	0	0	0	0	0	0	0.007	0	0.0031	42.8111	-78.8503
9/27/2016 8:40	0	0	0	0	0	0	0.004	0	0.0029	42.8112	-78.8503
9/27/2016 8:39	0	0	0	0	0	0	0.001	0	0.0028	42.8111	-78.8503
9/27/2016 8:38	0	0	0	0	0	0	0.003	0	0.0029	42.8111	-78.8503
9/27/2016 8:37	0	0	0	0	0	0	0.001	0	0.0029	42.8111	-78.8503
9/27/2016 8:36	0	0	0	0	0	0	0.002	0	0.0031	42.8111	-78.8503
9/27/2016 8:35	0	0	0	0	0	0	0.002	0	0.0033	42.8111	-78.8503
9/27/2016 8:34	0	0	0	0	0	0	0.007	0	0.0033	42.8111	-78.8503
9/27/2016 8:33	0	0	0	0	0	0	0.001	0	0.003	42.8111	-78.8503
9/27/2016 8:32	0	0	0	0	0	0	0.001	0	0.0031	42.8111	-78.8503
9/27/2016 8:31	0	0	0	0	0	0	0.009	0	0.0031	42.8111	-78.8503
9/27/2016 8:30	0	0	0	0	0	0	0.003	0	0.0026	42.8111	-78.8503
9/27/2016 8:29	0	0	0	0	0	0	0.003	0	0.0026	42.8112	-78.8503
9/27/2016 8:28	0	0	0	0	0	0	0.002	0	0.0025	42.8111	-78.8503
9/27/2016 8:27	0	0	0	0	0	0	0.001	0	0.0025	42.8111	-78.8503
9/27/2016 8:26	0	0	0	0	0	0	0.003	0	0.0026	42.8111	-78.8503
9/27/2016 8:25	0	0	0	0	0	0	0.003	0	0.0025	42.8111	-78.8503
9/27/2016 8:24	0	0	0	0	0	0	0.002	0	0.0025	42.8111	-78.8503
9/27/2016 8:23	0	0	0	0	0	0	0.004	0	0.0025	42.8111	-78.8503
9/27/2016 8:22	0	0	0	0	0	0	0.004	0	0.0024	42.8111	-78.8503

COMMUNITY AIR MONITORING

PERIODIC REVIEW REPORT

Tecumseh Phase III Business Park: Sites III-5 & III-6
Lackawanna, New York

Timestamp (GMT-4)	Low (ppm)	Peak (ppm)	STEL (ppm)	TWA (ppm)	VOC (ppm)	VOC (Avg15) (ppm)	Mass Conc. Total (mg/m³)	TWA (mg/m³)	Mass Conc. Total (Avg15) (mg/m³)	Latitude	Longitude
9/27/2016 8:21	0	0	0	0	0	0	0.004	0	0.0022	42.8112	-78.8504
9/27/2016 8:20	0	0	0	0	0	0	0.002	0	0.002	42.8111	-78.8503
9/27/2016 8:19	0	0	0	0	0	0	0.003	0	0.002	42.8111	-78.8503
9/27/2016 8:18	0	0	0	0	0	0	0.002	0	0.0018	42.8111	-78.8503
9/27/2016 8:17	0	0	0	0	0	0	0.001	0	0.0018	42.8112	-78.8503
9/27/2016 8:16	0	0	0	0	0	0	0.002	0	0.002	42.8111	-78.8503
9/27/2016 8:15	0	0	0	0	0	0	0.003	0	0.002	42.8111	-78.8503
9/27/2016 8:14	0	0	0	0	0	0	0.002	0	0.0015	42.8111	-78.8503
9/27/2016 8:13	0	0	0	0	0	0	0.001	0	0.001	42.8111	-78.8503
9/26/2016 14:47	0	0.046	0	0.002	0	0	0.018	0.01	0.0172	42.8152	-78.8453
9/26/2016 14:46	0	0.046	0	0.002	0	0	0.018	0.01	0.017	42.8153	-78.8453
9/26/2016 14:45	0	0.046	0	0.002	0	0	0.018	0.01	0.0173	42.8152	-78.8458
9/26/2016 14:44	0	0.046	0	0.002	0	0	0.018	0.01	0.0177	42.825	-78.8504
9/26/2016 14:43	0	0.046	0	0.002	0	0	0.018	0.01	0.0176	42.8237	-78.8503
9/26/2016 14:42	0	0.046	0	0.002	0	0	0.018	0.01	0.0178	42.8208	-78.8527
9/26/2016 14:41	0	0.046	0	0.002	0	0	0.018	0.01	0.0183	42.8158	-78.8518
9/26/2016 14:40	0	0.046	0	0.002	0	0	0.018	0.01	0.0178	42.8122	-78.8501
9/26/2016 14:38	0	0.046	0	0.002	0	0				42.8117	-78.8525
9/26/2016 14:37	0	0.046	0	0.002	0	0	0.018	0.01	0.0156	42.8117	-78.8525
9/26/2016 14:36	0	0.046	0	0.002	0	0	0.018	0.01	0.0149	42.8117	-78.8524
9/26/2016 14:35	0	0.046	0	0.002	0	0	0.009	0.01	0.014	42.8117	-78.8524
9/26/2016 14:34	0	0.046	0	0.002	0	0	0.006	0.01	0.0139	42.8117	-78.8524
9/26/2016 14:33	0	0.046	0	0.002	0	0	0.028	0.01	0.0139	42.8117	-78.8524
9/26/2016 14:32	0	0.046	0	0.002	0	0	0.016	0.01	0.0126	42.8117	-78.8525
9/26/2016 14:31	0	0.046	0	0.002	0	0	0.022	0.01	0.0118	42.8117	-78.8525
9/26/2016 14:30	0	0.046	0	0.002	0	0	0.023	0.01	0.0108	42.8117	-78.8524
9/26/2016 14:29	0	0.046	0	0.002	0	0	0.017	0.01	0.0101	42.8117	-78.8525
9/26/2016 14:28	0	0.046	0	0.002	0	0	0.02	0.009	0.0096	42.8117	-78.8525
9/26/2016 14:27	0	0.046	0	0.002	0	0	0.025	0.009	0.0088	42.8117	-78.8524
9/26/2016 14:26	0	0.046	0	0.002	0	0	0.012	0.009	0.0075	42.8117	-78.8524
9/26/2016 14:25	0	0.046	0	0.002	0	0	0.006	0.009	0.007	42.8117	-78.8525
9/26/2016 14:24	0	0.046	0	0.002	0	0	0.005	0.009	0.0077	42.8117	-78.8525
9/26/2016 14:23	0	0.046	0	0.002	0	0	0.009	0.009	0.0076	42.8117	-78.8525
9/26/2016 14:22	0	0.046	0	0.002	0	0	0.008	0.009	0.0076	42.8117	-78.8525
9/26/2016 14:21	0	0.046	0	0.002	0	0	0.004	0.009	0.0087	42.8117	-78.8525
9/26/2016 14:20	0	0.046	0	0.002	0	0	0.007	0.009	0.0091	42.8117	-78.8525
9/26/2016 14:19	0	0.046	0	0.002	0	0	0.007	0.009	0.0091	42.8117	-78.8525
9/26/2016 14:18	0	0.046	0	0.002	0	0	0.008	0.009	0.0088	42.8117	-78.8524
9/26/2016 14:17	0	0.046	0	0.002	0	0	0.004	0.009	0.0088	42.8117	-78.8524
9/26/2016 14:16	0	0.046	0	0.002	0	0	0.007	0.009	0.0088	42.8117	-78.8524
9/26/2016 14:15	0	0.046	0	0.002	0	0	0.013	0.009	0.0088	42.8117	-78.8524
9/26/2016 14:13										42.8117	-78.8525
9/26/2016 14:12	0	0.046	0	0.002	0	0	0.007	0.009	0.0078	42.8117	-78.8524
9/26/2016 14:11	0	0.046	0	0.002	0	0	0.006	0.009	0.0075	42.8117	-78.8524
9/26/2016 14:10	0	0.046	0	0.002	0	0	0.015	0.009	0.0076	42.8117	-78.8524
9/26/2016 14:09	0	0.046	0	0.002	0	0	0.004	0.009	0.0075	42.8117	-78.8524
9/26/2016 14:08	0	0.046	0	0.002	0	0	0.009	0.009	0.0076	42.8117	-78.8524
9/26/2016 14:07	0	0.046	0	0.002	0	0	0.022	0.009	0.0073	42.8117	-78.8524
9/26/2016 14:06	0	0.046	0	0.002	0	0	0.009	0.009	0.0062	42.8117	-78.8524
9/26/2016 14:05	0	0.046	0	0.002	0	0	0.007	0.009	0.0062	42.8117	-78.8525
9/26/2016 14:04	0	0.046	0	0.002	0	0	0.004	0.009	0.0062	42.8117	-78.8524
9/26/2016 14:03	0	0.046	0	0.002	0	0	0.007	0.009	0.0063	42.8117	-78.8525
9/26/2016 14:02	0	0.046	0	0.002	0	0	0.005	0.009	0.0063	42.8117	-78.8525

COMMUNITY AIR MONITORING

PERIODIC REVIEW REPORT

Tecumseh Phase III Business Park: Sites III-5 & III-6
Lackawanna, New York

Timestamp (GMT-4)	Low (ppm)	Peak (ppm)	STEL (ppm)	TWA (ppm)	VOC (ppm)	VOC (Avg15) (ppm)	Mass Conc. Total (mg/m³)	TWA (mg/m³)	Mass Conc. Total (Avg15) (mg/m³)	Latitude	Longitude
9/26/2016 14:01	0	0.046	0	0.002	0	0	0.006	0.009	0.0062	42.8117	-78.8525
9/26/2016 14:00	0	0.046	0	0.002	0	0	0.008	0.009	0.006	42.8117	-78.8525
9/26/2016 13:59	0	0.046	0	0.002	0	0	0.005	0.009	0.0056	42.8117	-78.8525
9/26/2016 13:58	0	0.046	0	0.002	0	0	0.003	0.009	0.0055	42.8117	-78.8525
9/26/2016 13:57	0	0.046	0	0.002	0	0	0.003	0.009	0.0053	42.8117	-78.8525
9/26/2016 13:56	0	0.046	0	0.002	0	0	0.007	0.009	0.0052	42.8117	-78.8525
9/26/2016 13:55	0	0.046	0	0.002	0	0	0.013	0.009	0.0054	42.8117	-78.8525
9/26/2016 13:54	0	0.046	0	0.002	0	0	0.006	0.009	0.0047	42.8117	-78.8525
9/26/2016 13:53	0	0.046	0	0.002	0	0	0.005	0.009	0.0048	42.8117	-78.8525
9/26/2016 13:52	0	0.046	0	0.002	0	0	0.005	0.009	0.0046	42.8117	-78.8525
9/26/2016 13:51	0	0.046	0	0.002	0	0	0.009	0.009	0.0045	42.8117	-78.8525
9/26/2016 13:50	0	0.046	0	0.002	0	0	0.007	0.009	0.0041	42.8117	-78.8525
9/26/2016 13:49	0	0.046	0	0.002	0	0	0.006	0.009	0.0039	42.8117	-78.8524
9/26/2016 13:48	0	0.046	0	0.002	0	0	0.006	0.009	0.0038	42.8117	-78.8524
9/26/2016 13:47	0	0.046	0	0.002	0	0	0.004	0.009	0.0045	42.8117	-78.8525
9/26/2016 13:46	0	0.046	0	0.002	0	0	0.003	0.009	0.0046	42.8117	-78.8525
9/26/2016 13:45	0	0.046	0	0.002	0	0	0.002	0.009	0.0047	42.8117	-78.8525
9/26/2016 13:44	0	0.046	0	0.002	0	0	0.003	0.009	0.0051	42.8117	-78.8525
9/26/2016 13:43	0	0.046	0	0.002	0	0	0.001	0.009	0.0053	42.8117	-78.8525
9/26/2016 13:42	0	0.046	0	0.002	0	0	0.001	0.009	0.0056	42.8117	-78.8525
9/26/2016 13:41	0	0.046	0	0.002	0	0	0.01	0.009	0.0061	42.8117	-78.8525
9/26/2016 13:40	0	0.046	0	0.002	0	0	0.002	0.009	0.0065	42.8117	-78.8525
9/26/2016 13:39	0	0.046	0	0.002	0	0	0.008	0.009	0.0064	42.8117	-78.8525
9/26/2016 13:38	0	0.046	0	0.002	0	0	0.002	0.009	0.0063	42.8117	-78.8525
9/26/2016 13:37	0	0.046	0	0.002	0	0	0.003	0.009	0.0062	42.8117	-78.8525
9/26/2016 13:36	0	0.046	0	0.002	0	0	0.003	0.009	0.0088	42.8117	-78.8524
9/26/2016 13:35	0	0.046	0	0.002	0	0	0.005	0.009	0.0095	42.8117	-78.8525
9/26/2016 13:34	0	0.046	0	0.002	0	0	0.004	0.009	0.0099	42.8117	-78.8524
9/26/2016 13:33	0	0.046	0	0.002	0	0	0.017	0.009	0.0107	42.8117	-78.8524
9/26/2016 13:32	0	0.046	0	0.002	0	0	0.005	0.009	0.0099	42.8117	-78.8525
9/26/2016 13:31	0	0.046	0	0.002	0	0	0.004	0.009	0.0133	42.8117	-78.8525
9/26/2016 13:30	0	0.046	0	0.002	0	0	0.008	0.009	0.0136	42.8117	-78.8524
9/26/2016 13:29	0	0.046	0	0.002	0	0	0.007	0.009	0.0144	42.8117	-78.8525
9/26/2016 13:28	0	0.046	0	0.002	0	0	0.005	0.009	0.0152	42.8117	-78.8525
9/26/2016 13:27	0	0.046	0	0.002	0	0	0.009	0.009	0.0149	42.8117	-78.8524
9/26/2016 13:26	0	0.046	0	0.002	0	0	0.015	0.008	0.0143	42.8117	-78.8524
9/26/2016 13:25	0	0.046	0	0.002	0	0	0.001	0.008	0.0154	42.8117	-78.8524
9/26/2016 13:24	0	0.046	0	0.002	0	0	0.006	0.008	0.0158	42.8117	-78.8524
9/26/2016 13:23	0	0.046	0	0.002	0	0	0.001	0.008	0.0156	42.8117	-78.8524
9/26/2016 13:22	0	0.046	0	0.002	0	0	0.042	0.008	0.0175	42.8117	-78.8524
9/26/2016 13:21	0	0.046	0	0.002	0	0	0.014	0.008	0.0158	42.8117	-78.8524
9/26/2016 13:20	0	0.046	0	0.002	0	0	0.011	0.008	0.0152	42.8117	-78.8525
9/26/2016 13:19	0	0.046	0	0.002	0	0	0.016	0.008	0.0155	42.8117	-78.8525
9/26/2016 13:18	0	0.046	0	0.002	0	0	0.005	0.008	0.0165	42.8117	-78.8525
9/26/2016 13:17	0	0.046	0	0.002	0	0	0.056	0.008	0.0168	42.8117	-78.8525
9/26/2016 13:16	0	0.046	0	0.002	0	0	0.008	0.008	0.0139	42.8117	-78.8524
9/26/2016 13:15	0	0.046	0	0.002	0	0	0.02	0.008	0.0137	42.8117	-78.8524
9/26/2016 13:14	0	0.046	0	0.002	0	0	0.019	0.008	0.013	42.8117	-78.8524
9/26/2016 13:13	0	0.046	0	0.002	0	0	0.001	0.008	0.0129	42.8117	-78.8524
9/26/2016 13:12	0	0.046	0	0.002	0	0	0	0.008	0.0138	42.8117	-78.8524
9/26/2016 13:11	0	0.046	0	0.002	0	0	0.031	0.008	0.0153	42.8117	-78.8524
9/26/2016 13:10	0	0.046	0	0.002	0	0	0.007	0.008	0.0136	42.8117	-78.8524
9/26/2016 13:09	0	0.046	0	0.002	0	0	0.003	0.008	0.0145	42.8117	-78.8524

COMMUNITY AIR MONITORING

PERIODIC REVIEW REPORT

Tecumseh Phase III Business Park: Sites III-5 & III-6
Lackawanna, New York

Timestamp (GMT-4)	Low (ppm)	Peak (ppm)	STEL (ppm)	TWA (ppm)	VOC (ppm)	VOC (Avg15) (ppm)	Mass Conc. Total (mg/m³)	TWA (mg/m³)	Mass Conc. Total (Avg15) (mg/m³)	Latitude	Longitude
9/26/2016 13:08	0	0.046	0	0.002	0	0	0.029	0.008	0.0161	42.8117	-78.8524
9/26/2016 13:07	0	0.046	0	0.002	0	0	0.017	0.008	0.0153	42.8117	-78.8524
9/26/2016 13:06	0	0.046	0	0.002	0	0	0.005	0.008	0.0153	42.8117	-78.8524
9/26/2016 13:05	0	0.046	0	0.002	0	0	0.015	0.008	0.0161	42.8117	-78.8525
9/26/2016 13:04	0	0.046	0	0.002	0	0	0.032	0.008	0.0162	42.8117	-78.8524
9/26/2016 13:03	0	0.046	0	0.002	0	0	0.009	0.008	0.0139	42.8117	-78.8524
9/26/2016 13:02	0	0.046	0	0.002	0	0	0.012	0.008	0.0146	42.8117	-78.8525
9/26/2016 13:01	0	0.046	0	0.002	0	0	0.006	0.008	0.0172	42.8117	-78.8525
9/26/2016 13:00	0	0.046	0	0.002	0	0	0.009	0.008	0.0169	42.8117	-78.8524
9/26/2016 12:59	0	0.046	0	0.002	0	0	0.017	0.008	0.0181	42.8117	-78.8524
9/26/2016 12:58	0	0.046	0	0.002	0	0	0.015	0.008	0.0178	42.8117	-78.8524
9/26/2016 12:57	0	0.046	0	0.002	0	0	0.022	0.008	0.0172	42.8117	-78.8524
9/26/2016 12:56	0	0.046	0	0.002	0	0	0.006	0.008	0.0179	42.8117	-78.8525
9/26/2016 12:55	0	0.046	0	0.002	0	0	0.02	0.008	0.0199	42.8117	-78.8525
9/26/2016 12:54	0	0.046	0	0.002	0	0	0.028	0.007	0.0208	42.8116	-78.8525
9/26/2016 12:53	0	0.046	0	0.002	0	0	0.016	0.007	0.0198	42.8117	-78.8525
9/26/2016 12:52	0	0.046	0	0.002	0	0	0.018	0.007	0.0196	42.8117	-78.8524
9/26/2016 12:50	0	0.046	0	0.002	0	0				42.8117	-78.8525
9/26/2016 12:49	0	0.046	0	0.002	0	0	0.003	0.007	0.02	42.8117	-78.8525
9/26/2016 12:48	0	0.046	0	0.002	0	0	0.018	0.007	0.0214	42.8117	-78.8525
9/26/2016 12:47	0	0.046	0	0.002	0	0	0.045	0.007	0.0278	42.8117	-78.8525
9/26/2016 12:46	0	0.046	0	0.002	0	0	0.003	0.007	0.0261	42.8117	-78.8525
9/26/2016 12:45	0	0.046	0	0.002	0	0	0.024	0.007	0.0279	42.8117	-78.8525
9/26/2016 12:44	0	0.046	0	0.002	0	0	0.013	0.007	0.0263	42.8117	-78.8525
9/26/2016 12:43	0	0.046	0	0.002	0	0	0.007	0.007	0.0275	42.8117	-78.8524
9/26/2016 12:42	0	0.046	0	0.002	0	0	0.032	0.007	0.0285	42.8117	-78.8525
9/26/2016 12:41	0	0.046	0	0.002	0	0	0.032	0.007	0.0275	42.8117	-78.8525
9/26/2016 12:40	0	0.046	0	0.002	0	0	0.031	0.007	0.0261	42.8117	-78.8524
9/26/2016 12:39	0	0.046	0	0.002	0	0	0.015	0.007	0.0247	42.8117	-78.8524
9/26/2016 12:38	0	0.046	0	0.002	0	0	0.014	0.007	0.0237	42.8117	-78.8524
9/26/2016 12:37	0	0.046	0	0.002	0	0	0.039	0.006	0.0229	42.8117	-78.8524
9/26/2016 12:36	0	0.046	0	0.002	0	0	0.021	0.006	0.0211	42.8117	-78.8525
9/26/2016 12:35	0	0.046	0	0.002	0	0	0.003	0.006	0.023	42.8117	-78.8525
9/26/2016 12:34	0	0.046	0	0.002	0	0	0.024	0.006	0.0259	42.8117	-78.8525
9/26/2016 12:33	0	0.046	0	0.002	0	0	0.114	0.006	0.0263	42.8116	-78.8525
9/26/2016 12:32	0	0.046	0	0.002	0	0	0.019	0.006	0.0225	42.8117	-78.8525
9/26/2016 12:31	0	0.046	0	0.002	0	0	0.031	0.006	0.0249	42.8117	-78.8525
9/26/2016 12:30	0	0.046	0	0.002	0	0	0	0.006	0.0235	42.8117	-78.8525
9/26/2016 12:29	0	0.046	0	0.002	0	0	0.03	0.006	0.0234	42.8117	-78.8524
9/26/2016 12:28	0	0.046	0	0.002	0	0	0.022	0.006	0.0273	42.8117	-78.8524
9/26/2016 12:27	0	0.046	0	0.002	0	0	0.018	0.006	0.0258	42.8117	-78.8524
9/26/2016 12:26	0	0.046	0	0.002	0	0	0.01	0.006	0.0246	42.8117	-78.8524
9/26/2016 12:25	0	0.046	0	0.002	0	0	0.01	0.006	0.0241	42.8117	-78.8524
9/26/2016 12:24	0	0.046	0	0.002	0	0	0	0.006	0.0237	42.8117	-78.8524
9/26/2016 12:23	0	0.046	0	0.002	0	0	0.002	0.006	0.0237	42.8117	-78.8525
9/26/2016 12:22	0	0.046	0	0.002	0	0	0.012	0.006	0.0237	42.8117	-78.8525
9/26/2016 12:21	0	0.046	0	0.002	0	0	0.05	0.006	0.0234	42.8117	-78.8524
9/26/2016 12:20	0	0.046	0	0.002	0	0	0.046	0.006	0.0223	42.8117	-78.8525
9/26/2016 12:19	0	0.046	0	0.002	0	0	0.03	0.006	0.02	42.8117	-78.8525
9/26/2016 12:18	0	0.046	0	0.002	0	0	0.057	0.005	0.0201	42.8117	-78.8525
9/26/2016 12:17	0	0.046	0	0.002	0	0	0.055	0.005	0.0169	42.8117	-78.8524
9/26/2016 12:16	0	0.046	0	0.002	0	0	0.01	0.005	0.0137	42.8117	-78.8525
9/26/2016 12:15	0	0.046	0	0.002	0	0	-0.001	0.005	0.0131	42.8117	-78.8525

COMMUNITY AIR MONITORING

PERIODIC REVIEW REPORT

Tecumseh Phase III Business Park: Sites III-5 & III-6
Lackawanna, New York

Timestamp (GMT-4)	Low (ppm)	Peak (ppm)	STEL (ppm)	TWA (ppm)	VOC (ppm)	VOC (Avg15) (ppm)	Mass Conc. Total (mg/m³)	TWA (mg/m³)	Mass Conc. Total (Avg15) (mg/m³)	Latitude	Longitude
9/26/2016 12:14	0	0.046	0	0.002	0	0	0.088	0.005	0.0131	42.8117	-78.8525
9/26/2016 12:13	0	0.046	0	0.002	0	0	0	0.005	0.0078	42.8117	-78.8525
9/26/2016 12:12	0	0.046	0	0.002	0	0	0	0.005	0.0078	42.8117	-78.8525
9/26/2016 12:11	0	0.046	0	0.002	0	0	0.003	0.005	0.0085	42.8117	-78.8525
9/26/2016 12:10	0	0.046	0	0.002	0	0	0.004	0.005	0.0083	42.8117	-78.8525
9/26/2016 12:09	0	0.046	0	0.002	0	0	0	0.005	0.0086	42.8117	-78.8525
9/26/2016 12:08	0	0.046	0	0.002	0	0	0.001	0.005	0.0091	42.8117	-78.8525
9/26/2016 12:07	0	0.046	0	0.002	0	0	0.008	0.005	0.0096	42.8117	-78.8525
9/26/2016 12:06	0	0.046	0	0.002	0	0	0.033	0.005	0.0094	42.8117	-78.8525
9/26/2016 12:05	0	0.046	0	0.002	0	0	0.012	0.005	0.0072	42.8117	-78.8524
9/26/2016 12:04	0	0.046	0	0.002	0	0	0.032	0.005	0.0064	42.8117	-78.8525
9/26/2016 12:03	0	0.046	0	0.002	0	0	0.009	0.005	0.0041	42.8117	-78.8525
9/26/2016 12:02	0	0.046	0	0.002	0	0	0.007	0.005	0.0041	42.8117	-78.8525
9/26/2016 12:01	0	0.046	0	0.002	0	0	0	0.005	0.0045	42.8117	-78.8524
9/26/2016 12:00	0	0.046	0	0.002	0	0	0	0.005	0.0047	42.8117	-78.8524
9/26/2016 11:58	0	0.046	0	0.002	0	0	0	0.005	0.0067	42.8117	-78.8525
9/26/2016 11:57	0	0.046	0	0.002	0	0	0.01	0.005	0.0067	42.8117	-78.8525
9/26/2016 11:56	0	0.046	0	0.002	0	0	0	0.005	0.0065	42.8117	-78.8524
9/26/2016 11:55	0	0.046	0	0.002	0	0	0.008	0.005	0.0065	42.8117	-78.8525
9/26/2016 11:54	0	0.046	0	0.002	0	0	0.007	0.005	0.0073	42.8117	-78.8524
9/26/2016 11:53	0	0.046	0	0.002	0	0	0.008	0.005	0.0079	42.8117	-78.8524
9/26/2016 11:52	0	0.046	0	0.002	0	0	0.005	0.005	0.0074	42.8117	-78.8524
9/26/2016 11:51	0	0.046	0	0.002	0	0	0.003	0.005	0.0073	42.8117	-78.8524
9/26/2016 11:50	0	0.046	0	0.002	0	0	0.001	0.005	0.0078	42.8117	-78.8524
9/26/2016 11:49	0	0.046	0	0.002	0	0	0	0.005	0.0077	42.8117	-78.8524
9/26/2016 11:48	0	0.046	0	0.002	0	0	0.008	0.005	0.0093	42.8117	-78.8524
9/26/2016 11:47	0	0.046	0	0.002	0	0	0.013	0.005	0.0091	42.8117	-78.8524
9/26/2016 11:46	0	0.046	0	0.002	0	0	0.003	0.005	0.0089	42.8117	-78.8525
9/26/2016 11:45	0	0.046	0	0.002	0	0.0002	0.03	0.005	0.0111	42.8117	-78.8524
9/26/2016 11:44	0	0.046	0.001	0.002	0	0.0005	0.005	0.005	0.0117	42.8117	-78.8524
9/26/2016 11:43	0	0.046	0.001	0.002	0	0.0011	0	0.005	0.0154	42.8117	-78.8524
9/26/2016 11:42	0	0.046	0.002	0.002	0	0.0018	0.006	0.005	0.0165	42.8117	-78.8524
9/26/2016 11:41	0	0.046	0.003	0.002	0	0.0025	0	0.005	0.0163	42.8117	-78.8525
9/26/2016 11:40	0	0.046	0.003	0.002	0	0.0032	0.021	0.004	0.0163	42.8117	-78.8524
9/26/2016 11:39	0	0.046	0.003	0.002	0	0.0036	0.016	0.004	0.015	42.8117	-78.8524
9/26/2016 11:38	0	0.046	0.003	0.002	0	0.0038	0	0.004	0.0141	42.8117	-78.8525
9/26/2016 11:37	0	0.046	0.003	0.002	0	0.0038	0.003	0.004	0.0143	42.8117	-78.8525
9/26/2016 11:36	0	0.046	0.003	0.002	0	0.0038	0.011	0.004	0.0141	42.8117	-78.8525
9/26/2016 11:35	0	0.046	0.003	0.002	0	0.0038	0	0.004	0.0149	42.8117	-78.8524
9/26/2016 11:34	0	0.046	0.003	0.002	0	0.0038	0.024	0.004	0.0154	42.8117	-78.8524
9/26/2016 11:33	0	0.046	0.003	0.002	0	0.0038	0.004	0.004	0.0137	42.8117	-78.8524
9/26/2016 11:32	0	0.046	0.003	0.002	0	0.0038	0.01	0.004	0.014	42.8117	-78.8524
9/26/2016 11:31	0	0.046	0.003	0.002	0.003	0.0038	0.036	0.004	0.0134	42.8117	-78.8525
9/26/2016 11:30	0	0.046	0.003	0.002	0.004	0.0036	0.039	0.004	0.0114	42.8117	-78.8525
9/26/2016 11:29	0	0.046	0.002	0.002	0.009	0.0033	0.061	0.004	0.0089	42.8117	-78.8524
9/26/2016 11:28	0	0.046	0.001	0.002	0.011	0.0027	0.016	0.004	0.005	42.8117	-78.8524
9/26/2016 11:27	0	0.046	0.001	0.002	0.01	0.002	0.004	0.004	0.0195	42.8117	-78.8524
9/26/2016 11:26	0	0.046	0	0.002	0.011	0.0013	0	0.004	0.0192	42.8117	-78.8524
9/26/2016 11:25	0	0.046	0	0.002	0.006	0.0006	0.001	0.004	0.0197	42.8117	-78.8524
9/26/2016 11:24	0	0.046	0	0.002	0.003	0.0002	0.003	0.004	0.0201	42.8117	-78.8524
9/26/2016 11:23	0	0.046	0	0.002	0	0	0.003	0.004	0.0199	42.8117	-78.8524
9/26/2016 11:22	0	0.046	0	0.002	0	0	0	0.004	0.0211	42.8117	-78.8524
9/26/2016 11:21	0	0.046	0	0.002	0	0	0.022	0.004	0.0227	42.8117	-78.8524

COMMUNITY AIR MONITORING

PERIODIC REVIEW REPORT

Tecumseh Phase III Business Park: Sites III-5 & III-6
Lackawanna, New York

Timestamp (GMT-4)	Low (ppm)	Peak (ppm)	STEL (ppm)	TWA (ppm)	VOC (ppm)	VOC (Avg15) (ppm)	Mass Conc. Total (mg/m³)	TWA (mg/m³)	Mass Conc. Total (Avg15) (mg/m³)	Latitude	Longitude
9/26/2016 11:20	0	0.046	0	0.002	0	0	0.008	0.004	0.0212	42.8117	-78.8524
9/26/2016 11:19	0	0.046	0	0.002	0	0.0001	-0.001	0.004	0.0207	42.8117	-78.8524
9/26/2016 11:18	0	0.046	0.001	0.002	0	0.0005	0.008	0.004	0.0214	42.8117	-78.8524
9/26/2016 11:17	0	0.046	0.001	0.002	0	0.001	0.001	0.004	0.0209	42.8117	-78.8524
9/26/2016 11:16	0	0.046	0.003	0.002	0	0.0019	0.006	0.004	0.0208	42.8117	-78.8524
9/26/2016 11:15	0	0.046	0.004	0.002	0	0.0031	0.002	0.004	0.0204	42.8117	-78.8524
9/26/2016 11:14	0	0.046	0.006	0.002	0	0.0044	0.002	0.004	0.0215	42.8117	-78.8524
9/26/2016 11:13	0	0.046	0.007	0.002	0	0.006	0.233	0.004	0.0223	42.8117	-78.8525
9/26/2016 11:12	0	0.046	0.009	0.002	0	0.0079	0	0.004	0.0069	42.8117	-78.8525
9/26/2016 11:11	0	0.046	0.012	0.002	0	0.0099	0.008	0.004	0.0071	42.8117	-78.8525
9/26/2016 11:10	0	0.046	0.014	0.002	0	0.012	0.007	0.004	0.0067	42.8117	-78.8525
9/26/2016 11:09	0	0.046	0.016	0.002	0	0.0143	0	0.004	0.0064	42.8117	-78.8525
9/26/2016 11:08	0	0.046	0.019	0.002	0	0.0168	0.02	0.004	0.0064	42.8117	-78.8525
9/26/2016 11:07	0	0.046	0.022	0.002	0	0.0194	0.024	0.004	0.0051	42.8117	-78.8525
9/26/2016 11:06	0	0.046	0.024	0.002	0	0.022	0	0.004	0.0043	42.8117	-78.8525
9/26/2016 11:05	0	0.046	0.027	0.002	0.002	0.0249	0	0.004	0.0059	42.8117	-78.8525
9/26/2016 11:04	0	0.046	0.03	0.002	0.005	0.0276	0.01	0.004	0.0059	42.8117	-78.8525
9/26/2016 11:03	0	0.046	0.032	0.002	0.008	0.032	0	0.004	0.0052	42.8117	-78.8524
9/26/2016 11:02	0	0.046	0.034	0.002	0.014	0.0348	0	0.004	0.005	42.8117	-78.8524
9/26/2016 11:01	0	0.046	0.035	0.002	0.017	0.0343	0	0.004	0.0055	42.8117	-78.8524
9/26/2016 11:00	0	0.046	0.036	0.002	0.02	0.0357	0.018	0.004	0.0063	42.8117	-78.8525
9/26/2016 10:59	0	0.046	0.037	0.002	0.024	0.0368	0.014	0.004	0.0055	42.8117	-78.8525
9/26/2016 10:58	0	0.046	0.037	0.002	0.028	0.0375	0.002	0.004	0.0051	42.8117	-78.8524
9/26/2016 10:57	0	0.046	0.037	0.002	0.03	0.0379	0.004	0.004	0.0048	42.8117	-78.8524
9/26/2016 10:56	0	0.046	0.037	0.002	0.032	0.0379	0.002	0.004	0.0047	42.8117	-78.8525
9/26/2016 10:55	0	0.046	0.036	0.002	0.034	0.0375	0.002	0.004	0.0047	42.8117	-78.8525
9/26/2016 10:54	0	0.046	0.035	0.002	0.038	0.037	0	0.004	0.0055	42.8117	-78.8525
9/26/2016 10:53	0	0.046	0.033	0.002	0.039	0.0358	0	0.004	0.0059	42.8117	-78.8525
9/26/2016 10:52	0	0.046	0.032	0.001	0.039	0.0345	0.013	0.004	0.0059	42.8117	-78.8525
9/26/2016 10:51	0	0.046	0.03	0.001	0.043	0.033	0.023	0.003	0.0051	42.8117	-78.8525
9/26/2016 10:50	0	0.046	0.027	0.001	0.043	0.031	0.001	0.003	0.0041	42.8117	-78.8525
9/26/2016 10:49	0	0.046	0.025	0.001	0.044	0.0287	0.006	0.003	0.0056	42.8117	-78.8525
9/26/2016 10:48	0	0.044	0.022	0.001	0.044	0.0263	-0.002	0.003	0.0067	42.8117	-78.8525
9/26/2016 10:47	0	0.042	0.02	0.001	0.039	0.0237	0	0.003	0.0067	42.8117	-78.8525
9/26/2016 10:46	0	0.039	0.017	0.001	0.039	0.0211	0.012	0.003	0.0067	42.8117	-78.8525
9/26/2016 10:45	0	0.037	0.015	0.001	0.036	0.0185	0.006	0.003	0.0059	42.8117	-78.8525
9/26/2016 10:44	0	0.036	0.012	0.001	0.035	0.0161	0.007	0.003	0.0072	42.8117	-78.8525
9/26/2016 10:43	0	0.033	0.01	0.001	0.033	0.0137	-0.002	0.003	0.0067	42.8117	-78.8525
9/26/2016 10:42	0	0.03	0.008	0.001	0.03	0.0115	0.002	0.003	0.0067	42.8117	-78.8525
9/26/2016 10:41	0	0.029	0.007	0.001	0.027	0.0095	0.002	0.003	0.0071	42.8117	-78.8525
9/26/2016 10:40	0	0.027	0.005	0.001	0.026	0.0077	0.015	0.003	0.0073	42.8117	-78.8525
9/26/2016 10:39	0	0.026	0.005	0.001	0.02	0.0064	0.006	0.003	0.0068	42.8117	-78.8525
9/26/2016 10:38	0	0.026	0.005	0.001	0.019	0.0054	0	0.003	0.0068	42.8117	-78.8525
9/26/2016 10:37	0	0.026	0.005	0	0.017	0.0043	0	0.003	0.0074	42.8117	-78.8525
9/26/2016 10:36	0	0.026	0.005	0	0.013	0.0031	0.009	0.003	0.0081	42.8117	-78.8525
9/26/2016 10:35	0	0.026	0.006	0	0.009	0.0021	0.023	0.003	0.008	42.8117	-78.8525
9/26/2016 10:34	0	0.026	0.006	0	0.007	0.0013	0.023	0.003	0.0063	42.8117	-78.8525
9/26/2016 10:33	0	0.026	0.007	0	0.005	0.0006	-0.002	0.003	0.0043	42.8117	-78.8525
9/26/2016 10:32	0	0.026	0.008	0	0	0	-0.001	0.003	0.0051	42.8117	-78.8525
9/26/2016 10:31	0	0.026	0.01	0	0	0	0	0.003	0.0062	42.8117	-78.8525
9/26/2016 10:30	0	0.026	0.011	0	0	0	0.026	0.003	0.0074	42.8117	-78.8525
9/26/2016 10:29	0	0.026	0.013	0	0	0	0	0.003	0.0028	42.8117	-78.8525
9/26/2016 10:28	0	0.026	0.014	0	0	0	-0.002	0.003	0.0037	42.8117	-78.8524

COMMUNITY AIR MONITORING

PERIODIC REVIEW REPORT

Tecumseh Phase III Business Park: Sites III-5 & III-6
Lackawanna, New York

Timestamp (GMT-4)	Low (ppm)	Peak (ppm)	STEL (ppm)	TWA (ppm)	VOC (ppm)	VOC (Avg15) (ppm)	Mass Conc. Total (mg/m³)	TWA (mg/m³)	Mass Conc. Total (Avg15) (mg/m³)	Latitude	Longitude
9/26/2016 10:27	0	0.026	0.016	0	0	0	0.008	0.003	0.0065	42.8117	-78.8524
9/26/2016 10:26	0	0.026	0.016	0	0	0	0.005	0.003	0.005	42.8117	-78.8524

APPENDIX B

FILL DISPOSAL DOCUMENTATION

Tonnage Summary

Date	Ticket	Tonnage
9/26/2016	202712	20.25
9/26/2016	202771	23.36
9/26/2016	202752	23.71
9/26/2016	202783	19.69
9/26/2016	202713	26.97
9/26/2016	202696	18.70
9/26/2016	202759	22.96
9/26/2016	202718	26.22
9/26/2016	202777	20.23
9/26/2016	202738	20.92
9/27/2016	202880	27.99
9/27/2016	202824	27.68
9/28/2016	202965	25.46
9/28/2016	202974	18.27
9/28/2016	202961	19.83
9/29/2016	203030	23.59
9/29/2016	203068	19.26
9/29/2016	203111	25.52
9/29/2016	203068	14.61
9/29/2016	203031	18.41
9/29/2016	203114	20.22
9/29/2016	203036	20.78
9/30/2016	203176	17.55
9/30/2016	203135	20.69
10/3/2016	203283	15.52
Total Tonnage		538.39

CHAUTAUQUA COUNTY LANDFILL
3889 Towerville Road
Jamestown, New York 14701

000486 ZOLADZ CONSTRUCTION COMPANY
13600 RAILROAD STREET
ALDEN NY 14004

SITE	TICKET	GRID		WEIGHMASTER	
02	202712	9		CHRIS GOODWILL	
DATE IN	DATE OUT	TIME IN	TIME OUT	VEHICLE	ROLL OFF
09/26/16	09/26/16	11:21	11:21	ZC284	
REFERENCE		ORIGIN			
041416S1		ERIE COUNTY (NY)			

Scale 1 Gross Wt. 65700 LB
Stored Tare Wt. 25200 LB
Net Weight 40500 LB

Inbound - Charge ticket

QTY.	UNIT	DESCRIPTION	RATE	EXTENSION	FEE	TOTAL
20.25	TON	Soil Benefit OutCo				

Operating hours 7:30 AM to 3:30 PM Monday thru Friday.

This is to certify that this load does not contain any
hazardous materials, medical waste or liquids of any
type.

Telephone (716) 985-4785

Driver TECUMSEH REDEVELOPMENT INC

Generator 2303 HAMBURG TURNPIKE

Comment LACKAWANNA, NY 14218

Hauler: ZOLADZ CONSTRUCTION COMPANY

WEIGHMASTER
TENDERED
CHANGE
CHECK SY

WW6T1 TO REORDER CONTACT CAROLINA SOFTWARE (910) 799-6767 SIGNATURE _____

NON-HAZARDOUS WASTE MANIFEST		1. Generator ID Number		2. Page 1 of	3. Emergency Response Phone 576-0345	4. Waste Tracking Number	
		5. Generator's Name and Mailing Address Taconic Redevelopment, Inc 2558 Hamburg Turnpike, LACKAWANNA NY		Generator's Site Address (if different than mailing address)			
6. Transporter 1 Company Name 20112 Consl Co, Inc		U.S. EPA ID Number 9A499					
7. Transporter 2 Company Name		U.S. EPA ID Number					
8. Designated Facility Name and Site Address CHAMQUOA CIV LF 1144, NY 1175-4785		U.S. EPA ID Number					
9. Waste Shipping Name and Description		10. Containers		11. Total Quantity	12. Unit Wt./Vol.		
		No.	Type				
1. non Reg soil/fill CC041416.SI		1	DT				
2.							
3.							
4.							
13. Special Handling Instructions and Additional Information							
14. GENERATOR'S/OFFEROR'S CERTIFICATION: I hereby declare that the contents of this consignment are fully and accurately described above by the proper shipping name, and are classified, packaged, marked and labeled/placarded, and are in all respects in proper condition for transport according to applicable international and national governmental regulations.							
Generator's/Offor's Printed/Typed Name P. J. 12 AS 9-01 FOR OWNER				Signature [Signature]		Month Day Year 9/25/16	
15. International Shipments		☐ Import to U.S.		☐ Export from U.S.		Port of entry/exit: Date leaving U.S.:	
16. Transporter Acknowledgment of Receipt of Materials							
Transporter 1 Printed/Typed Name X Rudy Hain				Signature [Signature]		Month Day Year 9/25/16	
Transporter 2 Printed/Typed Name				Signature		Month Day Year	
17. Discrepancy							
17a. Discrepancy Indication Space							
☐ Quantity		☐ Type		☐ Residue		☐ Partial Rejection ☐ Full Rejection	
17b. Alternate Facility (or Generator)				Manifest Reference Number:		U.S. EPA ID Number	
Facility's Phone:							
17c. Signature of Alternate Facility (or Generator)						Month Day Year	
18. Designated Facility Owner or Operator: Certification of receipt of materials covered by the manifest except as noted in item 17a:							
Printed/Typed Name Kathleen A Gurnsey				Signature [Signature]		Month Day Year 9/26/16	

000486 ZOLADZ CONSTRUCTION COMPANY
13600 RAILROAD STREET
ALDEN NY 14004

SITE	TICKET	GRID		WEIGHMASTER	
02	202771	9		CHRIS GOODWILL	
DATE IN	DATE OUT	TIME IN	TIME OUT	VEHICLE	ROLL OFF
09/26/16	09/26/16	14:41	14:41	ZC284	
REFERENCE		ORIGIN			
041416S1		ERIE COUNTY (NY)			

Scale 1 Gross Wt.	71920	LB
Stored Tare Wt.	25200	LB
Net Weight	46720	LB

Inbound - Charge ticket

QTY.	UNIT	DESCRIPTION	RATE	EXTENSION	FEE	TOTAL
23.36	TON	Soil Benefit OutCo				

Operating hours 7:30 AM to 3:30 PM Monday thru Friday

Operating hours 7:30 AM to 3:30 PM Monday thru Friday.
This is to certify that this is a true and correct copy of the original document.

This is to certify that this load does not contain any hazardous materials, medical waste or liquids of any type.

type.	Telephone (716) 985-4785
Driver	TECUMSEH REDEVELOPMENT INC
Generator	2303 HAMBURG TURNPIKE
Comment	LACKAWANNA, NY 14218
Hauler:	ZOLADZ CONSTRUCTION COMPANY

AMT PAID ON

TENDERED

CHANGE

CHECK NO

WW6TI TO REORDER CONTACT CAROLINA SOFTWARE (910) 799-6767 SIGNATURE

**NON-HAZARDOUS
WASTE MANIFEST**

1. Generator ID Number

2. Page 1 of

3. Emergency Response Phone

4. Waste Tracking Number

876-0599

5. Generator's Name and Mailing Address

Generator's Site Address (if different than mailing address)

Tecumseh Redevelopment, Inc
2558 Hamburg Turnpike, Lackawanna NY
Generator's Phone: 742-1742

6. Transporter 1 Company Name

U.S. EPA ID Number

Zachary Const Co, Inc

9A499

7. Transporter 2 Company Name

U.S. EPA ID Number

8. Designated Facility Name and Site Address

U.S. EPA ID Number

CHAUTAUQUA CITY LF
Elletts, NY 985-4785
Facility's Phone:

9. Waste Shipping Name and Description

10. Containers

11. Total
Quantity

12. Unit
Wt./Vol.

No.

Type

1. run Reg soil/flk CC041416, SI

1

DT

2.

3.

4.

13. Special Handling Instructions and Additional Information

14. GENERATOR'S/OFFEROR'S CERTIFICATION: I hereby declare that the contents of this consignment are fully and accurately described above by the proper shipping name, and are classified, packaged, marked and labeled/placarded, and are in all respects in proper condition for transport according to applicable international and national governmental regulations.

Generator's/Offor's Printed/Typed Name

Signature

Month Day Year

N. ABUSE AS Agent for Generator

X

9 25 16

15. International Shipments

☐ Import to U.S.

☐ Export from U.S.

Port of entry/exit:

Date leaving U.S.:

Transporter Signature (for exports only):

16. Transporter Acknowledgment of Receipt of Materials

Transporter 1 Printed/Typed Name

Signature

Month Day Year

X Rudy Harris

X Rudy Harris

9 25 16

Transporter 2 Printed/Typed Name

Signature

Month Day Year

17. Discrepancy

17a. Discrepancy Indication Space

☐ Quantity

☐ Type

☐ Residue

☐ Partial Rejection

☐ Full Rejection

Manifest Reference Number:

U.S. EPA ID Number

17b. Alternate Facility (or Generator)

Facility's Phone:

17c. Signature of Alternate Facility (or Generator)

Month Day Year

18. Designated Facility Owner or Operator: Certification of receipt of materials covered by the manifest except as noted in Item 17a

Printed/Typed Name

Signature

Month Day Year

Patricia A Gamsey

Patricia A Gamsey

9 26 16

CHAUTAUQUA COUNTY LANDFILL
3889 Towerville Road
Jamestown, New York 14701

000486 ZOLADZ CONSTRUCTION COMPANY
13600 RAILROAD STREET
ALDEN NY 14004

SITE	TICKET	GRID		WEIGHMASTER	
02	202752	9		CHRIS GOODWILL	
DATE IN	DATE OUT	TIME IN	TIME OUT	VEHICLE	ROLL OFF
09/26/16	09/26/16	13:32	13:32	ZC242	
REFERENCE			ORIGIN		
041416S1			ERIE COUNTY (NY)		

Scale 1 Gross Wt. 76680 LB
Stored Tare Wt. 29260 LB
Net Weight 47420 LB

Inbound - Charge ticket

QTY.	UNIT	DESCRIPTION	RATE	EXTENSION	FEE	TOTAL
23.71	TON	Soil Benefit OutCo				

Operating hours 7:30 AM to 3:30 PM Monday thru Friday.

This is to certify that this load does not contain any hazardous materials, medical waste or liquids of any type.

Telephone (716) 985-4785

Driver TECUMSEH REDEVELOPMENT INC

Generator 2303 HAMBURG TURNPIKE

Comment LACKAWANNA, NY 14218

Hauler: <USE ONLY AT LANDFILL>

NET AMOUNT

TENDERED

CHANGE

CHECK NO.

WW6T1 TO REORDER CONTACT CAROLINA SOFTWARE (910) 799-6767 SIGNATURE

NON-HAZARDOUS WASTE MANIFEST		1. Generator ID Number		2. Page 1 of 2		3. Emergency Response Phone 876-0599		4. Waste Tracking Number	
		5. Generator's Name and Mailing Address Triangle Remediation, Inc. 2335 Highway 100, P.O. Box 14218, Hickman, NY Generator's Phone: 518-899-1421		Generator's Site Address (if different than mailing address)					
6. Transporter 1 Company Name ZWILLER CONSULT CO, Inc.		U.S. EPA ID Number GA459		7. Transporter 2 Company Name		U.S. EPA ID Number		8. Designated Facility Name and Site Address CHAUTAUQUA CITY LF 21100, NY Facility's Phone: 915-4785	
U.S. EPA ID Number		U.S. EPA ID Number		U.S. EPA ID Number					
9. Waste Shipping Name and Description 1. WASTE SOIL/FILL (CO414/10.SI)		10. Containers		11. Total Quantity		12. Unit Wt./Vol.			
		No.	Type						
		1		OT					
2.									
3.									
4.									
13. Special Handling Instructions and Additional Information									
14. GENERATOR'S/OFFEROR'S CERTIFICATION: I hereby declare that the contents of this consignment are fully and accurately described above by the proper shipping name, and are classified, packaged, marked and labeled/placarded, and are in all respects in proper condition for transport according to applicable international and national governmental regulations.									
Generator's/Offor's Printed/Typed Name D. D. ASAGI for Generator					Signature 		Month Day Year 9/25/16		
15. International Shipments ☐ Import to U.S. ☐ Export from U.S. Port of entry/exit: Date leaving U.S.:									
16. Transporter Acknowledgment of Receipt of Materials									
Transporter 1 Printed/Typed Name Denny Fry					Signature 		Month Day Year 9/25/16		
Transporter 2 Printed/Typed Name					Signature		Month Day Year		
17. Discrepancy									
17a. Discrepancy Indication Space ☐ Quantity ☐ Type ☐ Residue ☐ Partial Rejection ☐ Full Rejection									
17b. Alternate Facility (or Generator) Manifest Reference Number: U.S. EPA ID Number									
Facility's Phone:									
17c. Signature of Alternate Facility (or Generator) Month Day Year									
18. Designated Facility Owner or Operator: Certification of receipt of materials covered by the manifest except as noted in Item 17a									
Printed/Typed Name Patricia A. Garnsey					Signature 		Month Day Year 9/25/16		

Mar 18/18

CHAUTAUQUA COUNTY LANDFILL
3889 Towerville Road
Jamestown, New York 14701

000486 ZOLADZ CONSTRUCTION COMPANY
13600 RAILROAD STREET
ALDEN NY 14004

SITE	TICKET	GRID		WEIGHMASTER	
02	202783	9		CHRIS GOODWILL	
DATE IN	DATE OUT	TIME IN	TIME OUT	VEHICLE	ROLL OFF
09/26/16	09/26/16	15:22	15:22	ZC181	
REFERENCE		ORIGIN			
041416S1		ERIE COUNTY (NY)			

Scale 1 Gross Wt.	66800	LB	Inbound - Charge ticket
Stored Tare Wt.	27420	LB	
Net Weight	39380	LB	

QTY.	UNIT	DESCRIPTION	RATE	EXTENSION	FEE	TOTAL
19.69	TON	Soil Benefit OutCo				

Operating hours 7:30 AM to 3:30 PM Monday thru Friday.



This is to certify that this load does not contain any hazardous materials, medical waste or liquids of any type.

Telephone (716) 985-4785
Driver TECUMSEH REDEVELOPMENT INC
Generator 2303 HAMBURG TURNPIKE
Comment LACKAWANNA, NY 14218
Hauler: <USE ONLY AT LANDFILL>

NET AMOUNT
TENDERED
CHANGE
CHECK NO.

WW6T1 TO REORDER CONTACT CAROLINA SOFTWARE (910) 799-6767 SIGNATURE

Mar 181 ②

NON-HAZARDOUS WASTE MANIFEST		1. Generator ID Number		2. Page 1 of		3. Emergency Response Phone 856-0579		4. Waste Tracking Number	
5. Generator's Name and Mailing Address Johnson Redevelopment Inc 2555 Imburs Turnpike Hickman, NY									
Generator's Site Address (if different than mailing address)									
6. Transporter 1 Company Name ZOLAR Const Co, Inc						U.S. EPA ID Number GA499			
7. Transporter 2 Company Name						U.S. EPA ID Number			
8. Designated Facility Name and Site Address Chautauque Ck LF Elk, NY						U.S. EPA ID Number			
Facility's Phone: 985-4785									
9. Waste Shipping Name and Description						10. Containers		11. Total Quantity	12. Unit Wt/Vol.
						No.	Type		
1. WV - Res Solid/Flu CC0411416.S1						1	DT		
2.									
3.									
4.									
13. Special Handling Instructions and Additional Information									
14. GENERATOR'S/OFFEROR'S CERTIFICATION: I hereby declare that the contents of this consignment are fully and accurately described above by the proper shipping name, and are classified, packaged, marked and labeled/placarded, and are in all respects in proper condition for transport according to applicable international and national governmental regulations.									
Generator's/Offor's Printed/Typed Name ROBERT AS A.M. FOR Generator						Signature 		Month Day Year 9 26 16	
15. International Shipments ☐ Import to U.S. ☐ Export from U.S.						Port of entry/exit: Date leaving U.S.:			
16. Transporter Acknowledgment of Receipt of Materials									
Transporter 1 Printed/Typed Name X Mary Langworthy						Signature 		Month Day Year 9 26 16	
Transporter 2 Printed/Typed Name						Signature		Month Day Year	
17. Discrepancy									
17a. Discrepancy Indication Space ☐ Quantity ☐ Type ☐ Residue ☐ Partial Rejection ☐ Full Rejection									
17b. Alternate Facility (or Generator)						Manifest Reference Number:			
Facility's Phone:						U.S. EPA ID Number			
17c. Signature of Alternate Facility (or Generator)						Month Day Year			
18. Designated Facility Owner or Operator: Certification of receipt of materials covered by the manifest except as noted in Item 17a									
Printed/Typed Name Patricia A. Gainsey						Signature 		Month Day Year 9 26 16	

GENERATOR

TRANSPORTER INT'L

TRANSPORTER

DESIGNATED FACILITY

man lfi ①

CHAUTAUQUA COUNTY LANDFILL
3889 Towerville Road
Jamestown, New York 14701

000486 ZOLADZ CONSTRUCTION COMPANY
13600 RAILROAD STREET
ALDEN NY 14004

SITE	TICKET	GRID		WEIGHMASTER	
02	202713	9		CHRIS GOODWILL	
DATE IN	DATE OUT	TIME IN	TIME OUT	VEHICLE	ROLL OFF
09/26/16	09/26/16	11:23	11:23	ZC181	
REFERENCE		ORIGIN			
041416S1		ERIE COUNTY (NY)			

Scale 1 Gross Wt. 81360 LB
Stored Tare Wt. 27420 LB
Net Weight 53940 LB

Inbound - Charge ticket

QTY.	UNIT	DESCRIPTION	RATE	EXTENSION	FEE	TOTAL
26.97	TON	Soil Benefit OutCo				

Operating hours 7:30 AM to 3:30 PM Monday thru Friday.

This is to certify that this load does not contain any hazardous materials, medical waste or liquids of any type.

Telephone (716) 985-4785

Driver TECUMSEH REDEVELOPMENT INC

Generator 2303 HAMBURG TURNPIKE

Comment LACKAWANNA, NY 14218

Hauler: <USE ONLY AT LANDFILL>

NET AMOUNT
TENDERED
CHANGE
CHECK NO.

WW6T1 TO REORDER CONTACT CAROLINA SOFTWARE (910) 799-6767 SIGNATURE _____

NON-HAZARDOUS WASTE MANIFEST

1. Generator ID Number

2. Page 1 of

3. Emergency Response Phone

4. Waste Tracking Number

5. Generator's Name and Mailing Address

Generator's Site Address (if different than mailing address)

6. Transporter 1 Company Name

U.S. EPA ID Number

7. Transporter 2 Company Name

U.S. EPA ID Number

8. Designated Facility Name and Site Address

U.S. EPA ID Number

Facility's Phone:

9. Waste Shipping Name and Description

10. Containers

No.

Type

11. Total
Quantity

12. Unit
Wt./Vol.

13. Special Handling Instructions and Additional Information

14. GENERATOR'S/OFFEROR'S CERTIFICATION: I hereby declare that the contents of this consignment are fully and accurately described above by the proper shipping name, and are classified, packaged, marked and labeled/placarded, and are in all respects in proper condition for transport according to applicable international and national governmental regulations.

Generator's/Offor's Printed/Typed Name

Signature

Month Day Year

15. International Shipments

☐ Import to U.S.

☐ Export from U.S.

Port of entry/exit:

Transporter Signature (for exports only):

Date leaving U.S.:

16. Transporter Acknowledgment of Receipt of Materials

Transporter 1 Printed/Typed Name

Signature

Month Day Year

Transporter 2 Printed/Typed Name

Signature

Month Day Year

17. Discrepancy

17a. Discrepancy Indication Space

☐ Quantity

☐ Type

☐ Residue

☐ Partial Rejection

☐ Full Rejection

Manifest Reference Number:

17b. Alternate Facility (or Generator)

U.S. EPA ID Number

Facility's Phone:

17c. Signature of Alternate Facility (or Generator)

Month Day Year

18. Designated Facility Owner or Operator: Certification of receipt of materials covered by the manifest except as noted in Item 17a

Printed/Typed Name

Signature

Month Day Year

CHAUTAUQUA COUNTY LANDFILL
3889 Towerville Road
Jamestown, New York 14701

000486 ZOLADZ CONSTRUCTION COMPANY
13600 RAILROAD STREET
ALDEN NY 14004

SITE	TICKET	GRID		WEIGHMASTER	
02	202696	9		CHRIS GOODWILL	
DATE IN	DATE OUT	TIME IN	TIME OUT	VEHICLE	ROLL OFF
09/26/16	09/26/16	10:36	10:36	ZC211	
REFERENCE		ORIGIN			
041416S1		CATTARAUGUS COUNTY			

Scale 1 Gross Wt. 67140 LB
Stored Tare Wt. 29740 LB
Net Weight 37400 LB

Inbound - Charge ticket

QTY.	UNIT	DESCRIPTION	RATE	EXTENSION	FEE	TOTAL
18.70	TON	Soil Benefit OutCo				

Operating hours 7:30 AM to 3:30 PM Monday thru Friday.

This is to certify that this load does not contain any hazardous materials, medical waste or liquids of any type.

Telephone (716) 985-4785

Driver TECUMSEH REDEVELOPMENT INC

Generator 2303 HAMBURG TURNPIKE

Comment LACKAWANNA, NY 14218

Hauler: <USE ONLY AT LANDFILL>

NET AMOUNT
TENDERED
CHANGE
CHECK NO.

WW6T1 TO REORDER CONTACT CAROLINA SOFTWARE (910) 799-6767 SIGNATURE _____

NON-HAZARDOUS
WASTE MANIFEST

1. Generator ID Number

2. Page 1 of

3. Emergency Response Phone

4. Waste Tracking Number

5. Generator's Name and Mailing Address

Generator's Site Address (if different than mailing address)

Generator's Phone:

6. Transporter 1 Company Name

U.S. EPA ID Number

7. Transporter 2 Company Name

U.S. EPA ID Number

8. Designated Facility Name and Site Address

U.S. EPA ID Number

Facility's Phone:

9. Waste Shipping Name and Description

10. Containers

No.

Type

11. Total
Quantity12. Unit
Wt./Vol.

1

2

3

4

13. Special Handling Instructions and Additional Information

14. GENERATOR'S/OFFEROR'S CERTIFICATION: I hereby declare that the contents of this consignment are fully and accurately described above by the proper shipping name, and are classified, packaged, marked and labeled/placarded, and are in all respects in proper condition for transport according to applicable international and national governmental regulations.

Generator's/Offor's Printed/Typed Name

Signature

Month Day Year

15. International Shipments

☐ Import to U.S.☐ Export from U.S.

Port of entry/exit:

Date leaving U.S.:

Transporter Signature (for exports only):

16. Transporter Acknowledgment of Receipt of Materials

Transporter 1 Printed/Typed Name

Signature

Month Day Year

Transporter 2 Printed/Typed Name

Signature

Month Day Year

17. Discrepancy

17a. Discrepancy Indication Space

☐ Quantity☐ Type☐ Residue☐ Partial Rejection☐ Full Rejection

Manifest Reference Number:

U.S. EPA ID Number

17b. Alternate Facility (or Generator)

Facility's Phone:

17c. Signature of Alternate Facility (or Generator)

Month Day Year

18. Designated Facility Owner or Operator. Certification of receipt of materials covered by the manifest except as noted in item 17a.

Printed/Typed Name

Signature

Month Day Year

GENERATOR

INT'L

TRANSPORTER

DESIGNATED FACILITY

CHAUTAUQUA COUNTY LANDFILL
3889 Towerville Road
Jamestown, New York 14701

000486 ZOLADZ CONSTRUCTION COMPANY
13600 RAILROAD STREET
ALDEN NY 14004

SITE	TICKET	GRID		WEIGHMASTER	
02	202759	9		CHRIS GOODWILL	
DATE IN	DATE OUT	TIME IN	TIME OUT	VEHICLE	ROLL OFF
09/26/16	09/26/16	14:02	14:02	ZC211	
REFERENCE		ORIGIN			
041416S1		ERIE COUNTY (NY)			

Scale 1 Gross Wt. 75660 LB
Stored Tare Wt. 29740 LB
Net Weight 45920 LB

Inbound - Charge ticket

QTY.	UNIT	DESCRIPTION	RATE	EXTENSION	FEE	TOTAL
22.96	TON	MSW LF Tons OutCo				

Operating hours 7:30 AM to 3:30 PM Monday thru Friday.

This is to certify that this load does not contain any hazardous materials, medical waste or liquids of any type.

Telephone (716) 985-4785

Driver TECUMSEH REDEVELOPMENT INC

Generator 2303 HAMBURG TURNPIKE

Comment LACKAWANNA, NY 14218

Hauler: <USE ONLY AT LANDFILL>

NET AMOUNT
TENDERED
CHANGE
CHECK NO.

WW6T1 TO REORDER CONTACT CAROLINA SOFTWARE (910) 799-6767 SIGNATURE

**NON-HAZARDOUS
WASTE MANIFEST**

1. Generator ID Number

2. Page 1 of

3. Emergency Response Phone

4. Waste Tracking Number

856-0599

5. Generator's Name and Mailing Address

Generator's Site Address (if different than mailing address)

Teamson Redevelopment, Inc
2558 Amburs Turnpike, Lackawanna, NY 14288
Generator's Phone: 856-0599

6. Transporter 1 Company Name

U.S. EPA ID Number

ZOLA02 CONST CO, INC

9A499

7. Transporter 2 Company Name

U.S. EPA ID Number

8. Designated Facility Name and Site Address

U.S. EPA ID Number

CHAUTAUQUA CY LF
Ellety, NY

Facility's Phone:

985-4785

9. Waste Shipping Name and Description

10. Containers

No.

Type

11. Total
Quantity

12. Unit
Wt./Vol.

1. new res soil/fill CC041/16.S1

1

DT

2.

3.

4.

13. Special Handling Instructions and Additional Information

14. GENERATOR'S/OFFEROR'S CERTIFICATION: I hereby declare that the contents of this consignment are fully and accurately described above by the proper shipping name, and are classified, packaged, marked and labeled/placarded, and are in all respects in proper condition for transport according to applicable international and national governmental regulations.

Generator's/Offor's Printed/Typed Name

Signature

Month Day Year

R. DUBSE AS Agent for Generator

[Signature]

15. International Shipments

☐ Import to U.S.

☐ Export from U.S.

Port of entry/exit

Date leaving U.S.:

Transporter Signature (for exports only):

16. Transporter Acknowledgment of Receipt of Materials

Transporter 1 Printed/Typed Name

Signature

Month Day Year

X Yvonne Vallet

X [Signature]

Transporter 2 Printed/Typed Name

Signature

Month Day Year

17. Discrepancy

17a. Discrepancy Indication Space

☐ Quantity

☐ Type

☐ Residue

☐ Partial Rejection

☐ Full Rejection

Manifest Reference Number:

U.S. EPA ID Number

17b. Alternate Facility (or Generator)

Facility's Phone:

17c. Signature of Alternate Facility (or Generator)

Month Day Year

18. Designated Facility Owner or Operator: Certification of receipt of materials covered by the manifest except as noted in Item 17a

Printed/Typed Name

Signature

Month Day Year

Patricia A. Garney

[Signature]

7/9/06/16

CHAUTAUQUA COUNTY LANDFILL
3889 Towerville Road
Jamestown, New York 14701

000486 ZOLADZ CONSTRUCTION COMPANY
13600 RAILROAD STREET
ALDEN NY 14004

SITE	TICKET	GRID		WEIGHMASTER	
02	202718	9		CHRIS GOODWILL	
DATE IN	DATE OUT	TIME IN	TIME OUT	VEHICLE	ROLL OFF
09/26/16	09/26/16	11:32	11:32	ZC244	
REFERENCE			ORIGIN		
041416S1			ERIE COUNTY (NY)		

Scale 1 Gross Wt. 81520 LB
Stored Tare Wt. 29080 LB
Net Weight 52440 LB

Inbound - Charge ticket

QTY	UNIT	DESCRIPTION	RATE	EXTENSION	FEE	TOTAL
26.22	TON	Soil Benefit OutCo				

Operating hours 7:30 AM to 3:30 PM Monday thru Friday.

This is to certify that this load does not contain any hazardous materials, medical waste or liquids of any type.

Telephone (716) 985-4785

Driver TECUMSEH REDEVELOPMENT INC

Generator 2303 HAMBURG TURNPIKE

Comment LACKAWANNA, NY 14218

Hauler: <USE ONLY AT LANDFILL>

NET AMOUNT
TENDERED
CHANGE
CHECK NO.

SIGNATURE

NON-HAZARDOUS
WASTE MANIFEST

1. Generator ID Number

2. Page 1 of

3. Emergency Response Phone

4. Waste Tracking Number

YIC 0199

5. Generator's Name and Mailing Address

Generator's Site Address (if different than mailing address)

Transit Technologies, Inc
2550 HAMPSHIRE AVENUE
GENESEE, NY 14456
Generator's Phone: 716-534-1344

6. Transporter 1 Company Name

U.S. EPA ID Number

2nd CO, INC

U.S. EPA ID Number

8. Designated Facility Name and Site Address

U.S. EPA ID Number

CHAUTAQUA CTY LF
ELMIRA, NY
Facility's Phone: 607-417-5555

9. Waste Shipping Name and Description

10. Containers

11. Total
Quantity12. Unit
Wt./Vol.

No.

Type

1. non-hal sil/fill 10041416.S1

1 DT

2.

3.

4.

13. Special Handling Instructions and Additional Information

14. GENERATOR'S/OFFEROR'S CERTIFICATION: I hereby declare that the contents of this consignment are fully and accurately described above by the proper shipping name, and are classified, packaged, marked and labeled/placarded, and are in all respects in proper condition for transport according to applicable international and national governmental regulations.

Generator's/Offor's Printed/Typed Name

Signature

Month Day Year

L. Ouse - 1st. Agent. Elmira, NY

[Signature]

9/12/16

15. International Shipments

☐ Import to U.S.☐ Export from U.S.

Port of entry/exit:

Date leaving U.S.:

Transporter Signature (for exports only):

16. Transporter Acknowledgment of Receipt of Materials

Transporter 1 Printed/Typed Name

Signature

Month Day Year

X Michael L. MacCabe

[Signature]

9/12/16

Transporter 2 Printed/Typed Name

Signature

Month Day Year

17. Discrepancy

17a. Discrepancy Indication Space

☐ Quantity☐ Type☐ Residue☐ Partial Rejection☐ Full Rejection

Manifest Reference Number:

U.S. EPA ID Number

17b. Alternate Facility (or Generator)

Facility's Phone:

17c. Signature of Alternate Facility (or Generator)

Month Day Year

18. Designated Facility Owner or Operator: Certification of receipt of materials covered by the manifest except as noted in Item 17a

Printed/Typed Name

Signature

Month Day Year

Patricia G. Garsy

[Signature]

9/26/16

000486 ZOLADZ CONSTRUCTION COMPANY
13600 RAILROAD STREET
ALDEN NY 14004

SITE	TICKET	GRID		WEIGHMASTER	
02	202777	9		CHRIS GOODWILL	
DATE IN	DATE OUT	TIME IN	TIME OUT	VEHICLE	ROLL OFF
09/26/16	09/26/16	14:58	14:58	ZC244	
REFERENCE		ORIGIN			
041416S1		ERIE COUNTY (NY)			

Scale 1 Gross Wt.	69540	LB
Stored Tare Wt.	29080	LB
Net Weight	40460	LB

Inbound - Charge ticket

QTY.	UNIT	DESCRIPTION	RATE	EXTENSION	FEE	TOTAL
20.23	TON	Soil Benefit OutCo				

Operating hours 7:30 AM to 3:30 PM

This is to certify that this load does not contain any hazardous materials, medical waste or liquids of any type. Telephone (716) 985-4785

Telephone (716) 985-4785

Hauler: <USE ONLY AT LANDFILL>

WW6T1 TO REORDER CONTACT CAROLINA SOFTWARE (910) 799-6767 SIGNATURE

NET AMOUNT
TENDERED
CHANGE
CHECK NO.

NON-HAZARDOUS WASTE MANIFEST		1. Generator ID Number	2. Page 1 of	3. Emergency Response Phone 516-0599	4. Waste Tracking Number
5. Generator's Name and Mailing Address Tromsø Rehabilitation, Inc 2518 Hamburg Turnpike, Lyncoln, NY Generator's Phone: 742-8			Generator's Site Address (if different than mailing address)		
6. Transporter 1 Company Name WASTE, COSI CO, INC			U.S. EPA ID Number 9A499		
7. Transporter 2 Company Name			U.S. EPA ID Number		
8. Designated Facility Name and Site Address CHAUTAQUA CTY LF Elletts, NY 925-4785 Facility's Phone:			U.S. EPA ID Number		
9. Waste Shipping Name and Description		10. Containers		11. Total Quantity	12. Unit Wt/Vol.
		No.	Type		
1. Non-Reg Soil/Fill 000411418.S1		1	DT		
2.					
3.					
4.					
13. Special Handling Instructions and Additional Information					
14. GENERATOR'S/OFFEROR'S CERTIFICATION: I hereby declare that the contents of this consignment are fully and accurately described above by the proper shipping name, and are classified, packaged, marked and labeled/placarded, and are in all respects in proper condition for transport according to applicable international and national governmental regulations.					
Generator's/Offor's Printed/Typed Name R. ABISL AS Agent For Owner			Signature 		Month Day Year 4/25/16
15. International Shipments ☐ Import to U.S. ☐ Export from U.S. Port of entry/exit: Date leaving U.S.:					
16. Transporter Acknowledgment of Receipt of Materials					
Transporter 1 Printed/Typed Name X. M. De Lanza			Signature 		Month Day Year 4/25/16
Transporter 2 Printed/Typed Name			Signature		Month Day Year
17. Discrepancy					
17a. Discrepancy Indication Space ☐ Quantity ☐ Type ☐ Residue ☐ Partial Rejection ☐ Full Rejection					
17b. Alternate Facility (or Generator) Manifest Reference Number: U.S. EPA ID Number					
Facility's Phone:					
17c. Signature of Alternate Facility (or Generator) Month Day Year					
18. Designated Facility Owner or Operator: Certification of receipt of materials covered by the manifest except as noted in Item 17a:					
Printed/Typed Name Patricia A. Garnsey			Signature 		Month Day Year 4/26/16

****DUPLICATE TICKET****

CHAUTAUQUA COUNTY LANDFILL
3889 Towerville Road
Jamestown, New York 14701

000486 ZOLADZ CONSTRUCTION COMPANY
13600 RAILROAD STREET
ALDEN NY 14004

SITE	TICKET	GRID	WEIGHMASTER
02	202738	9	CHRIS GOODWILL
DATE IN	DATE OUT	TIME IN	TIME OUT
09/26/16	09/26/16	12:19	12:19
REFERENCE		VEHICLE	ROLL OFF
		ZC147	
		ORIGIN	
041416S1		ERIE COUNTY (NY)	

Scale 1 Gross Wt. 69560 LB
Stored Tare Wt. 27720 LB
Net Weight 41840 LB

Inbound - Charge ticket

QTY.	UNIT	DESCRIPTION	RATE	EXTENSION	FEE	TOTAL
20.92	TON	Soil Benefit OutCo				

Operating hours 7:30 AM to 3:30 P.M. Monday thru Friday.

This is to certify that this load does not contain any hazardous materials, medical waste or liquids of any type.

Driver Telephone (716) 985-4785
Generator TECUMSEH REDEVELOPMENT INC
Comment 2303 HAMBURG TURNPIKE
LACKAWANNA, NY 14218

Hayler: <USE ONLY AT LANDFILL>

TO REORDER CONTACT: JAMES H. WARE (910) 799-6767

SIGNATURE

NET AMOUNT
TENDERED
CHANGE
CHECK NO.

Ticket 202738

NON-HAZARDOUS WASTE MANIFEST		1. Generator ID Number	2. Page 1 of	3. Emergency Response Phone	4. Waste Tracking Number
5. Generator's Name and Mailing Address KRONIN REDEMPTION, INC. 2557 HAWTHORNE BLVD, MC KENZIE NY		Generator's Site Address (if different than mailing address)			
6. Transporter 1 Company Name		U.S. EPA ID Number			
7. Transporter 2 Company Name		U.S. EPA ID Number			
8. Designated Facility Name and Site Address COLUMBIA CITY LF ELIOT, NY		U.S. EPA ID Number			
9. Waste Shipping Name and Description		10. Containers		11. Total Quantity	12. Unit Wt/Vol.
		No.	Type		
1. SOLID WASTE 1204410. S1		1	DR		
2.					
3.					
4.					
13. Special Handling Instructions and Additional Information					
14. GENERATOR'S/OFFEROR'S CERTIFICATION: I hereby declare that the contents of this consignment are fully and accurately described above by the proper shipping name, and are classified, packaged, marked and labeled/placarded, and are in all respects in proper condition for transport according to applicable international and national governmental regulations.					
Generator's/Offor's Printed/Typed Name		Signature		Month	Day Year
KRONIN REDEMPTION, INC.				1	1 1998
15. International Shipments ☐ Import to U.S. ☐ Export from U.S. Port of entry/exit: Date leaving U.S.:					
16. Transporter Acknowledgment of Receipt of Materials					
Transporter 1 Printed/Typed Name		Signature		Month	Day Year
X Melissa Baker		Melissa Baker		1	1 1998
Transporter 2 Printed/Typed Name		Signature		Month	Day Year
17. Discrepancy					
17a. Discrepancy Indication Space ☐ Quantity ☐ Type ☐ Residue ☐ Partial Rejection ☐ Full Rejection					
17b. Alternate Facility (or Generator) Manifest Reference Number: U.S. EPA ID Number					
Facility's Phone:					
17c. Signature of Alternate Facility (or Generator) Month Day Year					
18. Designated Facility Owner or Operator: Certification of receipt of materials covered by the manifest except as noted in Item 17a					
Printed/Typed Name		Signature		Month	Day Year
KRONIN REDEMPTION, INC.				1	1 1998

CHAUTAUQUA COUNTY LANDFILL
3889 Towerville Road
Jamestown, New York 14701

000486 ZOLADZ CONSTRUCTION COMPANY
13600 RAILROAD STREET
ALDEN NY 14004

SITE	TICKET	GRID		WEIGHMASTER	
02	202880	9		CHRIS GOODWILL	
DATE IN	DATE OUT	TIME IN	TIME OUT	VEHICLE	ROLL OFF
09/27/16	09/27/16	13:35	13:35	ZC181	
REFERENCE		ORIGIN			
041416S1		ERIE COUNTY (NY)			

Scale 1 Gross Wt.	83400	LB
Stored Tare Wt.	27420	LB
Net Weight	55980	LB

Inbound - Charge ticket

QTY.	UNIT	DESCRIPTION	RATE	EXTENSION	FEE	TOTAL
27.99	TON	Soil Benefit OutCo				

Operating hours 7:30 AM to 3:30 PM Monday thru Friday.

This is to certify that this load does not contain any hazardous materials, medical waste or liquids of any type. Telephone (716) 985-4785

Telephone (716) 985-4785

Driver TECUMSEH REDEVELOPMENT INC

Generator 2303 HAMBURG TURNPIKE

Comment LACKAWANNA, NY 14218

Hauler: <USE ONLY AT LANDFILL>

NET AMOUNT
TENDERED
CHANGE
CHECK NO.

WW6T1 TO REORDER CONTACT CAROLINA SOFTWARE (910) 799-6767 SIGNATURE _____

**NON-HAZARDOUS
WASTE MANIFEST**

1. Generator ID Number

2. Page 1 of

3. Emergency Response Phone

4. Waste Tracking Number

576-0543

5. Generator's Name and Mailing Address

Generator's Site Address (if different than mailing address)

James H. Hargrave, Inc.
2350 Highway 300, Suite 100, New York, NY 11201
Generator's Phone: 576-0543

6. Transporter 1 Company Name

U.S. EPA ID Number

7. Transporter 2 Company Name

U.S. EPA ID Number

8. Designated Facility Name and Site Address

U.S. EPA ID Number

Chaukappa, Inc.
4100, Ave.
Facility's Phone: 576-4211

9. Waste Shipping Name and Description

10. Containers

No.

Type

11. Total
Quantity

12. Unit
Wt./Vol.

1. New Dry Bulk Fuel CC 0414/1021

1

DR

13. Special Handling Instructions and Additional Information

14. GENERATOR'S/OFFEROR'S CERTIFICATION: I hereby declare that the contents of this consignment are fully and accurately described above by the proper shipping name, and are classified, packaged, marked and labeled/placarded, and are in all respects in proper condition for transport according to applicable international and national governmental regulations.

Generator's/Offor's Printed/Typed Name

Signature

Month Day Year

15. International Shipments

☐ Import to U.S.

☐ Export from U.S.

Port of entry/exit:

Date leaving U.S.:

16. Transporter Acknowledgment of Receipt of Materials

Transporter 1 Printed/Typed Name

Signature

Month Day Year

Transporter 2 Printed/Typed Name

Signature

Month Day Year

17. Discrepancy

17a. Discrepancy Indication Space

☐ Quantity

☐ Type

☐ Residue

☐ Partial Rejection

☐ Full Rejection

Manifest Reference Number:

17b. Alternate Facility (or Generator)

U.S. EPA ID Number

Facility's Phone:

17c. Signature of Alternate Facility (or Generator)

Month Day Year

18. Designated Facility Owner or Operator: Certification of receipt of materials covered by the manifest except as noted in Item 17a

Printed/typed Name

Signature

Month Day Year

Mar 18/1 ①
CHAUTAUQUA COUNTY LANDFILL
3889 Towerville Road
Jamestown, New York 14701

000486 ZOLADZ CONSTRUCTION COMPANY
13600 RAILROAD STREET
ALDEN NY 14004

SITE	TICKET	GRID		WEIGHMASTER	
02	202824	9		CHRIS GOODWILL	
DATE IN	DATE OUT	TIME IN	TIME OUT	VEHICLE	ROLL OFF
09/27/16	09/27/16	09:44	09:44	ZC181	
REFERENCE			ORIGIN		
041416S1			ERIE COUNTY (NY)		

Scale 1 Gross Wt. 82780 LB
Stored Tare Wt. 27420 LB
Net Weight 55360 LB

Inbound - Charge ticket

QTY.	UNIT	DESCRIPTION	RATE	EXTENSION	FEE	TOTAL
27.68	TON	Soil Benefit OutCo				

Operating hours 7:30 AM to 3:30 PM Monday thru Friday.

This is to certify that this load does not contain any hazardous materials, medical waste or liquids of any type.

Telephone (716) 985-4785

Driver TECUMSEH REDEVELOPMENT INC

Generator 2303 HAMBURG TURNPIKE

Comment LACKAWANNA, NY 14218

Hauler: <USE ONLY AT LANDFILL>

WW6T1 TO REORDER CONTACT CAROLINA SOFTWARE (910) 799-6767 SIGNATURE _____

NET AMOUNT
TENDERED
CHANGE
CHECK NO.

MAR 181 ②

NON-HAZARDOUS WASTE MANIFEST		1. Generator ID Number	2. Page 1 of	3. Emergency Response Phone 856-0599	4. Waste Tracking Number
5. Generator's Name and Mailing Address TRANSIX REDEVELOPMENT, INC. 2558 HANBURY TURNpike ACKAWAN, NY 14002 Generator's Phone: 856-0599					
6. Transporter 1 Company Name ZIMMER CONSTRUCTION CO, INC				U.S. EPA ID Number 9A449	
7. Transporter 2 Company Name				U.S. EPA ID Number	
8. Designated Facility Name and Site Address CHATEAUGUA CITY LF ELLIS, NY Facility's Phone: 981-2125				U.S. EPA ID Number	
9. Waste Shipping Name and Description 1. New Reg. Soil / Fill CCMH 16.51			10. Containers		11. Total Quantity
			No.	Type	
2.					
3.					
4.					
13. Special Handling Instructions and Additional Information MAR 181 ②					
14. GENERATOR'S/OFFEROR'S CERTIFICATION: I hereby declare that the contents of this consignment are fully and accurately described above by the proper shipping name, and are classified, packaged, marked and labeled/placarded, and are in all respects in proper condition for transport according to applicable international and national governmental regulations.					
Generator's/Offor's Printed/Typed Name R. D. 52 AS Aged For Generation			Signature 		Month Day Year 9/27/16
15. International Shipments ☐ Import to U.S. ☐ Export from U.S. Port of entry/exit: Date leaving U.S.:					
16. Transporter Acknowledgment of Receipt of Materials					
Transporter 1 Printed/Typed Name MARY LANGWORTHY			Signature 		Month Day Year 9/27/16
Transporter 2 Printed/Typed Name			Signature		Month Day Year
17. Discrepancy					
17a. Discrepancy Indication Space ☐ Quantity ☐ Type ☐ Residue ☐ Partial Rejection ☐ Full Rejection					
Manifest Reference Number:					
17b. Alternate Facility (or Generator)				U.S. EPA ID Number	
Facility's Phone:					
17c. Signature of Alternate Facility (or Generator)				Month Day Year	
18. Designated Facility Owner or Operator: Certification of receipt of materials covered by the manifest except as noted in Item 17a					
Printed/Typed Name PATRICIA A GAINSEY			Signature 		Month Day Year 9/27/16

CHAUTAUQUA COUNTY LANDFILL

3889 Towerville Road

Jamestown, New York 14701

000486 ZOLADZ CONSTRUCTION COMPANY

13600 RAILROAD STREET

ALDEN NY 14004

SITE	TICKET	GRID	WEIGHMASTER			
02	202965	9	CHRIS GOODWILL			
DATE IN	DATE OUT	TIME IN	TIME OUT	VEHICLE	ROLL OFF	
09/28/16	09/28/16	11:26	11:26	ZC171		
REFERENCE			ORIGIN			
041416S1			ERIE COUNTY (NY)			

Scale 1 Gross Wt. 79000 LB
Stored Tare Wt. 28080 LB
Net Weight 50920 LB

Inbound - Charge ticket

QTY.	UNIT	DESCRIPTION	RATE	EXTENSION	FEE	TOTAL
25.46	TON	Soil Benefit OutCo				

Operating hours 7:30 AM to 3:30 PM Monday thru Friday.

This is to certify that this load does not contain any
hazardous materials, medical waste or liquids of any
type.

Telephone (716) 985-4785

Driver TECUMSEH REDEVELOPMENT INC

Generator 2303 HAMBURG TURNPIKE

Comment LACKAWANNA, NY 14218

Hauler: <USE ONLY AT LANDFILL>

WW6T1 TO REORDER CONTACT CAROLINA SOFTWARE (910) 799-6767 SIGNATURE _____

NET AMOUNT
TENDERED
CHANGE
CHECK NO.

NON-HAZARDOUS WASTE MANIFEST		1. Generator ID Number		2. Page 1 of	3. Emergency Response Phone 878-0595	4. Waste Tracking Number	
5. Generator's Name and Mailing Address ITCUNYH Redevelopment, Inc 2337 Hamburg Turnpike, Lakewood NY 14285					Generator's Site Address (if different than mailing address)		
6. Transporter 1 Company Name SCHAEFFLER CO, INC					U.S. EPA ID Number CM499		
7. Transporter 2 Company Name					U.S. EPA ID Number		
8. Designated Facility Name and Site Address CHAMPAIGN CITY LF Elm, NY 1485-41285					U.S. EPA ID Number		
9. Waste Shipping Name and Description res - bag soil/fill CC 04/14/16 SI					10. Containers		11. Total Quantity
					No.	Type	12. Unit Wt./Vol.
					01	DT	
13. Special Handling Instructions and Additional Information							
14. GENERATOR'S/OFFEROR'S CERTIFICATION: I hereby declare that the contents of this consignment are fully and accurately described above by the proper shipping name, and are classified, packaged, marked and labeled/placarded, and are in all respects in proper condition for transport according to applicable international and national governmental regulations.							
Generator's/Offor's Printed/Typed Name D. Rose AS Agent For Generator					Signature 		Month Day Year 01/28/16
15. International Shipments ☐ Import to U.S. ☐ Export from U.S. Port of entry/exit: Date leaving U.S.:							
16. Transporter Acknowledgment of Receipt of Materials							
Transporter 1 Printed/Typed Name Melissa Baker					Signature 		Month Day Year 01/28/16
Transporter 2 Printed/Typed Name					Signature		Month Day Year
17. Discrepancy							
17a. Discrepancy Indication Space ☐ Quantity ☐ Type ☐ Residue ☐ Partial Rejection ☐ Full Rejection							
Manifest Reference Number:							
17b. Alternate Facility (or Generator)					U.S. EPA ID Number		
Facility's Phone:							
17c. Signature of Alternate Facility (or Generator)					Month Day Year		
18. Designated Facility Owner or Operator: Certification of receipt of materials covered by the manifest except as noted in Item 17a.							
Printed/Typed Name Patricia A. Gaudin					Signature 		Month Day Year 01/28/16

000486 ZOLADZ CONSTRUCTION COMPANY
13600 RAILROAD STREET
ALDEN NY 14004

SITE	TICKET	GRID		WEIGHMASTER	
02	202974	9		CHRIS GOODWILL	
DATE IN	DATE OUT	TIME IN	TIME OUT	VEHICLE	ROLL OFF
09/28/16	09/28/16	11:46	11:46	ECON246E	
REFERENCE		ORIGIN			
041416S1		ERIE COUNTY (NY)			

Scale 1 Gross Wt.	65120	LB	Inbound - Charge ticket
Stored Tare Wt.	28580	LB	
Net Weight	36540	LB	

QTY.	UNIT	DESCRIPTION	RATE	EXTENSION	FEE	TOTAL
18.27	TON	Soil Benefit OutCo				

This is to certify that this load does not contain any hazardous materials, medical waste or liquids of any type. Telephone (716) 985-4785

Telephone (716) 985-4785

Hauler: <USE ONLY AT LANDFILL>

NET AMOUNT
TENDERED
CHANGE
CHECK NO.

WW6T1 TO REORDER CONTACT CAROLINA SOFTWARE (910) 799-6767 SIGNATURE

**NON-HAZARDOUS
WASTE MANIFEST**

1. Generator ID Number

2. Page 1 of

3. Emergency Response Phone

4. Waste Tracking Number

836-0349

5. Generator's Name and Mailing Address

Generator's Site Address (if different than mailing address)

Perkins Plastics, Inc.
2338 Albany Expressway, NY

Generator's Phone:

356-0349 14218

6. Transporter 1 Company Name

ZULATZ CONST CO, INC

U.S. EPA ID Number

9A449

Box 246 E

7. Transporter 2 Company Name

U.S. EPA ID Number

8. Designated Facility Name and Site Address

U.S. EPA ID Number

CHATAQUA CTY LF / Economy Const
Ellery NY 985-4285

Facility's Phone:

9. Waste Shipping Name and Description

10. Containers

11. Total
Quantity

12. Unit
Wt/Vol.

No.

Type

1.

new Reg Soil/Fill CC 04/14/61

1

OT

2.

3.

4.

13. Special Handling Instructions and Additional Information

14. GENERATOR'S/OFFEROR'S CERTIFICATION: I hereby declare that the contents of this consignment are fully and accurately described above by the proper shipping name, and are classified, packaged, marked and labeled/placarded, and are in all respects in proper condition for transport according to applicable international and national governmental regulations.

Generator's/Offor's Printed/Typed Name

Signature

Month Day Year

X IL DUBISE AS Agent for Generator

[Signature]

9 1 16

15. International Shipments

☐ Import to U.S.

☐ Export from U.S.

Port of entry/exit:

Date leaving U.S.:

Transporter Signature (for exports only):

16. Transporter Acknowledgment of Receipt of Materials

Transporter 1 Printed/Typed Name

Signature

Month Day Year

X Zachary H Smith

[Signature]

9 1 16

Transporter 2 Printed/Typed Name

Signature

Month Day Year

17. Discrepancy

17a. Discrepancy Indication Space

☐ Quantity

☐ Type

☐ Residue

☐ Partial Rejection

☐ Full Rejection

Manifest Reference Number:

17b. Alternate Facility (or Generator)

U.S. EPA ID Number

Facility's Phone:

17c. Signature of Alternate Facility (or Generator)

Month Day Year

18. Designated Facility Owner or Operator: Certification of receipt of materials covered by the manifest except as noted in item 17a

Printed/Typed Name

Signature

Month Day Year

Kathleen A Gansley

[Signature]

9 1 16

CHAUTAUQUA COUNTY LANDFILL
3889 Towerville Road
Jamestown, New York 14701

000486 ZOLADZ CONSTRUCTION COMPANY
13600 RAILROAD STREET
ALDEN NY 14004

SITE	TICKET	GRID		WEIGHMASTER	
02	202961	9		CHRIS GOODWILL	
DATE IN	DATE OUT	TIME IN	TIME OUT	VEHICLE	ROLL OFF
09/28/16	09/28/16	11:04	11:04	ZC284	
REFERENCE			ORIGIN		
041416S1			ERIE COUNTY (NY)		

Scale 1 Gross Wt.	64860	LB	Inbound - Charge ticket
Stored Tare Wt.	25200	LB	
Net Weight	39660	LB	

QTY.	UNIT	DESCRIPTION	RATE	EXTENSION	FEE	TOTAL
19.83	TON	Soil Benefit OutCo				

Operating hours 7:30 AM to 3:30 PM Monday thru Friday.

This is to certify that this load does not contain any hazardous materials, medical waste or liquids of any type.

Telephone (716) 985-4785

Driver TECUMSEH REDEVELOPMENT INC

Generator 2303 HAMBURG TURNPIKE

Comment LACKAWANNA, NY 14218

Hauler: ZOLADZ CONSTRUCTION COMPANY

NET AMOUNT
TENDERED
CHANGE
CHECK NO.

WW6TI TO REORDER CONTACT CAROLINA SOFTWARE (910) 799-6767 SIGNATURE _____

NON-HAZARDOUS WASTE MANIFEST	1. Generator ID Number	2. Page 1 of	3. Emergency Response Phone	4. Waste Tracking Number
	856-0599			
5. Generator's Name and Mailing Address		Generator's Site Address (if different than mailing address)		
TAMM, REDUCED, INC. 211 HARRIS TOWN AVE LAWRENCE, NY 14057				
Generator's Phone: 1405 856-0599				
6. Transporter 1 Company Name		U.S. EPA ID Number		
ZADZ CONSI CO, INC		91499 9 TRUCK #34		
7. Transporter 2 Company Name		U.S. EPA ID Number		
8. Designated Facility Name and Site Address		U.S. EPA ID Number		
CHATEAUGRA CTR 2F LAWRENCE, NY 14057				
Facility's Phone: 1405 985-4785				
9. Waste Shipping Name and Description	10. Containers		11. Total Quantity	12. Unit Wt/Vol.
	No.	Type		
	1	DR	1	2000 LBS
	2			
	3			
13. Special Handling Instructions and Additional Information				
14. GENERATOR'S/OFFEROR'S CERTIFICATION: I hereby declare that the contents of this consignment are fully and accurately described above by the proper shipping name, and are classified, packaged, marked and labeled/placarded, and are in all respects in proper condition for transport according to applicable international and national governmental regulations.				
Generator's/Offor's Printed/Typed Name		Signature		Month Day Year
K. ASH AS Agent for Generator		[Signature]		7 28 16
15. International Shipments ☐ Import to U.S. ☐ Export from U.S.		Port of entry/exit: _____ Date leaving U.S.: _____		
16. Transporter Acknowledgment of Receipt of Materials				
Transporter 1 Printed/Typed Name		Signature		Month Day Year
X Rudy Harris		[Signature]		9 28 16
Transporter 2 Printed/Typed Name		Signature		Month Day Year
17. Discrepancy				
17a. Discrepancy Indication Space ☐ Quantity ☐ Type ☐ Residue ☐ Partial Rejection ☐ Full Rejection				
Manifest Reference Number: _____				
17b. Alternate Facility (or Generator)		U.S. EPA ID Number		
Facility's Phone: _____				
17c. Signature of Alternate Facility (or Generator)		Month Day Year		
18. Designated Facility Owner or Operator: Certification of receipt of materials covered by the manifest except as noted in Item 17a				
Printed/Typed Name		Signature		Month Day Year
K. ASH AS Agent for Generator		[Signature]		9 28 16

CHAUTAUQUA COUNTY LANDFILL
3889 Towerville Road
Jamestown, New York 14701

000486 ZOLADZ CONSTRUCTION COMPANY
13600 RAILROAD STREET
ALDEN NY 14004

SITE	TICKET	GRID		WEIGHMASTER	
02	203030	9		CHRIS GOODWILL	
DATE IN	DATE OUT	TIME IN	TIME OUT	VEHICLE	ROLL OFF
09/29/16	09/29/16	08:41	08:41	ZC181	
REFERENCE		ORIGIN			
041416S1		ERIE COUNTY (NY)			

Scale 1 Gross Wt. 74600 LB
Stored Tare Wt. 27420 LB
Net Weight 47180 LB

Inbound - Charge ticket

QTY.	UNIT	DESCRIPTION	RATE	EXTENSION	FEE	TOTAL
23.59	TON	Soil Benefit OutCo				

Operating hours 7:30 AM to 3:30 PM Monday thru Friday.

This is to certify that this load does not contain any hazardous materials, medical waste or liquids of any type.

Telephone (716) 985-4785

Driver TECUMSEH REDEVELOPMENT INC

Generator 2303 HAMBURG TURNPIKE

Comment LACKAWANNA, NY 14218

Hauler: <USE ONLY AT LANDFILL>

NET AMOUNT
TENDERED
CHANGE
CHECK NO.

WW6T1 TO REORDER CONTACT CAROLINA SOFTWARE (910) 799-6767 SIGNATURE _____

NON-HAZARDOUS
WASTE MANIFEST

1. Generator ID Number

2. Page 1 of

3. Emergency Response Phone

4. Waste Tracking Number

5. Generator's Name and Mailing Address

Generator's Site Address (if different than mailing address)

TECHNICAL REDEVELOPMENT, INC
2558 HUMBOLDT TOWNSHIP, ALLEGANY, WV
14028

Generator's Phone:

6. Transporter 1 Company Name

U.S. EPA ID Number

20002 CONST CO, INC

99999

7. Transporter 2 Company Name

U.S. EPA ID Number

8. Designated Facility Name and Site Address

U.S. EPA ID Number

CHAMBERSIA CIV LF
ENR, NY

Facility's Phone: 755-4755

9. Waste Shipping Name and Description

10. Containers

No.

Type

11. Total
Quantity12. Unit
Wt./Vol.

1. NON RES SOIL/FILL CC 041410 SI

1

D1

2

3

4

13. Special Handling Instructions and Additional Information

14. GENERATOR'S/OFFEROR'S CERTIFICATION: I hereby declare that the contents of this consignment are fully and accurately described above by the proper shipping name, and are classified, packaged, marked and labeled/placarded, and are in all respects in proper condition for transport according to applicable international and national governmental regulations.

Generator's/Offor's Printed/Typed Name

Signature

Month Day Year

J. R. R. AS A.M. FOR GOVERNMENT

9/29/16

15. International Shipments

☐ Import to U.S.☐ Export from U.S.

Port of entry/exit:

Transporter Signature (for exports only):

Date leaving U.S.:

16. Transporter Acknowledgment of Receipt of Materials

Transporter 1 Printed/Typed Name

Signature

Month Day Year

* Mary Langworthy

* Mary Langworthy

9/29/16

Transporter 2 Printed/Typed Name

Signature

Month Day Year

17. Discrepancy

17a. Discrepancy Indication Space

☐ Quantity☐ Type☐ Residue☐ Partial Rejection☐ Full Rejection

Manifest Reference Number:

17b. Alternate Facility (or Generator)

U.S. EPA ID Number

Facility's Phone:

17c. Signature of Alternate Facility (or Generator)

Month Day Year

18. Designated Facility Owner or Operator: Certification of receipt of materials covered by the manifest except as noted in Item 17a

Printed/Typed Name

Signature

Month Day Year

Patricia C. Spence

Patricia C. Spence

9/29/16

CHAUTAUQUA COUNTY LANDFILL
3889 Towerville Road
Jamestown, New York 14701

000486 ZOLADZ CONSTRUCTION COMPANY
13600 RAILROAD STREET
ALDEN NY 14004

SITE	TICKET	GRID		WEIGHMASTER	
02	203067	9		CHRIS GOODWILL	
DATE IN	DATE OUT	TIME IN	TIME OUT	VEHICLE	ROLL OFF
09/29/16	09/29/16	11:43	11:43	ZC181	
REFERENCE			ORIGIN		
041416S1			ERIE COUNTY (NY)		

Scale 1 Gross Wt. 65940 LB
Stored Tare Wt. 27420 LB
Net Weight 38520 LB

Inbound - Charge ticket

QTY.	UNIT	DESCRIPTION	RATE	EXTENSION	FEE	TOTAL
19.26	TON	Soil Benefit OutCo				

Operating hours 7:30 AM to 3:30 PM Monday thru Friday.

This is to certify that this load does not contain any hazardous materials, medical waste or liquids of any type.

Telephone (716) 985-4785

Driver TECUMSEH REDEVELOPMENT INC

Generator 2303 HAMBURG TURNPIKE

Comment LACKAWANNA, NY 14218

Hauler: <USE ONLY AT LANDFILL>

WW6T1 TO REORDER CONTACT CAROLINA SOFTWARE (910) 799-6767 SIGNATURE _____

NET AMOUNT
TENDERED
CHANGE
CHECK NO.

NON-HAZARDOUS WASTE MANIFEST		1. Generator ID Number		2. Page 1 of		3. Emergency Response Phone 856-6599		4. Waste Tracking Number																			
		5. Generator's Name and Mailing Address Teclumseh Redevelopment, Inc. 2558 Hamburg Turnpike, Larkawanna, NY 14214		Generator's Site Address (if different than mailing address)																							
GENERATOR		6. Transporter 1 Company Name Zolner Const. Co., Inc						U.S. EPA ID Number																			
		7. Transporter 2 Company Name						U.S. EPA ID Number																			
DESIGNATED FACILITY		8. Designated Facility Name and Site Address Chattanooga County Landfill Ellery, NY 965-4285						U.S. EPA ID Number																			
		9. Waste Shipping Name and Description Non-ry Soil/Fill						10. Containers		11. Total Quantity	12. Unit Wt./Vol.																
TRANSPORTER		<table border="1" style="width:100%; border-collapse: collapse;"> <tr> <th colspan="2">10. Containers</th> <th rowspan="2">11. Total Quantity</th> <th rowspan="2">12. Unit Wt./Vol.</th> </tr> <tr> <th>No.</th> <th>Type</th> </tr> <tr> <td>1.</td> <td>CC041410.51</td> <td rowspan="3">1</td> <td rowspan="3">DT</td> </tr> <tr> <td>2.</td> <td></td> </tr> <tr> <td>3.</td> <td></td> </tr> <tr> <td>4.</td> <td></td> <td></td> <td></td> </tr> </table>						10. Containers		11. Total Quantity	12. Unit Wt./Vol.	No.	Type	1.	CC041410.51	1	DT	2.		3.		4.					
								10. Containers				11. Total Quantity	12. Unit Wt./Vol.														
								No.	Type																		
								1.	CC041410.51	1	DT																
2.																											
3.																											
4.																											
13. Special Handling Instructions and Additional Information																											
14. GENERATOR'S/OFFEROR'S CERTIFICATION: I hereby declare that the contents of this consignment are fully and accurately described above by the proper shipping name, and are classified, packaged, marked and labeled/placarded, and are in all respects in proper condition for transport according to applicable international and national governmental regulations.																											
Generator's/Offor's Printed/Typed Name D. Lohman - as agent for generator						Signature <i>[Signature]</i>		Month 9	Day 27	Year 16																	
15. International Shipments ☐ Import to U.S. ☐ Export from U.S.						Port of entry/exit: Date leaving U.S.:																					
16. Transporter Acknowledgment of Receipt of Materials Transporter 1 Printed/Typed Name * Mary Langworthy						Signature <i>[Signature]</i>		Month 9	Day 28	Year 16																	
Transporter 2 Printed/Typed Name						Signature		Month	Day	Year																	
17. Discrepancy																											
17a. Discrepancy Indication Space ☐ Quantity ☐ Type ☐ Residue ☐ Partial Rejection ☐ Full Rejection						Manifest Reference Number:																					
17b. Alternate Facility (or Generator)						U.S. EPA ID Number																					
Facility's Phone:																											
17c. Signature of Alternate Facility (or Generator)								Month	Day	Year																	
18. Designated Facility Owner or Operator: Certification of receipt of materials covered by the manifest except as noted in Item 17a																											
Printed/Typed Name Ruth A. Gansley						Signature <i>[Signature]</i>		Month 11	Day 16	Year 16																	

Mar 18/13

CHAUTAUQUA COUNTY LANDFILL
3889 Towerville Road
Jamestown, New York 14701

000486 ZOLADZ CONSTRUCTION COMPANY
13600 RAILROAD STREET
ALDEN NY 14004

SITE	TICKET	GRID		WEIGHMASTER	
02	203111	9		CHRIS GOODWILL	
DATE IN	DATE OUT	TIME IN	TIME OUT	VEHICLE	ROLL OFF
09/29/16	09/29/16	15:08	15:08	ZC181	
REFERENCE			ORIGIN		
041416S1			ERIE COUNTY (NY)		

Scale 1 Gross Wt. 78460 LB
Stored Tare Wt. 27420 LB
Net Weight 51040 LB

Inbound - Charge ticket

QTY.	UNIT	DESCRIPTION	RATE	EXTENSION	FEE	TOTAL
25.52	TON	Soil Benefit OutCo				

Operating hours 7:30 AM to 3:30 PM Monday thru Friday.

This is to certify that this load does not contain any hazardous materials, medical waste or liquids of any type.

Telephone (716) 985-4785

Driver : TECUMSEH REDEVELOPMENT INC

Generator 2303 HAMBURG TURNPIKE

Comment LACKAWANNA, NY 14218

Hauler: <USE ONLY AT LANDFILL>

NET AMOUNT
TENDERED
CHANGE
CHECK NO.

WW6TI TO REORDER CONTACT CAROLINA SOFTWARE (910) 799-6767 SIGNATURE _____

NON-HAZARDOUS
WASTE MANIFEST

1. Generator ID Number

2. Page 1 of

3. Emergency Response Phone

4. Waste Tracking Number

956-0599

5. Generator's Name and Mailing Address

Generator's Site Address (if different than mailing address)

Tecumseh Redevelopment, Inc.

2558 Hamburg Turnpike, Lackawanna, NY
14203

Generator's Phone:

6. Transporter 1 Company Name

U.S. EPA ID Number

Zolade Const. Co., Inc.

9A 489

7. Transporter 2 Company Name

U.S. EPA ID Number

8. Designated Facility Name and Site Address

U.S. EPA ID Number

Chautauque County Landfill
Elletts, NY

Facility's Phone:

945-4785

9. Waste Shipping Name and Description

10. Containers

11. Total
Quantity12. Unit
Wt./Vol.

No.

Type

1.

22041410.51

Non-reg Soil/Fill

1 DT

2.

3.

4.

13. Special Handling Instructions and Additional Information

14. GENERATOR'S/OFFEROR'S CERTIFICATION: I hereby declare that the contents of this consignment are fully and accurately described above by the proper shipping name, and are classified, packaged, marked and labeled/placarded, and are in all respects in proper condition for transport according to applicable international and national governmental regulations.

Generator's/Officer's Printed/Typed Name

Signature

Month Day Year

R. Lebrano - as agent for generator

[Signature]

9 29 16

15. International Shipments

☐ Import to U.S.☐ Export from U.S.

Port of entry/exit:

Date leaving U.S.:

Transporter Signature (for exports only):

16. Transporter Acknowledgment of Receipt of Materials

Transporter 1 Printed/Typed Name

Signature

Month Day Year

* MARY LANGWORTHY

[Signature]

9 29 16

Transporter 2 Printed/Typed Name

Signature

Month Day Year

17. Discrepancy

17a. Discrepancy Indication Space

☐ Quantity☐ Type☐ Residue☐ Partial Rejection☐ Full Rejection

Manifest Reference Number:

17b. Alternate Facility (or Generator)

U.S. EPA ID Number

Facility's Phone:

17c. Signature of Alternate Facility (or Generator)

Month Day Year

18. Designated Facility Owner or Operator: Certification of receipt of materials covered by the manifest except as noted in Item 17a

Printer/Typed Name

Signature

Month Day Year

Patricia Garmsey

[Signature]

9 29 16

CHAUTAUQUA COUNTY LANDFILL
3889 Towerville Road
Jamestown, New York 14701

000486 ZOLADZ CONSTRUCTION COMPANY
13600 RAILROAD STREET
ALDEN NY 14004

SITE	TICKET	GRID		WEIGHMASTER	
02	203068	9		CHRIS GOODWILL	
DATE IN	DATE OUT	TIME IN	TIME OUT	VEHICLE	ROLL OFF
09/29/16	09/29/16	11:44	11:44	ZC284	
REFERENCE		ORIGIN			
041416S1		ERIE COUNTY (NY)			

Inbound - Charge ticket

Scale 1 Gross Wt.	54420	LB
Stored Tare Wt.	25200	LB
Net Weight	29220	LB

QTY	UNIT	DESCRIPTION	RATE	EXTENSION	FEE	TOTAL
14.61	TON	Soil Benefit OutCo				

Operating hours 7:30 AM to 3:30 PM Monday thru Friday.

This is to certify that this load does not contain any hazardous materials, medical waste or liquids of any type.

Telephone (716) 985-4785

Driver TECUMSEH REDEVELOPMENT INC

Generator 2303 HAMBURG TURNPIKE

Comment LACKAWANNA, NY 14218

Hauler: ZOLADZ CONSTRUCTION COMPANY




WW6T1 TO REORDER CONTACT CAROLINA SOFTWARE (910) 799-6767 SIGNATURE

NET AMOUNT

TENDERED

CHANGE

CHECK NO.

NON-HAZARDOUS WASTE MANIFEST		1. Generator ID Number		2. Page 1 of		3. Emergency Response Phone 856-0599		4. Waste Tracking Number	
5. Generator's Name and Mailing Address Tecumseh Refrillomatic, Inc 2557 Hamburg Turnpike ALKAWANNA, NY Generator's Phone: 856-0599 14218		Generator's Site Address (if different than mailing address)							
6. Transporter 1 Company Name Zulawski Const Co, Inc		7. Transporter 2 Company Name		U.S. EPA ID Number 9A499		U.S. EPA ID Number THIA #229		U.S. EPA ID Number	
8. Designated Facility Name and Site Address Chautauque Co LF Elmira, NY Facility's Phone: 955-4785		U.S. EPA ID Number							
9. Waste Shipping Name and Description 1. new 45 SOL/FILL CC041416 ST		10. Containers No. Type 1 DT		11. Total Quantity		12. Unit Wt./Vol.			
13. Special Handling Instructions and Additional Information									
14. GENERATOR'S/OFFEROR'S CERTIFICATION: I hereby declare that the contents of this consignment are fully and accurately described above by the proper shipping name, and are classified, packaged, marked and labeled/placarded, and are in all respects in proper condition for transport according to applicable international and national governmental regulations.									
Generator's/Offoror's Printed/Typed Name JOSE AN ALAN FUL GARCIA				Signature 		Month Day Year 9 29 16			
15. International Shipments ☐ Import to U.S. ☐ Export from U.S.									
16. Transporter Acknowledgment of Receipt of Materials									
Transporter 1 Printed/Typed Name X Rudy H...				Signature 		Month Day Year 9 29 16			
Transporter 2 Printed/Typed Name				Signature		Month Day Year			
17. Discrepancy									
17a. Discrepancy Indication Space ☐ Quantity ☐ Type ☐ Residue ☐ Partial Rejection ☐ Full Rejection									
17b. Alternate Facility (or Generator) Manifest Reference Number: U.S. EPA ID Number									
Facility's Phone:									
17c. Signature of Alternate Facility (or Generator) Month Day Year									
18. Designated Facility Owner or Operator: Certification of receipt of materials covered by the manifest except as noted in Item 17a									
Printed/Typed Name Kathleen G...				Signature 		Month Day Year 9 29 16			

CHAUTAUQUA COUNTY LANDFILL
3889 Towerville Road
Jamestown, New York 14701

000486 ZOLADZ CONSTRUCTION COMPANY
13600 RAILROAD STREET
ALDEN NY 14004

SITE	TICKET	GRID		WEIGHMASTER	
02	203031	9		CHRIS GOODWILL	
DATE IN	DATE OUT	TIME IN	TIME OUT	VEHICLE	ROLL OFF
09/29/16	09/29/16	08:42	08:42	ZC284	
REFERENCE			ORIGIN		
041416S1			ERIE COUNTY (NY)		

Scale 1 Gross Wt. 62020 LB
Stored Tare Wt. 25200 LB
Net Weight 36820 LB

Inbound - Charge ticket

QTY.	UNIT	DESCRIPTION	RATE	EXTENSION	FEE	TOTAL
18.41	TON	Soil Benefit OutCo				

Operating hours 7:30 AM to 3:30 PM Monday thru Friday.

This is to certify that this load does not contain any
hazardous materials, medical waste or liquids of any
type.

Telephone (716) 985-4785

Driver TECUMSEH REDEVELOPMENT INC

Generator 2303 HAMBURG TURNPIKE

Comment LACKAWANNA, NY 14218

Hauler: ZOLADZ CONSTRUCTION COMPANY

NET AMOUNT
TENDERED
CHANGE
CHECK NO.

WW6T1 TO REORDER CONTACT CAROLINA SOFTWARE (910) 799-6767 SIGNATURE _____

**NON-HAZARDOUS
WASTE MANIFEST**

1. Generator ID Number

2. Page 1 of

3. Emergency Response Phone

856-0599

4. Waste Tracking Number

5. Generator's Name and Mailing Address

TECUMSEH Redevelopment, Inc.
2558 Hamburg Turnpike, Lockawanna, NY

Generator's Site Address (if different than mailing address)

Generator's Phone:

14218

6. Transporter 1 Company Name

Zoladz Const. Co., Inc.

U.S. EPA ID Number

7. Transporter 2 Company Name

U.S. EPA ID Number

8. Designated Facility Name and Site Address

Chautauque County Landfill
Ellery, NY

U.S. EPA ID Number

Facility's Phone:

985-4785

9. Waste Shipping Name and Description

10. Containers

No.

Type

11. Total
Quantity

12. Unit
Wt./Vol.

1.

Non-Reg soil/Fill

CC041410.51

1

DT

2.

3.

4.

13. Special Handling Instructions and Additional Information

14. GENERATOR'S/OFFEROR'S CERTIFICATION: I hereby declare that the contents of this consignment are fully and accurately described above by the proper shipping name, and are classified, packaged, marked and labeled/placarded, and are in all respects in proper condition for transport according to applicable international and national governmental regulations.

Generator's/Offor's Printed/Typed Name

Signature

Month Day Year

R. Lebrano - as agent for generator

[Signature]

1 29 16

15. International Shipments

☐ Import to U.S.

☐ Export from U.S.

Port of entry/exit:

Date leaving U.S.:

16. Transporter Acknowledgment of Receipt of Materials

Transporter 1 Printed/Typed Name

Signature

Month Day Year

X Rudy Harris

X Rudy Harris

Transporter 2 Printed/Typed Name

Signature

Month Day Year

17. Discrepancy

17a. Discrepancy Indication Space

☐ Quantity

☐ Type

☐ Residue

☐ Partial Rejection

☐ Full Rejection

Manifest Reference Number:

17b. Alternate Facility (or Generator)

U.S. EPA ID Number

Facility's Phone:

17c. Signature of Alternate Facility (or Generator)

Month Day Year

18. Designated Facility Owner or Operator: Certification of receipt of materials covered by the manifest except as noted in Item 17a

Printed/Typed Name

Signature

Month Day Year

Rafael A. Garmey

Rafael A. Garmey

9 29 16

CHAUTAUQUA COUNTY LANDFILL
3889 Towerville Road
Jamestown, New York 14701

000486 ZOLADZ CONSTRUCTION COMPANY
13600 RAILROAD STREET
ALDEN NY 14004

SITE	TICKET	GRID		WEIGHMASTER	
02	203114	9		CHRIS GOODWILL	
DATE IN	DATE OUT	TIME IN	TIME OUT	VEHICLE	ROLL OFF
09/29/16	09/29/16	15:17	15:17	ZC284	
REFERENCE			ORIGIN		
041416S1			ERIE COUNTY (NY)		

Scale 1 Gross Wt. 65640 LB
Stored Tare Wt. 25200 LB
Net Weight 40440 LB

Inbound - Charge ticket

QTY.	UNIT	DESCRIPTION	RATE	EXTENSION	FEE	TOTAL
20.22	TON	Soil Benefit OutCo				

Operating hours 7:30 AM to 3:30 PM Monday thru Friday.

This is to certify that this load does not contain any hazardous materials, medical waste or liquids of any type:

Telephone (716) 985-4785

Driver TECUMSEH REDEVELOPMENT INC

Generator 2303 HAMBURG TURNPIKE

Comment LACKAWANNA, NY 14218

Hauler: ZOLADZ CONSTRUCTION COMPANY

WW6T1 TO REORDER CONTACT CAROLINA SOFTWARE (910) 799-6767 SIGNATURE _____

NET AMOUNT
TENDERED
CHANGE
CHECK NO.

GENERATOR	NON-HAZARDOUS WASTE MANIFEST		1. Generator ID Number		2. Page 1 of		3. Emergency Response Phone 856-0599		4. Waste Tracking Number	
	5. Generator's Name and Mailing Address Terumseh Redevelopment, Inc 2558 Hamburg Turnpike, Lockport, NY Generator's Phone: 14213					Generator's Site Address (if different than mailing address)				
	6. Transporter 1 Company Name Zoladz Const. Co, Inc					U.S. EPA ID Number				
	7. Transporter 2 Company Name					U.S. EPA ID Number				
	8. Designated Facility Name and Site Address Clatsop County Landfill Ellen, NY Facility's Phone: 485-4785					U.S. EPA ID Number				
	9. Waste Shipping Name and Description 1. Non-Reg Soil/Fill 10041410.51					10. Containers		11. Total Quantity	12. Unit Wt./Vol.	
						No.	Type			
13. Special Handling Instructions and Additional Information										
14. GENERATOR'S/OFFEROR'S CERTIFICATION: I hereby declare that the contents of this consignment are fully and accurately described above by the proper shipping name, and are classified, packaged, marked and labeled/placarded, and are in all respects in proper condition for transport according to applicable international and national governmental regulations.										
Generator's/Offor's Printed/Typed Name R. Labran - agent for generator					Signature [Signature]			Month Day Year 9/29/16		
TRANSPORTER	15. International Shipments ☐ Import to U.S. ☐ Export from U.S.					Port of entry/exit: Date leaving U.S.:				
	16. Transporter Acknowledgment of Receipt of Materials									
	Transporter 1 Printed/Typed Name x Rudy Ham					Signature x Rudy Ham			Month Day Year	
	Transporter 2 Printed/Typed Name					Signature			Month Day Year	
DESIGNATED FACILITY	17. Discrepancy									
	17a. Discrepancy Indication Space ☐ Quantity ☐ Type ☐ Residue ☐ Partial Rejection ☐ Full Rejection									
	17b. Alternate Facility (or Generator)					Manifest Reference Number: U.S. EPA ID Number				
	Facility's Phone:									
	17c. Signature of Alternate Facility (or Generator)					Month Day Year				
18. Designated Facility Owner or Operator: Certification of receipt of materials covered by the manifest except as noted in Item 17a										
Printed/Typed Name Kathleen G. Gansley					Signature Kathleen G. Gansley			Month Day Year 9/29/16		

****DUPLICATE TICKET****

CHAUTAUQUA COUNTY LANDFILL
3889 Towerville Road
Jamestown, New York 14701

000486 ZOLADZ CONSTRUCTION COMPANY
13600 RAILROAD STREET
ALDEN NY 14004

TICKET		GRID		WEIGHMASTER	
02	203036	9	CHRIS GOODWILL		
DATE IN	DATE OUT	TIME IN	TIME OUT	VEHICLE	ROLL OFF
09/29/16	09/29/16	09:00	09:00	ECON246E	
REFERENCE			ORIGIN		
041416S1			ERIE COUNTY (NY)		

Inbound - Charge ticket

Manual Gross Wt. 70140 LB
Stored Tare Wt. 28580 LB
Net Weight 41560 LB

QTY.	UNIT	DESCRIPTION	RATE	EXTENSION	FEE	TOTAL
20.78	TON	Soil Benefit OutCo				

Operating hours 7:30 AM to 3:30 P.M. Monday thru Friday.

This is to certify that this load does not contain any hazardous materials, medical waste or liquids of any type.

Telephone (716) 985-4785

Driver TECUMSEH REDEVELOPMENT INC

Generator 2303 HAMBURG TURNPIKE

Comment LACKAWANNA, NY 14218

Hauler: <USE ONLY AT LANDFILL>

WW671 TO REORDER CONTACT CAROLINA SOFTWARE (910) 799-6767 SIGNATURE

NET AMOUNT
TENDERED
CHANGE
CHECK NO.

CHAUTAUQUA COUNTY LANDFILL
3889 Towerville Road
Jamestown, New York 14701

000486 ZOLADZ CONSTRUCTION COMPANY
13600 RAILROAD STREET
ALDEN NY 14004

SITE	TICKET	GRID		WEIGHMASTER	
02	203176	9		CHRIS GOODWILL	
DATE IN	DATE OUT	TIME IN	TIME OUT	VEHICLE	ROLL OFF
09/30/16	09/30/16	12:15	12:15	ZC181	
REFERENCE		ORIGIN			
041416S1		ERIE COUNTY (NY)			

Scale 1 Gross Wt.	62520	LB	Inbound - Charge ticket
Stored Tare Wt.	27420	LB	
Net Weight	35100	LB	

QTY.	UNIT	DESCRIPTION	RATE	EXTENSION	FEE	TOTAL
17.55	TON	Soil Benefit OutCo				

Operating hours 7:30 AM to 3:30 PM Monday thru Friday.

This is to certify that this load does not contain any hazardous materials, medical waste or liquids of any type. Telephone (716) 985-4785

Driver TECUMSEH REDEVELOPMENT INC

Generator 2303 HAMBURG TURNPIKE

Comment LACKAWANNA, NY 14218

Hauler: <USE ONLY AT LANDFILL>

NET AMOUNT
TENDERED
CHANGE
CHECK NO.

**NON-HAZARDOUS
WASTE MANIFEST**

1. Generator ID Number

2. Page (of)

3. Emergency Response Phone

4. Waste Tracking Number

888-6579

5. Generator's Name and Mailing Address

Tecumseh Redevelopment, Inc
285a Hemlock Turnpike, Hickory, NY
14218

Generator's Site Address (if different than mailing address)

Generator's Phone

6. Transporter 1 Company Name

Edward J. Cost Co, Inc

U.S. EPA ID Number

9A 4779

7. Transporter 2 Company Name

U.S. EPA ID Number

8. Designated Facility Name and Site Address

Champlain County Health
Center, NY
185-4775

U.S. EPA ID Number

Facility's Phone

9. Waste Shipping Name and Description

Non-hg soil/Fill

10. Containers

No.

Type

11. Total Quantity

12. Unit (M/V)

1

DT

13. Special Handling Instructions and Additional Information

14. GENERATOR'S/OFFEROR'S CERTIFICATION: I hereby declare that the contents of this consignment are fully and accurately described above by the proper shipping name, and are classified, packaged, marked and labeled/placarded, and are in all respects in proper condition for transport according to applicable international and national governmental regulations.

Generator's/Officer's Printed/Typed Name

R. DUBSE AS AGENT FOR GARRETT

Signature

[Signature]

Month Day Year

9 30 16

15. International Shipments

☐

Import to U.S.

☐

Export from U.S.

Port of entry/exit

Transporter Signature (for exports only)

Date leaving U.S.

16. Transporter Acknowledgment of Receipt of Materials

Transporter 1 Printed/Typed Name

MARY LANGWORTHY

Signature

[Signature]

Month Day Year

9 30 16

Transporter 2 Printed/Typed Name

Signature

Month Day Year

17. Discrepancy

17a. Discrepancy Indication Space

☐

Quantity

☐

Type

☐

Residue

☐

Partial Reception

☒

Full Reception

17b. Alternate Facility (or Generator)

Manifest Reference Number

U.S. EPA ID Number

Facility's Phone

17c. Signature of Alternate Facility (or Generator)

Month Day Year

18. Designated Facility Owner's Certificate: I understand materials covered by the manifest are to be used in the following manner:

Landfill

Landfill

9 30 16

000486 ZOLADZ CONSTRUCTION COMPANY
13600 RAILROAD STREET
ALDEN NY 14004

SITE	TICKET	GRID		WEIGHMASTER	
02	203135	9		CHRIS GOODWILL	
DATE IN	DATE OUT	TIME IN	TIME OUT	VEHICLE	ROLL OFF
09/30/16	09/30/16	08:48	08:48	ZC181	
REFERENCE		ORIGIN			
041416S1		ERIE COUNTY (NY)			

Scale 1 Gross Wt.		68800	LB	Inbound - Charge ticket		
Stored Tare Wt.		27420	LB			
Net Weight		41380	LB			

QTY.	UNIT	DESCRIPTION	RATE	EXTENSION	FEE	TOTAL
20.69	TON	Soil Benefit OutCo				

Operating hours 7:30 AM to 3:30 PM Monday thru Friday.

This is to certify that this load does not contain any hazardous materials, medical waste or liquids of any type. Telephone (716) 985-4785

type. Telephone (716) 985-4785
Driver TECUMSEH REDEVELOPMENT INC
Generator 2303 HAMBURG TURNPIKE
Comment LACKAWANNA, NY 14218
Hauler: <USE ONLY AT LANDFILL>

NET AMOUNT
TENDERED
CHANGE
CHECK NO.

NAME _____ PHONE NO. _____
 ADDRESS _____
 CITY _____ STATE _____ ZIP _____
 E-MAIL _____
 FAX NO. _____
 TO REORDER CONTACT CAROLINA SOFTWARE (910) 799-6767 SIGNATURE _____

**NON-HAZARDOUS
WASTE MANIFEST**

1. Generator ID Number

2. Page 1 of 1

3. Emergency Response Phone

4. Waste Tracking Number

856-0599

5. Generator's Name and Mailing Address

Tecumseh Redevelopment, Inc.
2558 Hansburg Turnpike, Littleton, NY
General Phone: 742-14

Generator's Site Address (if different than mailing address)

6. Transporter's Company Name

20th Century Corp. Inc.

U.S. EPA ID Number

91999

7. Transporter's Company Name

U.S. EPA ID Number

8. Designator Facility Name and Site Address

Chautauque County Landfill
Ellettsburg, NY
Facility Phone: 745-4785

U.S. EPA ID Number

9. Waste Shipping Name and Description

Non-reg. Sp. 1/F 11

10. Containers

No.

Type

11. Total Quantity

12. Unit Wt/Vol

CE 111-110-51

Dr

13. Special Handling Instructions and Additional Information

14. GENERATOR'S OFFEROR'S CERTIFICATION: I hereby declare that the contents of this consignment are fully and accurately described above by the proper shipping name, and are classified, packaged, marked and labeled, prepared, and are in all respects in proper condition for transport according to applicable international and national governmental regulations.

Generator's/Officer's Printed/Typed Name

Signature

R. Lebrun

[Signature]

Month: 7 Day: 20 Year: 16

15. International Shipments

☒ Import to U.S.

☐ Export from U.S.

Port of entry/exit

Transporter's Signature (for exports only)

Date leaving U.S.

16. Transporter's Acknowledgment of Receipt of Materials

Transporter's Printed/Typed Name

Signature

MARY LANGWORTHY

[Signature]

Month: 9 Day: 30 Year: 16

Transporter's 2 Printed/Typed Name

Signature

Month: Day: Year:

17. Discrepancy

17a. Discrepancy Indication Space

☒ Quantity

☐ Type

☐ Residue

☐ Partial Rejection

☐ Full Rejection

Manifest Reference Number

17b. Alternate Facility (or Generator)

U.S. EPA ID Number

Facility's Phone

17c. Signature of Alternate Facility (or Generator)

Month: Day: Year:

18. I, the Receiver, Owner, Operator, or other person in control of the materials covered by this manifest, declare that the information is true and correct.

John A. Gansley

[Signature]

Month: 10 Day: 3 Year: 16

000486 ZOLADZ CONSTRUCTION COMPANY
13600 RAILROAD STREET
ALDEN NY 14004

SITE	TICKET	GRID		WEIGHMASTER	
02	203283	9		PATTI GARNSEY	
DATE IN	DATE OUT	TIME IN	TIME OUT	VEHICLE	ROLL OFF
10/03/16	10/03/16	13:01	13:01	ZC181	
REFERENCE		ORIGIN			
		ERIE COUNTY (NY)			

Scale 1 Gross Wt.		58460	LB	Inbound - Charge ticket			
Stored Tare Wt.		27420	LB				
Net Weight		31040	LB				
QTY.	UNIT	DESCRIPTION		RATE	EXTENSION	FEE	TOTAL
15.52	TON	Soil Contam OutCo					

This is to certify that this load does not contain any hazardous materials, medical waste or liquids of any type. Telephone (716) 985-4785

Driver	TECUMSEH REDEVELOPMENT
Generator	2558 HAMBURG TURNPIKE
Comment	LACKAWANNA NY
Hauler:	<USE ONLY AT LANDFILL>

WW6T1 TO REORDER CONTACT CAROLINA SOFTWARE (910) 799-6767

SIGNATURE

NET AMOUNT
TENDERED
CHANGE
CHECK NO.

NON-HAZARDOUS
WASTE MANIFEST

1. Generator ID Number

2. Page 1 of

3. Emergency Response Phone

4. Waste Tracking Number

856-0599

5. Generator's Name and Mailing Address

Tecumseh Redevelopment, Inc
2558 Hamburg Turnpike, Lockport, NY
14218

Generator's Site Address (if different than mailing address)

Generator's Phone:

6. Transporter 1 Company Name

Zoladz Const. Co., Inc

U.S. EPA ID Number

9A 499

7. Transporter 2 Company Name

U.S. EPA ID Number

8. Designated Facility Name and Site Address

Chautauque County Landfill
Elletts, NY

U.S. EPA ID Number

Facility's Phone:

985-4785

9. Waste Shipping Name and Description

10. Containers

11. Total
Quantity12. Unit
Wt./Vol.

1.

No.

Type

Non-reg Sol./Fill

CC041410.51

1

DT

2.

3.

4.

13. Special Handling Instructions and Additional Information

14. GENERATOR'S/OFFEROR'S CERTIFICATION: I hereby declare that the contents of this consignment are fully and accurately described above by the proper shipping name, and are classified, packaged, marked and labeled/placarded, and are in all respects in proper condition for transport according to applicable international and national governmental regulations.

Generator's/Offor's Printed/Typed Name

Signature

R. Lebrun - agent for generator

Month Day Year
10 3 16

15. International Shipments

☐

Import to U.S.

☐

Export from U.S.

Port of entry/exit:

Transporter Signature (for exports only):

Date leaving U.S.:

16. Transporter Acknowledgment of Receipt of Materials

Transporter 1 Printed/Typed Name

Signature

x Mary Langworthy

Month Day Year
10 3 16

Transporter 2 Printed/typed Name

Signature

Month Day Year

17. Discrepancy

17a. Discrepancy Indication Space

☐

Quantity

☐

Type

☐

Residue

☐

Partial Rejection

☐

Full Rejection

Manifest Reference Number:

U.S. EPA ID Number

17b. Alternate Facility (or Generator)

Facility's Phone:

17c. Signature of Alternate Facility (or Generator)

Month Day Year

18. Designated Facility Owner or Operator: Certification of receipt of materials covered by the manifest except as noted in Item 17a

Printed/Typed Name

Signature

Patricia A. Gannsey

Month Day Year
10 3 16

APPENDIX C

STONE IMPORT DOCUMENTATION

SUBMITTAL ITEM COVER SHEET

PROJECT No.: 16- 651-

PROJECT NAME: Excavation and Concrete Work at Steel Sun
Lackawanna

SUBMITTAL#: 002 REV: ANTICIPATED RETURN DATE: 09/03/2016 ☐ CRITICAL DATE NEEDED:
CONTRACT #: CONTRACTOR: Mark Cerrone, Inc.
SPEC SECTION #: SPEC SECT TITLE:
SPEC SECT PAR: REF / DWG #:
SUBMITTAL ITEM DESCRIPTION: Aggregates
(Include only one submittal item per cover sheet, each copy must have a copy of the cover sheet attached)
SUBMITTAL ITEM SUBCONTRACTOR/SUPPLIER: New Enterprise Stone & Lime Co., Inc.
SUBMITTAL ITEM MANUFACTURER:
SUBMITTAL ITEM STATUS: Sent

☐ SHOP DRAWING ☐ SCHEDULE ☐ SUBSTITUTE ITEM
☒ PRODUCT DATA ☐ TEST REPORT ☐ SAMPLE ☐ WARRANTY
☐ COLOR SAMPLE ☐ OTHER:

LIST REMARKS AND/OR DETAIL SUBSTITUTIONS FROM SPECIFICATIONS:

FOR MARK CERRONE, INC. USE ONLY

RCVD FROM SUB/SUPPLIER		SENT TO ARCH / ENG	
Date: 08/22/2016	Copies: 1	Date: 08/23/2016	Copies: 1
RCVD FROM ARCH / ENG		SENT TO SUB/SUPPLIER	
Date:	Copies: 1	Date:	Copies: 1
REMARKS:			
I HAVE REVIEWED THIS SUBMITTAL ITEM AND VERIFY THAT IT DOES MEET THE SPECIFICATIONS EXCEPT AS NOTED ABOVE			
REVIEWED BY: Chris Ganje DATE: 8/23/2016			

FOR ARCHITECT / ENGINEER USE ONLY

RCVD FROM MCI		SENT TO MCI	
Date:		Date:	
Copies:		Copies:	
ARCHITECT / ENGINEER ACTION STAMP			

Mailing AddressP.O. Box 3009
Niagara Falls, NY 14304**New York State, Buffalo and Erie County WBE Certified**

An Equal Opportunity Employer

Safety and Quality FirstPhysical Address2368 Maryland Avenue
Niagara Falls, NY 14305



BUFFALO CRUSHED STONE

Division of New Enterprise Stone & Lime Co., Inc.

500 Como Park Blvd, Buffalo, NY 14227 Phone (716) 826-7310 FAX (716) 826-1342



August 22, 2016

Mr. Andrea Calabrese
Mark Cerrone Construction, Inc.
PO Box 3009
Niagara Falls, NY 14304

Re: Steel Sun

Dear Andrea:

We certify the aggregates we supply on the subject project meet the New York State Department of Transportation Specification and Gradations as follows:

Item #304.12 // -2" Crusher Run Type 2 Subbase	
<u>Sieve Size</u>	<u>Percent Passing</u>
2"	100
1/4"	25-60
No. 40	5-40
No. 200	0-10

Item #703.0203 // Round 1A Gravel	
<u>Sieve Size</u>	<u>Percent Passing</u>
1/2"	100
1/4"	90-100
1/8"	0-15

Our New York State Source Number at our Wehrle Drive is 5-3R.

We trust this meets with your approval.

Very truly yours,

Bob Warrington
Account Representative

BW: DJ

**New Enterprise Stone & Lime Co., Inc.**

Buffalo, NY 14227

(716) 826-7310

INVOICE

Invoice No.

6444841

Invoice Date

9/30/2016

INVOICE

Sold To: Mark Cerrone Inc
PO Box 3009
Niagara Falls, NY 143047309

ACH/Wire Payment PNC Bank

Bank Acct # 8026302441

Routing # 031207607

EIN: 23-1374051

SERVICE CHARGE OF 1 1/2% PER MONTH (18% PER ANNUM) WILL BE APPLIED TO THE ACCOUNT ON ALL PAST DUE INVOICES.

TERMS

Net 30 Days

ACCT. NO.

81488

PURCHASE ORDER

651-1001

SALES ORDER

1000101656

PLANT

54230100 Wehrle Aggregates

JOB NO.

2016 Steel Sun

JOB NAME

2016 Steel Sun

Date	Ticket	Description	Qty	Unit	Unit Price	Amount
9/30/2016	50240397	STONE, 2" CRUSHER RUN	22.73	Ton		
9/30/2016	50240446	STONE, 2" CRUSHER RUN	21.89	Ton		
9/30/2016	50240491	STONE, 2" CRUSHER RUN	21.83	Ton		
9/30/2016	50240510	STONE, 2" CRUSHER RUN	19.56	Ton		
9/30/2016	50240540	STONE, 2" CRUSHER RUN	21.59	Ton		
9/30/2016	50240561	STONE, 2" CRUSHER RUN	19.16	Ton		
9/30/2016	50240604	STONE, 2" CRUSHER RUN	21.74	Ton		
9/30/2016	50240605	STONE, 2" CRUSHER RUN	21.20	Ton		

Subtotal**169.70**

Please detach and submit this portion with your payment. Thank you.

Payment Voucher


INVOICE NO.	DUE DATE	ACCT NO.	TOTAL DUE
6444841	10/30/2016	81488	

Make checks payable to New Enterprise Stone & Lime Co., Inc.

MAIL TO: New Enterprise Stone & Lime Co., Inc.
PO BOX 645211
Pittsburgh, PA 15264-5211

Amount Remitted \$ _____

Customer: Mark Cerrone Inc

**New Enterprise Stone & Lime Co., Inc.**

Buffalo, NY 14227

(716) 826-7310

INVOICE

Invoice No.

6444139

Invoice Date

9/30/2016

INVOICE

Sold To: Mark Cerrone Inc
PO Box 3009
Niagara Falls, NY 143047309

ACH/Wire Payment PNC Bank

Bank Acct # 8026302441

Routing # 031207607

EIN: 23-1374051

SERVICE CHARGE OF 1 1/2% PER MONTH (18% PER ANNUM) WILL BE APPLIED TO THE ACCOUNT ON ALL PAST DUE INVOICES.

TERMS

Net 30 Days

ACCT. NO.

81488

PURCHASE ORDER	SALES ORDER	PLANT
651-1001	1000101656	54230100 Wehrle Aggregates
JOB NO.	JOB NAME	
2016 Steel Sun	2016 Steel Sun	

Date	Ticket	Description	Qty	Unit	Unit Price	Amount
9/29/2016	50240107	STONE, 2" CRUSHER RUN	22.52	Ton		
9/29/2016	50240185	STONE, 2" CRUSHER RUN	21.37	Ton		
9/29/2016	50240245	STONE, 2" CRUSHER RUN	22.03	Ton		
9/29/2016	50240321	STONE, 2" CRUSHER RUN	22.25	Ton		
Subtotal			88.17			

INVOICE SUBTOTAL

TAX

AMOUNT DUE

Please detach and submit this portion with your payment. Thank you.

Payment Voucher

INVOICE NO.	DUE DATE	ACCT NO.	TOTAL DUE
6444139	10/30/2016	81488	

Make checks payable to New Enterprise Stone & Lime Co., Inc.

MAIL TO: New Enterprise Stone & Lime Co., Inc.
PO BOX 645211
Pittsburgh, PA 15264-5211

Amount Remitted \$ _____

Customer: Mark Cerrone Inc



New Enterprise Stone & Lime Co., Inc.
Buffalo, NY 14227
(716) 826-7310

INVOICE

Invoice No.

6441300

Invoice Date

9/27/2016

INVOICE

Sold To: Mark Cerrone Inc
PO Box 3009
Niagara Falls, NY 143047309

ACH/Wire Payment PNC Bank

Bank Acct # 8026302441

Routing # 031207607

EIN: 23-1374051

SERVICE CHARGE OF 1 1/2% PER MONTH (18% PER ANNUM) WILL BE APPLIED TO THE ACCOUNT ON ALL PAST DUE INVOICES.

TERMS

Net 30 Days

ACCT. NO.

81488

PURCHASE ORDER	SALES ORDER	PLANT
651-1001	1000101656	54230100 Wehrle Aggregates
JOB NO.	JOB NAME	
2016 Steel Sun	2016 Steel Sun	

Date	Ticket	Description	Qty	Unit	Unit Price	Amount
9/27/2016	50239771	STONE, 2" CRUSHER RUN	22.39	Ton		
Subtotal			22.39			

INVOICE SUBTOTAL
TAX
AMOUNT DUE

Please detach and submit this portion with your payment. Thank you.

Payment Voucher

INVOICE NO.	DUE DATE	ACCT NO.	TOTAL DUE
6441300	10/27/2016	81488	

Make checks payable to New Enterprise Stone & Lime Co., Inc.

Amount Remitted \$ _____

MAIL TO: **New Enterprise Stone & Lime Co., Inc.**
PO BOX 645211
Pittsburgh, PA 15264-5211

Customer: Mark Cerrone Inc

APPENDIX D

INSTITUTIONAL & ENGINEERING CONTROLS CERTIFICATION FORMS

APPENDIX D1

SITE III-5



Enclosure 2
NEW YORK STATE DEPARTMENT OF ENVIRONMENTAL CONSERVATION
Site Management Periodic Review Report Notice
Institutional and Engineering Controls Certification Form



Site Details		Box 1
Site No.	C915199E	
Site Name Site III-5 Tecumseh Phase III Business Park		
Site Address: 2303 Hamburg Turnpike Zip Code: 14218		
City/Town: Lackawanna		
County: Erie		
Site Acreage: 11.7		
Reporting Period: January 15, 2016 to March 15, 2017		
		YES NO
1. Is the information above correct?		☒ ☐
If NO, include handwritten above or on a separate sheet.		
2. Has some or all of the site property been sold, subdivided, merged, or undergone a tax map amendment during this Reporting Period?		☐ ☒
3. Has there been any change of use at the site during this Reporting Period (see 6NYCRR 375-1.11(d))?		☐ ☒
4. Have any federal, state, and/or local permits (e.g., building, discharge) been issued for or at the property during this Reporting Period?		☐ ☒
If you answered YES to questions 2 thru 4, include documentation or evidence that documentation has been previously submitted with this certification form.		
5. Is the site currently undergoing development?		☐ ☒

Box 2	
	YES NO
6. Is the current site use consistent with the use(s) listed below? Commercial and Industrial	☒ ☐
7. Are all ICs/ECs in place and functioning as designed?	☒ ☐
IF THE ANSWER TO EITHER QUESTION 6 OR 7 IS NO, sign and date below and DO NOT COMPLETE THE REST OF THIS FORM. Otherwise continue.	
A Corrective Measures Work Plan must be submitted along with this form to address these issues.	
_____ Signature of Owner, Remedial Party or Designated Representative	_____ Date

Box 2A

YES NO

8. Has any new information revealed that assumptions made in the Qualitative Exposure Assessment regarding offsite contamination are no longer valid?

☐ ☒

If you answered YES to question 8, include documentation or evidence that documentation has been previously submitted with this certification form.

9. Are the assumptions in the Qualitative Exposure Assessment still valid?
(The Qualitative Exposure Assessment must be certified every five years)

☒ ☐

If you answered NO to question 9, the Periodic Review Report must include an updated Qualitative Exposure Assessment based on the new assumptions.

SITE NO. C915199E**Box 3****Description of Institutional Controls**ParcelOwnerInstitutional Control**a portion of 141.11-1-50**

Tecumseh Redevelopment Inc.

Ground Water Use Restriction
Soil Management Plan
Landuse Restriction
Monitoring Plan
Site Management Plan
IC/EC Plan

Institutional Control Description:

Adherence to Site Management Plan (SMP)
Restriction to commercial re-use
Prohibition of groundwater use
Allowance for Departmental access
Requires a Periodic Review and Report

Box 4**Description of Engineering Controls**ParcelEngineering Control**a portion of 141.11-1-50**

Cover System

Engineering Control Description:

Beneficial Use Determination (Slag) cover over 5 acres

Periodic Review Report (PRR) Certification Statements

1. I certify by checking "YES" below that:

a) the Periodic Review report and all attachments were prepared under the direction of, and reviewed by, the party making the certification;

b) to the best of my knowledge and belief, the work and conclusions described in this certification are in accordance with the requirements of the site remedial program, and generally accepted engineering practices; and the information presented is accurate and complete.

YES NO

☒ ☐

2. If this site has an IC/EC Plan (or equivalent as required in the Decision Document), for each Institutional or Engineering control listed in Boxes 3 and/or 4, I certify by checking "YES" below that all of the following statements are true:

(a) the Institutional Control and/or Engineering Control(s) employed at this site is unchanged since the date that the Control was put in-place, or was last approved by the Department;

(b) nothing has occurred that would impair the ability of such Control, to protect public health and the environment;

(c) access to the site will continue to be provided to the Department, to evaluate the remedy, including access to evaluate the continued maintenance of this Control;

(d) nothing has occurred that would constitute a violation or failure to comply with the Site Management Plan for this Control; and

(e) if a financial assurance mechanism is required by the oversight document for the site, the mechanism remains valid and sufficient for its intended purpose established in the document.

YES NO

☒ ☐

**IF THE ANSWER TO QUESTION 2 IS NO, sign and date below and
DO NOT COMPLETE THE REST OF THIS FORM. Otherwise continue.**

A Corrective Measures Work Plan must be submitted along with this form to address these issues.

Signature of Owner, Remedial Party or Designated Representative

Date

IC CERTIFICATIONS
SITE NO. C915199E

Box 6

SITE OWNER OR DESIGNATED REPRESENTATIVE SIGNATURE

I certify that all information and statements in Boxes 1,2, and 3 are true. I understand that a false statement made herein is punishable as a Class "A" misdemeanor, pursuant to Section 210.45 of the Penal Law.

I Thomas C. Biddinger at 311 N Bayshore Drive, Safety Harbor, FL 34695.
print name print business address

am certifying as Remedial Party (Owner or Remedial Party)

for the Site named in the Site Details Section of this form.


Signature of Owner, Remedial Party, or Designated Representative
Rendering Certification

4/4/17
Date

IC/EC CERTIFICATIONS

Box 7

Professional Engineer Signature

I certify that all information in Boxes 4 and 5 are true. I understand that a false statement made herein is punishable as a Class "A" misdemeanor, pursuant to Section 210.45 of the Penal Law.

I Thomas Forbes, P.E. at 2558 Harding Turnpike
print name Buffalo, NY 14218
print business address

am certifying as a Professional Engineer for the _____
(Owner or Remedial Party)

Thomas Forbes

Signature of Professional Engineer, for the Owner or
Remedial Party, Rendering Certification



Stamp
(Required for PE)

Date

3-30-17

APPENDIX D2

SITE III-6



Enclosure 2
NEW YORK STATE DEPARTMENT OF ENVIRONMENTAL CONSERVATION
Site Management Periodic Review Report Notice
Institutional and Engineering Controls Certification Form



Site No. C915199F **Site Details** **Box 1**

Site Name Site III-6 Tecumseh Phase III Business Park

Site Address: 2303 Hamburg Turnpike **Zip Code:** 14218
City/Town: Lackawanna
County: Erie
Site Acreage: 10.9

Reporting Period: January 15, 2016 to March 15, 2017

- | | YES | NO |
|--|-------------------------------------|-------------------------------------|
| 1. Is the information above correct? | ☒ | ☐ |
| If NO, include handwritten above or on a separate sheet. | | |
| 2. Has some or all of the site property been sold, subdivided, merged, or undergone a tax map amendment during this Reporting Period? | ☐ | ☒ |
| 3. Has there been any change of use at the site during this Reporting Period (see 6NYCRR 375-1.11(d))? | ☐ | ☒ |
| 4. Have any federal, state, and/or local permits (e.g., building, discharge) been issued for or at the property during this Reporting Period? | ☐ | ☒ |
| If you answered YES to questions 2 thru 4, include documentation or evidence that documentation has been previously submitted with this certification form. | | |
| 5. Is the site currently undergoing development? | ☐ | ☒ |

Box 2

- | | YES | NO |
|--|-------------------------------------|--------------------------|
| 6. Is the current site use consistent with the use(s) listed below?
Commercial and Industrial | ☒ | ☐ |
| 7. Are all ICs/ECs in place and functioning as designed? | ☒ | ☐ |

**IF THE ANSWER TO EITHER QUESTION 6 OR 7 IS NO, sign and date below and
DO NOT COMPLETE THE REST OF THIS FORM. Otherwise continue.**

A Corrective Measures Work Plan must be submitted along with this form to address these issues.

Signature of Owner, Remedial Party or Designated Representative

Date

Box 2A

YES NO

8. Has any new information revealed that assumptions made in the Qualitative Exposure Assessment regarding offsite contamination are no longer valid? ☐ ☒

If you answered YES to question 8, include documentation or evidence that documentation has been previously submitted with this certification form.

9. Are the assumptions in the Qualitative Exposure Assessment still valid?
(The Qualitative Exposure Assessment must be certified every five years) ☒ ☐

If you answered NO to question 9, the Periodic Review Report must include an updated Qualitative Exposure Assessment based on the new assumptions.

SITE NO. C915199F**Box 3****Description of Institutional Controls**ParcelOwnerInstitutional Control

a portion of 141.11-1-50

Tecumseh Redevelopment Inc.

Ground Water Use Restriction
Soil Management Plan
Landuse Restriction
Monitoring Plan
Site Management Plan

IC/EC Plan

Institutional Control Description:

Adherence to Site Management Plan (SMP)
Restriction to commercial re-use
Prohibition of groundwater use
Allowance for Departmental access
Requires a Periodic Review and Report

Box 4**Description of Engineering Controls**ParcelEngineering Control

a portion of 141.11-1-50

Cover System

Engineering Control Description:

Beneficial Use Determination (Slag) cover over 5 acres

Periodic Review Report (PRR) Certification Statements

1. I certify by checking "YES" below that:

a) the Periodic Review report and all attachments were prepared under the direction of, and reviewed by, the party making the certification;

b) to the best of my knowledge and belief, the work and conclusions described in this certification are in accordance with the requirements of the site remedial program, and generally accepted engineering practices; and the information presented is accurate and complete.

YES NO

☒ ☐

2. If this site has an IC/EC Plan (or equivalent as required in the Decision Document), for each Institutional or Engineering control listed in Boxes 3 and/or 4, I certify by checking "YES" below that all of the following statements are true:

(a) the Institutional Control and/or Engineering Control(s) employed at this site is unchanged since the date that the Control was put in-place, or was last approved by the Department;

(b) nothing has occurred that would impair the ability of such Control, to protect public health and the environment;

(c) access to the site will continue to be provided to the Department, to evaluate the remedy, including access to evaluate the continued maintenance of this Control;

(d) nothing has occurred that would constitute a violation or failure to comply with the Site Management Plan for this Control; and

(e) if a financial assurance mechanism is required by the oversight document for the site, the mechanism remains valid and sufficient for its intended purpose established in the document.

YES NO

☒ ☐

**IF THE ANSWER TO QUESTION 2 IS NO, sign and date below and
DO NOT COMPLETE THE REST OF THIS FORM. Otherwise continue.**

A Corrective Measures Work Plan must be submitted along with this form to address these issues.

Signature of Owner, Remedial Party or Designated Representative

Date

IC CERTIFICATIONS
SITE NO. C915199F

Box 6

SITE OWNER OR DESIGNATED REPRESENTATIVE SIGNATURE

I certify that all information and statements in Boxes 1,2, and 3 are true. I understand that a false statement made herein is punishable as a Class "A" misdemeanor, pursuant to Section 210.45 of the Penal Law.

I Thomas C. Biddinger at 311 N Bayshore Drive, Safety Harbor, FL 34695
print name print business address

am certifying as Remedial Party (Owner or Remedial Party)

for the Site named in the Site Details Section of this form.


Signature of Owner, Remedial Party, or Designated Representative
Rendering Certification

4/4/17
Date

IC/EC CERTIFICATIONS

Box 7

Professional Engineer Signature

I certify that all information in Boxes 4 and 5 are true. I understand that a false statement made herein is punishable as a Class "A" misdemeanor, pursuant to Section 210.45 of the Penal Law.

I Thomas Forbes P.E. at 2558 Hamling Drive Buffalo, NY 14218
print name print business address

am certifying as a Professional Engineer for the _____
(Owner or Remedial Party)

Thomas Forbes

Signature of Professional Engineer, for the Owner or Remedial Party, Rendering Certification



Stamp
(Required for PE)

Date

8-30-17

APPENDIX E

SITE PHOTO LOG

PHOTOGRAPHIC LOG

Client Name: Steel Sun, LLC		Site Location: Tecumseh Phase III Business Park Sites III 5 & III 6	Project No.: 0397-017-001
Photo No. 1	Date 03/23/17		
Direction Photo Taken: North			
Description: Cover system with Solar Panels			

Photo No. 2	Date 03/23/17	
Direction Photo Taken: South		
Description: Cover system with Solar Panels		

PHOTOGRAPHIC LOG

Client Name: Steel Sun, LLC		Site Location: Tecumseh Phase III Business Park Sites III 5 & III 6	Project No.: 0397-017-001
Photo No. 3	Date 03/23/17		
Direction Photo Taken: East			
Description: Cover system with Solar Panels			

Photo No. 4	Date 03/23/17	
Direction Photo Taken: West		
Description: Cover system with Solar Panels		

PHOTOGRAPHIC LOG

Client Name: Steel Sun, LLC		Site Location: Tecumseh Phase III Business Park Sites III 5 & III 6	Project No.: 0397-017-001
Photo No. 5	Date 03/23/17		
Direction Photo Taken: West			
Description: Inverter equipment on concrete pads.			

Photo No. 6	Date 03/23/17	
Direction Photo Taken: East		
Description: Inverter equipment on concrete pads.		

PHOTOGRAPHIC LOG

Client Name: Steel Sun, LLC		Site Location: Tecumseh Phase III Business Park Sites III 5 & III 6	Project No.: 0397-017-001
Photo No. 7	Date 09/28/16		
Direction Photo Taken: North			
Description: Buried conduit installation.			

Photo No. 8	Date 09/28/16	
Direction Photo Taken: North		
Description: Concrete vault installation.		

PHOTOGRAPHIC LOG

Client Name: Steel Sun, LLC		Site Location: Tecumseh Phase III Business Park Sites III 5 & III 6	Project No.: 0397-017-001
Photo No. 9	Date 09/26/16		
Direction Photo Taken: North			
Description: Loading of excavated soil/fill for off site landfill disposal.			

Prepared By: RLD

APPENDIX F

GROUNDWATER MONITORING DATA

EQUIPMENT CALIBRATION LOG

PROJECT INFORMATION:

Project Name: Steel sm I GWM

Project No.: 0397-017-001

Client: Ray Kenyon

Date: 3/13/17

Instrument Source: ☐ BM ☐ Rental

METER TYPE	UNITS	TIME	MAKE/MODEL	SERIAL NUMBER	CAL. BY	STANDARD	POST CAL. READING	SETTINGS
☒ pH meter	units		Myron L Company Ultra Meter 6P	☒ 6213516 ☐ 6243084 ☐ 6212375 ☐ 6223973	<u>TAB</u>	4.00 7.00 10.01	3.57 7.05 9.54	4.0 2.0 10.0
☒ Turbidity meter	NTU		Hach 2100P or 2100Q Turbidimeter	☐ 06120C020523 (P) ☒ 13120C030432 (Q)	<u>TAB</u>	< 0.4 or 10 for 2100 Q 20 100 800	9.3 	Verified with 10.0 NTU
☐ Turbidity meter	NTU		LaMotte 2020	6523-1816 (La)		0.0 NTU 1.0 NTU 10.0 NTU		
☒ Sp. Cond. meter	uS mS		Myron L Company Ultra Meter 6P	☒ 6213516 ☐ 6212375 ☐ 6223973	<u>TAB</u>	<u>1414ms @ 25 °C</u>	<u>1413</u>	<u>1413</u>
☐ PID	ppm		MinRAE 2000			open air zero ppm Iso. Gas		MIBK response factor = 1.0
☒ Dissolved Oxygen	ppm		HACH Model HQ30d	☐ 080700023281 ☒ 100500041867 ☐ 1402000100319	<u>TAB</u>	100% Saturation	<u>101%</u> <u>slump</u>	
☐ Particulate meter	mg/m ³					zero air		
☐ Oxygen	%					open air		
☐ Hydrogen sulfide	ppm					open air		
☐ Carbon monoxide	ppm					open air		
☐ LEL	%					open air		
☐ Radiation Meter	uR/H					background area		

ADDITIONAL REMARKS:

PREPARED BY: TAB DATE: 3/13/17

GROUNDWATER FIELD FORM

Project Name: Steel Sun 1

Date: 3/13/17

Location: Lackawanna NY

Project No.: 0397-017-001 Field Team: TAB

Well No. <u>MWN-60</u>			Diameter (inches): <u>2"</u>			Sample Date / Time: <u>3/13/17 1100</u>			
Product Depth (ftTOR): <u>-</u>			Water Column (ft): <u>10.64</u>			DTW when sampled: <u>9.51</u>			
DTW (static) (ftTOR): <u>9.36</u>			One Well Volume (gal): <u>1.73</u>			Purpose: ☐ Development ☐ Sample ☒ Purge & Sample			
Total Depth (ftTOR): <u>20.0</u>			Total Volume Purged (gal): <u>6.0</u>			Purge Method: <u>Low Flow</u>			
Time	Water Level (ftTOR)	Acc. Volume (gallons)	pH (units)	Temp. (deg. C)	SC (uS)	Turbidity (NTU)	DO (mg/L)	ORP (mV)	Appearance & Odor
1021	0 Initial	20.25	7.87	6.0	1954	4100	1.00	-13	Blue color for 10 min
1026	1 9.51	0.5	7.31	6.3	720.6	45.8	1.51	-65	Clear No odor
1030	2 9.50	1.25	7.50	5.7	695.1	18.9	1.43	-67	"
1034	3 9.57	2.0	7.35	6.7	738.9	9.45	1.61	-43	"
1037	4 9.55	2.5	7.71	6.6	680.2	5.62	1.64	-56	"
1039	5 9.50	3.0	7.55	6.9	682.4	2.98	1.69	-2	"
1046	6 9.50	3.5	8.47	6.4	685.7	2.37	1.62	66	"
1049	7 9.51	4.5	7.92	6.6	674.8	1.75	1.76	39	"
1051	8 9.51	5.0	7.80	6.8	675.1	3.78	1.71	13	"
1054	9 9.51	5.5	7.70	5.9	672.4	3.12	1.84	15	"
1056	10 9.51	6.0	7.87	6.8	676.5	1.84	1.73	-13	"
Sample Information:									
1100	S1 9.51	-	7.62	7.1	672.4	1.33	2.15	7	"
1112	S2 9.51	-	7.87	6.4	666.7	1.29	3.54	43	"

Well No. <u>MWN-58</u>			Diameter (inches): <u>2"</u>			Sample Date / Time: <u>3/13/17 1204</u>			
Product Depth (ftTOR): <u>-</u>			Water Column (ft): <u>10.55</u>			DTW when sampled: <u>10.37</u>			
DTW (static) (ftTOR): <u>10.28</u>			One Well Volume (gal): <u>1.71</u>			Purpose: ☐ Development ☐ Sample ☒ Purge & Sample			
Total Depth (ftTOR): <u>20.83</u>			Total Volume Purged (gal): <u>5.15</u>			Purge Method: <u>Low Flow</u>			
Time	Water Level (ftTOR)	Acc. Volume (gallons)	pH (units)	Temp. (deg. C)	SC (uS)	Turbidity (NTU)	DO (mg/L)	ORP (mV)	Appearance & Odor
1139	0 Initial	20.25	7.82	8.2	530.8	212	1.42	69	SL Turbidity, orange sed
1142	1 1037	2.0	7.41	8.7	522.9	225	1.20	22	"
1146	2 1037	2.5	7.31	8.4	522.3	69.3	1.29	2	"
1149	3 1037	3.0	7.26	8.4	524.9	126	1.25	-5	"
1151	4 1037	3.5	7.25	8.3	528.2	66.7	1.25	-3	"
1154	5 1037	3.75	7.22	8.9	521.9	81.5	1.37	2	"
1158	6 1037	4.5	7.20	8.1	524.9	37.4	1.46	8	"
1201	7 1037	5.0	7.18	8.8	522.7	52.4	1.70	13	"
8									
9									
10									
Sample Information:									
1204	S1 10.37	-	7.38	9.0	523.3	29.6	1.25	31	"
1213	S2 10.37	-	7.38	8.5	522.4	26.5		42	"

REMARKS:

529.1

Volume Calculation

Diam.	Vol. (g/ft)
1"	0.041
2"	0.163
4"	0.653
6"	1.469

Stabilization Criteria

Parameter	Criteria
pH	± 0.1 unit
SC	± 3%
Turbidity	± 10%
DO	± 0.3 mg/L
ORP	± 10 mV

Note: All water level measurements are in feet, distance from top of riser.

PREPARED BY:

TAB

GROUNDWATER FIELD FORM

Project Name: Steel Seen I

Date: 3/13/17

Location: Location

Project No.: 0322-07-001

Field Team: TAB

Well No. <u>MLW-59</u>			Diameter (inches): <u>2"</u>			Sample Date / Time: <u>3/13/17 1305</u>			
Product Depth (ftTOR): <u>-</u>			Water Column (ft): <u>10.96</u>			DTW when sampled: <u>1076</u>			
DTW (static) (ftTOR): <u>10.34</u>			One Well Volume (gal): <u>1.78</u>			Purpose: ☐ Development ☐ Sample ☒ Purge & Sample			
Total Depth (ftTOR): <u>21.30</u>			Total Volume Purged (gal): <u>3.0</u>			Purge Method: <u>Low Flow</u>			
Time	Water Level (ftTOR)	Acc. Volume (gallons)	pH (units)	Temp. (deg. C)	SC (uS)	Turbidity (NTU)	DO (mg/L)	ORP (mV)	Appearance & Odor
1255	0 Initial	20.25	7.26	9.5	708.1	25.7	3.56	97	sl Turbid am
1257	1 10.64	1.5	7.28	8.7	708.0	94.5	3.07	95	"
1259	2 10.76	2.25	7.30	8.2	729.7	28.3	2.45	88	"
1302	3 10.76	3.0	7.32	8.4	733.5	10.7	2.72	75	"
	4								
	5								
	6								
	7								
	8								
	9								
	10								
Sample Information:									
1305	S1 1076	-	7.32	9.2	729.5	6.38	2.55	74	"
1311	S2 1076	-	7.36	8.7	722.4	5.31	2.65	75	"

Well No.			Diameter (inches):			Sample Date / Time:			
Product Depth (ftTOR):			Water Column (ft):			DTW when sampled:			
DTW (static) (ftTOR):			One Well Volume (gal):			Purpose: ☐ Development ☐ Sample ☐ Purge & Sample			
Total Depth (ftTOR):			Total Volume Purged (gal):			Purge Method:			
Time	Water Level (ftTOR)	Acc. Volume (gallons)	pH (units)	Temp. (deg. C)	SC (uS)	Turbidity (NTU)	DO (mg/L)	ORP (mV)	Appearance & Odor
	0 Initial								
	1								
	2								
	3								
	4								
	5								
	6								
	7								
	8								
	9								
	10								
Sample Information:									
	S1								
	S2								

REMARKS:

Note: All water level measurements are in feet, distance from top of riser.

Volume Calculation

Diam.	Vol. (g/ft)
1"	0.041
2"	0.163
4"	0.653
6"	1.469

Stabilization Criteria

Parameter	Criteria
pH	± 0.1 unit
SC	± 3%
Turbidity	± 10%
DO	± 0.3 mg/L
ORP	± 10 mV

PREPARED BY:

TAB



ANALYTICAL REPORT

Lab Number:	L1707779
Client:	Benchmark & Turnkey Companies 2558 Hamburg Turnpike Suite 300 Buffalo, NY 14218
ATTN:	Tom Forbes
Phone:	(716) 856-0599
Project Name:	STEEL SUN I GWM
Project Number:	B0397-017-001
Report Date:	03/20/17

The original project report/data package is held by Alpha Analytical. This report/data package is paginated and should be reproduced only in its entirety. Alpha Analytical holds no responsibility for results and/or data that are not consistent with the original.

Certifications & Approvals: MA (M-MA086), NH NELAP (2064), NJ NELAP (MA935), CT (PH-0574), IL (200077), ME (MA00086), MD (348), NY (11148), NC (25700/666), PA (68-03671), RI (LAO00065), TX (T104704476), VT (VT-0935), VA (460195), USDA (Permit #P330-14-00197).

Eight Walkup Drive, Westborough, MA 01581-1019
508-898-9220 (Fax) 508-898-9193 800-624-9220 - www.alphalab.com



Project Name: STEEL SUN I GWM
Project Number: B0397-017-001

Lab Number: L1707779
Report Date: 03/20/17

Alpha Sample ID	Client ID	Matrix	Sample Location	Collection Date/Time	Receive Date
L1707779-01	MWN-58A	WATER	LACKAWANNA, NY	03/13/17 12:04	03/13/17
L1707779-02	MWN-59A	WATER	LACKAWANNA, NY	03/13/17 13:05	03/13/17
L1707779-03	MWN-60A	WATER	LACKAWANNA, NY	03/13/17 11:00	03/13/17
L1707779-04	TRIP BLANK	WATER	LACKAWANNA, NY	03/13/17 00:00	03/13/17

Project Name: STEEL SUN I GWM
Project Number: B0397-017-001

Lab Number: L1707779
Report Date: 03/20/17

Case Narrative

The samples were received in accordance with the Chain of Custody and no significant deviations were encountered during the preparation or analysis unless otherwise noted. Sample Receipt, Container Information, and the Chain of Custody are located at the back of the report.

Results contained within this report relate only to the samples submitted under this Alpha Lab Number and meet NELAP requirements for all NELAP accredited parameters unless otherwise noted in the following narrative. The data presented in this report is organized by parameter (i.e. VOC, SVOC, etc.). Sample specific Quality Control data (i.e. Surrogate Spike Recovery) is reported at the end of the target analyte list for each individual sample, followed by the Laboratory Batch Quality Control at the end of each parameter. Tentatively Identified Compounds (TICs), if requested, are reported for compounds identified to be present and are not part of the method/program Target Compound List, even if only a subset of the TCL are being reported. If a sample was re-analyzed or re-extracted due to a required quality control corrective action and if both sets of data are reported, the Laboratory ID of the re-analysis or re-extraction is designated with an "R" or "RE", respectively. When multiple Batch Quality Control elements are reported (e.g. more than one LCS), the associated samples for each element are noted in the grey shaded header line of each data table. Any Laboratory Batch, Sample Specific % recovery or RPD value that is outside the listed Acceptance Criteria is bolded in the report. All specific QC information is also incorporated in the Data Usability format of our Data Merger tool where it can be reviewed along with any associated usability implications. Soil/sediments, solids and tissues are reported on a dry weight basis unless otherwise noted. Definitions of all data qualifiers and acronyms used in this report are provided in the Glossary located at the back of the report.

In reference to questions H (CAM) or 4 (RCP) when "NO" is checked, the performance criteria for CAM and RCP methods allow for some quality control failures to occur and still be within method compliance. In these instances the specific failure is not narrated but noted in the associated QC table. The information is also incorporated in the Data Usability format of our Data Merger tool where it can be reviewed along with any associated usability implications.

Please see the associated ADEx data file for a comparison of laboratory reporting limits that were achieved with the regulatory Numerical Standards requested on the Chain of Custody.

HOLD POLICY

For samples submitted on hold, Alpha's policy is to hold samples (with the exception of Air canisters) free of charge for 21 calendar days from the date the project is completed. After 21 calendar days, we will dispose of all samples submitted including those put on hold unless you have contacted your Client Service Representative and made arrangements for Alpha to continue to hold the samples. Air canisters will be disposed after 3 business days from the date the project is completed.

Please contact Client Services at 800-624-9220 with any questions.

Project Name: STEEL SUN I GWM
Project Number: B0397-017-001

Lab Number: L1707779
Report Date: 03/20/17

Case Narrative (continued)

Report Submission

All non-detect (ND) or estimated concentrations (J-qualified) have been quantitated to the limit noted in the MDL column.

Sample Receipt

The project number was specified by the client.

I, the undersigned, attest under the pains and penalties of perjury that, to the best of my knowledge and belief and based upon my personal inquiry of those responsible for providing the information contained in this analytical report, such information is accurate and complete. This certificate of analysis is not complete unless this page accompanies any and all pages of this report.

Authorized Signature:



Kara Lindquist

Title: Technical Director/Representative

Date: 03/20/17

ORGANICS

VOLATILES

Project Name: STEEL SUN I GWM

Lab Number: L1707779

Project Number: B0397-017-001

Report Date: 03/20/17

SAMPLE RESULTS

Lab ID: L1707779-01
 Client ID: MWN-58A
 Sample Location: LACKAWANNA, NY
 Matrix: Water
 Analytical Method: 1,8260C
 Analytical Date: 03/17/17 10:43
 Analyst: PD

Date Collected: 03/13/17 12:04
 Date Received: 03/13/17
 Field Prep: Not Specified

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
Volatile Organics by GC/MS - Westborough Lab						
Methylene chloride	ND		ug/l	2.5	0.70	1
1,1-Dichloroethane	ND		ug/l	2.5	0.70	1
Chloroform	ND		ug/l	2.5	0.70	1
Carbon tetrachloride	ND		ug/l	0.50	0.13	1
1,2-Dichloropropane	ND		ug/l	1.0	0.14	1
Dibromochloromethane	ND		ug/l	0.50	0.15	1
1,1,2-Trichloroethane	ND		ug/l	1.5	0.50	1
Tetrachloroethene	ND		ug/l	0.50	0.18	1
Chlorobenzene	ND		ug/l	2.5	0.70	1
Trichlorofluoromethane	ND		ug/l	2.5	0.70	1
1,2-Dichloroethane	ND		ug/l	0.50	0.13	1
1,1,1-Trichloroethane	ND		ug/l	2.5	0.70	1
Bromodichloromethane	ND		ug/l	0.50	0.19	1
trans-1,3-Dichloropropene	ND		ug/l	0.50	0.16	1
cis-1,3-Dichloropropene	ND		ug/l	0.50	0.14	1
Bromoform	ND		ug/l	2.0	0.65	1
1,1,2,2-Tetrachloroethane	ND		ug/l	0.50	0.17	1
Benzene	ND		ug/l	0.50	0.16	1
Toluene	ND		ug/l	2.5	0.70	1
Ethylbenzene	ND		ug/l	2.5	0.70	1
Chloromethane	ND		ug/l	2.5	0.70	1
Bromomethane	ND		ug/l	2.5	0.70	1
Vinyl chloride	ND		ug/l	1.0	0.07	1
Chloroethane	ND		ug/l	2.5	0.70	1
1,1-Dichloroethene	ND		ug/l	0.50	0.17	1
trans-1,2-Dichloroethene	ND		ug/l	2.5	0.70	1
Trichloroethene	ND		ug/l	0.50	0.18	1
1,2-Dichlorobenzene	ND		ug/l	2.5	0.70	1
1,3-Dichlorobenzene	ND		ug/l	2.5	0.70	1
1,4-Dichlorobenzene	ND		ug/l	2.5	0.70	1

Project Name: STEEL SUN I GWM

Lab Number: L1707779

Project Number: B0397-017-001

Report Date: 03/20/17

SAMPLE RESULTS

Lab ID: L1707779-01

Date Collected: 03/13/17 12:04

Client ID: MWN-58A

Date Received: 03/13/17

Sample Location: LACKAWANNA, NY

Field Prep: Not Specified

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
Volatile Organics by GC/MS - Westborough Lab						
Methyl tert butyl ether	ND		ug/l	2.5	0.70	1
p/m-Xylene	ND		ug/l	2.5	0.70	1
o-Xylene	ND		ug/l	2.5	0.70	1
cis-1,2-Dichloroethene	ND		ug/l	2.5	0.70	1
Styrene	ND		ug/l	2.5	0.70	1
Dichlorodifluoromethane	ND		ug/l	5.0	1.0	1
Acetone	ND		ug/l	5.0	1.5	1
Carbon disulfide	ND		ug/l	5.0	1.0	1
2-Butanone	ND		ug/l	5.0	1.9	1
4-Methyl-2-pentanone	ND		ug/l	5.0	1.0	1
2-Hexanone	ND		ug/l	5.0	1.0	1
Bromochloromethane	ND		ug/l	2.5	0.70	1
1,2-Dibromoethane	ND		ug/l	2.0	0.65	1
n-Butylbenzene	ND		ug/l	2.5	0.70	1
sec-Butylbenzene	ND		ug/l	2.5	0.70	1
1,2-Dibromo-3-chloropropane	ND		ug/l	2.5	0.70	1
Isopropylbenzene	ND		ug/l	2.5	0.70	1
p-Isopropyltoluene	ND		ug/l	2.5	0.70	1
n-Propylbenzene	ND		ug/l	2.5	0.70	1
1,2,3-Trichlorobenzene	ND		ug/l	2.5	0.70	1
1,2,4-Trichlorobenzene	ND		ug/l	2.5	0.70	1
1,3,5-Trimethylbenzene	ND		ug/l	2.5	0.70	1
1,2,4-Trimethylbenzene	ND		ug/l	2.5	0.70	1
Methyl Acetate	ND		ug/l	2.0	0.23	1
Cyclohexane	ND		ug/l	10	0.27	1
1,4-Dioxane	ND		ug/l	250	61.	1
Freon-113	ND		ug/l	2.5	0.70	1
Methyl cyclohexane	ND		ug/l	10	0.40	1

Surrogate	% Recovery	Qualifier	Acceptance Criteria
1,2-Dichloroethane-d4	95		70-130
Toluene-d8	96		70-130
4-Bromofluorobenzene	108		70-130
Dibromofluoromethane	103		70-130

Project Name: STEEL SUN I GWM

Lab Number: L1707779

Project Number: B0397-017-001

Report Date: 03/20/17

SAMPLE RESULTS

Lab ID: L1707779-02
 Client ID: MWN-59A
 Sample Location: LACKAWANNA, NY
 Matrix: Water
 Analytical Method: 1,8260C
 Analytical Date: 03/17/17 11:11
 Analyst: PD

Date Collected: 03/13/17 13:05
 Date Received: 03/13/17
 Field Prep: Not Specified

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
Volatile Organics by GC/MS - Westborough Lab						
Methylene chloride	ND		ug/l	2.5	0.70	1
1,1-Dichloroethane	ND		ug/l	2.5	0.70	1
Chloroform	ND		ug/l	2.5	0.70	1
Carbon tetrachloride	ND		ug/l	0.50	0.13	1
1,2-Dichloropropane	ND		ug/l	1.0	0.14	1
Dibromochloromethane	ND		ug/l	0.50	0.15	1
1,1,2-Trichloroethane	ND		ug/l	1.5	0.50	1
Tetrachloroethene	ND		ug/l	0.50	0.18	1
Chlorobenzene	ND		ug/l	2.5	0.70	1
Trichlorofluoromethane	ND		ug/l	2.5	0.70	1
1,2-Dichloroethane	ND		ug/l	0.50	0.13	1
1,1,1-Trichloroethane	ND		ug/l	2.5	0.70	1
Bromodichloromethane	ND		ug/l	0.50	0.19	1
trans-1,3-Dichloropropene	ND		ug/l	0.50	0.16	1
cis-1,3-Dichloropropene	ND		ug/l	0.50	0.14	1
Bromoform	ND		ug/l	2.0	0.65	1
1,1,2,2-Tetrachloroethane	ND		ug/l	0.50	0.17	1
Benzene	ND		ug/l	0.50	0.16	1
Toluene	ND		ug/l	2.5	0.70	1
Ethylbenzene	ND		ug/l	2.5	0.70	1
Chloromethane	ND		ug/l	2.5	0.70	1
Bromomethane	ND		ug/l	2.5	0.70	1
Vinyl chloride	ND		ug/l	1.0	0.07	1
Chloroethane	ND		ug/l	2.5	0.70	1
1,1-Dichloroethene	ND		ug/l	0.50	0.17	1
trans-1,2-Dichloroethene	ND		ug/l	2.5	0.70	1
Trichloroethene	ND		ug/l	0.50	0.18	1
1,2-Dichlorobenzene	ND		ug/l	2.5	0.70	1
1,3-Dichlorobenzene	ND		ug/l	2.5	0.70	1
1,4-Dichlorobenzene	ND		ug/l	2.5	0.70	1

Project Name: STEEL SUN I GWM

Lab Number: L1707779

Project Number: B0397-017-001

Report Date: 03/20/17

SAMPLE RESULTS

Lab ID: L1707779-02

Date Collected: 03/13/17 13:05

Client ID: MWN-59A

Date Received: 03/13/17

Sample Location: LACKAWANNA, NY

Field Prep: Not Specified

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
Volatile Organics by GC/MS - Westborough Lab						
Methyl tert butyl ether	ND		ug/l	2.5	0.70	1
p/m-Xylene	ND		ug/l	2.5	0.70	1
o-Xylene	ND		ug/l	2.5	0.70	1
cis-1,2-Dichloroethene	ND		ug/l	2.5	0.70	1
Styrene	ND		ug/l	2.5	0.70	1
Dichlorodifluoromethane	ND		ug/l	5.0	1.0	1
Acetone	ND		ug/l	5.0	1.5	1
Carbon disulfide	ND		ug/l	5.0	1.0	1
2-Butanone	ND		ug/l	5.0	1.9	1
4-Methyl-2-pentanone	ND		ug/l	5.0	1.0	1
2-Hexanone	ND		ug/l	5.0	1.0	1
Bromochloromethane	ND		ug/l	2.5	0.70	1
1,2-Dibromoethane	ND		ug/l	2.0	0.65	1
n-Butylbenzene	ND		ug/l	2.5	0.70	1
sec-Butylbenzene	ND		ug/l	2.5	0.70	1
1,2-Dibromo-3-chloropropane	ND		ug/l	2.5	0.70	1
Isopropylbenzene	ND		ug/l	2.5	0.70	1
p-Isopropyltoluene	ND		ug/l	2.5	0.70	1
n-Propylbenzene	ND		ug/l	2.5	0.70	1
1,2,3-Trichlorobenzene	ND		ug/l	2.5	0.70	1
1,2,4-Trichlorobenzene	ND		ug/l	2.5	0.70	1
1,3,5-Trimethylbenzene	ND		ug/l	2.5	0.70	1
1,2,4-Trimethylbenzene	ND		ug/l	2.5	0.70	1
Methyl Acetate	ND		ug/l	2.0	0.23	1
Cyclohexane	ND		ug/l	10	0.27	1
1,4-Dioxane	ND		ug/l	250	61.	1
Freon-113	ND		ug/l	2.5	0.70	1
Methyl cyclohexane	ND		ug/l	10	0.40	1

Surrogate	% Recovery	Qualifier	Acceptance Criteria
1,2-Dichloroethane-d4	94		70-130
Toluene-d8	96		70-130
4-Bromofluorobenzene	107		70-130
Dibromofluoromethane	104		70-130

Project Name: STEEL SUN I GWM

Lab Number: L1707779

Project Number: B0397-017-001

Report Date: 03/20/17

SAMPLE RESULTS

Lab ID: L1707779-03
 Client ID: MWN-60A
 Sample Location: LACKAWANNA, NY
 Matrix: Water
 Analytical Method: 1,8260C
 Analytical Date: 03/16/17 16:23
 Analyst: NL

Date Collected: 03/13/17 11:00
 Date Received: 03/13/17
 Field Prep: Not Specified

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
Volatile Organics by GC/MS - Westborough Lab						
Methylene chloride	ND		ug/l	2.5	0.70	1
1,1-Dichloroethane	ND		ug/l	2.5	0.70	1
Chloroform	ND		ug/l	2.5	0.70	1
Carbon tetrachloride	ND		ug/l	0.50	0.13	1
1,2-Dichloropropane	ND		ug/l	1.0	0.14	1
Dibromochloromethane	ND		ug/l	0.50	0.15	1
1,1,2-Trichloroethane	ND		ug/l	1.5	0.50	1
Tetrachloroethene	ND		ug/l	0.50	0.18	1
Chlorobenzene	ND		ug/l	2.5	0.70	1
Trichlorofluoromethane	ND		ug/l	2.5	0.70	1
1,2-Dichloroethane	ND		ug/l	0.50	0.13	1
1,1,1-Trichloroethane	ND		ug/l	2.5	0.70	1
Bromodichloromethane	ND		ug/l	0.50	0.19	1
trans-1,3-Dichloropropene	ND		ug/l	0.50	0.16	1
cis-1,3-Dichloropropene	ND		ug/l	0.50	0.14	1
Bromoform	ND		ug/l	2.0	0.65	1
1,1,2,2-Tetrachloroethane	ND		ug/l	0.50	0.17	1
Benzene	ND		ug/l	0.50	0.16	1
Toluene	ND		ug/l	2.5	0.70	1
Ethylbenzene	ND		ug/l	2.5	0.70	1
Chloromethane	ND		ug/l	2.5	0.70	1
Bromomethane	ND		ug/l	2.5	0.70	1
Vinyl chloride	ND		ug/l	1.0	0.07	1
Chloroethane	ND		ug/l	2.5	0.70	1
1,1-Dichloroethene	ND		ug/l	0.50	0.17	1
trans-1,2-Dichloroethene	ND		ug/l	2.5	0.70	1
Trichloroethene	ND		ug/l	0.50	0.18	1
1,2-Dichlorobenzene	ND		ug/l	2.5	0.70	1
1,3-Dichlorobenzene	ND		ug/l	2.5	0.70	1
1,4-Dichlorobenzene	ND		ug/l	2.5	0.70	1

Project Name: STEEL SUN I GWM

Lab Number: L1707779

Project Number: B0397-017-001

Report Date: 03/20/17

SAMPLE RESULTS

Lab ID: L1707779-03

Date Collected: 03/13/17 11:00

Client ID: MWN-60A

Date Received: 03/13/17

Sample Location: LACKAWANNA, NY

Field Prep: Not Specified

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
Volatile Organics by GC/MS - Westborough Lab						
Methyl tert butyl ether	ND		ug/l	2.5	0.70	1
p/m-Xylene	ND		ug/l	2.5	0.70	1
o-Xylene	ND		ug/l	2.5	0.70	1
cis-1,2-Dichloroethene	ND		ug/l	2.5	0.70	1
Styrene	ND		ug/l	2.5	0.70	1
Dichlorodifluoromethane	ND		ug/l	5.0	1.0	1
Acetone	20		ug/l	5.0	1.5	1
Carbon disulfide	ND		ug/l	5.0	1.0	1
2-Butanone	13		ug/l	5.0	1.9	1
4-Methyl-2-pentanone	ND		ug/l	5.0	1.0	1
2-Hexanone	ND		ug/l	5.0	1.0	1
Bromochloromethane	ND		ug/l	2.5	0.70	1
1,2-Dibromoethane	ND		ug/l	2.0	0.65	1
n-Butylbenzene	ND		ug/l	2.5	0.70	1
sec-Butylbenzene	ND		ug/l	2.5	0.70	1
1,2-Dibromo-3-chloropropane	ND		ug/l	2.5	0.70	1
Isopropylbenzene	ND		ug/l	2.5	0.70	1
p-Isopropyltoluene	ND		ug/l	2.5	0.70	1
n-Propylbenzene	ND		ug/l	2.5	0.70	1
1,2,3-Trichlorobenzene	ND		ug/l	2.5	0.70	1
1,2,4-Trichlorobenzene	ND		ug/l	2.5	0.70	1
1,3,5-Trimethylbenzene	ND		ug/l	2.5	0.70	1
1,2,4-Trimethylbenzene	ND		ug/l	2.5	0.70	1
Methyl Acetate	ND		ug/l	2.0	0.23	1
Cyclohexane	ND		ug/l	10	0.27	1
1,4-Dioxane	ND		ug/l	250	61.	1
Freon-113	ND		ug/l	2.5	0.70	1
Methyl cyclohexane	ND		ug/l	10	0.40	1

Surrogate	% Recovery	Qualifier	Acceptance Criteria
1,2-Dichloroethane-d4	112		70-130
Toluene-d8	102		70-130
4-Bromofluorobenzene	98		70-130
Dibromofluoromethane	105		70-130

Project Name: STEEL SUN I GWM

Lab Number: L1707779

Project Number: B0397-017-001

Report Date: 03/20/17

SAMPLE RESULTS

Lab ID: L1707779-04
 Client ID: TRIP BLANK
 Sample Location: LACKAWANNA, NY
 Matrix: Water
 Analytical Method: 1,8260C
 Analytical Date: 03/16/17 16:57
 Analyst: NL

Date Collected: 03/13/17 00:00
 Date Received: 03/13/17
 Field Prep: Not Specified

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
Volatile Organics by GC/MS - Westborough Lab						
Methylene chloride	ND		ug/l	2.5	0.70	1
1,1-Dichloroethane	ND		ug/l	2.5	0.70	1
Chloroform	ND		ug/l	2.5	0.70	1
Carbon tetrachloride	ND		ug/l	0.50	0.13	1
1,2-Dichloropropane	ND		ug/l	1.0	0.14	1
Dibromochloromethane	ND		ug/l	0.50	0.15	1
1,1,2-Trichloroethane	ND		ug/l	1.5	0.50	1
Tetrachloroethene	ND		ug/l	0.50	0.18	1
Chlorobenzene	ND		ug/l	2.5	0.70	1
Trichlorofluoromethane	ND		ug/l	2.5	0.70	1
1,2-Dichloroethane	ND		ug/l	0.50	0.13	1
1,1,1-Trichloroethane	ND		ug/l	2.5	0.70	1
Bromodichloromethane	ND		ug/l	0.50	0.19	1
trans-1,3-Dichloropropene	ND		ug/l	0.50	0.16	1
cis-1,3-Dichloropropene	ND		ug/l	0.50	0.14	1
Bromoform	ND		ug/l	2.0	0.65	1
1,1,2,2-Tetrachloroethane	ND		ug/l	0.50	0.17	1
Benzene	ND		ug/l	0.50	0.16	1
Toluene	ND		ug/l	2.5	0.70	1
Ethylbenzene	ND		ug/l	2.5	0.70	1
Chloromethane	ND		ug/l	2.5	0.70	1
Bromomethane	ND		ug/l	2.5	0.70	1
Vinyl chloride	ND		ug/l	1.0	0.07	1
Chloroethane	ND		ug/l	2.5	0.70	1
1,1-Dichloroethene	ND		ug/l	0.50	0.17	1
trans-1,2-Dichloroethene	ND		ug/l	2.5	0.70	1
Trichloroethene	ND		ug/l	0.50	0.18	1
1,2-Dichlorobenzene	ND		ug/l	2.5	0.70	1
1,3-Dichlorobenzene	ND		ug/l	2.5	0.70	1
1,4-Dichlorobenzene	ND		ug/l	2.5	0.70	1

Project Name: STEEL SUN I GWM

Lab Number: L1707779

Project Number: B0397-017-001

Report Date: 03/20/17

SAMPLE RESULTS

Lab ID: L1707779-04

Date Collected: 03/13/17 00:00

Client ID: TRIP BLANK

Date Received: 03/13/17

Sample Location: LACKAWANNA, NY

Field Prep: Not Specified

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
Volatile Organics by GC/MS - Westborough Lab						
Methyl tert butyl ether	ND		ug/l	2.5	0.70	1
p/m-Xylene	ND		ug/l	2.5	0.70	1
o-Xylene	ND		ug/l	2.5	0.70	1
cis-1,2-Dichloroethene	ND		ug/l	2.5	0.70	1
Styrene	ND		ug/l	2.5	0.70	1
Dichlorodifluoromethane	ND		ug/l	5.0	1.0	1
Acetone	ND		ug/l	5.0	1.5	1
Carbon disulfide	ND		ug/l	5.0	1.0	1
2-Butanone	ND		ug/l	5.0	1.9	1
4-Methyl-2-pentanone	ND		ug/l	5.0	1.0	1
2-Hexanone	ND		ug/l	5.0	1.0	1
Bromochloromethane	ND		ug/l	2.5	0.70	1
1,2-Dibromoethane	ND		ug/l	2.0	0.65	1
n-Butylbenzene	ND		ug/l	2.5	0.70	1
sec-Butylbenzene	ND		ug/l	2.5	0.70	1
1,2-Dibromo-3-chloropropane	ND		ug/l	2.5	0.70	1
Isopropylbenzene	ND		ug/l	2.5	0.70	1
p-Isopropyltoluene	ND		ug/l	2.5	0.70	1
n-Propylbenzene	ND		ug/l	2.5	0.70	1
1,2,3-Trichlorobenzene	ND		ug/l	2.5	0.70	1
1,2,4-Trichlorobenzene	ND		ug/l	2.5	0.70	1
1,3,5-Trimethylbenzene	ND		ug/l	2.5	0.70	1
1,2,4-Trimethylbenzene	ND		ug/l	2.5	0.70	1
Methyl Acetate	ND		ug/l	2.0	0.23	1
Cyclohexane	ND		ug/l	10	0.27	1
1,4-Dioxane	ND		ug/l	250	61.	1
Freon-113	ND		ug/l	2.5	0.70	1
Methyl cyclohexane	ND		ug/l	10	0.40	1

Surrogate	% Recovery	Qualifier	Acceptance Criteria
1,2-Dichloroethane-d4	110		70-130
Toluene-d8	102		70-130
4-Bromofluorobenzene	96		70-130
Dibromofluoromethane	103		70-130

Project Name: STEEL SUN I GWM

Lab Number: L1707779

Project Number: B0397-017-001

Report Date: 03/20/17

Method Blank Analysis Batch Quality Control

Analytical Method: 1,8260C
 Analytical Date: 03/16/17 10:37
 Analyst: BD

Parameter	Result	Qualifier	Units	RL	MDL
Volatile Organics by GC/MS - Westborough Lab for sample(s): 03-04 Batch: WG985910-5					
Methylene chloride	ND		ug/l	2.5	0.70
1,1-Dichloroethane	ND		ug/l	2.5	0.70
Chloroform	ND		ug/l	2.5	0.70
Carbon tetrachloride	ND		ug/l	0.50	0.13
1,2-Dichloropropane	ND		ug/l	1.0	0.14
Dibromochloromethane	ND		ug/l	0.50	0.15
1,1,2-Trichloroethane	ND		ug/l	1.5	0.50
Tetrachloroethene	ND		ug/l	0.50	0.18
Chlorobenzene	ND		ug/l	2.5	0.70
Trichlorofluoromethane	ND		ug/l	2.5	0.70
1,2-Dichloroethane	ND		ug/l	0.50	0.13
1,1,1-Trichloroethane	ND		ug/l	2.5	0.70
Bromodichloromethane	ND		ug/l	0.50	0.19
trans-1,3-Dichloropropene	ND		ug/l	0.50	0.16
cis-1,3-Dichloropropene	ND		ug/l	0.50	0.14
Bromoform	ND		ug/l	2.0	0.65
1,1,2,2-Tetrachloroethane	ND		ug/l	0.50	0.17
Benzene	ND		ug/l	0.50	0.16
Toluene	ND		ug/l	2.5	0.70
Ethylbenzene	ND		ug/l	2.5	0.70
Chloromethane	ND		ug/l	2.5	0.70
Bromomethane	ND		ug/l	2.5	0.70
Vinyl chloride	ND		ug/l	1.0	0.07
Chloroethane	ND		ug/l	2.5	0.70
1,1-Dichloroethene	ND		ug/l	0.50	0.17
trans-1,2-Dichloroethene	ND		ug/l	2.5	0.70
Trichloroethene	ND		ug/l	0.50	0.18
1,2-Dichlorobenzene	ND		ug/l	2.5	0.70
1,3-Dichlorobenzene	ND		ug/l	2.5	0.70

Project Name: STEEL SUN I GWM

Lab Number: L1707779

Project Number: B0397-017-001

Report Date: 03/20/17

Method Blank Analysis Batch Quality Control

Analytical Method: 1,8260C
 Analytical Date: 03/16/17 10:37
 Analyst: BD

Parameter	Result	Qualifier	Units	RL	MDL
Volatile Organics by GC/MS - Westborough Lab for sample(s): 03-04 Batch: WG985910-5					
1,4-Dichlorobenzene	ND		ug/l	2.5	0.70
Methyl tert butyl ether	ND		ug/l	2.5	0.70
p/m-Xylene	ND		ug/l	2.5	0.70
o-Xylene	ND		ug/l	2.5	0.70
cis-1,2-Dichloroethene	ND		ug/l	2.5	0.70
Styrene	ND		ug/l	2.5	0.70
Dichlorodifluoromethane	ND		ug/l	5.0	1.0
Acetone	ND		ug/l	5.0	1.5
Carbon disulfide	ND		ug/l	5.0	1.0
2-Butanone	ND		ug/l	5.0	1.9
4-Methyl-2-pentanone	ND		ug/l	5.0	1.0
2-Hexanone	ND		ug/l	5.0	1.0
Bromochloromethane	ND		ug/l	2.5	0.70
1,2-Dibromoethane	ND		ug/l	2.0	0.65
n-Butylbenzene	ND		ug/l	2.5	0.70
sec-Butylbenzene	ND		ug/l	2.5	0.70
1,2-Dibromo-3-chloropropane	ND		ug/l	2.5	0.70
Isopropylbenzene	ND		ug/l	2.5	0.70
p-Isopropyltoluene	ND		ug/l	2.5	0.70
n-Propylbenzene	ND		ug/l	2.5	0.70
1,2,3-Trichlorobenzene	ND		ug/l	2.5	0.70
1,2,4-Trichlorobenzene	ND		ug/l	2.5	0.70
1,3,5-Trimethylbenzene	ND		ug/l	2.5	0.70
1,2,4-Trimethylbenzene	ND		ug/l	2.5	0.70
Methyl Acetate	ND		ug/l	2.0	0.23
Cyclohexane	ND		ug/l	10	0.27
1,4-Dioxane	ND		ug/l	250	61.
Freon-113	ND		ug/l	2.5	0.70
Methyl cyclohexane	ND		ug/l	10	0.40

Project Name: STEEL SUN I GWM**Lab Number:** L1707779**Project Number:** B0397-017-001**Report Date:** 03/20/17**Method Blank Analysis**
Batch Quality Control

Analytical Method: 1,8260C

Analytical Date: 03/16/17 10:37

Analyst: BD

Parameter	Result	Qualifier	Units	RL	MDL
Volatile Organics by GC/MS - Westborough Lab for sample(s): 03-04 Batch: WG985910-5					

Surrogate	%Recovery	Qualifier	Acceptance Criteria
1,2-Dichloroethane-d4	112		70-130
Toluene-d8	103		70-130
4-Bromofluorobenzene	98		70-130
Dibromofluoromethane	105		70-130

Project Name: STEEL SUN I GWM

Lab Number: L1707779

Project Number: B0397-017-001

Report Date: 03/20/17

Method Blank Analysis Batch Quality Control

Analytical Method: 1,8260C
 Analytical Date: 03/17/17 09:48
 Analyst: PD

Parameter	Result	Qualifier	Units	RL	MDL
Volatile Organics by GC/MS - Westborough Lab for sample(s): 01-02 Batch: WG986256-5					
Methylene chloride	ND		ug/l	2.5	0.70
1,1-Dichloroethane	ND		ug/l	2.5	0.70
Chloroform	ND		ug/l	2.5	0.70
Carbon tetrachloride	ND		ug/l	0.50	0.13
1,2-Dichloropropane	ND		ug/l	1.0	0.14
Dibromochloromethane	ND		ug/l	0.50	0.15
1,1,2-Trichloroethane	ND		ug/l	1.5	0.50
Tetrachloroethene	ND		ug/l	0.50	0.18
Chlorobenzene	ND		ug/l	2.5	0.70
Trichlorofluoromethane	ND		ug/l	2.5	0.70
1,2-Dichloroethane	ND		ug/l	0.50	0.13
1,1,1-Trichloroethane	ND		ug/l	2.5	0.70
Bromodichloromethane	ND		ug/l	0.50	0.19
trans-1,3-Dichloropropene	ND		ug/l	0.50	0.16
cis-1,3-Dichloropropene	ND		ug/l	0.50	0.14
Bromoform	ND		ug/l	2.0	0.65
1,1,2,2-Tetrachloroethane	ND		ug/l	0.50	0.17
Benzene	ND		ug/l	0.50	0.16
Toluene	ND		ug/l	2.5	0.70
Ethylbenzene	ND		ug/l	2.5	0.70
Chloromethane	ND		ug/l	2.5	0.70
Bromomethane	ND		ug/l	2.5	0.70
Vinyl chloride	ND		ug/l	1.0	0.07
Chloroethane	ND		ug/l	2.5	0.70
1,1-Dichloroethene	ND		ug/l	0.50	0.17
trans-1,2-Dichloroethene	ND		ug/l	2.5	0.70
Trichloroethene	ND		ug/l	0.50	0.18
1,2-Dichlorobenzene	ND		ug/l	2.5	0.70
1,3-Dichlorobenzene	ND		ug/l	2.5	0.70

Project Name: STEEL SUN I GWM

Lab Number: L1707779

Project Number: B0397-017-001

Report Date: 03/20/17

Method Blank Analysis Batch Quality Control

Analytical Method: 1,8260C
 Analytical Date: 03/17/17 09:48
 Analyst: PD

Parameter	Result	Qualifier	Units	RL	MDL
Volatile Organics by GC/MS - Westborough Lab for sample(s): 01-02 Batch: WG986256-5					
1,4-Dichlorobenzene	ND		ug/l	2.5	0.70
Methyl tert butyl ether	ND		ug/l	2.5	0.70
p/m-Xylene	ND		ug/l	2.5	0.70
o-Xylene	ND		ug/l	2.5	0.70
cis-1,2-Dichloroethene	ND		ug/l	2.5	0.70
Styrene	ND		ug/l	2.5	0.70
Dichlorodifluoromethane	ND		ug/l	5.0	1.0
Acetone	ND		ug/l	5.0	1.5
Carbon disulfide	ND		ug/l	5.0	1.0
2-Butanone	ND		ug/l	5.0	1.9
4-Methyl-2-pentanone	ND		ug/l	5.0	1.0
2-Hexanone	ND		ug/l	5.0	1.0
Bromochloromethane	ND		ug/l	2.5	0.70
1,2-Dibromoethane	ND		ug/l	2.0	0.65
n-Butylbenzene	ND		ug/l	2.5	0.70
sec-Butylbenzene	ND		ug/l	2.5	0.70
1,2-Dibromo-3-chloropropane	ND		ug/l	2.5	0.70
Isopropylbenzene	ND		ug/l	2.5	0.70
p-Isopropyltoluene	ND		ug/l	2.5	0.70
n-Propylbenzene	ND		ug/l	2.5	0.70
1,2,3-Trichlorobenzene	ND		ug/l	2.5	0.70
1,2,4-Trichlorobenzene	ND		ug/l	2.5	0.70
1,3,5-Trimethylbenzene	ND		ug/l	2.5	0.70
1,2,4-Trimethylbenzene	ND		ug/l	2.5	0.70
Methyl Acetate	ND		ug/l	2.0	0.23
Cyclohexane	ND		ug/l	10	0.27
1,4-Dioxane	ND		ug/l	250	61.
Freon-113	ND		ug/l	2.5	0.70
Methyl cyclohexane	ND		ug/l	10	0.40

Project Name: STEEL SUN I GWM**Lab Number:** L1707779**Project Number:** B0397-017-001**Report Date:** 03/20/17**Method Blank Analysis**
Batch Quality Control

Analytical Method: 1,8260C

Analytical Date: 03/17/17 09:48

Analyst: PD

Parameter	Result	Qualifier	Units	RL	MDL
Volatile Organics by GC/MS - Westborough Lab for sample(s): 01-02 Batch: WG986256-5					

Surrogate	%Recovery	Qualifier	Acceptance Criteria
1,2-Dichloroethane-d4	92		70-130
Toluene-d8	96		70-130
4-Bromofluorobenzene	107		70-130
Dibromofluoromethane	102		70-130

Lab Control Sample Analysis

Batch Quality Control

Project Name: STEEL SUN I GWM

Project Number: B0397-017-001

Lab Number: L1707779

Report Date: 03/20/17

Parameter	LCS %Recovery	Qual	LCSD %Recovery	Qual	%Recovery Limits	RPD	Qual	RPD Limits
Volatile Organics by GC/MS - Westborough Lab Associated sample(s): 03-04 Batch: WG985910-3 WG985910-4								
Methylene chloride	100		99		70-130	1		20
1,1-Dichloroethane	100		100		70-130	0		20
Chloroform	110		100		70-130	10		20
Carbon tetrachloride	76		70		63-132	8		20
1,2-Dichloropropane	100		95		70-130	5		20
Dibromochloromethane	87		86		63-130	1		20
1,1,2-Trichloroethane	100		100		70-130	0		20
Tetrachloroethene	110		100		70-130	10		20
Chlorobenzene	110		110		75-130	0		20
Trichlorofluoromethane	91		85		62-150	7		20
1,2-Dichloroethane	110		110		70-130	0		20
1,1,1-Trichloroethane	86		81		67-130	6		20
Bromodichloromethane	99		97		67-130	2		20
trans-1,3-Dichloropropene	69	Q	69	Q	70-130	0		20
cis-1,3-Dichloropropene	80		78		70-130	3		20
Bromoform	76		76		54-136	0		20
1,1,2,2-Tetrachloroethane	100		100		67-130	0		20
Benzene	100		98		70-130	2		20
Toluene	110		100		70-130	10		20
Ethylbenzene	120		110		70-130	9		20
Chloromethane	100		97		64-130	3		20

Lab Control Sample Analysis Batch Quality Control

Project Name: STEEL SUN I GWM

Project Number: B0397-017-001

Lab Number: L1707779

Report Date: 03/20/17

Parameter	LCS %Recovery	Qual	LCSD %Recovery	Qual	%Recovery Limits	RPD	Qual	RPD Limits
Volatile Organics by GC/MS - Westborough Lab Associated sample(s): 03-04 Batch: WG985910-3 WG985910-4								
Bromomethane	59		56		39-139	5		20
Vinyl chloride	110		100		55-140	10		20
Chloroethane	100		97		55-138	3		20
1,1-Dichloroethene	98		90		61-145	9		20
trans-1,2-Dichloroethene	100		99		70-130	1		20
Trichloroethene	100		97		70-130	3		20
1,2-Dichlorobenzene	110		110		70-130	0		20
1,3-Dichlorobenzene	110		110		70-130	0		20
1,4-Dichlorobenzene	110		110		70-130	0		20
Methyl tert butyl ether	73		76		63-130	4		20
p/m-Xylene	120		110		70-130	9		20
o-Xylene	120		110		70-130	9		20
cis-1,2-Dichloroethene	100		100		70-130	0		20
Styrene	120		115		70-130	4		20
Dichlorodifluoromethane	86		81		36-147	6		20
Acetone	120		130		58-148	8		20
Carbon disulfide	93		85		51-130	9		20
2-Butanone	100		100		63-138	0		20
4-Methyl-2-pentanone	98		95		59-130	3		20
2-Hexanone	100		100		57-130	0		20
Bromochloromethane	110		100		70-130	10		20

Lab Control Sample Analysis

Batch Quality Control

Project Name: STEEL SUN I GWM

Project Number: B0397-017-001

Lab Number: L1707779

Report Date: 03/20/17

Parameter	LCS %Recovery	Qual	LCSD %Recovery	Qual	%Recovery Limits	RPD	Qual	RPD Limits
Volatile Organics by GC/MS - Westborough Lab Associated sample(s): 03-04 Batch: WG985910-3 WG985910-4								
1,2-Dibromoethane	98		97		70-130	1		20
n-Butylbenzene	120		110		53-136	9		20
sec-Butylbenzene	110		110		70-130	0		20
1,2-Dibromo-3-chloropropane	69		73		41-144	6		20
Isopropylbenzene	110		110		70-130	0		20
p-Isopropyltoluene	120		110		70-130	9		20
n-Propylbenzene	120		110		69-130	9		20
1,2,3-Trichlorobenzene	110		100		70-130	10		20
1,2,4-Trichlorobenzene	110		100		70-130	10		20
1,3,5-Trimethylbenzene	120		110		64-130	9		20
1,2,4-Trimethylbenzene	110		110		70-130	0		20
Methyl Acetate	110		110		70-130	0		20
Cyclohexane	94		89		70-130	5		20
1,4-Dioxane	118		126		56-162	7		20
Freon-113	91		83		70-130	9		20
Methyl cyclohexane	85		80		70-130	6		20

Lab Control Sample Analysis**Batch Quality Control****Project Name:** STEEL SUN I GWM**Lab Number:** L1707779**Project Number:** B0397-017-001**Report Date:** 03/20/17

Parameter	LCS %Recovery	Qual	LCSD %Recovery	Qual	%Recovery Limits	RPD	Qual	RPD Limits
------------------	--------------------------	-------------	---------------------------	-------------	-----------------------------	------------	-------------	-----------------------

Volatile Organics by GC/MS - Westborough Lab Associated sample(s): 03-04 Batch: WG985910-3 WG985910-4

Surrogate	LCS %Recovery	Qual	LCSD %Recovery	Qual	Acceptance Criteria
1,2-Dichloroethane-d4	110		110		70-130
Toluene-d8	104		103		70-130
4-Bromofluorobenzene	99		100		70-130
Dibromofluoromethane	105		106		70-130

Lab Control Sample Analysis

Batch Quality Control

Project Name: STEEL SUN I GWM

Project Number: B0397-017-001

Lab Number: L1707779

Report Date: 03/20/17

Parameter	LCS %Recovery	Qual	LCSD %Recovery	Qual	%Recovery Limits	RPD	Qual	RPD Limits
Volatile Organics by GC/MS - Westborough Lab Associated sample(s): 01-02 Batch: WG986256-3 WG986256-4								
Methylene chloride	110		120		70-130	9		20
1,1-Dichloroethane	110		120		70-130	9		20
Chloroform	110		120		70-130	9		20
Carbon tetrachloride	100		110		63-132	10		20
1,2-Dichloropropane	110		120		70-130	9		20
Dibromochloromethane	88		92		63-130	4		20
1,1,2-Trichloroethane	92		95		70-130	3		20
Tetrachloroethene	100		110		70-130	10		20
Chlorobenzene	100		110		75-130	10		20
Trichlorofluoromethane	95		100		62-150	5		20
1,2-Dichloroethane	100		110		70-130	10		20
1,1,1-Trichloroethane	110		120		67-130	9		20
Bromodichloromethane	100		110		67-130	10		20
trans-1,3-Dichloropropene	88		92		70-130	4		20
cis-1,3-Dichloropropene	100		110		70-130	10		20
Bromoform	86		87		54-136	1		20
1,1,2,2-Tetrachloroethane	91		94		67-130	3		20
Benzene	120		120		70-130	0		20
Toluene	100		110		70-130	10		20
Ethylbenzene	100		110		70-130	10		20
Chloromethane	120		120		64-130	0		20

Lab Control Sample Analysis

Batch Quality Control

Project Name: STEEL SUN I GWM

Project Number: B0397-017-001

Lab Number: L1707779

Report Date: 03/20/17

Parameter	LCS %Recovery	Qual	LCSD %Recovery	Qual	%Recovery Limits	RPD	Qual	RPD Limits
Volatile Organics by GC/MS - Westborough Lab Associated sample(s): 01-02 Batch: WG986256-3 WG986256-4								
Bromomethane	130		140	Q	39-139	7		20
Vinyl chloride	100		110		55-140	10		20
Chloroethane	110		110		55-138	0		20
1,1-Dichloroethene	110		120		61-145	9		20
trans-1,2-Dichloroethene	120		120		70-130	0		20
Trichloroethene	120		120		70-130	0		20
1,2-Dichlorobenzene	97		100		70-130	3		20
1,3-Dichlorobenzene	100		110		70-130	10		20
1,4-Dichlorobenzene	99		100		70-130	1		20
Methyl tert butyl ether	100		99		63-130	1		20
p/m-Xylene	110		110		70-130	0		20
o-Xylene	110		110		70-130	0		20
cis-1,2-Dichloroethene	120		120		70-130	0		20
Styrene	105		110		70-130	5		20
Dichlorodifluoromethane	70		74		36-147	6		20
Acetone	110		120		58-148	9		20
Carbon disulfide	100		110		51-130	10		20
2-Butanone	96		98		63-138	2		20
4-Methyl-2-pentanone	73		77		59-130	5		20
2-Hexanone	72		76		57-130	5		20
Bromochloromethane	110		110		70-130	0		20

Lab Control Sample Analysis

Batch Quality Control

Project Name: STEEL SUN I GWM

Project Number: B0397-017-001

Lab Number: L1707779

Report Date: 03/20/17

Parameter	LCS %Recovery	Qual	LCSD %Recovery	Qual	%Recovery Limits	RPD	Qual	RPD Limits
Volatile Organics by GC/MS - Westborough Lab Associated sample(s): 01-02 Batch: WG986256-3 WG986256-4								
1,2-Dibromoethane	90		92		70-130	2		20
n-Butylbenzene	81		88		53-136	8		20
sec-Butylbenzene	92		98		70-130	6		20
1,2-Dibromo-3-chloropropane	76		83		41-144	9		20
Isopropylbenzene	110		120		70-130	9		20
p-Isopropyltoluene	85		91		70-130	7		20
n-Propylbenzene	100		110		69-130	10		20
1,2,3-Trichlorobenzene	86		93		70-130	8		20
1,2,4-Trichlorobenzene	93		97		70-130	4		20
1,3,5-Trimethylbenzene	100		110		64-130	10		20
1,2,4-Trimethylbenzene	100		110		70-130	10		20
Methyl Acetate	94		96		70-130	2		20
Cyclohexane	100		110		70-130	10		20
1,4-Dioxane	86		88		56-162	2		20
Freon-113	100		100		70-130	0		20
Methyl cyclohexane	100		110		70-130	10		20

Lab Control Sample Analysis**Batch Quality Control****Project Name:** STEEL SUN I GWM**Lab Number:** L1707779**Project Number:** B0397-017-001**Report Date:** 03/20/17

Parameter	LCS %Recovery	Qual	LCSD %Recovery	Qual	%Recovery Limits	RPD	Qual	RPD Limits
------------------	--------------------------	-------------	---------------------------	-------------	-----------------------------	------------	-------------	-----------------------

Volatile Organics by GC/MS - Westborough Lab Associated sample(s): 01-02 Batch: WG986256-3 WG986256-4

Surrogate	LCS %Recovery	Qual	LCSD %Recovery	Qual	Acceptance Criteria
1,2-Dichloroethane-d4	86		88		70-130
Toluene-d8	96		97		70-130
4-Bromofluorobenzene	103		104		70-130
Dibromofluoromethane	98		99		70-130

SEMIVOLATILES

Project Name: STEEL SUN I GWM

Lab Number: L1707779

Project Number: B0397-017-001

Report Date: 03/20/17

SAMPLE RESULTS

Lab ID: L1707779-01
 Client ID: MWN-58A
 Sample Location: LACKAWANNA, NY
 Matrix: Water
 Analytical Method: 1,8270D
 Analytical Date: 03/20/17 03:53
 Analyst: PS

Date Collected: 03/13/17 12:04
 Date Received: 03/13/17
 Field Prep: Not Specified
 Extraction Method: EPA 3510C
 Extraction Date: 03/16/17 17:58

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
Semivolatile Organics by GC/MS - Westborough Lab						
Acenaphthene	ND		ug/l	2.0	0.59	1
1,2,4-Trichlorobenzene	ND		ug/l	5.0	0.66	1
Hexachlorobenzene	ND		ug/l	2.0	0.58	1
Bis(2-chloroethyl)ether	ND		ug/l	2.0	0.67	1
2-Chloronaphthalene	ND		ug/l	2.0	0.64	1
1,2-Dichlorobenzene	ND		ug/l	2.0	0.73	1
1,3-Dichlorobenzene	ND		ug/l	2.0	0.69	1
1,4-Dichlorobenzene	ND		ug/l	2.0	0.71	1
3,3'-Dichlorobenzidine	ND		ug/l	5.0	1.4	1
2,4-Dinitrotoluene	ND		ug/l	5.0	0.84	1
2,6-Dinitrotoluene	ND		ug/l	5.0	1.1	1
Fluoranthene	ND		ug/l	2.0	0.57	1
4-Chlorophenyl phenyl ether	ND		ug/l	2.0	0.62	1
4-Bromophenyl phenyl ether	ND		ug/l	2.0	0.73	1
Bis(2-chloroisopropyl)ether	ND		ug/l	2.0	0.70	1
Bis(2-chloroethoxy)methane	ND		ug/l	5.0	0.63	1
Hexachlorobutadiene	ND		ug/l	2.0	0.72	1
Hexachlorocyclopentadiene	ND		ug/l	20	7.8	1
Hexachloroethane	ND		ug/l	2.0	0.68	1
Isophorone	ND		ug/l	5.0	0.60	1
Naphthalene	ND		ug/l	2.0	0.68	1
Nitrobenzene	ND		ug/l	2.0	0.75	1
NDPA/DPA	ND		ug/l	2.0	0.64	1
n-Nitrosodi-n-propylamine	ND		ug/l	5.0	0.70	1
Bis(2-ethylhexyl)phthalate	ND		ug/l	3.0	0.91	1
Butyl benzyl phthalate	ND		ug/l	5.0	1.3	1
Di-n-butylphthalate	ND		ug/l	5.0	0.69	1
Di-n-octylphthalate	ND		ug/l	5.0	1.1	1
Diethyl phthalate	ND		ug/l	5.0	0.63	1
Dimethyl phthalate	ND		ug/l	5.0	0.65	1

Project Name: STEEL SUN I GWM

Lab Number: L1707779

Project Number: B0397-017-001

Report Date: 03/20/17

SAMPLE RESULTS

Lab ID: L1707779-01

Date Collected: 03/13/17 12:04

Client ID: MWN-58A

Date Received: 03/13/17

Sample Location: LACKAWANNA, NY

Field Prep: Not Specified

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
Semivolatile Organics by GC/MS - Westborough Lab						
Benzo(a)anthracene	ND		ug/l	2.0	0.61	1
Benzo(a)pyrene	ND		ug/l	2.0	0.54	1
Benzo(b)fluoranthene	ND		ug/l	2.0	0.64	1
Benzo(k)fluoranthene	ND		ug/l	2.0	0.60	1
Chrysene	ND		ug/l	2.0	0.54	1
Acenaphthylene	ND		ug/l	2.0	0.66	1
Anthracene	ND		ug/l	2.0	0.64	1
Benzo(ghi)perylene	ND		ug/l	2.0	0.61	1
Fluorene	ND		ug/l	2.0	0.62	1
Phenanthrene	ND		ug/l	2.0	0.61	1
Dibenzo(a,h)anthracene	ND		ug/l	2.0	0.55	1
Indeno(1,2,3-cd)pyrene	ND		ug/l	2.0	0.71	1
Pyrene	ND		ug/l	2.0	0.57	1
Biphenyl	ND		ug/l	2.0	0.76	1
4-Chloroaniline	ND		ug/l	5.0	0.63	1
2-Nitroaniline	ND		ug/l	5.0	1.1	1
3-Nitroaniline	ND		ug/l	5.0	1.2	1
4-Nitroaniline	ND		ug/l	5.0	1.3	1
Dibenzofuran	ND		ug/l	2.0	0.66	1
2-Methylnaphthalene	ND		ug/l	2.0	0.72	1
1,2,4,5-Tetrachlorobenzene	ND		ug/l	10	0.67	1
Acetophenone	ND		ug/l	5.0	0.85	1
Benzyl Alcohol	ND		ug/l	2.0	0.72	1
Carbazole	ND		ug/l	2.0	0.63	1

Surrogate	% Recovery	Qualifier	Acceptance Criteria
2-Fluorophenol	53		21-120
Phenol-d6	38		10-120
Nitrobenzene-d5	71		23-120
2-Fluorobiphenyl	71		15-120
2,4,6-Tribromophenol	81		10-120
4-Terphenyl-d14	63		41-149

Project Name: STEEL SUN I GWM

Lab Number: L1707779

Project Number: B0397-017-001

Report Date: 03/20/17

SAMPLE RESULTS

Lab ID: L1707779-02
 Client ID: MWN-59A
 Sample Location: LACKAWANNA, NY
 Matrix: Water
 Analytical Method: 1,8270D
 Analytical Date: 03/20/17 04:24
 Analyst: PS

Date Collected: 03/13/17 13:05
 Date Received: 03/13/17
 Field Prep: Not Specified
 Extraction Method: EPA 3510C
 Extraction Date: 03/16/17 17:58

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
Semivolatile Organics by GC/MS - Westborough Lab						
Acenaphthene	ND		ug/l	2.0	0.59	1
1,2,4-Trichlorobenzene	ND		ug/l	5.0	0.66	1
Hexachlorobenzene	ND		ug/l	2.0	0.58	1
Bis(2-chloroethyl)ether	ND		ug/l	2.0	0.67	1
2-Chloronaphthalene	ND		ug/l	2.0	0.64	1
1,2-Dichlorobenzene	ND		ug/l	2.0	0.73	1
1,3-Dichlorobenzene	ND		ug/l	2.0	0.69	1
1,4-Dichlorobenzene	ND		ug/l	2.0	0.71	1
3,3'-Dichlorobenzidine	ND		ug/l	5.0	1.4	1
2,4-Dinitrotoluene	ND		ug/l	5.0	0.84	1
2,6-Dinitrotoluene	ND		ug/l	5.0	1.1	1
Fluoranthene	ND		ug/l	2.0	0.57	1
4-Chlorophenyl phenyl ether	ND		ug/l	2.0	0.62	1
4-Bromophenyl phenyl ether	ND		ug/l	2.0	0.73	1
Bis(2-chloroisopropyl)ether	ND		ug/l	2.0	0.70	1
Bis(2-chloroethoxy)methane	ND		ug/l	5.0	0.63	1
Hexachlorobutadiene	ND		ug/l	2.0	0.72	1
Hexachlorocyclopentadiene	ND		ug/l	20	7.8	1
Hexachloroethane	ND		ug/l	2.0	0.68	1
Isophorone	ND		ug/l	5.0	0.60	1
Naphthalene	ND		ug/l	2.0	0.68	1
Nitrobenzene	ND		ug/l	2.0	0.75	1
NDPA/DPA	ND		ug/l	2.0	0.64	1
n-Nitrosodi-n-propylamine	ND		ug/l	5.0	0.70	1
Bis(2-ethylhexyl)phthalate	ND		ug/l	3.0	0.91	1
Butyl benzyl phthalate	ND		ug/l	5.0	1.3	1
Di-n-butylphthalate	ND		ug/l	5.0	0.69	1
Di-n-octylphthalate	ND		ug/l	5.0	1.1	1
Diethyl phthalate	ND		ug/l	5.0	0.63	1
Dimethyl phthalate	ND		ug/l	5.0	0.65	1

Project Name: STEEL SUN I GWM

Lab Number: L1707779

Project Number: B0397-017-001

Report Date: 03/20/17

SAMPLE RESULTS

Lab ID: L1707779-02

Date Collected: 03/13/17 13:05

Client ID: MWN-59A

Date Received: 03/13/17

Sample Location: LACKAWANNA, NY

Field Prep: Not Specified

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
Semivolatile Organics by GC/MS - Westborough Lab						
Benzo(a)anthracene	ND		ug/l	2.0	0.61	1
Benzo(a)pyrene	ND		ug/l	2.0	0.54	1
Benzo(b)fluoranthene	ND		ug/l	2.0	0.64	1
Benzo(k)fluoranthene	ND		ug/l	2.0	0.60	1
Chrysene	ND		ug/l	2.0	0.54	1
Acenaphthylene	ND		ug/l	2.0	0.66	1
Anthracene	ND		ug/l	2.0	0.64	1
Benzo(ghi)perylene	ND		ug/l	2.0	0.61	1
Fluorene	ND		ug/l	2.0	0.62	1
Phenanthrene	ND		ug/l	2.0	0.61	1
Dibenzo(a,h)anthracene	ND		ug/l	2.0	0.55	1
Indeno(1,2,3-cd)pyrene	ND		ug/l	2.0	0.71	1
Pyrene	ND		ug/l	2.0	0.57	1
Biphenyl	ND		ug/l	2.0	0.76	1
4-Chloroaniline	ND		ug/l	5.0	0.63	1
2-Nitroaniline	ND		ug/l	5.0	1.1	1
3-Nitroaniline	ND		ug/l	5.0	1.2	1
4-Nitroaniline	ND		ug/l	5.0	1.3	1
Dibenzofuran	ND		ug/l	2.0	0.66	1
2-Methylnaphthalene	ND		ug/l	2.0	0.72	1
1,2,4,5-Tetrachlorobenzene	ND		ug/l	10	0.67	1
Acetophenone	ND		ug/l	5.0	0.85	1
Benzyl Alcohol	ND		ug/l	2.0	0.72	1
Carbazole	ND		ug/l	2.0	0.63	1

Surrogate	% Recovery	Qualifier	Acceptance Criteria
2-Fluorophenol	46		21-120
Phenol-d6	32		10-120
Nitrobenzene-d5	65		23-120
2-Fluorobiphenyl	65		15-120
2,4,6-Tribromophenol	75		10-120
4-Terphenyl-d14	59		41-149

Project Name: STEEL SUN I GWM

Lab Number: L1707779

Project Number: B0397-017-001

Report Date: 03/20/17

SAMPLE RESULTS

Lab ID: L1707779-03
 Client ID: MWN-60A
 Sample Location: LACKAWANNA, NY
 Matrix: Water
 Analytical Method: 1,8270D
 Analytical Date: 03/20/17 04:54
 Analyst: PS

Date Collected: 03/13/17 11:00
 Date Received: 03/13/17
 Field Prep: Not Specified
 Extraction Method: EPA 3510C
 Extraction Date: 03/16/17 17:58

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
Semivolatile Organics by GC/MS - Westborough Lab						
Acenaphthene	ND		ug/l	2.0	0.59	1
1,2,4-Trichlorobenzene	ND		ug/l	5.0	0.66	1
Hexachlorobenzene	ND		ug/l	2.0	0.58	1
Bis(2-chloroethyl)ether	ND		ug/l	2.0	0.67	1
2-Chloronaphthalene	ND		ug/l	2.0	0.64	1
1,2-Dichlorobenzene	ND		ug/l	2.0	0.73	1
1,3-Dichlorobenzene	ND		ug/l	2.0	0.69	1
1,4-Dichlorobenzene	ND		ug/l	2.0	0.71	1
3,3'-Dichlorobenzidine	ND		ug/l	5.0	1.4	1
2,4-Dinitrotoluene	ND		ug/l	5.0	0.84	1
2,6-Dinitrotoluene	ND		ug/l	5.0	1.1	1
Fluoranthene	ND		ug/l	2.0	0.57	1
4-Chlorophenyl phenyl ether	ND		ug/l	2.0	0.62	1
4-Bromophenyl phenyl ether	ND		ug/l	2.0	0.73	1
Bis(2-chloroisopropyl)ether	ND		ug/l	2.0	0.70	1
Bis(2-chloroethoxy)methane	ND		ug/l	5.0	0.63	1
Hexachlorobutadiene	ND		ug/l	2.0	0.72	1
Hexachlorocyclopentadiene	ND		ug/l	20	7.8	1
Hexachloroethane	ND		ug/l	2.0	0.68	1
Isophorone	ND		ug/l	5.0	0.60	1
Naphthalene	ND		ug/l	2.0	0.68	1
Nitrobenzene	ND		ug/l	2.0	0.75	1
NDPA/DPA	ND		ug/l	2.0	0.64	1
n-Nitrosodi-n-propylamine	ND		ug/l	5.0	0.70	1
Bis(2-ethylhexyl)phthalate	ND		ug/l	3.0	0.91	1
Butyl benzyl phthalate	ND		ug/l	5.0	1.3	1
Di-n-butylphthalate	ND		ug/l	5.0	0.69	1
Di-n-octylphthalate	ND		ug/l	5.0	1.1	1
Diethyl phthalate	ND		ug/l	5.0	0.63	1
Dimethyl phthalate	ND		ug/l	5.0	0.65	1

Project Name: STEEL SUN I GWM

Lab Number: L1707779

Project Number: B0397-017-001

Report Date: 03/20/17

SAMPLE RESULTS

Lab ID: L1707779-03

Date Collected: 03/13/17 11:00

Client ID: MWN-60A

Date Received: 03/13/17

Sample Location: LACKAWANNA, NY

Field Prep: Not Specified

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
Semivolatile Organics by GC/MS - Westborough Lab						
Benzo(a)anthracene	ND		ug/l	2.0	0.61	1
Benzo(a)pyrene	ND		ug/l	2.0	0.54	1
Benzo(b)fluoranthene	ND		ug/l	2.0	0.64	1
Benzo(k)fluoranthene	ND		ug/l	2.0	0.60	1
Chrysene	ND		ug/l	2.0	0.54	1
Acenaphthylene	ND		ug/l	2.0	0.66	1
Anthracene	ND		ug/l	2.0	0.64	1
Benzo(ghi)perylene	ND		ug/l	2.0	0.61	1
Fluorene	ND		ug/l	2.0	0.62	1
Phenanthrene	ND		ug/l	2.0	0.61	1
Dibenzo(a,h)anthracene	ND		ug/l	2.0	0.55	1
Indeno(1,2,3-cd)pyrene	ND		ug/l	2.0	0.71	1
Pyrene	ND		ug/l	2.0	0.57	1
Biphenyl	ND		ug/l	2.0	0.76	1
4-Chloroaniline	ND		ug/l	5.0	0.63	1
2-Nitroaniline	ND		ug/l	5.0	1.1	1
3-Nitroaniline	ND		ug/l	5.0	1.2	1
4-Nitroaniline	ND		ug/l	5.0	1.3	1
Dibenzofuran	ND		ug/l	2.0	0.66	1
2-Methylnaphthalene	ND		ug/l	2.0	0.72	1
1,2,4,5-Tetrachlorobenzene	ND		ug/l	10	0.67	1
Acetophenone	ND		ug/l	5.0	0.85	1
Benzyl Alcohol	ND		ug/l	2.0	0.72	1
Carbazole	ND		ug/l	2.0	0.63	1

Surrogate	% Recovery	Qualifier	Acceptance Criteria
2-Fluorophenol	45		21-120
Phenol-d6	33		10-120
Nitrobenzene-d5	64		23-120
2-Fluorobiphenyl	64		15-120
2,4,6-Tribromophenol	74		10-120
4-Terphenyl-d14	61		41-149

Project Name: STEEL SUN I GWM

Lab Number: L1707779

Project Number: B0397-017-001

Report Date: 03/20/17

Method Blank Analysis Batch Quality Control

Analytical Method: 1,8270D
 Analytical Date: 03/19/17 21:47
 Analyst: PS

Extraction Method: EPA 3510C
 Extraction Date: 03/16/17 18:05

Parameter	Result	Qualifier	Units	RL	MDL
Semivolatile Organics by GC/MS - Westborough Lab for sample(s): 01-03 Batch: WG985966-1					
Acenaphthene	ND		ug/l	2.0	0.59
1,2,4-Trichlorobenzene	ND		ug/l	5.0	0.66
Hexachlorobenzene	ND		ug/l	2.0	0.58
Bis(2-chloroethyl)ether	ND		ug/l	2.0	0.67
2-Chloronaphthalene	ND		ug/l	2.0	0.64
1,2-Dichlorobenzene	ND		ug/l	2.0	0.73
1,3-Dichlorobenzene	ND		ug/l	2.0	0.69
1,4-Dichlorobenzene	ND		ug/l	2.0	0.71
3,3'-Dichlorobenzidine	ND		ug/l	5.0	1.4
2,4-Dinitrotoluene	ND		ug/l	5.0	0.84
2,6-Dinitrotoluene	ND		ug/l	5.0	1.1
Fluoranthene	ND		ug/l	2.0	0.57
4-Chlorophenyl phenyl ether	ND		ug/l	2.0	0.62
4-Bromophenyl phenyl ether	ND		ug/l	2.0	0.73
Bis(2-chloroisopropyl)ether	ND		ug/l	2.0	0.70
Bis(2-chloroethoxy)methane	ND		ug/l	5.0	0.63
Hexachlorobutadiene	ND		ug/l	2.0	0.72
Hexachlorocyclopentadiene	ND		ug/l	20	7.8
Hexachloroethane	ND		ug/l	2.0	0.68
Isophorone	ND		ug/l	5.0	0.60
Naphthalene	ND		ug/l	2.0	0.68
Nitrobenzene	ND		ug/l	2.0	0.75
NDPA/DPA	ND		ug/l	2.0	0.64
n-Nitrosodi-n-propylamine	ND		ug/l	5.0	0.70
Bis(2-ethylhexyl)phthalate	ND		ug/l	3.0	0.91
Butyl benzyl phthalate	ND		ug/l	5.0	1.3
Di-n-butylphthalate	ND		ug/l	5.0	0.69
Di-n-octylphthalate	ND		ug/l	5.0	1.1
Diethyl phthalate	ND		ug/l	5.0	0.63

Project Name: STEEL SUN I GWM

Lab Number: L1707779

Project Number: B0397-017-001

Report Date: 03/20/17

Method Blank Analysis Batch Quality Control

Analytical Method: 1,8270D
 Analytical Date: 03/19/17 21:47
 Analyst: PS

Extraction Method: EPA 3510C
 Extraction Date: 03/16/17 18:05

Parameter	Result	Qualifier	Units	RL	MDL
Semivolatile Organics by GC/MS - Westborough Lab for sample(s): 01-03 Batch: WG985966-1					
Dimethyl phthalate	ND		ug/l	5.0	0.65
Benzo(a)anthracene	ND		ug/l	2.0	0.61
Benzo(a)pyrene	ND		ug/l	2.0	0.54
Benzo(b)fluoranthene	ND		ug/l	2.0	0.64
Benzo(k)fluoranthene	ND		ug/l	2.0	0.60
Chrysene	ND		ug/l	2.0	0.54
Acenaphthylene	ND		ug/l	2.0	0.66
Anthracene	ND		ug/l	2.0	0.64
Benzo(ghi)perylene	ND		ug/l	2.0	0.61
Fluorene	ND		ug/l	2.0	0.62
Phenanthrene	ND		ug/l	2.0	0.61
Dibenzo(a,h)anthracene	ND		ug/l	2.0	0.55
Indeno(1,2,3-cd)pyrene	ND		ug/l	2.0	0.71
Pyrene	ND		ug/l	2.0	0.57
Biphenyl	ND		ug/l	2.0	0.76
4-Chloroaniline	ND		ug/l	5.0	0.63
2-Nitroaniline	ND		ug/l	5.0	1.1
3-Nitroaniline	ND		ug/l	5.0	1.2
4-Nitroaniline	ND		ug/l	5.0	1.3
Dibenzofuran	ND		ug/l	2.0	0.66
2-Methylnaphthalene	ND		ug/l	2.0	0.72
1,2,4,5-Tetrachlorobenzene	ND		ug/l	10	0.67
Acetophenone	ND		ug/l	5.0	0.85
Benzyl Alcohol	ND		ug/l	2.0	0.72
Carbazole	ND		ug/l	2.0	0.63

Project Name: STEEL SUN I GWM

Lab Number: L1707779

Project Number: B0397-017-001

Report Date: 03/20/17

Method Blank Analysis Batch Quality Control

Analytical Method: 1,8270D
 Analytical Date: 03/19/17 21:47
 Analyst: PS

Extraction Method: EPA 3510C
 Extraction Date: 03/16/17 18:05

Parameter	Result	Qualifier	Units	RL	MDL
Semivolatile Organics by GC/MS - Westborough Lab for sample(s): 01-03 Batch: WG985966-1					

Surrogate	%Recovery	Qualifier	Acceptance Criteria
2-Fluorophenol	39		21-120
Phenol-d6	30		10-120
Nitrobenzene-d5	57		23-120
2-Fluorobiphenyl	57		15-120
2,4,6-Tribromophenol	63		10-120
4-Terphenyl-d14	59		41-149

Lab Control Sample Analysis

Batch Quality Control

Project Name: STEEL SUN I GWM

Project Number: B0397-017-001

Lab Number: L1707779

Report Date: 03/20/17

Parameter	LCS %Recovery	Qual	LCSD %Recovery	Qual	%Recovery Limits	RPD	Qual	RPD Limits
Semivolatile Organics by GC/MS - Westborough Lab Associated sample(s): 01-03 Batch: WG985966-2 WG985966-3								
Acenaphthene	55		55		37-111	0		30
1,2,4-Trichlorobenzene	53		54		39-98	2		30
Hexachlorobenzene	61		61		40-140	0		30
Bis(2-chloroethyl)ether	54		54		40-140	0		30
2-Chloronaphthalene	58		58		40-140	0		30
1,2-Dichlorobenzene	50		52		40-140	4		30
1,3-Dichlorobenzene	50		52		40-140	4		30
1,4-Dichlorobenzene	49		52		36-97	6		30
3,3'-Dichlorobenzidine	47		45		40-140	4		30
2,4-Dinitrotoluene	60		60		48-143	0		30
2,6-Dinitrotoluene	63		62		40-140	2		30
Fluoranthene	57		56		40-140	2		30
4-Chlorophenyl phenyl ether	59		58		40-140	2		30
4-Bromophenyl phenyl ether	62		61		40-140	2		30
Bis(2-chloroisopropyl)ether	53		53		40-140	0		30
Bis(2-chloroethoxy)methane	59		59		40-140	0		30
Hexachlorobutadiene	50		50		40-140	0		30
Hexachlorocyclopentadiene	56		55		40-140	2		30
Hexachloroethane	49		50		40-140	2		30
Isophorone	59		59		40-140	0		30
Naphthalene	55		54		40-140	2		30

Lab Control Sample Analysis

Batch Quality Control

Project Name: STEEL SUN I GWM

Project Number: B0397-017-001

Lab Number: L1707779

Report Date: 03/20/17

Parameter	LCS %Recovery	Qual	LCSD %Recovery	Qual	%Recovery Limits	RPD	Qual	RPD Limits
Semivolatile Organics by GC/MS - Westborough Lab Associated sample(s): 01-03 Batch: WG985966-2 WG985966-3								
Nitrobenzene	57		57		40-140	0		30
NDPA/DPA	59		59		40-140	0		30
n-Nitrosodi-n-propylamine	58		58		29-132	0		30
Bis(2-ethylhexyl)phthalate	62		61		40-140	2		30
Butyl benzyl phthalate	53		52		40-140	2		30
Di-n-butylphthalate	60		59		40-140	2		30
Di-n-octylphthalate	63		62		40-140	2		30
Diethyl phthalate	59		58		40-140	2		30
Dimethyl phthalate	62		62		40-140	0		30
Benzo(a)anthracene	57		56		40-140	2		30
Benzo(a)pyrene	59		59		40-140	0		30
Benzo(b)fluoranthene	58		58		40-140	0		30
Benzo(k)fluoranthene	56		55		40-140	2		30
Chrysene	56		55		40-140	2		30
Acenaphthylene	60		60		45-123	0		30
Anthracene	57		56		40-140	2		30
Benzo(ghi)perylene	57		56		40-140	2		30
Fluorene	58		57		40-140	2		30
Phenanthrene	56		55		40-140	2		30
Dibenzo(a,h)anthracene	58		57		40-140	2		30
Indeno(1,2,3-cd)pyrene	60		58		40-140	3		30

Lab Control Sample Analysis

Batch Quality Control

Project Name: STEEL SUN I GWM

Project Number: B0397-017-001

Lab Number: L1707779

Report Date: 03/20/17

Parameter	LCS %Recovery	Qual	LCSD %Recovery	Qual	%Recovery Limits	RPD	Qual	RPD Limits
Semivolatile Organics by GC/MS - Westborough Lab Associated sample(s): 01-03 Batch: WG985966-2 WG985966-3								
Pyrene	55		54		26-127	2		30
Biphenyl	60		61		40-140	2		30
4-Chloroaniline	30	Q	26	Q	40-140	14		30
2-Nitroaniline	65		64		52-143	2		30
3-Nitroaniline	46		42		25-145	9		30
4-Nitroaniline	57		57		51-143	0		30
Dibenzofuran	57		56		40-140	2		30
2-Methylnaphthalene	57		56		40-140	2		30
1,2,4,5-Tetrachlorobenzene	58		58		2-134	0		30
Acetophenone	61		61		39-129	0		30
Benzyl Alcohol	52		52		26-116	0		30
Carbazole	57		56		55-144	2		30

Surrogate	LCS %Recovery	Qual	LCSD %Recovery	Qual	Acceptance Criteria
2-Fluorophenol	44		44		21-120
Phenol-d6	34		34		10-120
Nitrobenzene-d5	58		58		23-120
2-Fluorobiphenyl	59		59		15-120
2,4,6-Tribromophenol	67		64		10-120
4-Terphenyl-d14	51		51		41-149

METALS

Project Name: STEEL SUN I GWM

Lab Number: L1707779

Project Number: B0397-017-001

Report Date: 03/20/17

SAMPLE RESULTS

Lab ID: L1707779-01

Date Collected: 03/13/17 12:04

Client ID: MWN-58A

Date Received: 03/13/17

Sample Location: LACKAWANNA, NY

Field Prep: Not Specified

Matrix: Water

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor	Date Prepared	Date Analyzed	Prep Method	Analytical Method	Analyst
Total Metals - Mansfield Lab											
Arsenic, Total	0.1405		mg/l	0.00050	0.00016	1	03/15/17 12:30	03/16/17 10:42	EPA 3005A	1,6020A	AM
Chromium, Total	0.00067	J	mg/l	0.00100	0.00017	1	03/15/17 12:30	03/16/17 10:42	EPA 3005A	1,6020A	AM
Lead, Total	0.00077	J	mg/l	0.00100	0.00034	1	03/15/17 12:30	03/16/17 10:42	EPA 3005A	1,6020A	AM
Mercury, Total	ND		mg/l	0.00020	0.00006	1	03/15/17 10:15	03/15/17 17:51	EPA 7470A	1,7470A	EA



Project Name: STEEL SUN I GWM

Lab Number: L1707779

Project Number: B0397-017-001

Report Date: 03/20/17

SAMPLE RESULTS

Lab ID: L1707779-02

Date Collected: 03/13/17 13:05

Client ID: MWN-59A

Date Received: 03/13/17

Sample Location: LACKAWANNA, NY

Field Prep: Not Specified

Matrix: Water

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor	Date Prepared	Date Analyzed	Prep Method	Analytical Method	Analyst
Total Metals - Mansfield Lab											
Arsenic, Total	0.00343		mg/l	0.00050	0.00016	1	03/15/17 12:30	03/16/17 10:52	EPA 3005A	1,6020A	AM
Chromium, Total	0.00090	J	mg/l	0.00100	0.00017	1	03/15/17 12:30	03/16/17 10:52	EPA 3005A	1,6020A	AM
Lead, Total	ND		mg/l	0.00100	0.00034	1	03/15/17 12:30	03/16/17 10:52	EPA 3005A	1,6020A	AM
Mercury, Total	ND		mg/l	0.00020	0.00006	1	03/15/17 10:15	03/15/17 17:53	EPA 7470A	1,7470A	EA



Project Name: STEEL SUN I GWM

Lab Number: L1707779

Project Number: B0397-017-001

Report Date: 03/20/17

SAMPLE RESULTS

Lab ID: L1707779-03

Date Collected: 03/13/17 11:00

Client ID: MWN-60A

Date Received: 03/13/17

Sample Location: LACKAWANNA, NY

Field Prep: Not Specified

Matrix: Water

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor	Date Prepared	Date Analyzed	Prep Method	Analytical Method	Analyst
Total Metals - Mansfield Lab											
Arsenic, Total	0.00225		mg/l	0.00050	0.00016	1	03/15/17 12:30	03/16/17 10:55	EPA 3005A	1,6020A	AM
Chromium, Total	0.00029	J	mg/l	0.00100	0.00017	1	03/15/17 12:30	03/16/17 10:55	EPA 3005A	1,6020A	AM
Lead, Total	ND		mg/l	0.00100	0.00034	1	03/15/17 12:30	03/16/17 10:55	EPA 3005A	1,6020A	AM
Mercury, Total	ND		mg/l	0.00020	0.00006	1	03/15/17 10:15	03/15/17 17:55	EPA 7470A	1,7470A	EA



Project Name: STEEL SUN I GWM
Project Number: B0397-017-001

Lab Number: L1707779
Report Date: 03/20/17

Method Blank Analysis Batch Quality Control

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor	Date Prepared	Date Analyzed	Analytical Method	Analyst
Total Metals - Mansfield Lab for sample(s): 01-03 Batch: WG985493-1										
Mercury, Total	ND		mg/l	0.00020	0.00006	1	03/15/17 10:15	03/15/17 17:29	1,7470A	EA

Prep Information

Digestion Method: EPA 7470A

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor	Date Prepared	Date Analyzed	Analytical Method	Analyst
Total Metals - Mansfield Lab for sample(s): 01-03 Batch: WG985540-1										
Arsenic, Total	ND		mg/l	0.00050	0.00016	1	03/15/17 12:30	03/16/17 10:15	1,6020A	AM
Chromium, Total	ND		mg/l	0.00100	0.00017	1	03/15/17 12:30	03/16/17 10:15	1,6020A	AM
Lead, Total	ND		mg/l	0.00100	0.00034	1	03/15/17 12:30	03/16/17 10:15	1,6020A	AM

Prep Information

Digestion Method: EPA 3005A

Lab Control Sample Analysis

Batch Quality Control

Project Name: STEEL SUN I GWM

Project Number: B0397-017-001

Lab Number: L1707779

Report Date: 03/20/17

Parameter	LCS %Recovery	Qual	LCSD %Recovery	Qual	%Recovery Limits	RPD	Qual	RPD Limits
Total Metals - Mansfield Lab Associated sample(s): 01-03 Batch: WG985493-2								
Mercury, Total	102		-		80-120	-		
Total Metals - Mansfield Lab Associated sample(s): 01-03 Batch: WG985540-2								
Arsenic, Total	105		-		80-120	-		
Chromium, Total	98		-		80-120	-		
Lead, Total	109		-		80-120	-		

Matrix Spike Analysis **Batch Quality Control**

Project Name: STEEL SUN I GWM

Lab Number: L1707779

Project Number: B0397-017-001

Report Date: 03/20/17

Parameter	Native Sample	MS Added	MS Found	MS %Recovery	Qual	MSD Found	MSD %Recovery	Qual	Recovery Limits	RPD	Qual	RPD Limits
Total Metals - Mansfield Lab Associated sample(s): 01-03			QC Batch ID: WG985493-3		WG985493-4	QC Sample: L1707786-11		Client ID: MS Sample				
Mercury, Total	ND	0.005	0.00481	96		0.00482	96		75-125	0		20
Total Metals - Mansfield Lab Associated sample(s): 01-03			QC Batch ID: WG985540-3		WG985540-4	QC Sample: L1707786-11		Client ID: MS Sample				
Arsenic, Total	0.00062	0.12	0.1338	111		0.1309	108		75-125	2		20
Chromium, Total	0.05485	0.2	0.2637	104		0.2616	103		75-125	1		20
Lead, Total	ND	0.51	0.5735	112		0.5680	111		75-125	1		20

Project Name: STEEL SUN I GWM

Project Number: B0397-017-001

Lab Number: L1707779

Report Date: 03/20/17

Sample Receipt and Container Information

Were project specific reporting limits specified? YES

Cooler Information Custody Seal

Cooler

B Absent

Container Information

Container ID	Container Type	Cooler	pH	Temp deg C	Pres	Seal	Analysis(*)
L1707779-01A	Vial HCl preserved	B	N/A	3.4	Y	Absent	NYTCL-8260-R2(14)
L1707779-01B	Vial HCl preserved	B	N/A	3.4	Y	Absent	NYTCL-8260-R2(14)
L1707779-01C	Vial HCl preserved	B	N/A	3.4	Y	Absent	NYTCL-8260-R2(14)
L1707779-01D	Plastic 250ml HNO3 preserved	B	<2	3.4	Y	Absent	CR-6020T(180),PB-6020T(180),AS-6020T(180),HG-T(28)
L1707779-01E	Amber 1000ml unpreserved	B	7	3.4	Y	Absent	NYTCL-8270(7)
L1707779-01F	Amber 1000ml unpreserved	B	7	3.4	Y	Absent	NYTCL-8270(7)
L1707779-02A	Vial HCl preserved	B	N/A	3.4	Y	Absent	NYTCL-8260-R2(14)
L1707779-02B	Vial HCl preserved	B	N/A	3.4	Y	Absent	NYTCL-8260-R2(14)
L1707779-02C	Vial HCl preserved	B	N/A	3.4	Y	Absent	NYTCL-8260-R2(14)
L1707779-02D	Plastic 250ml HNO3 preserved	B	<2	3.4	Y	Absent	CR-6020T(180),PB-6020T(180),AS-6020T(180),HG-T(28)
L1707779-02E	Amber 1000ml unpreserved	B	7	3.4	Y	Absent	NYTCL-8270(7)
L1707779-02F	Amber 1000ml unpreserved	B	7	3.4	Y	Absent	NYTCL-8270(7)
L1707779-03A	Vial HCl preserved	B	N/A	3.4	Y	Absent	NYTCL-8260-R2(14)
L1707779-03B	Vial HCl preserved	B	N/A	3.4	Y	Absent	NYTCL-8260-R2(14)
L1707779-03C	Vial HCl preserved	B	N/A	3.4	Y	Absent	NYTCL-8260-R2(14)
L1707779-03D	Plastic 250ml HNO3 preserved	B	<2	3.4	Y	Absent	CR-6020T(180),PB-6020T(180),AS-6020T(180),HG-T(28)
L1707779-03E	Amber 1000ml unpreserved	B	7	3.4	Y	Absent	NYTCL-8270(7)
L1707779-03F	Amber 1000ml unpreserved	B	7	3.4	Y	Absent	NYTCL-8270(7)
L1707779-04A	Vial HCl preserved	B	N/A	3.4	Y	Absent	NYTCL-8260-R2(14)
L1707779-04B	Vial HCl preserved	B	N/A	3.4	Y	Absent	NYTCL-8260-R2(14)
L1707779-04C	Vial HCl preserved	B	N/A	3.4	Y	Absent	NYTCL-8260-R2(14)
L1707779-04D	Vial HCl preserved	B	N/A	3.4	Y	Absent	NYTCL-8260-R2(14)

*Values in parentheses indicate holding time in days



Project Name: STEEL SUN I GWM
Project Number: B0397-017-001

Lab Number: L1707779
Report Date: 03/20/17

GLOSSARY

Acronyms

EDL	- Estimated Detection Limit: This value represents the level to which target analyte concentrations are reported as estimated values, when those target analyte concentrations are quantified below the reporting limit (RL). The EDL includes any adjustments from dilutions, concentrations or moisture content, where applicable. The use of EDLs is specific to the analysis of PAHs using Solid-Phase Microextraction (SPME).
EPA	- Environmental Protection Agency.
LCS	- Laboratory Control Sample: A sample matrix, free from the analytes of interest, spiked with verified known amounts of analytes or a material containing known and verified amounts of analytes.
LCSD	- Laboratory Control Sample Duplicate: Refer to LCS.
LFB	- Laboratory Fortified Blank: A sample matrix, free from the analytes of interest, spiked with verified known amounts of analytes or a material containing known and verified amounts of analytes.
MDL	- Method Detection Limit: This value represents the level to which target analyte concentrations are reported as estimated values, when those target analyte concentrations are quantified below the reporting limit (RL). The MDL includes any adjustments from dilutions, concentrations or moisture content, where applicable.
MS	- Matrix Spike Sample: A sample prepared by adding a known mass of target analyte to a specified amount of matrix sample for which an independent estimate of target analyte concentration is available.
MSD	- Matrix Spike Sample Duplicate: Refer to MS.
NA	- Not Applicable.
NC	- Not Calculated: Term is utilized when one or more of the results utilized in the calculation are non-detect at the parameter's reporting unit.
NDPA/DPA	- N-Nitrosodiphenylamine/Diphenylamine.
NI	- Not Ignitable.
NP	- Non-Plastic: Term is utilized for the analysis of Atterberg Limits in soil.
RL	- Reporting Limit: The value at which an instrument can accurately measure an analyte at a specific concentration. The RL includes any adjustments from dilutions, concentrations or moisture content, where applicable.
RPD	- Relative Percent Difference: The results from matrix and/or matrix spike duplicates are primarily designed to assess the precision of analytical results in a given matrix and are expressed as relative percent difference (RPD). Values which are less than five times the reporting limit for any individual parameter are evaluated by utilizing the absolute difference between the values; although the RPD value will be provided in the report.
SRM	- Standard Reference Material: A reference sample of a known or certified value that is of the same or similar matrix as the associated field samples.
STLP	- Semi-dynamic Tank Leaching Procedure per EPA Method 1315.
TIC	- Tentatively Identified Compound: A compound that has been identified to be present and is not part of the target compound list (TCL) for the method and/or program. All TICs are qualitatively identified and reported as estimated concentrations.

Footnotes

- 1 - The reference for this analyte should be considered modified since this analyte is absent from the target analyte list of the original method.

Terms

Total: With respect to Organic analyses, a 'Total' result is defined as the summation of results for individual isomers or Aroclors. If a 'Total' result is requested, the results of its individual components will also be reported. This is applicable to 'Total' results for methods 8260, 8081 and 8082.

Analytical Method: Both the document from which the method originates and the analytical reference method. (Example: EPA 8260B is shown as 1,8260B.) The codes for the reference method documents are provided in the References section of the Addendum.

Data Qualifiers

- A** - Spectra identified as "Aldol Condensation Product".
- B** - The analyte was detected above the reporting limit in the associated method blank. Flag only applies to associated field samples that have detectable concentrations of the analyte at less than ten times (10x) the concentration found in the blank. For MCP-related projects, flag only applies to associated field samples that have detectable concentrations of the analyte at less than ten times (10x) the concentration found in the blank. For DOD-related projects, flag only applies to associated field samples that have detectable concentrations of the analyte at less than ten times (10x) the concentration found in the blank AND the analyte was detected above one-half the reporting limit (or above the reporting limit for common lab contaminants) in the associated method blank. For NJ-Air-related projects, flag only applies to associated field samples that have detectable concentrations of the analyte above the reporting limit. For NJ-related projects (excluding Air), flag only applies to associated field samples that have detectable concentrations of the analyte, which was detected above the reporting limit in the associated method blank or above five times the

Report Format: DU Report with 'J' Qualifiers



Project Name: STEEL SUN I GWM**Lab Number:** L1707779**Project Number:** B0397-017-001**Report Date:** 03/20/17**Data Qualifiers**

reporting limit for common lab contaminants (Phthalates, Acetone, Methylene Chloride, 2-Butanone).

- C** - Co-elution: The target analyte co-elutes with a known lab standard (i.e. surrogate, internal standards, etc.) for co-extracted analyses.
- D** - Concentration of analyte was quantified from diluted analysis. Flag only applies to field samples that have detectable concentrations of the analyte.
- E** - Concentration of analyte exceeds the range of the calibration curve and/or linear range of the instrument.
- G** - The concentration may be biased high due to matrix interferences (i.e. co-elution) with non-target compound(s). The result should be considered estimated.
- H** - The analysis of pH was performed beyond the regulatory-required holding time of 15 minutes from the time of sample collection.
- I** - The lower value for the two columns has been reported due to obvious interference.
- M** - Reporting Limit (RL) exceeds the MCP CAM Reporting Limit for this analyte.
- NJ** - Presumptive evidence of compound. This represents an estimated concentration for Tentatively Identified Compounds (TICs), where the identification is based on a mass spectral library search.
- P** - The RPD between the results for the two columns exceeds the method-specified criteria.
- Q** - The quality control sample exceeds the associated acceptance criteria. For DOD-related projects, LCS and/or Continuing Calibration Standard exceedences are also qualified on all associated sample results. Note: This flag is not applicable for matrix spike recoveries when the sample concentration is greater than 4x the spike added or for batch duplicate RPD when the sample concentrations are less than 5x the RL. (Metals only.)
- R** - Analytical results are from sample re-analysis.
- RE** - Analytical results are from sample re-extraction.
- S** - Analytical results are from modified screening analysis.
- J** - Estimated value. The Target analyte concentration is below the quantitation limit (RL), but above the Method Detection Limit (MDL) or Estimated Detection Limit (EDL) for SPME-related analyses. This represents an estimated concentration for Tentatively Identified Compounds (TICs).
- ND** - Not detected at the method detection limit (MDL) for the sample, or estimated detection limit (EDL) for SPME-related analyses.

Report Format: DU Report with 'J' Qualifiers



Project Name: STEEL SUN I GWM
Project Number: B0397-017-001

Lab Number: L1707779
Report Date: 03/20/17

REFERENCES

- 1 Test Methods for Evaluating Solid Waste: Physical/Chemical Methods. EPA SW-846. Third Edition. Updates I - IV, 2007.

LIMITATION OF LIABILITIES

Alpha Analytical performs services with reasonable care and diligence normal to the analytical testing laboratory industry. In the event of an error, the sole and exclusive responsibility of Alpha Analytical shall be to re-perform the work at it's own expense. In no event shall Alpha Analytical be held liable for any incidental, consequential or special damages, including but not limited to, damages in any way connected with the use of, interpretation of, information or analysis provided by Alpha Analytical.

We strongly urge our clients to comply with EPA protocol regarding sample volume, preservation, cooling, containers, sampling procedures, holding time and splitting of samples in the field.



Alpha Analytical, Inc.

ID No.:17873

Facility: **Company-wide**

Revision 10

Department: **Quality Assurance**

Published Date: 1/16/2017 11:00:05 AM

Title: **Certificate/Approval Program Summary**

Page 1 of 1

Certification Information

The following analytes are not included in our Primary NELAP Scope of Accreditation:

Westborough Facility**EPA 624:** m/p-xylene, o-xylene**EPA 8260C:** NPW: 1,2,4,5-Tetramethylbenzene; 4-Ethyltoluene, Azobenzene; SCM: Iodomethane (methyl iodide), Methyl methacrylate, 1,2,4,5-Tetramethylbenzene; 4-Ethyltoluene.**EPA 8270D:** NPW: Dimethylnaphthalene,1,4-Diphenylhydrazine; SCM: Dimethylnaphthalene,1,4-Diphenylhydrazine.**EPA 300:** DW: Bromide**EPA 6860:** NPW and SCM: Perchlorate**EPA 9010:** NPW and SCM: Amenable Cyanide Distillation**EPA 9012B:** NPW: Total Cyanide**EPA 9050A:** NPW: Specific Conductance**SM3500:** NPW: Ferrous Iron**SM4500:** NPW: Amenable Cyanide, Dissolved Oxygen; SCM: Total Phosphorus, TKN, NO₂, NO₃.**SM5310C:** DW: Dissolved Organic Carbon**Mansfield Facility****SM 2540D:** TSS**EPA 3005A** NPW**EPA 8082A:** NPW: PCB: 1, 5, 31, 87,101, 110, 141, 151, 153, 180, 183, 187.**EPA TO-15:** Halothane, 2,4,4-Trimethyl-2-pentene, 2,4,4-Trimethyl-1-pentene, Thiophene, 2-Methylthiophene,

3-Methylthiophene, 2-Ethylthiophene, 1,2,3-Trimethylbenzene, Indan, Indene, 1,2,4,5-Tetramethylbenzene, Benzothiophene, 1-Methylnaphthalene.

Biological Tissue Matrix: EPA 3050B

The following analytes are included in our Massachusetts DEP Scope of Accreditation

Westborough Facility:**Drinking Water****EPA 300.0:** Nitrate-N, Fluoride, Sulfate; **EPA 353.2:** Nitrate-N, Nitrite-N; **SM4500NO3-F:** Nitrate-N, Nitrite-N; **SM4500F-C, SM4500CN-CE, EPA 180.1, SM2130B, SM4500CI-D, SM2320B, SM2540C, SM4500H-B****EPA 332:** Perchlorate; **EPA 524.2:** THMs and VOCs; **EPA 504.1:** EDB, DBCP.**Microbiology:** **SM9215B; SM9223-P/A, SM9223B-Colilert-QT, SM9222D.****Non-Potable Water****SM4500H,B, EPA 120.1, SM2510B, SM2540C, SM2320B, SM4500CL-E, SM4500F-BC, SM4500NH3-BH, EPA 350.1:** Ammonia-N, **LACHAT 10-107-06-1-B:** Ammonia-N, **SM4500NO3-F, EPA 353.2:** Nitrate-N, **EPA 351.1, SM4500P-E, SM4500P-B, E, SM4500SO4-E, SM5220D, EPA 410.4, SM5210B, SM5310C, SM4500CL-D, EPA 1664, EPA 420.1, SM4500-CN-CE, SM2540D.****EPA 624:** Volatile Halocarbons & Aromatics,**EPA 608:** Chlordane, Toxaphene, Aldrin, alpha-BHC, beta-BHC, gamma-BHC, delta-BHC, Dieldrin, DDD, DDE, DDT, Endosulfan I, Endosulfan II, Endosulfan sulfate, Endrin, Endrin Aldehyde, Heptachlor, Heptachlor Epoxide, PCBs**EPA 625:** SVOC (Acid/Base/Neutral Extractables), **EPA 600/4-81-045:** PCB-Oil.**Microbiology:** **SM9223B-Colilert-QT; Enterolert-QT, SM9221E.****Mansfield Facility:****Drinking Water****EPA 200.7:** Ba, Be, Cd, Cr, Cu, Ni, Na, Ca. **EPA 200.8:** Sb, As, Ba, Be, Cd, Cr, Cu, Pb, Ni, Se, TL. **EPA 245.1 Hg.****Non-Potable Water****EPA 200.7:** Al, Sb, As, Be, Cd, Ca, Cr, Co, Cu, Fe, Pb, Mg, Mn, Mo, Ni, K, Se, Ag, Na, Sr, TL, Ti, V, Zn.**EPA 200.8:** Al, Sb, As, Be, Cd, Cr, Cu, Pb, Mn, Ni, Se, Ag, TL, Zn.**EPA 245.1 Hg.****SM2340B**

For a complete listing of analytes and methods, please contact your Alpha Project Manager.

L1707779

1377125