

DECEMBER 2021
GROUNDWATER MONITORING REPORT

FOR
FORMER MOBIL SERVICE STATION 99-MST - 979
MAIN STREET (1001 MAIN STREET)
BCP SITE No. C915260
CITY OF BUFFALO, ERIE COUNTY, NEW YORK

Prepared by:



C&S ENGINEERS, INC.
141 ELM STREET
BUFFALO, NEW YORK 14203

Prepared on Behalf of:

SEAVEST CORE BUFFALO CONVENTUS, LLC
CENTERPOINTE CORPORATE PARK
350 ESSJAY ROAD
WILLIAMSVILLE, NEW YORK 14221

DECEMBER 2021

TABLE OF CONTENTS

1. INTRODUCTION	1
1.1. GEOLOGY	1
1.2. HYDROGEOLOGY	2
1.3. CONTAMINANT TRANSPORT	2
2. ISCO TREATMENT	2
3. GROUNDWATER MONITORING	4
3.1. GROUNDWATER SAMPLING EVENTS	4
3.2. GROUNDWATER SAMPLING METHODS	4
3.3. GROUNDWATER LEVELS	4
3.4. BTEX MONITORING	2
4. CONCLUSION AND RECOMMENDATIONS	4

FIGURES

FIGURE 1 – SITE LOCATION

FIGURE 2 – OFFSITE AND ONSITE GROUNDWATER WELLS

FIGURE 3 – GROUNDWATER CONTOUR

FIGURE 4 – HISTORIC GROUNDWATER SAMPLE RESULTS

GRAPH 1 – GROUNDWATER TREATMENT MONITORING – TOTAL BTEX

TABLES

TABLE 3-2 – GROUNDWATER ANALYTICAL RESULTS

APPENDICES

APPENDIX A – LABORATORY ANALYTICAL RESULTS

APPENDIX B – GROUNDWATER MONITORING CONSTRUCTION & SAMPLING LOGS

APPENDIX C – IN-SITU PRODUCT INFORMATION

ACRONYM LIST

C&S	C&S ENGINEERS, INC.
NYSDEC	NEW YORK STATE DEPARTMENT OF ENVIRONMENTAL CONSERVATION
LUST	LEAKING UNDERGROUND STORAGE TANK
BCP	BROWNFIELD CLEANUP PROGRAM
SPH	SEPARATE PHASE HYDROCARBONS
RI/IRM	REMEDIAL INVESTIGATION / INTERIM REMEDIAL MEASURES
BTEX	BENZENE, TOLUENE, ETHYLBENZENE AND TOLUENE
LNAPL	LIGHT NON AQUEOUS PHASE LIQUID
VOC	VOLATILE ORGANIC COMPOUNDS
SCO	SOIL CLEANUP OBJECTIVES
PID	PHOTO-IONIZATION DETECTOR

1. INTRODUCTION

C&S Engineers, Inc. (C&S) has prepared this Groundwater Monitoring Report for the former Mobil Service Station 99-MST - 979 Main Street (1001 Main Street) (hereinafter referred to as the Site) located at 1001 Main Street in Buffalo, New York.

The Site was remediated in accordance with Brownfield Cleanup Agreement (BCA) Index #C915260-03-12, Site #C915260, which was executed on June 15, 2012 and last amended on August 7, 2012. A figure showing the Site location and boundaries is provided in **Figure 1** and **Figure 2**.

Remedial activities consisted of installing steel shoring around the property and removing contaminated soil and groundwater to 26 - 40 feet below ground surface. After completion of the remedial work, some contamination remained in the subsurface at this Site. A Site Management Plan (SMP) was prepared on November 28, 2014 to manage remaining groundwater contamination at the Site until the Environmental Easement is extinguished in accordance with ECL Article 71, Title 36.

Petroleum contaminated groundwater is present within a discontinuous layer of coarse sand and gravel located between 32 and 35 feet below ground surface. This layer generally ranges from 6 inches to three feet thick, provides a preferential pathway for groundwater flow, and is confined within dense silt and fine sand present above and below the groundwater bearing zone.

During the remedial efforts, seven groundwater monitoring wells were installed prior to the installation of the two floors of underground parking. These monitoring wells were used to monitor the effectiveness of in-situ chemical injections.

SUBSURFACE CONDITIONS

1.1. Geology

Geologic information is based on observations made during site excavations for the Site remedial efforts, as well as numerous previous studies such as the *Supplemental Subsurface Investigation and Quarterly Groundwater Monitoring Report*, (December 9, 2008, Groundwater & Environmental Service, Inc.) and the *Geotechnical Engineering Report, 1001 Main Street Medical Office Building, Buffalo New York*; (November 2010; McMahon and Mann Consulting Engineers).

The Site contained urban fill of varying depths. Fill depths ranged from 3 feet of parking lot subgrade and mixed stone to more urban fill ranging from 6 -12 feet of bricks concrete and miscellaneous building rubble, which at times was contained within old building basements.

Underlying the fill were native deposits of fine dense sand with silt with discrete clay lenses. Within this formation is a discrete, discontinuous water bearing zone comprised of coarse sand and fine to medium gravel. This zone is generally found between 32 and 35 feet bgs and ranging in thickness between 6-inches to several feet (GES, 2008).

Below this zone is the dry to moist fine sand and silt formation extends to nearly 70 feet bgs. Below this massive sand and silt formation is a coarse sand and gravel layer that grades to a sand, gravel; and clay till formation. Underlying the overburden is a grey cherty limestone formation at approximately 90 feet bgs (M&M, 2010).

1.2. Hydrogeology

The principal groundwater bearing zone beneath the Site is located within the coarse sand and gravel layer that is generally present between 32 and 35 feet bgs. This layer is of variable thickness (generally six inches to three feet) but is horizontally discontinuous. The layer is located within the central and northeastern portions of the Site, but does not extend completely to the southern, northwestern or southeastern areas of the Site (GES, 2008) and is confined by the dense fine sands and silt above and below the groundwater bearing zone.

Groundwater beneath the Site flows from the west to the northeast, following the depositional area of the confined groundwater bearing zone.

1.3. Contaminant Transport

Petroleum from leaking underground storage tanks (LUSTs) formerly located at a Mobil Service Station at the corner of Main and High Streets spilled petroleum products into the subsurface soils and groundwater for over 30 years. The main release area is located in the approximate area of the former LUSTs where contaminated soils were observed from 10 feet below ground surface (BGS) to approximately 20 feet BGS grade.

From the main release area, historic migration of petroleum product entered into a semi-confined coarse sand and gravel lens observed approximately 32 to 35 feet BGS. The water table is present within this semi-confined coarse sand and gravel lens. This lens varies in thickness (1/2 to 3 feet) and extends to the northeast, confined laterally to the east and west. Petroleum product within this lens generally moved horizontally across the Site with groundwater flow.

Because of low carbon in the fine sand silt and gravel formations, breakdown of benzene, toluene, ethylbenzene and xylene (BTEX) compounds was slow. Dissolved BTEX, once entering the groundwater bearing zone was transported via localized, preferential groundwater flow to the northeast corner of the Site (following the location of the sand/gravel lens).

2. ISCO TREATMENT

The remedial method selected for the Site was in-situ chemical oxidation (ISCO) using RegenOX manufactured by Regenesis. RegenOX is sodium percarbonate formulated to degrade petroleum hydrocarbons through direct oxidation and through the generation of free radical compounds which will also oxidize contaminants. RegenOx produces minimal heat and pressure and is non-corrosive, making it a relatively safe chemical oxidant that is compatible for use in direct contact with underground infrastructure such as utilities, tanks, piping, and communication lines. This was an important characteristic when selecting the ISCO product due to the close proximity of the monitoring wells to the earth retention sheeting for the Conventus Building.

The amount of RegenOX used was calculated based on Conventus Site specific data and professional experience of C&S and Regenesis. RegenOX was mixed with tap water in 55 gallon drums at a concentration of 100 pounds of RegenOX with 110 gallons of water for each location.

In-situ treatment consisted of gravity-feeding a chemical oxidizer mixed with water directly into monitoring wells, BCP-MW-3, BCP-MW-4, BCP-MW-5, and BCP-MW-6,. Groundwater samples were collected approximately three months after treatment. The first ISCO treatment was conducted on December 12, 2013.

Evaluation of the gravity fed treatments determined this method was not effective at reducing groundwater contaminants. A work plan for increasing the amount of treatment solution using pressure injections was developed. Borings were advanced in the lower floor of underground parking to apply in-situ treatments under pressure directly into the contaminated sand and gravel lens. The sections below describe the methods used to conduct two in-situ treatment events on October 13 and October 14 of 2021.

The ISCO solution was directly injected into the soil in 12 borings in the sub-basement. Three borings were advanced adjacent to each monitoring wells listed below:

- BCP-MW-3
- BCP-MW-5
- BCP-MW-4
- BCP-MW-6

Each injection boring had to be carefully located to avoid hitting utilities located underneath the floor, with the intent of being within 10 to 15 feet of each monitoring well. Each injection boring was advanced into the coarse sand and gravel layer, approximately 15 feet below the concrete floor.

The ISCO solution was pumped from the mixing station to a truck mounted geo-probe and into the subsurface. The mix of RegenOX and water was injected under pressure in each boring, and the 12 injection borings received approximately 100 pounds of RegenOx. Additionally, 100 pounds of ISCO material was gravity fed directly into each monitoring well. A total of 1,600 pounds of RegenOx was used for each treatment event. For two treatments, a total of 3,200 pounds of RegenOX was used. These large treatment events resulted in mixed results; some locations showed an increase in contaminant concentrations, likely due to additional petroleum desorption, other locations indicated a significant decrease of petroleum contaminants.

The current ISCO treatment method is smaller pressurized injections around each target location on a quarterly schedule. A total of six temporary PVC injection points were installed around BCP-MW-6 and BCP-MW-5. Each quarterly treatment injects a total of 800 pounds (130 pounds per injection point) of chemical oxidant. Groundwater monitoring is conducted biannually.

For this reporting period, the last in-situ treatment was completed on October 13 and October 14 of 2021.

GROUNDWATER MONITORING

2.1. Groundwater Sampling Events

Previously, groundwater samples were collected from the wells on following dates:

- September 20, 2013
- March 19, 2014
- May 22, 2014
- March 11, 2015
- June 17, 2015
- August 3, 2015
- October 7, 2015
- December 14, 2015
- January 27, 2016
- March 22, 2016
- June 3, 2016
- October 25, 2016
- December 8, 2016
- January 20, 2017
- May 17, 2017
- July 5, 2017
- November 2, 2017
- August 18, 2018
- November 30, 2018
- July 30, 2019
- December 4, 2019
- March 31, 2020
- November 25, 2020
- May 14, 2021
- December 14, 2021

For this reporting period, the groundwater sampling was completed on December 14, 2021.

2.2. Groundwater Sampling Methods

Before purging the wells, water levels were measured using an electric water level sounder capable of measuring to the 0.01-foot accuracy. Peristaltic or bladder pumps using manufacturer-specified tubing was used for purging and sampling groundwater. Calibration, purging and sampling procedures was performed as specified by the USEPA¹ for low-flow sampling. Decontamination was conducted after each well is sampled to reduce the likelihood of cross contamination. Groundwater sampling equipment including the in-well pump, flow cell and water level meter was cleaned with Alconox, a phosphate free cleaner.

Samples were collected for VOCs in three 40 ml glass vials. Groundwater filled each vial until it formed a meniscus and no air bubbles were inside the vial. The cap was placed on the vial and turned over to check if any air bubbles were in the sample. Groundwater samples were kept at 4°C until the laboratory took custody of the samples.

2.3. Groundwater Levels

Groundwater levels were measured from the top of the monitoring well casing an electric water level sounder capable of measuring to the 0.01-foot accuracy. Lidar data, downloaded from the New York State GIS Clearinghouse, was used to obtain ground elevations for each monitoring well. The Lidar dataset, developed in 2008, covers Erie County and achieves a

¹ U.S. EPA Region 1 Low Stress (low-flow) Purging and Sampling Procedure for the Collection of Groundwater Samples from Monitoring Wells, January 19, 2010.

vertical accuracy of 18.5 cm on open bare terrain and 37.0 cm for obscured areas. Groundwater elevations for each monitoring well are provided in **Table 3-1** below.

Table 3-1: Monitoring Well Ground Elevations

<i>MONITORING WELL ID</i>	<i>GROUND ELEVATION (FT.)</i>	<i>WATER LEVEL (FT.)</i>	<i>GROUNDWATER ELEVATION (FT.)</i>
BCP-MW-1	663.465	32.6	630.865
BCP-MW-3	663.465	33.2	630.265
BCP-MW-4	663.465	33.0	630.465
BCP-MW-5	663.465	32.2	631.265
BCP-MW-6	663.465	32.6	630.865
BCP-MW-7	663.465	29.9	633.565

Note: Ground elevations from Lidar Dataset.

Figure 3 presents groundwater elevation contours.

2.4. BTEX Monitoring

Table 3-2 attached to the end of this report presents detected VOC concentrations from December 2012 to December 2021. **Figure 4** presents total BTEX concentrations from each monitoring well. Lab analytical reports are provided in **Appendix A**.

BCP-MW-1

Total BTEX concentrations in this well after sampling showed 0 ug/L. This trend has been consistent since the sampling event that took place in October of 2016.

BCP-MW-2

BCP-MW-2 was installed adjacent to the source area that was backfilled with flowable fill. Since its installation, this well has been dry. NYSDEC requested the well be modified to evaluate if groundwater underneath the flowable fill mass contains residual contamination. On October 7, 2015 Nature's Way Environmental installed a 1-inch PVC well through the existing BCP-MW-2 to a final depth of 50 feet bgs. The modified well has remained dry.

BCP-MW-3

MW-3 had a total VOC concentration of 174.9 ug/l which is a significant increase from the previous sampling event that had a total VOC concentration of 4.8 ug/l. The total BTEX concentration in MW-3 increased from 0 ug/l during the May sampling event, to 126.49 ug/l for the most recent December sampling event. The BTEX and total VOC concentrations reached their highest levels since the 2017 sampling events.

BCP-MW-4

The December 14, 2021 sampling event for MW-4 showed a slight increase in total VOC levels as well as total BTEX concentrations. The total VOC concentration for MW-4 was 2,659 ug/L and total BTEX showed a concentration of 2,020 ug/L compared to the previous sampling event that showed a total VOC concentration of 2,100.5 ug/l and total BTEX concentration of 1,548.50 ug/l.

BCP-MW-5

The initial BTEX concentration of MW-5 was 17,670 ug/L in September of 2013. The December 14, 2021 sampling event for MW-5 showed a significant decrease in total VOC levels as well as total BTEX concentrations but showed an increase in total VOC and total BTEX concentrations from the previous sampling event in May of 2021. The total VOC concentration for MW-5 was 8,403 ug/l and total BTEX showed a concentration of 6,920 ug/l compared to the previous May 2021 sampling event that showed a total VOC concentration of 2.864 ug/l and total BTEX concentration of 2,325 ug/l. The December 14, 2021 sampling event shows concentrations that are similar to the concentrations that were sampled in November of 2020.

BCP-MW-6

This sampling event showed a decrease in concentrations from the previous sampling event. The total VOC concentration for MW-6 was 0 ug/L and total BTEX showed a concentration of 0 ug/L compared to the previous sampling event that showed a total VOC concentration of 5 ug/l and total BTEX concentration of 0 ug/l. This is the first sampling event from MW-6 that resulted in total VOCs and total BTEX concentrations of 0 ug/l, since sampling events were initiated in 2013.

BCP-MW-7

In the most recent sampling event on December 14, 2021 the decreasing concentration trend continued with total VOC concentrations as well as total BTEX concentrations, which both had concentrations of 0 ug/l. This sampling event is consistent with the previous sampling events in December of 2019 and in November of 2020 that also had a total BTEX and total VOC concentration of 0 ug/l.

3. CONCLUSION AND RECOMMENDATIONS

The October 2021 injection event appeared to be successful in most wells but slightly inefficient in three of the other wells. This could have a correlation with the time period between when the wells were injected and when the samples were collected from the wells. C&S recommends the following:

- Bi-annual groundwater sampling on all monitoring wells located on the Conventus site in 2022.

F:\Project\U86 - Seavest Core Buffalo Conventus, LLC\U86001004 - Conventus 2021 Groundwater remediation\Planning-Study\Reports\December 2021\December 2021 - Conventus Groundwater Monitoring Report.docx

TABLES

**Table 3-2 Groundwater Analytical Results
Summary of Detected Compounds
Former Mobil Station 99-MST 979 Main Street (1001 Main Street) Brownfield Cleanup**

Sample Name	MW-1	MW-1	MW-1	MW-1	MW-1	MW-1	MW-1	MW-1	MW-1	MW-1	MW-1	MW-1	MW-1	MW-1	MW-1	MW-1	MW-1	MW-1	MW-1	MW-1	MW-1	MW-1	MW-1		
	Date Collected	9/20/2013	3/19/2014	5/22/2014	3/11/2015	6/17/2015	8/3/2014	12/15/2015	3/22/2016	6/3/2016	10/25/2016	12/8/2016	1/20/2017	5/17/2017	7/5/2017	11/2/2017	8/16/2018	11/29/2018	7/30/2019	12/12/2019	3/31/2020	11/25/2020	5/14/2021	12/14/2021	
Matrix	WG	WG	WG	WG	WG	WG	WG	WG	WG	WG	WG	WG	WG	WG	WG	WG	WG	WG	WG	WG	WG	WG	WG	WG	
Unit	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	
NYSDEC Ambient Water Quality Standards & Guidance Values																									
Volatile Organic Compound	Surface Water	Groundwater																							
1,2-DICHLOROETHANE	3	3	ND	ND	ND			ND		ND										ND		ND		ND	
1,2-DICHLOROBENZENE	0.6	0.6	ND	ND	ND			ND		ND										.15 J		ND		ND	
1,2-DICHLOROPROPANE	1	1	ND	ND	ND			ND		ND												ND		ND	
1,3-DICHLOROBENZENE	3	3	ND	ND	ND			ND		ND										ND		ND		ND	
2-HEXANONE	50	50	ND	ND	ND			ND	ND	3.5	ND	ND	ND			ND	ND	ND	ND	ND	ND	ND	ND	ND	
ACETONE	50	50	ND	ND	ND			ND	ND	ND	ND	ND	ND			ND	5.1	ND	ND	1.8J	2.4 J	1.7	ND	ND	1.8
BENZENE	1	1	ND	ND	ND			35	39	5.7	1.4	0.72	ND			ND	ND	0.33	ND	ND	ND	ND	ND	ND	
DIBROMOCHLOROMETHANE	50	50	ND	ND	ND																				
DICHLORODIFLUOROMETHANE	5	5	ND	ND	ND																				
ETHYLBENZENE	5	5	ND	ND	ND			2	1.5	ND	ND	ND	ND			ND	ND	ND	ND	ND	ND	ND	ND	ND	
ISOPROPYLBENZENE (CUMENE)	5	5	ND	ND	ND			1.3	ND	ND	ND	ND	ND			ND	ND	ND	ND	ND	ND	ND	ND	ND	
METHYL ETHYL KETONE (2-BUTANONE)	50	50	ND	ND	ND			ND	45	ND	ND	ND	ND			ND	ND	ND	ND	ND	ND	ND	ND	ND	
METHYLENE CHLORIDE	5	5	ND	ND	ND			ND	ND	ND	ND	ND	ND			ND	ND	ND	ND	ND	ND	ND	ND	ND	
TOLUENE	5	5	ND	ND	ND			19	38	0.55	ND	ND	ND			ND	ND	1.1	ND	ND	ND	ND	ND	ND	
TRICHLOROETHYLENE (TCE)	5	5	ND	ND	ND			ND	ND	ND	ND	ND	ND			ND	ND	ND	ND	ND	ND	ND	ND	ND	
1,1,2-TRICHLOROETHANE	1	1	ND	ND	ND			ND	ND	ND	0.33 J	ND	ND			ND	ND	ND	ND	ND	ND	ND	ND	ND	
XYLENES, TOTAL	5	5	ND	ND	ND			6.4	4.2	ND	ND	ND	ND			ND	ND	ND	ND	ND	ND	ND	ND	ND	
NAPHTHALENE	10	10	ND	ND	ND			ND	ND	ND	0.33 J	ND	ND			ND	ND	ND	ND	4.3	ND	ND	ND	1.4	
No Standard																									
CARBON DISULFIDE			ND	ND	0.94			ND	ND	ND	ND	ND	ND			ND	ND	ND	ND	ND	ND	ND	ND	ND	
CYCLOHEXANE			ND	ND	ND			35	59	61	51	72	ND			ND	ND	ND	ND	ND	ND	ND	ND	ND	
METHYL ISOBUTYL KETONE			ND	ND	ND			ND	13	ND	ND	ND	ND			ND	ND	ND	ND	ND	ND	ND	ND	ND	
METHYLCYCLOHEXANE			ND	ND	0.47			3.2	17	15	11	ND	ND			ND	ND	ND	1.5	.88J	ND	ND	ND	ND	
Total VOCs	0	0	1.41	-	101.90	216.70	85.75	63.40	72.72	0	-	5.1	1.4	1.5	6.98	2.55	1.7	0	0	0	0	0	0	0	
Total BTEX	0	0	0	-	62	83	6	1.4	0.7	0	0.0	0	0	0	0	0	0	0	0	0	0	0	0	0	
Non-Standard VOC List																									
1,3,5-TRIMETHYLBENZENE	5	5														ND	ND		ND		ND		ND	ND	
1,2,4,5-TETRAMETHYLBENZENE	5	5														ND	ND		ND		ND		ND	ND	
1,2,4-TRIMETHYLBENZENE	5	5														ND	ND		ND		ND		1.6	ND	
SEC-BUTYLBENZENE	5	5														ND	ND		ND		ND		ND	ND	
N-PROPYLBENZENE	5	5														ND	ND		ND		ND		ND	ND	
N-BUTYLBENZENE	5	5														ND	ND		ND		ND		ND	ND	
P-ISOPROPYLTOLUENE																ND	ND		ND		ND		ND	ND	
1,4-DIETHYLBENZENE																ND	ND		ND		ND		ND	ND	

Notes:
 Not Sampled
1) Blank space = analyte concentration not reported
2) BCP MW-2 was dry and not sampled
3) For the March 11, 2015 monitoring event well MW-1, MW-5, MW-6 and MW-7 were dry or not enough water was inside the well for a representative sample.
4) WG = groundwater

**Table 3-2 Groundwater Analytical Results
Summary of Detected Compounds
Former Mobil Station 99-MST 979 Main Street (1001 Main Street) Brownfield Cleanup**

Sample Name	MW-3	MW-3	MW-3	MW-3	MW-3	MW-3	MW-3	MW-3	MW-3	MW-3	MW-3	MW-3	MW-3	MW-3	MW-3	MW-3	MW-3	MW-3	MW-3	MW-3	MW-3	MW-3	MW-3	MW-3	
Date Collected	9/20/2013	3/19/2014	5/22/2014	3/11/2015	6/17/2015	8/3/2015	12/15/2015	1/27/2015	3/22/2016	6/3/2016	10/25/2016	12/8/2016	1/20/2017	5/17/2017	7/5/2017	11/2/2017	8/16/2018	11/29/2018	7/30/2019	12/12/2019	3/31/2020	11/25/2020	5/14/2021	12/14/2021	
Matrix	WG	WG	WG	WG	WG	WG	WG	WG	WG	WG	WG	WG	WG	WG	WG	WG	WG	WG	WG	WG	WG	WG	WG	WG	
Unit	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	
NYSDEC Ambient Water Quality Standards & Guidance Values																									
Volatile Organic Compound	Surface Water	Groundwater																							
1,2-DICHLOROETHANE	3	3	ND	ND	ND																				
1,2-DICHLOROBENZENE	0.6	0.6	ND	ND	ND																				
1,2-DICHLOROPROPANE	1	1	ND	ND	ND																				
1,3-DICHLOROBENZENE	3	3	ND	ND	ND																				
2-HEXANONE	50	50	ND	ND	ND	3	ND	ND	8	ND	ND	ND	ND	ND	ND	ND	ND								
ACETONE	50	50	ND	98	ND	17	ND	ND	166	ND	2.3	24.0	2.1 J	ND	ND	ND	3.8	6.2							
BENZENE	1	1	6,600	4,500	4,700	3,700	4,300	4,100	2,100	2,200	1,900	3,100	1,390	635	363	451	3	364	ND	ND	0.2J	ND	ND	ND	0.49 J
DIBROMOCHLOROMETHANE	50	50	ND	ND	ND																				
DICHLORODIFLUOROMETHANE	5	5	ND	ND	ND																				
ETHYLBENZENE	5	5	1,200	1,600	1,500	1,600	1,500	1,700	1,400	1,600	1,600	610	194	899	517	197	2.4	384	ND	ND	ND	1.1 J	ND	ND	42
ISOPROPYLBENZENE (CUMENE)	5	5	ND	37	ND	32	ND	ND	ND	ND	8.7	ND	ND	ND	ND	ND	ND								
METHYL ETHYL KETONE (2-BUTANONE)	50	50	ND	71	ND	6.7	ND	201	51.4	51.4	ND	ND	ND	ND	ND	ND	ND								
METHYLENE CHLORIDE	5	5	ND	ND	ND	ND	ND	ND	ND	ND	35	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
TOLUENE	5	5	110	150	150	110	110	130	100	110	110	67	39.4	74.5	38.4	22.6	1.6	34.8	ND	ND	ND	ND	ND	ND	4.8
TRICHLOROETHYLENE (TCE)	5	5	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	
1,1,2-TRICHLOROETHANE	1	1	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	
XYLENES, TOTAL	5	5	3,700	3,600	3,200	4200	4000	3900	2200	2600	2200	2100	806.3	1430	949	639	7.1	930.0	ND	ND	ND	1.3 J	ND	ND	79.2 J
NAPHTHALENE	10	10	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	14	357	ND	ND	ND	ND	ND	1.5 J	ND	18
No Standard																									
CARBON DISULFIDE	ND	ND	ND	0.31	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
CYCLOHEXANE	120	320	270	390	330	210	100	93	110	170	ND	ND	ND	ND	ND	60.5	ND	ND	ND	ND	ND	ND	3.4 J	1	16
METHYL ISOBUTYL KETONE	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
METHYLCYCLOHEXANE	ND	130	150	120	160	96	34	33	36 J	170	47.7	ND	ND	29.5	ND	33.4	ND	ND	ND	ND	ND	ND	ND	ND	8.2 J
Total VOCs	11,730	10,506	9,970	10,179	10,400	10,136	5,934	6,636	5,920	6,252	2,477	3,038	1,867	1,540	254	2,224	2.3	24.0	2.1	2.6	0	4.9	4.8	174.9	
Total BTEX	11,610	9,850	9,550	9,610	9,910	9,830	5,800	6,510	5,810	5,877	2,430	3,038	1,867	1,310	14	1,713	-	-	-	2.6	0	0	0.0	126.49	
Non-Standard VOC List																									
1,3,5-TRIMETHYLBENZENE	5	5														ND	133	133	ND	ND	ND	ND	ND	ND	6.5
1,2,4,5-TETRAMETHYLBENZENE	5	5														ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,2,4-TRIMETHYLBENZENE	5	5														4.9	737	737	ND	ND	1.2 J	0.88J	ND	ND	68
SEC-BUTYLBENZENE	5	5														ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
N-PROPYLBENZENE	5	5														ND	ND	ND	ND	ND	ND	ND	ND	ND	2.3 J
N-BUTYLBENZENE	5	5														ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
P-ISOPROPYLTOLUENE																ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,4-DIETHYLBENZENE																ND	ND	ND	ND	ND	ND	ND	ND	ND	ND

- Notes:
- 1) Blank space = analyte concentration not reported
 - 2) BCP MW-2 was dry and not sampled
 - 3) For the March 11, 2015 monitoring event well MW-1, MW-5, MW-6 and MW-7 were dry or not enough water was inside the well for a representative sample.
 - 4) WG = groundwater

**Table 3-2 Groundwater Analytical Results
Summary of Detected Compounds
Former Mobil Station 99-MST 979 Main Street (1001 Main Street) Brownfield Cleanup**

Sample Name	MW-4	MW-4	MW-4	MW-4	MW-4	MW-4	MW-4	MW-4	MW-4	MW-4	MW-4	MW-4	MW-4	MW-4	MW-4	MW-4	MW-4	MW-4	MW-4	MW-4	MW-4	MW-4	MW-4	MW-4	MW-4	
Date Collected	9/20/2013	3/19/2014	5/22/2014	3/11/2015	6/17/2015	8/3/2015	12/15/2015	1/27/2016	3/22/2016	6/3/2016	10/25/2016	12/8/2016	1/20/2017	5/17/2017	7/5/2017	11/17/2017	8/16/2018	11/29/2018	7/30/2019	12/12/2019	3/31/2020	11/25/2020	5/14/2021	12/14/2021		
Matrix	WG	WG	WG	WG	WG	WG	WG	WG	WG	WG	WG	WG	WG	WG	WG	WG	WG	WG	WG	WG	WG	WG	WG	WG	WG	
Unit	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	
NYSDEC Ambient Water Quality Standards & Guidance Values																										
Volatiles Organic Compound	Surface Water	Groundwater																								
1,2-DICHLOROBENZENE	3	3	ND	ND	ND																					
1,2-DICHLOROETHANE	0.6	0.6	ND	ND	ND																					
1,2-DICHLOROPROPANE	1	1	ND	ND	ND																					
1,3-DICHLOROBENZENE	3	3	ND	ND	ND																					
2-HEXANONE	50	50	ND	ND	ND	1.7	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND								
ACETONE	50	50	10	250	170	67	ND	210	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	
BENZENE	1	1	42	29	15	26	24	242	ND	21	ND	21	9.57	12.8	10.2	10.8	1.3	97.0	45.0	36.0	6.7	6.4	7.6	7.8	8.5	5.0
DIBROMOCHLOROMETHANE	50	50	ND	ND	ND																					
DICHLORODIFLUOROMETHANE	5	5	ND	ND	ND																					
ETHYLBENZENE	5	5	4.7	34	32	560	1,000	680	1,100	1,300	1,400	1,400	1,000	1,170	1,300	1,220	28	1.8	ND	170	2.0 J	460	810	870	1,100	1,100
ISOPROPYLBENZENE (CUMENE)	5	5	ND	ND	ND	9.8	15.0	26	ND	ND	ND	ND	19	30.3	28.7	ND	2.3	ND	ND	8.3	1.3 J	19	28	34	28	35
METHYL ETHYL KETONE (2-BUTANONE)	50	50	ND	ND	ND	ND	8.50	ND	ND	ND	6.9	ND	ND	ND	ND	ND	ND	ND	ND							
METHYLENE CHLORIDE	5	5	ND	ND	1 J	ND	ND	ND	ND	52	ND	42	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	
TOLUENE	5	5	1.1	190	110	53	57	140	180	270	150	97	62.4	130	133	92.2	9.8	ND	ND	15	ND	11	46	29	22	64
TRICHLOROETHYLENE (TCE)	5	5	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	
1,1,2-TRICHLOROETHANE	1	1	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	
XYLENES, TOTAL	5	5	29	180	160	800	1,200	3,100	1,800	2,600	2,100	1,800	1,160	1,892	1,944	1,289.7	24.5	ND	ND	83.6	ND	157.3	534 J	358 J	418	651 J
NAPHTHALENE	10	10	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	1.9	ND	ND	36	ND	99	230	230	320	360
No Standard																										
CARBON DISULFIDE	ND	ND	1.9 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND											
CYCLOHEXANE	8.2	11	7	170	170	110	160	220	250	340	189	259	276	235	276	5.5	ND	24	41 J	60	100	140	160	190		
METHYL ISOBUTYL KETONE	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	
METHYLCYCLOHEXANE	7.5	3.7	3.1	87	92	69	86	100	110	140	85.1	110	123	99.7	123	2.4	0.47	8.9	ND	8	22J	38 J	44	54 J		
Total VOCs	102.5	697.7	497.1	1,774.5	2,566.5	4,577.0	3,326.0	4,563.0	4,010.0	3,840.0	2,525.5	3,604.1	3,814.9	2,947.4	511.9	116.7	47.1	381.8	10.4	821.7	1,777.6	1,706.8	2,100.5	2,659.0		
Total BTEX	76.8	433	317	1,439	2,281	4,162	3,080	4,191	3,650	3,318	2,232	3,205	3,387	2,613	64	99	45	304.6	8.7	634.7	1,397.60	1,264.80	1,548.50	2,020.0		
Non-Standard VOC List																										
1,3,5-TRIMETHYLBENZENE	5	5														2	ND	ND	1.4 J	ND	ND	7.0J	11 J	8.4	13 J	
1,2,4,5-TETRAMETHYLBENZENE	5	5														1.1	ND	ND	ND	ND	ND	ND	ND	ND	ND	
1,2,4-TRIMETHYLBENZENE	5	5														1.1	ND	ND	150	ND	470	1100	1300	1500	1500	
SEC-BUTYLBENZENE	5	5														ND	ND	ND	1.5 J	ND	2.9 J	ND	ND	ND	ND	
N-PROPYLBENZENE	5	5														2.3	ND	ND	37	ND	86	150	170	160	200	
N-BUTYLBENZENE	5	5														1.7	ND	ND	2.2 J	ND	4.1 J	10J	12 J	9.7	14 J	
P-ISOPROPYLTOLUENE																ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	
1,4-DIETHYLBENZENE																ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	

Notes:

- Not Sampled
- 1) Blank space = analyte concentration not reported
- 2) BCP MW-2 was dry and not sampled
- 3) For the March 11, 2015 monitoring event well MW-1, MW-5, MW-6 and MW-7 were dry or not enough water was inside the well for a representative sample.
- 4) WG = groundwater

**Table 3-2 Groundwater Analytical Results
Summary of Detected Compounds
Former Mobil Station 99-MST 979 Main Street (1001 Main Street) Brownfield Cleanup**

Sample Name	MW-5	MW-5	MW-5	MW-5	MW-5	MW-5	MW-5	MW-5	MW-5	MW-5	MW-5	MW-5	MW-5	MW-5	MW-5	MW-5	MW-5	MW-5	MW-5	MW-5	MW-5	MW-5	MW-5	MW-5		
Date Collected	9/20/2013	3/19/2014	5/22/2014	3/11/2015	6/17/2015	8/3/2015	12/15/2015	1/27/2016	3/22/2016	6/3/2016	10/25/2016	12/8/2016	1/20/2017	5/17/2017	7/5/2017	11/2/2017	8/16/2018	11/29/2018	7/30/2019	12/12/2019	3/31/2020	11/25/2020	5/14/2021	12/14/2021		
Matrix	WG	WG	WG	WG	WG	WG	WG	WG	WG	WG	WG	WG	WG	WG	WG	WG	WG	WG	WG	WG	WG	WG	WG	WG		
Unit	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L		
NYSDEC Ambient Water Quality Standards & Guidance Values																										
Volatile Organic Compound	Surface Water	Groundwater																								
1,2-DICHLOROBENZENE	3	3	ND	ND	ND																					
1,2-DICHLOROETHANE	0.6	0.6	ND	ND	ND																					
1,2-DICHLOROPROPANE	1	1	ND	ND	ND																					
1,3-DICHLOROBENZENE	3	3	ND	ND	ND																					
2-HEXANONE	50	50	11	ND	ND		ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	2.7 J	ND	ND	ND	ND	
ACETONE	50	50	ND	520	ND		ND	ND	ND	ND	ND	ND	ND	ND	ND	15.3	ND	41	69 J	44	97 J	ND	43 J	45 J	ND	
BENZENE	1	1	5,600	4,800	4,900		3,700	4,100	1,800	1,800	1,700	1,600	899	949	682	428	574	283	86	26	3.3	8.9 J	5.8 J	3.4 J	5.8 J	ND
DIBROMOCHLOROMETHANE	50	50	ND	ND	ND		ND		ND		ND		ND		ND		ND		ND		ND	ND	ND	ND	ND	
DICHLORODIFLUOROMETHANE	5	5	ND	ND	ND		ND		ND		ND		ND		ND		ND		ND		ND	ND	ND	ND	ND	
ETHYLBENZENE	5	5	1,900	1,600	1,600		2,800	2,600	1,600	1,900	2,200	2,200	1,490	1,450	2,070	584	534	1,660	1,500	810	520 E	1200	1,700	1,700	770	1800
ISOPROPYLBENZENE (CUMENE)	5	5	28	29	ND		ND	ND	ND	ND	ND	ND	ND	ND	ND	13.6	ND	20	16 J	23	24 J	30 J	33 J	13 J	33 J	
METHYL ETHYL KETONE (2-BUTANONE)	50	50	10	350	ND		ND	ND	ND	ND	ND	ND	ND	ND	ND	5.1	ND	ND		ND	ND	ND	ND	ND	ND	
METHYLENE CHLORIDE	5	5	ND	ND	ND		ND	ND	ND	ND	77	96	ND	ND	ND	ND	ND									
TOLUENE	5	5	170	220	310		290	290	70	80	88	77	68.5	84.9	86.6	ND	36.2	82.0	66.0	39 J	38.0	42 J	49 J	48 J	16 J	44 J
TRICHLOROETHYLENE (TCE)	5	5	ND	ND	ND		ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	22 J	ND	ND	ND	ND	ND
1,1,2-TRICHLOROETHANE	1	1	ND	ND	ND		ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
XYLENES, TOTAL	5	5	10,000	6,800	8,300		9,100	10,000	2,600	3,100	3,300	2,800	2,271.3	2,152.2	3,394.7	3,000.7	4,520.0	5,610.0	5,461.0	4,066.0	1879 E	3373	5,086.0	4,275	1,534.0	5,076
NAPHTHALENE	10	10	ND	ND	ND		ND	ND	ND	ND	ND	ND	ND	ND	ND	730	1,030	620	1,100		1100	940	820	430	1000	
No Standard																										
CARBON DISULFIDE	ND	ND	ND				ND	ND	ND	ND	ND	ND	ND	ND	ND	2.1	ND	ND		1.2 J	ND	ND	ND	ND	ND	
CYCLOHEXANE	230	340	240				430	260	230	250	280	430	198	148	257	ND	257	238	150	130 J	140	220	250	240	130	330
METHYL ISOBUTYL KETONE	23	ND	ND				ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	3.0 J	ND	ND	ND	ND	ND	
METHYLCYCLOHEXANE	100	170	150				190	130	92	100	100	140	67.5	58.4	92.8	49	92.8	106	70	82 J	65	96	110 J	110 J	60 J	120 J
Total VOCs	18,072	14,829	15,500	-			16,510	17,380	6,392	7,230	7,745	7,343	4,994	4,843	6,583	4,062	7,780	9,009	8,014	4,938	2,718.72	6,160.9	8,170.80	7,272.4	2,864.00	8,403.0
Total BTEX	17,670	13,420	15,110	-			15,890	16,990	6,070	6,880	7,288	6,677	4,729	4,636	6,233	4,013	5,664	7,635	7,113	4,941	2,440.30	4,623.90	6,840.80	6,026.40	2,325.80	6,920.00
Non-Standard VOC List																										
1,3,5-TRIMETHYLBENZENE	5	5														823	ND	ND	630	ND	480	520	400	99	430	
1,2,4,5-TETRAMETHYLBENZENE	5	5														135	ND	ND		ND	ND	ND	ND	ND	ND	
1,2,4-TRIMETHYLBENZENE	5	5														2,280	2,490	2,400	2,300	ND	2,200	2,500	2,500	1,200	2,500	
SEC-BUTYLBENZENE	5	5														3.2	ND	ND		ND	ND	ND	ND	ND	ND	
N-PROPYLBENZENE	5	5														34.8	ND	110	69	ND	110	140	150	64	170	
N-BUTYLBENZENE	5	5														43.3	ND	ND		ND	4.1 J	ND	ND	ND	ND	
P-ISOPROPYLTOLUENE																5.7	ND	ND		ND	ND	ND	ND	ND	ND	
1,4-DIETHYLBENZENE																347	ND	ND		ND	ND	ND	ND	ND	ND	

- Notes:
- Not Sampled
 - 1) Blank space = analyte concentration not reported
 - 2) BCP MW-2 was dry and not sampled
 - 3) For the March 11, 2015 monitoring event well MW-1, MW-5, MW-6 and MW-7 were dry or not enough water was inside the well for a representative sample.
 - 4) WG = groundwater

**Table 3-2 Groundwater Analytical Results
Summary of Detected Compounds
Former Mobil Station 99-MST 979 Main Street (1001 Main Street) Brownfield Cleanup**

Sample Name	MW-6	MW-6	MW-6	MW-6	MW-6	MW-6	MW-6	MW-6	MW-6	MW-6	MW-6	MW-6	MW-6	MW-6	MW-6	MW-6	MW-6	MW-6	MW-6	MW-6	MW-6	MW-6	MW-6	MW-6	
Date Collected	9/20/2013	3/19/2014	5/22/2014	3/11/2015	6/17/2015	8/3/2015	12/14/2015	1/27/2016	3/22/2016	6/3/2016	10/25/2016	12/8/2016	1/20/2017	5/17/2017	7/5/2017	11/2/2017	8/16/2018	11/29/2018	7/30/2019	12/12/2019	3/31/2020	11/25/2020	5/14/2021	12/14/2021	
Matrix	WG	WG	WG	WG	WG	WG	WG	WG	WG	WG	WG	WG	WG	WG	WG	WG	WG	WG	WG	WG	WG	WG	WG	WG	
Unit	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	
NYSDEC Ambient Water Quality Standards & Guidance Values																									
Volatile Organic Compound	Surface Water	Groundwater																							
1,2-DICHLOROBENZENE	3	3	ND	ND	ND														ND	ND	ND	ND	ND	ND	ND
1,2-DICHLOROETHANE	0.6	0.6	ND	ND	ND														ND	ND	ND	ND	ND	ND	ND
1,2-DICHLOROPROPANE	1	1	ND	ND	ND														ND	20 J	ND	ND	ND	ND	ND
1,3-DICHLOROBENZENE	3	3	ND	ND	ND														ND	ND	ND	ND	ND	ND	ND
2-HEXANONE	50	50	ND	ND	ND														190	ND	ND	ND	ND	ND	ND
ACETONE	50	50	ND	ND	ND														480	340	ND	ND	ND	ND	ND
BENZENE	1	1	190	33	16														470	890	250	230	200	120	302
DIBROMOCHLOROMETHANE	50	50	ND	ND	ND														ND	ND	ND	ND	ND	ND	ND
DICHLORODIFLUOROMETHANE	5	5	ND	ND	ND														ND	ND	ND	ND	ND	ND	ND
ETHYLBENZENE	5	5	130	20	31														36	210	22	44	67	50	163
ISOPROPYLBENZENE (CUMENE)	5	5	4.4	ND	1.9 J														ND	ND	ND	ND	ND	ND	ND
METHYL ETHYL KETONE (2-BUTANONE)	50	50	ND	ND	ND														110	ND	ND	ND	ND	ND	ND
METHYLENE CHLORIDE	5	5	ND	ND	ND														ND	ND	ND	ND	ND	ND	ND
TOLUENE	5	5	810	42	79														1,000	1,900	85	120	78	120	130
TRICHLOROETHYLENE (TCE)	5	5	ND	ND	ND														ND	ND	ND	ND	ND	ND	ND
1,1,2-TRICHLOROETHANE	1	1	ND	ND	ND														ND	ND	ND	ND	ND	ND	ND
XYLENES, TOTAL	5	5	750	85	150														740	1,100	140	190	130	210	393
NAPHTHALENE	10	10	ND	ND	ND														ND	ND	ND	ND	ND	ND	ND
No Standard																									
CARBON DISULFIDE			ND	ND	ND														ND	ND	ND	ND	ND	ND	ND
CYCLOHEXANE	68	ND	130																270	41	62	110	110	91	81.5
METHYL ISOBUTYL KETONE			ND	ND	ND														ND	ND	ND	ND	ND	ND	ND
METHYLCYCLOHEXANE	46	16	18																170	27	24	21	10	24	32.2
Total VOCs	1,998.4	196	424	-	3,466	4,508	583	715	595	615	1,101	983	1,212	661	925	5,526	35	17.32	0.6	44.5	1.6	43.6	5	0	
Total BTEX	1,880	180	276	-	2,246	4,100	497	584	475	500	988	952	1,175	626	677	5,398	3	4.52	-	21.10	0	21.70	0	0	
Non-Standard VOC List																									
1,3,5-TRIMETHYLBENZENE	5	5																							
1,2,4,5-TETRAMETHYLBENZENE	5	5																							
1,2,4-TRIMETHYLBENZENE	5	5																							
SEC-BUTYLBENZENE	5	5																							
N-PROPYLBENZENE	5	5																							
N-BUTYLBENZENE	5	5																							
P-ISOPROPYLTOLUENE																									
1,4-DIETHYLBENZENE																									

Notes:


- Not Sampled
- 1) Blank space = analyte concentration not reported
- 2) BCP MW-2 was dry and not sampled
- 3) For the March 11, 2015 monitoring event well MW-1, MW-5, MW-6 and MW-7 were dry or not enough water was inside the well for a representative sample.
- 4) WG = groundwater

**Table 3-2 Groundwater Analytical Results
Summary of Detected Compounds
Former Mobil Station 99-MST 979 Main Street (1001 Main Street) Brownfield Cleanup**

Sample Name	MW-7	MW-7	MW-7	MW-7	MW-7	MW-7	MW-7	MW-7	MW-7	MW-7	MW-7	MW-7	MW-7	MW-7	MW-7	MW-7	MW-7	MW-7	MW-7	MW-7	MW-7	MW-7	MW-7	
Date Collected	9/20/2013	3/19/2014	5/22/2014	3/11/2015	6/17/2015	8/3/2015	12/15/2015	3/22/2016	6/3/2016	10/25/2016	12/8/2016	1/20/2017	5/17/2017	7/5/2017	11/2/2017	8/16/2018	11/29/2018	7/30/2019	12/12/2019	3/31/2020	11/25/2020	5/14/2021	12/14/2021	
Matrix	WG	WG	WG	WG	WG	WG	WG	WG	WG	WG	WG	WG	WG	WG	WG	WG	WG	WG	WG	WG	WG	WG	WG	
Unit	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	
NYSDEC Ambient Water Quality Standards & Guidance Values																								
Volatile Organic Compound	Surface Water	Groundwater																						
1,2-DICHLOROETHANE	3	3	ND	ND	ND														ND	ND	ND	ND	ND	ND
1,2-DICHLOROBENZENE	0.6	0.6	ND	ND	ND														ND	ND	ND	ND	ND	ND
1,2-DICHLOROPROPANE	1	1	ND	ND	ND														ND	ND	ND	ND	ND	ND
1,3-DICHLOROBENZENE	3	3	ND	ND	ND														ND	ND	ND	ND	ND	ND
2-HEXANONE	50	50	ND	ND	4.8			ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	
ACETONE	50	50	ND	3	ND			ND	ND	ND	ND	ND	ND	ND	ND	ND	1.5	ND	4.2 J	ND	ND	ND	ND	
BENZENE	1	1	0.51	8.8	14			ND	ND	ND	ND	ND	ND	ND	ND	2.3	2.81	1.8	.18 J	.77	.17 J	ND	ND	
DIBROMOCHLOROMETHANE	50	50	ND	ND	ND			ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	
DICHLORODIFLUOROMETHANE	5	5	ND	ND	ND			ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	
ETHYLBENZENE	5	5	ND	ND	3			ND	ND	ND	ND	ND	ND	ND	ND	0	ND	ND	ND	ND	ND	ND	ND	
ISOPROPYLBENZENE (CUMENE)	5	5	ND	ND	ND			ND	ND	ND	ND	ND	ND	ND	ND	0.45	ND	ND	ND	ND	ND	ND	ND	
METHYL ETHYL KETONE (2-BUTANONE)	50	50	ND	ND	ND			ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	
METHYLENE CHLORIDE	5	5	ND	ND	ND			ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	
TOLUENE	5	5	ND	0.56	4.7			ND	ND	ND	ND	ND	ND	ND	ND	1.1	ND	ND	ND	ND	ND	ND	ND	
TRICHLOROETHYLENE (TCE)	5	5	ND	ND	ND			ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	
1,1,2-TRICHLOROETHANE	1	1																	ND	ND	ND	ND	ND	ND
XYLENES, TOTAL	5	5	0.96	4.8	94			ND	ND	ND	0.99 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	
NAPHTHALENE	10	10															1.50	.86 J	ND	ND	ND	ND	1 J	
No Standard																								
CARBON DISULFIDE			ND	ND	0.97			ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	
CYCLOHEXANE			ND	4.3	9.6			ND	ND	0.71	ND	ND	ND	ND	ND	0.99	0.66	ND	ND	ND	ND	ND	ND	
METHYL ISOBUTYL KETONE			ND	ND	ND			ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	
METHYLCYCLOHEXANE			ND	1.7	5.1			0.18	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	
Total VOCs			1.47	23.16	136.17			0.18			0.71					2.30	5.35	3.66	1.04	4.97	0.17	0	0	
Total BTEX			0.51	14.16	115.7											2.3	3.9	1.8	0.18	0.77	0.17	0	0	
Non-Standard VOC List																								
1,3,5-TRIMETHYLBENZENE	5	5														ND	ND	3.2		3.2	ND	ND	ND	
1,2,4,5-TETRAMETHYLBENZENE	5	5														ND	ND	ND	ND	ND	ND	ND	ND	
1,2,4-TRIMETHYLBENZENE	5	5														ND	ND	ND	ND	ND	ND	ND	ND	
SEC-BUTYLBENZENE	5	5														ND	ND	ND	ND	ND	ND	ND	ND	
N-PROPYLBENZENE	5	5														ND	ND	ND	ND	ND	ND	ND	ND	
N-BUTYLBENZENE	5	5														ND	ND	ND	ND	ND	ND	ND	ND	
P-ISOPROPYLTOLUENE																ND	ND	ND	ND	ND	ND	ND	ND	
1,4-DIETHYLBENZENE																ND	ND	ND	ND	ND	ND	ND	ND	

- Notes:
- Not Sampled
 - 1) Blank space = analyte concentration not reported
 - 2) BCP MW-2 was dry and not sampled
 - 3) For the March 11, 2015 monitoring event well MW-1, MW-5, MW-6 and MW-7 were dry or not enough water was inside the well for a representative sample.
 - 4) WG = groundwater

FIGURES



Legend


- Parcel Boundary
- Brownfield Cleanup Program Boundary

Property Note


1) The BCP Project Area ("Site") includes the entire western parcel [1001 Main Street (formerly 979 Main Street)] and extends approximately 40 feet east onto the adjacent eastern parcel (818 Ellicott Street). Total acreage of the BCP Project Site is 1.72 acres.

Notes

- 1) Groundwater elevation benchmark.
- 2) Coordinate System: NAD 1983 StatePlane NY West FIPS 3103
Projection: Transverse Mercator
Datum: North American 1983
Units: Foot US



C&S COMPANIES
 C&S Engineers, Inc.
 141 Elm Street
 Buffalo, New York 14203
 Phone: 716-847-1630
 Fax: 716-847-1454
 www.cscos.com




**FORMER MOBIL STATION 99-MST
 979 MAIN ST (1001 MAIN ST)
 BROWNFIELD CLEANUP PROGRAM
 BUFFALO, NEW YORK**

MARK	DATE	DESCRIPTION
REVISIONS		
PROJECT NO: K11.002.001		
DATE: May 4, 2016		
DRAWN BY: C. MARTIN		
DESIGNED BY: C. MARTIN		
CHECKED BY:		
NO ALTERATION PERMITTED HEREON EXCEPT AS PROVIDED UNDER SECTION 7209 SUBDIVISION 2 OF THE NEW YORK EDUCATION LAW		

SITE
LOCATION

FIGURE 1

Path: F:\Project\K11-Kaleida Health\K11.002.001 - MOB Brownfield Cleanup Program\Environmental-study\CADD-GIS\Projects\BCP_GW_WELL_LOCATIONS.mxd



Legend

- Property Lines
- Brownfield Cleanup Program Boundary
- Groundwater Monitoring Well Location

Property Note

1) The BCP Project Area ("Site") includes the entire western parcel [1001 Main Street (formerly 979 Main Street)] and extends approximately 40 feet east onto the adjacent eastern parcel (818 Ellicott Street). Total acreage of the BCP Project Site is 1.72 acres.


Notes

1) Coordinate System: NAD 1983 StatePlane NY West FIPS 3103
 Projection: Transverse Mercator
 Datum: North American 1983
 Units: Foot US

2) Survey data from McIntosh & McIntosh P.C. "Topographical Map of Part of Lot-29, TWP.-11, R.-8, Holland Purchase" Job No. 7669-B(2) September 24, 2008.



C&S Engineers, Inc.
 141 Elm Street
 Buffalo, New York 14203
 Phone: 716-847-1630
 Fax: 716-847-1454
 www.cscos.com




**FORMER MOBIL STATION 99-MST
 979 MAIN ST (1001 MAIN ST)
 BROWNFIELD CLEANUP PROGRAM
 BUFFALO, NEW YORK**

MARK	DATE	DESCRIPTION
REVISIONS		
PROJECT NO: K11.002.001		
DATE: JUNE 15, 2016		
DRAWN BY: C. MARTIN		
DESIGNED BY: C. MARTIN		
CHECKED BY: D. RIKER		

NO ALTERATION PERMITTED HEREON EXCEPT AS PROVIDED UNDER SECTION 7209 SUBDIVISION 2 OF THE NEW YORK EDUCATION LAW

OFFSITE & ONSITE
 GROUNDWATER
 WELLS

FIGURE 2



Legend

- Property Lines
- Brownfield Cleanup Program Boundary
- Area of Deep Excavation / Flowable Fill Area
- Groundwater Monitoring Well Location

Label Note

- 32.2' ← Depth to Water (ft) from ground surface
- 631.265' ← Groundwater Elevation below Benchmark (feet)

Property Note

1) The BCP Project Area ("Site") includes the entire western parcel [1001 Main Street (formerly 979 Main Street)] and extends approximately 40 feet east onto the adjacent eastern parcel (818 Ellicott Street). Total acreage of the BCP Project Site is 1.72 acres.


Notes

1) Coordinate System: NAD 1983 StatePlane NY West FIPS 3103
 Projection: Transverse Mercator
 Datum: North American 1983
 Units: Foot US

2) Survey data from McIntosh & McIntosh P.C. "Topographical Map of Part of Lot-29, TWP.-11, R.-8, Holland Purchase" Job No. 7669-B(2) September 24, 2008.



C&S Companies
 C&S Engineers, Inc.
 141 Elm Street
 Buffalo, New York 14203
 Phone: 716-847-1630
 Fax: 716-847-1454
 www.cscos.com



**FORMER MOBIL STATION 99-MST
 979 MAIN ST (1001 MAIN ST)
 BROWNFIELD CLEANUP PROGRAM
 BUFFALO, NEW YORK**


MARK	DATE	DESCRIPTION
REVISIONS		
PROJECT NO: K11.002.001		
DATE: December 2021		
DRAWN BY: R. BACKERT		
DESIGNED BY: C. MARTIN		
CHECKED BY: D. RIKER		

NO ALTERATION PERMITTED HEREON EXCEPT AS PROVIDED UNDER SECTION 7209 SUBDIVISION 2 OF THE NEW YORK EDUCATION LAW

GROUNDWATER
 CONTOUR

FIGURE 3

GROUNDWATER TREATMENT MONITORING - TOTAL BTEX



APPENDICES

APPENDIX A
LABORATORY ANALYTICAL RESULTS



ANALYTICAL REPORT

Lab Number:	L2168683
Client:	C&S Companies 141 Elm Street, Suite 100 Buffalo, NY 14203
ATTN:	Cody Martin
Phone:	(716) 847-1630
Project Name:	CONVENTUS
Project Number:	1186
Report Date:	12/29/21

The original project report/data package is held by Alpha Analytical. This report/data package is paginated and should be reproduced only in its entirety. Alpha Analytical holds no responsibility for results and/or data that are not consistent with the original.

Certifications & Approvals: MA (M-MA086), NH NELAP (2064), CT (PH-0574), IL (200077), ME (MA00086), MD (348), NJ (MA935), NY (11148), NC (25700/666), PA (68-03671), RI (LAO00065), TX (T104704476), VT (VT-0935), VA (460195), USDA (Permit #P330-17-00196).

Eight Walkup Drive, Westborough, MA 01581-1019
508-898-9220 (Fax) 508-898-9193 800-624-9220 - www.alphalab.com



Project Name: CONVENTUS
Project Number: 1186

Lab Number: L2168683
Report Date: 12/29/21

Alpha Sample ID	Client ID	Matrix	Sample Location	Collection Date/Time	Receive Date
L2168683-01	BCP-MW01	WATER	CONVENTUS 1 MAIN ST. BUFFALO NY	12/14/21 09:50	12/14/21
L2168683-02	BCP-MW07	WATER	CONVENTUS 1 MAIN ST. BUFFALO NY	12/14/21 10:40	12/14/21
L2168683-03	BCP-MW04	WATER	CONVENTUS 1 MAIN ST. BUFFALO NY	12/14/21 11:35	12/14/21
L2168683-04	BCP-MW03	WATER	CONVENTUS 1 MAIN ST. BUFFALO NY	12/14/21 12:00	12/14/21
L2168683-05	BCP-MW06	WATER	CONVENTUS 1 MAIN ST. BUFFALO NY	12/14/21 12:35	12/14/21
L2168683-06	BCP-MW05	WATER	CONVENTUS 1 MAIN ST. BUFFALO NY	12/14/21 13:10	12/14/21
L2168683-07	TRIP BLANK	WATER	CONVENTUS 1 MAIN ST. BUFFALO NY	12/14/21 00:00	12/14/21

Project Name: CONVENTUS
Project Number: 1186

Lab Number: L2168683
Report Date: 12/29/21

Case Narrative

The samples were received in accordance with the Chain of Custody and no significant deviations were encountered during the preparation or analysis unless otherwise noted. Sample Receipt, Container Information, and the Chain of Custody are located at the back of the report.

Results contained within this report relate only to the samples submitted under this Alpha Lab Number and meet NELAP requirements for all NELAP accredited parameters unless otherwise noted in the following narrative. The data presented in this report is organized by parameter (i.e. VOC, SVOC, etc.). Sample specific Quality Control data (i.e. Surrogate Spike Recovery) is reported at the end of the target analyte list for each individual sample, followed by the Laboratory Batch Quality Control at the end of each parameter. Tentatively Identified Compounds (TICs), if requested, are reported for compounds identified to be present and are not part of the method/program Target Compound List, even if only a subset of the TCL are being reported. If a sample was re-analyzed or re-extracted due to a required quality control corrective action and if both sets of data are reported, the Laboratory ID of the re-analysis or re-extraction is designated with an "R" or "RE", respectively.

When multiple Batch Quality Control elements are reported (e.g. more than one LCS), the associated samples for each element are noted in the grey shaded header line of each data table. Any Laboratory Batch, Sample Specific % recovery or RPD value that is outside the listed Acceptance Criteria is bolded in the report. In reference to questions H (CAM) or 4 (RCP) when "NO" is checked, the performance criteria for CAM and RCP methods allow for some quality control failures to occur and still be within method compliance. In these instances, the specific failure is not narrated but noted in the associated QC Outlier Summary Report, located directly after the Case Narrative. QC information is also incorporated in the Data Usability Assessment table (Format 11) of our Data Merger tool, where it can be reviewed in conjunction with the sample result, associated regulatory criteria and any associated data usability implications.

Soil/sediments, solids and tissues are reported on a dry weight basis unless otherwise noted. Definitions of all data qualifiers and acronyms used in this report are provided in the Glossary located at the back of the report.

HOLD POLICY - For samples submitted on hold, Alpha's policy is to hold samples (with the exception of Air canisters) free of charge for 21 calendar days from the date the project is completed. After 21 calendar days, we will dispose of all samples submitted including those put on hold unless you have contacted your Alpha Project Manager and made arrangements for Alpha to continue to hold the samples. Air canisters will be disposed after 3 business days from the date the project is completed.

Please contact Project Management at 800-624-9220 with any questions.

Project Name: CONVENTUS
Project Number: 1186

Lab Number: L2168683
Report Date: 12/29/21

Case Narrative (continued)

Report Submission

All non-detect (ND) or estimated concentrations (J-qualified) have been quantitated to the limit noted in the MDL column.

Volatile Organics

L2168683-05 and -06D: The sample was received in the proper acid-preserved containers; however, upon analysis, the pH was determined to be greater than 2, and thus the method required holding time was exceeded.

I, the undersigned, attest under the pains and penalties of perjury that, to the best of my knowledge and belief and based upon my personal inquiry of those responsible for providing the information contained in this analytical report, such information is accurate and complete. This certificate of analysis is not complete unless this page accompanies any and all pages of this report.

Authorized Signature:

 Caitlin Walukevich

Title: Technical Director/Representative

Date: 12/29/21

ORGANICS

VOLATILES

Project Name: CONVENTUS**Lab Number:** L2168683**Project Number:** 1186**Report Date:** 12/29/21**SAMPLE RESULTS**

Lab ID: L2168683-01
 Client ID: BCP-MW01
 Sample Location: CONVENTUS 1 MAIN ST. BUFFALO NY

Date Collected: 12/14/21 09:50
 Date Received: 12/14/21
 Field Prep: Not Specified

Sample Depth:

Matrix: Water
 Analytical Method: 1,8260C
 Analytical Date: 12/24/21 09:49
 Analyst: PD

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
Volatile Organics by GC/MS - Westborough Lab						
Methylene chloride	ND		ug/l	2.5	0.70	1
1,1-Dichloroethane	ND		ug/l	2.5	0.70	1
Chloroform	ND		ug/l	2.5	0.70	1
Carbon tetrachloride	ND		ug/l	0.50	0.13	1
1,2-Dichloropropane	ND		ug/l	1.0	0.14	1
Dibromochloromethane	ND		ug/l	0.50	0.15	1
1,1,2-Trichloroethane	ND		ug/l	1.5	0.50	1
Tetrachloroethene	ND		ug/l	0.50	0.18	1
Chlorobenzene	ND		ug/l	2.5	0.70	1
Trichlorofluoromethane	ND		ug/l	2.5	0.70	1
1,2-Dichloroethane	ND		ug/l	0.50	0.13	1
1,1,1-Trichloroethane	ND		ug/l	2.5	0.70	1
Bromodichloromethane	ND		ug/l	0.50	0.19	1
trans-1,3-Dichloropropene	ND		ug/l	0.50	0.16	1
cis-1,3-Dichloropropene	ND		ug/l	0.50	0.14	1
Bromoform	ND		ug/l	2.0	0.65	1
1,1,2,2-Tetrachloroethane	ND		ug/l	0.50	0.17	1
Benzene	ND		ug/l	0.50	0.16	1
Toluene	ND		ug/l	2.5	0.70	1
Ethylbenzene	ND		ug/l	2.5	0.70	1
Chloromethane	ND		ug/l	2.5	0.70	1
Bromomethane	ND		ug/l	2.5	0.70	1
Vinyl chloride	ND		ug/l	1.0	0.07	1
Chloroethane	ND		ug/l	2.5	0.70	1
1,1-Dichloroethene	ND		ug/l	0.50	0.17	1
trans-1,2-Dichloroethene	ND		ug/l	2.5	0.70	1
Trichloroethene	ND		ug/l	0.50	0.18	1
1,2-Dichlorobenzene	ND		ug/l	2.5	0.70	1

Project Name: CONVENTUS

Lab Number: L2168683

Project Number: 1186

Report Date: 12/29/21

SAMPLE RESULTS

Lab ID: L2168683-01

Date Collected: 12/14/21 09:50

Client ID: BCP-MW01

Date Received: 12/14/21

Sample Location: CONVENTUS 1 MAIN ST. BUFFALO NY

Field Prep: Not Specified

Sample Depth:

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
Volatile Organics by GC/MS - Westborough Lab						
1,3-Dichlorobenzene	ND		ug/l	2.5	0.70	1
1,4-Dichlorobenzene	ND		ug/l	2.5	0.70	1
Methyl tert butyl ether	ND		ug/l	2.5	0.70	1
p/m-Xylene	ND		ug/l	2.5	0.70	1
o-Xylene	ND		ug/l	2.5	0.70	1
cis-1,2-Dichloroethene	ND		ug/l	2.5	0.70	1
Styrene	ND		ug/l	2.5	0.70	1
Dichlorodifluoromethane	ND		ug/l	5.0	1.0	1
Acetone	ND		ug/l	5.0	1.5	1
Carbon disulfide	ND		ug/l	5.0	1.0	1
2-Butanone	ND		ug/l	5.0	1.9	1
4-Methyl-2-pentanone	ND		ug/l	5.0	1.0	1
2-Hexanone	ND		ug/l	5.0	1.0	1
1,2-Dibromoethane	ND		ug/l	2.0	0.65	1
n-Butylbenzene	ND		ug/l	2.5	0.70	1
sec-Butylbenzene	ND		ug/l	2.5	0.70	1
tert-Butylbenzene	ND		ug/l	2.5	0.70	1
1,2-Dibromo-3-chloropropane	ND		ug/l	2.5	0.70	1
Isopropylbenzene	ND		ug/l	2.5	0.70	1
p-Isopropyltoluene	ND		ug/l	2.5	0.70	1
Naphthalene	ND		ug/l	2.5	0.70	1
n-Propylbenzene	ND		ug/l	2.5	0.70	1
1,2,4-Trichlorobenzene	ND		ug/l	2.5	0.70	1
1,3,5-Trimethylbenzene	ND		ug/l	2.5	0.70	1
1,2,4-Trimethylbenzene	ND		ug/l	2.5	0.70	1
Methyl Acetate	ND		ug/l	2.0	0.23	1
Cyclohexane	ND		ug/l	10	0.27	1
Freon-113	ND		ug/l	2.5	0.70	1
Methyl cyclohexane	ND		ug/l	10	0.40	1

Surrogate	% Recovery	Qualifier	Acceptance Criteria
1,2-Dichloroethane-d4	113		70-130
Toluene-d8	100		70-130
4-Bromofluorobenzene	99		70-130
Dibromofluoromethane	112		70-130

Project Name: CONVENTUS**Lab Number:** L2168683**Project Number:** 1186**Report Date:** 12/29/21**SAMPLE RESULTS**

Lab ID: L2168683-02
 Client ID: BCP-MW07
 Sample Location: CONVENTUS 1 MAIN ST. BUFFALO NY

Date Collected: 12/14/21 10:40
 Date Received: 12/14/21
 Field Prep: Not Specified

Sample Depth:

Matrix: Water
 Analytical Method: 1,8260C
 Analytical Date: 12/24/21 10:12
 Analyst: PD

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
Volatile Organics by GC/MS - Westborough Lab						
Methylene chloride	ND		ug/l	2.5	0.70	1
1,1-Dichloroethane	ND		ug/l	2.5	0.70	1
Chloroform	ND		ug/l	2.5	0.70	1
Carbon tetrachloride	ND		ug/l	0.50	0.13	1
1,2-Dichloropropane	ND		ug/l	1.0	0.14	1
Dibromochloromethane	ND		ug/l	0.50	0.15	1
1,1,2-Trichloroethane	ND		ug/l	1.5	0.50	1
Tetrachloroethene	ND		ug/l	0.50	0.18	1
Chlorobenzene	ND		ug/l	2.5	0.70	1
Trichlorofluoromethane	ND		ug/l	2.5	0.70	1
1,2-Dichloroethane	ND		ug/l	0.50	0.13	1
1,1,1-Trichloroethane	ND		ug/l	2.5	0.70	1
Bromodichloromethane	ND		ug/l	0.50	0.19	1
trans-1,3-Dichloropropene	ND		ug/l	0.50	0.16	1
cis-1,3-Dichloropropene	ND		ug/l	0.50	0.14	1
Bromoform	ND		ug/l	2.0	0.65	1
1,1,2,2-Tetrachloroethane	ND		ug/l	0.50	0.17	1
Benzene	ND		ug/l	0.50	0.16	1
Toluene	ND		ug/l	2.5	0.70	1
Ethylbenzene	ND		ug/l	2.5	0.70	1
Chloromethane	ND		ug/l	2.5	0.70	1
Bromomethane	ND		ug/l	2.5	0.70	1
Vinyl chloride	ND		ug/l	1.0	0.07	1
Chloroethane	ND		ug/l	2.5	0.70	1
1,1-Dichloroethene	ND		ug/l	0.50	0.17	1
trans-1,2-Dichloroethene	ND		ug/l	2.5	0.70	1
Trichloroethene	ND		ug/l	0.50	0.18	1
1,2-Dichlorobenzene	ND		ug/l	2.5	0.70	1

Project Name: CONVENTUS

Lab Number: L2168683

Project Number: 1186

Report Date: 12/29/21

SAMPLE RESULTS

Lab ID: L2168683-02
 Client ID: BCP-MW07
 Sample Location: CONVENTUS 1 MAIN ST. BUFFALO NY

Date Collected: 12/14/21 10:40
 Date Received: 12/14/21
 Field Prep: Not Specified

Sample Depth:

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
Volatile Organics by GC/MS - Westborough Lab						
1,3-Dichlorobenzene	ND		ug/l	2.5	0.70	1
1,4-Dichlorobenzene	ND		ug/l	2.5	0.70	1
Methyl tert butyl ether	ND		ug/l	2.5	0.70	1
p/m-Xylene	ND		ug/l	2.5	0.70	1
o-Xylene	ND		ug/l	2.5	0.70	1
cis-1,2-Dichloroethene	ND		ug/l	2.5	0.70	1
Styrene	ND		ug/l	2.5	0.70	1
Dichlorodifluoromethane	ND		ug/l	5.0	1.0	1
Acetone	ND		ug/l	5.0	1.5	1
Carbon disulfide	ND		ug/l	5.0	1.0	1
2-Butanone	ND		ug/l	5.0	1.9	1
4-Methyl-2-pentanone	ND		ug/l	5.0	1.0	1
2-Hexanone	ND		ug/l	5.0	1.0	1
1,2-Dibromoethane	ND		ug/l	2.0	0.65	1
n-Butylbenzene	ND		ug/l	2.5	0.70	1
sec-Butylbenzene	ND		ug/l	2.5	0.70	1
tert-Butylbenzene	ND		ug/l	2.5	0.70	1
1,2-Dibromo-3-chloropropane	ND		ug/l	2.5	0.70	1
Isopropylbenzene	ND		ug/l	2.5	0.70	1
p-Isopropyltoluene	ND		ug/l	2.5	0.70	1
Naphthalene	ND		ug/l	2.5	0.70	1
n-Propylbenzene	ND		ug/l	2.5	0.70	1
1,2,4-Trichlorobenzene	ND		ug/l	2.5	0.70	1
1,3,5-Trimethylbenzene	ND		ug/l	2.5	0.70	1
1,2,4-Trimethylbenzene	ND		ug/l	2.5	0.70	1
Methyl Acetate	ND		ug/l	2.0	0.23	1
Cyclohexane	ND		ug/l	10	0.27	1
Freon-113	ND		ug/l	2.5	0.70	1
Methyl cyclohexane	ND		ug/l	10	0.40	1

Surrogate	% Recovery	Qualifier	Acceptance Criteria
1,2-Dichloroethane-d4	118		70-130
Toluene-d8	100		70-130
4-Bromofluorobenzene	97		70-130
Dibromofluoromethane	114		70-130

Project Name: CONVENTUS**Lab Number:** L2168683**Project Number:** 1186**Report Date:** 12/29/21**SAMPLE RESULTS**

Lab ID: L2168683-03 D
 Client ID: BCP-MW04
 Sample Location: CONVENTUS 1 MAIN ST. BUFFALO NY

Date Collected: 12/14/21 11:35
 Date Received: 12/14/21
 Field Prep: Not Specified

Sample Depth:

Matrix: Water
 Analytical Method: 1,8260C
 Analytical Date: 12/24/21 11:21
 Analyst: PD

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
Volatile Organics by GC/MS - Westborough Lab						
Methylene chloride	ND		ug/l	25	7.0	10
1,1-Dichloroethane	ND		ug/l	25	7.0	10
Chloroform	ND		ug/l	25	7.0	10
Carbon tetrachloride	ND		ug/l	5.0	1.3	10
1,2-Dichloropropane	ND		ug/l	10	1.4	10
Dibromochloromethane	ND		ug/l	5.0	1.5	10
1,1,2-Trichloroethane	ND		ug/l	15	5.0	10
Tetrachloroethene	ND		ug/l	5.0	1.8	10
Chlorobenzene	ND		ug/l	25	7.0	10
Trichlorofluoromethane	ND		ug/l	25	7.0	10
1,2-Dichloroethane	ND		ug/l	5.0	1.3	10
1,1,1-Trichloroethane	ND		ug/l	25	7.0	10
Bromodichloromethane	ND		ug/l	5.0	1.9	10
trans-1,3-Dichloropropene	ND		ug/l	5.0	1.6	10
cis-1,3-Dichloropropene	ND		ug/l	5.0	1.4	10
Bromoform	ND		ug/l	20	6.5	10
1,1,2,2-Tetrachloroethane	ND		ug/l	5.0	1.7	10
Benzene	5.0		ug/l	5.0	1.6	10
Toluene	64		ug/l	25	7.0	10
Ethylbenzene	1100		ug/l	25	7.0	10
Chloromethane	ND		ug/l	25	7.0	10
Bromomethane	ND		ug/l	25	7.0	10
Vinyl chloride	ND		ug/l	10	0.71	10
Chloroethane	ND		ug/l	25	7.0	10
1,1-Dichloroethene	ND		ug/l	5.0	1.7	10
trans-1,2-Dichloroethene	ND		ug/l	25	7.0	10
Trichloroethene	ND		ug/l	5.0	1.8	10
1,2-Dichlorobenzene	ND		ug/l	25	7.0	10

Project Name: CONVENTUS

Lab Number: L2168683

Project Number: 1186

Report Date: 12/29/21

SAMPLE RESULTS

Lab ID: L2168683-03 D
 Client ID: BCP-MW04
 Sample Location: CONVENTUS 1 MAIN ST. BUFFALO NY

Date Collected: 12/14/21 11:35
 Date Received: 12/14/21
 Field Prep: Not Specified

Sample Depth:

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
Volatile Organics by GC/MS - Westborough Lab						
1,3-Dichlorobenzene	ND		ug/l	25	7.0	10
1,4-Dichlorobenzene	ND		ug/l	25	7.0	10
Methyl tert butyl ether	ND		ug/l	25	7.0	10
p/m-Xylene	630		ug/l	25	7.0	10
o-Xylene	21	J	ug/l	25	7.0	10
cis-1,2-Dichloroethene	ND		ug/l	25	7.0	10
Styrene	ND		ug/l	25	7.0	10
Dichlorodifluoromethane	ND		ug/l	50	10.	10
Acetone	ND		ug/l	50	15.	10
Carbon disulfide	ND		ug/l	50	10.	10
2-Butanone	ND		ug/l	50	19.	10
4-Methyl-2-pentanone	ND		ug/l	50	10.	10
2-Hexanone	ND		ug/l	50	10.	10
1,2-Dibromoethane	ND		ug/l	20	6.5	10
n-Butylbenzene	14	J	ug/l	25	7.0	10
sec-Butylbenzene	ND		ug/l	25	7.0	10
tert-Butylbenzene	ND		ug/l	25	7.0	10
1,2-Dibromo-3-chloropropane	ND		ug/l	25	7.0	10
Isopropylbenzene	35		ug/l	25	7.0	10
p-Isopropyltoluene	ND		ug/l	25	7.0	10
Naphthalene	360		ug/l	25	7.0	10
n-Propylbenzene	200		ug/l	25	7.0	10
1,2,4-Trichlorobenzene	ND		ug/l	25	7.0	10
1,3,5-Trimethylbenzene	13	J	ug/l	25	7.0	10
1,2,4-Trimethylbenzene	1500		ug/l	25	7.0	10
Methyl Acetate	ND		ug/l	20	2.3	10
Cyclohexane	190		ug/l	100	2.7	10
Freon-113	ND		ug/l	25	7.0	10
Methyl cyclohexane	54	J	ug/l	100	4.0	10

Surrogate	% Recovery	Qualifier	Acceptance Criteria
1,2-Dichloroethane-d4	108		70-130
Toluene-d8	103		70-130
4-Bromofluorobenzene	98		70-130
Dibromofluoromethane	94		70-130

Project Name: CONVENTUS**Lab Number:** L2168683**Project Number:** 1186**Report Date:** 12/29/21**SAMPLE RESULTS**

Lab ID: L2168683-04
 Client ID: BCP-MW03
 Sample Location: CONVENTUS 1 MAIN ST. BUFFALO NY

Date Collected: 12/14/21 12:00
 Date Received: 12/14/21
 Field Prep: Not Specified

Sample Depth:

Matrix: Water
 Analytical Method: 1,8260C
 Analytical Date: 12/24/21 10:58
 Analyst: PD

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
Volatile Organics by GC/MS - Westborough Lab						
Methylene chloride	ND		ug/l	2.5	0.70	1
1,1-Dichloroethane	ND		ug/l	2.5	0.70	1
Chloroform	ND		ug/l	2.5	0.70	1
Carbon tetrachloride	ND		ug/l	0.50	0.13	1
1,2-Dichloropropane	ND		ug/l	1.0	0.14	1
Dibromochloromethane	ND		ug/l	0.50	0.15	1
1,1,2-Trichloroethane	ND		ug/l	1.5	0.50	1
Tetrachloroethene	ND		ug/l	0.50	0.18	1
Chlorobenzene	ND		ug/l	2.5	0.70	1
Trichlorofluoromethane	ND		ug/l	2.5	0.70	1
1,2-Dichloroethane	ND		ug/l	0.50	0.13	1
1,1,1-Trichloroethane	ND		ug/l	2.5	0.70	1
Bromodichloromethane	ND		ug/l	0.50	0.19	1
trans-1,3-Dichloropropene	ND		ug/l	0.50	0.16	1
cis-1,3-Dichloropropene	ND		ug/l	0.50	0.14	1
Bromoform	ND		ug/l	2.0	0.65	1
1,1,2,2-Tetrachloroethane	ND		ug/l	0.50	0.17	1
Benzene	0.49	J	ug/l	0.50	0.16	1
Toluene	4.8		ug/l	2.5	0.70	1
Ethylbenzene	42		ug/l	2.5	0.70	1
Chloromethane	ND		ug/l	2.5	0.70	1
Bromomethane	ND		ug/l	2.5	0.70	1
Vinyl chloride	ND		ug/l	1.0	0.07	1
Chloroethane	ND		ug/l	2.5	0.70	1
1,1-Dichloroethene	ND		ug/l	0.50	0.17	1
trans-1,2-Dichloroethene	ND		ug/l	2.5	0.70	1
Trichloroethene	ND		ug/l	0.50	0.18	1
1,2-Dichlorobenzene	ND		ug/l	2.5	0.70	1

Project Name: CONVENTUS

Lab Number: L2168683

Project Number: 1186

Report Date: 12/29/21

SAMPLE RESULTS

Lab ID: L2168683-04
 Client ID: BCP-MW03
 Sample Location: CONVENTUS 1 MAIN ST. BUFFALO NY

Date Collected: 12/14/21 12:00
 Date Received: 12/14/21
 Field Prep: Not Specified

Sample Depth:

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
Volatile Organics by GC/MS - Westborough Lab						
1,3-Dichlorobenzene	ND		ug/l	2.5	0.70	1
1,4-Dichlorobenzene	ND		ug/l	2.5	0.70	1
Methyl tert butyl ether	ND		ug/l	2.5	0.70	1
p/m-Xylene	77		ug/l	2.5	0.70	1
o-Xylene	2.2	J	ug/l	2.5	0.70	1
cis-1,2-Dichloroethene	ND		ug/l	2.5	0.70	1
Styrene	ND		ug/l	2.5	0.70	1
Dichlorodifluoromethane	ND		ug/l	5.0	1.0	1
Acetone	6.2		ug/l	5.0	1.5	1
Carbon disulfide	ND		ug/l	5.0	1.0	1
2-Butanone	ND		ug/l	5.0	1.9	1
4-Methyl-2-pentanone	ND		ug/l	5.0	1.0	1
2-Hexanone	ND		ug/l	5.0	1.0	1
1,2-Dibromoethane	ND		ug/l	2.0	0.65	1
n-Butylbenzene	ND		ug/l	2.5	0.70	1
sec-Butylbenzene	ND		ug/l	2.5	0.70	1
tert-Butylbenzene	ND		ug/l	2.5	0.70	1
1,2-Dibromo-3-chloropropane	ND		ug/l	2.5	0.70	1
Isopropylbenzene	ND		ug/l	2.5	0.70	1
p-Isopropyltoluene	ND		ug/l	2.5	0.70	1
Naphthalene	18		ug/l	2.5	0.70	1
n-Propylbenzene	2.3	J	ug/l	2.5	0.70	1
1,2,4-Trichlorobenzene	ND		ug/l	2.5	0.70	1
1,3,5-Trimethylbenzene	6.5		ug/l	2.5	0.70	1
1,2,4-Trimethylbenzene	68		ug/l	2.5	0.70	1
Methyl Acetate	ND		ug/l	2.0	0.23	1
Cyclohexane	16		ug/l	10	0.27	1
Freon-113	ND		ug/l	2.5	0.70	1
Methyl cyclohexane	8.2	J	ug/l	10	0.40	1

Surrogate	% Recovery	Qualifier	Acceptance Criteria
1,2-Dichloroethane-d4	108		70-130
Toluene-d8	104		70-130
4-Bromofluorobenzene	96		70-130
Dibromofluoromethane	98		70-130

Project Name: CONVENTUS**Lab Number:** L2168683**Project Number:** 1186**Report Date:** 12/29/21**SAMPLE RESULTS**

Lab ID: L2168683-05
 Client ID: BCP-MW06
 Sample Location: CONVENTUS 1 MAIN ST. BUFFALO NY

Date Collected: 12/14/21 12:35
 Date Received: 12/14/21
 Field Prep: Not Specified

Sample Depth:

Matrix: Water
 Analytical Method: 1,8260C
 Analytical Date: 12/24/21 10:35
 Analyst: PD

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
Volatile Organics by GC/MS - Westborough Lab						
Methylene chloride	ND		ug/l	2.5	0.70	1
1,1-Dichloroethane	ND		ug/l	2.5	0.70	1
Chloroform	ND		ug/l	2.5	0.70	1
Carbon tetrachloride	ND		ug/l	0.50	0.13	1
1,2-Dichloropropane	ND		ug/l	1.0	0.14	1
Dibromochloromethane	ND		ug/l	0.50	0.15	1
1,1,2-Trichloroethane	ND		ug/l	1.5	0.50	1
Tetrachloroethene	ND		ug/l	0.50	0.18	1
Chlorobenzene	ND		ug/l	2.5	0.70	1
Trichlorofluoromethane	ND		ug/l	2.5	0.70	1
1,2-Dichloroethane	ND		ug/l	0.50	0.13	1
1,1,1-Trichloroethane	ND		ug/l	2.5	0.70	1
Bromodichloromethane	ND		ug/l	0.50	0.19	1
trans-1,3-Dichloropropene	ND		ug/l	0.50	0.16	1
cis-1,3-Dichloropropene	ND		ug/l	0.50	0.14	1
Bromoform	ND		ug/l	2.0	0.65	1
1,1,2,2-Tetrachloroethane	ND		ug/l	0.50	0.17	1
Benzene	ND		ug/l	0.50	0.16	1
Toluene	ND		ug/l	2.5	0.70	1
Ethylbenzene	ND		ug/l	2.5	0.70	1
Chloromethane	ND		ug/l	2.5	0.70	1
Bromomethane	ND		ug/l	2.5	0.70	1
Vinyl chloride	ND		ug/l	1.0	0.07	1
Chloroethane	ND		ug/l	2.5	0.70	1
1,1-Dichloroethene	ND		ug/l	0.50	0.17	1
trans-1,2-Dichloroethene	ND		ug/l	2.5	0.70	1
Trichloroethene	ND		ug/l	0.50	0.18	1
1,2-Dichlorobenzene	ND		ug/l	2.5	0.70	1

Project Name: CONVENTUS

Lab Number: L2168683

Project Number: 1186

Report Date: 12/29/21

SAMPLE RESULTS

Lab ID: L2168683-05
 Client ID: BCP-MW06
 Sample Location: CONVENTUS 1 MAIN ST. BUFFALO NY

Date Collected: 12/14/21 12:35
 Date Received: 12/14/21
 Field Prep: Not Specified

Sample Depth:

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
Volatile Organics by GC/MS - Westborough Lab						
1,3-Dichlorobenzene	ND		ug/l	2.5	0.70	1
1,4-Dichlorobenzene	ND		ug/l	2.5	0.70	1
Methyl tert butyl ether	ND		ug/l	2.5	0.70	1
p/m-Xylene	ND		ug/l	2.5	0.70	1
o-Xylene	ND		ug/l	2.5	0.70	1
cis-1,2-Dichloroethene	ND		ug/l	2.5	0.70	1
Styrene	ND		ug/l	2.5	0.70	1
Dichlorodifluoromethane	ND		ug/l	5.0	1.0	1
Acetone	ND		ug/l	5.0	1.5	1
Carbon disulfide	ND		ug/l	5.0	1.0	1
2-Butanone	ND		ug/l	5.0	1.9	1
4-Methyl-2-pentanone	ND		ug/l	5.0	1.0	1
2-Hexanone	ND		ug/l	5.0	1.0	1
1,2-Dibromoethane	ND		ug/l	2.0	0.65	1
n-Butylbenzene	ND		ug/l	2.5	0.70	1
sec-Butylbenzene	ND		ug/l	2.5	0.70	1
tert-Butylbenzene	ND		ug/l	2.5	0.70	1
1,2-Dibromo-3-chloropropane	ND		ug/l	2.5	0.70	1
Isopropylbenzene	ND		ug/l	2.5	0.70	1
p-Isopropyltoluene	ND		ug/l	2.5	0.70	1
Naphthalene	ND		ug/l	2.5	0.70	1
n-Propylbenzene	ND		ug/l	2.5	0.70	1
1,2,4-Trichlorobenzene	ND		ug/l	2.5	0.70	1
1,3,5-Trimethylbenzene	ND		ug/l	2.5	0.70	1
1,2,4-Trimethylbenzene	ND		ug/l	2.5	0.70	1
Methyl Acetate	ND		ug/l	2.0	0.23	1
Cyclohexane	ND		ug/l	10	0.27	1
Freon-113	ND		ug/l	2.5	0.70	1
Methyl cyclohexane	ND		ug/l	10	0.40	1

Surrogate	% Recovery	Qualifier	Acceptance Criteria
1,2-Dichloroethane-d4	119		70-130
Toluene-d8	99		70-130
4-Bromofluorobenzene	95		70-130
Dibromofluoromethane	114		70-130

Project Name: CONVENTUS**Lab Number:** L2168683**Project Number:** 1186**Report Date:** 12/29/21**SAMPLE RESULTS**

Lab ID: L2168683-06 D
 Client ID: BCP-MW05
 Sample Location: CONVENTUS 1 MAIN ST. BUFFALO NY

Date Collected: 12/14/21 13:10
 Date Received: 12/14/21
 Field Prep: Not Specified

Sample Depth:

Matrix: Water
 Analytical Method: 1,8260C
 Analytical Date: 12/24/21 11:44
 Analyst: PD

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
Volatile Organics by GC/MS - Westborough Lab						
Methylene chloride	ND		ug/l	50	14.	20
1,1-Dichloroethane	ND		ug/l	50	14.	20
Chloroform	ND		ug/l	50	14.	20
Carbon tetrachloride	ND		ug/l	10	2.7	20
1,2-Dichloropropane	ND		ug/l	20	2.7	20
Dibromochloromethane	ND		ug/l	10	3.0	20
1,1,2-Trichloroethane	ND		ug/l	30	10.	20
Tetrachloroethene	ND		ug/l	10	3.6	20
Chlorobenzene	ND		ug/l	50	14.	20
Trichlorofluoromethane	ND		ug/l	50	14.	20
1,2-Dichloroethane	ND		ug/l	10	2.6	20
1,1,1-Trichloroethane	ND		ug/l	50	14.	20
Bromodichloromethane	ND		ug/l	10	3.8	20
trans-1,3-Dichloropropene	ND		ug/l	10	3.3	20
cis-1,3-Dichloropropene	ND		ug/l	10	2.9	20
Bromoform	ND		ug/l	40	13.	20
1,1,2,2-Tetrachloroethane	ND		ug/l	10	3.3	20
Benzene	ND		ug/l	10	3.2	20
Toluene	44	J	ug/l	50	14.	20
Ethylbenzene	1800		ug/l	50	14.	20
Chloromethane	ND		ug/l	50	14.	20
Bromomethane	ND		ug/l	50	14.	20
Vinyl chloride	ND		ug/l	20	1.4	20
Chloroethane	ND		ug/l	50	14.	20
1,1-Dichloroethene	ND		ug/l	10	3.4	20
trans-1,2-Dichloroethene	ND		ug/l	50	14.	20
Trichloroethene	ND		ug/l	10	3.5	20
1,2-Dichlorobenzene	ND		ug/l	50	14.	20

Project Name: CONVENTUS

Lab Number: L2168683

Project Number: 1186

Report Date: 12/29/21

SAMPLE RESULTS

Lab ID: L2168683-06 D
 Client ID: BCP-MW05
 Sample Location: CONVENTUS 1 MAIN ST. BUFFALO NY

Date Collected: 12/14/21 13:10
 Date Received: 12/14/21
 Field Prep: Not Specified

Sample Depth:

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
Volatile Organics by GC/MS - Westborough Lab						
1,3-Dichlorobenzene	ND		ug/l	50	14.	20
1,4-Dichlorobenzene	ND		ug/l	50	14.	20
Methyl tert butyl ether	ND		ug/l	50	14.	20
p/m-Xylene	5000		ug/l	50	14.	20
o-Xylene	76		ug/l	50	14.	20
cis-1,2-Dichloroethene	ND		ug/l	50	14.	20
Styrene	ND		ug/l	50	14.	20
Dichlorodifluoromethane	ND		ug/l	100	20.	20
Acetone	ND		ug/l	100	29.	20
Carbon disulfide	ND		ug/l	100	20.	20
2-Butanone	ND		ug/l	100	39.	20
4-Methyl-2-pentanone	ND		ug/l	100	20.	20
2-Hexanone	ND		ug/l	100	20.	20
1,2-Dibromoethane	ND		ug/l	40	13.	20
n-Butylbenzene	ND		ug/l	50	14.	20
sec-Butylbenzene	ND		ug/l	50	14.	20
tert-Butylbenzene	ND		ug/l	50	14.	20
1,2-Dibromo-3-chloropropane	ND		ug/l	50	14.	20
Isopropylbenzene	33	J	ug/l	50	14.	20
p-Isopropyltoluene	ND		ug/l	50	14.	20
Naphthalene	1000		ug/l	50	14.	20
n-Propylbenzene	170		ug/l	50	14.	20
1,2,4-Trichlorobenzene	ND		ug/l	50	14.	20
1,3,5-Trimethylbenzene	430		ug/l	50	14.	20
1,2,4-Trimethylbenzene	2500		ug/l	50	14.	20
Methyl Acetate	ND		ug/l	40	4.7	20
Cyclohexane	330		ug/l	200	5.4	20
Freon-113	ND		ug/l	50	14.	20
Methyl cyclohexane	120	J	ug/l	200	7.9	20

Surrogate	% Recovery	Qualifier	Acceptance Criteria
1,2-Dichloroethane-d4	109		70-130
Toluene-d8	103		70-130
4-Bromofluorobenzene	97		70-130
Dibromofluoromethane	97		70-130

Project Name: CONVENTUS**Lab Number:** L2168683**Project Number:** 1186**Report Date:** 12/29/21**SAMPLE RESULTS**

Lab ID: L2168683-07
 Client ID: TRIP BLANK
 Sample Location: CONVENTUS 1 MAIN ST. BUFFALO NY

Date Collected: 12/14/21 00:00
 Date Received: 12/14/21
 Field Prep: Not Specified

Sample Depth:

Matrix: Water
 Analytical Method: 1,8260C
 Analytical Date: 12/24/21 09:26
 Analyst: PD

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
Volatile Organics by GC/MS - Westborough Lab						
Methylene chloride	ND		ug/l	2.5	0.70	1
1,1-Dichloroethane	ND		ug/l	2.5	0.70	1
Chloroform	ND		ug/l	2.5	0.70	1
Carbon tetrachloride	ND		ug/l	0.50	0.13	1
1,2-Dichloropropane	ND		ug/l	1.0	0.14	1
Dibromochloromethane	ND		ug/l	0.50	0.15	1
1,1,2-Trichloroethane	ND		ug/l	1.5	0.50	1
Tetrachloroethene	ND		ug/l	0.50	0.18	1
Chlorobenzene	ND		ug/l	2.5	0.70	1
Trichlorofluoromethane	ND		ug/l	2.5	0.70	1
1,2-Dichloroethane	ND		ug/l	0.50	0.13	1
1,1,1-Trichloroethane	ND		ug/l	2.5	0.70	1
Bromodichloromethane	ND		ug/l	0.50	0.19	1
trans-1,3-Dichloropropene	ND		ug/l	0.50	0.16	1
cis-1,3-Dichloropropene	ND		ug/l	0.50	0.14	1
Bromoform	ND		ug/l	2.0	0.65	1
1,1,2,2-Tetrachloroethane	ND		ug/l	0.50	0.17	1
Benzene	ND		ug/l	0.50	0.16	1
Toluene	ND		ug/l	2.5	0.70	1
Ethylbenzene	ND		ug/l	2.5	0.70	1
Chloromethane	ND		ug/l	2.5	0.70	1
Bromomethane	ND		ug/l	2.5	0.70	1
Vinyl chloride	ND		ug/l	1.0	0.07	1
Chloroethane	ND		ug/l	2.5	0.70	1
1,1-Dichloroethene	ND		ug/l	0.50	0.17	1
trans-1,2-Dichloroethene	ND		ug/l	2.5	0.70	1
Trichloroethene	ND		ug/l	0.50	0.18	1
1,2-Dichlorobenzene	ND		ug/l	2.5	0.70	1

Project Name: CONVENTUS

Lab Number: L2168683

Project Number: 1186

Report Date: 12/29/21

SAMPLE RESULTS

Lab ID: L2168683-07
 Client ID: TRIP BLANK
 Sample Location: CONVENTUS 1 MAIN ST. BUFFALO NY

Date Collected: 12/14/21 00:00
 Date Received: 12/14/21
 Field Prep: Not Specified

Sample Depth:

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
Volatile Organics by GC/MS - Westborough Lab						
1,3-Dichlorobenzene	ND		ug/l	2.5	0.70	1
1,4-Dichlorobenzene	ND		ug/l	2.5	0.70	1
Methyl tert butyl ether	ND		ug/l	2.5	0.70	1
p/m-Xylene	ND		ug/l	2.5	0.70	1
o-Xylene	ND		ug/l	2.5	0.70	1
cis-1,2-Dichloroethene	ND		ug/l	2.5	0.70	1
Styrene	ND		ug/l	2.5	0.70	1
Dichlorodifluoromethane	ND		ug/l	5.0	1.0	1
Acetone	ND		ug/l	5.0	1.5	1
Carbon disulfide	ND		ug/l	5.0	1.0	1
2-Butanone	ND		ug/l	5.0	1.9	1
4-Methyl-2-pentanone	ND		ug/l	5.0	1.0	1
2-Hexanone	ND		ug/l	5.0	1.0	1
1,2-Dibromoethane	ND		ug/l	2.0	0.65	1
n-Butylbenzene	ND		ug/l	2.5	0.70	1
sec-Butylbenzene	ND		ug/l	2.5	0.70	1
tert-Butylbenzene	ND		ug/l	2.5	0.70	1
1,2-Dibromo-3-chloropropane	ND		ug/l	2.5	0.70	1
Isopropylbenzene	ND		ug/l	2.5	0.70	1
p-Isopropyltoluene	ND		ug/l	2.5	0.70	1
Naphthalene	ND		ug/l	2.5	0.70	1
n-Propylbenzene	ND		ug/l	2.5	0.70	1
1,2,4-Trichlorobenzene	ND		ug/l	2.5	0.70	1
1,3,5-Trimethylbenzene	ND		ug/l	2.5	0.70	1
1,2,4-Trimethylbenzene	ND		ug/l	2.5	0.70	1
Methyl Acetate	ND		ug/l	2.0	0.23	1
Cyclohexane	ND		ug/l	10	0.27	1
Freon-113	ND		ug/l	2.5	0.70	1
Methyl cyclohexane	ND		ug/l	10	0.40	1

Surrogate	% Recovery	Qualifier	Acceptance Criteria
1,2-Dichloroethane-d4	111		70-130
Toluene-d8	100		70-130
4-Bromofluorobenzene	97		70-130
Dibromofluoromethane	112		70-130

Project Name: CONVENTUS
Project Number: 1186

Lab Number: L2168683
Report Date: 12/29/21

Method Blank Analysis
Batch Quality Control

Analytical Method: 1,8260C
Analytical Date: 12/24/21 09:03
Analyst: PD

Parameter	Result	Qualifier	Units	RL	MDL
Volatile Organics by GC/MS - Westborough Lab for sample(s): 01-07 Batch: WG1587543-5					
Methylene chloride	ND		ug/l	2.5	0.70
1,1-Dichloroethane	ND		ug/l	2.5	0.70
Chloroform	ND		ug/l	2.5	0.70
Carbon tetrachloride	ND		ug/l	0.50	0.13
1,2-Dichloropropane	ND		ug/l	1.0	0.14
Dibromochloromethane	ND		ug/l	0.50	0.15
1,1,2-Trichloroethane	ND		ug/l	1.5	0.50
Tetrachloroethene	ND		ug/l	0.50	0.18
Chlorobenzene	ND		ug/l	2.5	0.70
Trichlorofluoromethane	ND		ug/l	2.5	0.70
1,2-Dichloroethane	ND		ug/l	0.50	0.13
1,1,1-Trichloroethane	ND		ug/l	2.5	0.70
Bromodichloromethane	ND		ug/l	0.50	0.19
trans-1,3-Dichloropropene	ND		ug/l	0.50	0.16
cis-1,3-Dichloropropene	ND		ug/l	0.50	0.14
Bromoform	ND		ug/l	2.0	0.65
1,1,2,2-Tetrachloroethane	ND		ug/l	0.50	0.17
Benzene	ND		ug/l	0.50	0.16
Toluene	ND		ug/l	2.5	0.70
Ethylbenzene	ND		ug/l	2.5	0.70
Chloromethane	ND		ug/l	2.5	0.70
Bromomethane	ND		ug/l	2.5	0.70
Vinyl chloride	ND		ug/l	1.0	0.07
Chloroethane	ND		ug/l	2.5	0.70
1,1-Dichloroethene	ND		ug/l	0.50	0.17
trans-1,2-Dichloroethene	ND		ug/l	2.5	0.70
Trichloroethene	ND		ug/l	0.50	0.18
1,2-Dichlorobenzene	ND		ug/l	2.5	0.70
1,3-Dichlorobenzene	ND		ug/l	2.5	0.70

Project Name: CONVENTUS
Project Number: 1186

Lab Number: L2168683
Report Date: 12/29/21

Method Blank Analysis
Batch Quality Control

Analytical Method: 1,8260C
Analytical Date: 12/24/21 09:03
Analyst: PD

Parameter	Result	Qualifier	Units	RL	MDL
Volatile Organics by GC/MS - Westborough Lab for sample(s): 01-07 Batch: WG1587543-5					
1,4-Dichlorobenzene	ND		ug/l	2.5	0.70
Methyl tert butyl ether	ND		ug/l	2.5	0.70
p/m-Xylene	ND		ug/l	2.5	0.70
o-Xylene	ND		ug/l	2.5	0.70
cis-1,2-Dichloroethene	ND		ug/l	2.5	0.70
Styrene	ND		ug/l	2.5	0.70
Dichlorodifluoromethane	ND		ug/l	5.0	1.0
Acetone	ND		ug/l	5.0	1.5
Carbon disulfide	ND		ug/l	5.0	1.0
2-Butanone	ND		ug/l	5.0	1.9
4-Methyl-2-pentanone	ND		ug/l	5.0	1.0
2-Hexanone	ND		ug/l	5.0	1.0
1,2-Dibromoethane	ND		ug/l	2.0	0.65
n-Butylbenzene	ND		ug/l	2.5	0.70
sec-Butylbenzene	ND		ug/l	2.5	0.70
tert-Butylbenzene	ND		ug/l	2.5	0.70
1,2-Dibromo-3-chloropropane	ND		ug/l	2.5	0.70
Isopropylbenzene	ND		ug/l	2.5	0.70
p-Isopropyltoluene	ND		ug/l	2.5	0.70
Naphthalene	ND		ug/l	2.5	0.70
n-Propylbenzene	ND		ug/l	2.5	0.70
1,2,4-Trichlorobenzene	ND		ug/l	2.5	0.70
1,3,5-Trimethylbenzene	ND		ug/l	2.5	0.70
1,2,4-Trimethylbenzene	ND		ug/l	2.5	0.70
Methyl Acetate	ND		ug/l	2.0	0.23
Cyclohexane	ND		ug/l	10	0.27
Freon-113	ND		ug/l	2.5	0.70
Methyl cyclohexane	ND		ug/l	10	0.40

Project Name: CONVENTUS
Project Number: 1186

Lab Number: L2168683
Report Date: 12/29/21

Method Blank Analysis
Batch Quality Control

Analytical Method: 1,8260C
Analytical Date: 12/24/21 09:03
Analyst: PD

Parameter	Result	Qualifier	Units	RL	MDL
Volatile Organics by GC/MS - Westborough Lab for sample(s): 01-07 Batch: WG1587543-5					

Surrogate	%Recovery	Qualifier	Acceptance Criteria
1,2-Dichloroethane-d4	115		70-130
Toluene-d8	100		70-130
4-Bromofluorobenzene	97		70-130
Dibromofluoromethane	112		70-130

Lab Control Sample Analysis

Batch Quality Control

Project Name: CONVENTUS

Project Number: 1186

Lab Number: L2168683

Report Date: 12/29/21

Parameter	LCS %Recovery	Qual	LCS %Recovery	Qual	%Recovery Limits	RPD	Qual	RPD Limits
Volatile Organics by GC/MS - Westborough Lab Associated sample(s): 01-07 Batch: WG1587543-3 WG1587543-4								
Methylene chloride	100		100		70-130	0		20
1,1-Dichloroethane	120		120		70-130	0		20
Chloroform	100		100		70-130	0		20
Carbon tetrachloride	94		93		63-132	1		20
1,2-Dichloropropane	120		120		70-130	0		20
Dibromochloromethane	87		93		63-130	7		20
1,1,2-Trichloroethane	89		97		70-130	9		20
Tetrachloroethene	96		97		70-130	1		20
Chlorobenzene	100		100		75-130	0		20
Trichlorofluoromethane	120		120		62-150	0		20
1,2-Dichloroethane	110		110		70-130	0		20
1,1,1-Trichloroethane	99		98		67-130	1		20
Bromodichloromethane	95		96		67-130	1		20
trans-1,3-Dichloropropene	81		86		70-130	6		20
cis-1,3-Dichloropropene	88		92		70-130	4		20
Bromoform	77		83		54-136	8		20
1,1,2,2-Tetrachloroethane	91		100		67-130	9		20
Benzene	100		100		70-130	0		20
Toluene	100		100		70-130	0		20
Ethylbenzene	100		100		70-130	0		20
Chloromethane	140	Q	140	Q	64-130	0		20
Bromomethane	98		85		39-139	14		20
Vinyl chloride	140		140		55-140	0		20

Lab Control Sample Analysis

Batch Quality Control

Project Name: CONVENTUS

Lab Number: L2168683

Project Number: 1186

Report Date: 12/29/21

Parameter	LCS %Recovery	Qual	LCSD %Recovery	Qual	%Recovery Limits	RPD	Qual	RPD Limits
Volatile Organics by GC/MS - Westborough Lab Associated sample(s): 01-07 Batch: WG1587543-3 WG1587543-4								
Chloroethane	130		130		55-138	0		20
1,1-Dichloroethene	110		110		61-145	0		20
trans-1,2-Dichloroethene	100		100		70-130	0		20
Trichloroethene	98		100		70-130	2		20
1,2-Dichlorobenzene	95		96		70-130	1		20
1,3-Dichlorobenzene	97		96		70-130	1		20
1,4-Dichlorobenzene	95		96		70-130	1		20
Methyl tert butyl ether	89		98		63-130	10		20
p/m-Xylene	100		100		70-130	0		20
o-Xylene	100		100		70-130	0		20
cis-1,2-Dichloroethene	100		100		70-130	0		20
Styrene	100		100		70-130	0		20
Dichlorodifluoromethane	100		100		36-147	0		20
Acetone	100		110		58-148	10		20
Carbon disulfide	120		110		51-130	9		20
2-Butanone	100		120		63-138	18		20
4-Methyl-2-pentanone	85		95		59-130	11		20
2-Hexanone	95		110		57-130	15		20
1,2-Dibromoethane	86		94		70-130	9		20
n-Butylbenzene	100		100		53-136	0		20
sec-Butylbenzene	100		100		70-130	0		20
tert-Butylbenzene	98		96		70-130	2		20
1,2-Dibromo-3-chloropropane	75		81		41-144	8		20

Lab Control Sample Analysis

Batch Quality Control

Project Name: CONVENTUS

Lab Number: L2168683

Project Number: 1186

Report Date: 12/29/21

Parameter	LCS %Recovery	Qual	LCS %Recovery	Qual	%Recovery Limits	RPD	Qual	RPD Limits
Volatile Organics by GC/MS - Westborough Lab Associated sample(s): 01-07 Batch: WG1587543-3 WG1587543-4								
Isopropylbenzene	100		100		70-130	0		20
p-Isopropyltoluene	98		96		70-130	2		20
Naphthalene	76		86		70-130	12		20
n-Propylbenzene	110		100		69-130	10		20
1,2,4-Trichlorobenzene	84		86		70-130	2		20
1,3,5-Trimethylbenzene	97		95		64-130	2		20
1,2,4-Trimethylbenzene	97		95		70-130	2		20
Methyl Acetate	110		120		70-130	9		20
Cyclohexane	140	Q	140	Q	70-130	0		20
Freon-113	110		110		70-130	0		20
Methyl cyclohexane	98		100		70-130	2		20

Surrogate	LCS %Recovery	Qual	LCS %Recovery	Qual	Acceptance Criteria
1,2-Dichloroethane-d4	112		115		70-130
Toluene-d8	104		104		70-130
4-Bromofluorobenzene	102		99		70-130
Dibromofluoromethane	107		106		70-130

Project Name: CONVENTUS**Lab Number:** L2168683**Project Number:** 1186**Report Date:** 12/29/21**Sample Receipt and Container Information**

Were project specific reporting limits specified?

YES

Cooler Information

Cooler	Custody Seal
A	Absent

Container Information

Container ID	Container Type	Cooler	Initial pH	Final pH	Temp deg C	Pres	Seal	Frozen Date/Time	Analysis(*)
L2168683-01A	Vial HCl preserved	A	NA		3.0	Y	Absent		NYTCL-8260-R2(14)
L2168683-01B	Vial HCl preserved	A	NA		3.0	Y	Absent		NYTCL-8260-R2(14)
L2168683-01C	Vial HCl preserved	A	NA		3.0	Y	Absent		NYTCL-8260-R2(14)
L2168683-02A	Vial HCl preserved	A	NA		3.0	Y	Absent		NYTCL-8260-R2(14)
L2168683-02B	Vial HCl preserved	A	NA		3.0	Y	Absent		NYTCL-8260-R2(14)
L2168683-02C	Vial HCl preserved	A	NA		3.0	Y	Absent		NYTCL-8260-R2(14)
L2168683-03A	Vial HCl preserved	A	NA		3.0	Y	Absent		NYTCL-8260-R2(14)
L2168683-03B	Vial HCl preserved	A	NA		3.0	Y	Absent		NYTCL-8260-R2(14)
L2168683-03C	Vial HCl preserved	A	NA		3.0	Y	Absent		NYTCL-8260-R2(14)
L2168683-04A	Vial HCl preserved	A	NA		3.0	Y	Absent		NYTCL-8260-R2(14)
L2168683-04B	Vial HCl preserved	A	NA		3.0	Y	Absent		NYTCL-8260-R2(14)
L2168683-04C	Vial HCl preserved	A	NA		3.0	Y	Absent		NYTCL-8260-R2(14)
L2168683-05A	Vial HCl preserved	A	NA		3.0	Y	Absent		NYTCL-8260-R2(14)
L2168683-05B	Vial HCl preserved	A	NA		3.0	Y	Absent		NYTCL-8260-R2(14)
L2168683-05C	Vial HCl preserved	A	NA		3.0	Y	Absent		NYTCL-8260-R2(14)
L2168683-06A	Vial HCl preserved	A	NA		3.0	Y	Absent		NYTCL-8260-R2(14)
L2168683-06B	Vial HCl preserved	A	NA		3.0	Y	Absent		NYTCL-8260-R2(14)
L2168683-06C	Vial HCl preserved	A	NA		3.0	Y	Absent		NYTCL-8260-R2(14)
L2168683-07A	Vial HCl preserved	A	NA		3.0	Y	Absent		NYTCL-8260-R2(14)
L2168683-07B	Vial HCl preserved	A	NA		3.0	Y	Absent		NYTCL-8260-R2(14)

Project Name: CONVENTUS
Project Number: 1186

Lab Number: L2168683
Report Date: 12/29/21

GLOSSARY

Acronyms

DL	- Detection Limit: This value represents the level to which target analyte concentrations are reported as estimated values, when those target analyte concentrations are quantified below the limit of quantitation (LOQ). The DL includes any adjustments from dilutions, concentrations or moisture content, where applicable. (DoD report formats only.)
EDL	- Estimated Detection Limit: This value represents the level to which target analyte concentrations are reported as estimated values, when those target analyte concentrations are quantified below the reporting limit (RL). The EDL includes any adjustments from dilutions, concentrations or moisture content, where applicable. The use of EDLs is specific to the analysis of PAHs using Solid-Phase Microextraction (SPME).
EMPC	- Estimated Maximum Possible Concentration: The concentration that results from the signal present at the retention time of an analyte when the ions meet all of the identification criteria except the ion abundance ratio criteria. An EMPC is a worst-case estimate of the concentration.
EPA	- Environmental Protection Agency.
LCS	- Laboratory Control Sample: A sample matrix, free from the analytes of interest, spiked with verified known amounts of analytes or a material containing known and verified amounts of analytes.
LCSD	- Laboratory Control Sample Duplicate: Refer to LCS.
LFB	- Laboratory Fortified Blank: A sample matrix, free from the analytes of interest, spiked with verified known amounts of analytes or a material containing known and verified amounts of analytes.
LOD	- Limit of Detection: This value represents the level to which a target analyte can reliably be detected for a specific analyte in a specific matrix by a specific method. The LOD includes any adjustments from dilutions, concentrations or moisture content, where applicable. (DoD report formats only.)
LOQ	- Limit of Quantitation: The value at which an instrument can accurately measure an analyte at a specific concentration. The LOQ includes any adjustments from dilutions, concentrations or moisture content, where applicable. (DoD report formats only.) Limit of Quantitation: The value at which an instrument can accurately measure an analyte at a specific concentration. The LOQ includes any adjustments from dilutions, concentrations or moisture content, where applicable. (DoD report formats only.)
MDL	- Method Detection Limit: This value represents the level to which target analyte concentrations are reported as estimated values, when those target analyte concentrations are quantified below the reporting limit (RL). The MDL includes any adjustments from dilutions, concentrations or moisture content, where applicable.
MS	- Matrix Spike Sample: A sample prepared by adding a known mass of target analyte to a specified amount of matrix sample for which an independent estimate of target analyte concentration is available. For Method 332.0, the spike recovery is calculated using the native concentration, including estimated values.
MSD	- Matrix Spike Sample Duplicate: Refer to MS.
NA	- Not Applicable.
NC	- Not Calculated: Term is utilized when one or more of the results utilized in the calculation are non-detect at the parameter's reporting unit.
NDPA/DPA	- N-Nitrosodiphenylamine/Diphenylamine.
NI	- Not Ignitable.
NP	- Non-Plastic: Term is utilized for the analysis of Atterberg Limits in soil.
NR	- No Results: Term is utilized when 'No Target Compounds Requested' is reported for the analysis of Volatile or Semivolatile Organic TIC only requests.
RL	- Reporting Limit: The value at which an instrument can accurately measure an analyte at a specific concentration. The RL includes any adjustments from dilutions, concentrations or moisture content, where applicable.
RPD	- Relative Percent Difference: The results from matrix and/or matrix spike duplicates are primarily designed to assess the precision of analytical results in a given matrix and are expressed as relative percent difference (RPD). Values which are less than five times the reporting limit for any individual parameter are evaluated by utilizing the absolute difference between the values; although the RPD value will be provided in the report.
SRM	- Standard Reference Material: A reference sample of a known or certified value that is of the same or similar matrix as the associated field samples.
STLP	- Semi-dynamic Tank Leaching Procedure per EPA Method 1315.
TEF	- Toxic Equivalency Factors: The values assigned to each dioxin and furan to evaluate their toxicity relative to 2,3,7,8-TCDD.
TEQ	- Toxic Equivalent: The measure of a sample's toxicity derived by multiplying each dioxin and furan by its corresponding TEF and then summing the resulting values.
TIC	- Tentatively Identified Compound: A compound that has been identified to be present and is not part of the target compound list (TCL) for the method and/or program. All TICs are qualitatively identified and reported as estimated concentrations.

Report Format: DU Report with 'J' Qualifiers



Project Name: CONVENTUS
Project Number: 1186

Lab Number: L2168683
Report Date: 12/29/21

Footnotes

- 1 - The reference for this analyte should be considered modified since this analyte is absent from the target analyte list of the original method.

Terms

Analytical Method: Both the document from which the method originates and the analytical reference method. (Example: EPA 8260B is shown as 1,8260B.) The codes for the reference method documents are provided in the References section of the Addendum.

Difference: With respect to Total Oxidizable Precursor (TOP) Assay analysis, the difference is defined as the Post-Treatment value minus the Pre-Treatment value.

Final pH: As it pertains to Sample Receipt & Container Information section of the report, Final pH reflects pH of container determined after adjustment at the laboratory, if applicable. If no adjustment required, value reflects Initial pH.

Frozen Date/Time: With respect to Volatile Organics in soil, Frozen Date/Time reflects the date/time at which associated Reagent Water-preserved vials were initially frozen. Note: If frozen date/time is beyond 48 hours from sample collection, value will be reflected in 'bold'.

Initial pH: As it pertains to Sample Receipt & Container Information section of the report, Initial pH reflects pH of container determined upon receipt, if applicable.

PAH Total: With respect to Alkylated PAH analyses, the 'PAHs, Total' result is defined as the summation of results for all or a subset of the following compounds: Naphthalene, C1-C4 Naphthalenes, 2-Methylnaphthalene, 1-Methylnaphthalene, Biphenyl, Acenaphthylene, Acenaphthene, Fluorene, C1-C3 Fluorenes, Phenanthrene, C1-C4 Phenanthrenes/Anthracenes, Anthracene, Fluoranthene, Pyrene, C1-C4 Fluoranthenes/Pyrenes, Benz(a)anthracene, Chrysene, C1-C4 Chrysenes, Benzo(b)fluoranthene, Benzo(j)+(k)fluoranthene, Benzo(e)pyrene, Benzo(a)pyrene, Perylene, Indeno(1,2,3-cd)pyrene, Dibenz(ah)+(ac)anthracene, Benzo(g,h,i)perylene. If a 'Total' result is requested, the results of its individual components will also be reported.

PFAS Total: With respect to PFAS analyses, the 'PFAS, Total (5)' result is defined as the summation of results for: PFHpA, PFHxS, PFOA, PFNA and PFOS. In addition, the 'PFAS, Total (6)' result is defined as the summation of results for: PFHpA, PFHxS, PFOA, PFNA, PFDA and PFOS. For MassDEP DW compliance analysis only, the 'PFAS, Total (6)' result is defined as the summation of results at or above the RL. Note: If a 'Total' result is requested, the results of its individual components will also be reported.

The target compound Chlordane (CAS No. 57-74-9) is reported for GC ECD analyses. Per EPA, this compound "refers to a mixture of chlordane isomers, other chlorinated hydrocarbons and numerous other components." (Reference: USEPA Toxicological Review of Chlordane, In Support of Summary Information on the Integrated Risk Information System (IRIS), December 1997.)

Total: With respect to Organic analyses, a 'Total' result is defined as the summation of results for individual isomers or Aroclors. If a 'Total' result is requested, the results of its individual components will also be reported. This is applicable to 'Total' results for methods 8260, 8081 and 8082.

Data Qualifiers

- A** - Spectra identified as "Aldol Condensates" are byproducts of the extraction/concentration procedures when acetone is introduced in the process.
- B** - The analyte was detected above the reporting limit in the associated method blank. Flag only applies to associated field samples that have detectable concentrations of the analyte at less than ten times (10x) the concentration found in the blank. For MCP-related projects, flag only applies to associated field samples that have detectable concentrations of the analyte at less than ten times (10x) the concentration found in the blank. For DOD-related projects, flag only applies to associated field samples that have detectable concentrations of the analyte at less than ten times (10x) the concentration found in the blank AND the analyte was detected above one-half the reporting limit (or above the reporting limit for common lab contaminants) in the associated method blank. For NJ-Air-related projects, flag only applies to associated field samples that have detectable concentrations of the analyte above the reporting limit. For NJ-related projects (excluding Air), flag only applies to associated field samples that have detectable concentrations of the analyte, which was detected above the reporting limit in the associated method blank or above five times the reporting limit for common lab contaminants (Phthalates, Acetone, Methylene Chloride, 2-Butanone).
- C** - Co-elution: The target analyte co-elutes with a known lab standard (i.e. surrogate, internal standards, etc.) for co-extracted analyses.
- D** - Concentration of analyte was quantified from diluted analysis. Flag only applies to field samples that have detectable concentrations of the analyte.
- E** - Concentration of analyte exceeds the range of the calibration curve and/or linear range of the instrument.
- F** - The ratio of quantifier ion response to qualifier ion response falls outside of the laboratory criteria. Results are considered to be an estimated maximum concentration.
- G** - The concentration may be biased high due to matrix interferences (i.e. co-elution) with non-target compound(s). The result should be considered estimated.
- H** - The analysis of pH was performed beyond the regulatory-required holding time of 15 minutes from the time of sample collection.
- I** - The lower value for the two columns has been reported due to obvious interference.
- J** - Estimated value. The Target analyte concentration is below the quantitation limit (RL), but above the Method Detection Limit (MDL) or Estimated Detection Limit (EDL) for SPME-related analyses. This represents an estimated concentration for Tentatively Identified Compounds (TICs).
- M** - Reporting Limit (RL) exceeds the MCP CAM Reporting Limit for this analyte.
- ND** - Not detected at the method detection limit (MDL) for the sample, or estimated detection limit (EDL) for SPME-related analyses.

Report Format: DU Report with 'J' Qualifiers



Project Name: CONVENTUS
Project Number: 1186

Lab Number: L2168683
Report Date: 12/29/21

Data Qualifiers

- NJ** - Presumptive evidence of compound. This represents an estimated concentration for Tentatively Identified Compounds (TICs), where the identification is based on a mass spectral library search.
- P** - The RPD between the results for the two columns exceeds the method-specified criteria.
- Q** - The quality control sample exceeds the associated acceptance criteria. For DOD-related projects, LCS and/or Continuing Calibration Standard exceedences are also qualified on all associated sample results. Note: This flag is not applicable for matrix spike recoveries when the sample concentration is greater than 4x the spike added or for batch duplicate RPD when the sample concentrations are less than 5x the RL. (Metals only.)
- R** - Analytical results are from sample re-analysis.
- RE** - Analytical results are from sample re-extraction.
- S** - Analytical results are from modified screening analysis.
- V** - The surrogate associated with this target analyte has a recovery outside the QC acceptance limits. (Applicable to MassDEP DW Compliance samples only.)
- Z** - The batch matrix spike and/or duplicate associated with this target analyte has a recovery/RPD outside the QC acceptance limits. (Applicable to MassDEP DW Compliance samples only.)

Project Name: CONVENTUS
Project Number: 1186

Lab Number: L2168683
Report Date: 12/29/21

REFERENCES

- 1 Test Methods for Evaluating Solid Waste: Physical/Chemical Methods. EPA SW-846. Third Edition. Updates I - VI, 2018.

LIMITATION OF LIABILITIES

Alpha Analytical performs services with reasonable care and diligence normal to the analytical testing laboratory industry. In the event of an error, the sole and exclusive responsibility of Alpha Analytical shall be to re-perform the work at it's own expense. In no event shall Alpha Analytical be held liable for any incidental, consequential or special damages, including but not limited to, damages in any way connected with the use of, interpretation of, information or analysis provided by Alpha Analytical.

We strongly urge our clients to comply with EPA protocol regarding sample volume, preservation, cooling, containers, sampling procedures, holding time and splitting of samples in the field.



Certification Information

The following analytes are not included in our Primary NELAP Scope of Accreditation:

Westborough Facility

EPA 624/624.1: m/p-xylene, o-xylene, Naphthalene

EPA 625/625.1: alpha-Terpineol

EPA 8260C/8260D: NPW: 1,2,4,5-Tetramethylbenzene; 4-Ethyltoluene, Azobenzene; SCM: Iodomethane (methyl iodide), 1,2,4,5-Tetramethylbenzene; 4-Ethyltoluene.

EPA 8270D/8270E: NPW: Dimethylnaphthalene, 1,4-Diphenylhydrazine, alpha-Terpineol; SCM: Dimethylnaphthalene, 1,4-Diphenylhydrazine.

SM4500: NPW: Amenable Cyanide; SCM: Total Phosphorus, TKN, NO₂, NO₃.

Mansfield Facility

SM 2540D: TSS

EPA 8082A: NPW: PCB: 1, 5, 31, 87,101, 110, 141, 151, 153, 180, 183, 187.

EPA TO-15: Halothane, 2,4,4-Trimethyl-2-pentene, 2,4,4-Trimethyl-1-pentene, Thiophene, 2-Methylthiophene,

3-Methylthiophene, 2-Ethylthiophene, 1,2,3-Trimethylbenzene, Indan, Indene, 1,2,4,5-Tetramethylbenzene, Benzothiophene, 1-Methylnaphthalene.

Biological Tissue Matrix: EPA 3050B

The following analytes are included in our Massachusetts DEP Scope of Accreditation

Westborough Facility:

Drinking Water

EPA 300.0: Chloride, Nitrate-N, Fluoride, Sulfate; **EPA 353.2:** Nitrate-N, Nitrite-N; **SM4500NO3-F:** Nitrate-N, Nitrite-N; **SM4500F-C, SM4500CN-CE,**

EPA 180.1, SM2130B, SM4500CI-D, SM2320B, SM2540C, SM4500H-B, SM4500NO2-B

EPA 332: Perchlorate; **EPA 524.2:** THMs and VOCs; **EPA 504.1:** EDB, DBCP.

Microbiology: **SM9215B; SM9223-P/A, SM9223B-Colilert-QT, SM9222D.**

Non-Potable Water

SM4500H,B, EPA 120.1, SM2510B, SM2540C, SM2320B, SM4500CL-E, SM4500F-BC, SM4500NH3-BH: Ammonia-N and Kjeldahl-N, **EPA 350.1:**

Ammonia-N, **LCHAT 10-107-06-1-B:** Ammonia-N, **EPA 351.1, SM4500NO3-F, EPA 353.2:** Nitrate-N, **SM4500P-E, SM4500P-B, E, SM4500SO4-E,**

SM5220D, EPA 410.4, SM5210B, SM5310C, SM4500CL-D, EPA 1664, EPA 420.1, SM4500-CN-CE, SM2540D, EPA 300: Chloride, Sulfate, Nitrate.

EPA 624.1: Volatile Halocarbons & Aromatics,

EPA 608.3: Chlordane, Toxaphene, Aldrin, alpha-BHC, beta-BHC, gamma-BHC, delta-BHC, Dieldrin, DDD, DDE, DDT, Endosulfan I, Endosulfan II,

Endosulfan sulfate, Endrin, Endrin Aldehyde, Heptachlor, Heptachlor Epoxide, PCBs

EPA 625.1: SVOC (Acid/Base/Neutral Extractables), **EPA 600/4-81-045:** PCB-Oil.

Microbiology: **SM9223B-Colilert-QT; Enterolert-QT, SM9221E, EPA 1600, EPA 1603, SM9222D.**

Mansfield Facility:

Drinking Water

EPA 200.7: Al, Ba, Cd, Cr, Cu, Fe, Mn, Ni, Na, Ag, Ca, Zn. **EPA 200.8:** Al, Sb, As, Ba, Be, Cd, Cr, Cu, Pb, Mn, Ni, Se, Ag, TL, Zn. **EPA 245.1 Hg.**

EPA 522, EPA 537.1.

Non-Potable Water

EPA 200.7: Al, Sb, As, Be, Cd, Ca, Cr, Co, Cu, Fe, Pb, Mg, Mn, Mo, Ni, K, Se, Ag, Na, Sr, TL, Ti, V, Zn.

EPA 200.8: Al, Sb, As, Be, Cd, Cr, Cu, Fe, Pb, Mn, Ni, K, Se, Ag, Na, TL, Zn.

EPA 245.1 Hg.

SM2340B

For a complete listing of analytes and methods, please contact your Alpha Project Manager.

 NEW YORK CHAIN OF CUSTODY Westborough, MA 01581 8 Walkup Dr. TEL: 508-898-9220 FAX: 508-898-9193	NEW YORK CHAIN OF CUSTODY Mansfield, MA 02048 320 Forbes Blvd TEL: 508-822-9300 FAX: 508-822-3288	Service Centers Mahwah, NJ 07430: 35 Whitney Rd, Suite 5 Albany, NY 12205: 14 Walker Way Tonawanda, NY 14150: 275 Cooper Ave, Suite 105	Page 1 of 1	Date Rec'd in Lab 12/15/21	ALPHA Job # 12168683		
		Project Information Project Name: <u>CONVENTUS</u> Project Location: <u>CONVENTUS / MAIN ST. BUFFALO NY</u> Project # <u>486</u> (Use Project name as Project #) <input type="checkbox"/>		Deliverables <input type="checkbox"/> ASP-A <input checked="" type="checkbox"/> ASP-B <input checked="" type="checkbox"/> EQUIS (1 File) <input type="checkbox"/> EQUIS (4 File) <input type="checkbox"/> Other		Billing Information <input type="checkbox"/> Same as Client Info PO #	
Client Information Client: <u>CES ENGINEERS</u> Address: <u>141 ELM ST. BUFFALO, NY 14203</u> Phone: <u>(716)-792-3520</u> Fax: _____ Email: <u>Rbackert@cesus.com</u>		Project Manager: <u>Cochy MARTIN</u> ALPHAQuote #: _____ Turn-Around Time Standard <input checked="" type="checkbox"/> Due Date: _____ Rush (only if pre approved) <input type="checkbox"/> # of Days: _____		Regulatory Requirement <input type="checkbox"/> NY TOGS <input checked="" type="checkbox"/> NY Part 375 <input type="checkbox"/> AWQ Standards <input type="checkbox"/> NY CP-51 <input type="checkbox"/> NY Restricted Use <input type="checkbox"/> Other <input type="checkbox"/> NY Unrestricted Use <input type="checkbox"/> NYC Sewer Discharge		Disposal Site Information Please identify below location of applicable disposal facilities. Disposal Facility: <input type="checkbox"/> NJ <input type="checkbox"/> NY <input type="checkbox"/> Other:	
These samples have been previously analyzed by Alpha <input type="checkbox"/> Other project specific requirements/comments:			ANALYSIS			Sample Filtration <input type="checkbox"/> Done <input type="checkbox"/> Lab to do Preservation <input type="checkbox"/> Lab to do (Please Specify below)	
Please specify Metals or TAL.						Total Bottles	
ALPHA Lab ID (Lab Use Only)	Sample ID	Collection Date	Collection Time	Sample Matrix	Sampler's Initials		VOCs 8260
08683-01	BCP-MW01	12/14/21	9:50	GW	RB		x
-02	BCP-MW07	12/14/21	10:40	GW	RB		x
-03	BCP-MW04	12/14/21	11:35	GW	RB		x
-07	BCP-MW03	12/14/21	12:00	GW	RB		x
-05	BCP-MW06	12/14/21	12:35	GW	RB		x
-06	BCP-MW05	12/14/21	1:10	GW	RB		x
-04	TRIP BLANK						x
Preservative Code: A = None B = HCl C = HNO ₃ D = H ₂ SO ₄ E = NaOH F = MeOH G = NaHSO ₄ H = Na ₂ S ₂ O ₃ K/E = Zn Ac/NaOH O = Other		Container Code P = Plastic A = Amber Glass V = Vial G = Glass B = Bacteria Cup C = Cube O = Other E = Encore D = BOD Bottle		Westboro: Certification No: MA935 Mansfield: Certification No: MA015		Container Type: <u>V</u> Preservative: <u>B</u>	Please print clearly, legibly and completely. Samples can not be logged in and turnaround time clock will not start until any ambiguities are resolved. BY EXECUTING THIS COC, THE CLIENT HAS READ AND AGREES TO BE BOUND BY ALPHA'S TERMS & CONDITIONS. (See reverse side.)
Relinquished By: _____ Date/Time: <u>12/14/21 1508</u> _____ Date/Time: <u>12/14/21 1502</u>		Received By: _____ Date/Time: <u>12/14/21 1508</u> _____ Date/Time: <u>12/15/21 0120</u>					

APPENDIX B
GROUNDWATER MONITORING CONSTRUCTION & SAMPLING LOGS



C&S Engineers, Inc.
 141 Elm Street Suite 100
 Buffalo, New York 14203
 Phone: 716-847-1630
 www.cscos.com

Well Sampling Field Data Sheet

Well Casing Unit Volume (gal/l.f.)		
1 1/4" = 0.08	2" = 0.17	3" = 0.38
4" = 0.66	6" = 1.5	8" = 2.6

Client Name: CONVENTUS
 Site Name: _____
 Project No.: U96
 Field Staff: RICH BACKERT

WELL DATA

Date	12/14/21	12/14/21	12/14/21	12/14/21	12/14/21	12/14/21
Well Number	BCPMW01	BCPMW07	BCPMW04	BCPMW03	BCPMW06	BCPMW05
Diameter (inches)	2"	2"	2"	8"	8"	2"
Total Sounded Depth (feet)	15'	15'	14.8'	15'	15'	15'
Static Water Level (feet)	7.4'	10.1'	7.0'	6.8'	7.4'	7.8'
H ₂ O Column (feet)	7.6'	4.9'	8.0'	8.2'	7.6'	7.2'
Pump Intake (feet)						
Well Volume (gallons)						
Amount to Evacuate (gallons)	5 gal	5 gal	2 gal	2 gal	2 gal	2 gal
Amount Evacuated (gallons)	5 gal	5 gal	2 gal	2 gal	2 gal	2 gal

FIELD READINGS

Date	12/14/21	12/14/21	12/14/21	12/14/21	12/14/21	12/14/21
Time	9:50	10:40	11:35	12:00	12:35	1:10
pH (Std. Units)	+/-0.1	7.25	7.34	8.07	9.15	10.08
Conductivity (mS/cm)	3%	10.1	5.10	4.07	6.66	14.4
Turbidity (NTU)	10%	12.7	55.9	4.6	5.6	0.5
D.O. (mg/L)	10%	6.62	0.84	0.91	0.72	3.43
Temperature (°C) (°F)	3%	14.07°	14.85°	15.36°	15.98°	14.99°
ORP ³ (mV)	+/-10 mv	5	49	-176	-95	24
Appearance		CLEAR	CLEAR	CLEAR	CLEAR	CLEAR
Free Product (Yes/No)		NONE	NONE	NONE	NONE	NONE
Odor		NONE	NONE	MINOR	NONE	NONE
Comments	BCPMW04 MINOR PHENOLIC ODOR					

C = Clear T = Turbid ST = Semi Turbid VT = Very Turbid



C&S Engineers, Inc.
 90 Broadway
 Buffalo, New York 14203
 Phone: 716-847-1630
 Fax: 716-847-1454
 www.cscos.com

BORING LOG

Boring No. MW-01

Sheet 1 of: 1

Project No.: K11.002.001

Project Name: Main St ROW Investigation

Surface Elev.:

Location: MOB - Buffalo, NY

Datum: 6. Surface

Client: Kaleida Health

Start Date: 8/15/13

Drilling Firm: SJB

Driller: Tony

Finish Date: 8/15/13

Groundwater

Depth

Date & Time

Drill Rig: CME 45C

Inspector: N. Wohlabough

While Drilling:

Casing:

Rock Core:

Undist:

Before Casing Removal:

Sampler:

Other:

After Casing Removal:

Hammer: Auto

(N -- No. of blows to drive sampler 12" w/140 lb. hammer falling 30" ASTM D-1586, Standard Penetration Test)

Depth (ft)	Sample No.	Symbol	Blows on Sampler per 6"	MATERIAL DESCRIPTION <small>c - coarse m - medium f - fine S - Sand, \$ - Silt, G - Gravel, C - Clay, cly - clayey</small>	a - and - 35-50% s - some - 20-35% l - little - 10-20% t - trace - 0-10%	COMMENTS
						(e.g., N-value, recovery, relative moisture, core run, RQD, % recovered)
1			5			Start: 12:15 PM
			4	<u>Crushed Stone (dry)</u>		12" rec
2			9			0.2 ppm
			10			
3			6			
			6	<u>Crushed Stone (dry)</u>		15" rec
4			8	<u>Silt (red/brown - dry)</u>		0.2 ppm
			8			
5			11			
			12	<u>Silt (red/brown - moist)</u>		13" rec
6			15			2.5 ppm
			18			
7			16			
			22	<u>Silt (red/brown - saturated)</u>		24" rec
8			22	<u>Gravel (fine - medium grey - saturated)</u>		0 ppm
			24			
9			13			
			19	<u>Gravel (medium fine - medium grey - saturated)</u>		18" rec
10			19	<u>Silt (saturated)</u>		15.3 ppm
			22			
11			7			
			18	<u>Gravel (medium fine - medium grey - saturated)</u>		17" rec
12			18	<u>Silt (saturated)</u>		229 ppm
			28			
13			50/4	<u>Gravel (medium fine - medium grey - saturated)</u>		5" rec
						16.3 ppm
14			16			
			24	<u>Gravel (medium fine - medium grey - saturated)</u>		17" rec
15			14			14.0 ppm
			16			
16						
17						
18						
19						
20						
21						
22						
23						
24						



C&S Engineers, Inc.
 90 Broadway
 Buffalo, New York 14203
 Phone: 716-847-1630
 Fax: 716-847-1454
 www.cscos.com

BORING LOG

Boring No. MW-02

Sheet 1 of: 1

Project No.: K11.002.001

Project Name: Main St ROW Investigation

Surface Elev.:

Location: MOB - Buffalo, NY

Datum: 6. Surface

Client: Kaleida Health

Start Date: 8/16/13

Drilling Firm: SJB

Driller: Tony

Finish Date: 8/16/13

Groundwater

Depth

Date & Time

Drill Rig: CME 45C

Inspector: N. Wohlabough

While Drilling:

Casing:

Rock Core:

Undist:

Before Casing Removal:

Sampler:

Other:

After Casing Removal:

Hammer: Auto

(N -- No. of blows to drive sampler 12" w/140 lb. hammer falling 30" ASTM D-1586, Standard Penetration Test)

Depth (ft)	Sample No.	Symbol	Blows on Sampler per 6"	<small>c - coarse m - medium f - fine</small> MATERIAL DESCRIPTION <small>S - Sand, \$ - Silt, G - Gravel, C - Clay, cly - clayey</small>	<small>a - and - 35-50% s - some - 20-35% l - little - 10-20% t - trace - 0-10%</small>	COMMENTS (e.g., N-value, recovery, relative moisture, core run, RQD, % recovered)
1			7			Start: 9:20 AM
			7	<u>Crushed Stone (grey - dry)</u>		6" rec
2			15			0.2 ppm
			17			
3			10			
			10	<u>Flowable Fill (black - dry/damp)</u>		6" rec
4			23			0.2 ppm
			26			
5			3			
			3	<u>Flowable Fill (black - dry/damp)</u>		24" rec
6			12			3.1 ppm
			10			
7			13			
			15	<u>Flowable Fill (black - dry/damp)</u>		24" rec
8			22			5.6 ppm
			23			
9			4			
			4	<u>Flowable Fill (black - damp/moist)</u>		24" rec
10			5			4.3 ppm
			8			
11			5			
			9	<u>Flowable Fill (black - damp/moist)</u>		20" rec
12			14	<u>Medium Sand (Caorse - gray - moist)</u>		1.5 ppm
			48			
13			3-May	<u>2" of Slough</u>		N/A
14						N/A
15				<u>Bottom of @ 13'+3' = 16' bg</u>		
16						
17						
18						
19						
20						
21						
22						
23						
24						



C&S Engineers, Inc.
 90 Broadway
 Buffalo, New York 14203
 Phone: 716-847-1630
 Fax: 716-847-1454
 www.cscos.com

BORING LOG

Boring No. MW-03

Sheet 1 of: 1

Project No.: K11.002.001

Project Name: Main St ROW Investigation

Surface Elev.:

Location: MOB - Buffalo, NY

Datum: 26' - Surface

Client: Kaleida Health

Start Date: 9/12/13

Drilling Firm: SJB

Driller:

Tony

Finish Date: 9/12/13

Groundwater

Depth

Date & Time

Drill Rig:

CME 45C

Inspector:

N. Wohlabough

While Drilling:

Casing:

Rock Core:

Undist:

Before Casing Removal:

Sampler:

Other:

After Casing Removal:

Hammer:

Auto

(N -- No. of blows to drive sampler 12" w/140 lb. hammer falling 30" ASTM D-1586, Standard Penetration Test)

Depth (ft)	Sample No.	Symbol	Blows on Sampler per 6"	MATERIAL DESCRIPTION <small>c - coarse m - medium f - fine S - Sand, \$ - Silt, G - Gravel, C - Clay, cly - clayey</small>	a - and - 35-50% s - some - 20-35% l - little - 10-20% t - trace - 0-10%	COMMENTS (e.g., N-value, recovery, relative moisture, core run, RQD, % recovered)
1			4			Start: 8:30 AM
			7	<u>Sand (med brown - fine sand - moist)</u>		12" rec
2			10	<u>some Silt</u>		0.2 ppm
			12			
3			17			
			17	<u>Silt (med brown - wet to saturated)</u>		15" rec
4			18	<u>some Fine Sand and Clay</u>		0.4 ppm
			17			
5			6			
			8	<u>Sand (black - med grained - sheen - saturated)</u>		14" rec
6			7			415 ppm
			7			
7			9			
			10	<u>Sand (black - med grained - sheen - saturated)</u>		16"
8			10			0 ppm
			11			
9			2			
			4	<u>Sand (med grey - saturated)</u>		20" rec
10			5	<u>4" of Clay at the bottom (red/brown)</u>		175 ppm
			15			
11			16			
			35	<u>Sand (upper 10" - black - wet to moist)</u>		20" rec
12			50/3	<u>Sand (lower 10" - coarse - with angular gravel - west to moist)</u>		305 ppm
13			27			
			50/4	<u>Sand (med grey - coarse - with angular gravel - moist)</u>		8" rec
14						19.4 ppm
15			13			
			19	<u>Sand (med grey - coarse - with angular gravel - moist)</u>		15" rec
16			37			12 ppm
			30			
17						
18						
19						
20						
21						
22						
23						
24						



C&S Engineers, Inc.
 90 Broadway
 Buffalo, New York 14203
 Phone: 716-847-1630
 Fax: 716-847-1454
 www.cscos.com

BORING LOG

Boring No. MW-04

Sheet 1 of: 1

Project No.: K11.002.001

Project Name: Main St ROW Investigation

Surface Elev.:

Location: MOB - Buffalo, NY

Datum: 6. Surface

Client: Kaleida Health

Start Date: 8/15/13

Drilling Firm: SJB

Driller: Tony

Finish Date: 8/15/13

Groundwater

Depth

Date & Time

Drill Rig: CME 45C

Inspector: N. Wohlabough

While Drilling:

Casing:

Rock Core:

Undist:

Before Casing Removal:

Sampler:

Other:

After Casing Removal:

Hammer: Auto

(N -- No. of blows to drive sampler 12" w/140 lb. hammer falling 30" ASTM D-1586, Standard Penetration Test)

Depth (ft)	Sample No.	Symbol	Blows on Sampler per 6"	<small>c - coarse m - medium f - fine</small> MATERIAL DESCRIPTION <small>S - Sand, \$ - Silt, G - Gravel, C - Clay, cly - clayey</small>	<small>a - and - 35-50% s - some - 20-35% l - little - 10-20% t - trace - 0-10%</small>	COMMENTS (e.g., N-value, recovery, relative moisture, core run, RQD, % recovered)
1			9			Start: 7:20 AM
			12	<u>Crushed Stone (dry)</u>		12" rec
			13			0.2 ppm
2			10			
			15			
3			21	<u>Crushed Stone (dry)</u>		15" rec
			23			0.2 ppm
4			25			
			20			
5			19	<u>Crushed Stone (dry)</u>		16" rec
			19	<u>Bottom 2" Flowable Fill</u>		0.5 ppm
6			20			
			13			
7			16	<u>Flowable Fill (black - moist)</u>		24" rec
			19			0 ppm
8			40			
			12			
9			13	<u>Flowable Fill (black - moist)</u>		24" rec
			15			0 ppm
10			19			
			7			
11			8	<u>Flowable Fill (black - moist)</u>		24" rec
			9	<u>Sand (medium brown - saturated)</u>		517 ppm
12			9			
			5			
13			9	<u>Sand (medium brown - moist)</u>		16" rec
			6	<u>Clay (red/brown - moist)</u>		59 ppm
14			14			
			6			
15			4	<u>Clay (red/brown - moist)</u>		23" rec
			7			1.2 ppm
16			15			
17						
18						
19						
20						
21						
22						
23						
24						



C&S Engineers, Inc.
 90 Broadway
 Buffalo, New York 14203
 Phone: 716-847-1630
 Fax: 716-847-1454
 www.cscos.com

BORING LOG

Boring No. MW-05

Sheet 1 of: 1

Project No.: K11.002.001

Project Name: Main St ROW Investigation

Surface Elev.:

Location: MOB - Buffalo, NY

Datum: 26' - Surface

Client: Kaleida Health

Start Date: 9/12/13

Drilling Firm: SJB

Driller:

Tony

Finish Date: 9/12/12

Groundwater

Depth

Date & Time

Drill Rig:

CME 45C

Inspector:

N. Wohlabough

While Drilling:

Casing:

Rock Core:

Undist:

Before Casing Removal:

Sampler:

Other:

After Casing Removal:

Hammer:

Auto

(N -- No. of blows to drive sampler 12" w/140 lb. hammer falling 30" ASTM D-1586, Standard Penetration Test)

Depth (ft)	Sample No.	Symbol	Blows on Sampler per 6"	<small>c - coarse m - medium f - fine</small> MATERIAL DESCRIPTION <small>S - Sand, \$ - Silt, G - Gravel, C - Clay, cly - clayey</small>	<small>a - and - 35-50% s - some - 20-35% l - little - 10-20% t - trace - 0-10%</small>	COMMENTS (e.g., N-value, recovery, relative moisture, core run, RQD, % recovered)
1			2			Start: 12:35 PM
			3	<u>Sand (med - red/brown - fine - moist)</u>		19" rec
2			5			0.6 ppm
			11			
3			12			
			16	<u>Sand (med - red/brown - fine - moist)</u>		16" rec
4			16	<u>some clay</u>		0.9 ppm
			20			
5			6			
			8	<u>Sand (top 8" - med - brown - coarse - saturated)</u>		16" rec
6			10	<u>Sand (bottom 8" - grey/black - coarse/gravelly - product sheet)</u>		382 ppm
			9			
7			6			
			7	<u>Sand (med - black - product sheen - saturated)</u>		21" rec
8			6			1628 ppm
			8			
9			5			
			8	<u>Sand (upper 12" - grey/black - wet)</u>		20" rec
10			12	<u>Sand (lower 8" - red/brown - clay - wet)</u>		17.2 ppm
			50/4			
11			10			
			16	<u>Sand (grey - round and angular gravel - saturated)</u>		11" rec
12			47			12 pmm
			50/2			
13			50/3	<u>Sand (coarse - grey - angular gravel - saturated)</u>		3" rec
						4.2 ppm
14						
15			15			
			23	<u>Gravel (angular gravel - grey - moist to saturated)</u>		14" rec
16			50/4	<u>some Sand</u>		10.5 ppm
17						
18						
19						
20						
21						
22						
23						
24						



C&S Engineers, Inc.
 90 Broadway
 Buffalo, New York 14203
 Phone: 716-847-1630
 Fax: 716-847-1454
 www.cscos.com

BORING LOG

Boring No. MW-06

Sheet 1 of: 1

Project No.: K11.002.001

Project Name: Main St ROW Investigation

Surface Elev.:

Location: MOB - Buffalo, NY

Datum: 6. Surface

Client: Kaleida Health

Start Date: 8/14/13

Drilling Firm: SJB

Driller:

Tony

Finish Date: 8/14/13

Groundwater

Depth

Date & Time

Drill Rig:

CME 45C

Inspector:

N. Wohlabough

While Drilling:

Casing:

Rock Core:

Undist:

Before Casing Removal:

Sampler:

Other:

After Casing Removal:

Hammer:

Auto

(N -- No. of blows to drive sampler 12" w/140 lb. hammer falling 30" ASTM D-1586, Standard Penetration Test)

Depth (ft)	Sample No.	Symbol	Blows on Sampler per 6"	MATERIAL DESCRIPTION <small>c - coarse m - medium f - fine S - Sand, \$ - Silt, G - Gravel, C - Clay, cly - clayey</small>	a - and - 35-50% s - some - 20-35% l - little - 10-20% t - trace - 0-10%	COMMENTS
						(e.g., N-value, recovery, relative moisture, core run, RQD, % recovered)
1			8			Start: 8:15 AM
			7	<u>Crushed Stone (dry)</u>		12" rec
2			6			0.6 ppm
			16			
3			9			
			10	<u>Crushed Stone (dry)</u>		15" rec
4			10			0.0 ppm
			17			
5			5			
			6	<u>Sand(medium/dark grey/brown - moist)</u>		10" rec
6			6			33.4
			8			
7			11			
			9	<u>Silty CLAY (red/brown - moist)</u>		18" rec
8			11	<u>Sand(brown - fine - moist)</u>		43.0 ppm
			14			
9			4			10" rec
			5	<u>Clayey SILT (red/brown - wet/saturated)</u>		53.0 ppm
10			13	<u>Sand(brown - fine - wet/saturated)</u>		
			38			
11			1			
			1	<u>Medium Sand (dark grey - saturated)</u>		11" rec
12			3	<u>Some Silt/Gravel (saturated)</u>		1.8 ppm
			7			
13			5			
			8	<u>Medium Sand (medium grey - saturated)</u>		24" rec
14			10	<u>Sand (lower 6" black- saturated)</u>		2.9 ppm
			11			
15			1			
			2	<u>Medium Sand (black - degraded oil smell - saturated)</u>		24" rec
16			4	<u>Clay (red/brown - rotten - saturated)</u>		
			5			
17						
18						
19						
20						
21						
22						
23						
24						



C&S Engineers, Inc.
 90 Broadway
 Buffalo, New York 14203
 Phone: 716-847-1630
 Fax: 716-847-1454
 www.cscos.com

BORING LOG

Boring No. MW-07

Sheet 1 of: 1

Project No.: K11.002.001

Project Name: Main St ROW Investigation

Surface Elev.:

Location: MOB - Buffalo, NY

Datum: 6. Surface

Client: Kaleida Health

Start Date: 8/16/13

Drilling Firm: SJB

Driller: Tony

Finish Date: 8/16/13

Groundwater

Depth

Date & Time

Drill Rig: CME 45C

Inspector: N. Wohlabough

While Drilling:

Casing:

Rock Core:

Undist:

Before Casing Removal:

Sampler:

Other:

After Casing Removal:

Hammer: Auto

(N -- No. of blows to drive sampler 12" w/140 lb. hammer falling 30" ASTM D-1586, Standard Penetration Test)

Depth (ft)	Sample No.	Symbol	Blows on Sampler per 6"	MATERIAL DESCRIPTION <small>c - coarse m - medium f - fine S - Sand, \$ - Silt, G - Gravel, C - Clay, cly - clayey</small>	a - and - 35-50% s - some - 20-35% l - little - 10-20% t - trace - 0-10%	COMMENTS
						(e.g., N-value, recovery, relative moisture, core run, RQD, % recovered)
1			3			Start: 2:45 PM
			5	<u>Crushed Stone (grey - dry)</u>		12" rec
2			5			0.4 ppm
			9			
3			19			
			16	<u>Sand (fine - red/brown - dry to moist)</u>		15" rec
4			18	<u>Silt (red/brown - dry to moist)</u>		1.0 ppm
			18			
5			12			
			17	<u>Sand (fine - red/brown - moist)</u>		16" rec
6			18	<u>Silt (red/brown - moist)</u>		0.2 ppm
			20			
7			24			
			24	<u>Sand (fine - red/brown - wet to saturated)</u>		23" rec
8			28	<u>Silt (red/brown - wet to saturated)</u>		0.5 ppm
			37			
9			14			
			16	<u>Sand (fine - red/brown - saturated)</u>		21" rec
10			22	<u>Silt (red/brown - saturated)</u>		0.8 ppm
			39			
11			16			
			28	<u>Silt (red/brown - wet)</u>		18" rec
12			32	<u>Clay (red/brown - wet)</u>		0.1 ppm
			31			
13			25			
			17	<u>Silt (red/brown - saturated)</u>		24" rec
14			26	<u>Clay (red/brown - saturated)</u>		0.0 ppm
			33			
15			20			
			19	<u>Silt (red/brown - moist to wet)</u>		19" rec
16			19	<u>Gravel (red/brown - moist to wet)</u>		0.0 ppm
			21			
17						
18						
19						
20						
21						
22						
23						
24						

APPENDIX C
IN SITU PRODUCT INFORMATION

RegenOx™

CHEMICAL OXIDATION REDEFINED...

RegenOx™ is an advanced in situ chemical oxidation technology designed to treat organic contaminants including high concentration source areas in the saturated and vadose zones*

PRODUCT FEATURES:

- Rapid and sustained oxidation of target compounds
- Easily applied with readily available equipment
- Destroys a broad range of contaminants
- More efficient than other solid oxidants
- Enhances subsequent bioremediation
- Avoids detrimental impacts to groundwater aquifers



RegenOx product application

HOW IT WORKS:

RegenOx maximizes in situ performance using a solid alkaline oxidant that employs a sodium percarbonate complex with a multi-part catalytic formula. The product is delivered as two parts that are combined and injected into the subsurface using common drilling or direct-push equipment. Once in the subsurface, the combined product produces an effective oxidation reaction comparable to that of Fenton's Reagent without a violent exothermic reaction. RegenOx safely, effectively and rapidly destroys a wide range of contaminants in both soil and groundwater (Table 1).


ACHIEVES RAPID OXIDATION VIA A NUMBER OF MECHANISMS

RegenOx directly oxidizes contaminants while its unique catalytic complex generates a suite of highly charged, oxidative free radicals that are responsible for the rapid destruction of contaminants. The mechanisms by which RegenOx operates are:

- **Surface-Mediated Oxidation:** (see Figure 1 and description below)
- **Direct Oxidation:** $C_2Cl_4 + 2 Na_2CO_3 + 3 H_2O_2 + 2 H_2O \leftrightarrow 2CO_2 + 4 NaCl + 4 H_2O + 2 H_2CO_3$
- **Free Radical Oxidation:**
 - Peroxyhydroxyl Radical ($HO_2\bullet$)
 - Hydroxyl Radical ($OH\bullet$)
 - Superoxide Radical ($O_2\bullet$)

Figure 1. Surface-Mediated Oxidation is responsible for the majority of RegenOx contaminant destruction. This process takes place in two stages. First, the RegenOx activator complex coats the subsurface. Second, the oxidizer complex and contaminant react with the activator complex surface destroying the contaminant.

Figure 1. RegenOx™ Surface-Mediated Oxidation



* Patent applied for



From Mass Reduction to Bioremediation:

RegenOx™ is an effective and rapid contaminant mass reduction technology. A single injection will remove significant amounts of target contaminants from the subsurface. Strategies employing multiple Regenox injections coupled with follow-on accelerated bioremediation can be used to treat highly contaminated sites to regulatory closure. In fact, RegenOx was designed specifically to allow for a seamless transition to low-cost accelerated bioremediation using any of Regenesis controlled release compounds.

Significant Longevity:

RegenOx has been shown to destroy contaminants for periods of up to one month.

Product Application Made Safe and Easy:

RegenOx produces minimal heat and as with all oxidants proper health and safety procedures must be followed. The necessary safety guidance accompanies all shipments of RegenOx and additional resources are available on request. Through the use of readily available, highly mobile, direct-push equipment and an array of pumps, RegenOx has been designed to be as easy to install as other Regenesis products like ORC® and HRC®.

Effective on a Wide Range of Contaminants:

RegenOx has been rigorously tested in both the laboratory and the field on petroleum hydrocarbons (aliphatics and aromatics), gasoline oxygenates (e.g., MTBE and TAME), polyaromatic hydrocarbons (e.g., naphthalene and phenanthrene) and chlorinated hydrocarbons (e.g., PCE, TCE, TCA).

Oxidant Effectiveness vs. Contaminant Type:

Table 1

Contaminant	RegenOx™	Fenton's Reagent	Permanganate	Persulfate	Activated Persulfate	Ozone
Petroleum Hydrocarbons	A	A	B	B	B	A
Benzene	A	A	D	B	B	A
MTBE	A	B	B	C	B	B
Phenols	A	A	B	C	B	A
Chlorinated Ethenes (PCE, TCE, DCE, VC)	A	A	A	B	A	A
Chlorinated Ethanes (TCA, DCA)	A	B	C	D	C	B
Polycyclic Aromatic Hydrocarbons (PAHs)	A	A	B	B	A	A
Polychlorinated Biphenyls (PCBs)	B	C	D	D	D	B
Explosives (RDX, HMX)	A	A	A	A	A	A

Based on laboratory kinetic data, thermodynamic calculations, and literature reports.

Oxidant Effectiveness Key:

- A = Short half life, low free energy (most energetically favored), most complete
- B = Intermediate half life, low free energy, intermediate degree of completion
- C = Intermediate half life, intermediate free energy, low degree of completion
- D = Long half life, high free energy (least favored), very low degree of completion



Advanced Technologies for Groundwater Resources

1011 Calle Sombra / San Clemente / California 92673-6244
Tel: 949/366-8000 / Fax: 949/366-8090 / www.regenesis.com

The original Oxygen Release Compound (ORC®) is a fine, powdery material comprised of a patented formulation of phosphate-intercalated magnesium peroxide. The intercalation or embedding of phosphates within the magnesium peroxide is Regenesi's patented, controlled-release mechanism. Upon hydration, ORC is designed to produce a controlled-release of oxygen (10% by weight) into the subsurface in accordance with the following reaction:



This process can proceed for periods of up to one year depending on site conditions. In the presence of this long-lasting oxygen source, aerobic microbes flourish - accelerating the naturally slow rates of aerobic biodegradation.

Product Benefits

By enhancing bioremediation using ORC, in-situ treatment of contaminants can result in an efficient, simple and cost-effective alternative to traditional technologies. With low capital costs, no operations and maintenance, minimal site disturbance and proven effectiveness, ORC can restore water quality and property values at a reasonable cost.

Subsurface Emplacement

- Direct – Push Injection
- Hollow Stem Augers
- Replaceable Filter Socks (existing wells)
- Excavations
- Trenches
- *Ex Situ* biophiles

Treatable Contaminants

ORC can treat a wide range of contaminants and most any aerobically degradable compound including: gasoline and fuel additives (BTEX and MTBE), diesel, kerosene, jet fuel, gas condensates, fuel oils, lubricants, bunker oil, PAHs, certain pesticides/herbicides and certain industrial solvents (alcohols and ketones).

Material Application

Most contaminated sites are treated using ORC slurry which is a prescribed and easily injectable water and ORC mixture (Figure 2). The direct-push injection of ORC slurry maximizes ORC and oxygen distribution in the subsurface increasing the range of enhanced biodegradation. ORC is dosed in pounds per vertical foot of material treated. The amount of ORC recommended depends greatly on various factors such as contaminant concentrations, oxygen sinks, groundwater flow rates and subsurface geology. It is recommended that a Regenesi Technical Services Representative be contacted for detailed design information. ORC treatment approaches or designs may consist of one, or combinations of the following: Source Area Grids, Plume Area Grids or Barriers, Excavations and Biopiles.