

**POTENTIAL TRANSPORT OF URANIUM FROM
SUBSURFACE SOILS IN CELL 6 TO THE POINT OF
INTEREST**

**FORMER SYLVANIA ELECTRIC PRODUCTS
INCORPORATED FACILITY**

HICKSVILLE, NEW YORK

SITE NUMBER V 00089-1

*Prepared by
URS Corporation
and
Envirocon, Inc.*


For:

**GTE Operations Support Incorporated
One Verizon Way
Basking Ridge, NJ 07920**

November 2006

This Potential Transport of Uranium from Subsurface Soils in Cell 6 to the Point of Interest Report has been reviewed by URS Corporation – New York, and I am in agreement with the conclusions.

URS Corporation – New York



Robert D. Brathovde, P.E.
Engineer of Record

This Potential Transport of Uranium from Subsurface Soils in Cell 6 to the Point of Interest Report has been reviewed by Professional Radiation Consulting, Inc. (PRCI), and I am in agreement with the conclusions.

Professional Radiation Consulting, Inc.

A handwritten signature in black ink, appearing to read "Shane Brightwell".

Shane Brightwell, CHP
President

This Potential Transport of Uranium from Subsurface Soils in Cell 6 to the Point of Interest Report has been reviewed by Envirocon, Inc. and I am in agreement with the conclusions.

Envirocon, Inc.

A handwritten signature in black ink, appearing to read "Richard Hafner".

Richard Hafner
Radiation Safety Officer

TABLE OF CONTENTS

EXECUTIVE SUMMARY	1
1.0 INTRODUCTION.....	3
1.1 BACKGROUND	3
1.2 OBJECTIVE.....	4
1.3 GROUND WATER STANDARDS FOR URANIUM.....	4
1.4 REPORT ORGANIZATION	5
2.0 MODEL SELECTION.....	6
2.1 PHYSICAL PROCESSES	6
2.2 SELECTED MODELS	7
2.3 DESCRIPTION OF SELECTED MODELS	7
2.3.1 <i>Transport Model</i>	7
2.3.2 <i>Desorption Model</i>	8
2.3.3 <i>Retardation Factor</i>	9
3.0 FIELD DATA FOR GROUND WATER DEPTH AND U-238 CONCENTRATIONS	10
3.1 DEPTH TO GROUND WATER	10
3.2 CONCENTRATIONS OF U-238	10
4.0 ESTIMATION OF RELEVANT MODEL PARAMETERS.....	13
4.1 SITE-SPECIFIC SOIL CHARACTERISTICS	13
4.1.1 <i>Solid/Liquid Phase Partition or Distribution Coefficient</i>	13
4.1.2 <i>Organic Content</i>	14
4.1.3 <i>Hydraulic Conductivity</i>	15
4.1.4 <i>Porosity</i>	15
4.1.5 <i>Bulk Density</i>	15
4.2 RADIOACTIVE DECAY.....	15
4.3 HYDRAULIC GRADIENT	16
4.4 DISPERSIVITY	17
4.5 EFFECTIVE AVERAGE AQUIFER THICKNESS	17
4.6 U-238 CONTAMINATION IN RESIDUAL SOILS AT SOURCE.....	18
4.6.1 <i>U-238 Concentration in Soils at Source</i>	18
4.6.2 <i>Length and Width of U-238-impacted Soils at Source</i>	20
4.7 PRECIPITATION, RECHARGE, AND INFILTRATION.....	20
4.7.1 <i>Precipitation</i>	21
4.7.2 <i>Recharge</i>	21
4.7.3 <i>Infiltration</i>	22
5.0 BASELINE SIMULATION SCENARIO.....	23
6.0 CONCLUSION.....	25
7.0 REFERENCES	27

TABLES

3-1	Observed U-238 Concentrations in Select Monitoring Wells and Profiles	11
4-1	Weighted Average Concentrations of U-238 in Soils at Source, Cell 6.....	19
4-2	Estimated, Reported, and Adopted Rates of Annual Recharge	22
4-3	Estimated Rates of Annual Infiltration	22
5-1	Input Model Parameters.....	24
6-1	Result of Ground Water Transport Analysis	26

FIGURES

1	Plan View—Potential Uranium Transport from Series U Subcells of Cell 6
2	Cross-Sectional View—Potential Uranium Transport from Series U Subcells of Cell 6
3	Location of Referenced Monitoring Wells, Profiles, and Borings

APPENDICES

A	Radiometric and Mass Units and MCLs for Uranium and U-238
B	Comparative Evaluation of Diffusion and Dispersion
C	Evaluation of Applicable Ground Water Transport Models
D	Description of MULTIMED Model
E	U-238 Transport Assuming Paved Cell Surface
F	Boring Logs
G	Hydraulic Gradient and Length of Flow Path
H	Volume and Mass Calculations for Residual Soils

The Boring Logs, Appendix F, are presented on the enclosed CD which also includes a complete electronic copy of the remainder of this report.

EXECUTIVE SUMMARY

Under the New York State Department of Environmental Conservation (NYSDEC) Voluntary Cleanup Program, GTE Operations Support Incorporated (GTEOSI) conducted soil investigations and completed Phase 1 of a soil remediation program at the Former Sylvania Electric Products Incorporated (Sylvania) Facility, Hicksville, New York Site (the Site). During these remediation activities, soils above the cleanup level of 100 picoCuries per gram (pCi/g) of total uranium were excavated and replaced with clean fill. In certain portions (cells) of the Site, residual soils remain in limited areas at depths below the engineered excavation limits, but above the water table, with low levels of uranium (i.e., total uranium). Although these levels are generally below the soil cleanup levels, GTEOSI asked URS and Envirocon to conduct a preliminary study to evaluate whether these residual levels would, if mobilized by percolating rainwater, exceed the U.S. Environmental Protection Agency (USEPA) maximum contaminant level (MCL) for total uranium in drinking water after eventual transport to a Site boundary. This Report discusses the methodology and results of this study related to the levels of uranium in residual soils in Cell 6.

After a review of several numerical and analytical models (Appendix C), the MULTIMED model (USEPA, 1996a) was selected to simulate the ground water transport of uranium. This model has the capability to account for dispersion in three dimensions, retardation, source depletion, and dilution due to recharge by infiltration along the path of ground water transport. It assumes that a dominant direction of ground water transport can be identified along with the dimensions of the contaminated area and the concentration of uranium in infiltrating rainwater desorbed from contaminated soils and entering the water table. A separate desorption model, which is based on linear equilibrium conditions between concentrations in the liquid and solid phases, was used to estimate the concentration entering the water table.

Detailed soil analytical data for the Site were collected and are available for the uranium isotope, U-238. Therefore, uranium-238 (U-238) is used as an indicator for the transport of uranium. The U-238 concentration in soils used as input for the desorption model was selected from the set of subcells with the highest weighted average concentration in Cell 6, specifically the series U subcells with an estimated weighted average concentration of 8.87 pCi/g. (see Figure 1). This estimated weighted average concentration is higher than the estimated weighted average U-238 concentration in the adjacent subcells (subcell series Q and R). Series U subcells in Cell 1 are located immediately upgradient of series U subcells in Cell 6. Therefore, potential transport of U-238 from series U subcells in Cell 1 was also considered in conjunction with the transport from U series subcells in Cell 6. The weighted average concentration in series U subcells in Cell 1 was used to estimate the U-238 concentration entering the water table from these subcells in Cell 1. The estimated weighted average concentrations of U-238 in the series U subcells in Cell 1 is 13.79 pCi/g.

Simulations for U-238 transport using the MULTIMED model were conducted using reasonably conservative assumptions and model input parameters supported by available Site-specific data and commonly accepted literature values. Site-specific values were used for partition coefficient (K_d), hydraulic conductivity (K), porosity (ϕ), and bulk density (ρ_b). The partition coefficient values were obtained from laboratory analysis of several soil samples collected at varying depths from several locations around the Site. The values of the other three parameters (K , ϕ , and ρ_b)

were obtained from laboratory analysis of several samples taken from a bore hole drilled in the vicinity of Cell 1, which is located on the northeast corner of Cell 6. Other parameters derived from Site-specific information include source dimensions, U-238 concentration in residual soils, direction of dominant ground water flow, and hydraulic gradient. The parameters that are based on literature values include recharge, infiltration, dispersivities, and effective aquifer thickness.

A baseline scenario was simulated using a vertical plane rectangular patch source configuration and assuming that the area occupied by series U subcells in Cell 6 and Cell 1 remains unpaved or undeveloped. This baseline scenario indicated a maximum U-238 concentration of approximately 11.0 picoCuries per liter (pCi/L) of U-238 in ground water at the southern Site boundary. This predicted concentration of 11.0 pCi/L is close to the lower limit of the range of MCL for U-238 (i.e., 10 to 22.5 pCi/L).

Because it is likely that the area occupied by Series U subcells in Cell 6 and Cell 1 may be developed in future and paved or covered with buildings, an additional simulation was performed to examine the effect of this condition. In this simulation, infiltration through the residual soils containing uranium is significantly reduced. The result of this simulation indicates much smaller concentrations of U-238 at the southern Site boundary (see Appendix E).

Because there is considerable variation in measured U-238 concentrations in the data collected, and the concentrations at different locations and depths include different and indeterminate degrees of dilution due to mixing with ambient ground water flow, reliable data for the calibration or “benchmarking” of a uranium transport model are not available. However, predicted U-238 concentration for the aforementioned baseline scenario is similar to the observed concentrations in downgradient monitoring wells and profiles. This suggests that the adopted model parameters are reasonable.

The results of this study indicate that future concentrations of U-238 or total uranium in ground water at the southern Site boundary associated with the uranium concentrations in residual soils in Cell 6 are within the range of MCLs for drinking water.

1.0 INTRODUCTION

1.1 BACKGROUND

This report documents the method and results of ground water transport modeling at the Site. While the former Site is currently subdivided into three lots known as 140, 100 and 70 Cantiague Rock Road, it was a single site when operated by Sylvania in the 1950s and 1960s. Beginning in 1952, Sylvania used the Site to fulfill contracts with the U.S. Atomic Energy Commission (AEC) and the AEC's prime contractors for the production of nuclear fuel elements and components comprised of thorium, natural and enriched uranium, and aluminum alloys. Residual soil contamination created by operations conducted in support of these contracts includes uranium (U-238, U-235, and U-234).

Previous concurrence between NYSDEC and GTEOSI under Voluntary Cleanup Agreement, Site V-00089-1, Index W1-0903-01-12, established a cleanup level of 100 pCi/g of total uranium for soils at the Site. In this report, the words total uranium and uranium are used interchangeably and refer to all uranium isotopes. The above cleanup level was selected because it provides appropriate safety from the radiological and toxicological hazards of uranium for future users of the property if the remediated Site were released without restriction. To comply with this Agreement, most of the soils within the Site area with total uranium concentrations above the cleanup level were excavated and replaced with clean fill. However, residual soils remain with small amounts of uranium (i.e., generally below cleanup levels) in limited areas at depths below the engineered excavation limits in Cell 6 and Cell 1.

Rather than performing a chemical analysis for total uranium during remediation, the State authorized analysis for specific isotopes at the Site. This approved methodology was adopted because of the ease and sensitivity of the radiometric method and because it provided the ability to analyze for enriched uranium. Since information on uranium contamination in residual soils is available in terms of U-238 concentrations, the U-238 isotope is used as an indicator of the transport of uranium in this study (see Appendix A).

At the Site, isotopic uranium activities as a percent of the total uranium observed in Cell 6 (average for 70 samples) were U-238 \approx 49%; U-234 \approx 49%; and U-235 (and other isotopes) \approx 2%, while in Cell 1 (average for 44 samples) the percentages were U-238 \approx 49%; U-234 \approx 48%; and U-235 (and other isotopes) \approx 3%. Therefore, the concentration of total uranium in soils in Cell 1 and Cell 6 is considered to be two times the measured concentration for U-238. For the transport analysis (for U-238) included in this study, the results for U-238 were adjusted by a factor of two to reflect the approximate concentration of total uranium.

For Site management and excavation control, the area of interest was divided into cells, and soil removal and replacement were conducted on a cell-by-cell basis. To further facilitate remediation and monitoring of contamination in residual soils, each cell was divided into several series of smaller subcells. Cell 6 is divided into three series of subcells, Q, R and U. The subcells within Cell 6 include Q06 to Q11 in series Q, R06 to R11 in series R, and U08 to U11 in series U. Residual soils in series U subcells in Cell 6 were found to contain relatively higher concentrations of U-238 compared to subcells in series Q and R.

During the Phase I remediation, the other cell identified with residual soils containing small amounts of uranium that had required additional study was Cell 1 as reported in *Potential Transport of Uranium from Subsurface Soils in Cell 1 to the Point of Interest* (October 2006). Subcells U04, U05, U06 and U07 within Cell 1 are directly upgradient of the U-series subcells of Cell 6. Therefore, these four subcells in series U of Cell 1 are also relevant to potential transport of uranium-238 (U-238) from Cell 6 (Figure 1) and were included in the Cell 6 analysis.

Identified concentrations of U-238 in residual soils, below the engineered excavation limits to a depth of approximately 64 feet (ft) below ground surface (bgs) vary from 13.66 pCi/g in subcell U07 to 20.26 pCi/g in subcell U06 of Cell 6 and 28.79 pCi/g in subcell U05 of Cell 1. The investigative soil borings were stopped approximately five to ten ft above the water table to prevent the introduction of potentially impacted soils or water from the unsaturated soil zone into the ground water environment.

1.2 OBJECTIVE

The objective of this preliminary modeling study is to understand and quantify the risk, if any, due to ground water contamination associated with uranium in residual soils by way of potential migration to ground water and eventual transport to the intersection with a Site boundary (Figures 1 and 2). Potential risk of ground water contamination is evaluated by comparison of predicted ground water contamination at the point of interest with the maximum permissible contaminant level (MCL) of uranium for drinking water established by the USEPA.

1.3 GROUND WATER STANDARDS FOR URANIUM

The USEPA regulates uranium in drinking water under the Safe Drinking Water Act, with MCLs published in Title 40 Code of Federal Regulations (CFR), Part 141. Uranium is a naturally occurring radioactive element and a heavy metal, and the MCL reflects consideration of both the chemical and radiological toxicities. The USEPA MCL for total uranium was set at 30 microgram/liter ($\mu\text{g/L}$) with an effective date of December 8, 2003 (USEPA, 2000a and 2002). The NYSDEC has adopted this MCL for uranium as an appropriate goal for evaluating the impacts of the contaminant on ground water at cleanup sites in New York.

For comparison to the MCL, it is necessary to convert the radiometric or activity measurements (picoCuries or pCi) of specific isotopes to the mass units of the MCL (microgram or μg). In this analysis, the range of conversion factors, 0.67 to 1.5 pCi/ μg , recommended by USEPA for total uranium was considered (USEPA, 2002a and 2002b). Applicable to a variable isotopic mix of natural uranium, this range resulted in an equivalent MCL range of 20 to 45 pCi/L for total uranium. Based on the proportions of uranium isotopes on an activity basis measured in the soils in Cell 1 (see Subsection 4.1.1), this range of MCL for total uranium (20 to 45 pCi/L) is expressed as 10 to 22.5 pCi/L for U-238 and 10 to 22.5 pCi/L for U-234 (MCL for U-235 being less than 0.5 pCi/L). Thus, the cleanup target of 30 $\mu\text{g/L}$ of total uranium in drinking water is interpreted as a range of 10 to 22.5 pCi/L of U-238 in ground water in this analysis (see Appendix A).

Data collected from ground water close to the water table and at various depths below the water table at the Site indicated either non-detect or relatively low levels below the range of MCL of

U-238 in most monitoring wells and profiles. Exceptions are an unfiltered sample from monitoring well MW-2 collected on March 15, 2003, and field-filtered samples (analyzed in April-June 2005) from two profiles, P-103 and P-107, drilled and sampled in April and May, 2005 (see Section 3).

1.4 REPORT ORGANIZATION

This report is organized in seven sections as described below:

Section 1 (Introduction) describes the Site background, objective of the study, and relevant ground water standard for uranium and U-238.

Section 2 (Model Selection) describes relevant physical processes and the models selected to simulate those processes.

Section 3 (Field Data for Ground Water Depth and U-238 Concentrations) summarizes observed data for depth to ground water, U-238 concentrations, and their relevance to model development.

Section 4 (Estimation of Relevant Model Parameters) includes the process and sources for estimating different model parameters.

Section 5 (Baseline Simulation Scenario) includes description of the baseline scenario and model result for the baseline scenario.

Section 6 (Conclusion) summarizes the results of the study.

Section 7 (References) includes a list of references used in the study.

Relevant details of models evaluated for the study along with a list of relevant references, back-up material for the justification of specific items of information used in the analysis, additional model simulation assuming paved surface of subcells, and the logs of the boreholes from which soil samples were taken for laboratory analyses are included in the appendices.

2.0 MODEL SELECTION

The physical processes that govern the fate and transport of uranium at the Site and provide the basis for model selection are described in the following subsection.

2.1 PHYSICAL PROCESSES

The rainwater infiltrating through a column of soil with U-238 contamination would dissolve (desorb) a portion of the U-238 adsorbed to the soils and transport it through the unsaturated soil column (known as the vadose zone) down to the water table. At the Site, U-238 in residual soils has been detected at various depths below the engineered excavation limits encountered during the Phase I soil remediation program down to approximately five to ten ft above the water table. The concentrations of U-238 in these residual soils are known. Since soil in the area above the residual soils was removed and replaced with clean soil, detailed modeling of the processes related to transport into the vadose zone has little relevance.

In most field situations, the transport from the vadose zone to the water table would occur under partially saturated conditions. This transport is generally not a steady state process. But, for the sake of simplicity and conservatism, it is assumed in the model that sufficient soil moisture is available and the exchange of contamination from soils to water occurs under equilibrium conditions corresponding to the average concentration in subcells in Cell 6 and Cell 1. As such, the infiltrating water continuously receives a portion of the U-238 from the soils. Due to the exchange of U-238 from soil to ground water, the soil concentration would be reduced from year to year. Thus, the vadose soil zone is a continuous source with gradually diminishing concentrations of U-238 available for transport into the saturated zone. In this analysis, however, it is assumed that the source concentration remains constant and does not deplete with time.

The transport of U-238 in the saturated zone is controlled primarily by the amount of contaminant present in the soils at the source; the rate of release from the source; and hydrologic factors such as dispersion (Subsection 4.4), advection (i.e., ground water flow velocity), dilution, and adsorption/desorption (Subsection 4.1.1). A brief description of the relevance of such processes to the present study is included in the following paragraphs.

Chemical Speciation

Chemical speciation is not relevant to this study because transport of U-238 (an isotope of uranium) is used as an indicator of the concentrations of total uranium.

Diffusion

In ground water transport modeling, the contribution of diffusion is usually accounted for by adding the molecular diffusion coefficient for the contaminant of concern to the dispersion coefficients. However, the molecular diffusion coefficient for total uranium may be several orders of magnitude smaller than the dispersion coefficients (see Appendix B). Therefore, the contribution of diffusion is not considered significant and is not incorporated in this study. So far as the dispersion of contaminants is concerned, this is a conservative assumption.

Relevant Processes

In view of the above, relevant processes governing the fate and transport of U-238 from the soils to the ground water environment at the Site include the following (see Figures 1 and 2):

- Transfer of U-238 contamination from soils to water due to desorption with infiltrating rainwater;
- Dilution of U-238 concentrations reaching the water table with ambient ground water flow beneath the cell; and
- Transport of the dissolved concentrations in ground water beneath the cell to the point of interest through the saturated soil zone with dispersion, retardation, radioactive decay, dilution due to ground water recharge, and dilution with ambient ground water flow.

The criteria for model selection and brief descriptions of ground water transport models evaluated to simulate the above processes are described in Appendix C. The specific models adopted for the study are described in Subsection 2.2.

2.2 SELECTED MODELS

The selected models include the main ground water transport model and a suite of supplementary models to estimate some of the input parameters for the transport model.

The descriptions of ground water transport models included in Appendix C suggest that the effort required and accuracy of prediction provided by a sophisticated finite-difference or finite-element model or suite of models may not be commensurate or possible with available Site-specific information and the objective of this analysis. Instead, a less complex and reasonably conservative approach is appropriate.

The comparative evaluation of different modeling approaches included in Appendix C indicates that the MULTIMED model (USEPA, 1996a) captures the essential processes associated with the transport of U-238 or total uranium and is expected to predict reasonably conservative concentrations at a specified downgradient location. Therefore, this model is selected for a preliminary and conservative analysis of the fate and transport of U-238.

The MULTIMED model (like most other models) requires supplementary models to estimate the source concentration for ground water transport and retardation factor. Brief descriptions of the MULTIMED model and supplementary models used to estimate the concentration at the ground water source and retardation factor are included in Subsection 2.3.

2.3 DESCRIPTION OF SELECTED MODELS

Brief descriptions of the models selected for this analysis are included in the following subsections.

2.3.1 Transport Model

As indicated in Subsection 2.2, the transport model selected for this study is the MULTIMED model (USEPA, 1996a). The capabilities of the MULTIMED model are described in

Appendix D. In particular, this model can simulate dilution due to recharge by infiltration along the path of ground water transport. This simulation option assumes that the recharge and resulting dilution are uniformly distributed throughout the effective thickness of the aquifer.

In the case of the Site, the area with potentially contaminated soils was divided into several cells. Each cell was divided into several series of subcells and soil concentrations were measured at different spatial locations in each subcell. In this analysis, the series of subcells with maximum soil concentration of U-238 is used to estimate the concentration in the infiltrating water entering the water table. U-238 concentration in the soil in each subcell is assumed to be uniformly distributed within the width of the subcell nearly perpendicular to the direction of dominant ground water flow. Contaminant concentrations in the soils in the vadose zone at the source are discussed in Subsection 4.6.

Due to desorption by infiltrating water, a portion of the contamination in residual soils in the vadose zone reaches the water table. After its entry into the saturated zone, this dissolved contamination mixes and moves with ambient ground water along the bottom of the contributing subcells. During this transport, it undergoes some dilution due to mixing with ambient ground water and reaches the vertical cross section of the aquifer at the downgradient edge of the contributing subcells. The soils in the area downgradient of the above-mentioned contributing subcells are relatively clean in the model and at the Site. Thus, infiltrating rainwater entering the water table through the vadose zone downgradient of the edge of the contributing subcells is relatively clean and is referred to as recharge (see Figure 2).

Within the abovementioned vertical cross section at the downgradient edge of the contributing subcells, the diluted contamination is distributed down to a depth, designated as the mixing zone depth. This vertical cross section in the saturated zone with its width equal to the width of the subcells and its depth equal to the mixing zone depth constitutes a vertical plane (designated as rectangular patch) source for ground water transport in the model domain.

The rectangular patch source is a vertical plane of finite width and depth located in the saturated zone at the downgradient edge of the relevant series of subcells in Cell 6 (see Figure 2). The concentration in ground water at every point along the vertical plane at the source is the same and does not undergo reduction with time. The effect of source depletion should be progressive reduction in the concentrations at the point of interest with time. Since modeling with a rectangular patch source does not provide for source reduction, the predicted concentration is overly conservative, remaining at a constant level and extending impacts unrealistically into the future.

2.3.2 Desorption Model

The desorption model is used to estimate the concentration of infiltrating water entering the water table beneath the series of subcells with residual contamination in soils in the vadose zone. It is based on the following linear equilibrium model (USEPA, 1988; ANL, 2001):

$$\text{Eq. (1)} \quad C = S / K_{du}$$

where, C = equilibrium concentration in water (pCi/ml);
 S = mass (or activity in pCi/g) adsorbed per unit mass of soil; and

K_{du} = partition/distribution coefficient (for the unsaturated zone) in milliliters per gram (ml/g).

This model assumes that the mass (or activity) adsorbed per unit mass of the soils (pCi/g) is in equilibrium with the liquid phase concentration (pCi/ml), and the relationship between concentrations in the solid (pCi/g) and liquid (pCi/ml) phases is linear. The parameter K_{du} is assumed to lump the effects of most partitioning processes (e.g., soil texture, soil grain size, soil classification, pH of ground water, and organic carbon content of the soil) into one value. The parameter K_d or K_{du} is discussed in more detail in Subsection 4.1.1.

Using the linear equilibrium model (Eq. 1), the following expression is developed to estimate the concentration in infiltrating water corresponding to the average concentration in the soil column in contributing subcells above the water table (IPCB, 2004):

Eq. (2)
$$C_i = (C_s \rho_b) / (\phi_w + \rho_b K_{du})$$

where, C_i = concentration in infiltrating water in the vadose zone (pCi/ml) entering the water table beneath the subcells;

C_s = average concentration in soils in the contributing subcells (pCi/g);

ρ_b = bulk density of soils in grams per cubic centimeter (g/cc); and

ϕ_w = water-filled porosity in the unsaturated soil zone (unitless).

Eq. 2 is designated as the desorption model. The concentration in infiltrating water, C_i , is used as input to the MULTIMED model. In this model, the ground water source for downgradient transport is a vertical plane located within the saturated zone at the downgradient edge of the subcells with U-238 in residual soils. With the concentration in infiltrating water reaching the water table as input, the MULTIMED model computes the concentration, C_0 , at the ground water source after initial mixing of ambient ground water beneath the subcells with residual contamination in soils.

2.3.3 Retardation Factor

One of the effects of the partition/distribution coefficient on contaminants is to retard the rate (velocity) of transport in ground water. The retardation factor, R (unitless), used as input in the transport model, is computed as follows (USEPA, 1996a):

Eq. (3)
$$R = 1 + (\rho_b K_d / \phi)$$

where ρ_b = bulk density of soils in grams per cubic centimeter (g/cc);

ϕ = effective porosity in the saturated zone (unitless); and

K_d = partition/distribution coefficient for the saturated zone (ml/g).

Any other consistent set of units may also be used for the variables in Eq. 1-3.

3.0 FIELD DATA FOR GROUND WATER DEPTH AND U-238 CONCENTRATIONS

3.1 DEPTH TO GROUND WATER

Ground surface elevations from Cell 6 to the point of interest on the southern Site boundary vary from approximately 145.23 ft to 142.96 ft. In the vicinity of the Site, the water table was observed between 72 and 74 ft bgs.

3.2 CONCENTRATIONS OF U-238

Field data for U-238 concentrations are available for 112 ground water samples from 12 monitoring wells and 45 ground water profiles. Most of the measured values of U-238 concentrations in ground water were either non-detect or below the MCL. The data for those samples collected in 2002 and 2003 that exceeded 1.0 pCi/L are abstracted in Table 3-1. In addition, data based on analysis of field-filtered samples from three recent profiles are also included (e-mail communications with MPI, June-July, 2005) (see Figure 3). The term 'field-filtered sample' included in footnotes b and c to Table 3-1 indicates that the particulate matter in the ground water sample was filtered out before analyzing the filtrate for U-238 concentration.

Table 3-1. Observed U-238 Concentrations in Select Monitoring Wells and Profiles

Profile or Monitoring Well	Approx. Location (See Figure 4)	Depth (bgs) (ft)	Date of Sampling	U-238 Concentration (pCi/L)
P-2 ^a	On the 140 Property, subcell W10, approximately 113 ft east of the 100 Building	98.8	October- December, 2002	1.27 (+ or – 0.44)
P-6 ^a	On the 100 Property, subcell P23, approximately 90 ft south of the southeast corner of the 100 Building	82.8	October- December, 2002	2.43 (+ or – 0.78)
P-28 ^b	On the Golf Course Driving Range, subcell 22A, approximately 63 ft east of the 100 Property	87.02	May 3, 2003	1.03 (+ or – 0.38)
P-35 ^a	On the 70 Property, subcell W73, approximately 85 ft north of the 70 Building	87.2	July 9, 2003	1.43 (+ or – 0.48)
MW-01 ^a	On the 70 Property, border of subcells F22 and F23, approximately 58 ft north of the 70 Building	58-78 (screened interval)	March 15, 2003	2.22 (+ or – 0.72)
MW-02 ^a	On the 70 Property, subcell I22, approximately 56 ft north of the 70 Building	59-79 (screened interval)	March 15, 2003	38.3 (+ or – 8.1)
MW-12 ^a	On the 70 Property, subcell R32, approximately 13 ft northwest of southeast corner of the 70 Property	120-130 (screened interval)	March 15, 2003	1.76 (+ or – 0.60)
P-103 ^c	On the 100 Property, subcell G21, approximately 50 ft south of the 100 Building	74	April 19, 2005	26.5 (+ or – 2.9)
		84.5	April 19, 2005	3.34 (+ or – 0.62)
P-107 ^c	Located on the 140 Property, appears to straddle subcells R08 and U08, approximately 73 ft east of the 140 Building	74.30	May 16, 2005	96 (+ or – 11)
		84.30	May 16, 2005	56.3 (+ or – 5.8)
		94.30	May 17, 2005	6.1 (+ or – 1.6)
		104.30	May 17, 2005	11.6 (+ or – 2.2)
P-108 ^c	Located on the 100 Property, subcell W18, 100 ft east of the 100 Building and downgradient of Cells 1, 2, 6, and 3	84.15	May 02, 2005	0.75 (+ or – 0.28)

^aBased on analysis of an unfiltered sample.

^bBased on analysis of a field-filtered sample.

^cBased on analysis of a field-filtered sample as per MPI (e-mail communications, June-July, 2005).

As noted in Table 3-1, the maximum concentrations of U-238 detected were between 10 to 20 ft below the water table. All concentrations measured below 100 ft bgs (30 ft or more below the water table) are below or close to the lower limit of MCL for U-238 (10 to 22.5 pCi/L).

The data collected and listed in Table 3-1 indicate that there is significant variation in measured concentrations in different monitoring wells and profiles, and it is difficult to identify specific concentrations which may be used for model calibration. Additional limitations associated with this data include the following:

- The uranium found in soils existed in thin zones and not large source areas. The locations and dimensions (i.e., length, width, depth) of the uranium-impacted soils and the specific concentrations of uranium therein which may be the source of ground water concentrations shown in Table 3-1 are not known.
- It is difficult to estimate the durations of the transport of uranium through the unsaturated and saturated soil zones from the source or sources to the respective profile or monitoring well indicated in Table 3-1.
- The concentrations in ground water at the respective sources and the corresponding mixing zone and effective aquifer depths applicable to the concentrations shown in Table 3-1 are difficult to identify.
- The orientations of the ground water flow paths to various profiles and monitoring wells and other transport parameters applicable to the transport process are also not known. This is further complicated by the fact that various sources of ground water recharge and extraction operated in the Site vicinity and historically have changed over time. These changes have locally impacted ground water flow rates and directions and resulted in the concentrations shown in Table 3-1.

Because of the above-mentioned limitations, the data included in Table 3-1 are not used for a quantitative model calibration. Instead, they are used for a qualitative assessment of the model parameters and model results presented in this study.

4.0 ESTIMATION OF RELEVANT MODEL PARAMETERS

The adopted model input parameters include Site-specific parameters based on field measurements, laboratory analysis of soil samples from boreholes in the vicinity, and information available in the literature.

4.1 SITE-SPECIFIC SOIL CHARACTERISTICS

Soil samples from various locations and depths have been analyzed to estimate specific values of relevant parameters. The results of the analysis for soils in the vicinity of the Site are summarized in the following subsections.

4.1.1 Solid/Liquid Phase Partition or Distribution Coefficient

Definition

The partition or distribution coefficient (K_{du} for unsaturated or vadose zone and K_d for saturated zone) is a soil parameter which is used to assess the degree to which a chemical species will be distributed in the solid and liquid phases. It provides an indication of how rapidly an ion can move relative to the rate of ground water movement under the geochemical conditions tested (ASTM, 1990). In simpler terms, K_d is defined as the concentration of a chemical of interest in the solid phase divided by the concentration of that species in the liquid phase, at steady-state (Brookhaven National Laboratory, 1999). In this analysis, the parameter K_{du} or K_d quantifies certain sorption (adsorption/desorption) processes relevant to the transport of uranium from the soils at the Site to the point of interest.

The soils in the unsaturated zone at the Site generally consist of poorly graded or gravelly sands with little or no fines which have a group symbol of SP according to the Unified Soil Classification System (USCS) (see Appendix F). Soils in the saturated zone at the Site generally consist of poorly graded or gravelly sands with little or no fines (USCS group symbol SP) with mixtures of silty sands (USCS group symbol SM). The average reported value of K_{du} or K_d for uranium for sandy soils is 35 ml/g and generally higher average values are reported for finer materials (USEPA, 1999).

Site-specific Sampling

Usually, K_{du} or K_d values used for ground water transport modeling are obtained from literature or laboratory analysis of soil samples from a studied area. The K_{du} or K_d values for total uranium (or U-238) used for this analysis were obtained from laboratory analysis of soil samples collected from several locations at various depths around the Site using the ASTM batch equilibrium method, ASTM D4319-83 as interpreted by Severn Trent Laboratories in their Standard Operating Procedure *K_d Leaching Procedure*, revision April 19, 2004 (see locations KD1, KD2, KD3, and KD4, Figure 3).

The K_{du} or K_d values measured in laboratory analysis pertain to total uranium. However, detailed field information regarding uranium found in residual soils relates to U-238. As such, the U-238 transport analysis assumes that the values of K_{du} or K_d estimated for total uranium are applicable

to U-238 as well (see Appendix A).

Results of Laboratory Analysis

Generally, the same values of K_{du} and K_d are assumed to be applicable to both unsaturated and saturated soils. Laboratory analysis for K_{du} and K_d for soil samples from different depths at and adjacent to the Site indicated that there is appreciable variation with depth. In particular, the values for the saturated zone were lower than the values for the vadose zone.

In Cell 6, contaminated soils have been excavated and replaced with clean fill down to an average depth of approximately 23 ft bgs. Contaminated soils in Cell 1, upgradient and east of Cell 6, have been excavated and replaced with clean fill down to an average depth of approximately 21 ft bgs. The average depth down to which soils have been excavated and replaced with clean fill in series U subcells in Cell 6 and Cell 1 (i.e., subcells U04 to U11) is approximately 26 ft bgs. Laboratory analysis of six samples from various locations in the unsaturated zone in the Site vicinity from depths ranging from 30 to 42 ft bgs indicate an average Site-specific value of 5.45 ml/g for K_{du} for uranium. The range of K_{du} values for these six values from the unsaturated zone was 2.98 to 7.72 ml/g.

Laboratory analysis of seven soil samples from various locations in the saturated zone in the Site vicinity from a depth range of 70 to 110 ft bgs indicated an average value of 0.89 ml/g for K_d . The range of K_d values for these seven values from the saturated zone was 0.52 to 1.01 ml/g.

Computations for the baseline case for Cell 6 and Cell 1 were made using the average values of $K_{du} = 5.45$ and $K_d = 0.89$ ml/g for the unsaturated and saturated zones, respectively.

Implication of Site-specific K_{du} or K_d Values

A review of Site-specific K_{du} and K_d values indicates that they are generally lower than the average values reported in the literature for similar soils (i.e., sands) (USEPA, 1999).

The low (compared to literature values) Site-specific K_{du} or K_d values for uranium result in the following notable consequences so far as the transport of uranium is concerned:

- A higher equilibrium concentration of the contaminant in pore water in the subcells (see Eq. 1, Subsection 2.3.2);
- A higher concentration in infiltrating rainwater entering the water table (see Eq. 2, Subsection 2.3.2); and
- Lower retardation of the contaminant of interest (i.e., faster rate of movement of dissolved uranium with ground water) (see Eq. 3, Subsection 2.3.3).

4.1.2 Organic Content

Since Site-specific K_d or K_{du} values have been determined, organic carbon content is not required to estimate K_d or K_{du} values for this analysis.

4.1.3 Hydraulic Conductivity

Laboratory analysis of three soil samples from depths of 25 to 64 ft bgs collected from Boring KD4 (Figure 3) indicated a Site-specific geometric mean hydraulic conductivity of 1.64×10^{-2} cm/sec (i.e., 46.50 ft/day or 5171.9 m/yr). The three test results varied from 1.15×10^{-2} to 2.22×10^{-2} cm/sec (32.6 to 62.93 ft/day or 3626.6 to 7001 m/yr). While the above samples were collected from the Upper Glacial deposits, the results were consistent with reported values of the hydraulic conductivity of the Magothy Formation, which range from 27 ft/day to 150 ft/day (see Subsection 4.5) (CDM, 2003). The average value of 5171.9 m/yr (46.50 ft/day) is used for the baseline scenario simulated in this study.

4.1.4 Porosity

The three soil samples from Boring KD4 (depths of 25 to 64 ft bgs) were analyzed in the laboratory for dry unit weight and specific gravity. The porosity of the soils is estimated using the measured values of dry unit weight and specific gravity. The estimated values of porosity for the three samples vary from 0.386 to 0.413 with an average value of 0.39 for soils in the vicinity of Cell 6 and Cell 1. For unconsolidated sediments coarser than silt size, effective porosity can be less than total porosity by approximately 2% to 5%. Typical values of effective porosity for fine to coarse sands reported in the literature vary from 0.10 to 0.35 (USEPA, 2000). The reported mean values of specific yield (which is generally equal to the effective porosity) for fine to coarse sands are between 0.30 and 0.33 (USEPA, 1985).

In view of the above, the effective soil porosity (ϕ) under saturated conditions is taken to be 0.30.

Default soil porosity under unsaturated soil conditions may vary from 0.15 at the ground surface to 0.30 for subsurface conditions and from 0.18 for sand to 0.20 for gravel (IPCB, 2005). Use of an empirical equation included in Tiered Approach to Corrective Action Objectives (TACO) (IPCB, 2004) suggests values in the range of approximately 0.16 to 0.19.

In view of the above, a value of 0.18 is adopted for porosity under unsaturated soil conditions (ϕ_w). Minor variations in the adopted value of porosity under unsaturated conditions (e.g., in the approximate range from 0.17 to 0.20) are not expected to have significant effect on the results of this analysis.

4.1.5 Bulk Density

Based on the results of the aforementioned laboratory tests of the three soil samples for dry unit weight, the bulk density of soils in the vicinity of Cell 6 and Cell 1 is estimated to vary from 1.55 to 1.63 grams per cubic centimeter (g/cc) with an average of 1.60 g/cc. The average value of 1.60 g/cc is used in this analysis.

4.2 RADIOACTIVE DECAY

In most environmental transport models, the term decay is defined by the first-order decay coefficient which is a function of the half life of the constituent. U-238 has a relatively long half life of 4.47×10^9 years resulting in little decrease in U-238 concentrations due to natural decay

during the time period of interest in this study (www.ornl.gov/sci/isotopes). The other natural isotopes of uranium also have relatively long half lives (i.e., half life of U-234 = $2.46\text{E}+05$ years and half life of U-235 = $7.04\text{E}+08$ years). The longer half life (i.e., half life of U-238) with the corresponding lower decay coefficient of $0.155\text{E}-09 \text{ year}^{-1}$, is used in this study to analyze the transport of U-238.

4.3 HYDRAULIC GRADIENT

The selected ground water transport model simulates the propagation of concentration along a specified direction of ground water flow, i.e., along a vertical profile of the aquifer with distinct localized hydraulic gradient. By definition, this localized hydraulic gradient (unitless) for ground water in unconfined situations is the slope of the water table between two points of interest or between points closest to the two points of interest on the above-mentioned vertical profile.

The dominant on-Site ground water flow direction and localized hydraulic gradient were identified from available field data. While the regional ground water flow direction in the vicinity of the Site is towards the south, small areas may have localized variation. This localized variation is important for ground water transport modeling within the relatively short transport distance considered in this study (see Figure 1).

For Cell 6, the source in ground water is assumed to be located at the downgradient edge of subcell U11 (see Subsection 4.6). For Cell 1, the source in ground water is assumed to be located at the downgradient edge of subcell U07 (see Subsection 4.6). Thus, the localized hydraulic gradient applicable to the transport of dissolved uranium from subcells in series U in Cell 6 and Cell 1 to the point of interest is estimated by the difference in ground water levels in the monitoring wells closest to the downgradient edge of subcell series U of Cell 6 and Cell 1 and the point of interest.

To estimate the localized hydraulic gradient, ground water elevations were used from three on-Site monitoring wells for two monitoring events. The localized hydraulic gradient was taken to be the average of values computed from ground water elevations measured during the December 2002 (URS Corporation, unpublished data) and March 2003 sampling events for monitoring wells MW-07, MW-11, and MW-09. Monitoring well MW-07 is located downgradient of Cell 1 and Cell 6 and MW-09 and MW-11 are located further downgradient near the southern Site boundary (see Figure 3). These three monitoring wells were selected because they define the plane representing the water table in the area between Cell 6 and Cell 1 and the southern Site boundary.

Three different approaches were used to estimate the average hydraulic gradient using observed ground water elevations for the aforementioned monitoring wells, MW-07, MW-09, and MW-11 (see Appendix G). The estimated average hydraulic gradients using the three approaches are 0.00049, 0.00054, and 0.00056, respectively. To be conservative, the highest value of 0.00056 is used in this study.

The length of the transport distance from the downgradient edge of subcell U11 of Cell 6 to its intersection with the southern Site boundary is estimated to be 490 ft (149 m). The length of the transport distance from the downgradient edge of subcell U07 of Cell 1 to its intersection with the southern Site boundary is estimated to be 579 ft (176.5 m).

4.4 DISPERSIVITY

The spreading of a contaminant dissolved in ground water beyond the region it is expected to occupy due to average flow alone is called dispersion. It is quantified by a factor called the dispersion coefficient. The dispersion coefficient is a function of a soil property known as dispersivity and the velocity of ground water through soil pores.

There is large variation in values of dispersivities reported in the literature (e.g., Maidment, 2003; USEPA, 1985). Based on commonly used practice, the longitudinal (α_x), transverse (α_y), and vertical (α_z) dispersivities for this analysis are estimated using the following equations (USEPA, 1996a; IPCB, 2004; ASTM, 1995), i.e.,

Eq. (9) $(\alpha_x) = 0.1 x$

Eq. (10) $(\alpha_y) = (\alpha_x)/3$ and

Eq. (11) $(\alpha_z) = 0.056 (\alpha_x)$,

where x = the length of the ground water flow path (m).

These equations are based on a review of a range of values reported in the literature, are generally accepted for screening level (which are normally considered to be conservative and preliminary) analyses, and are included in several commonly used industry guides (e.g., IPCB, 2004; ASTM, 1995). In addition, they are included as 'other commonly used relationships' in several other models (e.g., USEPA, 1996b; USEPA, 2000b).

4.5 EFFECTIVE AVERAGE AQUIFER THICKNESS

Three major aquifers exist in the Site vicinity (i.e., Upper Glacial at the top underlain in order by the Magothy, and Lloyd Aquifers). These aquifers are interconnected to various degrees and the combined depth is fairly large (i.e., more than 600 ft) (Isbister, 1966). Recent Site-specific ground water investigations indicate that the Upper Glacial deposits in the vicinity extend to approximately 75 ft bgs. The water table was observed between 71 to 74 ft bgs, which is near the contact between the Upper Glacial and Magothy Aquifer. Thus, the saturated thickness of interest for this study is primarily within the Magothy Aquifer. The Magothy Aquifer was encountered during recent area investigations from approximately 75 ft bgs to as deep as 532 ft bgs (as noted by Malcolm Pirnie during their ground water investigation in 2004 - 2005).

During ground water investigations, silt and clay lenses were encountered beneath and downgradient of the Site. This may limit the effective aquifer thickness available for contaminant transport. Also, the vertical dispersivity of the medium is relatively low (see Sub Section 4.4 and Table 5-1). These factors are expected to limit the depth of the zone of effective U-238 transport and effective thickness of the aquifer relevant to the transport of U-238 with ground water.

A review of the data for profiles downgradient or south and southwest of Cell 1 (i.e., P-103 and P-108) included in Table 3-1 indicates relatively low concentrations of U-238 at a depth of 84.5 ft bgs (or approximately 10 ft below the water table). In addition, there is significant reduction in U-238 concentrations with depth in Profile P-107 which is also located within Cell 6, downgradient of Cell 1. This suggests that a relatively small portion of the total aquifer depth may be effective along the path of any appreciable transport of U-238 from Cell 6 and Cell 1.

In view of the above, a relatively small effective aquifer thickness of 30 ft (i.e., extending to approximately 102 to 104 ft bgs) is used. The mixing zone depth corresponding to this effective aquifer thickness is internally calculated in the MULTIMED model using an analytical equation (IPCB, 2004; and USEPA, 1996a).

4.6 U-238 CONTAMINATION IN RESIDUAL SOILS AT SOURCE

The characteristics of the U-238 contamination at the source in soils in series U subcells in Cell 6 and Cell 1 are described in the following subsections.

4.6.1 U-238 Concentration in Soils at Source

Measured concentrations of U-238 are available to a depth of approximately 64 ft bgs at various spatial locations in several borings in Cell 6 and Cell 1. Because of different spatial locations of the borings, several values are available at each depth.

Cell 6 is divided into three series (rows) of subcells, Q, R, and U (Figure 1). Each series of subcells constitutes a linear segment for U-238 or total uranium transport to the point of interest. The contamination originating from soils at different depths in a particular vertical column or subcell is likely to appear as mixed dissolved concentration at the bottom of the column near the water table. This mixed dissolved concentration from all such vertical columns or subcells would be transported downgradient with ambient ground water flow along the length of the series parallel to the direction of ground water flow. Ultimately, this mixed concentration from all columns or subcells in a series would appear at the downgradient edge of the contaminated subcells. The effect of mixing during ground water transport along the length of the subcells is internally computed in the MULTIMED model. Thus, the source concentration of dissolved U-238 or total uranium in ground water in the saturated zone appearing at the downgradient edge of a series of subcells would correspond to the average of depth-wise, width-wise, and length-wise soil concentrations in that series.

Cell 6 includes six subcells in each of series Q and R and four subcells in series U (see Figure 3). The weighted average soil concentration of U-238 in subcells in series U (i.e., subcells U08, U09, U10, and U11) in Cell 6 is higher than the weighted average concentration of U-238 in subcells in series Q (i.e., subcells Q06 to Q11) or subcells in series R (i.e., subcells R06 to R11) (see Figures 1 and 3 and Appendix H). To be conservative, the highest weighted average concentration in soils in subcells U08, U09, U10, and U11 in series U is assumed to be the source concentration in soils in Cell 6.

Subcells U04, U05, U06, and U07 in series U in Cell 1 constitute the upgradient continuation of subcells U08, U09, U10, and U11 in series U of Cell 6 (see Figure 1). The U-238 desorbed from the abovementioned subcells of Cell 1 would likely be transported along the same ground water flow path as the concentration desorbed from series U subcells of Cell 6. Residual soil concentrations in the above subcells in Cell 1 (i.e., U04 to U07) are used to estimate the source concentration in soils to analyze potential transport of U-238 from series U subcells in Cell 1.

The weighted average concentrations of U-238 in subcells U08 to U11 in series U in Cell 6 and U04 to U07 in Cell 1 are estimated from measured concentrations in soils at various depths

within the areas occupied by these subcells. The computations are made using the EVS software (C Tech Development Corporation, 2005). The EVS software uses a three-dimensional interpolation algorithm to estimate concentrations at various points within the specified model domain based on relative proximity of each point from the surrounding points where measured values are available. The resulting grid or contours are used to estimate the volume or mass of soils and mass of contaminants represented by each point on the grid or between specified contours. This information is used to estimate the weighted average concentration in the specified model domain (e.g., an individual subcell).

Using the results of the EVS model for each subcell, the weighted average concentrations of U-238 in the soil mass at the source in Cell 6 (i.e., subcells U08 to U11) and Cell 1 (i.e., subcells U04 to U07) are estimated. These computations are made using the following equation:

$$\text{Eq. (12)} \quad X = [\sum w_i x_i] / [\sum w_i]$$

where X = weighted average concentration of U-238 (pCi/g) in subcells U08 to U11 in Cell 6 or U04 to U07 in Cell 1;

i = index identifying an individual subcell (e.g., U04, U05, etc.);

w_i = mass of soil (g) in subcell i ;

x_i = weighted average concentration (pCi/g) within subcell i as estimated by the EVS software; and

\sum = summation over all subcells from U08 to U11 in Cell 6 or U04 to U07 in Cell 1.

The information used to estimate the weighted average concentration of U-238 in the soils at the source is included in Table 4-1.

Table 4-1. Weighted Average Concentrations of U-238 in Soils at Source

Cell	Subcell	Average thickness of residual soils in subcell ^a (ft)	Mass of residual soils ^a (kg)	Weighted average U-238 concentration in subcell ^a (pCi/g)
6	U08	41.17	776,320	8.25
6	U09	48.73	933,680	12.76
6	U10	57.54	1,089,400	9.95
6	U11	57	1,081,200	4.88
Weighted average U-238 concentration in the four subcells in Cell 6 (Eq. 12) = 8.87 pCi/g				
1	U04	60.98	1,162,800	6.24
1	U05	50.85	951,900	20.31
1	U06	33.88	648,770	17.49
1	U07	34.57	650,610	14.08
Weighted average U-238 concentration in the four subcells in Cell 1 (Eq. 12) = 13.79 pCi/g				

^aEVS model output (see Appendix H).

The average of the thicknesses of residual soils with U-238 contamination at the source in Cell 6 shown in Table 4-1 is approximately 51 ft (15.58 m) and the estimated weighted average concentration of U-238 is 8.87 pCi/g. The corresponding source concentration of total uranium in soils at the source is taken to be twice the value for U-238 (i.e., a concentration of 17.74 pCi/g

of total uranium in soils at the source).

The average of the thicknesses of residual soils with U-238 contamination at the source in Cell 1 shown in Table 4-1 is approximately 45 ft (13.74 m) and the estimated weighted average concentration of U-238 is 13.79 pCi/g. The corresponding source concentration of total uranium in soils at the source is taken to be twice the value for U-238 (i.e., a concentration of 27.58 pCi/g of total uranium in soils at the source).

The desorption model (Subsection 2.3.2, Eq. 2) is used to estimate the concentration of U-238 entering the water table beneath subcell series U in Cell 6 and Cell 1 corresponding to the aforementioned concentrations in soils at the source (see Figure 2).

4.6.2 Length and Width of U-238-impacted Soils at Source

Cell 6 is not rectangular in plan (see Figure 3). The length of subcells U08 to U11 in Cell 6 along the direction of ground water flow is approximately 90 ft (27.5 m). This is the length along which desorbed U-238 enters the water table at the concentration, C_i , estimated by the desorption model (Eq. 2). The width of series U subcells in Cell 6 (i.e., U08 to U11), nearly perpendicular to the direction of dominant ground water flow, is 20 ft (6.1 m). This is the width along which desorbed U-238 enters the water table.

The length and width of subcells U04 to U07 in Cell 1 are approximately the same as in Cell 6.

Upon entry into the saturated zone, the desorbed U-238 undergoes mixing with ambient ground water as it moves along the length of the contaminated soils (i.e., subcells U08 to U11 in Cell 6 and subcells U04 to U07 in Cell 1) at source. It is assumed that there is little lateral dispersion along this length. Therefore, the width of the contaminated water that reaches the downgradient edge of the contaminated soils at source remains the same as the width of the subcells. The initial dilution along this length of transport and the mixing zone depth, H , at the downgradient edge of this length are internally computed by the MULTIMED model. Due to mixing during this transport, the concentration changes from C_i to C_0 . It is the above-mentioned width, mixing zone depth, and concentration in ground water, C_0 , at the downgradient edge of the subcells in Cell 6 and Cell 1 that constitute the physical dimensions and ground water concentration for the vertical plane source in the saturated zone in each cell used for ground water transport simulation in the MULTIMED model (see Figure 2).

4.7 PRECIPITATION, RECHARGE, AND INFILTRATION

In the MULTIMED model, the term infiltration is used to define the portion of precipitation that percolates through the impacted soil at the source and enters the water table. With greater infiltration, more contaminant is mobilized from the soil into the ground water. Recharge is defined as the portion of precipitation that percolates from the ground surface along the path of ground water transport and enters the water table as relatively fresh water (i.e., water that is not impacted by the contamination at the source). Greater recharge means more dilution of contaminant along the path of ground water transport. Infiltration or recharge is estimated as precipitation minus surface runoff and other losses applicable to the source area or domain of ground water transport. They are expressed as the volume of water percolating per unit time per

unit area of surface (i.e., m³/yr per square meter, or more commonly, m/yr).

4.7.1 Precipitation

The average annual precipitation for the period 1951-1980 at Mineola, New York is approximately 1.11 m (Gale Research Company, 1985). Based on 10 years (1994 to 2003) of daily precipitation data for Mineola, New York (with 48 missing daily values) the average annual precipitation is estimated to be 43.7 inches (1.11 m) (nrcc@cornell.edu). Mineola is approximately 7 miles west of Hicksville. This suggests that an annual average precipitation of 1.11 m is reasonable for the Site area.

4.7.2 Recharge

On an average, approximately 25 percent or more of annual precipitation is expected to infiltrate into the ground (Avon and Durbin, 1994; Donovan and Katzer, 2000). The 25 percent value is reported for arid climates. The average annual recharge in the Site vicinity, which is sub-humid to humid, is expected to be larger than 25 percent (e.g., 33 percent to 45 percent) of the average annual precipitation.

Previous studies reported in the literature have used different rates of recharge/infiltration. A report describing the Nassau County Groundwater Model (CDM, 2003) states an overall recharge rate of 51.8 percent of precipitation for the model as a whole. A qualifier is added suggesting that this amount of recharge could be slightly higher than would be expected during a normal year. This suggests that an overall recharge rate in the model domain may be approximately 50 percent of precipitation or 0.56 m/year for the region. However, in the tabulated values of recharge in the CDM (2003) report, a rate of 80 percent of precipitation is shown for Nassau County. This suggests a recharge rate of approximately 0.89 m/year for the Site area.

A USGS modeling study for Kings and Queens Counties, Long Island, New York (USGS, 1999) indicates a recharge rate of approximately 23.1 inches/year or 0.59 m/year for Nassau County.

The estimated, reported, and adopted rates of annual recharge for the Site are abstracted in Table 4-2.

Table 4-2. Estimated, Reported, and Adopted Rates of Annual Recharge

Source	Annual Recharge Rate (m/yr)
Estimated as fraction of annual precipitation (Avon and Durbin, 1994; Donovan and Katzer, 2000)	0.37 to 0.50
CDM (2003)	0.56-0.89
USGS (1999)	0.59
Adopted (along potential path of ground water transport)	0.59

The information presented in the previous paragraphs and abstracted in Table 4-2 suggests that an average recharge rate of 0.59 m/yr may be reasonably conservative for the path of ground water transport from the area occupied by Cell 6 and Cell 1 to the point of interest.

Recharge immediately below paved areas or areas occupied by buildings may be significantly lower. However, Nassau County regulations require that a system of leach basins should provide for most of the storm water runoff from a site to discharge into the subsoil even if the area is paved. This results in a greater portion of precipitation entering the ground water regime and greater net recharge.

4.7.3 Infiltration

Infiltration from unpaved source areas is taken to be the same as the recharge described in Subsection 4.7.2 (i.e., 0.59 m/yr).

If the source area occupied by subcells U04 to U11 in Cell 6 and Cell 1 were to be paved, then water infiltration through the underlying unsaturated soils and the resulting contamination entering the saturated zone would be significantly reduced. For an estimate of the infiltration rate for paved areas, the Soil Conservation Service (SCS) curve number method is used (USDA, 1986). It is assumed that the entire amount of annual rainfall that does not appear as surface runoff from paved areas is lost as infiltration. The SCS curve number (CN) for paved areas is reported to be 98 (USDA, 1986). Computations using the SCS curve number method, with CN = 98, suggest that the annual infiltration from paved areas corresponding to an annual rainfall of 1.11 m may approximate 0.006 m (USDA, 1986). The infiltration rate at the location of the subcells may be even smaller than this if buildings were to occupy the surface area.

The estimated rates of annual infiltration for the Site are abstracted in Table 4-3.

Table 4-3. Estimated Rates of Annual Infiltration

Surface Condition	Annual Infiltration Rate (m/yr)
Unpaved areas of subcells	0.59
Paved areas of subcells (USDA, 1986)	0.006

5.0 BASELINE SIMULATION SCENARIO

The baseline scenario is modeled using average values of the estimated model parameters and rectangular source configuration in the MULTIMED model. In statistical terms, use of the average model parameters is expected to provide the most plausible results.

The baseline scenario assumes that the area occupied by subcell series U of Cell 6 and Cell 1 (i.e., subcells U04 to U11) remains unpaved with an infiltration rate of 0.59 m/yr through the U-238-impacted residual soils.

The path of ground water transport intersects the southern Site boundary approximately 149 m from the downgradient edge of subcell U11 in Cell 6 (see Figure 1). This intersection with the southern Site boundary is the point of interest for model predictions. The length of the ground water flow path from the downgradient edge of subcell U07 in Cell 1 to the above point of interest is approximately 176.5 m.

Potential transport of U-238 is simulated using the average values of measured Site-specific parameters. Thus, the input parameters of this case include K_{du} and K_d values of 5.45 and 0.89 ml/g, respectively, for the unsaturated and saturated soil zones; geometric mean value of hydraulic conductivity, i.e., 5171.9 m/yr (46.50 ft/day); average annual recharge rate of 0.59 m/yr along the path of ground water transport; and infiltration rate of 0.59 m/yr for the unpaved surface of subcells U08 to U11 in Cell 6 and U04 to U07 in Cell 1.

Relevant input parameters for this baseline scenario for transports from Cell 6 and Cell 1 are abstracted in Table 5-1.

Table 5-1. Input Model Parameters for Baseline Scenario

Effective soil porosity (saturated conditions)	(ϕ)	0.30
Water-filled soil porosity (unsaturated conditions)	(ϕ_w)	0.18
Soil bulk density	(ρ_b)	1.60 g/cc
Average hydraulic conductivity	(K)	5171.9 m/yr (46.5 ft/day)
Average hydraulic gradient	(i)	0.00056
Average recharge rate (along path of ground water transport)	(q)	0.59 m/yr (23.2 in/yr) (see Table 4-2)
Average infiltration rate in area occupied by series U subcells in Cell 6 and Cell 1	(I)	0.59 m/yr (23.2 in/yr) (see Table 4-3)
Effective aquifer thickness gradient	(B)	9.14 m (30 ft)
Partition/distribution coefficient for unsaturated zone (Average of measured values)	(K_{du})	5.45 ml/g
Partition/distribution coefficient for saturated zone (Average of measured values)	(K_d)	0.89 ml/g
Retardation factor in saturated zone (Eq. 3, Subsection 2.3..3)	(R)	5.75
Radioactive decay constant for U-238	(λ)	1.55E-10 yr ⁻¹
Source depletion coefficient		0.0 yr ⁻¹
Distance from downgradient edge of subcell U11 in Cell 6 and U07 in Cell 1 to downgradient point on southern Site boundary	(x)	149 m (490 ft) Cell 6; 176.5 m (579 ft) Cell 1
Longitudinal dispersivity	(α_x)	14.9 m (49 ft) Cell 6; 17.65 m (57.9 ft) Cell 1
Transverse dispersivity	(α_y)	4.97 m (16.3 ft) Cell 6; 5.88 m (19.3 ft) Cell 1
Vertical dispersivity	(α_z)	0.83 m (2.74 ft) Cell 6; 0.988 m (3.24 ft) Cell 1
Length of series U subcells in Cell 6 or Cell 1	(L)	27.5 m (90 ft)
Width of series U subcells in Cell 6 or Cell 1	(W)	6.1 m (20 ft)
Initial concentration of U-238 in soils	(C_s)	8.87 pCi/g in Cell 6 and 13.79 pCi/g in Cell 1
Concentration of U-238 in rainwater entering the saturated zone (Eq. 2, Subsection 2.3.2)	(C_i)	1,595 pCi/L (or 1.6 pCi/mL) in Cell 6 and 2,479 pCi/L (or 2.5 pCi/mL) in Cell 1

The three-dimensional transport equation on which the MULTIMED model is based is linear (USEPA, 1996a). Therefore, the total contribution of the two sources (i.e., series U subcells in Cell 6 and Cell 1) at the point of interest is approximated by linear superposition of the results for transport from the two sources.

The rectangular patch source configuration implies that U-238 concentration in soils is uniformly distributed and remains at 8.87 pCi/g in Cell 6 and 13.79 pCi/g in Cell 1 within the width of the subcells for all times in the future.

For the baseline scenario, the maximum predicted concentration at the point of interest (i.e., southern Site boundary) is 11.0 pCi/L. This is close to the lower limit of the range of MCL for U-238 (i.e., 10 to 22.5 pCi/L). The predicted maximum concentration occurs after approximately 225 years from the start of the transport process and stays at that level thereafter due to the conservative assumption of a continuous source. At 5 m (16.5 ft) downgradient of the Site boundary, this maximum concentration reduces to 10 pCi/L. As noted in Section 2.3.1, because source depletion is not included in the analysis, the concentration at the point of interest remains at the equilibrium (or steady-state) value indefinitely.

6.0 CONCLUSION

Potential transport of U-238 or total uranium from residual soils in Cell 6 at the Site has been analyzed using the MULTIMED model. The input data for this preliminary study include values based on commonly used practices, information available in the literature, and measured Site-specific parameters. In particular, values of partition/distribution coefficient are obtained from several soil samples from several locations and depths in the Site vicinity. Geotechnical properties including hydraulic conductivity, porosity, and soil bulk density are estimated from laboratory analysis of several soil samples obtained from Boring KD4, which is close to Cell 6 and Cell 1 (see Appendix F and Figure 3).

Residual soils in series U subcells are found to contain the maximum concentration of U-238 in Cell 6. Series U subcells in Cell 1 are upgradient of series U subcells in Cell 6. Therefore, U-238 concentrations in residual soils in series U subcells in both Cell 6 and Cell 1 are considered in this analysis. The estimated weighted average concentrations of U-238 in residual soils in series U subcells in Cell 6 and Cell 1 are 8.87 pCi/g and 13.79 pCi/g, respectively. These concentrations are used to estimate the U-238 concentration in infiltrating rainwater entering the saturated zone beneath the subcells in the respective cells (i.e., Cell 6 and Cell 1). The total contribution of the two sources (i.e., series U subcells in Cell 6 and Cell 1) to ground water concentrations at the point of interest is obtained by linear superposition.

A baseline scenario is simulated using average values of parameters obtained from laboratory analysis of soil samples and a vertical plane rectangular patch source configuration assuming that the area occupied by subcell series U in Cell 6 and Cell 1 remains unpaved or undeveloped.

The rectangular patch source implies constant and uniform concentration within the width of the source, which is equal to the width of the subcells. This is consistent with the use of a weighted average soil concentration in subcell series U.

The result of the scenario with rectangular patch source configuration for a condition which postulated that the area occupied by subcell series U in Cell 6 and Cell 1 is paved is included in Appendix E.

The results of this study are summarized in Table 6-1 and discussed in the following subsections. Note that the predicted maximum concentrations at the point of interest on the southern Site boundary are close to or below the lower limit of the range of applicable MCL for U-238 (i.e., 10 to 22.5 pCi/L).

**Table 6-1. Results of Ground Water Transport Analysis
(includes Sources in Soils in Cell 6 and Cell 1)**

Description of Scenario	Estimated total Concentrations at Point of Interest (due to U-238 contamination in residual soils in subcell series U in Cell 6 and Cell 1)	
Point of Interest	Southern Site boundary, 149 m from source in Cell 6 and 176.5 m from source in Cell 1	
BASELINE SCENARIO		
Average soil parameters; unpaved cell surface		
Maximum concentration of U-238	(pCi/L)	11.0
Maximum concentration of total uranium ^a	(pCi/L)	22.0
Approximate time to maximum concentration (years)		225
PAVED CELL SURFACE (APPENDIX E)		
Reduced infiltration; more conservative model parameters		
Maximum concentration of U-238	(pCi/L)	0.27
Maximum concentration of total uranium ^a	(pCi/L)	0.54
Approximate time to maximum concentration (years)		150

^aPredicted maximum concentration reduces to 10 pCi/L at approximately 5 m (16.5 ft) downgradient of the Site boundary.

^bMCL for total uranium is 20 to 45 pCi/L or 30 µg/L (Appendix A).

Simulation with average values of Site-specific parameters with a vertical plane rectangular patch source configuration indicates a maximum U-238 concentration of 11 pCi/L in ground water at the southern Site boundary. This concentration is close to the lower limit of the range of MCL (i.e., 10 to 22.5 pCi/L) for U-238. Based on this simulation, the corresponding maximum concentration of total uranium in ground water is approximately 22 pCi/L. This indicates that future concentrations of U-238 or total uranium in ground water at the southern Site boundary associated with the soils containing residual uranium in Cell 6 are close to the lower limit of the respective ranges of MCLs of 10 to 22.5 pCi/L for U-238 and 20 to 45 pCi/L for total uranium.

It is likely that the area occupied by Series U subcells in Cell 6 and Cell 1 may be developed in future. To evaluate the effect of paved surface of subcell series U in Cell 6 and Cell 1, an additional simulation was conducted assuming more conservative model parameters (see Appendix E). Even with relatively more conservative model parameters, the predicted concentration of U-238 at the southern Site boundary for this case is 0.27 pCi/L. With a paved surface of subcells, infiltration through residual soils with U-238 contamination is significantly reduced resulting in significant reduction in predicted U-238 concentrations at the southern Site boundary.

7.0 REFERENCES

- American Society of Testing Materials (ASTM). 1983. ASTM D 4319 – 83 (Reapproved 1990) Standard Test Method for Distribution Ratios by the Short-Term Batch Method, Philadelphia, PA.
- ASTM, 1995. ASTM E-1739-95, Standard Guide for Risk-Based Corrective Action Applied at Petroleum Release Sites, Philadelphia, PA.
- Argonne National Laboratory (ANL), 2001. User's Manual for RESRAD, Version 6, ANL/EAD-4, Argonne, Illinois, July 2001.
- Avon, L., and T.J. Durbin, 1994. Evaluation of the Maxey-Eakin Method for Estimating Recharge to Ground-water Basins in Nevada, Water Resources Bulletin, 30(1), February, 1994.
- Brookhaven National Laboratory, 1999. Draft – Radionuclide Partition Coefficients for the BNL Site For the Saturated and Unsaturated Zones, Mark Fuhrmann, Environmental and Waste Technology Group, February, 1999.
- CDM, 2003. Nassau County Groundwater Model, Long Island Source Water Assessment Program (SWAP), Task 3A.1 Report, New York State Department of Health.
- C Tech Development Corporation, 2005, Commercial Terrain Visualization Software, EVS-Standard, Huntington Beach, CA.
- Donovan, D. J. and Katzer, T., 2000. Hydrologic Implications of Greater Ground Water Recharge to Las Vegas Valley, Nevada, JAWRA, 36(5), October, 2000.
- Duursma, E. K., 1966. Molecular Diffusion of Radioisotopes in Interstitial Water of Sediments, International Atomic Energy Agency, Vienna, IAEA SM-72/20.
- Gale Research Company, 1985. Climates of the States, Book Tower, Detroit, Michigan.
- Illinois Pollution Control Board (IPCB), 2004. Tiered Approach to Corrective Action Objectives.
- Isbister, John, 1966. Geology and Hydrology of Northeastern Nassau County Long Island, New York, U.S. Geologic Survey Water-Supply Paper No. 1825.
- NRCC, Daily Precipitation Data for Mineola, New York, nrcc@cornell.edu.
- New York State Department of Environmental Conservation, Rules and Regulations, 1999. 6 NYCRR Part 703, Surface Water and Groundwater Quality Standards and Groundwater Effluent Limitations.
- Severn Trent Laboratories, Inc. 2004. STL St. Louis Standard Operating Procedure STL-IP-0018, K_d Leaching Procedure, April 19, 2004.
- URS and Envirocon, Inc. 2006. Potential Transport of Uranium from Subsurface Soils in Cell 1 to the Point of Interest. October 2006.
- U.S. Department of Agriculture (USDA), 1986. Urban Hydrology for Small Watersheds, Technical Release 55, Soil Conservation Service, June 1986.
- U.S. Environmental Protection Agency (USEPA), 1985. Water Quality Assessment: A Screening Procedure for Toxic and Conventional Pollutants in Surface and Ground Water-Part II, EPA/600/6-85/002b, September 1985, Environmental Research Laboratory, Athens, GA.
- USEPA, 1988. Superfund Exposure Assessment Manual, EPA/540/1-88/001, OSWER Directive 9285.5-1, Office of Remedial Response, Washington, DC.
- USEPA, 1996a. Multimedia Exposure Assessment Model (MULTIMED) for Evaluating the Land Disposal of Wastes, Environmental Research Laboratory, Athens, GA.
- USEPA, 1996b. Natural Attenuation Decision Support System, BIOSCREEN, User's Manual, version 1.3, EPA/600/R-96/087, Office of Research and Development, Washington, D.C.
- USEPA, 1999. Understanding Variations in Partition Coefficient, K_d Values, Volume II, EPA/402-R-99-004B, August 1999, Office of Air and Radiation.

- USEPA, 2000a. National Primary Drinking Water Regulations; Radionuclides; Final Rule, Federal Register, Vol. 65, No. 236, December 7, 2000.
- USEPA, 2000b. Natural Attenuation Decision Support System, BIOCHLOR, User's Manual, version 1.0 and 2.2, EPA/600/R-00/008, Office of Research and Development, Washington, D.C.
- USEPA, 2002a. Implementation Guidance for Radionuclides, March 2002, Appendix E, SDWIS/FED DTF, Reporting Requirements Guidance and RC Section 6109.04, 3745-81-15, Maximum contaminant levels and best available technologies for radionuclide contaminants (effective 09/15/2004).
- USEPA, 2002b. Uranium Activity to Mass Conversion Factor Guideline for Use in Drinking Water Compliance Monitoring and Risk Assessment, July 2002.
- U.S. Geological Survey (USGS), 1999. Simulation of Ground-Water Flow and Pumpage in Kings and Queens Counties, Long Island, New York, Water Resources Investigations Report 98-4071, Coram, New York.

APPENDIX A

RADIOMETRIC AND MASS UNITS AND MCLs FOR URANIUM AND U-238

A.1 Use of U-238 as Indicator of Total Uranium Transport

In its natural state uranium consists of three radioisotopes, U-234, U-235 and U-238, all having uranium chemical properties, but differing in their radioactive characteristics. These radioisotopes each decay through alpha particle emission, but the rates of decay (and emission) for each isotope are very different, as shown by the half-lives shown in Table A-1. The half-life influences the relative abundance when comparing the isotope content by activity (radiological properties) rather than by mass fraction (chemical properties).

Table A-1. Relative Abundances of Uranium Isotopes

Isotope	Half-life (years)	Relative Isotopic Abundance (%)			
		Natural Uranium		3% Enriched Uranium	
		By Mass	By Activity	By Mass	By Activity
U-234	246,000	0.0054	49.0	0.03	82.7
U-235	704,000,000	0.711	2.25	2.96	2.84
U-238	4,470,000,000	99.283	48.7	97.01	14.5

Half-life data from *Chart of Nuclides (14th Edition)*, General Electric Co, San Jose, CA, 1989

During the Site investigations, uranium was analyzed for isotope specificity rather than through chemical analysis for total uranium. The State approved this approach because of the ease and sensitivity of the radiometric method as well as the need to rule out (or identify) the presence of enriched uranium. Enriched uranium is natural uranium processed to enhance the U-235 through removal of a small fraction of the U-238. Uranium used at the Hicksville Site is understood to have included both natural and enriched uranium. Historically, the value of enriched uranium imposed special handling procedures, so that enriched uranium was rarely discarded as waste, but recycled to recapture the valuable asset. Consistent with this understanding, very little enriched uranium was found at the Hicksville Site. And, considering relative isotopic abundance by mass, U-238 makes up 99+% of the total uranium found. As such, U-238 is an appropriate marker for tracking or predicting transport of total uranium.

Chemical properties of total uranium (such as the partition or distribution coefficient or K_d) are unaffected by the radioisotope properties. Thus, K_d for the three radioisotopes is essentially the same as the K_d for uranium. While we use the radiometric properties for detection at very sensitive levels, the radiometric properties are transparent to the physical and chemical processes driving the environmental transport.

Environmental transport is fundamentally a physical transfer process influenced by chemical interactions of the contaminant species, independent of radioisotope properties (Sheppard and Thibault, 1990; Yu et al., 1993). The only radionuclide property with any significant impact on environmental transport is the half-life, in that extremely short-lived radionuclides undergo significant decay during the periods elapsed for environmental transport processes. From Table

A-1 it is seen that all three uranium isotopes have long half-lives, so that the analysis of transport considered at the Hicksville Site is unaffected by uranium decay.

A.2 MCLs for Total Uranium and U-238

The US Environmental Protection Agency (USEPA) regulates uranium in drinking water under the Safe Drinking Water Act, with maximum contaminant levels (MCLs) published in Title 40 Code of Federal Regulations (CFR), Part 141. Uranium is a naturally occurring radioactive element and a heavy metal, and the MCL reflects consideration of both the chemical and radiological toxicities. The USEPA MCL for uranium was set at 30 microgram/liter ($\mu\text{g/L}$) with an effective date of December 8, 2003 (USEPA 2000). The NYSDEC has adopted the drinking water standard MCL for uranium as an appropriate goal for evaluating impacts of this contaminant on ground water at cleanup sites in New York.

Considering relative abundance by activity, the percentage of each of the U-238 and U-234 isotopes in the soils in Cell 6 is 49%. The percentages in Cell 1 are 49% and 48%, respectively. This is consistent with the information included in Table A-1.

For comparison to the MCL, it is necessary to convert the radiometric measurements (picoCuries or pCi) of specific isotopes to the units of the MCL (microgram or μg) for total uranium. In the supplementary information published when promulgating the MCL for uranium, USEPA indicated that “the typical conversion factors that are observed in drinking water range between 0.67 up to 1.5 pCi/ μg ” (USEPA 2000). According to USEPA’s uranium activity to mass conversion factor guidelines (USEPA, 2002), “the mass to activity ratio for uranium in a water sample varies depending on the isotopic ratio in that water supply. The nature of radioactivity in drinking water is such that there can be a significant difference in the activity due to the mixtures of isotopes in different water supplies.” “The major challenge is to determine which factor is most appropriate to use to calculate an exposure point concentration for compliance monitoring or to use in a human health risk assessment. Ideally the activity to mass ratio should be calculated for each water supply but if this is not possible, there is a health protective approach to evaluate compliance with the regulatory level.” This health protective approach includes a conversion factor of 0.67 in Tier I and calculated site-specific value in Tier II.

In light of the fact that there are no public or private drinking water wells within a mile downgradient of the Site, it is not anticipated, and is almost improbable, that ground water at the Site boundaries would be used as a source of public water supply. And, ground water entering the public water supply downgradient of the Site would involve ground water contributed by a much larger extent of the aquifer than the limited area under the Site. However, recognizing that significant mixing and dilution with ambient ground water would occur before ground water downgradient of the Site can be extracted for any use, it is reasonable to consider the upper range of conversion factors in the analysis. But, for the present study to be conservative, the full range of factors is presented to qualitatively assess the impacts of uranium in residual soils at Cell 6 and Cell 1 on ground water at the Site boundaries.

Using the recommended range of conversion factors of 0.67 to 1.5 pCi/ μg and the total uranium MCL of 30 $\mu\text{g/L}$, the range of MCL for total uranium in radiometric units can be expressed as 20 to 45 pCi/L.

For the aforementioned abundance activity ratios, the range of MCL of 20 to 45 pCi/L for total uranium can be expressed as 10 to 22.5 pCi/L for U-238 because the ratio of U-238 to total uranium in the soils in Cell 6 and Cell 1 is approximately 49%, i.e., approximately one-half.

Thus in this analysis, the cleanup target of 30 µg/L of total uranium in drinking water is interpreted as 10 to 22.5 pCi/L of U-238 in ground water. Modeling results for U-238 in ground water at the point of interest are compared to this range of 10 to 22.5 pCi/L to evaluate compliance.

References- Appendix A

- General Electric Co, *Chart of Nuclides (14th Edition)*, San Jose, CA, 1989
- New York State Department of Environmental Conservation, Rules and Regulations, 1999. 6 NYCRR Part 703, Surface Water and Groundwater Quality Standards and Groundwater Effluent Limitations.
- Sheppard, M. I. and Thibault, D. H. 1990. Default Soil Solid/Liquid Partition Coefficients, K_{ds} , For Four Major Soil Types: A Compendium. *Health Physics*, Vol. 59. No. 4 (October), pp. 471-482, 1990
- U.S. Environmental Protection Agency (USEPA), 2000. National Primary Drinking Water Regulations; Radionuclides; Final Rule, Federal Register, Vol. 65, No. 236, December 7, 2000.
- USEPA, 2002. Uranium Activity to Mass Conversion Factor Guideline for Use in Drinking Water Compliance Monitoring and Risk Assessment, July 2002.
- Yu, C. et al., 1993. Data Collection Handbook to Support Modeling the Impacts of Radioactive Material in Soil, Report ANL/EAIS-8, Argonne National Laboratory, Argonne, IL

APPENDIX B

COMPARATIVE EVALUATION OF DIFFUSION AND DISPERSION

B.1 Introduction

The contribution of molecular diffusion is not included in the simulation of ground water transport for U-238 because its contribution is small compared to dispersion (see Subsection 2.1). To clarify the rationale for this, a comparison of the coefficients of molecular diffusion and dispersion is presented below.

Diffusion or molecular diffusion is a microscopic and molecular scale process that results from the random thermal induced motion of the solute molecules within the liquid phase. It is independent of the advective motion of ground water. Dispersion or mechanical dispersion occurs predominantly on a macro and megascopic scale and is due to mechanical mixing of the solute. Mechanical mixing is caused by velocity variations within the pores, tortuosity of the porous medium, and variations in sizes of pore channels (USEPA, 1985).

In ground water transport modeling, the contribution of diffusion is usually accounted for by adding the molecular diffusion coefficient for the contaminant of concern to the dispersion coefficients. However, the molecular diffusion coefficient for total uranium may be several orders of magnitude smaller than the dispersion coefficients.

B.2 Diffusion Coefficient

Most chemical species are reported to have molecular diffusion coefficient in liquids on the order of 10^{-9} m²/s to 10^{-10} m²/s at 20° C and so the contribution of molecular diffusion is not included in most cases of ground water contaminant transport (Waterloo Hydrogeologic, Inc., 1994).

For most simple aqueous species, the diffusion coefficient, D_d , is approximately 10^{-9} m²/s (0.0315 m²/yr) (USEPA, 1999, Volume I, Page 2.35). The diffusion coefficient in soils is less than in free aqueous solutions due to the constrained geometry of the porous media represented by media characteristics such as tortuosity and porosity (USEPA, 1999, Volume I; Baehr, 1987). So, the effective diffusion coefficient for the Site conditions may be smaller than 10^{-9} m²/s.

Based on an experimental investigation of molecular diffusion of radioisotopes, Duursma (1966; USEPA, 1985) reported molecular diffusion coefficients that ranged between 2×10^{-10} to 6×10^{-10} m²/s (0.006 to 0.019 m²/yr) for trivalent and monovalent ions (both positive and negative) in fine sand.

While the above values are not specific to the temperatures and other environmental conditions at the Site, they provide reasonable guidance for use in the analysis. The reasonableness of the above values is, in part, corroborated by the results of experimental and theoretical investigations reported in the literature to estimate self-diffusion of some metals under microgravity (Itami, et al., 2000). According to this report, the diffusion coefficients for lead (Pb), germanium (Ge), tin (Sn), and silicon (Si) vary from approximately 10^{-8} to 10^{-9} m²/s at much higher ranges of temperatures (e.g., 400° to 1,700° K) than those expected in the field. The diffusion coefficients at lower temperatures are expected to be lower than these values.

B.3 Dispersion Coefficient

For comparison with the above values of diffusion coefficients, estimated values of longitudinal, transverse, and vertical dispersion coefficients for the Site conditions are indicated in Tables B-1a and B-1b. The values of parameters used to estimate the dispersion coefficients are also shown in these tables and are taken from Section 4.0.

Table B-1a. Estimated Dispersion Coefficients for Cell 6

For Cell 6, hydraulic gradient (i) = 0.00056; effective porosity (ϕ) = 0.30; longitudinal dispersivity (α_x) = 14.9 m; transverse dispersivity (α_y) = 4.97 m; and vertical dispersivity (α_z) = 0.83 m.

Parameter	Maximum	Average	Minimum
Hydraulic Conductivity (K) (m/yr)	7001.0	5171.9	3626.6
Longitudinal dispersion coefficient ^a (m ² /yr)	194.7	143.8	100.9
Transverse dispersion coefficient ^a (m ² /yr)	64.9	48.0	33.6
Vertical dispersion coefficient ^a (m ² /yr)	10.8	8.0	5.6

^aLongitudinal dispersion coefficient = $K i \alpha_x / \phi$, Transverse dispersion coefficient = $K i \alpha_y / \phi$, and Vertical dispersion coefficient = $K i \alpha_z / \phi$,

Table B-1b. Estimated Dispersion Coefficients for Cell 1

For Cell 1, hydraulic gradient (i) = 0.00056; effective porosity (ϕ) = 0.30; longitudinal dispersivity (α_x) = 17.65 m; transverse dispersivity (α_y) = 5.88 m; and vertical dispersivity (α_z) = 0.988 m.

Parameter	Maximum	Average	Minimum
Hydraulic Conductivity (K) (m/yr)	7001.0	5171.9	3626.6
Longitudinal dispersion coefficient ^a (m ² /yr)	230.6	170.4	119.5
Transverse dispersion coefficient ^a (m ² /yr)	76.8	56.8	39.8
Vertical dispersion coefficient ^a (m ² /yr)	12.9	9.5	6.7

^aLongitudinal dispersion coefficient = $K i \alpha_x / \phi$, Transverse dispersion coefficient = $K i \alpha_y / \phi$, and Vertical dispersion coefficient = $K i \alpha_z / \phi$,

The above values evidence that the dispersion coefficients are approximately 2 to 4 orders of magnitude greater than the expected diffusion coefficient for uranium. Therefore, the contribution of diffusion is not incorporated in the analysis.

References - Appendix B

- Baehr, A.T., 1987. Selective Transport of Hydrocarbons in the Unsaturated Zone due to Aqueous and Vapor Phase Partitioning, Water Resources Research 23(10).
- Duursma, E.K., 1966. Molecular Diffusion of Radioisotopes in Interstitial Water of Sediments,

- International Atomic Energy Agency, Vienna, IAEA SM-72/20.
- Itami, et al., 2000, The Self-Diffusion of Liquid Group IVB Metals Under Microgravity.
www.space.gc.ca/asc/pdf/2000_Itami.pdf
- U.S. Environmental Protection Agency (USEPA), 1985. Water Quality Assessment: A Screening Procedure for Toxic and Conventional Pollutants in Surface and Ground Water-Part II, EPA/600/6-85/002b, September 1985, Environmental Research Laboratory, Athens, GA.
- U.S. Environmental Protection Agency (USEPA), 1999. Understanding Variation In Partition Coefficient, K_d Values, Office of Air and Radiation, 6602J, EPA/402-R-99-004A.
- Waterloo Hydrologic, Inc., 1994. PRINCE, User Guide Version 3.0: Princeton Analytical Models of Flow and Mass Transport, (authors, R.W. Cleary and M.J. Ungs), Ontario, Canada.

APPENDIX C

EVALUATION OF APPLICABLE GROUND WATER TRANSPORT MODELS

C.1 CRITERIA FOR MODEL SELECTION

The criteria used for selecting an appropriate ground water transport model for the analysis are:

- The model must be relatively simple. It should preferably be available in the public domain and should have a history of use by more than one entity;
- The model should be capable of simulating the relevant physical processes listed in Section 2.1, particularly in a predictive mode;
- The model should use a conservative approach for simulating the above-mentioned processes; and
- The details of the required model input should be commensurate with available site-specific data, current knowledge of site conditions, and expected time-frame of analysis for the transport of dissolved U-238.

C.2 MODELS CONSIDERED

The relevant processes listed in Subsection 2.1 can be modeled using several different approaches. Steady state and non-steady state models (approaches), which may be relevant in this study with appropriate assumptions, are described in the following paragraphs. A non-steady state model predicts contaminant concentrations at different time periods. A steady state model predicts concentrations with no reference to time (i.e., the simulated transport conditions do not vary with time).

- a. **A Rapid Assessment Nomograph** developed by USEPA based upon a simple analytical solution of the advective-dispersion equation for ground water transport (USEPA, 1983). This non-steady state model assumes one-dimensional flow, one-dimensional (i.e., longitudinal) dispersion, and a continuous constant concentration point source. It accounts for retardation and biodegradation during transport through saturated soils but does not account for recharge along the flow path, decreasing source concentrations, and dilution due to lateral and vertical dispersion.
- b. **USEPA Analytical model** based on an equation included in USEPA (1985). This non-steady-state model assumes one-dimensional flow, one-dimensional (i.e., longitudinal) dispersion, and a diminishing point source. It accounts for retardation and biodegradation during transport through saturated soils but does not account for recharge along the flow path and dilution due to lateral and vertical dispersion.
- c. **Model based on the Domenico equations** (e.g., IPCB, 2004; Domenico, 1987; Domenico and Robbins, 1985; and ASTM, 1995). The steady and non-steady state versions of this model assume one-dimensional flow, three-dimensional dispersion, and a continuous vertical plane source with constant concentration. It can account for retardation and biodegradation during transport through saturated soils but does not account for recharge along the flow path nor for reduction in source concentration due to rainwater infiltration.

- d. **Natural Attenuation Decision Support System, BIOCHLOR** (USEPA, 2000). This model is based on modified Domenico equations (Domenico, 1987; Domenico and Robbins, 1985) and simulates one-dimensional advection, three-dimensional dispersion, linear adsorption, and biotransformation. Just like the Domenico equations, this model also assumes a fully penetrating, vertical plane source oriented perpendicular to ground water flow. It can account for source reduction but does not account for recharge along the flow path.
- e. **Analytical Transient One-, Two-, and Three-Dimensional Model, AT123D** (Yeh, 1981). This model is a collection of analytical solutions for one-, two-, and three-dimensional contaminant transport with advection, dispersion, and source reduction. A uniform flow field with constant velocity is assumed. It is applicable to the transport of radioactive waste, heat, and chemicals from linear, areal, or volumetric sources with instantaneous, finite-time, or continuous release. The model does not account for recharge along the flow path. According to some reviews, numerical errors may occur during calculation of the series summation which means convergence and accuracy may not be guaranteed (e.g., Maidment, 1993).
- f. **Multimedia Exposure Assessment Model, MULTIMED** (USEPA, 1996) for saturated and unsaturated zone fate and transport of dissolved chemicals. This model can simulate both steady and non-steady state transport. It assumes one-dimensional flow, three-dimensional dispersion, and can simulate contaminant transport emanating from a continuous or finite-duration, non-decaying patch type or decaying or non-decaying Gaussian source. It accounts for retardation, biodegradation, and recharge along the flow path during transport through saturated soils.
- g. **Coupled and uncoupled two- and three-dimensional finite-difference or finite-element flow and transport models.** There are a number of complex and sophisticated models in this category. A few examples include:
- The MT3D (USEPA, 1992) model coupled with the MODFLOW model (USGS, 2000);
 - USGS MOC model (Konikow and Bredehoeft, 1978; Goode and Konikow, 1989);
 - SEFTRAN model (Geotrans, Inc., 1988);
 - CFEST model (Gupta, et al., 1987);
 - FTWORK model (Faust, et al, 1989);
 - HST3D model (Kipp, 1987);
 - SUTRA model (Voss, 1984; Souza, 1987);
 - SWIFT II model (Reeves et al., 1986); and
 - TARGET model (Sharma et al., 1981).

These models can simulate two- and three-dimensional flow and transport under steady or non-steady state conditions. The model domain boundaries have to be defined based on existing natural and man-made surface and ground water flow and transport conditions in the site vicinity. To minimize boundary effects, the model domain has to include an area much larger than the site area. Appropriate hydraulic head, flow, and concentration conditions have to be

provided at these boundaries and verified during calibration. The model domain is divided into variable size discrete elements or cells and layers. Site-specific hydrogeologic and chemical data have to be available or estimated for each of the discrete elements or cells. A relatively large amount of field data is required for model calibration. The larger the number of input parameters, the more difficult it is to obtain adequate and reliable information for them. Therefore, several assumptions may have to be made or default values may have to be used based on the judgment of the user.

C.3 COMPARATIVE EVALUATION

Each model has its own assumptions and limitations and may require adaptations and additional simplifying assumptions to simulate specific site situations. The more sophisticated models (coupled or decoupled two- and three-dimensional flow and transport models) require more data on site-specific parameters for calibration and simulation.

U-238 contamination at different concentrations has been detected at different depths in the ground water profiles and monitoring wells drilled and investigated at the Site. There is considerable variation in measured U-238 concentrations. In addition, the concentrations at different locations and depths include different and indeterminate degrees of dilution due to mixing with ambient ground water flow. Thus, reliable data for the calibration or “benchmarking” of the uranium transport model are not available. Without adequate calibration, the results of the sophisticated models may not have a higher degree of accuracy.

Regardless of model used, one of the significant model input parameters is the concentration of U-238 at the source. This parameter has to be estimated outside the above-mentioned models and will not be affected by the sophistication or simplicity of the selected transport model. In addition, the time horizon for the transport of U-238 is fairly large (approximately several decades to several hundred years or so), so a number of simplifying and conservative assumptions have to be made to evaluate the potential for ground water contamination at the point of interest at some time in the distant future regardless of the model selected. However, when a relatively large number of assumed input parameters are required for a model, there is a possibility that more than one combination of input parameters may provide similar results (or that the model over or under predicts transport). In such cases, without the ability to properly calibrate a model, it may be difficult to distinguish between realistic and spurious results.

Of the analytical models listed in Section C.2 (a, b, c, d, e, and f), only MULTIMED (USEPA, 1996) has the capability to simulate dilution due to recharge along the path of ground water transport.

The afore-mentioned finite-difference and finite-element models may provide ground water flow (advection) in three directions. Because three-dimensional advection may result in more dilution, using a three-dimensional model may predict relatively lower concentrations reaching the point of interest. Consequently, the predicted concentrations may not be conservative when compared to the case in which ground water flow is assumed to have only one dominant flow direction. This is true for each of the more sophisticated models.

References: See Appendix D References.

APPENDIX D

DESCRIPTION OF MULTIMED MODEL

The Multimedia Exposure Assessment Model (MULTIMED) simulates the movement of contaminants leaching from a waste disposal facility or contaminated soils. The model consists of a number of modules which predict concentrations at a receptor due to transport in both unsaturated and saturated soil zones. The output from the unsaturated zone module may be used to couple the unsaturated zone transport module with the steady-state or transient, semi-analytical saturated zone transport module. The saturated zone transport module includes one-dimensional uniform flow, three-dimensional dispersion, linear adsorption, first-order decay, and dilution due to direct infiltration into the ground water plume. The unsaturated zone module of MULTIMED is not relevant in this analysis because the prior excavation activities removed upper levels of soil and left residual soils relevant to this analysis that have been characterized to approximately 5 to 10 ft above the water table.

The fate of contaminants in various media depends on the chemical properties of the contaminants as well as a number of media- and environment-specific parameters. The uncertainty in these parameters can be quantified in MULTIMED using the Monte Carlo simulation technique. To enhance the user-friendly nature of MULTIMED, a preprocessor, PREMED, and a postprocessor, POSTMED, have been developed.

The operation of each module requires specific input, which is organized into data groups. The General Data Group, which is required for all simulations, contains flags and data which describe the scenario being modeled. The input parameters needed for the Saturated Zone Transport Model are arranged in three additional data groups: the Chemical Data Group, the Source Data Group, and the Aquifer Data Group.

The simplifying assumptions required to obtain the analytical solutions for the equations used in MULTIMED limit the complexity of the systems that can be modeled. Accordingly, MULTIMED cannot be used to account for site-specific spatial variability or boundary conditions, landfill shape, multiple aquifers and pumping wells, flow in fractures, or chemical reactions between reactants. As a result, MULTIMED should be used only as a screening level tool when applied to complex sites.

MULTIMED was developed primarily for, and has seen extensive application in, predicting leachate movement from a Subtitle D (hazardous waste) landfill. This type of application, however, only utilizes a subset of MULTIMED's full capabilities. When MULTIMED has been used in conjunction with a separate source model, such as HELP (USEPA, 1995), it has been applied to a much larger range of scenarios. Such scenarios may include development and comparison of the effects of different facility designs or conditions on ground water quality to address questions related to appropriate cleanup levels for contaminated soils.

The MULTIMED model has undergone a series of tests to verify the correctness of the model. Discussion of these tests and related model application considerations are included in the model documentation (USEPA, 1996). The model can simulate steady and non-steady state transport of conservative or decaying substances emanating from a rectangular (patch type) or Gaussian

source with specified leach rates. The source may be a constant concentration source or a decaying source.

References - Appendix C and D

- American Society of Testing and Materials (ASTM), 1995. Standard Guide for Risk-Based Corrective Action Applied at Petroleum Release Sites, E 1739-95, West Conshohocken, Pa.
- Domenico, P.A. and G.A., Robbins, 1985. A New Method of Contaminant Plume Analysis, Ground Water, 23(4), 476-485.
- Domenico, P.A., 1987. An Analytical Model for Multidimensional Transport of a Decaying Contaminant Species, J. Hydrology, 91, 49-58.
- Faust, C.R., P.N. Sims, C.P. Spalding, P.F. Andersen, and D.E. Stephensen, 1989. FTWORK: Groundwater Flow and Solute Transport in Three Dimensions. Westinghouse Savannah River Company, WRSC-RP-89-1085, Savannah River Site, Aiken, S.C.
- GeoTrans, Inc., 1988. SEFTRAN: A Simple and Efficient Two-dimensional Groundwater Flow and Transport Model, Herndon, VA.
- Goode D.J., and L.F. Konikow, 1989. Modification of a Method-of Characteristics Solute Transport Model to Incorporate Decay and Equilibrium-Controlled Sorption or Ion Exchange. Water Resources Investigations Report 89-4030, U.S. Geological Survey.
- Gupta, S.K., C.R. Cole, C.T. Kincaid, and A.M. Monti. 1987. Coupled Fluid, Energy and Solute Transport (CFEST) Model: Formulation and User's Manual. BMI/ONWI-660, Office of Nuclear Waste Isolation, Battelle Memorial Institute, Columbus, Ohio.
- Illinois Pollution Control Board (IPCB), 2004. Tiered Approach to Corrective Action Objectives (TACO).
- Kipp, K.L., Jr., 1987. HST3D: A Computer Code for Simulation of Heat and Solute Transport in Three-dimensional Ground-Water Systems, 1987. Water Resources Investigations Report 86-4095, U.S. Geological Survey.
- Konikow, L.F. and J.D. Bredehoeft, 1978. Computer Model of Two-Dimensional Solute Transport and Dispersion in Ground Water. Techniques of Water resources Investigations, Book 7, Chapter C2, U.S. Geological Survey.
- Maidment, D.R. ed. 1993. Handbook of Hydrology, McGraw-Hill, New York.
- Reeves, M., D.S. Ward, and N.D. Johns, 1986. Theory and Implementation for SWIFT II. The Sandia Waste-Isolation Flow and Transport Model for Fractured Media. Release 4.84, Sandia National Laboratories. Albuquerque, New Mexico.
- Sharma, D., J.L. Moreno, and M.I. Asgian, 1981. A Computational Procedure for Predicting Coupled Fluid Flows and transport of reactive Chemical Species in Variably Saturated Porous Media, Proc. Joint ASME/ASCE Mechanics Conference, Boulder, CO., June 1981.
- Souza, W.R., 1987. Documentation of a Graphical Display program for the Saturated-Unsaturated Transport (SUTRA) Finite-Element Simulation Model. Water Resources Investigations Report 87-4245, U.S. Geological Survey.
- U.S. Environmental Protection Agency (USEPA), 1983. Rapid Assessment of Potential Ground-Water Contamination Under Emergency Response Conditions, EPA/600/8-83-030, Office of Research and Development, Washington, DC.
- USEPA, 1985. Water Quality Assessment: A Screening Guide for Toxic and Conventional Pollutants in Surface and ground Water- Part II, EPA/600/6-85/002b, Environmental Research Laboratory, Athens, GA.

APPENDIX E

U-238 TRANSPORT ASSUMING PAVED CELL SURFACE

E.1 Introduction

It is likely that the area occupied by subcell series U in Cell 6 and Cell 1 may be paved or occupied by buildings at some point in future. If the area occupied by subcell series U in Cell 6 and Cell 1 is paved, it would significantly reduce infiltration of rainwater through the residual soils containing U-238. Thus the quantity and rate of desorption of U-238 from the residual soils would also be reduced. As a result, the volumetric rate and concentration of U-238 entering the water table would be significantly reduced.

To illustrate the effect of paved surface of subcell series U in Cell 6 and Cell 1, an additional scenario is simulated with relatively more conservative values of model parameters. This scenario is designated as Scenario E-1. The result of this postulated case is presented in this Appendix.

E.2 Model Parameters

The model parameters for Scenario E-1 are shown in Table E-1. The K_{du} value is assumed to be the lowest of the six samples mentioned in Subsection 4.1.1 for the unsaturated zone and the K_d value is taken to be the lowest of the seven samples for the saturated zone. In addition, the hydraulic conductivity is assumed to be the highest of the three samples mentioned in Subsection 4.1.3. The infiltration for paved surfaces is taken to be 0.006 m/yr (see Subsection 4.7.3).

Table E-1. Input Model Parameters for Scenario E-1- Paved Surface of Subcells

Effective soil porosity (saturated conditions)	(ϕ)	0.30
Water-filled soil porosity (unsaturated conditions)	(ϕ_w)	0.18
Soil bulk density	(ρ_b)	1.60 g/cc
Hydraulic conductivity (maximum of measured values)	(K)	7001 m/yr (62.9 ft/day)
Average hydraulic gradient	(i)	0.00056
Average recharge rate (along path of ground water transport)	(q)	0.59 m/yr (23.2 in/yr) (see Table 4-2)
Average infiltration rate (in the paved area occupied by subcell series U in Cell 6 and Cell 1)	(I)	0.006 m/yr (0.24 in/yr) (see Table 4-3)
Effective aquifer thickness	(B)	9.14 m (30 ft)
Distribution coefficient for unsaturated zone (Minimum of relevant measured values)	(K_{du})	2.98 ml/g
Distribution coefficient for saturated zone (Minimum of relevant measured values)	(K_d)	0.52 ml/g
Retardation factor in saturated zone (Eq. 3, Subsection 2.3..3)	(R)	3.77
Radioactive decay constant for U-238	(λ)	1.55E-10 yr ⁻¹
Source depletion coefficient		0.0 yr ⁻¹
Distance from downgradient edge of subcell U11 in Cell 6 and U07 in Cell 1 to downgradient point on southern Site boundary	(x)	149 m (490 ft) Cell 6; 176.5 m (579 ft) Cell 1
Longitudinal dispersivity	(α_x)	14.9 m (49 ft) Cell 6; 17.65 m (57.9 ft) Cell 1
Transverse dispersivity	(α_y)	4.97 m (16.3 ft) Cell 6; 5.88 m (19.3 ft) Cell 1
Vertical dispersivity	(α_z)	0.83 m (2.74 ft) Cell 6; 0.988 m (3.24 ft) Cell 1
Length of series U subcells in Cell 6 or Cell 1	(L)	27.5 m (90 ft)
Width of series U subcells in Cell 6 or Cell 1	(W)	6.1 m (20 ft)
Initial concentration of U-238 in soils	(C_s)	8.87 pCi/g in Cell 6 and 13.79 pCi/g in Cell 1
Concentration of U-238 in rainwater entering the saturated zone (Eq. 2, Subsection 2.3.2)	(C_i)	2,868 pCi/L (or 2.9 pCi/mL) in Cell 6 and 4,459 pCi/L (or 4.4 pCi/mL) in Cell 1

E.3 Results of Simulations with Paved Subcells

The predicted maximum U-238 concentrations at the southern Site boundary for the relatively more conservative model parameters included in Table E-1 is 0.27 pCi/L if the area occupied by subcell series U in Cell 6 and Cell 1 is paved. The maximum concentration for Scenario E-1 occurs after 150 years from the initiation of the transport process.

If the area occupied by series U subcells in Cell 6 and Cell 1 is occupied by buildings, then rainwater infiltration, desorption of U-238 from soils in the vadose zone, and vertical transport of U-238 to the saturated zone would be reduced to a minimum. In this case predicted concentration of U-238 in ground water reaching the southern Site boundary would be even smaller than the above value of 0.27 pCi/Ls.

APPENDIX F
BORING LOGS

APPENDIX G

HYDRAULIC GRADIENT AND LENGTH OF FLOW PATH

G.1 Introduction

The MULTIMED model is based on one-dimensional ground water flow and predicts the propagation of concentration along a vertical profile of the aquifer downgradient from the source. This profile follows a straight line along the uni-directional flow path specified as input to the model. The localized hydraulic gradient of ground water along the above-mentioned vertical profile in unconfined situations is the slope of the water table between two selected points or between points closest to these two points on this vertical profile. Thus, the localized hydraulic gradient applicable to the transport of dissolved uranium from subcell series U of Cell 6 and Cell 1 to the point of interest has to be estimated by the difference in ground water levels in the monitoring wells closest to the downgradient edges of subcell series U of Cell 6 and Cell 1 and the point of interest.

The dominant on-Site localized ground water flow direction and localized hydraulic gradient were identified from available field data. While the regional ground water flow direction in the vicinity of the Site is to the south, small areas may have localized variation. This localized variation is relevant for ground water transport modeling within the short transport distance considered in this study (USEPA, 1985, Page 346).

To estimate the localized hydraulic gradient between Cell 6 and Cell 1 and the southern Site boundary, ground water elevations were used from three on-Site monitoring wells (MW-07, MW-11, and MW-09) for two monitoring events (December 2002 and March 2003). The localized hydraulic gradient was taken to be the average of values computed for the above two monitoring events. MW-07 is located downgradient of Cell 6 and Cell 1 and MW-09 and MW-11 are located further downgradient near the southern Site boundary (see Figure 3). These three monitoring wells were selected because they define the plane representing the water table in the area between Cell 6 or Cell 1 and the southern Site boundary (USEPA, 1998; IPCB, 2004).

Relevant data for monitoring wells MW-07, MW-11, and MW-09 are included in Table G-1.

Table G-1. Relevant Data for Selected on-Site Monitoring Wells

Monitoring Well	Screen Interval (ft)	Relative Coordinates ^a (ft)		Ground Water Elevation (ft)	
		x	y	March 2003	December 2002
MW-09	72-82	0	0	68.80	67.90
MW-11	71-81	110	0	68.84	67.91
MW-07	69.5-79.5	330.46	317.11	68.98	68.16

^aBased on distances scaled from Site map (1 inch = 80 ft). (MW-09 to MW-11 = 110 ft; MW-09 to MW-07 = 458 ft; and MW-11 to MW-07 = 390 ft).

G.2 Estimation of Localized Hydraulic Gradient

Three different approaches were used to estimate the localized hydraulic gradient using ground water elevation data for the three monitoring wells included in Table G-1.

G.2.1 Hydraulic Gradient Estimation Using Average Ground Water Elevations

In this approach hydraulic gradient is estimated between monitoring well MW-07 and the point between monitoring wells MW-9 and MW-11 where ground water elevation is equal to the average of ground water elevations in these two wells. The distance of this point from MW-07 is approximately 420 ft.

The estimated hydraulic gradients for the March 2003 and December 2002 ground water elevations are 0.00038 and 0.00061, respectively. This gives an average hydraulic gradient of 0.00049 toward the southern Site boundary.

G.2.2 Hydraulic Gradient based on Potentiometric Contours

In this case ground water contours were sketched for each of the two monitoring events (March 2003 and December 2002). The estimated average ground water gradients from these contours for March 2003 and December 2002 are 0.00054 and 0.00068, respectively. This gives an average hydraulic gradient of 0.00054.

G.2.3 Estimation of Slope of Water Table

This approach uses a matrix solver to develop the equation of a plane through the measured ground water elevations in the three monitoring wells in March 2003 and December 2002, respectively. Each plane represents the plane of water table in the vicinity for that particular monitoring event (March 2003 and December 2002). The slope of this plane with respect to the horizontal plane gives the hydraulic gradient (Devlin, 2002).

According to this method, the estimated hydraulic gradients for the March 2003 and December 2002 ground water elevations are 0.00041 and 0.00071, respectively. This gives an average hydraulic gradient of 0.00056 toward the southern Site boundary.

G.3 Adopted Localized Hydraulic Gradient and Length of Flow Path

So far as the transport of U-238 is concerned, the three estimates of hydraulic gradient included in Subsections G.2.1, G.2.2, and G.2.3 are not significantly different. The highest value of 0.00056 is adopted for ground water transport modeling.

Scaling from a Site map (scale 1 inch = 80 ft), the length of the flow path from the downgradient edge of subcell U11 of Cell 6 to the southern Site boundary along the direction of the above hydraulic gradient is approximated to be 490 ft (149 m). The length of the flow path from the downgradient edge of subcell U07 of Cell 1 to the southern Site boundary along the direction of the above hydraulic gradient is approximated to be 579 ft (176.5 m).

Reference - Appendix G

- Devlin, J.F., 2002. A Spreadsheet Method of Estimating Best-Fit Hydraulic Gradients Using Head Data from Multiple Wells, *Ground Water*, Vol. 41, No. 3, 316-320.
- Illinois Pollution Control Board (IPCB), 2004. Tiered Approach to Corrective Action Objectives.
- U.S. Environmental Protection Agency (USEPA), 1985. Water Quality Assessment: A Screening Procedure for Toxic and Conventional Pollutants in Surface and Ground Water-Part II, EPA/600/6-85/002b, September 1985, Environmental Research Laboratory, Athens, GA.
- U.S. Environmental Protection Agency (USEPA), 1998. USEPA Technical Protocol for Evaluating Natural Attenuation of Chlorinated Solvents in Ground Water 1998, EPA/600/R-98/128, September 1998, Office of Research and Development, Washington, D.C.

APPENDIX H

VOLUME AND MASS CALCULATIONS FOR RESIDUAL SOILS

Since series U subcells in Cell 1 are located immediately upgradient of series U subcells in Cell 6, U-238 concentrations in residual soils in both Cell 6 and Cell 1 are considered. Volume and mass calculations for both cells are included in the following tables.

VOLUME AND MASS CALCULATIONS FOR RESIDUAL SOILS IN CELL 6

Calculations constrained to the area below the excavation level and above the water table for each subcell

Cell 6 includes subcells Q06 to Q11; R06 to R11; and U08 to U11

All input sample data is from the on-Site gamma spectroscopy service.

Water table is approximated at 71 ft elevation, and is assumed constant throughout Cell 6

* All values were calculated at the 0 (zero) isolevel for U-238

U-238 mass calculation is based on a specific activity of 3.3601 E-7 Ci/g

Subcell	Excavation Depth (ft)	Surface Elevation (ft)	Excavation Elevation (ft)	Soil Volume* (cubic ft)	Soil Mass* (kilograms)	U-238 Mass* (kilograms)	Average U-238* (pCi/g)	Center of Mass* (Elevation in ft MSL)
Q06	32.03	145.46	113.43	18,180	832,150	10.73	4.33	90.5
R06	39.4	145.38	105.98	24,949	1,142,000	38.03	11.18	86.7
Q07	36.47	145.56	109.09	16,241	743,400	11.83	5.34	90.3
R07	40.63	145.1	104.47	21,619	989,550	26.59	9.02	89.5
Q08	27.35	145.39	118.04	19,873	909,640	14.24	5.25	97.2
R08	34.24	145.09	110.85	22,954	1,050,700	34.13	10.9	91.8
U08	32.61	144.78	112.17	16,960	776,320	19.09	8.25	92.4
Q09	18.04	145.02	126.98	23,255	1,064,400	17.4	5.48	99.5
R09	24.8	144.71	119.91	25,078	1,147,900	41.23	12.05	97
U09	24.96	144.69	119.73	20,398	933,680	35.52	12.76	100.5
Q10	7.67	145.5	137.83	27,624	1,264,400	19.12	5.07	104.5
R10	9.27	144.55	135.28	28,956	1,325,400	27.68	7.01	99.1
U10	16.71	145.25	128.54	23,800	1,089,400	32.31	9.95	98.9
Q11	4.9	145.23	140.33	28,776	1,317,200	12.69	3.23	107.8
R11	4.63	145.01	140.38	26,517	1,213,700	12.86	3.55	105.7
U11	16.67	144.67	128	23,621	1,081,200	15.71	4.88	99.7

VOLUME AND MASS CALCULATIONS FOR RESIDUAL SOILS IN CELL 1

Subcell	Excavation Depth (ft)	Surface Elevation (ft)	Excavation Elevation (ft)	Soil Volume* (cubic ft)	Soil Mass* (kilograms)	U-238 Mass* (kilograms)	Average U-238* (pCi/g)	Center of Mass* (Elevation in ft MSL)
U04	13.65	145.63	131.98	25,403	1,162,800	21.63	6.24	101.8
V04	14.88	145.70	130.82	25,710	1,176,800	29.97	8.55	102.1
W04	12.76	145.46	132.70	25,912	1,186,100	28.60	8.09	100.1
U05	23.32	145.17	121.85	20,796	951,900	57.61	20.31	96.4
V05	18.68	145.26	126.58	23,534	1,077,200	75.20	23.43	98.8
W05	14.60	145.76	131.16	25,684	1,175,600	34.40	9.82	104.2
U06	40.13	145.01	104.88	14,174	648,770	33.82	17.49	87.8
V06	17.40	144.71	127.31	24,057	1,101,100	97.18	29.62	96.2
W06	18.03	145.76	127.73	24,125	1,104,300	36.55	11.11	96.5
U07	39.48	145.05	105.57	14,214	650,610	27.29	14.08	89.2
V07	17.27	144.62	127.35	23,619	1,081,100	33.95	10.54	94.9
W07	18.43	145.28	126.85	23,497	1,075,500	19.46	6.07	96.2



NORTH


LEGEND:




= SERIES U SUBCELLS
IN CELL 6 AND CELL 1




= LONGITUDINAL TRANSPORT
OF URANIUM



= CELL BOUNDARIES




= SUBCELL BOUNDARIES



= PROPERTY LINES



= URANIUM TRANSPORT
WITH GROUND WATER
(DIRECTION OF GROUND
WATER FLOW MAY VARY)





**GTE OPERATIONS
SUPPORT INCORPORATED
HICKSVILLE, NEW YORK**

**FIGURE 1 - PLAN VIEW
POTENTIAL URANIUM TRANSPORT
FROM SERIES U SUBCELLS OF CELL 6**

DATE: Sep 18, 2006
JOB NO.: 25595516
DRAWN BY: BKR
CHK'D BY: AP
SCALE: NOT TO SCALE

URS

5 PENN PLAZA, FLOOR 13
NEW YORK, NEW YORK



NOTES:

- C₀ = POTENTIAL URANIUM CONCENTRATION IN GROUND WATER AT SOURCE
- C = POTENTIAL URANIUM CONCENTRATION AT POINT
OF INTEREST
- H = MIXING ZONE DEPTH
- W = WIDTH OF SOURCE

SCHEMATIC DIAGRAM -
NOT TO SCALE

**GTE OPERATIONS
SUPPORT INCORPORATED
HICKSVILLE, NEW YORK**

**FIGURE 2 - CROSS-SECTIONAL VIEW
POTENTIAL URANIUM TRANSPORT
FROM SERIES U SUBCELLS OF CELL 6**

DATE: OCT. 6, 2006

JOB NO.: 25595516

DRAWN BY: BKR

CHECKED BY: AP

SCALE: NOT TO SCALE

URS

5 PENN PLAZA, FLOOR 13
NEW YORK, NEW YORK

Figure 3
Location of Referenced
Monitoring Wells,
Profiles, and Borings

Legend

- Monitoring Wells (Existing)
- Monitoring Wells (Abandoned)
- Profile Locations
- KD1, KD2, KD3, KD4 Boring Locations
- Building
- Property Line
- Subcell Boundary
- Cell Boundaries



Feet
0 25 50

Projection Information
State Plane Projection
Long Island Zone
North American Datum 1983
Feet

NYSDEC V00089-1 URS27010-039

GTE OPERATIONS SUPPORT INCORPORATED
HICKSVILLE, NEW YORK



DESTINY
RESOURCES, INC.

Appendix F – Boring Logs

This appendix provides the boring log for the Potential Uranium Transport Report. Boring logs are provided in sequential order, KD1 through KD4. Borings KD1 and KD3 were advanced using a hollow-stem auger drilling rig; Borings KD2 and KD4 were advanced using hollow-stem augers to 69 feet below ground surface, then casing was advanced with a 300-pound hammer to the bottom of the boring. The borings were backfilled with clean fill upon completion.

The main lithologic name with the appropriate group symbol is described at the top of each stratum. The main lithologic group is in capital letters and bold font. Minor variations within the soil stratum are called out at the approximate elevation in which they occur, and the main lithologic group is not repeated nor any variations above the one identified.

Fill is defined as non-native material (evidenced by color, texture, structure, or miscellaneous debris), other than the material GTEOSI used to backfill excavations, which is noted as 'backfill' in the logs.

MAJOR DIVISIONS			GRAPHIC SYMBOL	LETTER SYMBOL	TYPICAL DESCRIPTIONS			
COARSE GRAINED SOILS	GRAVEL AND GRAVELLY SOILS	CLEAN GRAVELS (LITTLE OR NO FINES)		GW	WELL-GRADED GRAVELS, GRAVEL-SAND MIXTURES, LITTLE OR NO FINES			
				GP	POORLY-GRADED GRAVELS, GRAVEL-SAND MIXTURES, LITTLE OR NO FINES			
		GRAVELS WITH FINES (APPRECIABLE AMOUNT OF FINES)		GM	SILTY GRAVELS, GRAVEL-SAND-SILT MIXTURES			
				GC	CLAYEY GRAVELS, GRAVEL-SAND-CLAY MIXTURES			
	SAND AND SANDY SOILS	CLEAN SAND (LITTLE OR NO FINES)		SW	WELL-GRADED SANDS, GRAVELLY SANDS, LITTLE OR NO FINES			
				SP	POORLY-GRADED SANDS, GRAVELLY SANDS, LITTLE OR NO FINES			
		SANDS WITH FINES (APPRECIABLE AMOUNT OF FINES)		SM	SILTY SANDS, SAND-SILT MIXTURES			
				SC	CLAYEY SANDS, SAND-CLAY MIXTURES			
			FINE GRAINED SOILS	SILTS AND CLAYS	LIQUID LIMIT LESS THAN 50		ML	INORGANIC SILTS AND VERY FINE SANDS, ROCK FLOUR, SILTY OR CLAYEY FINE SANDS OR CLAYEY SILTS WITH SLIGHT PLASTICITY
							CL	INORGANIC CLAYS OF LOW TO MEDIUM PLASTICITY, GRAVELLY CLAYS, SANDY CLAYS, SILTY CLAYS, LEAN CLAYS
LIQUID LIMIT GREATER THAN 50		OL			ORGANIC SILTS AND ORGANIC SILTY CLAYS OF LOW PLASTICITY			
		MH			INORGANIC SILTS, MICACEOUS OR DIATOMACEOUS FINE SAND OR SILTY SOILS			
SILTS AND CLAYS	LIQUID LIMIT GREATER THAN 50			CH	INORGANIC CLAYS OF HIGH PLASTICITY, FAT CLAYS			
				OH	ORGANIC CLAYS OF MEDIUM TO HIGH PLASTICITY, ORGANIC SILTS			
	HIGHLY ORGANIC SOILS				PT	PEAT, HUMUS, SWAMP SOILS WITH HIGH ORGANIC CONTENTS		

SOIL CLASSIFICATION CHART

MATERIAL SIZE		PARTICLE SIZE			
		LOWER LIMIT		UPPER LIMIT	
		MILLIMETERS	SIEVE SIZE*	MILLIMETERS	SIEVE SIZE*
SAND	FINE	.075	#200*	0.425	#40*
	MEDIUM	0.425	#40*	2.00	#10*
	COARSE	2.00	#10*	4.75	#4*
GRAVEL	FINE	4.75	#4*	19.0	3/4"
	COARSE	19.0	3/4"	75.0	3"
COBBLES		75.0	3"	300.0	12"
BOULDERS		300.0	12"	900.0	36"

* U.S. STANDARD

* CLEAR SQUARE OPENINGS

GRADATION CHART

Notes:

- Dual symbols are used to indicate borderline classifications or intermixed strata.
- Soil descriptions and classification are based on field observations, not on laboratory testing of soil physical properties.
- When used on the boring logs, the following terms are used to describe the consistency of cohesive soils and the relative compactness of cohesionless soils:

Cohesive Soils

Very Soft
Soft
Medium Stiff
Stiff
Very Stiff
Hard

Cohesionless Soils

Very Loose
Loose
Medium Dense
Dense
Very Dense

- When used on the boring logs, the following terms indicate the volume percentage of the minor soil components estimated in the field based on visual observations:
trace: 1 to 10% little: 10 to 20% some: 20 to 35% and: 35 to 50%.

- Moisture Content:

Dry: Absence of moisture, dusty, dry to the touch
Moist: Damp but no visible water
Wet: Visible free water, usually soil is below the water table

UNIFIED SOIL CLASSIFICATION SYSTEM AND KEY TO LOG OF BORINGS

Project No.: NYSDEC: V-00089-1; URS: 27010-039

Project: Kd Drilling Program

Client: GTEOSI, Hicksville, NY

Log of Boring: KD1

Date Drilled: 8/24/04

Sampler Type: 3-inch/2-inch split spoon driven by 300-lb/140-lb hammer

Logged By: Carrie Olsen



5 Penn Plaza
13th Floor
New York, NY 10001

Depth (feet)	USCS Letter Symbol	USCS Lithologic Symbol	Blows/Foot (center ft only)	Recovery (in per 2-ft interval)	PID Sample Screen (ppm)	Nal 3x3 (kcpm)	Sample Type	Description	Remarks
1								Asphalt Surface elevation at 144.9', first sample at 20'	
2								FILL , dark brown, fine to medium sand, trace fine gravel and cobbles, dry (lithology observed from auger cuttings to 20' bgs)	
3									
4								(Fill depth interpreted from adjacent borings)	
5								Brown, fine to medium SAND , trace coarse sand, fine to coarse gravel and cobbles	
6	SP								
7									
8									
9									
10								Cobble layer	
11									
12									
13									

Project No.: NYSDEC: V-00089-1; URS: 27010-039

Project: Kd Drilling Program

Client: GTEOSI, Hicksville, NY

Log of Boring: KD1





Date Drilled: 8/24/04

Sampler Type: 3-inch/2-inch split spoon driven by 300-lb/140-lb hammer

Logged By: Carrie Olsen



5 Penn Plaza
13th Floor
New York, NY 10001

Depth (feet)	USCS Letter Symbol	USCS Lithologic Symbol	Blows/Foot (center ft only)	Recovery (in per 2-ft interval)	PID Sample Screen (ppm)	NaI 3x3 (kcpm)	Sample Type	Description	Remarks
14	SP							Brown, fine to medium SAND , trace coarse sand, fine to coarse gravel and cobbles	NA = Not available (rad data not recorded)
15									
16									
17									
18	GW							Light brown, fine to coarse SAND and fine to coarse GRAVEL , medium dense, dry	
19									
20									
21	GW		21	12	0.0	10.3	Kd	Dense	
22									
23	SP		30	18	0.0	10.3		Tan, fine to medium SAND , trace fine gravel, dense, dry Medium dense Medium to coarse sand, some fine to coarse gravel	
24									
25			21	18	0.0	NA			
26									

Project No.: NYSDEC: V-00089-1; URS: 27010-039

Project: Kd Drilling Program

Client: GTEOSI, Hicksville, NY

Log of Boring: KD1

Date Drilled: 8/24/04

Sampler Type: 3-inch/2-inch split spoon driven by 300-lb/140-lb hammer

Logged By: Carrie Olsen



5 Penn Plaza
13th Floor
New York, NY 10001

Depth (feet)	USCS Letter Symbol	USCS Lithologic Symbol	Blows/Foot (center ft only)	Recovery (in per 2-ft interval)	PID Sample Screen (ppm)	Nal 3x3 (kcpm)	Sample Type	Description	Remarks
27	SW		41	24	0.0	9.0		Light brown, fine to coarse SAND , some gravel, dense, moist	
28	SP							Light brown, fine to medium SAND , trace fine gravel, dense, moist	
29	SW		26	20	0.0	8.5		Light brown, fine to coarse SAND , trace fine to coarse gravel, medium dense, moist	
30								Brown, fine to medium SAND , trace fine gravel, medium dense, moist	
31			26	21	0.0	10.8	Kd	Trace coarse sand	
32	SP								
33			35	24	0.0	10.8		Light brown to tan, fine sand, trace medium to coarse sand and fine gravel to 34', dense, moist	
34								Medium dense	
35			23	24	0.0	9.0			
36	SW							Light brown, fine to coarse SAND , trace fine gravel, medium dense, moist	
37	GP		36	22	0.0	9.3		Tan, fine to coarse sandy, GRAVEL , moist	
38	SW							Light brown to tan, fine to coarse SAND , trace fine gravel, dense, moist	
39	SP		31	24	1.4	9.1		Tan with reddish mottles, fine SAND , trace medium sand and fine gravel, dense, moist	

Project No.: NYSDEC: V-00089-1; URS: 27010-039

Project: Kd Drilling Program

Client: GTEOSI, Hicksville, NY

Log of Boring: KD1

Date Drilled: 8/24/04

Sampler Type: 3-inch/2-inch split spoon driven by 300-lb/140-lb hammer

Logged By: Carrie Olsen



5 Penn Plaza
13th Floor
New York, NY 10001

Depth (feet)	USCS Letter Symbol	USCS Lithologic Symbol	Blows/Foot (center ft only)	Recovery (in per 2-ft interval)	PID Sample Screen (ppm)	Nal 3x3 (kcpm)	Sample Type	Description	Remarks
40	SP							Tan with reddish mottle, fine SAND , dense, moist Tan, trace clay	
41			28	24	0.8	9.0	Kd	Tan to light brown, occasional gravel, medium dense Dark brown, clay grades out Tan, occasional fine gravel	
42								Trace gravel	
43			26	24	1.7	9.0			
44	CL							Trace clay Light brown, some clay, medium dense	
45			18	24	0.7	9.1		Light brown, fine sandy, CLAY , moist, very stiff	
46	CL							Silty, soft, moist to wet	
47			2	24	0.5	10.1			
48	SC							Light brown, clayey, fine SAND , moist, very loose	
49	SP		38	24	6.2	8.1		Light brown to tan, fine to medium SAND , trace fine gravel, dense, moist	
50								Trace coarse sand and fine to coarse gravel Trace medium sand, dense, moist	
51			43	24	7.3	9.5	Kd		
52									

Project No.: NYSDEC: V-00089-1; URS: 27010-039

Project: Kd Drilling Program

Client: GTEOSI, Hicksville, NY

Log of Boring: KD1


Date Drilled: 8/24/04

Sampler Type: 3-inch/2-inch split spoon driven by 300-lb/140-lb hammer

Logged By: Carrie Olsen

URS

5 Penn Plaza
13th Floor
New York, NY 10001

Depth (feet)	USCS Letter Symbol	USCS Lithologic Symbol	Blows/Foot (center ft only)	Recovery (in per 2-ft interval)	PID Sample Screen (ppm)	Nal 3x3 (kcpm)	Sample Type	Description	Remarks
53	SP		48	24	10.2	9.0		Light brown, fine to medium SAND , trace fine to coarse gravel, dense, moist 1" orange sandy clay	
54								Tan to light tan, medium sand grades out, medium dense	
55			21	24	2.5	9.0			
56									
57			20	24	1.6	9.0			
58									
59			20	24	0.5	9.0			
60									
61			22	24	1.3	9.4	Kd		
62									
63			23	24	1.2	9.1			
64									
65			31	24	0.0	10.7		Dense	

Project No.: NYSDEC: V-00089-1; URS: 27010-039

Project: Kd Drilling Program

Client: GTEOSI, Hicksville, NY

Log of Boring: KD1

Date Drilled: 8/24/04

Sampler Type: 3-inch/2-inch split spoon driven by 300-lb/140-lb hammer

Logged By: Carrie Olsen



5 Penn Plaza
13th Floor
New York, NY 10001

Depth (feet)	USCS Letter Symbol	USCS Lithologic Symbol	Blows/Foot (center ft only)	Recovery (in per 2-ft interval)	PID Sample Screen (ppm)	Nal 3x3 (kcpm)	Sample Type	Description	Remarks
66	CL							Tan to light tan, fine SAND , dense, moist	
67			37	24	0.5	9.1		Trace bright orange, 1/2" clay seam	
68									
69			26	24	0.9	9.0		Medium dense	
70	SP								
71			33	24	0.0	9.4	Kd	Dense	
72									
73			52	24	0.0	9.1			
74								inferred groundwater level	
75			5	0	-	-		No recovery, wet	
76				0					
77									
78			18	14	0.0	NA			NA = Not available (rad data not recorded)

Project No.: NYSDEC: V-00089-1; URS: 27010-039

Project: Kd Drilling Program

Client: GTEOSI, Hicksville, NY

Log of Boring: KD1

Date Drilled: 8/24/04

Sampler Type: 3-inch/2-inch split spoon driven by 300-lb/140-lb hammer

Logged By: Carrie Olsen



5 Penn Plaza
13th Floor
New York, NY 10001

Depth (feet)	USCS Letter Symbol	USCS Lithologic Symbol	Blows/Foot (center ft only)	Recovery (in per 2-ft interval)	PID Sample Screen (ppm)	Nal 3x3 (kcpm)	Sample Type	Description	Remarks
79	SP							Tan, fine to medium SAND , trace coarse sand and silt, wet	NA = Not available (PID and rad data not recorded)
				0				No recovery	
80									
81			11	20	0.0	NA	Kd	Tan, fine to medium SAND , trace coarse sand and silt, medium dense, wet	
82									
83	SP		23	22	NA	NA			
84									
85			16	10	NA	NA			
86								No samples collected	
87									
88	SP		135	12	NA	NA		Tan, fine to medium SAND , trace coarse sand and silt, very dense, wet	
89								No samples collected	
90									
91	SP		79	22	NA	NA		Tan, fine to medium SAND , trace coarse sand and silt, very dense, wet	

Project No.: NYSDEC: V-00089-1; URS: 27010-039

Project: Kd Drilling Program

Client: GTEOSI, Hicksville, NY

Log of Boring: KD1

Date Drilled: 8/24/04

Sampler Type: 3-inch/2-inch split spoon driven by 300-lb/140-lb hammer

Logged By: Carrie Olsen



5 Penn Plaza
13th Floor
New York, NY 10001

Depth (feet)	USCS Letter Symbol	USCS Lithologic Symbol	Blows/Foot (center ft only)	Recovery (in per 2-ft interval)	PID Sample Screen (ppm)	NaI 3x3 (kcpm)	Sample Type	Description	Remarks
92	SP							Tan, fine to medium SAND , trace coarse sand and silt, very dense, wet	NA = Not available (PID and rad data not recorded)
								No samples collected	
93								No lithology data recorded	
94			63	10	NA	NA			
95								No samples collected	
96									
97									
98									
99									
100									
101			14	0	-	-		No recovery	
102								No samples collected	
103									
104									

Project No.: NYSDEC: V-00089-1; URS: 27010-039

Project: Kd Drilling Program

Client: GTEOSI, Hicksville, NY

Log of Boring: KD1

Date Drilled: 8/24/04

Sampler Type: 3-inch/2-inch split spoon driven by 300-lb/140-lb hammer

Logged By: Carrie Olsen



5 Penn Plaza
13th Floor
New York, NY 10001

Depth (feet)	USCS Letter Symbol	USCS Lithologic Symbol	Blows/Foot (center ft only)	Recovery (in per 2-ft interval)	PID Sample Screen (ppm)	Nal 3x3 (kcpm)	Sample Type	Description	Remarks
105								No samples collected	
106									
107									
108									
109									
110									
111									
112									
113									
114									
115									
116									
117									

Project No.: NYSDEC: V-00089-1; URS: 27010-039

Project: Kd Drilling Program

Client: GTEOSI, Hicksville, NY

Log of Boring: KD1

Date Drilled: 8/24/04

Sampler Type: 3-inch/2-inch split spoon driven by 300-lb/140-lb hammer

Logged By: Carrie Olsen



5 Penn Plaza
13th Floor
New York, NY 10001

Depth (feet)	USCS Letter Symbol	USCS Lithologic Symbol	Blows/Foot (center ft only)	Recovery (in per 2-ft interval)	PID Sample Screen (ppm)	Nal 3x3 (kcpm)	Sample Type	Description	Remarks
118								No samples collected	
119									
120									
121								No recovery	
122									
123			65	0	-	-			
124	EOB							NOTES: 1. Boring completed to a depth of 124' on 8/31/04 2. Groundwater estimated at 74' bgs during drilling 3. Continuous sampling was discontinued from 94.5-120' bgs (flowing sand in auger) 4. Boring backfilled to surface with clean soil on 9/3/04 5. Kd samples included off-Site nickel, off-Site uranium, off-Site thorium, on-Site VOCs, and a sample for the GTE attorneys	
125									
126									
127									
128									
129									
130									

Project No.: NYSDEC: V-00089-1; URS: 27010-039

Project: Kd Drilling Program/Lithological Drilling Program

Client: GTEOSI, Hicksville, NY

Log of Boring: KD2

Date Drilled: 9/20/04

Sampler Type: 3-inch split spoon driven by 300-lb hammer / Shelby tube / piston sampler

Logged By: Carrie Olsen



5 Penn Plaza
13th Floor
New York, NY 10001

Depth (feet)	USCS Letter Symbol	USCS Lithologic Symbol	Blows/Foot (center ft only)	Recovery (in per 2-ft interval)	PID Sample Screen (ppm)	Nal 3x3 (kcpm)	Sample Type	Description	Remarks
1								Asphalt Surface elevation at 145.8', first sample at 20' below reference	
2								FILL , brown, fine sand, some medium sand, trace coarse sand, fine to coarse gravel, and asphalt debris, dry (lithology observed from auger cuttings to 20' bgs)	
3									
4									
5								(Fill depth interpreted from adjacent borings) Brown, fine SAND , some medium sand, trace coarse sand, fine to coarse gravel, dry	
6									
7									
8	SP								
9									
10									
11									
12									
13									

Project No.: NYSDEC: V-00089-1; URS: 27010-039

Project: Kd Drilling Program/Lithological Drilling Program

Client: GTEOSI, Hicksville, NY

Log of Boring: KD2





Date Drilled: 9/20/04

Sampler Type: 3-inch split spoon driven by 300-lb hammer / Shelby tube / piston sampler

Logged By: Carrie Olsen



5 Penn Plaza
13th Floor
New York, NY 10001

Depth (feet)	USCS Letter Symbol	USCS Lithologic Symbol	Blows/Foot (center ft only)	Recovery (in per 2-ft interval)	PID Sample Screen (ppm)	Nal 3x3 (kcpm)	Sample Type	Description	Remarks
14	SP							Brown, fine SAND , some medium sand, trace coarse sand, fine to coarse gravel, dry	
15									
16									
17									
18	SW							Brown, fine to coarse SAND , trace fine gravel, medium dense, dry	
19									
20									
21			11	18	0.2	11.1	Kd		
22	SW							Light brown, some to trace gravel	
23			25	32	-	-			
24									
25			SP	19	18	-	-		
26	SW						Kd	Light brown, fine to coarse SAND , some to trace fine gravel, medium dense, dry	

Project No.: NYSDEC: V-00089-1; URS: 27010-039

Project: Kd Drilling Program/Lithological Drilling Program

Client: GTEOSI, Hicksville, NY

Log of Boring: KD2

Date Drilled: 9/20/04

Sampler Type: 3-inch split spoon driven by 300-lb hammer / Shelby tube / piston sampler

Logged By: Carrie Olsen



5 Penn Plaza
13th Floor
New York, NY 10001

Depth (feet)	USCS Letter Symbol	USCS Lithologic Symbol	Blows/Foot (center ft only)	Recovery (in per 2-ft interval)	PID Sample Screen (ppm)	Nal 3x3 (kcpm)	Sample Type	Description	Remarks
27								No samples collected	
28									
29									
30									
31	SP		28	18	0.0	10.4	Kd	Light brown, fine to medium SAND , some coarse sand and fine gravel, medium dense, dry	
32								Gravel and coarse sand grade out from 31.7-32'	
33								No samples collected	
34									
35									
36									
37									
38									
39									

Project No.: NYSDEC: V-00089-1; URS: 27010-039

Project: Kd Drilling Program/Lithological Drilling Program

Client: GTEOSI, Hicksville, NY

Log of Boring: KD2

Date Drilled: 9/20/04

Sampler Type: 3-inch split spoon driven by 300-lb hammer / Shelby tube / piston sampler

Logged By: Carrie Olsen



5 Penn Plaza
13th Floor
New York, NY 10001

Depth (feet)	USCS Letter Symbol	USCS Lithologic Symbol	Blows/Foot (center ft only)	Recovery (in per 2-ft interval)	PID Sample Screen (ppm)	Nal 3x3 (kcpm)	Sample Type	Description	Remarks
40								No samples collected	
41	SP		20	19	0.5	10.3	Kd	Light brown, fine to medium SAND , some coarse sand and fine gravel, medium dense, dry Coarse gravel/cobbles at 40.75' Fine sand, some medium sand, trace fine gravel, medium dense, moist	
42								No samples collected	
43									
44	SP							Light brown, fine SAND , some medium sand, trace fine gravel, medium dense, moist	
45			14	17	-	-	Kd	Light brown, silty, fine SAND , medium dense, moist	
46	SM								
47			21	19	-	-	GT	Light brown to tan	
48								No samples collected	
49									
50									
51	SP		27	22	0.4	10.5	Kd	Brown, fine to medium SAND , trace coarse sand and fine gravel, medium dense, moist Tan, fine sand, coarse sand and gravel grade out, occasional clay balls	
52									

Project No.: NYSDEC: V-00089-1; URS: 27010-039

Project: Kd Drilling Program/Lithological Drilling Program

Client: GTEOSI, Hicksville, NY

Log of Boring: KD2

Date Drilled: 9/20/04

Sampler Type: 3-inch split spoon driven by 300-lb hammer / Shelby tube / piston sampler

Logged By: Carrie Olsen



5 Penn Plaza
13th Floor
New York, NY 10001

Depth (feet)	USCS Letter Symbol	USCS Lithologic Symbol	Blows/Foot (center ft only)	Recovery (in per 2-ft interval)	PID Sample Screen (ppm)	Nal 3x3 (kcpm)	Sample Type	Description	Remarks		
53								No samples collected			
54											
55											
56											
57											
58											
59											
60											
61	SP		20	13	0.2	10.4		Tan, fine SAND , intermittent clay, medium dense, moist			
62											
63								No samples collected			
64											
65											

Project No.: NYSDEC: V-00089-1; URS: 27010-039

Project: Kd Drilling Program/Lithological Drilling Program

Client: GTEOSI, Hicksville, NY

Log of Boring: KD2

Date Drilled: 9/20/04

Sampler Type: 3-inch split spoon driven by 300-lb hammer / Shelby tube / piston sampler

Logged By: Carrie Olsen



5 Penn Plaza
13th Floor
New York, NY 10001

Depth (feet)	USCS Letter Symbol	USCS Lithologic Symbol	Blows/Foot (center ft only)	Recovery (in per 2-ft interval)	PID Sample Screen (ppm)	NaI 3x3 (kcpm)	Sample Type	Description	Remarks
66								No samples collected	
67									
68									
69									
70			27	24	0.6	NA	Kd	Tan, fine SAND , medium dense, moist	
71	SP								
72			46	24	-	-	GT	Tan to light brown, fine to medium sand, trace silt, dense, moist	
73									
74	▼							No samples collected inferred groundwater level	
75									
76									
77									
78									

Project No.: NYSDEC: V-00089-1; URS: 27010-039

Project: Kd Drilling Program/Lithological Drilling Program

Client: GTEOSI, Hicksville, NY

Log of Boring: KD2

Date Drilled: 9/20/04

Sampler Type: 3-inch split spoon driven by 300-lb hammer / Shelby tube / piston sampler

Logged By: Carrie Olsen



5 Penn Plaza
13th Floor
New York, NY 10001

Depth (feet)	USCS Letter Symbol	USCS Lithologic Symbol	Blows/Foot (center ft only)	Recovery (in per 2-ft interval)	PID Sample Screen (ppm)	Nal 3x3 (kcpm)	Sample Type	Description	Remarks
79			69	0	-	-		No recovery	
80									
81								No samples collected	
82									
83			46	0	-	-		No recovery	
84									
85								No samples collected	
86									
87									
88								No recovery (piston sample attempt)	
89			-	0	-	-			
90								No samples collected	
91									

Project No.: NYSDEC: V-00089-1; URS: 27010-039

Project: Kd Drilling Program/Lithological Drilling Program

Client: GTEOSI, Hicksville, NY

Log of Boring: KD2

Date Drilled: 9/20/04

Sampler Type: 3-inch split spoon driven by 300-lb hammer / Shelby tube / piston sampler

Logged By: Carrie Olsen



5 Penn Plaza
13th Floor
New York, NY 10001

Depth (feet)	USCS Letter Symbol	USCS Lithologic Symbol	Blows/Foot (center ft only)	Recovery (in per 2-ft interval)	PID Sample Screen (ppm)	Nal 3x3 (kcpm)	Sample Type	Description	Remarks
92								No samples collected	
93									
94								No recovery	
95	SM		43	<2	0.0	-	GT	Light brown, silty, fine to medium SAND , some coarse sand, wet	
96			53	12	0.0	-			
97									
98								No samples collected	
99	SM							Light brown, silty, fine to medium SAND , some coarse sand, wet	
100			76	4	0.0	-			
101									
102								No samples collected	
103								No recovery	
104			93	0	-	-			

Project No.: NYSDEC: V-00089-1; URS: 27010-039

Project: Kd Drilling Program/Lithological Drilling Program

Client: GTEOSI, Hicksville, NY

Log of Boring: KD2

Date Drilled: 9/20/04

Sampler Type: 3-inch split spoon driven by 300-lb hammer / Shelby tube / piston sampler

Logged By: Carrie Olsen

URS

5 Penn Plaza
13th Floor
New York, NY 10001

Depth (feet)	USCS Letter Symbol	USCS Lithologic Symbol	Blows/Foot (center ft only)	Recovery (in per 2-ft interval)	PID Sample Screen (ppm)	Nal 3x3 (kcpm)	Sample Type	Description	Remarks
105								No recovery	
106									
107								No samples collected	
108									
109	SM		51	8	0.0	-		Light brown, silty, fine to medium SAND , some coarse sand and fine gravel, wet	
110									
111								No samples collected	
112									
113									
114								Light brown, silty, fine to coarse SAND , wet	
115	SM		47	12	0.0	-			
116							Kd		
117									

Project No.: NYSDEC: V-00089-1; URS: 27010-039

Project: Kd Drilling Program/Lithological Drilling Program

Client: GTEOSI, Hicksville, NY

Log of Boring: KD2


Date Drilled: 9/20/04

Sampler Type: 3-inch split spoon driven by 300-lb hammer / Shelby tube / piston sampler

Logged By: Carrie Olsen



5 Penn Plaza
13th Floor
New York, NY 10001

Depth (feet)	USCS Letter Symbol	USCS Lithologic Symbol	Blows/Foot (center ft only)	Recovery (in per 2-ft interval)	PID Sample Screen (ppm)	Nal 3x3 (kcpm)	Sample Type	Description	Remarks
118	SM		51	11	0.0	-	Kd	Light brown, silty, fine to coarse SAND , wet	
119	EOB							NOTES: 1. Boring completed to 118.9' bgs on 9/23/04 2. Groundwater estimated at 74' bgs during drilling 3. Casing and hollow stem auger removed and boring backfilled with clean soil on 09/24/04 4. Kd samples include off-Site nickel, off-Site uranium, off-site thorium, on-Site VOCs, and GTE attorney samples 5. GT, geotechnical samples; samples analyzed for particle size distribution, hydraulic conductivity, total organic carbon, specific gravity, and percent moisture. The sample at 94.5-98.7' bgs was analyzed for particle size distribution and percent moisture.	
120									
121									
122									
123									
124									
125									
126									
127									
128									
129									
130									

Project No.: NYSDEC: V-00089-1; URS: 27010-039

Project: Kd Drilling Program/Lithological Drilling Program

Client: GTEOSI, Hicksville, NY

Log of Boring: KD3

Date Drilled: 9/1/04

Sampler Type: 3-inch split spoon driven by 300-lb hammer

Logged By: Carrie Olsen



5 Penn Plaza
13th Floor
New York, NY 10001

Depth (feet)	USCS Letter Symbol	USCS Lithologic Symbol	Blows/Foot (center ft only)	Recovery (in per 2-ft interval)	PID Sample Screen (ppm)	Nal 3x3 (kcpm)	Sample Type	Description	Remarks
1								Asphalt Surface elevation at 144.9', first sample at 18 ft	
2								FILL , brown, fine to coarse sand, some gravel and topsoil to 5' bgs , trace cobbles, moist (lithology observed from auger cuttings to 18' bgs)	
3									
4								(Fill depth interpreted from adjacent borings)	
5								Brown, fine to coarse SAND , some gravel, trace cobbles, moist	
6									
7									
8	SW								
9									
10									
11									
12									
13									

Project No.: NYSDEC: V-00089-1; URS: 27010-039

Project: Kd Drilling Program/Lithological Drilling Program

Client: GTEOSI, Hicksville, NY

Log of Boring: KD3

Date Drilled: 9/1/04

Sampler Type: 3-inch split spoon driven by 300-lb hammer

Logged By: Carrie Olsen



5 Penn Plaza
13th Floor
New York, NY 10001

Depth (feet)	USCS Letter Symbol	USCS Lithologic Symbol	Blows/Foot (center ft only)	Recovery (in per 2-ft interval)	PID Sample Screen (ppm)	Nal 3x3 (kcpm)	Sample Type	Description	Remarks
14	SW							Brown, fine to coarse SAND , some gravel, trace cobbles, moist	
15									
16									
17									
18	SW								
19			18	20	0.0	9.8		Coarse gravel and cobbles grade out, medium dense, dry	
20									
21	GW		18	21	0.0	9.8	GT	Well graded GRAVEL	
22	SW							Brown, fine to coarse SAND , some fine gravel, medium dense, dry	
23								No samples collected	
24									
25									
26									

Project No.: NYSDEC: V-00089-1; URS: 27010-039

Project: Kd Drilling Program/Lithological Drilling Program

Client: GTEOSI, Hicksville, NY

Log of Boring: KD3

Date Drilled: 9/1/04

Sampler Type: 3-inch split spoon driven by 300-lb hammer

Logged By: Carrie Olsen

URS

5 Penn Plaza
13th Floor
New York, NY 10001

Depth (feet)	USCS Letter Symbol	USCS Lithologic Symbol	Blows/Foot (center ft only)	Recovery (in per 2-ft interval)	PID Sample Screen (ppm)	Nal 3x3 (kcpm)	Sample Type	Description	Remarks
27									
28									
29			25	24	0.0	9.0			
30	SP								
31			19	22	0.0	9.0	GT		
32									
33								No samples collected	
34									
35									
36									
37									
38									
39									

Project No.: NYSDEC: V-00089-1; URS: 27010-039

Project: Kd Drilling Program/Lithological Drilling Program

Client: GTEOSI, Hicksville, NY

Log of Boring: KD3

Date Drilled: 9/1/04

Sampler Type: 3-inch split spoon driven by 300-lb hammer

Logged By: Carrie Olsen





5 Penn Plaza
13th Floor
New York, NY 10001

Depth (feet)	USCS Letter Symbol	USCS Lithologic Symbol	Blows/Foot (center ft only)	Recovery (in per 2-ft interval)	PID Sample Screen (ppm)	Nal 3x3 (kcpm)	Sample Type	Description	Remarks
40									
41	SP		25	24	0.0	9.1	GT	Light brown, fine to medium SAND , trace fine gravel, medium dense, moist	
42								No samples collected	
43									NA = Not available (rad data not recorded)
44	SP		18	24	0.0	NA		Light brown, fine to medium SAND , medium dense, moist Trace clay, medium sand grades out from 44.8-45'	
45									
46	SC		11	24	0.0	11.9	Kd	Light brown, clayey SAND , stiff, moist	
47	ML						GT	SILT	
48	SP		71	15	0.0	11.9		Brown, fine SAND , trace clay, moist	
49								No samples collected	
50									
51	SP							Light brown, fine to medium SAND , medium dense, moist	
51	SP-SM		29	24	0.0	9.8			
52	SP						GT	Poorly graded SAND and silty SAND Light brown, fine to medium SAND , medium dense, moist	

Project No.: NYSDEC: V-00089-1; URS: 27010-039
Project: Kd Drilling Program/Lithological Drilling Program
Client: GTEOSI, Hicksville, NY
Log of Boring: KD3
Date Drilled: 9/1/04
Sampler Type: 3-inch split spoon driven by 300-lb hammer
Logged By: Carrie Olsen




5 Penn Plaza
 13th Floor
 New York, NY 10001

Depth (feet)	USCS Letter Symbol	USCS Lithologic Symbol	Blows/Foot (center ft only)	Recovery (in per 2-ft interval)	PID Sample Screen (ppm)	Nal 3x3 (kcpm)	Sample Type	Description	Remarks
53								No samples collected	
54									
55									
56									
57									
58								Tan, fine SAND , medium dense, moist	
59									
60									
61	SP		18	21	0.0	9.7		Poorly graded SAND and silty SAND	
62	SP-SM						GT		
63								No samples collected	
64									
65									

Project No.: NYSDEC: V-00089-1; URS: 27010-039
Project: Kd Drilling Program/Lithological Drilling Program
Client: GTEOSI, Hicksville, NY
Log of Boring: KD3
Date Drilled: 9/1/04
Sampler Type: 3-inch split spoon driven by 300-lb hammer
Logged By: Carrie Olsen



5 Penn Plaza
 13th Floor
 New York, NY 10001

Depth (feet)	USCS Letter Symbol	USCS Lithologic Symbol	Blows/Foot (center ft only)	Recovery (in per 2-ft interval)	PID Sample Screen (ppm)	Nal 3x3 (kcpm)	Sample Type	Description	Remarks
66								No samples collected	
67									
68									
69									
70									
71	SP		23	20	0.0	9.1	GT	Tan, fine to medium SAND , trace coarse sand, medium dense, moist	
72								No samples collected	
73									
74	▼							inferred groundwater level	
75									
76									
77									
78									

Project No.: NYSDEC: V-00089-1; URS: 27010-039
Project: Kd Drilling Program/Lithological Drilling Program
Client: GTEOSI, Hicksville, NY
Log of Boring: KD3
Date Drilled: 9/1/04
Sampler Type: 3-inch split spoon driven by 300-lb hammer
Logged By: Carrie Olsen



5 Penn Plaza
 13th Floor
 New York, NY 10001

Depth (feet)	USCS Letter Symbol	USCS Lithologic Symbol	Blows/Foot (center ft only)	Recovery (in per 2-ft interval)	PID Sample Screen (ppm)	Nal 3x3 (kcpm)	Sample Type	Description	Remarks
79								No samples collected	
80								No recovery	
81			21	0	-	-			
82									
83			6	0	-	-			
84									
85			19	0	-	-			
86									
87			33	0	-	-			
88									
89	SP		24	12	-	-	GT	Tan, fine to medium SAND , trace coarse sand, medium dense, wet	
90								No recovery	
91									

Project No.: NYSDEC: V-00089-1; URS: 27010-039
Project: Kd Drilling Program/Lithological Drilling Program
Client: GTEOSI, Hicksville, NY
Log of Boring: KD3
Date Drilled: 9/1/04
Sampler Type: 3-inch split spoon driven by 300-lb hammer
Logged By: Carrie Olsen



5 Penn Plaza
 13th Floor
 New York, NY 10001

Depth (feet)	USCS Letter Symbol	USCS Lithologic Symbol	Blows/Foot (center ft only)	Recovery (in per 2-ft interval)	PID Sample Screen (ppm)	Nal 3x3 (kcpm)	Sample Type	Description	Remarks
92	SP		22	12	0.0	9.0	Kd	No recovery	
								Tan, fine to medium SAND , trace coarse sand, medium dense, wet	
93								No samples collected	
94									
95									
96									
97									
98									
99									
100									
101	SW		20	4	0.0	-		Tan, fine to coarse SAND , medium dense, wet	
102									
103									
104	SP		22	5	0.0	-		Light brown, fine SAND , trace silt, wet	

Project No.: NYSDEC: V-00089-1; URS: 27010-039

Project: Kd Drilling Program/Lithological Drilling Program

Client: GTEOSI, Hicksville, NY

Log of Boring: KD3

Date Drilled: 9/1/04

Sampler Type: 3-inch split spoon driven by 300-lb hammer

Logged By: Carrie Olsen



5 Penn Plaza
13th Floor
New York, NY 10001

Depth (feet)	USCS Letter Symbol	USCS Lithologic Symbol	Blows/Foot (center ft only)	Recovery (in per 2-ft interval)	PID Sample Screen (ppm)	Nal 3x3 (kcpm)	Sample Type	Description	Remarks
105	SP							Light brown, fine SAND , trace silt, medium dense, wet	
106			9	0	-	-		No recovery	
107	EOB							NOTES: 1. Boring completed to a depth of 107' on 9/3/04 2. Groundwater estimated at 74' bgs during drilling 3. Boring backfilled to surface with clean soil on 9/3/04 4. Kd samples included off-Site nickel, off-Site uranium, off-site thorium, on-Site VOCs, and sample for the GTE attorneys 5. GT= geotechnical samples; geotechnical samples analyzed for grain size analysis, total organic carbon, specific gravity, and percent moisture. The sample from 100' to 103' bgs was analyzed for total organic carbon.	
108									
109									
110									
111									
112									
113									
114									
115									
116									
117									

Project No.: NYSDEC: V-00089-1; URS: 27010-039

Project: Kd Drilling Program/Lithological Drilling Program

Client: GTEOSI, Hicksville, NY

Log of Boring: KD4

Date Drilled: 9/24/04

Sampler Type: 3-inch/2-inch split spoon driven by 300-lb/140-lb hammer

Logged By: Aimee Clark, Carrie Olsen



5 Penn Plaza
13th Floor
New York, NY 10001

Depth (feet)	USCS Letter Symbol	USCS Lithologic Symbol	Blows/Foot (center ft only)	Recovery (in per 2-ft interval)	PID Sample Screen (ppm)	Nal 3x3 (kcpm)	Sample Type	Description	Remarks
16								BACKFILL Soil previously excavated to 20' bgs and backfilled Surface elevation at 142', first sample at 20'	Lithological observations and field readings limited on geotechnical samples due to their being encased almost entirely in sample tubes. USCS classification of geotechnical samples are based on laboratory results.
17									
18									
19									
20									
21	SW		14	14	0.0	-			
22	SP								
23	SW		25	22	0.1	-	Kd	Tan, fine to coarse SAND , medium dense, moist	
24								Tan, fine to medium SAND , medium dense, moist	
25	SP		10	20	-	-	GT	Tan, fine to medium SAND , medium dense, moist	
26								No samples collected	
27									
28									

Project No.: NYSDEC: V-00089-1; URS: 27010-039

Project: Kd Drilling Program/Lithological Drilling Program

Client: GTEOSI, Hicksville, NY

Log of Boring: KD4

Date Drilled: 9/24/04

Sampler Type: 3-inch/2-inch split spoon driven by 300-lb/140-lb hammer

Logged By: Aimee Clark, Carrie Olsen



5 Penn Plaza
13th Floor
New York, NY 10001

Depth (feet)	USCS Letter Symbol	USCS Lithologic Symbol	Blows/Foot (center ft only)	Recovery (in per 2-ft interval)	PID Sample Screen (ppm)	Nal 3x3 (kcpm)	Sample Type	Description	Remarks
29								No samples collected	
30	SP							Tan, fine to medium SAND , medium dense, moist Brown, some fine gravel, trace silt	
31	SW		12	18	0.1	-	Kd	Tan, fine to coarse SAND , trace fine gravel, medium dense, moist	
32								No samples collected	
33									
34									
35									
36									
37									
38									
39									
40									
41	SP		18	18	16.9	-	Kd	Tan, fine to medium SAND , medium dense, moist	

Project No.: NYSDEC: V-00089-1; URS: 27010-039

Project: Kd Drilling Program/Lithological Drilling Program

Client: GTEOSI, Hicksville, NY

Log of Boring: KD4

Date Drilled: 9/24/04

Sampler Type: 3-inch/2-inch split spoon driven by 300-lb/140-lb hammer

Logged By: Aimee Clark, Carrie Olsen



5 Penn Plaza
13th Floor
New York, NY 10001

Depth (feet)	USCS Letter Symbol	USCS Lithologic Symbol	Blows/Foot (center ft only)	Recovery (in per 2-ft interval)	PID Sample Screen (ppm)	Nal 3x3 (kcpm)	Sample Type	Description	Remarks
42	SP						Kd	Tan, fine to medium SAND , medium dense, moist	
43			23	22	-	-	GT		
44								No samples collected	
45									
46									
47									
48									
49									
50	SP							Tan, fine to medium SAND , medium dense, moist	
51			19	19	0.0	-	Kd		
52								No samples collected	
53									
54									

Project No.: NYSDEC: V-00089-1; URS: 27010-039

Project: Kd Drilling Program/Lithological Drilling Program

Client: GTEOSI, Hicksville, NY

Log of Boring: KD4

Date Drilled: 9/24/04

Sampler Type: 3-inch/2-inch split spoon driven by 300-lb/140-lb hammer

Logged By: Aimee Clark, Carrie Olsen

URS

5 Penn Plaza
13th Floor
New York, NY 10001

Depth (feet)	USCS Letter Symbol	USCS Lithologic Symbol	Blows/Foot (center ft only)	Recovery (in per 2-ft interval)	PID Sample Screen (ppm)	NaI 3x3 (kcpm)	Sample Type	Description	Remarks
55								No samples collected	
56									
57									
58									
59								Tan, fine to medium SAND , cobbles at 60', moist	NA = Not available (blow counts and/or recovery not recorded)
60									
61			NA	16	0.0	-	Kd		
62	SP								
63	SP/SM		NA	NA	-	-	GT	No samples collected	The water table depth was measured inside the auger, and is thus higher than the actual water table depth within the formation. The water table at the time of drilling lay below 71 ft bgs, as the sample collected from 69 to 71 ft was moist, not wet.
64									
65									
66									
67								inferred groundwater level after boring completion	

Project No.: NYSDEC: V-00089-1; URS: 27010-039

Project: Kd Drilling Program/Lithological Drilling Program

Client: GTEOSI, Hicksville, NY

Log of Boring: KD4

Date Drilled: 9/24/04

Sampler Type: 3-inch/2-inch split spoon driven by 300-lb/140-lb hammer

Logged By: Aimee Clark, Carrie Olsen



5 Penn Plaza
13th Floor
New York, NY 10001

Depth (feet)	USCS Letter Symbol	USCS Lithologic Symbol	Blows/Foot (center ft only)	Recovery (in per 2-ft interval)	PID Sample Screen (ppm)	Nal 3x3 (kcpm)	Sample Type	Description	Remarks
68								No samples collected	Borehole advanced from 69 ft to 113 ft bgs using 4-in diameter casing driven by a 300-lb hammer.
69									
70	SP		25	24	0.0	-	Kd	Tan, fine to medium SAND , trace fine gravel	
71									
72								No samples collected	
73									
74									
75									
76									
77									
78									
79								No recovery	
80			88	0	-	-			

Project No.: NYSDEC: V-00089-1; URS: 27010-039

Project: Kd Drilling Program/Lithological Drilling Program

Client: GTEOSI, Hicksville, NY

Log of Boring: KD4

Date Drilled: 9/24/04

Sampler Type: 3-inch/2-inch split spoon driven by 300-lb/140-lb hammer

Logged By: Aimee Clark, Carrie Olsen



5 Penn Plaza
13th Floor
New York, NY 10001

Depth (feet)	USCS Letter Symbol	USCS Lithologic Symbol	Blows/Foot (center ft only)	Recovery (in per 2-ft interval)	PID Sample Screen (ppm)	Nal 3x3 (kcpm)	Sample Type	Description	Remarks
81								No recovery	* Blow counts >100 per ft for casing from 85.25 to 89.25 ft bgs.
82			130					No samples collected	
83			203						
84								No recovery	
85			*						
86								No samples collected	
87									
88									
89									
90									
91									
92									
93									

Project No.: NYSDEC: V-00089-1; URS: 27010-039

Project: Kd Drilling Program/Lithological Drilling Program

Client: GTEOSI, Hicksville, NY

Log of Boring: KD4

Date Drilled: 9/24/04

Sampler Type: 3-inch/2-inch split spoon driven by 300-lb/140-lb hammer

Logged By: Aimee Clark, Carrie Olsen



5 Penn Plaza
13th Floor
New York, NY 10001

Depth (feet)	USCS Letter Symbol	USCS Lithologic Symbol	Blows/Foot (center ft only)	Recovery (in per 2-ft interval)	PID Sample Screen (ppm)	Nal 3x3 (kcpm)	Sample Type	Description	Remarks
94	SP		*63	8	0.0	-	GT	Light brown, fine to medium SAND , some silt, wet	The permeability test was not conducted at the 93-96' bgs sample *These 3 spoons were each over-driven 1'; the blow counts given are for the 6-18" interval within the larger 3' interval.
95									
96									
97			*66	12	0.0	-	Kd		
98									
99									
100			75	0	-	-		No recovery	
101									
102									
103			*54	0	-	-			
104									
105									
106	SM		**48	4	0.0	-	GT	Light brown, silty, fine SAND , some medium sand, wet	**This spoon was over-driven 9"; the blow counts are for the 6-18" interval within the larger 3' interval.

