2023 Periodic Review Report

Location:

Former Alumax Extrusions Site
440 and 320 South Roberts Road, Dunkirk, New York
VCP Site No. V00589-9

Prepared for:

Chautauqua County Department of Public Facilities
454 North Work Street
Falconer, New York

LaBella Project No. 2200014

February 22, 2024

Olympic Towers, 300 Pearl Street, Suite 130 | Buffalo, NY 14202 | p 716-551-6281 | f 716-551-6282

www.labellapc.com

Table of Contents

TABLE OF CONTENTS

Continued

1.0 EXECUTIVE SUMMARY

1.1 Site Summary

The former Alumax Extrusions, Inc. Facility (hereinafter referred to as the "Site") consists of two adjoining tax parcels located at 440 and 320 South Roberts Road, Parcels A and B respectively, City of Dunkirk, New York (Figure 1). According to Chautauqua County and City of Dunkirk online assessment records, the Site is comprised of approximately 12 acres of land situated on the north side of South Roberts Road (see Appendix 1). Progress Drive, constructed in 2014, transects both parcels associated with the Site in a northeast-southwest general direction. Parcel A, located at 440 South Roberts Road and owned by 440 Roberts Road, LLC, contains an approximately 7,200 square-foot office building while the remainder of the parcel consists of a parking area. Parcel B, located at 320 South Roberts Road and owned by Chautauqua County, formerly contained a 140,000 square-foot building that was demolished in early 2009. It should be noted that the concrete floor slabs were left-in-place at that time.

An environmental investigation conducted at the Site revealed that contamination, likely associated with historical operations, had impacted the Site, necessitating remedial activities. Subsequent remedial activities conducted at the Site included in-situ chemical treatment using zero valent iron (ZVI) in the residual source area (December 2004), removal and off-site disposal of sediments within two catch basins at the Site (mid-2000) and installation of a sub-slab vapor (SSV) mitigation system (December 2003). The remedial efforts also included the development of deed restrictions and the June 2004 Combined Institution Control Plan and Operations and Maintenance Plan (CICP/OMP), which provides initial guidance concerning the surface cover, soil/fill excavation and management, groundwater use and routine monitoring for the groundwater within the residual source area. Such guidance has since been updated in the agency-approved November 2021 LaBella Associates, D.P.C. (LaBella) Site Management Plan (SMP).

1.2 Effectiveness of Remedial Program

Based on a recent inspection of the Site, the cover system elements that are currently present on the Site are intact and functioning as intended on the Site. The anticipated construction of the new driveway through the 440 South Roberts Road parcel should be completed in compliance with the SMP's Excavation Work Plan (EWP).

Overall, the remedial program is viewed to be effective in achieving the remedial objectives of the Site. The Site will continue to be monitored in accordance with the SMP. Based upon current analytical results, total chlorinated volatile organic compound (VOC) concentrations in two of the three groundwater wells (AL-2 and AL-7) that comprise the Site's monitoring network were below the SMP threshold of 100 micrograms per liter (ug/L). Analytical results dating back to post remediation suggest that natural attenuation is occurring at the Site. However, the total VOC concentrations at AL-1 were in exceedance of the 100 ug/L threshold. As such and in accordance with the SMP, annual groundwater monitoring will continue until total concentrations of chlorinated VOCs fall below 100 ug/L in all three wells.

1.3 Compliance

No areas of non-compliance regarding the major elements of the SMP were identified during the preparation of this Periodic Review Report (PRR). No change of use, groundwater use, excavations or imports occurred during the certifying period.

1.4 Recommendations

No recommended changes to SMP were identified during this PRR.

2.0 SITE OVERVIEW

2.1 Site Background

Industrial development of the project Site was initiated around 1920, when the American Locomotive Company expanded its Dunkirk operations onto the project Site. The Site use has varied over time and uses have included a foundry, coal storage, locomotive manufacturing and finned heat exchanger fabrication. In 1976, the facility was acquired by Alumax, Inc. (Alumax), which operated an aluminum extrusion business at the Site until 1993, operating as Alumax Extrusions, Inc. Alcoa's acquisition of Alumax in 1998 included the idle Dunkirk facility.

The project Site consists of two adjoining parcels located at 440 and 320 South Roberts Road, Parcels A and B respectively, within the City of Dunkirk, New York (Figure 1). According to Chautauqua County online assessment records, the Site is comprised of approximately 12 acres of land situated on the north side of South Roberts Road (see Appendix 1). Progress Drive, constructed in 2014, transects both parcels associated with the Site in a northeast-southwest general direction. Parcel A, located at 440 South Roberts Road and owned by 440 Roberts Road, LLC, contains an approximately 7,200 square-foot office building while the remainder of the parcel consists of parking areas. Parcel B, located at 320 South Roberts Road and owned by Chautauqua County, formerly contained a 140,000 square-foot building that was demolished in early 2009. It should be noted that the concrete floor slabs were left-in-place at that time. Parcel B has remained vacant and undeveloped with the exception of the construction of a segment of Progress Drive that transects the Site. The plans for the construction of this roadway were developed and carried out in accordance with the CICP/OMP. During construction of the roadway, select portions of the former building concrete slabs were crushed and spread out on the surface of the Site outside of the new roadway limits. Construction of the roadway was completed in Fall 2014. Parcels A and B are identified in the November 2004 Deed Restriction (Appendix 1) and are depicted on Figure 2. It should be noted that the parcels detailed in the Deed Restriction are different than the current Chautauqua County parcel boundaries, since the Deed Restriction was written prior to construction of the roadway.

A Notice of Intrusive Activities (NIA) was submitted for the 440 South Roberts Road parcel only, to the New York State Department of Environmental Conservation (NYSDEC), on November 11, 2022 (Revised December 1, 2022). 440 Roberts Road, LLC took ownership of this parcel from Chautauqua County in 2022. The intent of the NIA was to inform the NYSDEC of the proposed construction of a new driveway through the parcel, connecting the north adjacent Edgewood Warehouse property to the south abutting thoroughfare (Progress Drive). On January 3, 2023, a Change-of-Use (COU) form was submitted by 440 Roberts Road, LLC, for the construction of this new driveway to take place. As of the date of this PRR, construction of the new driveway has not commenced and 440 Roberts Road, LLC has indicated that there is currently no confirmed schedule for construction of the new driveway.

An illustration of the proposed new driveway is presented in Figure 3.

2.2 Remedial Program Overview

An environmental investigation conducted at the Site revealed that contamination, likely associated with the historical operations, had impacted the Site, necessitating remedial activities. Constituents of potential concern (COPCs) identified within soil/fill at the Site consisted primarily of chlorinated hydrocarbons (specifically trichloroethene (TCE) and its degradation products), polycyclic aromatic hydrocarbons, polychlorinated biphenyls and metals.

A residual source area containing concentrations of TCE, and its degradation products was identified in the subsurface on the north-central portion of the Site.

With the exception of the chlorinated hydrocarbons, groundwater has not shown impacts from the COCPs identified in the soil/fill.

Subsequent remedial activities conducted at the Site included in-situ chemical treatment of groundwater using ZVI in the residual source area (December 2004), removal and off-site disposal of sediments within two catch basins at the Site (mid-2000s) and installation of a SSV mitigation system (December 2003). The remedial efforts also included the development of deed restrictions and the June 2004 CICP/OMP, which provides initial guidance concerning the surface cover, soil/fill excavation and management, groundwater use, and routine monitoring for the groundwater within the residual source area. Such guidance has since been updated in the agency-approved November 2021 LaBella SMP.

Additionally, as indicated previously, the 140,000 square-foot building formerly located on Parcel B was demolished in early 2009. Prior to the demolition, the asbestos-containing-materials within the former Site building were abated in accordance with the requirements outlined in12 NYCRR Part 56 of New York State Department of Labor Industrial Code Rule 56 (ICR 56). The abatement work was completed between November and December of 2008. Demolition of the building occurred in January and February of 2009. Operation of the SSV mitigation system associated with the building ceased in conjunction with the demolition project and this system no longer exists.

3.0 EFFECTIVENESS OF THE REMEDIAL PROGRAM

Remedial goals for the Site were accomplished through in-situ chemical treatment of groundwater using ZVI in the residual source area; the removal and off-site disposal of sediments within the two catch basins at the Site; the installation of a sub-slab venting system; and the development of deed restrictions and the June 2004 CICP/OMP.

As indicated in the December 15, 2014, Corrective Measures Summary Report, cover system requirements were satisfied within the Progress Drive corridor that transects the Site. Such included at a minimum, six inches of material (asphalt and sub-base) for the roadway and 12 inches of clean NYSDEC Division of Environmental Remediation (DER)-10 approved soil underlain by a demarcation layer (orange fencing) beneath road shoulders and parallel storm water ditches associated with the roadway. Review of construction as-builts confirmed that all applicable minimum cover system thicknesses were met within the road corridor.

Based on the comparison of the pre-remedial and the post-remedial groundwater analytical results, the enhanced natural attenuation appears to be achieving the goal of reducing the concentrations of chlorinated hydrocarbons in the groundwater. However, the total VOC concentrations at AL-1 were in exceedance of the 100 ug/L threshold. As such and in accordance with the SMP, annual groundwater monitoring will continue until total concentrations of chlorinated VOCs fall below 100 ug/L in all three wells.

4.0 INSTITUTIONAL/ENGINEERING CONTROL (IC/EC) PLAN COMPLIANCE REPORT

4.1 Institutional Controls

4.1.1 Site Use Restrictions

In accordance with the deed restrictions and the SMP, the Site is to be used for restricted commercial or restricted industrial uses only. The SMP presents the following definitions for these use categories:

- Restricted Commercial-Residential uses are not allowed under this category. Commercial uses are allowed but require engineering controls and/or institutional controls. Some types of "commercial" uses that could create "residential" types of exposures are excluded, such as day-care and health-care facilities. Retail stores, warehouse/distribution centers, service facilities and offices would be included in the commercial definition.
- Restricted Industrial-Residential and commercial uses are not allowed. Industrial uses are allowed but they require engineering controls and/or institutional controls. Metal working, manufacturing and other industrial uses are included in this category.

The office building on Parcel A is currently vacant, but was formerly used for commercial office purposes, while the remainder of the Site was used for office-related parking. The use of Parcel A meets the definition of Restricted Commercial use. Parcel B is vacant and undeveloped. Both parcels are now transected by a segment of Progress Drive, which was constructed in late 2014.

4.1.2 Groundwater Use Restrictions

Previous investigations conducted at the Site and adjacent properties have determined that groundwater resources are limited, particularly within the uppermost groundwater-bearing zone at the Site. Groundwater is not generally used in the vicinity of the Site, nor would it be expected to be used in the future, given the industrial character of the area, the availability of a municipal water supply in the area and the construction of the roadway. The clayey soils and shale bedrock have low hydraulic conductivities and produce limited quantities of water. The most productive zone is the top five feet of the shale bedrock, which is fractured and weathered. This zone is also considered to be perched and may be laterally limited. Groundwater in the north-central portion of the Site (i.e. residual source area) is impacted with chlorinated hydrocarbons. Low concentrations of petroleum-related constituents were encountered in other wells. The residual source area was addressed via in-situ treatment technology; however, low-level impacts to groundwater may linger due to the low conductivity and the potential dissolution of chlorinated constituents adsorbed to the clayey soils. Therefore, groundwater use restrictions were implemented at the Site to limit potential exposure to impacted groundwater and are identified in the deed restrictions recorded with the Site deed.

Although groundwater use is not prohibited, it is restricted. Should a future owner or operator determine that groundwater use is beneficial to their operations, permission from the NYSDEC must be obtained. Additionally, the owner or operator must conduct an evaluation of the suitability for the potential use of the groundwater and define the ultimate point of discharge (e.g. sanitary sewer, surface water, or reinjection) for any once-through water or blowdown from any recirculation system(s). Use of groundwater may require appropriate treatment to meet water quality requirements for use and discharge. Groundwater extracted for testing, monitoring and remediation, while excluded from the provisions of this groundwater use restriction, must meet local, state and federal disposal requirements.

4.1.3 Excavation Work Plan

The EWP was prepared to identify environmental guidelines for the management of subsurface soil/fill and long-term maintenance of the cover system. The EWP includes requirements that address the following key components:

- Any breach of the cover system;
- Surface erosion and storm water runoff control;
- Management of excavated soil/fill;
- Allowable reuse of excavated soil/fill;
- Requirements for off-site fill and grading materials;
- Notification requirements; and,
- Annual reporting and certification results.

4.1.4 Groundwater Monitoring

Groundwater monitoring is required for evaluating the effectiveness of ZVI application in the residual source area that was completed in December 2004. This monitoring consists of sampling and analysis of groundwater collected from Monitoring wells AL-1, AL-2 and AL-7 (see Figure 2). The samples are analyzed for United States Environmental Protection Agency (USEPA) Target Compound List (TCL) VOCs. Annual groundwater monitoring is performed in conjunction with the annual review of the institutional and engineering controls. In accordance with the SMP, this annual monitoring will occur until total concentrations of chlorinated VOCs fall below 100 ug/L in all three monitoring wells. Groundwater monitoring conducted in 2022 revealed that total VOC concentrations in well AL-1 exceeded the 100 ug/L concentration threshold. Therefore, groundwater samples were collected from all three wells during the current reporting period and the results, which are compared with the aforementioned threshold for total VOCs and the pre-remedial analytical results, are summarized in Section 5.2 of this report.

Groundwater elevation data for this reporting period and monitoring well details are presented in the table below.

Well ID	Top of Casing (ft)	Depth to Water (ft bgs)	Groundwater Elevation (ft AMSL)
AL-1	615.66	7.59	608.07
AL-2	617.63	6.65	610.98
AL-7	611.27	1.95	609.32

1. Ft bgs = Feet below the ground surface
2. AMSL = Above mean sea level
3. Top of casing elevation data was sourced from the August 2011 TVGA Consultants PRR.

4.2 Engineering Controls

4.2.1 Surface Cover System

The long history of industrial use of the Site has resulted in widespread, low-level impacts of Site-wide soils. To limit casual exposure to the Site soils, a surface soil cover system consisting of clean soil, pavement, and/or concrete will be constructed as the Site is developed. The purpose of the surface cover system will be to eliminate the potential for human contact with fill material and eliminate the potential for contaminated runoff from the Site. The cover system will consist of one or more of the following types of clean material:

- Soil: 12 inches of vegetated soil cover underlain by a demarcation layer in outdoor vegetated areas.
- Asphalt: A minimum of six inches of material (asphalt and sub-base material) in areas that will become roads, sidewalks and parking lots.
- Concrete: A minimum of six inches of material (concrete and sub-base material) in areas that will become slab-on-grade structures or for roads, sidewalks, and parking lots in lieu of asphalt.

In the Summer/Fall of 2014, a new public roadway and associated storm water drainage ditches were constructed across a portion of the Site. Construction details implemented for the roadway included a 12-inch sub-base followed by a 6-inch base course, 2-inch binder course and 1.5-inch top course of asphalt. Between 2-3 feet of clean, NYSDEC DER-10 approved soil, underlain by a demarcation layer (orange fencing), was placed along the margins of the roadway. The drainage ditches were then constructed within the clean soil to depths of a minimum of 12-inches above the demarcation layer. Figure 4 details the 2004 Soil Cover and Paving Plan extracted from the projects November 2021 LaBella SMP.

On December 12, 2023, Mr. Andrew Koons of LaBella conducted the annual inspection, which included traversing the Site on foot to observe the current conditions. Parcel A contained an approximately 7,200 square-foot building and related parking areas, as well as a portion of Progress Drive. Parcel B was vacant and undeveloped with the exception of Progress Drive, which transects the parcel in a northeast-southwest direction.

At the time of the Site inspection, the asphalt cover occurring within the Progress Drive corridor was in good condition and no areas of exposed sub-base were observed. The floor and walls of the roadside ditches were covered with coarse, low-lying vegetation. No evidence of erosion or exposed synthetic erosion control fabric was observed within the storm water ditches. The remainder of Parcel B consisted of portions of intact concrete building slabs that remain following demolition of the former on-site buildings and rubblized concrete.

Given the current extent of cover, the limited area that currently lacks cover and the vacant nature of the Site, as it's currently unused, no current sources of surface soil contamination are present at this time.

Appendix 2 includes photographs taken during the Site inspection.

4.2.2 Sub-Slab Vapor Mitigation

The former building that occupied the Site contained a sub-slab venting system that was located over the residual source area. The building and sub slab venting system were demolished in early 2009. Therefore, the continued maintenance and operation of this system is no longer required.

For slab-on-grade structures, an 8-millimeter polyethylene barrier will be placed beneath the concrete for new structures built in the portion of the Site identified as the residual source area. The vapor barrier is not required in areas other than the residual source area because VOCs were not found in significant quantities on any other portion of the Site. A soil vapor intrusion assessment will be completed for any new construction near the residual source area.

4.3 IC/EC Certification

The IC/EC Certification Form was completed in its entirety as all ICs/ECs are in place for the Site per the SMP. No change of use, groundwater use, excavations or imports occurred during the certifying period. Appendix 3 includes the NYSDEC "Site Management Periodic Review Report Notice-Institutional and Engineering Controls Certification Form."

5.0 MONITORING PLAN COMPLIANCE REPORT

5.1 Requirements

Sections 4.0 and 7.0 of the SMP include groundwater monitoring requirements associated with the performance monitoring of the in-situ remedial measures for the chlorinated hydrocarbons and the annual certification of the implementation of the Institutional Control Plan, respectively.

5.2 Groundwater Monitoring

Groundwater Monitoring is required for evaluating the effectiveness of the ZVI application in the residual source area that was completed in December 2004. In accordance with the SMP, this annual monitoring will occur at three well locations (AL-1, AL-2 and AL-7) until total concentrations of chlorinated VOCs fall below 100 ug/L in all three wells.

5.2.1 Sampling Procedure

The three groundwater monitoring wells were purged and sampled in general accordance with the procedures detailed in the SMP. All monitoring well sampling activities were recorded on groundwater sampling logs, which are included in Appendix 4.

Other observations (e.g., well integrity, etc.) were also noted on the well sampling logs. Prior to the initiation of groundwater sampling, groundwater levels were measured with an electronic water level indicator to determine the static water level below the ground surface elevation. The groundwater levels were used to determine the volume of standing water in the wells.

Per Section 4.3.1 of the SMP, if a well was purged dry then the well was sampled once sufficient volume recovered in the well. Well purging consisted of the evacuation of select well volumes from AL-1, AL-2 and AL-7 using NYSDEC-approved low-flow purging procedures via a Geotech Geopump II Pump. The samples were then collected within three hours of completion of well purging using the low-flow method previously identified.

Sample volumes were collected into clean sample bottles containing hydrochloric acid preservative provided by the laboratory. The groundwater samples were submitted for analysis of TCL VOCs via USEPA Method 8260.

5.2.2 Sample Preservation and Handling

Immediately after collection, all samples were placed in a cooler and chilled with ice. To ensure sample integrity, a Chain-of-Custody (COC) sample record was established and kept with the samples to document each person that handled the samples. The samples were transported to Eurofins/Test America Laboratories, Inc., a New York State Department of Health, Environmental Laboratory Accreditation Program certified laboratory for analysis. The COC records established for the collected samples were maintained throughout the laboratory handling. Copies of the COC and the complete analytical laboratory report are included in Appendix 5.

5.2.3 Quality Assurance/Quality Control

In addition to field samples, QA/QC samples were collected to evaluate the effectiveness of the QA/QC procedures implemented during the field and laboratory activities associated with the project. The QA/QC samples included a blind field duplicate and a trip blank that were also analyzed for TCL VOCs.

Well sampling at the Site and adjoining former Roblin Steel Site were conducted in conjunction with one another on December 12, 2023, and the samples from both sites were submitted to the laboratory together in one batch and recorded on one COC. As such, the blind field duplicate collected from the former Roblin Steel Site (collected from MW-09R) and trip blank associated with the samples from both sites were utilized to evaluate the effectiveness of the QA/QC procedures for the Site.

5.2.4 Analytical Results

The following section summarizes and discusses the analytical results generated during the aforementioned monitoring event. For discussion purposes, this data is compared with the Standards Criteria and Guidance Values applicable to groundwater: NYSDEC's June 1998 Ambient Water Quality Standards and Guidance Values and Groundwater Effluent Limitations in the Technical and Operational Guidance Series (TOGS) 1.1.1.

Table 1 summarizes the groundwater pre- and post-remedial sampling results and compares the results to applicable water quality standards. Figure 2 depicts the locations of the monitoring wells.

Groundwater flow is generally to the north/northwest in the area containing the Site. However, according to the SMP for the Site, localized flow direction in the vicinity of these wells is generally to the southwest.

Due to the influence of building foundations and subsurface utilities in the area of these wells; however, the water level data from these wells are not likely suitable for determining groundwater flow direction. It should be noted that foundations and utilities were not removed during the building demolition; therefore, flow conditions in this area likely continue to be influenced by these subsurface features.

5.3 Comparisons with Remedial Objectives

The groundwater analytical data for this monitoring event indicate that total chlorinated VOC concentrations in AL-2 and AL-7 were below the 100 ug/L threshold specified in the SMP. However, the total chlorinated VOC concentration in AL-1 exceeded this threshold. The results from each of the monitoring wells are further discussed below. Historical monitoring well data and trendlines are included in Appendix 6.

While six VOCs were identified within AL-1, including four VOCs above NYSDEC TOGS Standards; at 356 ug/L, the total VOC concentration in AL-1 was found to be significantly lower than the pre-remedial sample results recorded in January 2003. However, given that the total VOC concentration in AL-1 exceeds the site-specific threshold, continued monitoring of this location is warranted.

Three VOCs were identified in AL-2, including one VOC above NYSDEC TOGS Standards; at 42.5 ug/L. While, the total VOC concentration in AL-2 has slightly increased since the December 2022 sampling event, such is well below the site-specific threshold prescribed in the SMP.

Three VOCs were identified in AL-7 at 10.9 ug/L. While, the total VOC concentration in AL-7 has slightly increased since the December 2022 sampling event, the total VOC concentration in AL-7 was found to be significantly lower than the initial post-remedial sampling event in February 2009 and is well below the site-specific threshold prescribed in the SMP.

A comparison of the results from MW-09R on the adjacent Roblin Steel Site with the blind field duplicate indicates that the data coincide. No VOCs were identified within the trip blank.

5.4 Monitoring Deficiencies

No monitoring deficiencies were noted during the completion of the PRR and annual sampling event.

5.5 Conclusions and Recommendations

Groundwater monitoring is required for evaluating the effectiveness of the ZVI application that was completed in the residual source area in December 2004. Based upon current analytical results, total chlorinated VOC concentrations in AL-2 and AL-7 are well below the SMP threshold of 100 ug/L. The total chlorinated VOC concentration in AL-1 is significantly lower than the pre-remedial sample results from January 2003. However, given that the total VOC concentration in AL-1 (356 ug/L) was in exceedance of the 100 ug/L threshold, in accordance with the SMP, annual groundwater monitoring will continue until total concentrations of chlorinated VOCs fall below 100 ug/L in all three wells. No changes to the Monitoring Plan or the SMP are recommended at this time.

6.0 CONCLUSIONS AND RECOMMENDATIONS

At the time of the Site inspection, the Site was found to be in compliance with the SMP.

No issues relating to the condition or integrity of the Progress Drive cover system components were noted as a result of the Site inspection conducted by LaBella. The anticipated construction of the new driveway through the 440 South Roberts Road parcel should be completed in compliance with the SMP's, EWP.

Based upon current analytical results, total chlorinated VOC concentrations in two of the three groundwater wells (AL-2 and AL-7) that comprise the Site's monitoring network were below the SMP threshold of 100 ug/L. Analytical results dating back to post remediation suggest that natural attenuation is occurring at the Site. However, the total VOC concentration in AL-1 was in exceedance of the 100 ug/L threshold. As such and in accordance with the SMP, annual groundwater monitoring will continue until total concentrations of chlorinated VOCs fall below 100 ug/L in all three wells.

No changes to the Monitoring Plan, the SMP or the PRR frequency are recommended at this time. The next groundwater sampling event and PRR will occur in December 2024.

7.0 LIMITATIONS

The conclusions presented in this report are based on information gathered in accordance with generally acceptable professional consulting principles and practices. All conclusions reflect observable conditions existing at the time of the Site inspection. Information provided by outside sources (individuals, agencies, laboratories, etc.) as cited herein, was used in the assessment of the Site. The accuracy of the conclusions drawn from this assessment is, therefore, dependent upon the accuracy of information provided by these sources. Furthermore, LaBella is not responsible for the impact of any changes in environmental standards, practices, or regulations subsequent to the performance of services.

This report is based upon the application of scientific principles and professional judgment to certain facts with resultant subjective interpretations. Professional judgments expressed herein are based upon the facts currently available with the limits of the existing data, scope of services, budget and schedule. To the extent that more definitive conclusions are desired by the Client than are warranted by the current available facts, it is specifically Labella's intent that the conclusions and recommendations stated herein will be intended as guidance and not necessarily a firm course of action except where explicitly stated as such. LaBella makes no warranties, expressed or implied including without limitation, warranties as to merchantability or fitness of a particular purpose. Furthermore, the information provided in this report should not be construed as legal advice.

This assessment and report have been completed and prepared on behalf of and for the exclusive use of Chautauqua County. Any reliance on this report by a third party is at such party's sole risk.

8.0 REFERENCES

Declaration of Covenants and Restrictions, Deed Book 02560, Page 0509, Chautauqua County Clerk, November 22, 2004

DER-10/Technical Guidance for Site Investigation and Remediation, NYSDEC, May 3, 2010

Voluntary Clean-Up Program, Combined Institutional Control Plan/Operations and Maintenance Plan, URS Corp., June 23, 2004

Voluntary Clean-Up Program, Interim Remedial Measures Completion Report, Alumax Extrusions, Inc., URS Corp., April 30, 2004

Periodic Review Report, Former Alumax Extrusions Site, TVGA Consultants, August 2011

Corrective Measures Summary Report, Former Alumax Extrusions, Inc. Facility, KHEOPS Architecture, Engineering and Survey, DPC, December 15, 2014

Site Management Plan, Closed Alumax Extrusions Inc., Facility, LaBella Associates, D.P.C., November 2021

Periodic Review Report, Former Alumax Extrusions Site, LaBella Associates, D.P.C., February 2023

LaBella
Powered by partnership.

FIGURES



N

Not To Scale

FIGURE 1
SITE LOCATION MAP

Former Alumax Extrusions Site
320 and 440 South Roberts Road
Dunkirk, New York

LaBella
Powered by partnership.

PROJECT NO. 2200014



LaBella
Powered by partnership.

N
W E
S

0 50 100
Feet

1 inch = 100 feet

INTENDED TO PRINT AS: 11" X 17"

PROJECT:

FORMER ALUMAX EXTRUSIONS SITE

DRAWING NAME:

SITE PLAN

Source: Chautauqua County; Labella 2021.

PROJECT #/DRAWING #/ DATE

2200014

FIGURE 2

1/6/2022

I:\Chautauqua County\2200014 - Dunkirk Brownfield Monitoring\Reports\Event_December 2021\Alumax December 2021\Fig 2 Alumax Site Plan.mxd



NEW DRIVEWAY CONSTRUCTION

SCALE: 1" = 60'

N

LaBella
Powered by partnership.
300 Pearl Street, Suite 130
Buffalo, NY 14202
716-551-6281
labellapc.com

ISSUED FOR:

DRAWING NAME: NEW DRIVEWAY CONSTRUCTION

DRAWN BY:

DATE: 11/07/2022

PROJECT NO.: 2224480

PROJECT NAME: **440 SOUTH ROBERTS DRIVE**
DUNKIRK, NEW YORK

DRAWING NUMBER: FIGURE 3



LaBella
Powered by partnership.

N
W E
S

0 50 100
Feet

1 inch = 100 feet

INTENDED TO PRINT AS: 11" X 17"

PROJECT:

CLOSED ALUMAX EXTRUSIONS, INC. FACILITY

DRAWING NAME:

2004 SOIL COVER & PAVING PLAN

PROJECT #/DRAWING #/ DATE

2200014

FIGURE 4

November 2021

I:\Chautauqua County\2210039.01 - Site Mgmt Plan Updates\DIG\Maps\MXD\2021_10_25\Fig5 2004 Soil Cover & Paving Plan.mxd

LaBella
Powered by partnership.

TABLE

Table 1
Former Alumax Extrusions Site
Summary of Analytical Results
Groundwater Samples

PARAMETER	REGULATORY VALUE	AL-1															
Collection Date		5/31/00	1/16/03	2/10/09	2/22/11	7/19/12	8/15/13	7/15/14	12/12/15	12/14/16	2/2/18	12/12/18	12/5/19	12/3/20	12/2/21	12/13/22	12/12/23
		Pre-Remedial Results		Post-Remedial Results													
Volatile Organic Compounds (ug/L)																	
1,1-Dichloroethene	5		73			9.3			24		2.2						
cis-1,2-Dichloroethene	5	1,500	9,400	1,280	1,140	1,000	961	1,820	3,200	2,500	850	1,100	180	240	26	450	140
trans-1,2-Dichloroethene	5		39			3.9			10		2.4						
2-Butanone	50																
Acetone	50										7.6						
Benzene	1		38	9.77	17.1	17	14.9		9.5		18	14	33	6.8	29	25	27
Carbon Disulfide	60										0.45						
Chloromethane	5																
Cyclohexane	NL		64			180			5.2		17	11	37	4	56	21	33
Ethylbenzene	5		6			2.5					1.1						
Isopropylbenzene	5					5.9											
Methyl Chloride	5																
Methyl Cyclohexane	NL		41			120					16	6.3	24	1.3	27	10	18
Methylene Chloride	5									45							
Toluene	5		43			2.2			3.1		0.81		4.9				
m,p-Xylene	5					4.5											
o-Xylene	5					7.9			2.4								
Total Xylenes	5		13			12.4					3.3		4.2		22		7.6
Trichloroethene	5	2,400	4,600	118	197	100	192	278	88	130	55						
Vinyl chloride	2	240	740	977	825	460	416	1040	850	850	150	540	160	230		200	130
BTEX Compounds	-	0	87	10	17	34	15	0	15	0	20	14	38	7	29	25	35
Total VOCs	-	4,140	15,057	2,385	2,179	1,913	1,584	3,138	4,192	3,525	1,124	1,671	443	482	160	706	356

PARAMETER	AL-2															
Collection Date	5/31/00	1/16/03	2/10/09	2/22/11	7/19/12	8/15/13	7/15/14	12/15/15	12/14/16	2/2/18	12/12/18	12/5/19	12/3/20	12/2/21	12/13/22	12/12/23
	Pre-Remedial Results		Post-Remedial Results													
Volatile Organic Compounds (ug/L)																
1,1-Dichloroethene																
cis-1,2-Dichloroethene			9.36	6.94	2.3	394	1160	8.7		0.87	4.3	14	25	1.6		
trans-1,2-Dichloroethene																
2-Butanone																
Acetone																
Benzene		12	6.1	16.1	13	5.47		5.5	9	4.1	7	11	8.6	23	6.2	30
Carbon Disulfide																
Chloromethane																
Cyclohexane		2			34			4.2		2.4	3.6	1.8	1.4	6.9	1.3	11
Ethylbenzene		4						0.23								
Isopropylbenzene																
Methyl Chloride																
Methyl Cyclohexane								1.5		0.5	0.34	0.25		2.3	0.25 J	1.5
Methylene Chloride									12							
Toluene																
m,p-Xylene																
o-Xylene																
Total Xylenes														4.9		
Trichloroethene								1.5								
Vinyl chloride			3.7			246	104	2.7		1.2		4.6	7			
BTEX Compounds	0	16	6	16	13	5	0	6	9	4	7	11	9	23	6	30
Total VOCs	0	18	19	23	49	645	1,264	24	21	9	15	32	42	39	8	42.5

PARAMETER	AL-7														
Collection Date	2/25/04	2/10/09	2/22/11	7/19/12	8/15/13	7/15/14	12/15/15	12/14/16	2/2/18	12/12/18	12/5/19	12/3/20	12/2/21	12/13/22	12/12/23
	Pre-Remedial Results	Post-Remedial Results													
Volatile Organic Compounds (ug/L)															
1,1-Dichloroethene				4.2											
cis-1,2-Dichloroethene	1,100	600	473	300	517	124	42	7	6.5	7.2	2	3.4	3.7	5.3	2
trans-1,2-Dichloroethene				1.9			0.4								
2-Butanone															1.6 J
Acetone					138	17.9	1.3								7.3 J
Benzene							0.23								
Carbon Disulfide															
Chloromethane														0.99 J	
Cyclohexane				14			0.73			0.54	1				
Ethylbenzene															
Isopropylbenzene															
Methyl Chloride															
Methyl Cyclohexane				27			0.55				0.33				
Methylene Chloride															
Toluene															
m,p-Xylene															
o-Xylene							0.31								
Total Xylenes	29														
Trichloroethene	3,000	154	138	55	109	9.26	6.7	2	0.96						
Vinyl chloride	160	331	271	190	247	17.1	4.8			1.4	1.4	1.3		1.4	
BTEX Compounds	0	0	0	0	0	0	1	0	0	0	0	0	0	0	0
Total VOCs	4,289	1,085	882	592	1,011	168	57	9	7.46	9.14	4.73	4.7	3.7	7.69	10.9

Notes:
Regulatory values are derived from NYS Ambient Water Quality Standards TOGS 1.1.1 (Source of Drinking Water, groundwater).
(-) = No regulatory value is associated with this compound.
Shaded values represent exceedances of the regulatory value.
ug/L = Micrograms per Liter (equivalent to parts per billion (ppb)).
Only compounds with one or more detections are shown.
"NL" = Regulatory value not listed for parameter
Blank spaces indicate that the analyte was not detected.

APPENDIX 1

November 2004 Deed Restrictions/Property Information

Chautauqua County Clerk

Return To:

PUBLIC ABSTRACT CORPORATION
DEFAULT SERVICES
31 E MAIN ST 3RD FL
ROCHESTER NY 14614

Index DEED BOOK

Book 02560 Page 0509

No. Pages 0007

Instrument DECLAR-DEEDS

Date : 11/22/2004

Time : 2:20:53

Control # 200411220133

INST# DE 2004 007426

Employee ID LORENZOT

ALCOA INC

NEW YORK STATE DEPARTMENT OF E
NVIRONMENTAL CONSERV ATION

COUNTY	$	27.00
	$	.00
ST ED DEPT	$	4.75
	$	.00
	$	.00
	$	.00
	$	.00
CEA	$	14.25
	$	.00
Total:	$	46.00

STATE OF NEW YORK
Chautauqua County Clerk

TRANSFER TAX

WARNING: THIS SHEET CONSTITUTES THE CLERK'S ENDORSEMENT, REQUIRED BY SECTION 316-a(5) & SECTION 319 OF THE REAL PROPERTY LAW OF THE STATE OF NEW YORK. DO NOT DETACH.

CONSIDERATN $ .00

Transfer Tax $ .00

Sandra K. Sopak
County Clerk

D025600509

DECLARATION of COVENANTS and RESTRICTIONS

THIS COVENANT is made the 3rd day of November 2004, by ALCOA INC., a Pennsylvania corporation, as successor in interest to Alumax Inc., a Delaware corporation, whose address is Alcoa Corporate Center, 201 Isabella Street, Pittsburgh, Pennsylvania 15212-5858 ("Alcoa").

WHEREAS Alcoa is the subject of Voluntary Agreement Index No. B9-0616-02-06, dated 08 August 2002 (the "Agreement") executed by Robert S. Bear (on behalf of Alcoa) and Susan I. Taluto, Deputy Commissioner – NYSDEC Water Quality and Environmental Remediation as part of the New York State Department of Environmental Conservation's (the "Department's) Voluntary Cleanup Program, namely that parcel of real property located at 320 South Roberts Road in the City of Dunkirk, County of Chautauqua, State of New York, which is part of lands conveyed by:

Warranty Deed made by Alumax Inc. to Alcoa, dated November 3, 2004 and recorded on November 22, 2004 in Liber 2510 of Deeds at page 505;

and being more particularly described in Appendix "A," attached to this declaration and made a part hereof, and hereinafter referred to as "the Property"; and

WHEREAS, the Department approved a remedy to eliminate or mitigate all significant threats to the environment presented by the contamination disposed at the Property and such remedy requires that the Property be subject to restrictive covenants.

NOW, THEREFORE, Alcoa, for itself and its successors and/or assigns, covenants that:

First, the Property subject to this Declaration of Covenants and Restrictions is as shown on a map attached to this declaration as Appendix "B" and made a part hereof, and consists of:

PARCEL A

ALL THAT TRACT OR PARCEL OF LAND, situate in the City of Dunkirk, County of Chautauqua and State of New York and more particularly described as follows:

BEGINNING on the centerline of Roberts Road at the point located 601.13

feet northwesterly along said centerline from the northerly line of lands of the Norfolk and Western Railroad, (former New York, Chicago and St. Louis Railroad); thence north 40° 28' east (assumed bearing) a distance of 396.0 feet to a point; thence north 81° 31' east a distance of 95.9 feet to a point; thence south 8° 39' east a distance of 514.37 feet to an iron pin; thence south 38° 16' west a distance of 114.28 feet to said centerline of Roberts Road; thence north 51° 44' west a distance of 456.6 feet along said centerline to the point or place of beginning.

PARCEL B

ALL THAT TRACT OR PARCEL OF LAND, situate in the City of Dunkirk, County of Chautauqua and State of New York and more particularly described as follows:

BEGINNING in the center line of the existing 30.3 foot pavement in Roberts Road at a point located 94.53 feet northwesterly along said centerline from the northwesterly line of lands of the New York, Chicago & St. Louis Railroad Company; thence north 51° 44' west along said centerline a distance of 50 feet to a point on line of lands now or formerly of Plymouth Tube Company; thence north 38° 16' east a distance of 114.28 feet to an iron pin and passing through an iron pin located 33 feet northeasterly along the last described course from the centerline of Roberts Road; thence north 8° 39' west a distance of 514.37 feet to an iron pin on point of lands now or formerly of Roblin Industries, Inc.; thence continuing along line of lands of Roblin Industries, north 81° 31' east a distance of 822 feet to an iron pin and south 8° 29' east 251.95 feet to a point on line of lands now or formerly of said Railroad Company; thence south 53° 33' west 219.15 feet to a monument; thence north 87° 18' west 24.88 feet to a monument; thence south 53° 33' west 137.59 feet to an iron pin; thence north 88° 30' west 111.6 feet to an iron pin; thence south 56° 19' 32" west 381.7 feet to a monument; thence south 38° 16' west, 102.49 feet to the point or place of beginning, and passing through an iron pin located 33 feet northeasterly along the last described course from the place of beginning.

Second, unless prior written approval by the Department or, if the Department shall no longer exist, any New York State agency or agencies subsequently created to protect the environment of the State and the health of the State's citizens, hereinafter referred to as "the Relevant Agency," is first obtained, there shall be no construction, use or occupancy; disturbance or excavation of the Property that is inconsistent with the approved "Combined Institutional Control Plan and Operations and Maintenance Plan – Former Alumax Extrusions Site," Site No. V00589-9 (Combined Plan) and that results in unacceptable human exposure to contaminated soils.

Third, the owner of the Property shall be responsible to implement the Combined Plan or implementing any modifications to the Combined Plan after obtaining the written approval of the Relevant Agency.

Fourth, the owner of the Property shall prohibit the Property from ever being used for purposes other than for restricted industrial or restricted commercial use without the express written waiver of such prohibition by the Relevant Agency.

Fifth, the owner of the Property shall prohibit the use of the groundwater underlying the Property without treatment rendering it safe for drinking water or industrial purposes, as appropriate, unless the user first obtains permission to do so from the Relevant Agency.

Sixth, the owner of the Property shall continue in full force and effect the prohibition against uses other than restricted commercial and/or industrial uses, and shall assure that any construction, use, occupancy, disturbance or excavation on the property shall be in conformance with the "Combined Plan" as institutional and engineering controls required under the Agreement, and shall continue to implement and annually report on the status, results and effectiveness of the operation, monitoring and maintenance requirements to the Relevant Agency unless the owner first obtains permission to discontinue to do so.

Seventh, this Declaration is and shall be deemed a covenant that shall run with the land and shall be binding upon all future owners of the Property, and shall provide that the owner and its successors and assigns consent to enforcement by the Relevant Agency of the prohibitions, restrictions and requirements set out in this Covenant, the Agreement, and the Combined Plan, and hereby covenant not to contest the authority of the Relevant Agency to seek enforcement.

Eighth, any deed of conveyance of the Property, or any portion thereof, shall recite, unless the Relevant Agency has consented to the termination of such covenants and restrictions, that said conveyance is subject to this Declaration of Covenants and Restrictions.

IN WITNESS WHEREOF, the undersigned has executed this instrument the day first above written.

ALCOA INC.

By: Russell W Porter Jr

Russell W. Porter, Jr.
Vice President

Date: November 3, 2004

STATE OF PENNSYLVANIA)
) SS:
COUNTY OF ALLEGHENY)

Personally appeared before me, the undersigned authority in and for the said county and state, on this 3rd day of November, 2004, within my jurisdiction, the within named Russell W. Porter, Jr., who acknowledged that he is a Vice President of Alcoa Inc., a Pennsylvania corporation, and that for and on behalf of the said corporation, and as its act and deed, he executed the above and foregoing instrument, after first having been duly authorized by said corporation so to do.

Jacqueline L Murtha
Notary Public

My Commission Expires:

Notarial Seal
Jacqueline L. Murtha, Notary Public
City Of Pittsburgh, Allegheny County
My Commission Expires Jan. 24, 2007
Member, Pennsylvania Association Of Notaries

(SEAL)

APPENDIX "A"

PARCEL A

ALL THAT TRACT OR PARCEL OF LAND, situate in the City of Dunkirk, County of Chautauqua and State of New York and more particularly described as follows:

BEGINNING on the centerline of Roberts Road at the point located 601.13 feet northwesterly along said centerline from the northerly line of lands of the Norfolk and Western Railroad, (former New York, Chicago and St. Louis Railroad); thence north 40° 28' east (assumed bearing) a distance of 396.0 feet to a point; thence north 81° 31' east a distance of 95.9 feet to a point; thence south 8° 39' east a distance of 514.37 feet to an iron pin; thence south 38° 16' west a distance of 114.28 feet to said centerline of Roberts Road; thence north 51° 44' west a distance of 456.6 feet along said centerline to the point or place of beginning.

PARCEL B

ALL THAT TRACT OR PARCEL OF LAND, situate in the City of Dunkirk, County of Chautauqua and State of New York and more particularly described as follows:

BEGINNING in the center line of the existing 30.3 foot pavement in Roberts Road at a point located 94.53 feet northwesterly along said centerline from the northwesterly line of lands of the New York, Chicago & St. Louis Railroad Company; thence north 51° 44' west along said centerline a distance of 50 feet to a point on line of lands now or formerly of Plymouth Tube Company; thence north 38° 16' east a distance of 114.28 feet to an iron pin and passing through an iron pin located 33 feet northeasterly along the last described course from the centerline of Roberts Road; thence north 8° 39' west a distance of 514.37 feet to an iron pin on point of lands now or formerly of Roblin Industries, Inc.; thence continuing along line of lands of Roblin Industries, north 81° 31' east a distance of 822 feet to an iron pin and south 8° 29' east 251.95 feet to a point on line of lands now or formerly of said Railroad Company; thence south 53° 33' west 219.15 feet to a monument; thence north 87° 18' west 24.88 feet to a monument; thence south 53° 33' west 137.59 feet to an iron pin; thence north 88° 30' west 111.6 feet to an iron pin; thence south 56° 19' 32" west 381.7 feet to a monument; thence south 38° 16' west, 102.49 feet to the point or place of beginning, and passing through an iron pin located 33 feet northeasterly along the last described course from the place of beginning.

STATE OF NEW YORK, COUNTY OF CHAUTAUQUA, A TRUE COPY OF THE ORIGINAL FILED OR RECORDED IN THIS OFFICE

NOV 24 2004

WITNESS MY HAND AND OFFICIAL SEAL OF THE COUNTY OF CHAUTAUQUA

CHAUTAUQUA COUNTY CLERK



DRAWING OF
BOUNDARY SURVEY
PROPERTY OF
ALUMAX EXTRUSIONS, INC.
City of Dunkirk
Chautauqua County New York
Scale: 1" = 100' January 22, 2001

Land Surveyor, NYS Lic. No. 49520 (GROUND SNOW COVERED)

STATE OF NEW YORK
WESLEY J. WOODBURY STRAIGHT
No. 049520
LICENSED LAND SURVEYOR

WOODBURY SURVEYING – OFFICE OF WESLEY J. WOODBURY STRAIGHT, LS 12 E. 3TH STREET DUNKIRK, NY 14048 366-1990

Chautauqua County - Parcel Report

Parcel Information: **DUNKIRK - C** **79.16-2-5**

Street: 320 Roberts Rd
School District: 60300 - Dunkirk

Acres:	8.81	**Tract:**		**Sub Land Sep.:**	
Frontage:	0	**Lot:**		**Prop Class:**	Vacant comm
Depth:	0	**Section:**		**Sub Div. Lot**	
		Township:		**Filed Map No.:**	
		Range:		**Filed Date:**	

Merge Request Note:
Note:

Current Ownership:

Last	First	Middle	Suffix	Liber	Page	Deed Date	Sale Price	Deed Has Note
County of Chautauqua				2656	219	7/10/2008	1	

Historic Ownership:

Last	First	Middle	Suffix	Liber	Page	Deed Date	Sale Price	Deed Has Note
Alcoa	Inc.			2560	505	11/3/2004	700000	

CHAUTAUQUA COUNTY PROPERTY INFORMATION

LOCATION: 320 S Roberts Rd, Dunkirk SBL (NEW): 79.16-2-5 (OLD): 30-1-7.2.1

PROPERTY INFORMATION

Owner Name	County of Chautauqua	**Neighborhood Code**	200
Total Assessed Value (73.00% Market)	$115,800	**School District Code**	060300
Full Market Value	$158,600	**SWIS Code**	060300
Land Value	$12,600	**Parcel Status**	ACTIVE
Property Type	330 - Vacant comm	**County Taxable**	$0
Lot Size	Acres: 8, Front:0, Depth:0	**Town Taxable**	$0
Mailing Address 1	N 3 Erie St	**School Taxable**	$0
Mailing Address 2		**Village Taxable**	$0
Mailing City, State	Mayville, NY	**Tax Code**	
Mailing ZIP Code	14757	**Bank Code**	
Description #1		**Deed Book**	2656
Description #2		**Deed Page**	219
Description #3	30-1-7.2.1	**Year Built**	-
Roll Year	2021	**Last Sale Date**	7/10/2008

PHYSICAL INFORMATION

# of Bedrooms		**Home/Building Style**	-
# of Baths	-	**Structure Year Built**	-
# of Fireplaces		**Square Footage**	
# of Kitchens		**1st Story Sq. Ft.**	
# of Stories		**2nd Story Sq. Ft.**	
Construction Quality	-	**Additional Story Sq. Ft.**	
Utilities	Gas & elec	**1/2 Story Sq. Ft.**	
Sewer Type	Comm/public	**3/4 Story Sq. Ft.**	
Water Type	Comm/public	**Finished Over Garage Sq. Ft.**	
Waterfront Type	-	**Finished Attic Sq. Ft.**	
Overall Condition	-	**Finished Basement Sq. Ft.**	
Exterior Wall	-	**Unfinished 1/2 Story Sq. Ft.**	
Basement Type	-	**Unfinished 3/4 Story Sq. Ft.**	
Heat Type	-	**Unfinished Room Sq. Ft.**	
Fuel Type	-	**Unfinished Over Garage Sq. Ft.**	
Central Air	-	**Total Living Area**	
Road Type		**Finished Rec Room Sq. Ft.**	

CURRENT TAXES

See current taxes on the Chautauqua County Real Property Services web site

LATEST OWNER

See latest property owner on the Chautauqua County Parcel History Database

COMMERCIAL INFORMATION

Property Class: Vacant comm **Bldg Sq Ft:** -1 **Assessment/Sq Ft:** -1

Buildings:

Site #	Bldg #	Act. Yr. Built	Eff. Yr. Built

Property Use:
Click on site's row for details

Site #	Use #	Used As	Rent Sq Ft	Acres	Rent Type
1	1	Light mfg	153,993	9	

HISTORICAL INFORMATION

Owner History	Deed Book	Deed Page	Sale Date	Valid Sale	Sale Price
County of Chautauqua	2656	219	7/10/2008	NO	$1
Alcoa, Inc	2560	505	11/3/2004	NO	$700,000

IMPROVEMENT INFORMATION

Structure	Size	Grade	Condition	Year Built
Shed-machine	6.00 x 8.00	Average	Normal	1960
Shed-machine	7.00 x 10.00	Average	Normal	1960

EXEMPTIONS

Code Description	Amount	Exempt Percent	Start Year	End Year
CO PROPTY	115800	0	2010	

PHOTO

Image
Not Available

MAP

COMPARABLE SALES

Comparable sales not available for this property.

COMPARABLE ASSESSMENTS

Comparable assessments not available for this property.

Chautauqua County - Parcel Report

Parcel Information: **DUNKIRK - C** **79.16-2-4**

Street: 440 Roberts Rd
School District: 60300 - Dunkirk

Acres:	2.22	**Tract:**		**Sub Land Sep.:**	
Frontage:	0	**Lot:**		**Prop Class:**	Office bldg.
Depth:	0	**Section:**		**Sub Div. Lot**	
		Township:		**Filed Map No.:**	
		Range:		**Filed Date:**	

Merge Request Note:
Note:

Current Ownership:

Last	First	Middle	Suffix	Liber	Page	Deed Date	Sale Price	Deed Has Note
440 Roberts Road LLC				2022	6012	9/14/2022	275,000	

Historic Ownership:

Last	First	Middle	Suffix	Liber	Page	Deed Date	Sale Price	Deed Has Note
County of Chaut. IDA				2022	5223	8/19/2022	275,000	
Cliffstar LLC				2012	5226	9/13/2012	150,000	X
Cliffstar LLC				2705	426	8/24/2010	0	
Cliffstar LLC				2013	6243	10/17/2013	0	X
Cliffstar Corporation				2688	360	11/09/2009	1000000	
Star Wine	LLC			2587	453	11/16/2005	400000	X
Alcoa	Inc			2560	505	11/22/2004		

CHAUTAUQUA COUNTY PROPERTY INFORMATION

LOCATION: 440 S Roberts Rd, Dunkirk SBL (NEW): 79.16-2-4 (OLD): 30-1-7.3

PROPERTY INFORMATION

Owner Name	Cliffstar LLC	**Neighborhood Code**	200
Total Assessed Value (73.00% Market)	$199,340	**School District Code**	060300
Full Market Value	$273,100	**SWIS Code**	060300
Land Value	$11,500	**Parcel Status**	ACTIVE
Property Type	464 - Office bldg.	**County Taxable**	$199,340
Lot Size	Acres: 2, Front:0, Depth:0	**Town Taxable**	$199,340
Mailing Address 1	1 Cliffstar Dr	**School Taxable**	$199,340
Mailing Address 2		**Village Taxable**	$0
Mailing City, State	Dunkirk, NY	**Tax Code**	
Mailing ZIP Code	14048	**Bank Code**	
Description #1		**Deed Book**	2022
Description #2		**Deed Page**	6012
Description #3	30-1-7.3	**Year Built**	-
Roll Year	2021	**Last Sale Date**	8/17/2010

PHYSICAL INFORMATION

# of Bedrooms		**Home/Building Style**	-
# of Baths	-	**Structure Year Built**	-
# of Fireplaces		**Square Footage**	
# of Kitchens		**1st Story Sq. Ft.**	
# of Stories		**2nd Story Sq. Ft.**	
Construction Quality	-	**Additional Story Sq. Ft.**	
Utilities	Gas & elec	**1/2 Story Sq. Ft.**	
Sewer Type	Comm/public	**3/4 Story Sq. Ft.**	
Water Type	Comm/public	**Finished Over Garage Sq. Ft.**	
Waterfront Type	-	**Finished Attic Sq. Ft.**	
Overall Condition	-	**Finished Basement Sq. Ft.**	
Exterior Wall	-	**Unfinished 1/2 Story Sq. Ft.**	
Basement Type	-	**Unfinished 3/4 Story Sq. Ft.**	
Heat Type	-	**Unfinished Room Sq. Ft.**	
Fuel Type	-	**Unfinished Over Garage Sq. Ft.**	
Central Air	-	**Total Living Area**	
Road Type		**Finished Rec Room Sq. Ft.**	

CURRENT TAXES

See current taxes on the Chautauqua County Real Property Services web site

LATEST OWNER

See latest property owner on the Chautauqua County Parcel History Database

COMMERCIAL INFORMATION

Property Class: Office bldg. **Bldg Sq Ft:** 5,902 **Assessment/Sq Ft:** 46

Buildings:

Site #	Bldg #	Act. Yr. Built	Eff. Yr. Built
1	1	1990	

Property Use:
Click on site's row for details

Site #	Use #	Used As	Rent Sq Ft	Acres	Rent Type
1	1	Profssnl off	5,902	2	
1	2	Cold str/Rfrg/W	5,902	2	

HISTORICAL INFORMATION

Owner History	Deed Book	Deed Page	Sale Date	Valid Sale	Sale Price
Cliffstar Corporation	2688	360	10/30/2009	NO	$1,000,000
Cliffstar LLC	2705	426	8/17/2010	NO	$1
Star Wine, LLC	2587	453	11/16/2005	NO	$400,000

IMPROVEMENT INFORMATION

Structure	Size	Grade	Condition	Year Built

EXEMPTIONS

Code Description	Amount	Exempt Percent	Start Year	End Year

PHOTO

Image
Not Available

MAP

COMPARABLE SALES

Comparable sales not available for this property.

COMPARABLE ASSESSMENTS

Comparable assessments not available for this property.

APPENDIX 2

Photographs

View of AL-1 and AL-2

View of AL-7

View of ditch along Progress Drive

View of cover and concrete pad

APPENDIX 3

Site Management Periodic Review Report Notice-Institutional and Engineering Controls Certification Form

Enclosure 2
NEW YORK STATE DEPARTMENT OF ENVIRONMENTAL CONSERVATION
Site Management Periodic Review Report Notice
Institutional and Engineering Controls Certification Form

Site Details **Box 1**

Site No. V00589

Site Name Closed Alumax Extrusions, Inc. Facility
440&
Site Address: 320 South Roberts Road Zip Code: 14048-
City/Town: Dunkirk (C)
County: Chautauqua
Site Acreage: 12.040

Reporting Period: December 15, 2022 to December 15, 2023

	YES	NO
1. Is the information above correct?	X	☐
If NO, include handwritten above or on a separate sheet.		
2. Has some or all of the site property been sold, subdivided, merged, or undergone a tax map amendment during this Reporting Period?	☐	X
3. Has there been any change of use at the site during this Reporting Period (see 6NYCRR 375-1.11(d))?	☐	X
4. Have any federal, state, and/or local permits (e.g., building, discharge) been issued for or at the property during this Reporting Period?	☐	X
If you answered YES to questions 2 thru 4, include documentation or evidence that documentation has been previously submitted with this certification form.		
5. Is the site currently undergoing development?	☐	X

Box 2

	YES	NO
6. Is the current site use consistent with the use(s) listed below? Commercial and Industrial	X	☐
7. Are all ICs in place and functioning as designed?	X	☐

IF THE ANSWER TO EITHER QUESTION 6 OR 7 IS NO, sign and date below and DO NOT COMPLETE THE REST OF THIS FORM. Otherwise continue.

A Corrective Measures Work Plan must be submitted along with this form to address these issues.

Signature of Owner, Remedial Party or Designated Representative Date

SITE NO. V00589 **Box 3**

Description of Institutional Controls

Parcel	Owner	Institutional Control
79.16-2-4	440 Roberts Road, LLC	Ground Water Use Restriction Soil Management Plan Landuse Restriction O&M Plan

Site Management Plan (11/01/2021)and Deed Restriction (filed 11/3/2004):

1) Landuse Restiction: Restricted Industrial or Restricted Commercial.
2) Ground water use restriction.
3) Soils Management Plan/Excavation Work Plan.
4) Surface Cover System.

79.16-2-5	Chautauqua County	Ground Water Use Restriction Landuse Restriction Soil Management Plan Monitoring Plan O&M Plan

Site Management Plan (11/01/2021) and Deed Restriction (filed 11/3/2004):

1) Landuse Restiction: Restricted Industrial or Restricted Commercial.
2) Ground water use restriction.
3) Soils Management Plan/Excavation Work Plan.
4) Surface Cover System.
5) Ground water monitoring.

Box 4

Description of Engineering Controls

Parcel	Engineering Control
79.16-2-4	Cover System

Cover system to be placed once site redeveloped

79.16-2-5	Vapor Mitigation Cover System

Soil vapor intrusion evaluation required for any new or existing building onsite

Cover system to be placed once site redeveloped

Box 5

Periodic Review Report (PRR) Certification Statements

1. I certify by checking "YES" below that:

   a) the Periodic Review report and all attachments were prepared under the direction of, and reviewed by, the party making the Engineering Control certification;

   b) to the best of my knowledge and belief, the work and conclusions described in this certification are in accordance with the requirements of the site remedial program, and generally accepted engineering practices; and the information presented is accurate and compete.

YES	NO
X	☐

2. For each Engineering control listed in Box 4, I certify by checking "YES" below that all of the following statements are true:

   (a) The Engineering Control(s) employed at this site is unchanged since the date that the Control was put in-place, or was last approved by the Department;

   (b) nothing has occurred that would impair the ability of such Control, to protect public health and the environment;

   (c) access to the site will continue to be provided to the Department, to evaluate the remedy, including access to evaluate the continued maintenance of this Control;

   (d) nothing has occurred that would constitute a violation or failure to comply with the Site Management Plan for this Control; and

   (e) if a financial assurance mechanism is required by the oversight document for the site, the mechanism remains valid and sufficient for its intended purpose established in the document.

YES	NO
X	☐

IF THE ANSWER TO QUESTION 2 IS NO, sign and date below and DO NOT COMPLETE THE REST OF THIS FORM. Otherwise continue.

A Corrective Measures Work Plan must be submitted along with this form to address these issues.

_____ _____

Signature of Owner, Remedial Party or Designated Representative Date

IC CERTIFICATIONS
SITE NO. V00589

Box 6

SITE OWNER OR DESIGNATED REPRESENTATIVE SIGNATURE

I certify that all information and statements in Boxes 1,2, and 3 are true. I understand that a false statement made herein is punishable as a Class "A" misdemeanor, pursuant to Section 210.45 of the Penal Law.

I Tim Card (print name) at 454 N. Work St, Falconer, NY 14733, (print business address)

am certifying as Remedial Party (Owner or Remedial Party)

for the Site named in the Site Details Section of this form.

Tim Card

Signature of Owner, Remedial Party, or Designated Representative Rendering Certification

1/4/24

Date

EC CERTIFICATIONS

Box 7

Qualified Environmental Professional Signature

I certify that all information in Boxes 4 and 5 are true. I understand that a false statement made herein is punishable as a Class "A" misdemeanor, pursuant to Section 210.45 of the Penal Law.

I Daniel Noll (print name) at LaBella Associates, DPC 300 State Street, Rochester, NY (print business address),

am certifying as a Qualified Environmental Professional for the Owner (Owner or Remedial Party)

Signature of Qualified Environmental Professional, for the Owner or Remedial Party, Rendering Certification	Stamp (Required for PE)	Date
		1.9.2024

APPENDIX 4

Groundwater Sampling Logs

LaBella
Powered by partnership.

300 Pearl Street Suite 130
Buffalo, New York 14202
Telephone: (716) 551-6281

Project Name: Alumax PRR
Location: Former Alumax Site
Project No.: 2200014
Sampled By: A. Koons
Date: 12/12/2023
Weather: Cloudy, 34°F

WELL I.D.: AL-1

WELL SAMPLING INFORMATION

Well Diameter: 2.0”
Depth of Well: 20.0’
Measuring Point: Top of inner casing
Pump Type: Peri-pump

Static Water Level: 7.59’
Length of Well Screen:
Depth to Top of Pump:
Tubing Type: ¼” OD

FIELD PARAMETER MEASUREMENT

Time	Pump Rate (mL/min)	Gallons Purged	Temp °C	Conductivity (mS/cm) +/- 3%	pH +/- 0.1	Redox (mV) +/- 10 mV	Turbidity (NTU) +/- 10%	Dissolved Oxygen (mg/L) +/- 10%	Comments
8:10	1,000	0	12.3	1.335	6.88	-17.2	7.34	5.28	
8:17	1,000	2.0	13.4	0.773	7.37	-81.9	11.37	4.73	
8:21	1,000	4.0	13.2	0.719	7.42	-38.1	12.43	4.82	

Total 4.0 Gallons Purged

Purge Time Start: 8:10 Purge Time End: 8:21 Final Static Water Level:

OBSERVATIONS

Sampled @ 8:30

Well going dry after 2 well volumes

LaBella
Powered by partnership.

300 Pearl Street Suite 130
Buffalo, New York 14202
Telephone: (716) 551-6281

Project Name: Alumax PRR
Location: Former Alumax Site
Project No.: 2200014
Sampled By: A. Koons
Date: 12/12/2023
Weather: Cloudy, 34°F

WELL I.D.: AL-2

WELL SAMPLING INFORMATION

Well Diameter: 2.0”
Depth of Well: 19.4’
Measuring Point: Top of inner casing
Pump Type: Peri-pump

Static Water Level: 6.65’
Length of Well Screen:
Depth to Top of Pump:
Tubing Type: ¼” OD

FIELD PARAMETER MEASUREMENT

Time	Pump Rate (mL/min)	Gallons Purged	Temp °C	Conductivity (mS/cm) +/- 3%	pH +/- 0.1	Redox (mV) +/- 10 mV	Turbidity (NTU) +/- 10%	Dissolved Oxygen (mg/L) +/- 10%	Comments
9:10	1,000	0.0	12.8	0.843	7.19	-93.2	19.70	6.69	
9:17	1,000	2.0	12.9	0.847	7.33	-166.7	33.76	5.67	
9:24	1,000	4.0	13.5	0.854	7.43	-188.6	17.48	4.24	

Total 4.0 Gallons Purged

Purge Time Start: 9:10 Purge Time End: 9:24 Final Static Water Level:

OBSERVATIONS

Sampled @ 9:35

Well going dry after 2 well volumes

LaBella
Powered by partnership.

300 Pearl Street Suite 130
Buffalo, New York 14202
Telephone: (716) 551-6281

Project Name: Alumax PRR
Location: Former Alumax Site
Project No.: 2200014
Sampled By: A. Koons
Date: 12/12/2023
Weather: Cloudy, 34°F

WELL I.D.: AL-7

WELL SAMPLING INFORMATION

Well Diameter: 2.0”
Depth of Well: 11.5’
Measuring Point: Top of inner casing
Pump Type: Peri-pump

Static Water Level: 1.95’
Length of Well Screen:
Depth to Top of Pump:
Tubing Type: ¼” OD

FIELD PARAMETER MEASUREMENT

Time	Pump Rate (mL/min)	Gallons Purged	Temp °C	Conductivity (mS/cm) +/- 3%	pH +/- 0.1	Redox (mV) +/- 10 mV	Turbidity (NTU) +/- 10%	Dissolved Oxygen (mg/L) +/- 10%	Comments
8:37	1,000	0.0	11.5	0.309	7.50	-133.3	356.99	4.71	
8:42	1,000	1.5	10.8	0.208	7.16	-96.6	24.55	4.56	
8:47	1,000	3.0	10.2	0.282	7.19	-58.9	12.56	6.75	

Total 3.0 Gallons Purged

Purge Time Start: 8:37 Purge Time End: 8:47 Final Static Water Level:

OBSERVATIONS

Sampled @ 8:55

Well going dry after 2 well volumes

APPENDIX 5

Laboratory Analytical Results

eurofins | Environment Testing

ANALYTICAL REPORT

PREPARED FOR

Attn: Chris Kibler
LaBella Associates DPC
300 Pearl Street
Suite 130
Buffalo, New York 14202

Generated 12/22/2023 11:51:51 AM

JOB DESCRIPTION

Alumax & Roblin Periodic Review Reports

JOB NUMBER

480-215658-1

Eurofins Buffalo
10 Hazelwood Drive
Amherst NY 14228-2298

See page two for job notes and contact information.

Job Notes

This report may not be reproduced except in full, and with written approval from the laboratory. The results relate only to the samples tested. For questions please contact the Project Manager at the e-mail address or telephone number listed on this page.

The test results in this report relate only to the samples as received by the laboratory and will meet all requirements of the methodology, with any exceptions noted. This report shall not be reproduced except in full, without the express written approval of the laboratory. All questions should be directed to the Eurofins Environment Testing Northeast, LLC Project Manager.

Authorization

Generated
12/22/2023 11:51:51 AM

Authorized for release by
Rebecca Jones, Project Management Assistant I
Rebecca.Jones@et.eurofinsus.com
Designee for
Brian Fischer, Manager of Project Management
Brian.Fischer@et.eurofinsus.com
(716)504-9835

Table of Contents

Qualifiers

GC/MS VOA

Qualifier	Qualifier Description
E	Result exceeded calibration range.
F1	MS and/or MSD recovery exceeds control limits.
F2	MS/MSD RPD exceeds control limits
J	Result is less than the RL but greater than or equal to the MDL and the concentration is an approximate value.

Glossary

Abbreviation	These commonly used abbreviations may or may not be present in this report.
¤	Listed under the "D" column to designate that the result is reported on a dry weight basis
%R	Percent Recovery
CFL	Contains Free Liquid
CFU	Colony Forming Unit
CNF	Contains No Free Liquid
DER	Duplicate Error Ratio (normalized absolute difference)
Dil Fac	Dilution Factor
DL	Detection Limit (DoD/DOE)
DL, RA, RE, IN	Indicates a Dilution, Re-analysis, Re-extraction, or additional Initial metals/anion analysis of the sample
DLC	Decision Level Concentration (Radiochemistry)
EDL	Estimated Detection Limit (Dioxin)
LOD	Limit of Detection (DoD/DOE)
LOQ	Limit of Quantitation (DoD/DOE)
MCL	EPA recommended "Maximum Contaminant Level"
MDA	Minimum Detectable Activity (Radiochemistry)
MDC	Minimum Detectable Concentration (Radiochemistry)
MDL	Method Detection Limit
ML	Minimum Level (Dioxin)
MPN	Most Probable Number
MQL	Method Quantitation Limit
NC	Not Calculated
ND	Not Detected at the reporting limit (or MDL or EDL if shown)
NEG	Negative / Absent
POS	Positive / Present
PQL	Practical Quantitation Limit
PRES	Presumptive
QC	Quality Control
RER	Relative Error Ratio (Radiochemistry)
RL	Reporting Limit or Requested Limit (Radiochemistry)
RPD	Relative Percent Difference, a measure of the relative difference between two points
TEF	Toxicity Equivalent Factor (Dioxin)
TEQ	Toxicity Equivalent Quotient (Dioxin)
TNTC	Too Numerous To Count

Job Narrative
480-215658-1

Analytical test results meet all requirements of the associated regulatory program listed on the Accreditation/Certification Summary Page unless otherwise noted under the individual analysis. Data qualifiers are applied to indicate exceptions. Noncompliant quality control (QC) is further explained in narrative comments.

- Matrix QC may not be reported if insufficient sample or site-specific QC samples were not submitted. In these situations, to demonstrate precision and accuracy at a batch level, a LCS/LCSD may be performed, unless otherwise specified in the method.
- Surrogate and/or isotope dilution analyte recoveries (if applicable) which are outside of the QC window are confirmed unless attributed to a dilution or otherwise noted in the narrative.

Regulated compliance samples (e.g. SDWA, NPDES) must comply with the associated agency requirements/permits.

Receipt
The samples were received on 12/13/2023 9:00 AM. Unless otherwise noted below, the samples arrived in good condition, and, where required, properly preserved and on ice. The temperature of the cooler at receipt time was 2.9°C

GC/MS VOA
Method 8260C: The continuing calibration verification (CCV) associated with batch 480-695216 recovered outside acceptance criteria, low biased, for 2-Butanone (MEK) . A reporting limit (RL) standard was analyzed, and the target analytes are detected. Since the associated samples were non-detect for the analyte(s), the data are reported. The associated samples are impacted: AL-7 (480-215658-2), AL-2 (480-215658-3), MW-09R (480-215658-4), MW-02R (480-215658-6), EX-MW-12 (480-215658-7), MW-04 (480-215658-8), MW-13 (480-215658-9), MW-07R (480-215658-10) and TRIP BLANK (480-215658-12).

Method 8260C: The following samples were diluted to bring the concentration of target analytes within the calibration range: MW-09R (480-215658-4), MW-02R (480-215658-6) and MW-07R (480-215658-10). Elevated reporting limits (RLs) are provided.

Method 8260C: The following volatiles samples were diluted due to foaming at the time of purging during the original sample analysis: EX-MW-12 (480-215658-7), MW-04 (480-215658-8) and MW-13 (480-215658-9). Elevated reporting limits (RLs) are provided.

Method 8260C: The following sample(s) was collected in a properly preserved vial; however, the pH was outside the required criteria when verified by the laboratory. The sample was analyzed within the 7-day holding time specified for unpreserved samples: AL-7 (480-215658-2).

Method 8260C: The continuing calibration verification (CCV) associated with batch 480-695377 recovered outside acceptance criteria, low biased, for Chloromethane. A reporting limit (RL) standard was analyzed, and the target analytes are detected. Since the associated samples were non-detect for the analyte(s), the data are reported. The associated samples are impacted: AL-1 (480-215658-1), EX-MW-11R (480-215658-5), MW-07R (480-215658-10) and DUP (480-215658-11).

Method 8260C: The following samples were diluted to bring the concentration of target analytes within the calibration range: AL-1 (480-215658-1), EX-MW-11R (480-215658-5), MW-07R (480-215658-10), DUP (480-215658-11), (480-215658-B-11 MS) and (480-215658-B-11 MSD). Elevated reporting limits (RLs) are provided.

No additional analytical or quality issues were noted, other than those described above or in the Definitions/ Glossary page.

Detection Summary

Client: LaBella Associates DPC
Job ID: 480-215658-1
Project/Site: Alumax & Roblin Periodic Review Reports

Client Sample ID: AL-1 — Lab Sample ID: 480-215658-1

Analyte	Result	Qualifier	RL	MDL	Unit	Dil Fac	D	Method	Prep Type
Benzene	27		2.0	0.82	ug/L	2		8260C	Total/NA
cis-1,2-Dichloroethene	140		2.0	1.6	ug/L	2		8260C	Total/NA
Cyclohexane	33		2.0	0.36	ug/L	2		8260C	Total/NA
Methylcyclohexane	18		2.0	0.32	ug/L	2		8260C	Total/NA
Vinyl chloride	130		2.0	1.8	ug/L	2		8260C	Total/NA
Xylenes, Total	7.6		4.0	1.3	ug/L	2		8260C	Total/NA

Client Sample ID: AL-7 — Lab Sample ID: 480-215658-2

Analyte	Result	Qualifier	RL	MDL	Unit	Dil Fac	D	Method	Prep Type
2-Butanone (MEK)	1.6	J	10	1.3	ug/L	1		8260C	Total/NA
Acetone	7.3	J	10	3.0	ug/L	1		8260C	Total/NA
cis-1,2-Dichloroethene	2.0		1.0	0.81	ug/L	1		8260C	Total/NA

Client Sample ID: AL-2 — Lab Sample ID: 480-215658-3

Analyte	Result	Qualifier	RL	MDL	Unit	Dil Fac	D	Method	Prep Type
Benzene	30		1.0	0.41	ug/L	1		8260C	Total/NA
Cyclohexane	11		1.0	0.18	ug/L	1		8260C	Total/NA
Methylcyclohexane	1.5		1.0	0.16	ug/L	1		8260C	Total/NA

Client Sample ID: MW-09R — Lab Sample ID: 480-215658-4

Analyte	Result	Qualifier	RL	MDL	Unit	Dil Fac	D	Method	Prep Type
cis-1,2-Dichloroethene	75		10	8.1	ug/L	10		8260C	Total/NA
Cyclohexane	37		10	1.8	ug/L	10		8260C	Total/NA
Methylcyclohexane	34		10	1.6	ug/L	10		8260C	Total/NA
Vinyl chloride	310		10	9.0	ug/L	10		8260C	Total/NA

Client Sample ID: EX-MW-11R — Lab Sample ID: 480-215658-5

Analyte	Result	Qualifier	RL	MDL	Unit	Dil Fac	D	Method	Prep Type
cis-1,2-Dichloroethene	1700		50	41	ug/L	50		8260C	Total/NA
Cyclohexane	13	J	50	9.0	ug/L	50		8260C	Total/NA
Methylcyclohexane	17	J	50	8.0	ug/L	50		8260C	Total/NA
Trichloroethene	44	J	50	23	ug/L	50		8260C	Total/NA
Vinyl chloride	1100		50	45	ug/L	50		8260C	Total/NA

Client Sample ID: MW-02R — Lab Sample ID: 480-215658-6

Analyte	Result	Qualifier	RL	MDL	Unit	Dil Fac	D	Method	Prep Type
Benzene	2.7	J	5.0	2.1	ug/L	5		8260C	Total/NA
cis-1,2-Dichloroethene	320		5.0	4.1	ug/L	5		8260C	Total/NA
Cyclohexane	7.7		5.0	0.90	ug/L	5		8260C	Total/NA
Methylcyclohexane	7.7		5.0	0.80	ug/L	5		8260C	Total/NA
Trichloroethene	3.6	J	5.0	2.3	ug/L	5		8260C	Total/NA
Vinyl chloride	280		5.0	4.5	ug/L	5		8260C	Total/NA

Client Sample ID: EX-MW-12 — Lab Sample ID: 480-215658-7

No Detections.

Client Sample ID: MW-04 — Lab Sample ID: 480-215658-8

No Detections.

This Detection Summary does not include radiochemical test results.

Eurofins Buffalo

Detection Summary

Client: LaBella Associates DPC
Job ID: 480-215658-1
Project/Site: Alumax & Roblin Periodic Review Reports

Client Sample ID: MW-13 — Lab Sample ID: 480-215658-9

Analyte	Result	Qualifier	RL	MDL	Unit	Dil Fac	D	Method	Prep Type
Benzene	2.1	J	4.0	1.6	ug/L	4		8260C	Total/NA
Cyclohexane	6.1		4.0	0.72	ug/L	4		8260C	Total/NA
Methylcyclohexane	6.8		4.0	0.64	ug/L	4		8260C	Total/NA
Toluene	3.0	J	4.0	2.0	ug/L	4		8260C	Total/NA
Xylenes, Total	5.0	J	8.0	2.6	ug/L	4		8260C	Total/NA

Client Sample ID: MW-07R — Lab Sample ID: 480-215658-10

Analyte	Result	Qualifier	RL	MDL	Unit	Dil Fac	D	Method	Prep Type
1,1-Dichloroethene	12		10	2.9	ug/L	10		8260C	Total/NA
cis-1,2-Dichloroethene	3200	E	10	8.1	ug/L	10		8260C	Total/NA
trans-1,2-Dichloroethene	9.6	J	10	9.0	ug/L	10		8260C	Total/NA
Trichloroethene	21		10	4.6	ug/L	10		8260C	Total/NA
Vinyl chloride	690	F1	10	9.0	ug/L	10		8260C	Total/NA
cis-1,2-Dichloroethene - DL	3400		80	65	ug/L	80		8260C	Total/NA
Vinyl chloride - DL	780		80	72	ug/L	80		8260C	Total/NA

Client Sample ID: DUP — Lab Sample ID: 480-215658-11

Analyte	Result	Qualifier	RL	MDL	Unit	Dil Fac	D	Method	Prep Type
cis-1,2-Dichloroethene	99		10	8.1	ug/L	10		8260C	Total/NA
Cyclohexane	39		10	1.8	ug/L	10		8260C	Total/NA
Methylcyclohexane	37		10	1.6	ug/L	10		8260C	Total/NA
Vinyl chloride	360	F1	10	9.0	ug/L	10		8260C	Total/NA

Client Sample ID: TRIP BLANK — Lab Sample ID: 480-215658-12

No Detections.

This Detection Summary does not include radiochemical test results.

Client: LaBella Associates DPC
Job ID: 480-215658-1
Project/Site: Alumax & Roblin Periodic Review Reports

Client Sample ID: AL-1
Lab Sample ID: 480-215658-1
Date Collected: 12/12/23 08:30
Matrix: Water
Date Received: 12/13/23 09:00

Method: SW846 8260C - Volatile Organic Compounds by GC/MS

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
1,1,1-Trichloroethane	ND		2.0	1.6	ug/L			12/14/23 11:48	2
1,1,2,2-Tetrachloroethane	ND		2.0	0.42	ug/L			12/14/23 11:48	2
1,1,2-Trichloroethane	ND		2.0	0.46	ug/L			12/14/23 11:48	2
1,1,2-Trichloro-1,2,2-trifluoroethane	ND		2.0	0.62	ug/L			12/14/23 11:48	2
1,1-Dichloroethane	ND		2.0	0.76	ug/L			12/14/23 11:48	2
1,1-Dichloroethene	ND		2.0	0.58	ug/L			12/14/23 11:48	2
1,2,4-Trichlorobenzene	ND		2.0	0.82	ug/L			12/14/23 11:48	2
1,2-Dibromo-3-Chloropropane	ND		2.0	0.78	ug/L			12/14/23 11:48	2
1,2-Dichlorobenzene	ND		2.0	1.6	ug/L			12/14/23 11:48	2
1,2-Dichloroethane	ND		2.0	0.42	ug/L			12/14/23 11:48	2
1,2-Dichloropropane	ND		2.0	1.4	ug/L			12/14/23 11:48	2
1,3-Dichlorobenzene	ND		2.0	1.6	ug/L			12/14/23 11:48	2
1,4-Dichlorobenzene	ND		2.0	1.7	ug/L			12/14/23 11:48	2
2-Butanone (MEK)	ND		20	2.6	ug/L			12/14/23 11:48	2
2-Hexanone	ND		10	2.5	ug/L			12/14/23 11:48	2
4-Methyl-2-pentanone (MIBK)	ND		10	4.2	ug/L			12/14/23 11:48	2
Acetone	ND		20	6.0	ug/L			12/14/23 11:48	2
Benzene	**27**		2.0	0.82	ug/L			12/14/23 11:48	2
Bromodichloromethane	ND		2.0	0.78	ug/L			12/14/23 11:48	2
Bromoform	ND		2.0	0.52	ug/L			12/14/23 11:48	2
Bromomethane	ND		2.0	1.4	ug/L			12/14/23 11:48	2
Carbon disulfide	ND		2.0	0.38	ug/L			12/14/23 11:48	2
Carbon tetrachloride	ND		2.0	0.54	ug/L			12/14/23 11:48	2
Chlorobenzene	ND		2.0	1.5	ug/L			12/14/23 11:48	2
Dibromochloromethane	ND		2.0	0.64	ug/L			12/14/23 11:48	2
Chloroethane	ND		2.0	0.64	ug/L			12/14/23 11:48	2
Chloroform	ND		2.0	0.68	ug/L			12/14/23 11:48	2
Chloromethane	ND		2.0	0.70	ug/L			12/14/23 11:48	2
cis-1,2-Dichloroethene	**140**		2.0	1.6	ug/L			12/14/23 11:48	2
cis-1,3-Dichloropropene	ND		2.0	0.72	ug/L			12/14/23 11:48	2
Cyclohexane	**33**		2.0	0.36	ug/L			12/14/23 11:48	2
Dichlorodifluoromethane	ND		2.0	1.4	ug/L			12/14/23 11:48	2
Ethylbenzene	ND		2.0	1.5	ug/L			12/14/23 11:48	2
1,2-Dibromoethane	ND		2.0	1.5	ug/L			12/14/23 11:48	2
Isopropylbenzene	ND		2.0	1.6	ug/L			12/14/23 11:48	2
Methyl acetate	ND		5.0	2.6	ug/L			12/14/23 11:48	2
Methyl tert-butyl ether	ND		2.0	0.32	ug/L			12/14/23 11:48	2
Methylcyclohexane	**18**		2.0	0.32	ug/L			12/14/23 11:48	2
Methylene Chloride	ND		2.0	0.88	ug/L			12/14/23 11:48	2
Styrene	ND		2.0	1.5	ug/L			12/14/23 11:48	2
Tetrachloroethene	ND		2.0	0.72	ug/L			12/14/23 11:48	2
Toluene	ND		2.0	1.0	ug/L			12/14/23 11:48	2
trans-1,2-Dichloroethene	ND		2.0	1.8	ug/L			12/14/23 11:48	2
trans-1,3-Dichloropropene	ND		2.0	0.74	ug/L			12/14/23 11:48	2
Trichloroethene	ND		2.0	0.92	ug/L			12/14/23 11:48	2
Trichlorofluoromethane	ND		2.0	1.8	ug/L			12/14/23 11:48	2
Vinyl chloride	**130**		2.0	1.8	ug/L			12/14/23 11:48	2
Xylenes, Total	**7.6**		4.0	1.3	ug/L			12/14/23 11:48	2

Client: LaBella Associates DPC
Job ID: 480-215658-1
Project/Site: Alumax & Roblin Periodic Review Reports

Client Sample ID: AL-1
Lab Sample ID: 480-215658-1
Date Collected: 12/12/23 08:30
Matrix: Water
Date Received: 12/13/23 09:00

Surrogate	%Recovery	Qualifier	Limits	Prepared	Analyzed	Dil Fac
Toluene-d8 (Surr)	97		80 - 120		12/14/23 11:48	2
1,2-Dichloroethane-d4 (Surr)	83		77 - 120		12/14/23 11:48	2
4-Bromofluorobenzene (Surr)	97		73 - 120		12/14/23 11:48	2
Dibromofluoromethane (Surr)	88		75 - 123		12/14/23 11:48	2

Client: LaBella Associates DPC
Job ID: 480-215658-1
Project/Site: Alumax & Roblin Periodic Review Reports

Client Sample ID: AL-7
Lab Sample ID: 480-215658-2
Date Collected: 12/12/23 08:55
Matrix: Water
Date Received: 12/13/23 09:00

Method: SW846 8260C - Volatile Organic Compounds by GC/MS

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
1,1,1-Trichloroethane	ND		1.0	0.82	ug/L			12/13/23 13:57	1
1,1,2,2-Tetrachloroethane	ND		1.0	0.21	ug/L			12/13/23 13:57	1
1,1,2-Trichloroethane	ND		1.0	0.23	ug/L			12/13/23 13:57	1
1,1,2-Trichloro-1,2,2-trifluoroethane	ND		1.0	0.31	ug/L			12/13/23 13:57	1
1,1-Dichloroethane	ND		1.0	0.38	ug/L			12/13/23 13:57	1
1,1-Dichloroethene	ND		1.0	0.29	ug/L			12/13/23 13:57	1
1,2,4-Trichlorobenzene	ND		1.0	0.41	ug/L			12/13/23 13:57	1
1,2-Dibromo-3-Chloropropane	ND		1.0	0.39	ug/L			12/13/23 13:57	1
1,2-Dichlorobenzene	ND		1.0	0.79	ug/L			12/13/23 13:57	1
1,2-Dichloroethane	ND		1.0	0.21	ug/L			12/13/23 13:57	1
1,2-Dichloropropane	ND		1.0	0.72	ug/L			12/13/23 13:57	1
1,3-Dichlorobenzene	ND		1.0	0.78	ug/L			12/13/23 13:57	1
1,4-Dichlorobenzene	ND		1.0	0.84	ug/L			12/13/23 13:57	1
2-Butanone (MEK)	**1.6**	**J**	10	1.3	ug/L			12/13/23 13:57	1
2-Hexanone	ND		5.0	1.2	ug/L			12/13/23 13:57	1
4-Methyl-2-pentanone (MIBK)	ND		5.0	2.1	ug/L			12/13/23 13:57	1
Acetone	**7.3**	**J**	10	3.0	ug/L			12/13/23 13:57	1
Benzene	ND		1.0	0.41	ug/L			12/13/23 13:57	1
Bromodichloromethane	ND		1.0	0.39	ug/L			12/13/23 13:57	1
Bromoform	ND		1.0	0.26	ug/L			12/13/23 13:57	1
Bromomethane	ND		1.0	0.69	ug/L			12/13/23 13:57	1
Carbon disulfide	ND		1.0	0.19	ug/L			12/13/23 13:57	1
Carbon tetrachloride	ND		1.0	0.27	ug/L			12/13/23 13:57	1
Chlorobenzene	ND		1.0	0.75	ug/L			12/13/23 13:57	1
Dibromochloromethane	ND		1.0	0.32	ug/L			12/13/23 13:57	1
Chloroethane	ND		1.0	0.32	ug/L			12/13/23 13:57	1
Chloroform	ND		1.0	0.34	ug/L			12/13/23 13:57	1
Chloromethane	ND		1.0	0.35	ug/L			12/13/23 13:57	1
cis-1,2-Dichloroethene	**2.0**		1.0	0.81	ug/L			12/13/23 13:57	1
cis-1,3-Dichloropropene	ND		1.0	0.36	ug/L			12/13/23 13:57	1
Cyclohexane	ND		1.0	0.18	ug/L			12/13/23 13:57	1
Dichlorodifluoromethane	ND		1.0	0.68	ug/L			12/13/23 13:57	1
Ethylbenzene	ND		1.0	0.74	ug/L			12/13/23 13:57	1
1,2-Dibromoethane	ND		1.0	0.73	ug/L			12/13/23 13:57	1
Isopropylbenzene	ND		1.0	0.79	ug/L			12/13/23 13:57	1
Methyl acetate	ND		2.5	1.3	ug/L			12/13/23 13:57	1
Methyl tert-butyl ether	ND		1.0	0.16	ug/L			12/13/23 13:57	1
Methylcyclohexane	ND		1.0	0.16	ug/L			12/13/23 13:57	1
Methylene Chloride	ND		1.0	0.44	ug/L			12/13/23 13:57	1
Styrene	ND		1.0	0.73	ug/L			12/13/23 13:57	1
Tetrachloroethene	ND		1.0	0.36	ug/L			12/13/23 13:57	1
Toluene	ND		1.0	0.51	ug/L			12/13/23 13:57	1
trans-1,2-Dichloroethene	ND		1.0	0.90	ug/L			12/13/23 13:57	1
trans-1,3-Dichloropropene	ND		1.0	0.37	ug/L			12/13/23 13:57	1
Trichloroethene	ND		1.0	0.46	ug/L			12/13/23 13:57	1
Trichlorofluoromethane	ND		1.0	0.88	ug/L			12/13/23 13:57	1
Vinyl chloride	ND		1.0	0.90	ug/L			12/13/23 13:57	1
Xylenes, Total	ND		2.0	0.66	ug/L			12/13/23 13:57	1

Client: LaBella Associates DPC
Job ID: 480-215658-1
Project/Site: Alumax & Roblin Periodic Review Reports

Client Sample ID: AL-7
Lab Sample ID: 480-215658-2
Date Collected: 12/12/23 08:55
Matrix: Water
Date Received: 12/13/23 09:00

Surrogate	%Recovery	Qualifier	Limits	Prepared	Analyzed	Dil Fac
Toluene-d8 (Surr)	97		80 - 120		12/13/23 13:57	1
1,2-Dichloroethane-d4 (Surr)	90		77 - 120		12/13/23 13:57	1
4-Bromofluorobenzene (Surr)	99		73 - 120		12/13/23 13:57	1
Dibromofluoromethane (Surr)	87		75 - 123		12/13/23 13:57	1

Client: LaBella Associates DPC
Job ID: 480-215658-1
Project/Site: Alumax & Roblin Periodic Review Reports

Client Sample ID: AL-2
Lab Sample ID: 480-215658-3
Date Collected: 12/12/23 09:35
Matrix: Water
Date Received: 12/13/23 09:00

Method: SW846 8260C - Volatile Organic Compounds by GC/MS

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
1,1,1-Trichloroethane	ND		1.0	0.82	ug/L			12/13/23 14:19	1
1,1,2,2-Tetrachloroethane	ND		1.0	0.21	ug/L			12/13/23 14:19	1
1,1,2-Trichloroethane	ND		1.0	0.23	ug/L			12/13/23 14:19	1
1,1,2-Trichloro-1,2,2-trifluoroethane	ND		1.0	0.31	ug/L			12/13/23 14:19	1
1,1-Dichloroethane	ND		1.0	0.38	ug/L			12/13/23 14:19	1
1,1-Dichloroethene	ND		1.0	0.29	ug/L			12/13/23 14:19	1
1,2,4-Trichlorobenzene	ND		1.0	0.41	ug/L			12/13/23 14:19	1
1,2-Dibromo-3-Chloropropane	ND		1.0	0.39	ug/L			12/13/23 14:19	1
1,2-Dichlorobenzene	ND		1.0	0.79	ug/L			12/13/23 14:19	1
1,2-Dichloroethane	ND		1.0	0.21	ug/L			12/13/23 14:19	1
1,2-Dichloropropane	ND		1.0	0.72	ug/L			12/13/23 14:19	1
1,3-Dichlorobenzene	ND		1.0	0.78	ug/L			12/13/23 14:19	1
1,4-Dichlorobenzene	ND		1.0	0.84	ug/L			12/13/23 14:19	1
2-Butanone (MEK)	ND		10	1.3	ug/L			12/13/23 14:19	1
2-Hexanone	ND		5.0	1.2	ug/L			12/13/23 14:19	1
4-Methyl-2-pentanone (MIBK)	ND		5.0	2.1	ug/L			12/13/23 14:19	1
Acetone	ND		10	3.0	ug/L			12/13/23 14:19	1
Benzene	**30**		1.0	0.41	ug/L			12/13/23 14:19	1
Bromodichloromethane	ND		1.0	0.39	ug/L			12/13/23 14:19	1
Bromoform	ND		1.0	0.26	ug/L			12/13/23 14:19	1
Bromomethane	ND		1.0	0.69	ug/L			12/13/23 14:19	1
Carbon disulfide	ND		1.0	0.19	ug/L			12/13/23 14:19	1
Carbon tetrachloride	ND		1.0	0.27	ug/L			12/13/23 14:19	1
Chlorobenzene	ND		1.0	0.75	ug/L			12/13/23 14:19	1
Dibromochloromethane	ND		1.0	0.32	ug/L			12/13/23 14:19	1
Chloroethane	ND		1.0	0.32	ug/L			12/13/23 14:19	1
Chloroform	ND		1.0	0.34	ug/L			12/13/23 14:19	1
Chloromethane	ND		1.0	0.35	ug/L			12/13/23 14:19	1
cis-1,2-Dichloroethene	ND		1.0	0.81	ug/L			12/13/23 14:19	1
cis-1,3-Dichloropropene	ND		1.0	0.36	ug/L			12/13/23 14:19	1
Cyclohexane	**11**		1.0	0.18	ug/L			12/13/23 14:19	1
Dichlorodifluoromethane	ND		1.0	0.68	ug/L			12/13/23 14:19	1
Ethylbenzene	ND		1.0	0.74	ug/L			12/13/23 14:19	1
1,2-Dibromoethane	ND		1.0	0.73	ug/L			12/13/23 14:19	1
Isopropylbenzene	ND		1.0	0.79	ug/L			12/13/23 14:19	1
Methyl acetate	ND		2.5	1.3	ug/L			12/13/23 14:19	1
Methyl tert-butyl ether	ND		1.0	0.16	ug/L			12/13/23 14:19	1
Methylcyclohexane	**1.5**		1.0	0.16	ug/L			12/13/23 14:19	1
Methylene Chloride	ND		1.0	0.44	ug/L			12/13/23 14:19	1
Styrene	ND		1.0	0.73	ug/L			12/13/23 14:19	1
Tetrachloroethene	ND		1.0	0.36	ug/L			12/13/23 14:19	1
Toluene	ND		1.0	0.51	ug/L			12/13/23 14:19	1
trans-1,2-Dichloroethene	ND		1.0	0.90	ug/L			12/13/23 14:19	1
trans-1,3-Dichloropropene	ND		1.0	0.37	ug/L			12/13/23 14:19	1
Trichloroethene	ND		1.0	0.46	ug/L			12/13/23 14:19	1
Trichlorofluoromethane	ND		1.0	0.88	ug/L			12/13/23 14:19	1
Vinyl chloride	ND		1.0	0.90	ug/L			12/13/23 14:19	1
Xylenes, Total	ND		2.0	0.66	ug/L			12/13/23 14:19	1

Client: LaBella Associates DPC
Job ID: 480-215658-1
Project/Site: Alumax & Roblin Periodic Review Reports

Client Sample ID: AL-2
Lab Sample ID: 480-215658-3
Date Collected: 12/12/23 09:35
Matrix: Water
Date Received: 12/13/23 09:00

Surrogate	%Recovery	Qualifier	Limits	Prepared	Analyzed	Dil Fac
Toluene-d8 (Surr)	99		80 - 120		12/13/23 14:19	1
1,2-Dichloroethane-d4 (Surr)	88		77 - 120		12/13/23 14:19	1
4-Bromofluorobenzene (Surr)	99		73 - 120		12/13/23 14:19	1
Dibromofluoromethane (Surr)	88		75 - 123		12/13/23 14:19	1

Client: LaBella Associates DPC
Job ID: 480-215658-1
Project/Site: Alumax & Roblin Periodic Review Reports

Client Sample ID: MW-09R
Lab Sample ID: 480-215658-4
Date Collected: 12/12/23 10:15
Matrix: Water
Date Received: 12/13/23 09:00

Method: SW846 8260C - Volatile Organic Compounds by GC/MS

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
1,1,1-Trichloroethane	ND		10	8.2	ug/L			12/13/23 14:41	10
1,1,2,2-Tetrachloroethane	ND		10	2.1	ug/L			12/13/23 14:41	10
1,1,2-Trichloroethane	ND		10	2.3	ug/L			12/13/23 14:41	10
1,1,2-Trichloro-1,2,2-trifluoroethane	ND		10	3.1	ug/L			12/13/23 14:41	10
1,1-Dichloroethane	ND		10	3.8	ug/L			12/13/23 14:41	10
1,1-Dichloroethene	ND		10	2.9	ug/L			12/13/23 14:41	10
1,2,4-Trichlorobenzene	ND		10	4.1	ug/L			12/13/23 14:41	10
1,2-Dibromo-3-Chloropropane	ND		10	3.9	ug/L			12/13/23 14:41	10
1,2-Dichlorobenzene	ND		10	7.9	ug/L			12/13/23 14:41	10
1,2-Dichloroethane	ND		10	2.1	ug/L			12/13/23 14:41	10
1,2-Dichloropropane	ND		10	7.2	ug/L			12/13/23 14:41	10
1,3-Dichlorobenzene	ND		10	7.8	ug/L			12/13/23 14:41	10
1,4-Dichlorobenzene	ND		10	8.4	ug/L			12/13/23 14:41	10
2-Butanone (MEK)	ND		100	13	ug/L			12/13/23 14:41	10
2-Hexanone	ND		50	12	ug/L			12/13/23 14:41	10
4-Methyl-2-pentanone (MIBK)	ND		50	21	ug/L			12/13/23 14:41	10
Acetone	ND		100	30	ug/L			12/13/23 14:41	10
Benzene	ND		10	4.1	ug/L			12/13/23 14:41	10
Bromodichloromethane	ND		10	3.9	ug/L			12/13/23 14:41	10
Bromoform	ND		10	2.6	ug/L			12/13/23 14:41	10
Bromomethane	ND		10	6.9	ug/L			12/13/23 14:41	10
Carbon disulfide	ND		10	1.9	ug/L			12/13/23 14:41	10
Carbon tetrachloride	ND		10	2.7	ug/L			12/13/23 14:41	10
Chlorobenzene	ND		10	7.5	ug/L			12/13/23 14:41	10
Dibromochloromethane	ND		10	3.2	ug/L			12/13/23 14:41	10
Chloroethane	ND		10	3.2	ug/L			12/13/23 14:41	10
Chloroform	ND		10	3.4	ug/L			12/13/23 14:41	10
Chloromethane	ND		10	3.5	ug/L			12/13/23 14:41	10
cis-1,2-Dichloroethene	**75**		10	8.1	ug/L			12/13/23 14:41	10
cis-1,3-Dichloropropene	ND		10	3.6	ug/L			12/13/23 14:41	10
Cyclohexane	**37**		10	1.8	ug/L			12/13/23 14:41	10
Dichlorodifluoromethane	ND		10	6.8	ug/L			12/13/23 14:41	10
Ethylbenzene	ND		10	7.4	ug/L			12/13/23 14:41	10
1,2-Dibromoethane	ND		10	7.3	ug/L			12/13/23 14:41	10
Isopropylbenzene	ND		10	7.9	ug/L			12/13/23 14:41	10
Methyl acetate	ND		25	13	ug/L			12/13/23 14:41	10
Methyl tert-butyl ether	ND		10	1.6	ug/L			12/13/23 14:41	10
Methylcyclohexane	**34**		10	1.6	ug/L			12/13/23 14:41	10
Methylene Chloride	ND		10	4.4	ug/L			12/13/23 14:41	10
Styrene	ND		10	7.3	ug/L			12/13/23 14:41	10
Tetrachloroethene	ND		10	3.6	ug/L			12/13/23 14:41	10
Toluene	ND		10	5.1	ug/L			12/13/23 14:41	10
trans-1,2-Dichloroethene	ND		10	9.0	ug/L			12/13/23 14:41	10
trans-1,3-Dichloropropene	ND		10	3.7	ug/L			12/13/23 14:41	10
Trichloroethene	ND		10	4.6	ug/L			12/13/23 14:41	10
Trichlorofluoromethane	ND		10	8.8	ug/L			12/13/23 14:41	10
Vinyl chloride	**310**		10	9.0	ug/L			12/13/23 14:41	10
Xylenes, Total	ND		20	6.6	ug/L			12/13/23 14:41	10

Client: LaBella Associates DPC
Job ID: 480-215658-1
Project/Site: Alumax & Roblin Periodic Review Reports

Client Sample ID: MW-09R
Lab Sample ID: 480-215658-4
Date Collected: 12/12/23 10:15
Matrix: Water
Date Received: 12/13/23 09:00

Surrogate	%Recovery	Qualifier	Limits	Prepared	Analyzed	Dil Fac
Toluene-d8 (Surr)	97		80 - 120		12/13/23 14:41	10
1,2-Dichloroethane-d4 (Surr)	92		77 - 120		12/13/23 14:41	10
4-Bromofluorobenzene (Surr)	98		73 - 120		12/13/23 14:41	10
Dibromofluoromethane (Surr)	92		75 - 123		12/13/23 14:41	10

Client: LaBella Associates DPC
Job ID: 480-215658-1
Project/Site: Alumax & Roblin Periodic Review Reports

Client Sample ID: EX-MW-11R
Lab Sample ID: 480-215658-5
Date Collected: 12/12/23 10:45
Matrix: Water
Date Received: 12/13/23 09:00

Method: SW846 8260C - Volatile Organic Compounds by GC/MS

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
1,1,1-Trichloroethane	ND		50	41	ug/L			12/14/23 12:11	50
1,1,2,2-Tetrachloroethane	ND		50	11	ug/L			12/14/23 12:11	50
1,1,2-Trichloroethane	ND		50	12	ug/L			12/14/23 12:11	50
1,1,2-Trichloro-1,2,2-trifluoroethane	ND		50	16	ug/L			12/14/23 12:11	50
1,1-Dichloroethane	ND		50	19	ug/L			12/14/23 12:11	50
1,1-Dichloroethene	ND		50	15	ug/L			12/14/23 12:11	50
1,2,4-Trichlorobenzene	ND		50	21	ug/L			12/14/23 12:11	50
1,2-Dibromo-3-Chloropropane	ND		50	20	ug/L			12/14/23 12:11	50
1,2-Dichlorobenzene	ND		50	40	ug/L			12/14/23 12:11	50
1,2-Dichloroethane	ND		50	11	ug/L			12/14/23 12:11	50
1,2-Dichloropropane	ND		50	36	ug/L			12/14/23 12:11	50
1,3-Dichlorobenzene	ND		50	39	ug/L			12/14/23 12:11	50
1,4-Dichlorobenzene	ND		50	42	ug/L			12/14/23 12:11	50
2-Butanone (MEK)	ND		500	66	ug/L			12/14/23 12:11	50
2-Hexanone	ND		250	62	ug/L			12/14/23 12:11	50
4-Methyl-2-pentanone (MIBK)	ND		250	110	ug/L			12/14/23 12:11	50
Acetone	ND		500	150	ug/L			12/14/23 12:11	50
Benzene	ND		50	21	ug/L			12/14/23 12:11	50
Bromodichloromethane	ND		50	20	ug/L			12/14/23 12:11	50
Bromoform	ND		50	13	ug/L			12/14/23 12:11	50
Bromomethane	ND		50	35	ug/L			12/14/23 12:11	50
Carbon disulfide	ND		50	9.5	ug/L			12/14/23 12:11	50
Carbon tetrachloride	ND		50	14	ug/L			12/14/23 12:11	50
Chlorobenzene	ND		50	38	ug/L			12/14/23 12:11	50
Dibromochloromethane	ND		50	16	ug/L			12/14/23 12:11	50
Chloroethane	ND		50	16	ug/L			12/14/23 12:11	50
Chloroform	ND		50	17	ug/L			12/14/23 12:11	50
Chloromethane	ND		50	18	ug/L			12/14/23 12:11	50
cis-1,2-Dichloroethene	**1700**		50	41	ug/L			12/14/23 12:11	50
cis-1,3-Dichloropropene	ND		50	18	ug/L			12/14/23 12:11	50
Cyclohexane	**13**	**J**	50	9.0	ug/L			12/14/23 12:11	50
Dichlorodifluoromethane	ND		50	34	ug/L			12/14/23 12:11	50
Ethylbenzene	ND		50	37	ug/L			12/14/23 12:11	50
1,2-Dibromoethane	ND		50	37	ug/L			12/14/23 12:11	50
Isopropylbenzene	ND		50	40	ug/L			12/14/23 12:11	50
Methyl acetate	ND		130	65	ug/L			12/14/23 12:11	50
Methyl tert-butyl ether	ND		50	8.0	ug/L			12/14/23 12:11	50
Methylcyclohexane	**17**	**J**	50	8.0	ug/L			12/14/23 12:11	50
Methylene Chloride	ND		50	22	ug/L			12/14/23 12:11	50
Styrene	ND		50	37	ug/L			12/14/23 12:11	50
Tetrachloroethene	ND		50	18	ug/L			12/14/23 12:11	50
Toluene	ND		50	26	ug/L			12/14/23 12:11	50
trans-1,2-Dichloroethene	ND		50	45	ug/L			12/14/23 12:11	50
trans-1,3-Dichloropropene	ND		50	19	ug/L			12/14/23 12:11	50
Trichloroethene	**44**	**J**	50	23	ug/L			12/14/23 12:11	50
Trichlorofluoromethane	ND		50	44	ug/L			12/14/23 12:11	50
Vinyl chloride	**1100**		50	45	ug/L			12/14/23 12:11	50
Xylenes, Total	ND		100	33	ug/L			12/14/23 12:11	50

Client: LaBella Associates DPC
Job ID: 480-215658-1
Project/Site: Alumax & Roblin Periodic Review Reports

Client Sample ID: EX-MW-11R
Lab Sample ID: 480-215658-5
Date Collected: 12/12/23 10:45
Matrix: Water
Date Received: 12/13/23 09:00

Surrogate	%Recovery	Qualifier	Limits	Prepared	Analyzed	Dil Fac
Toluene-d8 (Surr)	99		80 - 120		12/14/23 12:11	50
1,2-Dichloroethane-d4 (Surr)	88		77 - 120		12/14/23 12:11	50
4-Bromofluorobenzene (Surr)	98		73 - 120		12/14/23 12:11	50
Dibromofluoromethane (Surr)	86		75 - 123		12/14/23 12:11	50

Client: LaBella Associates DPC
Job ID: 480-215658-1
Project/Site: Alumax & Roblin Periodic Review Reports

Client Sample ID: MW-02R
Lab Sample ID: 480-215658-6
Date Collected: 12/12/23 11:25
Matrix: Water
Date Received: 12/13/23 09:00

Method: SW846 8260C - Volatile Organic Compounds by GC/MS

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
1,1,1-Trichloroethane	ND		5.0	4.1	ug/L			12/13/23 15:25	5
1,1,2,2-Tetrachloroethane	ND		5.0	1.1	ug/L			12/13/23 15:25	5
1,1,2-Trichloroethane	ND		5.0	1.2	ug/L			12/13/23 15:25	5
1,1,2-Trichloro-1,2,2-trifluoroethane	ND		5.0	1.6	ug/L			12/13/23 15:25	5
1,1-Dichloroethane	ND		5.0	1.9	ug/L			12/13/23 15:25	5
1,1-Dichloroethene	ND		5.0	1.5	ug/L			12/13/23 15:25	5
1,2,4-Trichlorobenzene	ND		5.0	2.1	ug/L			12/13/23 15:25	5
1,2-Dibromo-3-Chloropropane	ND		5.0	2.0	ug/L			12/13/23 15:25	5
1,2-Dichlorobenzene	ND		5.0	4.0	ug/L			12/13/23 15:25	5
1,2-Dichloroethane	ND		5.0	1.1	ug/L			12/13/23 15:25	5
1,2-Dichloropropane	ND		5.0	3.6	ug/L			12/13/23 15:25	5
1,3-Dichlorobenzene	ND		5.0	3.9	ug/L			12/13/23 15:25	5
1,4-Dichlorobenzene	ND		5.0	4.2	ug/L			12/13/23 15:25	5
2-Butanone (MEK)	ND		50	6.6	ug/L			12/13/23 15:25	5
2-Hexanone	ND		25	6.2	ug/L			12/13/23 15:25	5
4-Methyl-2-pentanone (MIBK)	ND		25	11	ug/L			12/13/23 15:25	5
Acetone	ND		50	15	ug/L			12/13/23 15:25	5
Benzene	**2.7**	**J**	5.0	2.1	ug/L			12/13/23 15:25	5
Bromodichloromethane	ND		5.0	2.0	ug/L			12/13/23 15:25	5
Bromoform	ND		5.0	1.3	ug/L			12/13/23 15:25	5
Bromomethane	ND		5.0	3.5	ug/L			12/13/23 15:25	5
Carbon disulfide	ND		5.0	0.95	ug/L			12/13/23 15:25	5
Carbon tetrachloride	ND		5.0	1.4	ug/L			12/13/23 15:25	5
Chlorobenzene	ND		5.0	3.8	ug/L			12/13/23 15:25	5
Dibromochloromethane	ND		5.0	1.6	ug/L			12/13/23 15:25	5
Chloroethane	ND		5.0	1.6	ug/L			12/13/23 15:25	5
Chloroform	ND		5.0	1.7	ug/L			12/13/23 15:25	5
Chloromethane	ND		5.0	1.8	ug/L			12/13/23 15:25	5
cis-1,2-Dichloroethene	**320**		5.0	4.1	ug/L			12/13/23 15:25	5
cis-1,3-Dichloropropene	ND		5.0	1.8	ug/L			12/13/23 15:25	5
Cyclohexane	**7.7**		5.0	0.90	ug/L			12/13/23 15:25	5
Dichlorodifluoromethane	ND		5.0	3.4	ug/L			12/13/23 15:25	5
Ethylbenzene	ND		5.0	3.7	ug/L			12/13/23 15:25	5
1,2-Dibromoethane	ND		5.0	3.7	ug/L			12/13/23 15:25	5
Isopropylbenzene	ND		5.0	4.0	ug/L			12/13/23 15:25	5
Methyl acetate	ND		13	6.5	ug/L			12/13/23 15:25	5
Methyl tert-butyl ether	ND		5.0	0.80	ug/L			12/13/23 15:25	5
Methylcyclohexane	**7.7**		5.0	0.80	ug/L			12/13/23 15:25	5
Methylene Chloride	ND		5.0	2.2	ug/L			12/13/23 15:25	5
Styrene	ND		5.0	3.7	ug/L			12/13/23 15:25	5
Tetrachloroethene	ND		5.0	1.8	ug/L			12/13/23 15:25	5
Toluene	ND		5.0	2.6	ug/L			12/13/23 15:25	5
trans-1,2-Dichloroethene	ND		5.0	4.5	ug/L			12/13/23 15:25	5
trans-1,3-Dichloropropene	ND		5.0	1.9	ug/L			12/13/23 15:25	5
Trichloroethene	**3.6**	**J**	5.0	2.3	ug/L			12/13/23 15:25	5
Trichlorofluoromethane	ND		5.0	4.4	ug/L			12/13/23 15:25	5
Vinyl chloride	**280**		5.0	4.5	ug/L			12/13/23 15:25	5
Xylenes, Total	ND		10	3.3	ug/L			12/13/23 15:25	5

Client: LaBella Associates DPC
Job ID: 480-215658-1
Project/Site: Alumax & Roblin Periodic Review Reports

Client Sample ID: MW-02R
Lab Sample ID: 480-215658-6
Date Collected: 12/12/23 11:25
Matrix: Water
Date Received: 12/13/23 09:00

Surrogate	%Recovery	Qualifier	Limits	Prepared	Analyzed	Dil Fac
Toluene-d8 (Surr)	97		80 - 120		12/13/23 15:25	5
1,2-Dichloroethane-d4 (Surr)	90		77 - 120		12/13/23 15:25	5
4-Bromofluorobenzene (Surr)	99		73 - 120		12/13/23 15:25	5
Dibromofluoromethane (Surr)	91		75 - 123		12/13/23 15:25	5

Client: LaBella Associates DPC
Job ID: 480-215658-1
Project/Site: Alumax & Roblin Periodic Review Reports

Client Sample ID: EX-MW-12
Lab Sample ID: 480-215658-7
Date Collected: 12/12/23 12:10
Matrix: Water
Date Received: 12/13/23 09:00

Method: SW846 8260C - Volatile Organic Compounds by GC/MS

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
1,1,1-Trichloroethane	ND		4.0	3.3	ug/L			12/13/23 15:48	4
1,1,2,2-Tetrachloroethane	ND		4.0	0.84	ug/L			12/13/23 15:48	4
1,1,2-Trichloroethane	ND		4.0	0.92	ug/L			12/13/23 15:48	4
1,1,2-Trichloro-1,2,2-trifluoroethane	ND		4.0	1.2	ug/L			12/13/23 15:48	4
1,1-Dichloroethane	ND		4.0	1.5	ug/L			12/13/23 15:48	4
1,1-Dichloroethene	ND		4.0	1.2	ug/L			12/13/23 15:48	4
1,2,4-Trichlorobenzene	ND		4.0	1.6	ug/L			12/13/23 15:48	4
1,2-Dibromo-3-Chloropropane	ND		4.0	1.6	ug/L			12/13/23 15:48	4
1,2-Dichlorobenzene	ND		4.0	3.2	ug/L			12/13/23 15:48	4
1,2-Dichloroethane	ND		4.0	0.84	ug/L			12/13/23 15:48	4
1,2-Dichloropropane	ND		4.0	2.9	ug/L			12/13/23 15:48	4
1,3-Dichlorobenzene	ND		4.0	3.1	ug/L			12/13/23 15:48	4
1,4-Dichlorobenzene	ND		4.0	3.4	ug/L			12/13/23 15:48	4
2-Butanone (MEK)	ND		40	5.3	ug/L			12/13/23 15:48	4
2-Hexanone	ND		20	5.0	ug/L			12/13/23 15:48	4
4-Methyl-2-pentanone (MIBK)	ND		20	8.4	ug/L			12/13/23 15:48	4
Acetone	ND		40	12	ug/L			12/13/23 15:48	4
Benzene	ND		4.0	1.6	ug/L			12/13/23 15:48	4
Bromodichloromethane	ND		4.0	1.6	ug/L			12/13/23 15:48	4
Bromoform	ND		4.0	1.0	ug/L			12/13/23 15:48	4
Bromomethane	ND		4.0	2.8	ug/L			12/13/23 15:48	4
Carbon disulfide	ND		4.0	0.76	ug/L			12/13/23 15:48	4
Carbon tetrachloride	ND		4.0	1.1	ug/L			12/13/23 15:48	4
Chlorobenzene	ND		4.0	3.0	ug/L			12/13/23 15:48	4
Dibromochloromethane	ND		4.0	1.3	ug/L			12/13/23 15:48	4
Chloroethane	ND		4.0	1.3	ug/L			12/13/23 15:48	4
Chloroform	ND		4.0	1.4	ug/L			12/13/23 15:48	4
Chloromethane	ND		4.0	1.4	ug/L			12/13/23 15:48	4
cis-1,2-Dichloroethene	ND		4.0	3.2	ug/L			12/13/23 15:48	4
cis-1,3-Dichloropropene	ND		4.0	1.4	ug/L			12/13/23 15:48	4
Cyclohexane	ND		4.0	0.72	ug/L			12/13/23 15:48	4
Dichlorodifluoromethane	ND		4.0	2.7	ug/L			12/13/23 15:48	4
Ethylbenzene	ND		4.0	3.0	ug/L			12/13/23 15:48	4
1,2-Dibromoethane	ND		4.0	2.9	ug/L			12/13/23 15:48	4
Isopropylbenzene	ND		4.0	3.2	ug/L			12/13/23 15:48	4
Methyl acetate	ND		10	5.2	ug/L			12/13/23 15:48	4
Methyl tert-butyl ether	ND		4.0	0.64	ug/L			12/13/23 15:48	4
Methylcyclohexane	ND		4.0	0.64	ug/L			12/13/23 15:48	4
Methylene Chloride	ND		4.0	1.8	ug/L			12/13/23 15:48	4
Styrene	ND		4.0	2.9	ug/L			12/13/23 15:48	4
Tetrachloroethene	ND		4.0	1.4	ug/L			12/13/23 15:48	4
Toluene	ND		4.0	2.0	ug/L			12/13/23 15:48	4
trans-1,2-Dichloroethene	ND		4.0	3.6	ug/L			12/13/23 15:48	4
trans-1,3-Dichloropropene	ND		4.0	1.5	ug/L			12/13/23 15:48	4
Trichloroethene	ND		4.0	1.8	ug/L			12/13/23 15:48	4
Trichlorofluoromethane	ND		4.0	3.5	ug/L			12/13/23 15:48	4
Vinyl chloride	ND		4.0	3.6	ug/L			12/13/23 15:48	4
Xylenes, Total	ND		8.0	2.6	ug/L			12/13/23 15:48	4

Client: LaBella Associates DPC
Job ID: 480-215658-1
Project/Site: Alumax & Roblin Periodic Review Reports

Client Sample ID: EX-MW-12
Lab Sample ID: 480-215658-7
Date Collected: 12/12/23 12:10
Matrix: Water
Date Received: 12/13/23 09:00

Surrogate	%Recovery	Qualifier	Limits	Prepared	Analyzed	Dil Fac
Toluene-d8 (Surr)	96		80 - 120		12/13/23 15:48	4
1,2-Dichloroethane-d4 (Surr)	89		77 - 120		12/13/23 15:48	4
4-Bromofluorobenzene (Surr)	99		73 - 120		12/13/23 15:48	4
Dibromofluoromethane (Surr)	93		75 - 123		12/13/23 15:48	4

Client: LaBella Associates DPC
Job ID: 480-215658-1
Project/Site: Alumax & Roblin Periodic Review Reports

Client Sample ID: MW-04
Lab Sample ID: 480-215658-8
Date Collected: 12/12/23 12:45
Matrix: Water
Date Received: 12/13/23 09:00

Method: SW846 8260C - Volatile Organic Compounds by GC/MS

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
1,1,1-Trichloroethane	ND		4.0	3.3	ug/L			12/13/23 16:10	4
1,1,2,2-Tetrachloroethane	ND		4.0	0.84	ug/L			12/13/23 16:10	4
1,1,2-Trichloroethane	ND		4.0	0.92	ug/L			12/13/23 16:10	4
1,1,2-Trichloro-1,2,2-trifluoroethane	ND		4.0	1.2	ug/L			12/13/23 16:10	4
1,1-Dichloroethane	ND		4.0	1.5	ug/L			12/13/23 16:10	4
1,1-Dichloroethene	ND		4.0	1.2	ug/L			12/13/23 16:10	4
1,2,4-Trichlorobenzene	ND		4.0	1.6	ug/L			12/13/23 16:10	4
1,2-Dibromo-3-Chloropropane	ND		4.0	1.6	ug/L			12/13/23 16:10	4
1,2-Dichlorobenzene	ND		4.0	3.2	ug/L			12/13/23 16:10	4
1,2-Dichloroethane	ND		4.0	0.84	ug/L			12/13/23 16:10	4
1,2-Dichloropropane	ND		4.0	2.9	ug/L			12/13/23 16:10	4
1,3-Dichlorobenzene	ND		4.0	3.1	ug/L			12/13/23 16:10	4
1,4-Dichlorobenzene	ND		4.0	3.4	ug/L			12/13/23 16:10	4
2-Butanone (MEK)	ND		40	5.3	ug/L			12/13/23 16:10	4
2-Hexanone	ND		20	5.0	ug/L			12/13/23 16:10	4
4-Methyl-2-pentanone (MIBK)	ND		20	8.4	ug/L			12/13/23 16:10	4
Acetone	ND		40	12	ug/L			12/13/23 16:10	4
Benzene	ND		4.0	1.6	ug/L			12/13/23 16:10	4
Bromodichloromethane	ND		4.0	1.6	ug/L			12/13/23 16:10	4
Bromoform	ND		4.0	1.0	ug/L			12/13/23 16:10	4
Bromomethane	ND		4.0	2.8	ug/L			12/13/23 16:10	4
Carbon disulfide	ND		4.0	0.76	ug/L			12/13/23 16:10	4
Carbon tetrachloride	ND		4.0	1.1	ug/L			12/13/23 16:10	4
Chlorobenzene	ND		4.0	3.0	ug/L			12/13/23 16:10	4
Dibromochloromethane	ND		4.0	1.3	ug/L			12/13/23 16:10	4
Chloroethane	ND		4.0	1.3	ug/L			12/13/23 16:10	4
Chloroform	ND		4.0	1.4	ug/L			12/13/23 16:10	4
Chloromethane	ND		4.0	1.4	ug/L			12/13/23 16:10	4
cis-1,2-Dichloroethene	ND		4.0	3.2	ug/L			12/13/23 16:10	4
cis-1,3-Dichloropropene	ND		4.0	1.4	ug/L			12/13/23 16:10	4
Cyclohexane	ND		4.0	0.72	ug/L			12/13/23 16:10	4
Dichlorodifluoromethane	ND		4.0	2.7	ug/L			12/13/23 16:10	4
Ethylbenzene	ND		4.0	3.0	ug/L			12/13/23 16:10	4
1,2-Dibromoethane	ND		4.0	2.9	ug/L			12/13/23 16:10	4
Isopropylbenzene	ND		4.0	3.2	ug/L			12/13/23 16:10	4
Methyl acetate	ND		10	5.2	ug/L			12/13/23 16:10	4
Methyl tert-butyl ether	ND		4.0	0.64	ug/L			12/13/23 16:10	4
Methylcyclohexane	ND		4.0	0.64	ug/L			12/13/23 16:10	4
Methylene Chloride	ND		4.0	1.8	ug/L			12/13/23 16:10	4
Styrene	ND		4.0	2.9	ug/L			12/13/23 16:10	4
Tetrachloroethene	ND		4.0	1.4	ug/L			12/13/23 16:10	4
Toluene	ND		4.0	2.0	ug/L			12/13/23 16:10	4
trans-1,2-Dichloroethene	ND		4.0	3.6	ug/L			12/13/23 16:10	4
trans-1,3-Dichloropropene	ND		4.0	1.5	ug/L			12/13/23 16:10	4
Trichloroethene	ND		4.0	1.8	ug/L			12/13/23 16:10	4
Trichlorofluoromethane	ND		4.0	3.5	ug/L			12/13/23 16:10	4
Vinyl chloride	ND		4.0	3.6	ug/L			12/13/23 16:10	4
Xylenes, Total	ND		8.0	2.6	ug/L			12/13/23 16:10	4

Client: LaBella Associates DPC
Job ID: 480-215658-1
Project/Site: Alumax & Roblin Periodic Review Reports

Client Sample ID: MW-04
Lab Sample ID: 480-215658-8
Date Collected: 12/12/23 12:45
Matrix: Water
Date Received: 12/13/23 09:00

Surrogate	%Recovery	Qualifier	Limits	Prepared	Analyzed	Dil Fac
Toluene-d8 (Surr)	97		80 - 120		12/13/23 16:10	4
1,2-Dichloroethane-d4 (Surr)	90		77 - 120		12/13/23 16:10	4
4-Bromofluorobenzene (Surr)	97		73 - 120		12/13/23 16:10	4
Dibromofluoromethane (Surr)	90		75 - 123		12/13/23 16:10	4

Client: LaBella Associates DPC
Job ID: 480-215658-1
Project/Site: Alumax & Roblin Periodic Review Reports

Client Sample ID: MW-13
Lab Sample ID: 480-215658-9
Date Collected: 12/12/23 13:30
Matrix: Water
Date Received: 12/13/23 09:00

Method: SW846 8260C - Volatile Organic Compounds by GC/MS

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
1,1,1-Trichloroethane	ND		4.0	3.3	ug/L			12/13/23 16:32	4
1,1,2,2-Tetrachloroethane	ND		4.0	0.84	ug/L			12/13/23 16:32	4
1,1,2-Trichloroethane	ND		4.0	0.92	ug/L			12/13/23 16:32	4
1,1,2-Trichloro-1,2,2-trifluoroethane	ND		4.0	1.2	ug/L			12/13/23 16:32	4
1,1-Dichloroethane	ND		4.0	1.5	ug/L			12/13/23 16:32	4
1,1-Dichloroethene	ND		4.0	1.2	ug/L			12/13/23 16:32	4
1,2,4-Trichlorobenzene	ND		4.0	1.6	ug/L			12/13/23 16:32	4
1,2-Dibromo-3-Chloropropane	ND		4.0	1.6	ug/L			12/13/23 16:32	4
1,2-Dichlorobenzene	ND		4.0	3.2	ug/L			12/13/23 16:32	4
1,2-Dichloroethane	ND		4.0	0.84	ug/L			12/13/23 16:32	4
1,2-Dichloropropane	ND		4.0	2.9	ug/L			12/13/23 16:32	4
1,3-Dichlorobenzene	ND		4.0	3.1	ug/L			12/13/23 16:32	4
1,4-Dichlorobenzene	ND		4.0	3.4	ug/L			12/13/23 16:32	4
2-Butanone (MEK)	ND		40	5.3	ug/L			12/13/23 16:32	4
2-Hexanone	ND		20	5.0	ug/L			12/13/23 16:32	4
4-Methyl-2-pentanone (MIBK)	ND		20	8.4	ug/L			12/13/23 16:32	4
Acetone	ND		40	12	ug/L			12/13/23 16:32	4
Benzene	**2.1**	**J**	4.0	1.6	ug/L			12/13/23 16:32	4
Bromodichloromethane	ND		4.0	1.6	ug/L			12/13/23 16:32	4
Bromoform	ND		4.0	1.0	ug/L			12/13/23 16:32	4
Bromomethane	ND		4.0	2.8	ug/L			12/13/23 16:32	4
Carbon disulfide	ND		4.0	0.76	ug/L			12/13/23 16:32	4
Carbon tetrachloride	ND		4.0	1.1	ug/L			12/13/23 16:32	4
Chlorobenzene	ND		4.0	3.0	ug/L			12/13/23 16:32	4
Dibromochloromethane	ND		4.0	1.3	ug/L			12/13/23 16:32	4
Chloroethane	ND		4.0	1.3	ug/L			12/13/23 16:32	4
Chloroform	ND		4.0	1.4	ug/L			12/13/23 16:32	4
Chloromethane	ND		4.0	1.4	ug/L			12/13/23 16:32	4
cis-1,2-Dichloroethene	ND		4.0	3.2	ug/L			12/13/23 16:32	4
cis-1,3-Dichloropropene	ND		4.0	1.4	ug/L			12/13/23 16:32	4
Cyclohexane	**6.1**		4.0	0.72	ug/L			12/13/23 16:32	4
Dichlorodifluoromethane	ND		4.0	2.7	ug/L			12/13/23 16:32	4
Ethylbenzene	ND		4.0	3.0	ug/L			12/13/23 16:32	4
1,2-Dibromoethane	ND		4.0	2.9	ug/L			12/13/23 16:32	4
Isopropylbenzene	ND		4.0	3.2	ug/L			12/13/23 16:32	4
Methyl acetate	ND		10	5.2	ug/L			12/13/23 16:32	4
Methyl tert-butyl ether	ND		4.0	0.64	ug/L			12/13/23 16:32	4
Methylcyclohexane	**6.8**		4.0	0.64	ug/L			12/13/23 16:32	4
Methylene Chloride	ND		4.0	1.8	ug/L			12/13/23 16:32	4
Styrene	ND		4.0	2.9	ug/L			12/13/23 16:32	4
Tetrachloroethene	ND		4.0	1.4	ug/L			12/13/23 16:32	4
Toluene	**3.0**	**J**	4.0	2.0	ug/L			12/13/23 16:32	4
trans-1,2-Dichloroethene	ND		4.0	3.6	ug/L			12/13/23 16:32	4
trans-1,3-Dichloropropene	ND		4.0	1.5	ug/L			12/13/23 16:32	4
Trichloroethene	ND		4.0	1.8	ug/L			12/13/23 16:32	4
Trichlorofluoromethane	ND		4.0	3.5	ug/L			12/13/23 16:32	4
Vinyl chloride	ND		4.0	3.6	ug/L			12/13/23 16:32	4
Xylenes, Total	**5.0**	**J**	8.0	2.6	ug/L			12/13/23 16:32	4

Client: LaBella Associates DPC
Job ID: 480-215658-1
Project/Site: Alumax & Roblin Periodic Review Reports

Client Sample ID: MW-13
Lab Sample ID: 480-215658-9
Date Collected: 12/12/23 13:30
Matrix: Water
Date Received: 12/13/23 09:00

Surrogate	%Recovery	Qualifier	Limits	Prepared	Analyzed	Dil Fac
Toluene-d8 (Surr)	100		80 - 120		12/13/23 16:32	4
1,2-Dichloroethane-d4 (Surr)	89		77 - 120		12/13/23 16:32	4
4-Bromofluorobenzene (Surr)	98		73 - 120		12/13/23 16:32	4
Dibromofluoromethane (Surr)	92		75 - 123		12/13/23 16:32	4

Client: LaBella Associates DPC
Job ID: 480-215658-1
Project/Site: Alumax & Roblin Periodic Review Reports

Client Sample ID: MW-07R
Lab Sample ID: 480-215658-10
Date Collected: 12/12/23 14:05
Matrix: Water
Date Received: 12/13/23 09:00

Method: SW846 8260C - Volatile Organic Compounds by GC/MS

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
1,1,1-Trichloroethane	ND		10	8.2	ug/L			12/13/23 16:54	10
1,1,2,2-Tetrachloroethane	ND		10	2.1	ug/L			12/13/23 16:54	10
1,1,2-Trichloroethane	ND		10	2.3	ug/L			12/13/23 16:54	10
1,1,2-Trichloro-1,2,2-trifluoroethane	ND		10	3.1	ug/L			12/13/23 16:54	10
1,1-Dichloroethane	ND		10	3.8	ug/L			12/13/23 16:54	10
1,1-Dichloroethene	**12**		10	2.9	ug/L			12/13/23 16:54	10
1,2,4-Trichlorobenzene	ND		10	4.1	ug/L			12/13/23 16:54	10
1,2-Dibromo-3-Chloropropane	ND		10	3.9	ug/L			12/13/23 16:54	10
1,2-Dichlorobenzene	ND		10	7.9	ug/L			12/13/23 16:54	10
1,2-Dichloroethane	ND		10	2.1	ug/L			12/13/23 16:54	10
1,2-Dichloropropane	ND		10	7.2	ug/L			12/13/23 16:54	10
1,3-Dichlorobenzene	ND		10	7.8	ug/L			12/13/23 16:54	10
1,4-Dichlorobenzene	ND		10	8.4	ug/L			12/13/23 16:54	10
2-Butanone (MEK)	ND		100	13	ug/L			12/13/23 16:54	10
2-Hexanone	ND		50	12	ug/L			12/13/23 16:54	10
4-Methyl-2-pentanone (MIBK)	ND		50	21	ug/L			12/13/23 16:54	10
Acetone	ND		100	30	ug/L			12/13/23 16:54	10
Benzene	ND		10	4.1	ug/L			12/13/23 16:54	10
Bromodichloromethane	ND		10	3.9	ug/L			12/13/23 16:54	10
Bromoform	ND		10	2.6	ug/L			12/13/23 16:54	10
Bromomethane	ND		10	6.9	ug/L			12/13/23 16:54	10
Carbon disulfide	ND		10	1.9	ug/L			12/13/23 16:54	10
Carbon tetrachloride	ND		10	2.7	ug/L			12/13/23 16:54	10
Chlorobenzene	ND		10	7.5	ug/L			12/13/23 16:54	10
Dibromochloromethane	ND		10	3.2	ug/L			12/13/23 16:54	10
Chloroethane	ND		10	3.2	ug/L			12/13/23 16:54	10
Chloroform	ND		10	3.4	ug/L			12/13/23 16:54	10
Chloromethane	ND		10	3.5	ug/L			12/13/23 16:54	10
cis-1,2-Dichloroethene	**3200**	**E**	10	8.1	ug/L			12/13/23 16:54	10
cis-1,3-Dichloropropene	ND		10	3.6	ug/L			12/13/23 16:54	10
Cyclohexane	ND		10	1.8	ug/L			12/13/23 16:54	10
Dichlorodifluoromethane	ND		10	6.8	ug/L			12/13/23 16:54	10
Ethylbenzene	ND		10	7.4	ug/L			12/13/23 16:54	10
1,2-Dibromoethane	ND		10	7.3	ug/L			12/13/23 16:54	10
Isopropylbenzene	ND		10	7.9	ug/L			12/13/23 16:54	10
Methyl acetate	ND		25	13	ug/L			12/13/23 16:54	10
Methyl tert-butyl ether	ND		10	1.6	ug/L			12/13/23 16:54	10
Methylcyclohexane	ND		10	1.6	ug/L			12/13/23 16:54	10
Methylene Chloride	ND		10	4.4	ug/L			12/13/23 16:54	10
Styrene	ND		10	7.3	ug/L			12/13/23 16:54	10
Tetrachloroethene	ND		10	3.6	ug/L			12/13/23 16:54	10
Toluene	ND		10	5.1	ug/L			12/13/23 16:54	10
trans-1,2-Dichloroethene	**9.6**	**J**	10	9.0	ug/L			12/13/23 16:54	10
trans-1,3-Dichloropropene	ND		10	3.7	ug/L			12/13/23 16:54	10
Trichloroethene	**21**		10	4.6	ug/L			12/13/23 16:54	10
Trichlorofluoromethane	ND		10	8.8	ug/L			12/13/23 16:54	10
Vinyl chloride	**690**	**F1**	10	9.0	ug/L			12/13/23 16:54	10
Xylenes, Total	ND		20	6.6	ug/L			12/13/23 16:54	10

Client: LaBella Associates DPC
Job ID: 480-215658-1
Project/Site: Alumax & Roblin Periodic Review Reports

Client Sample ID: MW-07R
Lab Sample ID: 480-215658-10

Date Collected: 12/12/23 14:05
Matrix: Water

Date Received: 12/13/23 09:00

Surrogate	%Recovery	Qualifier	Limits	Prepared	Analyzed	Dil Fac
Toluene-d8 (Surr)	*97*		*80 - 120*		*12/13/23 16:54*	*10*
1,2-Dichloroethane-d4 (Surr)	*88*		*77 - 120*		*12/13/23 16:54*	*10*
4-Bromofluorobenzene (Surr)	*99*		*73 - 120*		*12/13/23 16:54*	*10*
Dibromofluoromethane (Surr)	*89*		*75 - 123*		*12/13/23 16:54*	*10*

Method: SW846 8260C - Volatile Organic Compounds by GC/MS - DL

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
1,1,1-Trichloroethane	ND		80	66	ug/L			12/14/23 12:33	80
1,1,2,2-Tetrachloroethane	ND		80	17	ug/L			12/14/23 12:33	80
1,1,2-Trichloroethane	ND		80	18	ug/L			12/14/23 12:33	80
1,1,2-Trichloro-1,2,2-trifluoroethane	ND		80	25	ug/L			12/14/23 12:33	80
1,1-Dichloroethane	ND		80	30	ug/L			12/14/23 12:33	80
1,1-Dichloroethene	ND		80	23	ug/L			12/14/23 12:33	80
1,2,4-Trichlorobenzene	ND		80	33	ug/L			12/14/23 12:33	80
1,2-Dibromo-3-Chloropropane	ND		80	31	ug/L			12/14/23 12:33	80
1,2-Dichlorobenzene	ND		80	63	ug/L			12/14/23 12:33	80
1,2-Dichloroethane	ND		80	17	ug/L			12/14/23 12:33	80
1,2-Dichloropropane	ND		80	58	ug/L			12/14/23 12:33	80
1,3-Dichlorobenzene	ND		80	62	ug/L			12/14/23 12:33	80
1,4-Dichlorobenzene	ND		80	67	ug/L			12/14/23 12:33	80
2-Butanone (MEK)	ND		800	110	ug/L			12/14/23 12:33	80
2-Hexanone	ND		400	99	ug/L			12/14/23 12:33	80
4-Methyl-2-pentanone (MIBK)	ND		400	170	ug/L			12/14/23 12:33	80
Acetone	ND		800	240	ug/L			12/14/23 12:33	80
Benzene	ND		80	33	ug/L			12/14/23 12:33	80
Bromodichloromethane	ND		80	31	ug/L			12/14/23 12:33	80
Bromoform	ND		80	21	ug/L			12/14/23 12:33	80
Bromomethane	ND		80	55	ug/L			12/14/23 12:33	80
Carbon disulfide	ND		80	15	ug/L			12/14/23 12:33	80
Carbon tetrachloride	ND		80	22	ug/L			12/14/23 12:33	80
Chlorobenzene	ND		80	60	ug/L			12/14/23 12:33	80
Dibromochloromethane	ND		80	26	ug/L			12/14/23 12:33	80
Chloroethane	ND		80	26	ug/L			12/14/23 12:33	80
Chloroform	ND		80	27	ug/L			12/14/23 12:33	80
Chloromethane	ND		80	28	ug/L			12/14/23 12:33	80
cis-1,2-Dichloroethene	**3400**		80	65	ug/L			12/14/23 12:33	80
cis-1,3-Dichloropropene	ND		80	29	ug/L			12/14/23 12:33	80
Cyclohexane	ND		80	14	ug/L			12/14/23 12:33	80
Dichlorodifluoromethane	ND		80	54	ug/L			12/14/23 12:33	80
Ethylbenzene	ND		80	59	ug/L			12/14/23 12:33	80
1,2-Dibromoethane	ND		80	58	ug/L			12/14/23 12:33	80
Isopropylbenzene	ND		80	63	ug/L			12/14/23 12:33	80
Methyl acetate	ND		200	100	ug/L			12/14/23 12:33	80
Methyl tert-butyl ether	ND		80	13	ug/L			12/14/23 12:33	80
Methylcyclohexane	ND		80	13	ug/L			12/14/23 12:33	80
Methylene Chloride	ND		80	35	ug/L			12/14/23 12:33	80
Styrene	ND		80	58	ug/L			12/14/23 12:33	80
Tetrachloroethene	ND		80	29	ug/L			12/14/23 12:33	80
Toluene	ND		80	41	ug/L			12/14/23 12:33	80
trans-1,2-Dichloroethene	ND		80	72	ug/L			12/14/23 12:33	80

Client: LaBella Associates DPC
Job ID: 480-215658-1
Project/Site: Alumax & Roblin Periodic Review Reports

Client Sample ID: MW-07R
Lab Sample ID: 480-215658-10
Date Collected: 12/12/23 14:05
Matrix: Water
Date Received: 12/13/23 09:00

Method: SW846 8260C - Volatile Organic Compounds by GC/MS - DL (Continued)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
trans-1,3-Dichloropropene	ND		80	30	ug/L			12/14/23 12:33	80
Trichloroethene	ND		80	37	ug/L			12/14/23 12:33	80
Trichlorofluoromethane	ND		80	70	ug/L			12/14/23 12:33	80
Vinyl chloride	**780**		80	72	ug/L			12/14/23 12:33	80
Xylenes, Total	ND		160	53	ug/L			12/14/23 12:33	80

Surrogate	*%Recovery*	*Qualifier*	*Limits*	*Prepared*	*Analyzed*	*Dil Fac*
Toluene-d8 (Surr)	*98*		*80 - 120*		*12/14/23 12:33*	*80*
1,2-Dichloroethane-d4 (Surr)	*90*		*77 - 120*		*12/14/23 12:33*	*80*
4-Bromofluorobenzene (Surr)	*104*		*73 - 120*		*12/14/23 12:33*	*80*
Dibromofluoromethane (Surr)	*92*		*75 - 123*		*12/14/23 12:33*	*80*

Client: LaBella Associates DPC
Job ID: 480-215658-1
Project/Site: Alumax & Roblin Periodic Review Reports

Client Sample ID: DUP
Lab Sample ID: 480-215658-11
Date Collected: 12/12/23 00:00
Matrix: Water
Date Received: 12/13/23 09:00

Method: SW846 8260C - Volatile Organic Compounds by GC/MS

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
1,1,1-Trichloroethane	ND		10	8.2	ug/L			12/14/23 12:56	10
1,1,2,2-Tetrachloroethane	ND		10	2.1	ug/L			12/14/23 12:56	10
1,1,2-Trichloroethane	ND		10	2.3	ug/L			12/14/23 12:56	10
1,1,2-Trichloro-1,2,2-trifluoroethane	ND		10	3.1	ug/L			12/14/23 12:56	10
1,1-Dichloroethane	ND		10	3.8	ug/L			12/14/23 12:56	10
1,1-Dichloroethene	ND		10	2.9	ug/L			12/14/23 12:56	10
1,2,4-Trichlorobenzene	ND		10	4.1	ug/L			12/14/23 12:56	10
1,2-Dibromo-3-Chloropropane	ND		10	3.9	ug/L			12/14/23 12:56	10
1,2-Dichlorobenzene	ND		10	7.9	ug/L			12/14/23 12:56	10
1,2-Dichloroethane	ND		10	2.1	ug/L			12/14/23 12:56	10
1,2-Dichloropropane	ND		10	7.2	ug/L			12/14/23 12:56	10
1,3-Dichlorobenzene	ND		10	7.8	ug/L			12/14/23 12:56	10
1,4-Dichlorobenzene	ND		10	8.4	ug/L			12/14/23 12:56	10
2-Butanone (MEK)	ND		100	13	ug/L			12/14/23 12:56	10
2-Hexanone	ND		50	12	ug/L			12/14/23 12:56	10
4-Methyl-2-pentanone (MIBK)	ND		50	21	ug/L			12/14/23 12:56	10
Acetone	ND		100	30	ug/L			12/14/23 12:56	10
Benzene	ND		10	4.1	ug/L			12/14/23 12:56	10
Bromodichloromethane	ND		10	3.9	ug/L			12/14/23 12:56	10
Bromoform	ND		10	2.6	ug/L			12/14/23 12:56	10
Bromomethane	ND	F2	10	6.9	ug/L			12/14/23 12:56	10
Carbon disulfide	ND		10	1.9	ug/L			12/14/23 12:56	10
Carbon tetrachloride	ND		10	2.7	ug/L			12/14/23 12:56	10
Chlorobenzene	ND		10	7.5	ug/L			12/14/23 12:56	10
Dibromochloromethane	ND		10	3.2	ug/L			12/14/23 12:56	10
Chloroethane	ND	F2	10	3.2	ug/L			12/14/23 12:56	10
Chloroform	ND		10	3.4	ug/L			12/14/23 12:56	10
Chloromethane	ND		10	3.5	ug/L			12/14/23 12:56	10
cis-1,2-Dichloroethene	**99**		10	8.1	ug/L			12/14/23 12:56	10
cis-1,3-Dichloropropene	ND		10	3.6	ug/L			12/14/23 12:56	10
Cyclohexane	**39**		10	1.8	ug/L			12/14/23 12:56	10
Dichlorodifluoromethane	ND		10	6.8	ug/L			12/14/23 12:56	10
Ethylbenzene	ND		10	7.4	ug/L			12/14/23 12:56	10
1,2-Dibromoethane	ND		10	7.3	ug/L			12/14/23 12:56	10
Isopropylbenzene	ND		10	7.9	ug/L			12/14/23 12:56	10
Methyl acetate	ND		25	13	ug/L			12/14/23 12:56	10
Methyl tert-butyl ether	ND		10	1.6	ug/L			12/14/23 12:56	10
Methylcyclohexane	**37**		10	1.6	ug/L			12/14/23 12:56	10
Methylene Chloride	ND		10	4.4	ug/L			12/14/23 12:56	10
Styrene	ND		10	7.3	ug/L			12/14/23 12:56	10
Tetrachloroethene	ND		10	3.6	ug/L			12/14/23 12:56	10
Toluene	ND		10	5.1	ug/L			12/14/23 12:56	10
trans-1,2-Dichloroethene	ND		10	9.0	ug/L			12/14/23 12:56	10
trans-1,3-Dichloropropene	ND		10	3.7	ug/L			12/14/23 12:56	10
Trichloroethene	ND		10	4.6	ug/L			12/14/23 12:56	10
Trichlorofluoromethane	ND		10	8.8	ug/L			12/14/23 12:56	10
Vinyl chloride	**360**	**F1**	10	9.0	ug/L			12/14/23 12:56	10
Xylenes, Total	ND		20	6.6	ug/L			12/14/23 12:56	10

Client: LaBella Associates DPC
Job ID: 480-215658-1
Project/Site: Alumax & Roblin Periodic Review Reports

Client Sample ID: DUP
Lab Sample ID: 480-215658-11
Date Collected: 12/12/23 00:00
Matrix: Water
Date Received: 12/13/23 09:00

Surrogate	%Recovery	Qualifier	Limits	Prepared	Analyzed	Dil Fac
Toluene-d8 (Surr)	95		80 - 120		12/14/23 12:56	10
1,2-Dichloroethane-d4 (Surr)	97		77 - 120		12/14/23 12:56	10
4-Bromofluorobenzene (Surr)	100		73 - 120		12/14/23 12:56	10
Dibromofluoromethane (Surr)	97		75 - 123		12/14/23 12:56	10

Client: LaBella Associates DPC
Job ID: 480-215658-1
Project/Site: Alumax & Roblin Periodic Review Reports

Client Sample ID: TRIP BLANK
Lab Sample ID: 480-215658-12
Date Collected: 12/12/23 00:00
Matrix: Water
Date Received: 12/13/23 09:00

Method: SW846 8260C - Volatile Organic Compounds by GC/MS

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
1,1,1-Trichloroethane	ND		1.0	0.82	ug/L			12/13/23 17:39	1
1,1,2,2-Tetrachloroethane	ND		1.0	0.21	ug/L			12/13/23 17:39	1
1,1,2-Trichloroethane	ND		1.0	0.23	ug/L			12/13/23 17:39	1
1,1,2-Trichloro-1,2,2-trifluoroethane	ND		1.0	0.31	ug/L			12/13/23 17:39	1
1,1-Dichloroethane	ND		1.0	0.38	ug/L			12/13/23 17:39	1
1,1-Dichloroethene	ND		1.0	0.29	ug/L			12/13/23 17:39	1
1,2,4-Trichlorobenzene	ND		1.0	0.41	ug/L			12/13/23 17:39	1
1,2-Dibromo-3-Chloropropane	ND		1.0	0.39	ug/L			12/13/23 17:39	1
1,2-Dichlorobenzene	ND		1.0	0.79	ug/L			12/13/23 17:39	1
1,2-Dichloroethane	ND		1.0	0.21	ug/L			12/13/23 17:39	1
1,2-Dichloropropane	ND		1.0	0.72	ug/L			12/13/23 17:39	1
1,3-Dichlorobenzene	ND		1.0	0.78	ug/L			12/13/23 17:39	1
1,4-Dichlorobenzene	ND		1.0	0.84	ug/L			12/13/23 17:39	1
2-Butanone (MEK)	ND		10	1.3	ug/L			12/13/23 17:39	1
2-Hexanone	ND		5.0	1.2	ug/L			12/13/23 17:39	1
4-Methyl-2-pentanone (MIBK)	ND		5.0	2.1	ug/L			12/13/23 17:39	1
Acetone	ND		10	3.0	ug/L			12/13/23 17:39	1
Benzene	ND		1.0	0.41	ug/L			12/13/23 17:39	1
Bromodichloromethane	ND		1.0	0.39	ug/L			12/13/23 17:39	1
Bromoform	ND		1.0	0.26	ug/L			12/13/23 17:39	1
Bromomethane	ND		1.0	0.69	ug/L			12/13/23 17:39	1
Carbon disulfide	ND		1.0	0.19	ug/L			12/13/23 17:39	1
Carbon tetrachloride	ND		1.0	0.27	ug/L			12/13/23 17:39	1
Chlorobenzene	ND		1.0	0.75	ug/L			12/13/23 17:39	1
Dibromochloromethane	ND		1.0	0.32	ug/L			12/13/23 17:39	1
Chloroethane	ND		1.0	0.32	ug/L			12/13/23 17:39	1
Chloroform	ND		1.0	0.34	ug/L			12/13/23 17:39	1
Chloromethane	ND		1.0	0.35	ug/L			12/13/23 17:39	1
cis-1,2-Dichloroethene	ND		1.0	0.81	ug/L			12/13/23 17:39	1
cis-1,3-Dichloropropene	ND		1.0	0.36	ug/L			12/13/23 17:39	1
Cyclohexane	ND		1.0	0.18	ug/L			12/13/23 17:39	1
Dichlorodifluoromethane	ND		1.0	0.68	ug/L			12/13/23 17:39	1
Ethylbenzene	ND		1.0	0.74	ug/L			12/13/23 17:39	1
1,2-Dibromoethane	ND		1.0	0.73	ug/L			12/13/23 17:39	1
Isopropylbenzene	ND		1.0	0.79	ug/L			12/13/23 17:39	1
Methyl acetate	ND		2.5	1.3	ug/L			12/13/23 17:39	1
Methyl tert-butyl ether	ND		1.0	0.16	ug/L			12/13/23 17:39	1
Methylcyclohexane	ND		1.0	0.16	ug/L			12/13/23 17:39	1
Methylene Chloride	ND		1.0	0.44	ug/L			12/13/23 17:39	1
Styrene	ND		1.0	0.73	ug/L			12/13/23 17:39	1
Tetrachloroethene	ND		1.0	0.36	ug/L			12/13/23 17:39	1
Toluene	ND		1.0	0.51	ug/L			12/13/23 17:39	1
trans-1,2-Dichloroethene	ND		1.0	0.90	ug/L			12/13/23 17:39	1
trans-1,3-Dichloropropene	ND		1.0	0.37	ug/L			12/13/23 17:39	1
Trichloroethene	ND		1.0	0.46	ug/L			12/13/23 17:39	1
Trichlorofluoromethane	ND		1.0	0.88	ug/L			12/13/23 17:39	1
Vinyl chloride	ND		1.0	0.90	ug/L			12/13/23 17:39	1
Xylenes, Total	ND		2.0	0.66	ug/L			12/13/23 17:39	1

Client: LaBella Associates DPC
Job ID: 480-215658-1
Project/Site: Alumax & Roblin Periodic Review Reports

Client Sample ID: TRIP BLANK
Lab Sample ID: 480-215658-12
Date Collected: 12/12/23 00:00
Matrix: Water
Date Received: 12/13/23 09:00

Surrogate	%Recovery	Qualifier	Limits	Prepared	Analyzed	Dil Fac
Toluene-d8 (Surr)	99		80 - 120		12/13/23 17:39	1
1,2-Dichloroethane-d4 (Surr)	93		77 - 120		12/13/23 17:39	1
4-Bromofluorobenzene (Surr)	100		73 - 120		12/13/23 17:39	1
Dibromofluoromethane (Surr)	92		75 - 123		12/13/23 17:39	1

Surrogate Summary

Client: LaBella Associates DPC
Job ID: 480-215658-1
Project/Site: Alumax & Roblin Periodic Review Reports

Method: 8260C - Volatile Organic Compounds by GC/MS

Matrix: Water **Prep Type: Total/NA**

		Percent Surrogate Recovery (Acceptance Limits)			
		TOL	DCA	BFB	DBFM
Lab Sample ID	Client Sample ID	(80-120)	(77-120)	(73-120)	(75-123)
480-215658-1	AL-1	97	83	97	88
480-215658-2	AL-7	97	90	99	87
480-215658-3	AL-2	99	88	99	88
480-215658-4	MW-09R	97	92	98	92
480-215658-5	EX-MW-11R	99	88	98	86
480-215658-6	MW-02R	97	90	99	91
480-215658-7	EX-MW-12	96	89	99	93
480-215658-8	MW-04	97	90	97	90
480-215658-9	MW-13	100	89	98	92
480-215658-10	MW-07R	97	88	99	89
480-215658-10 - DL	MW-07R	98	90	104	92
480-215658-11	DUP	95	97	100	97
480-215658-11 MS	DUP	95	89	100	92
480-215658-11 MSD	DUP	96	87	106	90
480-215658-12	TRIP BLANK	99	93	100	92
LCS 480-695216/6	Lab Control Sample	96	87	98	89
LCS 480-695377/6	Lab Control Sample	97	84	102	88
MB 480-695216/8	Method Blank	97	89	98	91
MB 480-695377/8	Method Blank	98	87	104	93

Surrogate Legend

TOL = Toluene-d8 (Surr)
DCA = 1,2-Dichloroethane-d4 (Surr)
BFB = 4-Bromofluorobenzene (Surr)
DBFM = Dibromofluoromethane (Surr)

Method: 8260C - Volatile Organic Compounds by GC/MS

Lab Sample ID: MB 480-695216/8
Matrix: Water
Analysis Batch: 695216

Client Sample ID: Method Blank
Prep Type: Total/NA

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
1,1,1-Trichloroethane	ND		1.0	0.82	ug/L			12/13/23 11:40	1
1,1,2,2-Tetrachloroethane	ND		1.0	0.21	ug/L			12/13/23 11:40	1
1,1,2-Trichloroethane	ND		1.0	0.23	ug/L			12/13/23 11:40	1
1,1,2-Trichloro-1,2,2-trifluoroethane	ND		1.0	0.31	ug/L			12/13/23 11:40	1
1,1-Dichloroethane	ND		1.0	0.38	ug/L			12/13/23 11:40	1
1,1-Dichloroethene	ND		1.0	0.29	ug/L			12/13/23 11:40	1
1,2,4-Trichlorobenzene	ND		1.0	0.41	ug/L			12/13/23 11:40	1
1,2-Dibromo-3-Chloropropane	ND		1.0	0.39	ug/L			12/13/23 11:40	1
1,2-Dichlorobenzene	ND		1.0	0.79	ug/L			12/13/23 11:40	1
1,2-Dichloroethane	ND		1.0	0.21	ug/L			12/13/23 11:40	1
1,2-Dichloropropane	ND		1.0	0.72	ug/L			12/13/23 11:40	1
1,3-Dichlorobenzene	ND		1.0	0.78	ug/L			12/13/23 11:40	1
1,4-Dichlorobenzene	ND		1.0	0.84	ug/L			12/13/23 11:40	1
2-Butanone (MEK)	ND		10	1.3	ug/L			12/13/23 11:40	1
2-Hexanone	ND		5.0	1.2	ug/L			12/13/23 11:40	1
4-Methyl-2-pentanone (MIBK)	ND		5.0	2.1	ug/L			12/13/23 11:40	1
Acetone	ND		10	3.0	ug/L			12/13/23 11:40	1
Benzene	ND		1.0	0.41	ug/L			12/13/23 11:40	1
Bromodichloromethane	ND		1.0	0.39	ug/L			12/13/23 11:40	1
Bromoform	ND		1.0	0.26	ug/L			12/13/23 11:40	1
Bromomethane	ND		1.0	0.69	ug/L			12/13/23 11:40	1
Carbon disulfide	ND		1.0	0.19	ug/L			12/13/23 11:40	1
Carbon tetrachloride	ND		1.0	0.27	ug/L			12/13/23 11:40	1
Chlorobenzene	ND		1.0	0.75	ug/L			12/13/23 11:40	1
Dibromochloromethane	ND		1.0	0.32	ug/L			12/13/23 11:40	1
Chloroethane	ND		1.0	0.32	ug/L			12/13/23 11:40	1
Chloroform	ND		1.0	0.34	ug/L			12/13/23 11:40	1
Chloromethane	ND		1.0	0.35	ug/L			12/13/23 11:40	1
cis-1,2-Dichloroethene	ND		1.0	0.81	ug/L			12/13/23 11:40	1
cis-1,3-Dichloropropene	ND		1.0	0.36	ug/L			12/13/23 11:40	1
Cyclohexane	ND		1.0	0.18	ug/L			12/13/23 11:40	1
Dichlorodifluoromethane	ND		1.0	0.68	ug/L			12/13/23 11:40	1
Ethylbenzene	ND		1.0	0.74	ug/L			12/13/23 11:40	1
1,2-Dibromoethane	ND		1.0	0.73	ug/L			12/13/23 11:40	1
Isopropylbenzene	ND		1.0	0.79	ug/L			12/13/23 11:40	1
Methyl acetate	ND		2.5	1.3	ug/L			12/13/23 11:40	1
Methyl tert-butyl ether	ND		1.0	0.16	ug/L			12/13/23 11:40	1
Methylcyclohexane	ND		1.0	0.16	ug/L			12/13/23 11:40	1
Methylene Chloride	ND		1.0	0.44	ug/L			12/13/23 11:40	1
Styrene	ND		1.0	0.73	ug/L			12/13/23 11:40	1
Tetrachloroethene	ND		1.0	0.36	ug/L			12/13/23 11:40	1
Toluene	ND		1.0	0.51	ug/L			12/13/23 11:40	1
trans-1,2-Dichloroethene	ND		1.0	0.90	ug/L			12/13/23 11:40	1
trans-1,3-Dichloropropene	ND		1.0	0.37	ug/L			12/13/23 11:40	1
Trichloroethene	ND		1.0	0.46	ug/L			12/13/23 11:40	1
Trichlorofluoromethane	ND		1.0	0.88	ug/L			12/13/23 11:40	1
Vinyl chloride	ND		1.0	0.90	ug/L			12/13/23 11:40	1
Xylenes, Total	ND		2.0	0.66	ug/L			12/13/23 11:40	1

Method: 8260C - Volatile Organic Compounds by GC/MS (Continued)

Lab Sample ID: MB 480-695216/8
Matrix: Water
Analysis Batch: 695216

Client Sample ID: Method Blank
Prep Type: Total/NA

Surrogate	MB %Recovery	MB Qualifier	Limits	Prepared	Analyzed	Dil Fac
Toluene-d8 (Surr)	*97*		*80 - 120*		*12/13/23 11:40*	*1*
1,2-Dichloroethane-d4 (Surr)	*89*		*77 - 120*		*12/13/23 11:40*	*1*
4-Bromofluorobenzene (Surr)	*98*		*73 - 120*		*12/13/23 11:40*	*1*
Dibromofluoromethane (Surr)	*91*		*75 - 123*		*12/13/23 11:40*	*1*

Lab Sample ID: LCS 480-695216/6
Matrix: Water
Analysis Batch: 695216

Client Sample ID: Lab Control Sample
Prep Type: Total/NA

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec Limits
1,1,1-Trichloroethane	25.0	26.5		ug/L		106	73 - 126
1,1,2,2-Tetrachloroethane	25.0	25.9		ug/L		104	76 - 120
1,1,2-Trichloroethane	25.0	24.8		ug/L		99	76 - 122
1,1,2-Trichloro-1,2,2-trifluoroethane	25.0	25.3		ug/L		101	61 - 148
1,1-Dichloroethane	25.0	24.0		ug/L		96	77 - 120
1,1-Dichloroethene	25.0	22.4		ug/L		90	66 - 127
1,2,4-Trichlorobenzene	25.0	23.7		ug/L		95	79 - 122
1,2-Dibromo-3-Chloropropane	25.0	27.7		ug/L		111	56 - 134
1,2-Dichlorobenzene	25.0	24.8		ug/L		99	80 - 124
1,2-Dichloroethane	25.0	23.2		ug/L		93	75 - 120
1,2-Dichloropropane	25.0	25.5		ug/L		102	76 - 120
1,3-Dichlorobenzene	25.0	24.8		ug/L		99	77 - 120
1,4-Dichlorobenzene	25.0	23.9		ug/L		96	80 - 120
2-Butanone (MEK)	125	106		ug/L		85	57 - 140
2-Hexanone	125	113		ug/L		91	65 - 127
4-Methyl-2-pentanone (MIBK)	125	114		ug/L		91	71 - 125
Acetone	125	104		ug/L		83	56 - 142
Benzene	25.0	24.7		ug/L		99	71 - 124
Bromodichloromethane	25.0	26.8		ug/L		107	80 - 122
Bromoform	25.0	25.1		ug/L		100	61 - 132
Bromomethane	25.0	25.4		ug/L		102	55 - 144
Carbon disulfide	25.0	21.6		ug/L		87	59 - 134
Carbon tetrachloride	25.0	29.2		ug/L		117	72 - 134
Chlorobenzene	25.0	25.2		ug/L		101	80 - 120
Dibromochloromethane	25.0	25.1		ug/L		101	75 - 125
Chloroethane	25.0	24.9		ug/L		100	69 - 136
Chloroform	25.0	24.6		ug/L		98	73 - 127
Chloromethane	25.0	24.0		ug/L		96	68 - 124
cis-1,2-Dichloroethene	25.0	24.4		ug/L		98	74 - 124
cis-1,3-Dichloropropene	25.0	27.2		ug/L		109	74 - 124
Cyclohexane	25.0	24.0		ug/L		96	59 - 135
Dichlorodifluoromethane	25.0	27.6		ug/L		110	59 - 135
Ethylbenzene	25.0	23.8		ug/L		95	77 - 123
1,2-Dibromoethane	25.0	26.6		ug/L		106	77 - 120
Isopropylbenzene	25.0	27.9		ug/L		112	77 - 122
Methyl acetate	50.0	49.7		ug/L		99	74 - 133
Methyl tert-butyl ether	25.0	24.1		ug/L		97	77 - 120
Methylcyclohexane	25.0	26.1		ug/L		104	68 - 134

Method: 8260C - Volatile Organic Compounds by GC/MS (Continued)

Lab Sample ID: LCS 480-695216/6
Matrix: Water
Analysis Batch: 695216

Client Sample ID: Lab Control Sample
Prep Type: Total/NA

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec Limits
Methylene Chloride	25.0	25.6		ug/L		102	75 - 124
Styrene	25.0	24.7		ug/L		99	80 - 120
Tetrachloroethene	25.0	25.5		ug/L		102	74 - 122
Toluene	25.0	25.9		ug/L		104	80 - 122
trans-1,2-Dichloroethene	25.0	23.3		ug/L		93	73 - 127
trans-1,3-Dichloropropene	25.0	28.3		ug/L		113	80 - 120
Trichloroethene	25.0	25.5		ug/L		102	74 - 123
Trichlorofluoromethane	25.0	26.4		ug/L		106	62 - 150
Vinyl chloride	25.0	26.3		ug/L		105	65 - 133

Surrogate	*LCS %Recovery*	*LCS Qualifier*	*Limits*
Toluene-d8 (Surr)	*96*		*80 - 120*
1,2-Dichloroethane-d4 (Surr)	*87*		*77 - 120*
4-Bromofluorobenzene (Surr)	*98*		*73 - 120*
Dibromofluoromethane (Surr)	*89*		*75 - 123*

Lab Sample ID: MB 480-695377/8
Matrix: Water
Analysis Batch: 695377

Client Sample ID: Method Blank
Prep Type: Total/NA

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
1,1,1-Trichloroethane	ND		1.0	0.82	ug/L			12/14/23 11:16	1
1,1,2,2-Tetrachloroethane	ND		1.0	0.21	ug/L			12/14/23 11:16	1
1,1,2-Trichloroethane	ND		1.0	0.23	ug/L			12/14/23 11:16	1
1,1,2-Trichloro-1,2,2-trifluoroethane	ND		1.0	0.31	ug/L			12/14/23 11:16	1
1,1-Dichloroethane	ND		1.0	0.38	ug/L			12/14/23 11:16	1
1,1-Dichloroethene	ND		1.0	0.29	ug/L			12/14/23 11:16	1
1,2,4-Trichlorobenzene	ND		1.0	0.41	ug/L			12/14/23 11:16	1
1,2-Dibromo-3-Chloropropane	ND		1.0	0.39	ug/L			12/14/23 11:16	1
1,2-Dichlorobenzene	ND		1.0	0.79	ug/L			12/14/23 11:16	1
1,2-Dichloroethane	ND		1.0	0.21	ug/L			12/14/23 11:16	1
1,2-Dichloropropane	ND		1.0	0.72	ug/L			12/14/23 11:16	1
1,3-Dichlorobenzene	ND		1.0	0.78	ug/L			12/14/23 11:16	1
1,4-Dichlorobenzene	ND		1.0	0.84	ug/L			12/14/23 11:16	1
2-Butanone (MEK)	ND		10	1.3	ug/L			12/14/23 11:16	1
2-Hexanone	ND		5.0	1.2	ug/L			12/14/23 11:16	1
4-Methyl-2-pentanone (MIBK)	ND		5.0	2.1	ug/L			12/14/23 11:16	1
Acetone	ND		10	3.0	ug/L			12/14/23 11:16	1
Benzene	ND		1.0	0.41	ug/L			12/14/23 11:16	1
Bromodichloromethane	ND		1.0	0.39	ug/L			12/14/23 11:16	1
Bromoform	ND		1.0	0.26	ug/L			12/14/23 11:16	1
Bromomethane	ND		1.0	0.69	ug/L			12/14/23 11:16	1
Carbon disulfide	ND		1.0	0.19	ug/L			12/14/23 11:16	1
Carbon tetrachloride	ND		1.0	0.27	ug/L			12/14/23 11:16	1
Chlorobenzene	ND		1.0	0.75	ug/L			12/14/23 11:16	1
Dibromochloromethane	ND		1.0	0.32	ug/L			12/14/23 11:16	1
Chloroethane	ND		1.0	0.32	ug/L			12/14/23 11:16	1
Chloroform	ND		1.0	0.34	ug/L			12/14/23 11:16	1

Method: 8260C - Volatile Organic Compounds by GC/MS (Continued)

Lab Sample ID: MB 480-695377/8
Matrix: Water
Analysis Batch: 695377

Client Sample ID: Method Blank
Prep Type: Total/NA

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Chloromethane	ND		1.0	0.35	ug/L			12/14/23 11:16	1
cis-1,2-Dichloroethene	ND		1.0	0.81	ug/L			12/14/23 11:16	1
cis-1,3-Dichloropropene	ND		1.0	0.36	ug/L			12/14/23 11:16	1
Cyclohexane	ND		1.0	0.18	ug/L			12/14/23 11:16	1
Dichlorodifluoromethane	ND		1.0	0.68	ug/L			12/14/23 11:16	1
Ethylbenzene	ND		1.0	0.74	ug/L			12/14/23 11:16	1
1,2-Dibromoethane	ND		1.0	0.73	ug/L			12/14/23 11:16	1
Isopropylbenzene	ND		1.0	0.79	ug/L			12/14/23 11:16	1
Methyl acetate	ND		2.5	1.3	ug/L			12/14/23 11:16	1
Methyl tert-butyl ether	ND		1.0	0.16	ug/L			12/14/23 11:16	1
Methylcyclohexane	ND		1.0	0.16	ug/L			12/14/23 11:16	1
Methylene Chloride	ND		1.0	0.44	ug/L			12/14/23 11:16	1
Styrene	ND		1.0	0.73	ug/L			12/14/23 11:16	1
Tetrachloroethene	ND		1.0	0.36	ug/L			12/14/23 11:16	1
Toluene	ND		1.0	0.51	ug/L			12/14/23 11:16	1
trans-1,2-Dichloroethene	ND		1.0	0.90	ug/L			12/14/23 11:16	1
trans-1,3-Dichloropropene	ND		1.0	0.37	ug/L			12/14/23 11:16	1
Trichloroethene	ND		1.0	0.46	ug/L			12/14/23 11:16	1
Trichlorofluoromethane	ND		1.0	0.88	ug/L			12/14/23 11:16	1
Vinyl chloride	ND		1.0	0.90	ug/L			12/14/23 11:16	1
Xylenes, Total	ND		2.0	0.66	ug/L			12/14/23 11:16	1

Surrogate	*MB %Recovery*	*MB Qualifier*	*Limits*	*Prepared*	*Analyzed*	*Dil Fac*
Toluene-d8 (Surr)	*98*		*80 - 120*		*12/14/23 11:16*	*1*
1,2-Dichloroethane-d4 (Surr)	*87*		*77 - 120*		*12/14/23 11:16*	*1*
4-Bromofluorobenzene (Surr)	*104*		*73 - 120*		*12/14/23 11:16*	*1*
Dibromofluoromethane (Surr)	*93*		*75 - 123*		*12/14/23 11:16*	*1*

Lab Sample ID: LCS 480-695377/6
Matrix: Water
Analysis Batch: 695377

Client Sample ID: Lab Control Sample
Prep Type: Total/NA

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec Limits
1,1,1-Trichloroethane	25.0	27.2		ug/L		109	73 - 126
1,1,2,2-Tetrachloroethane	25.0	25.2		ug/L		101	76 - 120
1,1,2-Trichloroethane	25.0	25.3		ug/L		101	76 - 122
1,1,2-Trichloro-1,2,2-trifluoroethane	25.0	24.8		ug/L		99	61 - 148
1,1-Dichloroethane	25.0	23.9		ug/L		96	77 - 120
1,1-Dichloroethene	25.0	22.9		ug/L		92	66 - 127
1,2,4-Trichlorobenzene	25.0	25.7		ug/L		103	79 - 122
1,2-Dibromo-3-Chloropropane	25.0	28.1		ug/L		113	56 - 134
1,2-Dichlorobenzene	25.0	25.3		ug/L		101	80 - 124
1,2-Dichloroethane	25.0	23.2		ug/L		93	75 - 120
1,2-Dichloropropane	25.0	24.3		ug/L		97	76 - 120
1,3-Dichlorobenzene	25.0	25.4		ug/L		102	77 - 120
1,4-Dichlorobenzene	25.0	24.5		ug/L		98	80 - 120
2-Butanone (MEK)	125	114		ug/L		91	57 - 140
2-Hexanone	125	116		ug/L		92	65 - 127

Method: 8260C - Volatile Organic Compounds by GC/MS (Continued)

Lab Sample ID: LCS 480-695377/6
Matrix: Water
Analysis Batch: 695377

Client Sample ID: Lab Control Sample
Prep Type: Total/NA

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec Limits
4-Methyl-2-pentanone (MIBK)	125	122		ug/L		97	71 - 125
Acetone	125	136		ug/L		109	56 - 142
Benzene	25.0	24.4		ug/L		98	71 - 124
Bromodichloromethane	25.0	26.0		ug/L		104	80 - 122
Bromoform	25.0	25.7		ug/L		103	61 - 132
Bromomethane	25.0	22.2		ug/L		89	55 - 144
Carbon disulfide	25.0	21.4		ug/L		86	59 - 134
Carbon tetrachloride	25.0	30.3		ug/L		121	72 - 134
Chlorobenzene	25.0	25.3		ug/L		101	80 - 120
Dibromochloromethane	25.0	26.8		ug/L		107	75 - 125
Chloroethane	25.0	25.1		ug/L		100	69 - 136
Chloroform	25.0	24.8		ug/L		99	73 - 127
Chloromethane	25.0	20.3		ug/L		81	68 - 124
cis-1,2-Dichloroethene	25.0	25.1		ug/L		100	74 - 124
cis-1,3-Dichloropropene	25.0	26.9		ug/L		108	74 - 124
Cyclohexane	25.0	24.1		ug/L		96	59 - 135
Dichlorodifluoromethane	25.0	15.5		ug/L		62	59 - 135
Ethylbenzene	25.0	24.8		ug/L		99	77 - 123
1,2-Dibromoethane	25.0	26.2		ug/L		105	77 - 120
Isopropylbenzene	25.0	29.3		ug/L		117	77 - 122
Methyl acetate	50.0	51.7		ug/L		103	74 - 133
Methyl tert-butyl ether	25.0	25.2		ug/L		101	77 - 120
Methylcyclohexane	25.0	26.5		ug/L		106	68 - 134
Methylene Chloride	25.0	26.0		ug/L		104	75 - 124
Styrene	25.0	25.3		ug/L		101	80 - 120
Tetrachloroethene	25.0	27.0		ug/L		108	74 - 122
Toluene	25.0	26.4		ug/L		106	80 - 122
trans-1,2-Dichloroethene	25.0	23.7		ug/L		95	73 - 127
trans-1,3-Dichloropropene	25.0	28.6		ug/L		114	80 - 120
Trichloroethene	25.0	24.6		ug/L		99	74 - 123
Trichlorofluoromethane	25.0	25.6		ug/L		102	62 - 150
Vinyl chloride	25.0	23.1		ug/L		93	65 - 133

Surrogate	*LCS %Recovery*	*LCS Qualifier*	*Limits*
Toluene-d8 (Surr)	*97*		*80 - 120*
1,2-Dichloroethane-d4 (Surr)	*84*		*77 - 120*
4-Bromofluorobenzene (Surr)	*102*		*73 - 120*
Dibromofluoromethane (Surr)	*88*		*75 - 123*

Lab Sample ID: 480-215658-11 MS
Matrix: Water
Analysis Batch: 695377

Client Sample ID: DUP
Prep Type: Total/NA

Analyte	Sample Result	Sample Qualifier	Spike Added	MS Result	MS Qualifier	Unit	D	%Rec	%Rec Limits
1,1,1-Trichloroethane	ND		250	274		ug/L		109	73 - 126
1,1,2,2-Tetrachloroethane	ND		250	260		ug/L		104	76 - 120
1,1,2-Trichloroethane	ND		250	255		ug/L		102	76 - 122
1,1,2-Trichloro-1,2,2-trifluoroethane	ND		250	266		ug/L		106	61 - 148

Method: 8260C - Volatile Organic Compounds by GC/MS (Continued)

Lab Sample ID: 480-215658-11 MS
Matrix: Water
Analysis Batch: 695377

Client Sample ID: DUP
Prep Type: Total/NA

Analyte	Sample Result	Sample Qualifier	Spike Added	MS Result	MS Qualifier	Unit	D	%Rec	%Rec Limits
1,1-Dichloroethane	ND		250	248		ug/L		99	77 - 120
1,1-Dichloroethene	ND		250	224		ug/L		90	66 - 127
1,2,4-Trichlorobenzene	ND		250	257		ug/L		103	79 - 122
1,2-Dibromo-3-Chloropropane	ND		250	262		ug/L		105	56 - 134
1,2-Dichlorobenzene	ND		250	255		ug/L		102	80 - 124
1,2-Dichloroethane	ND		250	241		ug/L		96	75 - 120
1,2-Dichloropropane	ND		250	260		ug/L		104	76 - 120
1,3-Dichlorobenzene	ND		250	259		ug/L		104	77 - 120
1,4-Dichlorobenzene	ND		250	249		ug/L		100	78 - 124
2-Butanone (MEK)	ND		1250	1200		ug/L		96	57 - 140
2-Hexanone	ND		1250	1190		ug/L		95	65 - 127
4-Methyl-2-pentanone (MIBK)	ND		1250	1170		ug/L		93	71 - 125
Acetone	ND		1250	1330		ug/L		106	56 - 142
Benzene	ND		250	257		ug/L		103	71 - 124
Bromodichloromethane	ND		250	272		ug/L		109	80 - 122
Bromoform	ND		250	234		ug/L		93	61 - 132
Bromomethane	ND	F2	250	193		ug/L		77	55 - 144
Carbon disulfide	ND		250	195		ug/L		78	59 - 134
Carbon tetrachloride	ND		250	297		ug/L		119	72 - 134
Chlorobenzene	ND		250	254		ug/L		101	80 - 120
Dibromochloromethane	ND		250	248		ug/L		99	75 - 125
Chloroethane	ND	F2	250	196		ug/L		79	69 - 136
Chloroform	ND		250	263		ug/L		105	73 - 127
Chloromethane	ND		250	199		ug/L		80	68 - 124
cis-1,2-Dichloroethene	99		250	337		ug/L		95	74 - 124
cis-1,3-Dichloropropene	ND		250	270		ug/L		108	74 - 124
Cyclohexane	39		250	276		ug/L		95	59 - 135
Dichlorodifluoromethane	ND		250	152		ug/L		61	59 - 135
Ethylbenzene	ND		250	251		ug/L		100	77 - 123
1,2-Dibromoethane	ND		250	256		ug/L		102	77 - 120
Isopropylbenzene	ND		250	291		ug/L		117	77 - 122
Methyl acetate	ND		500	544		ug/L		109	74 - 133
Methyl tert-butyl ether	ND		250	248		ug/L		99	77 - 120
Methylcyclohexane	37		250	298		ug/L		104	68 - 134
Methylene Chloride	ND		250	256		ug/L		103	75 - 124
Styrene	ND		250	253		ug/L		101	80 - 120
Tetrachloroethene	ND		250	270		ug/L		108	74 - 122
Toluene	ND		250	262		ug/L		105	80 - 122
trans-1,2-Dichloroethene	ND		250	239		ug/L		96	73 - 127
trans-1,3-Dichloropropene	ND		250	272		ug/L		109	80 - 120
Trichloroethene	ND		250	258		ug/L		103	74 - 123
Trichlorofluoromethane	ND		250	262		ug/L		105	62 - 150
Vinyl chloride	360	F1	250	489	F1	ug/L		53	65 - 133

Surrogate	*MS %Recovery*	*MS Qualifier*	*Limits*
Toluene-d8 (Surr)	*95*		*80 - 120*
1,2-Dichloroethane-d4 (Surr)	*89*		*77 - 120*
4-Bromofluorobenzene (Surr)	*100*		*73 - 120*

Method: 8260C - Volatile Organic Compounds by GC/MS (Continued)

Lab Sample ID: 480-215658-11 MS
Matrix: Water
Analysis Batch: 695377

Client Sample ID: DUP
Prep Type: Total/NA

Surrogate	MS %Recovery	MS Qualifier	Limits
Dibromofluoromethane (Surr)	*92*		*75 - 123*

Lab Sample ID: 480-215658-11 MSD
Matrix: Water
Analysis Batch: 695377

Client Sample ID: DUP
Prep Type: Total/NA

Analyte	Sample Result	Sample Qualifier	Spike Added	MSD Result	MSD Qualifier	Unit	D	%Rec	%Rec Limits	RPD	RPD Limit
1,1,1-Trichloroethane	ND		250	269		ug/L		108	73 - 126	2	15
1,1,2,2-Tetrachloroethane	ND		250	262		ug/L		105	76 - 120	1	15
1,1,2-Trichloroethane	ND		250	255		ug/L		102	76 - 122	0	15
1,1,2-Trichloro-1,2,2-trifluoroethane	ND		250	262		ug/L		105	61 - 148	1	20
1,1-Dichloroethane	ND		250	248		ug/L		99	77 - 120	0	20
1,1-Dichloroethene	ND		250	227		ug/L		91	66 - 127	1	16
1,2,4-Trichlorobenzene	ND		250	255		ug/L		102	79 - 122	1	20
1,2-Dibromo-3-Chloropropane	ND		250	267		ug/L		107	56 - 134	2	15
1,2-Dichlorobenzene	ND		250	246		ug/L		98	80 - 124	4	20
1,2-Dichloroethane	ND		250	241		ug/L		97	75 - 120	0	20
1,2-Dichloropropane	ND		250	276		ug/L		111	76 - 120	6	20
1,3-Dichlorobenzene	ND		250	261		ug/L		104	77 - 120	1	20
1,4-Dichlorobenzene	ND		250	248		ug/L		99	78 - 124	0	20
2-Butanone (MEK)	ND		1250	1250		ug/L		100	57 - 140	3	20
2-Hexanone	ND		1250	1190		ug/L		95	65 - 127	0	15
4-Methyl-2-pentanone (MIBK)	ND		1250	1240		ug/L		99	71 - 125	6	35
Acetone	ND		1250	1320		ug/L		106	56 - 142	0	15
Benzene	ND		250	255		ug/L		102	71 - 124	1	13
Bromodichloromethane	ND		250	266		ug/L		106	80 - 122	2	15
Bromoform	ND		250	235		ug/L		94	61 - 132	1	15
Bromomethane	ND	F2	250	226	F2	ug/L		91	55 - 144	16	15
Carbon disulfide	ND		250	195		ug/L		78	59 - 134	0	15
Carbon tetrachloride	ND		250	306		ug/L		123	72 - 134	3	15
Chlorobenzene	ND		250	253		ug/L		101	80 - 120	0	25
Dibromochloromethane	ND		250	260		ug/L		104	75 - 125	5	15
Chloroethane	ND	F2	250	244	F2	ug/L		98	69 - 136	22	15
Chloroform	ND		250	255		ug/L		102	73 - 127	3	20
Chloromethane	ND		250	187		ug/L		75	68 - 124	6	15
cis-1,2-Dichloroethene	99		250	342		ug/L		97	74 - 124	2	15
cis-1,3-Dichloropropene	ND		250	265		ug/L		106	74 - 124	2	15
Cyclohexane	39		250	271		ug/L		93	59 - 135	2	20
Dichlorodifluoromethane	ND		250	157		ug/L		63	59 - 135	4	20
Ethylbenzene	ND		250	251		ug/L		100	77 - 123	0	15
1,2-Dibromoethane	ND		250	262		ug/L		105	77 - 120	2	15
Isopropylbenzene	ND		250	291		ug/L		116	77 - 122	0	20
Methyl acetate	ND		500	556		ug/L		111	74 - 133	2	20
Methyl tert-butyl ether	ND		250	254		ug/L		102	77 - 120	3	37
Methylcyclohexane	37		250	292		ug/L		102	68 - 134	2	20
Methylene Chloride	ND		250	260		ug/L		104	75 - 124	1	15
Styrene	ND		250	252		ug/L		101	80 - 120	0	20
Tetrachloroethene	ND		250	277		ug/L		111	74 - 122	3	20

Method: 8260C - Volatile Organic Compounds by GC/MS (Continued)

Lab Sample ID: 480-215658-11 MSD
Client Sample ID: DUP
Matrix: Water
Prep Type: Total/NA
Analysis Batch: 695377

Analyte	Sample Result	Sample Qualifier	Spike Added	MSD Result	MSD Qualifier	Unit	D	%Rec	%Rec Limits	RPD	RPD Limit
Toluene	ND		250	256		ug/L		102	80 - 122	2	15
trans-1,2-Dichloroethene	ND		250	240		ug/L		96	73 - 127	0	20
trans-1,3-Dichloropropene	ND		250	277		ug/L		111	80 - 120	2	15
Trichloroethene	ND		250	265		ug/L		106	74 - 123	3	16
Trichlorofluoromethane	ND		250	254		ug/L		102	62 - 150	3	20
Vinyl chloride	360	F1	250	488	F1	ug/L		52	65 - 133	0	15

Surrogate	*MSD %Recovery*	*MSD Qualifier*	*Limits*
Toluene-d8 (Surr)	*96*		*80 - 120*
1,2-Dichloroethane-d4 (Surr)	*87*		*77 - 120*
4-Bromofluorobenzene (Surr)	*106*		*73 - 120*
Dibromofluoromethane (Surr)	*90*		*75 - 123*

QC Association Summary

Client: LaBella Associates DPC
Job ID: 480-215658-1
Project/Site: Alumax & Roblin Periodic Review Reports

GC/MS VOA

Analysis Batch: 695216

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
480-215658-2	AL-7	Total/NA	Water	8260C	
480-215658-3	AL-2	Total/NA	Water	8260C	
480-215658-4	MW-09R	Total/NA	Water	8260C	
480-215658-6	MW-02R	Total/NA	Water	8260C	
480-215658-7	EX-MW-12	Total/NA	Water	8260C	
480-215658-8	MW-04	Total/NA	Water	8260C	
480-215658-9	MW-13	Total/NA	Water	8260C	
480-215658-10	MW-07R	Total/NA	Water	8260C	
480-215658-12	TRIP BLANK	Total/NA	Water	8260C	
MB 480-695216/8	Method Blank	Total/NA	Water	8260C	
LCS 480-695216/6	Lab Control Sample	Total/NA	Water	8260C	

Analysis Batch: 695377

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
480-215658-1	AL-1	Total/NA	Water	8260C	
480-215658-5	EX-MW-11R	Total/NA	Water	8260C	
480-215658-10 - DL	MW-07R	Total/NA	Water	8260C	
480-215658-11	DUP	Total/NA	Water	8260C	
MB 480-695377/8	Method Blank	Total/NA	Water	8260C	
LCS 480-695377/6	Lab Control Sample	Total/NA	Water	8260C	
480-215658-11 MS	DUP	Total/NA	Water	8260C	
480-215658-11 MSD	DUP	Total/NA	Water	8260C	

Lab Chronicle

Client: LaBella Associates DPC
Job ID: 480-215658-1
Project/Site: Alumax & Roblin Periodic Review Reports

Client Sample ID: AL-1
Lab Sample ID: 480-215658-1
Date Collected: 12/12/23 08:30
Matrix: Water
Date Received: 12/13/23 09:00

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Analysis	8260C		2	695377	CR	EET BUF	12/14/23 11:48

Client Sample ID: AL-7
Lab Sample ID: 480-215658-2
Date Collected: 12/12/23 08:55
Matrix: Water
Date Received: 12/13/23 09:00

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Analysis	8260C		1	695216	CR	EET BUF	12/13/23 13:57

Client Sample ID: AL-2
Lab Sample ID: 480-215658-3
Date Collected: 12/12/23 09:35
Matrix: Water
Date Received: 12/13/23 09:00

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Analysis	8260C		1	695216	CR	EET BUF	12/13/23 14:19

Client Sample ID: MW-09R
Lab Sample ID: 480-215658-4
Date Collected: 12/12/23 10:15
Matrix: Water
Date Received: 12/13/23 09:00

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Analysis	8260C		10	695216	CR	EET BUF	12/13/23 14:41

Client Sample ID: EX-MW-11R
Lab Sample ID: 480-215658-5
Date Collected: 12/12/23 10:45
Matrix: Water
Date Received: 12/13/23 09:00

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Analysis	8260C		50	695377	CR	EET BUF	12/14/23 12:11

Client Sample ID: MW-02R
Lab Sample ID: 480-215658-6
Date Collected: 12/12/23 11:25
Matrix: Water
Date Received: 12/13/23 09:00

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Analysis	8260C		5	695216	CR	EET BUF	12/13/23 15:25

Client Sample ID: EX-MW-12
Lab Sample ID: 480-215658-7
Date Collected: 12/12/23 12:10
Matrix: Water
Date Received: 12/13/23 09:00

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Analysis	8260C		4	695216	CR	EET BUF	12/13/23 15:48

Lab Chronicle

Client: LaBella Associates DPC
Job ID: 480-215658-1
Project/Site: Alumax & Roblin Periodic Review Reports

Client Sample ID: MW-04
Lab Sample ID: 480-215658-8
Date Collected: 12/12/23 12:45
Matrix: Water
Date Received: 12/13/23 09:00

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Analysis	8260C		4	695216	CR	EET BUF	12/13/23 16:10

Client Sample ID: MW-13
Lab Sample ID: 480-215658-9
Date Collected: 12/12/23 13:30
Matrix: Water
Date Received: 12/13/23 09:00

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Analysis	8260C		4	695216	CR	EET BUF	12/13/23 16:32

Client Sample ID: MW-07R
Lab Sample ID: 480-215658-10
Date Collected: 12/12/23 14:05
Matrix: Water
Date Received: 12/13/23 09:00

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Analysis	8260C		10	695216	CR	EET BUF	12/13/23 16:54
Total/NA	Analysis	8260C	DL	80	695377	CR	EET BUF	12/14/23 12:33

Client Sample ID: DUP
Lab Sample ID: 480-215658-11
Date Collected: 12/12/23 00:00
Matrix: Water
Date Received: 12/13/23 09:00

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Analysis	8260C		10	695377	CR	EET BUF	12/14/23 12:56

Client Sample ID: TRIP BLANK
Lab Sample ID: 480-215658-12
Date Collected: 12/12/23 00:00
Matrix: Water
Date Received: 12/13/23 09:00

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Analysis	8260C		1	695216	CR	EET BUF	12/13/23 17:39

Laboratory References:

EET BUF = Eurofins Buffalo, 10 Hazelwood Drive, Amherst, NY 14228-2298, TEL (716)691-2600

Accreditation/Certification Summary

Client: LaBella Associates DPC
Job ID: 480-215658-1
Project/Site: Alumax & Roblin Periodic Review Reports

Laboratory: Eurofins Buffalo

The accreditations/certifications listed below are applicable to this report.

Authority	Program	Identification Number	Expiration Date
New York	NELAP	10026	03-31-24

Method Summary

Client: LaBella Associates DPC
Job ID: 480-215658-1
Project/Site: Alumax & Roblin Periodic Review Reports

Method	Method Description	Protocol	Laboratory
8260C	Volatile Organic Compounds by GC/MS	SW846	EET BUF
5030C	Purge and Trap	SW846	EET BUF

Protocol References:

SW846 = "Test Methods For Evaluating Solid Waste, Physical/Chemical Methods", Third Edition, November 1986 And Its Updates.

Laboratory References:

EET BUF = Eurofins Buffalo, 10 Hazelwood Drive, Amherst, NY 14228-2298, TEL (716)691-2600

Sample Summary

Client: LaBella Associates DPC
Job ID: 480-215658-1
Project/Site: Alumax & Roblin Periodic Review Reports

Lab Sample ID	Client Sample ID	Matrix	Collected	Received
480-215658-1	AL-1	Water	12/12/23 08:30	12/13/23 09:00
480-215658-2	AL-7	Water	12/12/23 08:55	12/13/23 09:00
480-215658-3	AL-2	Water	12/12/23 09:35	12/13/23 09:00
480-215658-4	MW-09R	Water	12/12/23 10:15	12/13/23 09:00
480-215658-5	EX-MW-11R	Water	12/12/23 10:45	12/13/23 09:00
480-215658-6	MW-02R	Water	12/12/23 11:25	12/13/23 09:00
480-215658-7	EX-MW-12	Water	12/12/23 12:10	12/13/23 09:00
480-215658-8	MW-04	Water	12/12/23 12:45	12/13/23 09:00
480-215658-9	MW-13	Water	12/12/23 13:30	12/13/23 09:00
480-215658-10	MW-07R	Water	12/12/23 14:05	12/13/23 09:00
480-215658-11	DUP	Water	12/12/23 00:00	12/13/23 09:00
480-215658-12	TRIP BLANK	Water	12/12/23 00:00	12/13/23 09:00

Eurofins Buffalo
10 Hazelwood Drive
Amherst, NY 14228-2298
Phone: 716-691-2600 Fax: 716-691-7991

Chain of Custody Record

eurofins | Environment Testing

Client Information	Sampler: A. Koons	Lab PM: Fischer, Brian J	Carrier Tracking No(s):	COC No: 480-190974-40138.1
Client Contact: Chris Kibler	Phone: 716.417.9156	E-Mail: Brian.Fischer@et.eurofinsus.com	State of Origin: NY	Page: Page 1 of 2
Company: LaBella Associates DPC	PWSID:			Job #:
Address: 300 Pearl Street Suite 130	Due Date Requested:			
City: Buffalo	TAT Requested (days): Standard			
State, Zip: NY, 14202	Compliance Project: Δ Yes Δ No			
Phone:	PO #: Purchase Order Requested			
Email: CKibler@labellapc.com	WO #:			
Project Name: Alumax & Roblin Periodic Review Reports	Project #: 48015183			
Site:	SSOW#:			

Analysis Requested

480-215658 Chain of Custody

Preservation Codes:
A - HCL, B - NaOH, C - Zn Acetate, D - Nitric Acid, E - NaHSO4, F - MeOH, G - Amchlor, H - Ascorbic Acid, I - Ice, J - DI Water, K - EDTA, L - EDA, M - Hexane, N - None, O - AsNaO2, P - Na2O4S, Q - Na2SO3, R - Na2S2O3, S - H2SO4, T - TSP Dodecahydrate, U - Acetone, V - MCAA, W - pH 4-5, Y - Trizma, Z - other (specify)
Other:

Sample Identification	Sample Date	Sample Time	Sample Type (C=comp, G=grab)	Matrix (W=water, S=solid, O=waste/oil, BT=Tissue, A=Air)	Field Filtered Sample (Yes or No)	Perform MS/MSD (Yes or No)	8260C - TCL VOCs	Total Number of Containers	Special Instructions/Note:
			Preservation Code:				A		
AL-1	12/12/23	0830	G	Water			X		
AL-7		0855		Water					
AL-2		0935		Water					
MW-09R		1015		Water					
EX-MW-11R		1045		Water					
~~MW-02R~~ MW-02R		1125		Water					
EX-MW-12		1210		Water					
MW-04		1245		Water					
MW-13		1330		Water					
MW-07R		1405		Water					
DUP		—		Water					

Possible Hazard Identification
☐ Non-Hazard ☐ Flammable ☐ Skin Irritant ☐ Poison B ☑ Unknown ☐ Radiological

Sample Disposal (A fee may be assessed if samples are retained longer than 1 month)
☐ Return To Client ☒ Disposal By Lab ☐ Archive For _____ Months

Deliverable Requested: I, II, III, IV, Other (specify)

Special Instructions/QC Requirements:

Empty Kit Relinquished by:	Date:	Time:	Method of Shipment:

	Relinquished by:	Date/Time:	Company	Received by:	Date/Time:	Company
1	[signature]	12/12/23 1530	LaBella	[signature]	12-13-23 900	TAB
2	Relinquished by:	Date/Time:	Company	Received by:	Date/Time:	Company
3	Relinquished by:	Date/Time:	Company	Received by:	Date/Time:	Company

Custody Seals Intact: Δ Yes Δ No | Custody Seal No.:

Cooler Temperature(s) °C and Other Remarks: 2.9 ICE

Ver: 06/08/2021

Eurofins Buffalo
10 Hazelwood Drive
Amherst, NY 14228-2298
Phone: 716-691-2600 Fax: 716-691-7991

Chain of Custody Record

eurofins | Environment Testing

Client Information	Sampler: A. Koons	Lab PM: Fischer, Brian J	Carrier Tracking No(s):	COC No: 480-190974-40138.2
Client Contact: Chris Kibler	Phone: 716-417-9158	E-Mail: Brian.Fischer@et.eurofinsus.com	State of Origin: NY	Page: Page 2 of 2
Company: LaBella Associates DPC	PWSID:			Job #:
Address: 300 Pearl Street Suite 130	Due Date Requested:	Analysis Requested		
City: Buffalo	TAT Requested (days): Standard			Preservation Codes: A - HCL, B - NaOH, C - Zn Acetate, D - Nitric Acid, E - NaHSO4, F - MeOH, G - Amchlor, H - Ascorbic Acid, I - Ice, J - DI Water, K - EDTA, L - EDA, M - Hexane, N - None, O - AsNaO2, P - Na2O4S, Q - Na2SO3, R - Na2S2O3, S - H2SO4, T - TSP Dodecahydrate, U - Acetone, V - MCAA, W - pH 4-5, Y - Trizma, Z - other (specify)
State, Zip: NY, 14202	Compliance Project: Δ Yes Δ No			
Phone:	PO #: Purchase Order Requested			Other:
Email: CKibler@labellapc.com	WO #:			
Project Name: Alumax & Roblin Periodic Review Reports	Project #: 48015183			
Site:	SSOW#:			

Sample Identification	Sample Date	Sample Time	Sample Type (C=Comp, G=grab)	Matrix (W=water, S=solid, O=waste/oil, BT=Tissue, A=Air)	Field Filtered Sample (Yes or No)	Perform MS/MSD (Yes or No)	8260C - TCL VOCs	Total Number of containers	Special Instructions/Note:
			Preservation Code:				A		
Trip Blank	12/12/23	~	G	Water			X		

Possible Hazard Identification
☐ Non-Hazard ☐ Flammable ☐ Skin Irritant ☐ Poison B ☒ Unknown ☐ Radiological

Sample Disposal (A fee may be assessed if samples are retained longer than 1 month)
☐ Return To Client ☒ Disposal By Lab ☐ Archive For _____ Months

Deliverable Requested: I, II, III, IV, Other (specify)

Special Instructions/QC Requirements:

Empty Kit Relinquished by:	Date:	Time:	Method of Shipment:
Relinquished by:	Date/Time: 12/12/23 1530	Company LaBella	Received by:	Date/Time: 12-13-23 900	Company TAL
Relinquished by:	Date/Time:	Company	Received by:	Date/Time:	Company
Relinquished by:	Date/Time:	Company	Received by:	Date/Time:	Company

Custody Seals Intact: Δ Yes Δ No | Custody Seal No.: | Cooler Temperature(s) °C and Other Remarks:

Ver: 06/08/2021

Login Sample Receipt Checklist

Client: LaBella Associates DPC

Job Number: 480-215658-1

Login Number: 215658

List Source: Eurofins Buffalo

List Number: 1

Creator: Stopa, Erik S

Question	Answer	Comment
Radioactivity either was not measured or, if measured, is at or below background	True	
The cooler's custody seal, if present, is intact.	True	
The cooler or samples do not appear to have been compromised or tampered with.	True	
Samples were received on ice.	True	
Cooler Temperature is acceptable.	True	
Cooler Temperature is recorded.	True	
COC is present.	True	
COC is filled out in ink and legible.	True	
COC is filled out with all pertinent information.	True	
Is the Field Sampler's name present on COC?	True	
There are no discrepancies between the sample IDs on the containers and the COC.	True	
Samples are received within Holding Time (Excluding tests with immediate HTs)..	True	
Sample containers have legible labels.	True	
Containers are not broken or leaking.	True	
Sample collection date/times are provided.	True	
Appropriate sample containers are used.	True	
Sample bottles are completely filled.	True	
Sample Preservation Verified	True	
There is sufficient vol. for all requested analyses, incl. any requested MS/MSDs	True	
VOA sample vials do not have headspace or bubble is <6mm (1/4") in diameter.	True	
If necessary, staff have been informed of any short hold time or quick TAT needs	True	
Multiphasic samples are not present.	True	
Samples do not require splitting or compositing.	True	
Sampling Company provided.	True	LABELLA
Samples received within 48 hours of sampling.	True	
Samples requiring field filtration have been filtered in the field.	N/A	
Chlorine Residual checked.	N/A	

APPENDIX 6

Historical Monitoring Well Data and Trendlines


AL-1
16,000
14,000
12,000
10,000
8,000
6,000
4,000
2,000
0
5/31/00
2/25/03
11/21/05
8/17/08
5/14/11
2/7/14
11/3/16
7/31/19
4/26/22
Total VOC Concentrations (ug/L)


AL-2
1,400
1,200
1,000
800
600
400
200
0
5/31/00
2/25/03
11/21/05
8/17/08
5/14/11
2/7/14
11/3/16
7/31/19
4/26/22
Total VOC Conentrations (ug/L)


AL-7
5,000
4,500
4,000
3,500
3,000
2,500
2,000
1,500
1,000
500
0
2/25/04
11/21/06
8/17/09
5/13/12
2/7/15
11/3/17
7/30/20
4/26/23
Total VOC Concentrations (ug/L)