



August 6, 2020

Mr. Jon Rioch
Tesla
1339 South Park Ave.
Buffalo, NY 14220

Subject: **Tesla – 1339 South Park Ave.
Vehicle Chargers – Work Scope
Lehigh Quote #2020-0449**

Dear Mr. Rioch

Pursuant to your request, we are pleased to submit our Work Scope to furnish all necessary labor, material, equipment and supervision for the above referenced project per the following scope, exclusions and/or qualifications and conditions.

Scope – Excavation for Chargers

- Excavate two trenches for the conduit.
- Trenches to be dug at 36” wide by 30” deep at approx. 425’ long.
- Excavated material will be separated between material above and below protective mesh.
- Spoils from below orange mesh to be stored separate and a plastic barrier above and below material. Backfilling under mesh will be reusing of same material.
- Material above orange mesh to be reused as topsoil.
- Re-seed topsoil.
- Saw-cutting and removal of sidewalk and driveway.
- Replace sidewalk and blacktop at conduit install.
- Clean up any construction related debris.
- Testing and removal of spoils not included in this proposal.

We trust this meets with your approval, and we look forward to answering any questions you have concerning this scope of work. Thank you for giving us the opportunity to quote.

Regards,

Jonathan C. Wilcox
Estimator / Project Manager

LEHIGH CONSTRUCTION GROUP, INC.