



<b>Lake Luzerne</b>		Town of Lake Luzerne	Warren County
 <b>Department of Environmental Conservation</b>			
	<b>Lake Characteristics</b>	Surface area (ac/ha)	96 / 39
		Max depth (ft/m)	52 / 16
		Mean depth (ft/m) (est)	24 / 7
		Retention time (years)	0.1
		Lake Classification	B
		Dam Classification	B
	<b>Watershed Characteristics</b>	Watershed area (ac /ha)	14110 / 5710
		Watershed / Lake ratio	147
		Lake & wetlands %	6.3%
		Agricultural %	0.3%
Forest, shrub, grasses %		88.9%	
Residential		4.5%	
<b>LCI Participation</b>	Years	1999-2004, 2012	
	Samplers	NYSDEC Division of Water staff (2012)	
<b>Trophic state</b>	<b>HABs Susceptibility</b>	<b>Invasive Vulnerability</b>	<b>PWL Assessment</b>
Mesoligotrophic	No reported blooms, Low susceptibility	Invasives present, High vulnerability	Threatened

Water quality values for Lake Luzerne for the 2012 sampling season. "Seasonal change" shows current year variability. Light red color indicates eutrophic conditions in top table and bloom conditions in bottom table.


Open Water Indicators	2012 Sampling Results					Seasonal change	2012 Avg
	6/6	7/12	7/18	8/6	9/13		
Clarity (m)	3.1	4.3		5.9	4.8		4.4
Surface TP (mg/l)	0.012	0.010	0.007	0.006	0.007		0.009
Surface TDP (mg/l)		0.004	0.006	0.004			0.005
Deep TP (mg/l)	0.007	0.008	0.010	0.009	0.013		0.009
Deep TDP (mg/l)							
Deep/Surface TP	1	1	1	1	2		1
TN (mg/l)	0.300	0.250	0.200	0.150	0.170		0.225
Surface N:P Ratio	25	26	29	23	25		26
Deep/Surface NH4	3	1					2
Chl.a (ug/l)	3.0	1.0	2.3	1.5			2.0
pH	7.1	8.2		7.4	8.4		7.5
Conductivity (umho/cm)	71	95		113	116		93
Total Organic Carbon (mg/l)							
True Color (ptu)	41	17	33	19	18		28
Deep Manganese (mg/l)	0.093	0.197	0.311	0.137	0.147		0.184
Deep Iron (mg/l)	0.130	0.233	0.380	0.130	0.187		0.218
Deep Arsenic (mg/l)							

### Shoreline bloom and HABs notifications


Date of first listing	Date of last listing	# weeks on the DEC notification list	# Weeks with updates
None	None	0	0

HAB Indicators	HAB criteria	6/8	7/12	7/18	8/6	9/13
BGA	25 - 30 ug/L					
microcystin	20 ug/L					
anatoxin - a						

### HABs Status Shoreline Algae




### Shoreline Toxins




### Seasonal Changes- Lake Luzerne 2012


#### Clarity




#### Chlorophyll a



#### Surface and Deep Phosphorus




#### Surface and Deep Ammonia




# Depth Profiles- Lake Luzerne 2012


Temperature




Dissolved Oxygen



pH



Specific Conductance (Conductivity)



## Scorecard

Lake Use			
	PWL	2012	Primary issue
Potable Water	□	□	Not applicable
Swimming	●	●	No impacts
Recreation	▲	●	No impacts
Aquatic Life	□	●	No impacts
Aesthetics	□	▲	Invasive plants
Habitat	□	▲	Invasive plants
Fish Consumption	□	□	Not applicable

Legend:

- Supported / Good
- ▲ Threatened / Fair
- ◆ Stressed / Poor
- Impaired
- Not Known

## **LCI sampling summary- Lake Luzerne 2012**

### **What is the condition of the lake?:**

NYSDEC conducted routine (monthly) sampling of Lake Luzerne as part of the Lake Classification and Inventory Survey of the Upper Hudson River basin. Lake Luzerne can be characterized as mesoligotrophic, or moderately unproductive, based on moderate water clarity, moderate algae levels (chlorophyll a), and low nutrient (phosphorus) levels. The lake has near neutral pH, soft water, moderately low water color, and low nitrogen levels.

### **Do conditions change over the summer?:**

Significant seasonal increases were measured in plant coverage and water clarity. Small seasonal increases were measured in pH and chlorophyll a. No seasonal changes were measured in deep phosphorus, specific conductance, and total phosphorus.

### **Do conditions change from surface to bottom?:**

Deepwater phosphorus levels were similar to those measured at the lake surface. Ammonia readings were similar to surface readings. The hypolimnion is at times devoid of oxygen during at least part of the summer, but the impact to water quality is probably low.

### **How do these conditions compare to nearby lakes?:**

Compared to other nearby lakes, Lake Luzerne usually has higher water clarity, conductivity, calcium levels, and chloride levels, similar pH, and lower chlorophyll a and phosphorus readings.

### **Have these conditions changed over time?**

Since 1999 (CSLAP sampling was conducted from 1999 to 2004), pH has decreased significantly. Color readings have increased slightly.

### **Were any algal blooms or HABS observed or reported?:**

Water quality conditions indicate a moderate susceptibility to blooms, with no reported blooms along the shoreline or in the open water.

### **Are there any aquatic invasive species on the lake?:**

There is at least one invasive plant species reported or present at Lake Luzerne, and no invasives have been reported in nearby waterbodies. Invasive species reported in the lake include Eurasian watermilfoil and curly leafed pondweed. No invasive animals have been reported in Lake Luzerne. Lake Luzerne has high vulnerability for new invasives, based on the presence of aquatic invasives.

### **Were there any other observations?:**

Native aquatic plants observed in the lake included coontail and large leaf pondweed. Other plant surveys conducted as part of the aquatic herbicide treatments (by DFWI) found many other native plants.

### **Are any designated uses likely impacted by these conditions?:**

Lake Luzerne supports recreation and public bathing use. This waterbody is not designated for use as a public water supply. Public bathing, recreation, and aquatic life appear to be fully supported. Aesthetics and habitat are fair due to presence of invasive aquatic plants. Fish Consumption use is considered to be unassessed. There are no health advisories limiting the

consumption of fish from this waterbody (beyond the general advice for all waters). However due to the presence of impacts in the lake and the uncertainty as to whether the lack of a waterbody-specific health advisory is based on actual sampling, fish consumption use is noted as unassessed, rather than fully supported but unconfirmed.

**What actions, if any, are appropriate for consideration?:**

The apparent change in some water quality indicators in recent years suggests that new or additional watershed management actions should be considered. A buffer of native plants next to the lakeshore may help reduce nutrient and sediment loading to the lake. In the rest of the watershed outside the control of the municipality, stewardship activities such as pumping septic systems, reducing fertilization, shoreline erosion and channelized stormwater runoff, and other best management practices can also help to maintain or improve water quality. More information about in-lake algae control measures and watershed nutrient control measures to improve lake condition can be found in Diet for a Small Lake (<https://www.dec.ny.gov/chemical/82123.html>).

## How to Read the Report

In order to make this lake report as easy to digest as possible for the typical reader, only the most critical information collected in the LCI is presented. We hope that presenting the data in a more succinct manner will draw in more readers and hold their attention. Unfortunately, this new format leaves little room for definitions of terms, so we are including this section primarily as a glossary of terms for which the typical reader may not know the definition.

The report begins with the lake name, town, and county. The next section contains some physical characteristics of the lake. The surface area is the two dimensional area of the lakes surface and is given in units of acres and hectares. The max depth is the water depth measured at the deepest part of the lake and is given in units of feet and meters. The mean depth is either known from a rigorous study of the bathymetry of the lake or is calculated as 0.46 times the maximum depth and is given in units of feet and meters. The retention time is the time it takes for a drop of water to pass through a lake, given in units of years. The lake classification is a letter defining the “best uses” for this particular lake, based on the legal classification assigned by New York state. Class AA, AAspec and A lakes may be used as sources of potable water. Class B lakes are suitable for contact recreational activities, like swimming. Class C lakes are suitable for non-contact recreational activities, including fishing, although they may still support swimming. The addition of a T or TS to any of these classes indicates the ability of a lake to support trout populations and/or trout spawning. The dam classification is a letter defining the hazard class of a dam if one exists. Class A, B, C, and D dams are defined as low, intermediate, high, or negligible/no hazard dams in that order. A “0” or blank indicates that no class has been assigned to a particular dam, or that no dam exists.

The next section contains some watershed characteristics including the watershed area in acres and hectares and the land use composition of the watershed. A watershed is the entire area that will drain to a particular lake and is constrained by the topology and hydrology of the land. The watershed area was calculated by the US Geological Survey “StreamStats” program. This area map was then used to calculate land uses from the most recent (2011) National Land Use Cover data on the NYSDEC ArcGIS mapping program. The map itself is shown on the left side of the front page. In general, blue colors show water, green and light brown show forested or shrub land, yellow and dark brown are agriculture, and pink to red is developed land. The program participation section lists the years the lake has been sampled

through LCI over a two year period, and the names of the DEC samplers conducting the work.

The next section includes four boxes. The trophic state of a lake refers to its nutrient loading and productivity- in other words, how much algae is produced, and the cause (nutrients) and outcome (changes in clarity) of this algae growth. An oligotrophic lake has low nutrient and algae levels (low productivity) and high clarity while a eutrophic lake has high nutrient and algae levels (high productivity) and low clarity. Mesotrophic lakes fall somewhere in the middle. For most lakes, the nutrient of concern is phosphorus. A more productive lake will support more plant life, which may be good for warmwater fish, but may lower the quality of the lake if growth becomes excessive.

The harmful algal bloom susceptibility section contains a summary of the available historical HAB data. Although the factors that lead to the formation of HAB's is not yet well-understood, a history of HAB occurrences and high nutrient levels may indicate a susceptibility in the lake that could result in more HAB events in the future.

The invasive vulnerability section indicates if aquatic invasive species (AIS) are found in this lake or in nearby lakes. Invasive species are non-native and tend to rapidly colonize a waterbody once introduced, leaving little space for native species. Lakes with invasives or near other lakes with invasives are vulnerable to introductions of new AIS.

The next section is the priority waterbody list (PWL) assessment section. The PWL is a statewide inventory of the waters of New York State that DEC uses to track support (or impairment) of water uses, overall assessment water quality, causes and sources of water quality impact/impairment, and the status of restoration, protection and other water quality activities and efforts. A PWL assessment is broken into categories that include the following: potable water, swimming or public bathing, recreation, aquatic life, aesthetics, habitat, and fish consumption. All of the categories except aesthetics and habitat are accessed on a scale to determine if each of the listed uses are supported. The scale goes from best to worst in the following progression: fully supported, threatened, stressed, impaired, and precluded. Aesthetics and habitat are evaluated as good, fair, or poor. The cited PWL assessment reflects the "worst" assessment for the lake. The full PWL assessment for each lake can (or will eventually) be found on the DEC website by searching on "PWL" and the lake basin, at <http://www.dec.ny.gov/chemical/36730.html#WIPWL>.

The rest of the report contains a collection of tables and charts. A glossary of all the water quality and HABs indicators used in the plots and tables is included below. Of particular note are the seasonal change and average for the sampling season. There is also a seasonal change sparkline chart, which only shows the last year of summer trends. The average column summarizes the average of the last year of sampling results, with all samples weighted equally in the reported average. Data shown in these plots represent 0-2 meter depth integrated surface samples and grab samples collected one meter from the bottom in the deepest section of thermally stratified lakes.

The next table contains a summary of shoreline (and open water if appropriate) HABs data for the lake, along with the associated HAB notification information. If a HAB is suspected, a sample from the worst part of the bloom (usually along the shoreline) is collected and sent in for laboratory confirmation. A HAB notification is added to the HAB database where entries

are updated on a weekly basis. Additional information- samples or visual reports- are used to update these listings. The HABs Status plots show the algal component (total algae and fractions associated with cyanobacteria (blue green algae), green algae, diatoms, and other algae, as measured by chlorophyll *a*, in any collected samples, and the associated levels of total microcystin. The shoreline toxin data graphs include the World Health Organization (WHO) high risk criteria to protect swimmers and the EPA low risk criteria to protect those using *treated* (not raw lake) drinking water.

The next section of the report shows seasonal changes in water clarity, (extracted) chlorophyll *a*, surface and deep phosphorus (if deep samples are collected) and surface and deep ammonia levels. Surface samples are indicated with round markers, while deep samples are shown as triangular markers. If multiple years of samples were collected, results from all samples are shown, with previous years data shown in red.

The depth profile section shows the water temperatures, dissolved oxygen, and some combination of pH, conductivity, or oxygen reduction potential (ORP), the latter an indication of the likelihood (present or recent) of oxygen deficits. These field depth profile measurements are not as accurate as laboratory measurements, and in some cases may indicate some measurement or calibration errors. This report identifies when these measurement may be less accurate or not representative of conditions at that time.

The next section of the report includes Lake Use Scorecard. The scorecard presents the results of the existing Priority Waterbody List assessment for this lake in a graphical form and compares it to information from the current year from LCI data and other lake information. The scorecard also includes a column that lists some primary issues that could impact specific use categories. Multiple issues could affect each designated use, but only the primary issue is listed.

The final section of the report is the Lake Summary. This includes a brief summary of the most recent LCI data for the lake, although there is some comparison to previously LCI data when available. It is essentially the same as the Q&A section of reports generated through the NY Citizens Statewide Lake Assessment Program (CSLAP), and with the Lake Use Scorecard, represents perhaps the most easily understood single page summary of the LCI data for the lake. This was intentionally created as the last page of the report to allow easy copying and distribution to interested parties.

## Glossary of water quality and HAB indicators

**Clarity:** The depth to which a Secchi disk lowered into the water is visible, measured in meters. Water clarity is one of the trophic indicators for each lake.

**TP:** Total phosphorus, measured in milligrams per liter at the lake surface (1.5 meters below the surface). TP includes all dissolved and particulate forms of phosphorus. Total phosphorus is a second trophic indicator for each lake.

**Soluble P:** Dissolved phosphorus, measured in milligrams per liter at the lake surface, measured in water that passes through a 0.45 micron filter. It is an estimate of the amount of phosphorus available for biological uptake or growth, although available phosphorus is more accurately measured by soluble reactive P.

**Deep TP:** Total phosphorus measured in milligrams per liter at depth (1-2 meters above the lake bottom at the deepest part of the lake)

**Deep Soluble P:** Dissolved phosphorus measured at depth, measured in milligrams per liter

**TN:** Total nitrogen, measured in milligrams per liter at the lake surface. TN includes all forms of nitrogen, including **NO<sub>x</sub>** (nitrite and nitrate) and **NH<sub>4</sub>** (ammonia).

**Surface N:P Ratio:** The ratio of total nitrogen to total phosphorus, unitless (mass ratio), in surface samples analyzed for TP and TN. This ratio helps determine if a lake is phosphorus or nitrogen limited.

**Deep to Surface NH<sub>4</sub> Ratio:** The ratio of ammonia measured in deep and surface samples; this is a surrogate for lake anoxia when these ratios are > 10

**Chl.a (ug/l):** Chlorophyll a, measured in micrograms per liter as chlorophyll extracted from surface water samples using reagents and a desktop fluorometer

**pH:** A range from 0 to 14, with 0 being the most acidic and 14 being the most basic or alkaline. A healthy lake generally ranges between 6 and 9.

**Conductivity:** Specific conductance is a measure of the conductivity of water, measured as micromhos per centimeter and corrected to 25 degrees centigrade. A higher value indicates the presence of more dissolved ions that help conduct electricity. Conductivity results may indicate hard or softwater conditions with high ion concentrations resulting in hardwater.

**Total (or Dissolved) Organic Carbon:** Organic carbon measures the carbon (total or dissolved) in living material within the water, measured in milligrams per liter.

**True Color** is a visual measure of the brownness of the water, based on water passing through a 0.45 micron filter and compared to a visual series of standards developed from a platinum-cobalt standard (and thus measured as platinum units)



**Deep Manganese, Iron or Arsenic** measure total manganese, iron or arsenic levels in milligrams per liter in samples collected near the lake bottom. Elevated levels indicate anoxic conditions.

**BG Chl.a (ug/L):** Chlorophyll a from blue-green algae, measured in micrograms per liter. Readings above 25 ug/L are indicative of bloom conditions.

**HABs Reported?:** Were any algal blooms reported within a week of the dates listed, and, if so, were they located along the shoreline, in open water, or both?

**BGA:** Blue-green algae, as measured with a desktop or field fluorometer and reported as micrograms per liter of unextracted chlorophyll a

**Microcystin:** The most common HAB liver toxin; total microcystin above 20 micrograms per liter indicates a “high toxin” bloom. However, ALL BGA blooms should be avoided, even if toxin levels are low.

**Anatoxin-a:** Another type of toxin that may be produced in a HAB and may be more dangerous as it targets the central nervous system. Neither EPA nor NYS has developed a risk threshold for anatoxin-a, although readings above 4 micrograms per liter are believed to represent an elevated risk.