














Kibbie Lake		Town of Constantia	Oswego County
		Lake Characteristics	
		Surface area (ac/ha)	19 / 8
		Max depth (ft/m)	19 / 6
Lake Characteristics		Mean depth (ft/m)	9 / 3
Lake Characteristics		Retention time (years)	2.6
Lake Characteristics		Lake Classification	B
Lake Characteristics		Dam Classification	
Watershed Characteristics		Watershed area (ac /ha)	35 / 14
Watershed Characteristics		Watershed / Lake ratio	2
Watershed Characteristics		Lake & wetlands %	62.3%
Watershed Characteristics		Agricultural %	0.0%
Watershed Characteristics		Forest, shrub, grasses %	37.7%
Watershed Characteristics		Residential	0.0%
Watershed Characteristics		Urban	0.0%
LCI Participation		Years	2016-2017
LCI Participation		Samplers	David Newman, Sara Gonzalez, Dan Hayes
Trophic state	HABs Susceptibility	Invasive Vulnerability	PWL Assessment
Eutrophic	No reported blooms, Some susceptibility	No invasives present, Some vulnerability	Unassessed

Water quality values for Kibbie Lake for the 2017 sampling season. "Seasonal change" shows current year variability. Light red color indicates eutrophic conditions in top table and bloom conditions in bottom table.


Open Water Indicators	2016	2017 Sampling Results				Seasonal change	2017 Avg
	7/27	6/27	7/25	8/24	9/19		
Clarity (m)	1.3	0.9	0.9	1.0	1.2		1.1
TP (mg/l)	0.026	0.035	0.017	0.042	0.016		0.027
Soluble P (mg/l)	0.013	0.007	0.011	0.011	0.007		0.010
Deep TP (mg/l)	0.042	0.050	0.037	0.047	0.029		0.041
Deep Soluble P (mg/l)	0.012	0.011	0.009	0.008	0.007		0.009
TN (mg/l)	0.640	0.690	0.950	0.680	0.860		2.647
Surface N:P Ratio	25	20	56	16	55		98
Deep to Surface NH4 Ratio	1.0		869.2				869.2
Chl.a (ug/l)	24.1	64.6	24.9	37.2	23.5		34.9
pH	5.1	7.5	4.8	4.9	5.0		5.4
Conductivity (umho/cm)	9	10	11	13	11		11
Total Organic Carbon (mg/l)							
True Color (ptu)	45	50	45	49	48		47
Deep Manganese (mg/l)							
Deep Iron (mg/l)							
Deep Arsenic (mg/l)							

Shoreline bloom and HABs notifications


Date of first listing	Date of last listing	# weeks on the DEC notification list	# Weeks with updates
None	None	None	None

HAB Indicators	HAB criteria	6/27	7/25	8/24	9/19
BGA	25 - 30 ug/L				
microcystin	20 ug/L				
anatoxin - a					

HABs Status Shoreline Algae




Shoreline Toxins




Seasonal Changes- Kibbie Lake 2017


Clarity




Chlorophyll a



Surface and Deep Phosphorus




Surface and Deep Ammonia




Depth Profiles- Kibbie Lake 2017


Temperature




Dissolved Oxygen



Chlorophyll (corrected)



Phycocyanin



Scorecard

	Lake Use			
	PWL	2017	Primary issue	
Potable Water	□	□	No impacts	
Swimming	□	■	Algae levels	● Supported / Good
Recreation	□	■	Algae levels	▲ Threatened / Fair
Aquatic Life	□	◆	Low pH	◆ Stressed / Poor
Aesthetics	□	◆	Excessive Nutrients	■ Impaired
Habitat	□	●	No impacts	□ Not Known
Fish Consumption	□	□	Not applicable	

LCI sampling summary- Kibby Lake 2017

What is the condition of the lake?: NYSDEC conducted routine (monthly) sampling of Kibby Lake (aka Kibbie Lake) as part of the DEC Lake Classification and Inventory (LCI) survey of the Seneca River / Oneida River / Oswego River drainage basin. Kibby Lake can be characterized as a *eutrophic* lake, based on slightly elevated nutrient (phosphorus) levels, highly elevated algae (chlorophyll *a*) levels, and low water clarity (Secchi disk transparency). The lake has acidic, very soft water, with low to intermediate nitrogen (mostly organic) levels, and moderate to high water color (brownness).

Do conditions change over the summer?: Lake productivity varies slightly during the summer- nutrient and algae levels do not exhibit any clear seasonal patterns, although water clarity increases slightly from June through September. pH and conductivity vary slightly during the summer.

Do conditions change from surface to bottom?: Kibby Lake is strongly (thermally) stratified, with the thermocline separating the warmer upper waters and colder lower waters at a depth of about 3 meters. These depth profiles show a significant reduction in deepwater oxygen levels, with oxygen bottoming out in the hypolimnion, below a depth of about 3-4 meters. As a result, although deepwater phosphorus levels are similar to those measured at the lake surface, deep nitrogen levels are higher. This is also consistent with a strong hydrogen sulfide odor in the deep samples.

How do these conditions compare to nearby lakes?: Kibby Lake has lower productivity- lower nutrient and algae levels, but similar water clarity- than many other lakes in the Seneca River / Oneida River / Oswego River region. Lake pH and hardness is much lower than in these other lakes.

Have these conditions changed over time? Kibby Lake was not previously sampled by the NYSDEC, so these 2017 results cannot provide information about water quality trends.

Were any algal blooms or HABS observed or reported?: Water quality conditions indicated a low susceptibility to blooms, and no cyanobacteria (blue green algae) blooms were observed along the shoreline in 2017.

Are there any aquatic invasive species on the lake?: No aquatic invasive species have been documented in Kibby Lake, although many AIS have been found in nearby lakes. This suggests that the lake may be susceptible to introduction of some AIS, although water quality conditions may not support Eurasian watermilfoil and some AIS. Calcium levels are probably not high enough to support zebra mussels, and these invasive mussels have not been reported in the lake.

Were there any other observations?: Water lilies and watershield were observed in Kibby Lake, typical of softwater lakes. It is likely that other native plants are present but were not documented in the lake during these water quality surveys.

Are any designated uses likely impacted by these conditions?: Kibby Lake provides some recreational uses, with access through Camp Woodland associated with the Boy Scouts of America Longhouse Council. Algae levels at times are high enough, and water clarity is low

enough, to impair the use of the lake for recreation and swimming (and algae might also affect lake aesthetics). Aquatic life may be stressed by depressed pH and deepwater oxygen.

What actions, if any, are appropriate for consideration?: It is not known to what extent the lake is managed by the Boy Scouts of America. A buffer of native plants next to the lakeshore may help reduce nutrient and sediment loading to the lake. In the rest of the watershed outside the control of the municipality, stewardship activities such as pumping septic systems, reducing fertilization, shoreline erosion and channelized stormwater runoff, and other best management practices can also help to maintain or improve water quality. More information about in-lake algae control measures and watershed nutrient control measures to improve lake condition can be found in Diet for a Small Lake (<https://www.dec.ny.gov/chemical/82123.html>).

How to Read the Report

In order to make this lake report as easy to digest as possible for the typical reader, only the most critical information collected in the LCI is presented. We hope that presenting the data in a more succinct manner will draw in more readers and hold their attention. Unfortunately, this new format leaves little room for definitions of terms, so we are including this section primarily as a glossary of terms for which the typical reader may not know the definition.

The report begins with the lake name, town, and county. The next section contains some physical characteristics of the lake. The surface area is the two dimensional area of the lakes surface and is given in units of acres and hectares. The max depth is the water depth measured at the deepest part of the lake and is given in units of feet and meters. The mean depth is either known from a rigorous study of the bathymetry of the lake or is calculated as 0.46 times the maximum depth and is given in units of feet and meters. The retention time is the time it takes for a drop of water to pass through a lake, given in units of years. The lake classification is a letter defining the “best uses” for this particular lake, based on the legal classification assigned by New York state. Class AA, AAspec and A lakes may be used as sources of potable water. Class B lakes are suitable for contact recreational activities, like swimming. Class C lakes are suitable for non-contact recreational activities, including fishing, although they may still support swimming. The addition of a T or TS to any of these classes indicates the ability of a lake to support trout populations and/or trout spawning. The dam classification is a letter defining the hazard class of a dam if one exists. Class A, B, C, and D dams are defined as low, intermediate, high, or negligible/no hazard dams in that order. A “0” or blank indicates that no class has been assigned to a particular dam, or that no dam exists.

The next section contains some watershed characteristics including the watershed area in acres and hectares and the land use composition of the watershed. A watershed is the entire area that will drain to a particular lake and is constrained by the topology and hydrology of the land. The watershed area was calculated by the US Geological Survey “StreamStats” program. This area map was then used to calculate land uses from the most recent (2011) National Land Use Cover data on the NYSDEC ArcGIS mapping program. The map itself is shown on the left side of the front page. In general, blue colors show water, green and light brown show forested or shrub land, yellow and dark brown are agriculture, and pink to red is developed land. The program participation section lists the years the lake has been sampled through LCI over a two year period, and the names of the DEC samplers conducting the work.

The next section includes four boxes. The trophic state of a lake refers to its nutrient loading and productivity- in other words, how much algae is produced, and the cause (nutrients) and outcome (changes in clarity) of this algae growth. An oligotrophic lake has low nutrient and algae levels (low productivity) and high clarity while a eutrophic lake has high nutrient and algae levels (high productivity) and low clarity. Mesotrophic lakes fall somewhere in the middle. For most lakes, the nutrient of concern is phosphorus. A more productive lake will support more plant life, which may be good for warmwater fish, but may lower the quality of the lake if growth becomes excessive.

The harmful algal bloom susceptibility section contains a summary of the available historical HAB data. Although the factors that lead to the formation of HAB's is not yet well-understood, a history of HAB occurrences and high nutrient levels may indicate a susceptibility in the lake that could result in more HAB events in the future.

The invasive vulnerability section indicates if aquatic invasive species (AIS) are found in this lake or in nearby lakes. Invasive species are non-native and tend to rapidly colonize a waterbody once introduced, leaving little space for native species. Lakes with invasives or near other lakes with invasives are vulnerable to introductions of new AIS.

The next section is the priority waterbody list (PWL) assessment section. The PWL is a statewide inventory of the waters of New York State that DEC uses to track support (or impairment) of water uses, overall assessment water quality, causes and sources of water quality impact/impairment, and the status of restoration, protection and other water quality activities and efforts. A PWL assessment is broken into categories that include the following: potable water, swimming or public bathing, recreation, aquatic life, aesthetics, habitat, and fish consumption. All of the categories except aesthetics and habitat are assessed on a scale to determine if each of the listed uses are supported. The scale goes from best to worst in the following progression: fully supported, threatened, stressed, impaired, and precluded. Aesthetics and habitat are evaluated as good, fair, or poor. The cited PWL assessment reflects the "worst" assessment for the lake. The full PWL assessment for each lake can (or will eventually) be found on the DEC website by searching on "PWL" and the lake basin, at <http://www.dec.ny.gov/chemical/36730.html#WIPWL>.

The rest of the report contains a collection of tables and charts. A glossary of all the water quality and HABs indicators used in the plots and tables is included below. Of particular note are the seasonal change and average for the sampling season. There is also a seasonal change sparkline chart, which only shows the last year of summer trends. The average column summarizes the average of the last year of sampling results, with all samples weighted equally in the reported average. Data shown in these plots represent 0-2 meter depth integrated surface samples and grab samples collected one meter from the bottom in the deepest section of thermally stratified lakes.

The next table contains a summary of shoreline (and open water if appropriate) HABs data for the lake, along with the associated HAB notification information. If a HAB is suspected, a sample from the worst part of the bloom (usually along the shoreline) is collected and sent in for laboratory confirmation. A HAB notification is added to the HAB database where entries are updated on a weekly basis. Additional information- samples or visual reports- are used to update these listings. The HABs Status plots show the algal component (total algae and fractions associated with cyanobacteria (blue green algae), green algae, diatoms, and other

algae, as measured by chlorophyll *a*, in any collected samples, and the associated levels of total microcystin. The shoreline toxin data graphs include the World Health Organization (WHO) high risk criteria to protect swimmers and the EPA low risk criteria to protect those using *treated* (not raw lake) drinking water.

The next section of the report shows seasonal changes in water clarity, (extracted) chlorophyll *a*, surface and deep phosphorus (if deep samples are collected) and surface and deep ammonia levels. Surface samples are indicated with round markers, while deep samples are shown as triangular markers. If multiple years of samples were collected, results from all samples are shown, with previous years data shown in red.

The depth profile section shows the water temperatures, dissolved oxygen, chlorophyll, and phycocyanin (a measure of blue green pigments) as measured on a profiling electronic meter. Chlorophyll measures are “corrected” to reflect the expected extracted chlorophyll measurement based on the relationship between the surface integrated chlorophyll (extracted) data and the profiler unextracted data. As such, these results should be considered estimated relative values, and should not be compared to water quality criteria developed from extracted measurements only. Phycocyanin data are reported in relative units, although they are characterized as cells per mL.

The next section of the report includes Lake Use Scorecard. The scorecard presents the results of the existing Priority Waterbody List assessment for this lake in a graphical form and compares it to information from the current year from LCI data and other lake information. The scorecard also includes a column that lists some primary issues that could impact specific use categories. Multiple issues could affect each designated use, but only the primary issue is listed.

The final section of the report is the Lake Summary. This includes a brief summary of the most recent LCI data for the lake, although there is some comparison to previously LCI data when available. It is essentially the same as the Q&A section of reports generated through the NY Citizens Statewide Lake Assessment Program (CSLAP), and with the Lake Use Scorecard, represents perhaps the most easily understood single page summary of the LCI data for the lake. This was intentionally created as the last page of the report to allow easy copying and distribution to interested parties.

Glossary of water quality and HAB indicators

Clarity: The depth to which a Secchi disk lowered into the water is visible, measured in meters. Water clarity is one of the trophic indicators for each lake.

TP: Total phosphorus, measured in milligrams per liter at the lake surface (1.5 meters below the surface). TP includes all dissolved and particulate forms of phosphorus. Total phosphorus is a second trophic indicator for each lake.

Soluble P: Dissolved phosphorus, measured in milligrams per liter at the lake surface, measured in water that passes through a 0.45 micron filter. It is an estimate of the amount of phosphorus available for biological uptake or growth, although available phosphorus is more accurately measured by soluble reactive P.

Deep TP: Total phosphorus measured in milligrams per liter at depth (1-2 meters above the lake bottom at the deepest part of the lake)

Deep Soluble P: Dissolved phosphorus measured at depth, measured in milligrams per liter

TN: Total nitrogen, measured in milligrams per liter at the lake surface. TN includes all forms of nitrogen, including **NO_x** (nitrite and nitrate) and **NH₄** (ammonia).

Surface N:P Ratio: The ratio of total nitrogen to total phosphorus, unitless (mass ratio), in surface samples analyzed for TP and TN. This ratio helps determine if a lake is phosphorus or nitrogen limited.

Deep to Surface NH₄ Ratio: The ratio of ammonia measured in deep and surface samples; this is a surrogate for lake anoxia when these ratios are > 10

Chl.a (ug/l): Chlorophyll a, measured in micrograms per liter as chlorophyll extracted from surface water samples using reagents and a desktop fluorometer

pH: A range from 0 to 14, with 0 being the most acidic and 14 being the most basic or alkaline. A healthy lake generally ranges between 6 and 9.

Conductivity: Specific conductance is a measure of the conductivity of water, measured as micromhos per centimeter and corrected to 25 degrees centigrade. A higher value indicates the presence of more dissolved ions that help conduct electricity. Conductivity results may indicate hard or softwater conditions with high ion concentrations resulting in hardwater.

Total (or Dissolved) Organic Carbon: Organic carbon measures the carbon (total or dissolved) in living material within the water, measured in milligrams per liter.

True Color is a visual measure of the brownness of the water, based on water passing through a 0.45 micron filter and compared to a visual series of standards developed from a platinum-cobalt standard (and thus measured as platinum units)

Deep Manganese, Iron or Arsenic measure total manganese, iron or arsenic levels in milligrams per liter in samples collected near the lake bottom. Elevated levels indicate anoxic conditions.

BG Chl.a (ug/L): Chlorophyll a from blue-green algae, measured in micrograms per liter. Readings above 25 ug/L are indicative of bloom conditions.

HABs Reported?: Were any algal blooms reported within a week of the dates listed, and, if so, were they located along the shoreline, in open water, or both?

BGA: Blue-green algae, as measured with a desktop or field fluorometer and reported as micrograms per liter of unextracted chlorophyll a

Microcystin: The most common HAB liver toxin; total microcystin above 20 micrograms per liter indicates a “high toxin” bloom. However, ALL BGA blooms should be avoided, even if toxin levels are low.

Anatoxin-a: Another type of toxin that may be produced in a HAB and may be more dangerous as it targets the central nervous system. Neither EPA nor NYS has developed a risk threshold for anatoxin-a, although readings above 4 micrograms per liter are believed to represent an elevated risk.