



|   |                                  |   |                  |  |
|---|----------------------------------|---|------------------|--|
| <b>Stewarts Bridge Reservoir</b>  |                                  | Town of Hadley  | Saratoga County  |  |
|  <b>Department of Environmental Conservation</b> |                                  |   |                  |  |
|    | <b>Lake Characteristics</b>      | Surface area (ac/ha)  | 889 / 324        |  |
|   |                                  | Max depth (ft/m)  | 78 / 24          |  |
|   |                                  | Mean depth (ft/m)   | 36 / 11          |  |
|   |                                  | Retention time (years)  | <0.1             |  |
|   |                                  | Lake Classification   | C                |  |
|   |                                  | Dam Classification  | C                |  |
|   | <b>Watershed Characteristics</b> | Watershed area (ac /ha)   | 6721347 / 271998 |  |
|   |                                  | Watershed / Lake ratio  | 839              |  |
|   |                                  | Lake & wetlands %   | 11.7%            |  |
|   |                                  | Agricultural %  | 1.1%             |  |
| Forest, shrub, grasses %  |                                  | 84.8%   |                  |  |
| Residential   |                                  | 2.0%  |                  |  |
| <b>LCI Participation</b>  | Years                            | 2017  |                  |  |
|   | Samplers                         | David Newman, Sara Gonzalez, Courtney King, Dan Woltmann, Scott Kishbaugh, Andy Luce, Erik Posner |                  |  |

|                      |  |                                       |                       |
|----------------------|--|---------------------------------------|-----------------------|
| <b>Trophic state</b> | <b>HABs Susceptibility</b>             | <b>Invasive Vulnerability</b>         | <b>PWL Assessment</b> |
| Mesoligotrophic      | No reported blooms, Low susceptibility | Invasives present, High Vulnerability | Stressed              |

Water quality values for Stewarts Bridge Reservoir for the 2017 sampling season. “Seasonal change” shows current year variability. Light red color indicates eutrophic conditions in top table and bloom conditions in bottom table.


| Open Water Indicators       | 2016 | 2017 Sampling Results |       |       |       | Seasonal change | 2017 Avg |
|-----------------------------|------|-----------------------|-------|-------|-------|-----------------|----------|
|                             |      | 6/27                  | 7/19  | 8/16  | 9/28  |                 |          |
| Clarity (m)                 |      |                       | 2.2   | 2.1   | 2.1   |                 | 2.1      |
| TP (mg/l)                   |      | 0.011                 | 0.009 | 0.011 | 0.007 |                 | 0.009    |
| Soluble P (mg/l)            |      | 0.009                 | 0.005 |       | 0.010 |                 | 0.008    |
| Deep TP (mg/l)              |      | 0.006                 | 0.006 | 0.007 | 0.005 |                 | 0.006    |
| Deep Soluble P (mg/l)       |      | 0.006                 | 0.006 |       | 0.009 |                 | 0.007    |
| TN (mg/l)                   |      | 0.290                 | 0.320 | 0.550 | 0.510 |                 | 2.709    |
| Surface N:P Ratio           |      | 27                    | 37    | 50    | 73    |                 | 289      |
| Deep to Surface NH4 Ratio   |      | 3.5                   | 1.8   |       | 1.6   |                 | 2.3      |
| Chl.a (ug/l)                |      | 4.5                   | 5.9   | 4.2   | 5.5   |                 | 5.0      |
| pH                          |      | 7.2                   | 6.7   | 6.4   | 7.0   |                 | 6.8      |
| Conductivity (umho/cm)      |      | 48                    | 49    | 51    | 55    |                 | 51       |
| Total Organic Carbon (mg/l) |      |                       |       |       |       |                 |          |
| True Color (ptu)            |      | 21                    | 28    | 27    | 20    |                 | 24       |
| Deep Manganese (mg/l)       |      |                       |       |       |       |                 |          |
| Deep Iron (mg/l)            |      |                       |       |       |       |                 |          |
| Deep Arsenic (mg/l)         |      |                       |       |       |       |                 |          |

### Shoreline bloom and HABs notifications


| Date of first listing | Date of last listing | # weeks on the DEC notification list | # Weeks with updates |
|-----------------------|----------------------|--------------------------------------|----------------------|
| None                  | None                 | None                                 | None                 |

| HAB Indicators | HAB criteria | 6/27 | 7/19 | 8/16 | 9/28 |
|----------------|--------------|------|------|------|------|
| BGA            | 25 - 30 ug/L |      |      |      |      |
| microcystin    | 20 ug/L      |      |      |      |      |
| anatoxin - a   |              |      |      |      |      |

### HABs Status Shoreline Algae




### Shoreline Toxins




### Seasonal Changes- Stewarts Bridge Reservoir 2017


#### Clarity




#### Chlorophyll a



#### Surface and Deep Phosphorus




#### Surface and Deep Ammonia




# Depth Profiles- Stewarts Bridge Reservoir 2017


## Temperature




## Dissolved Oxygen



## Chlorophyll (corrected)



## Phycocyanin



## Scorecard

| Lake Use         |     |      |                 |
|------------------|-----|------|-----------------|
|                  | PWL | 2017 | Primary issue   |
| Potable Water    | □   | □    | No impacts      |
| Swimming         | □   | ●    | No impacts      |
| Recreation       | □   | ●    | No impacts      |
| Aquatic Life     | ◆   | ▲    | Bottom Oxygen   |
| Aesthetics       | □   | ▲    | Invasive plants |
| Habitat          | ◆   | ▲    | Invasive plants |
| Fish Consumption | □   | □    | Not applicable  |

● Supported / Good  
▲ Threatened / Fair  
◆ Stressed / Poor  
■ Impaired  
 Not Known

## LCI sampling summary- Stewarts Bridge Reservoir 2017

**What is the condition of the lake?:** NYSDEC conducted routine (monthly) sampling of Stewarts Bridge Reservoir as part of the DEC Lake Classification and Inventory (LCI) survey of the Upper Hudson River drainage basin. Stewarts Bridge Reservoir can be characterized as a *mesoligotrophic* reservoir, based on low nutrient (phosphorus), intermediate algae (chlorophyll *a*) levels, and intermediate water clarity (Secchi disk transparency) readings. Algae levels are slightly higher than expected given the nutrient levels in the reservoir, suggesting that any additional nutrient loading to the reservoir would further increase algae levels. Stewarts Bridge Reservoir is circumneutral (near neutral pH) with soft water, low nitrogen (mostly organic) levels, and low to intermediate water color (brownness).

**Do conditions change over the summer?:** Reservoir productivity is fairly stable over the course of a typical summer; no clear seasonal trends are apparent in water clarity, nutrient, or algae levels. Conductivity increases slightly from June through September, but all readings were typical of softwater lakes.

**Do conditions change from surface to bottom?:** Stewarts Bridge Reservoir is strongly (thermally) stratified, with the thermocline separating the warmer upper waters and colder lower waters at a depth of about 10-12 meters. These depth profiles show a slight reduction in deepwater oxygen levels, with oxygen decreasing toward the Reservoir bottom, below a depth of about 10 meters. However, anoxic (no oxygen) conditions were not measured. As a result of some oxygenation in deeper waters, deepwater phosphorus and nitrogen levels are similar to those measured at the surface. However, the bottom of the deepest part of the Reservoir was not sampled due to the inability of the sampling gear to access water as deep as found in the Reservoir.

**How do these conditions compare to nearby lakes?:** Stewarts Bridge Reservoir has lower productivity- lower nutrient and algae levels, though similar to slightly lower water clarity- than many other lakes in the Upper Hudson River region.

**Have these conditions changed over time?** Stewarts Bridge Reservoir was sampled as part of the New York LCI for a single sampling session in 2002. These results indicated higher nutrient levels but also higher water clarity. This suggests that water quality conditions might be variable in the Reservoir.

**Were any algal blooms or HABS observed or reported?:** Water quality conditions indicated a low susceptibility to blooms, and no blooms were observed along the shoreline in 2017.

**Are there any aquatic invasive species in the lake?:** Spiny water flea, an invasive crustacean, has been found in the Reservoir and other nearby lakes. Several invasive plants have also been reported in neighboring lakes, but only Eurasian watermilfoil has been reported in Stewarts Bridge Reservoir. Calcium levels are probably not high enough to support zebra mussels, and these invasive mussels have not been reported in the lake.

**Were there any other observations?:** It is likely that many native plants are found in the lake, but these were not evaluated during these water quality sampling sessions.

**Are any designated uses likely impacted by these conditions?:** Stewarts Bridge Reservoir supports recreation, with boat access provided by Alliance Energy via a concrete boat ramp located on the east shore off of Starlight Rd. Fish species in the lake include brook trout, brown trout, bream, brown bullhead, bluegill, crappie, pumpkinseed sunfish, rock bass, largemouth bass, smallmouth bass, common carp, walleye, yellow perch, and white perch. Water quality conditions appear to be adequate to support most recreational uses. Aquatic life may be threatened by spiny water flea and low oxygen levels near the reservoir bottom and aesthetics and habitat and aesthetics may be affected by invasive plants.

**What actions, if any, are appropriate for consideration?:** It is not known what reservoir management activities have been conducted by Alliance Energy or local stewards. Watershed management actions implemented to keep nutrients on the land and away from the reservoir should be considered or continued. A buffer of native plants next to the shoreline may help reduce nutrient and sediment loading to the reservoir. In other nearshore areas and in the rest of the watershed, stewardship activities such as pumping septic systems, reducing fertilization, shoreline erosion and channelized stormwater runoff, and other best management practices can also help to maintain or improve water quality. More information about in-lake algae control measures and watershed nutrient control measures to improve lake condition can be found in Diet for a Small Lake (<https://www.dec.ny.gov/chemical/82123.html>), although algae control is not warranted in the Reservoir.

## How to Read the Report

In order to make this lake report as easy to digest as possible for the typical reader, only the most critical information collected in the LCI is presented. We hope that presenting the data in a more succinct manner will draw in more readers and hold their attention. Unfortunately, this new format leaves little room for definitions of terms, so we are including this section primarily as a glossary of terms for which the typical reader may not know the definition.

The report begins with the lake name, town, and county. The next section contains some physical characteristics of the lake. The surface area is the two dimensional area of the lakes surface and is given in units of acres and hectares. The max depth is the water depth measured at the deepest part of the lake and is given in units of feet and meters. The mean depth is either known from a rigorous study of the bathymetry of the lake or is calculated as 0.46 times the maximum depth and is given in units of feet and meters. The retention time is the time it takes for a drop of water to pass through a lake, given in units of years. The lake classification is a letter defining the “best uses” for this particular lake, based on the legal classification assigned by New York state. Class AA, AAspec and A lakes may be used as sources of potable water. Class B lakes are suitable for contact recreational activities, like swimming. Class C lakes are suitable for non-contact recreational activities, including fishing, although they may still support swimming. The addition of a T or TS to any of these classes indicates the ability of a lake to support trout populations and/or trout spawning. The dam classification is a letter defining the hazard class of a dam if one exists. Class A, B, C, and D dams are defined as low, intermediate, high, or negligible/no hazard dams in that order. A “0” or blank indicates that no class has been assigned to a particular dam, or that no dam exists.

The next section contains some watershed characteristics including the watershed area in acres and hectares and the land use composition of the watershed. A watershed is the entire area that will drain to a particular lake and is constrained by the topology and hydrology of

the land. The watershed area was calculated by the US Geological Survey “StreamStats” program. This area map was then used to calculate land uses from the most recent (2011) National Land Use Cover data on the NYSDEC ArcGIS mapping program. The map itself is shown on the left side of the front page. In general, blue colors show water, green and light brown show forested or shrub land, yellow and dark brown are agriculture, and pink to red is developed land. The program participation section lists the years the lake has been sampled through LCI over a two year period, and the names of the DEC samplers conducting the work.

The next section includes four boxes. The trophic state of a lake refers to its nutrient loading and productivity- in other words, how much algae is produced, and the cause (nutrients) and outcome (changes in clarity) of this algae growth. An oligotrophic lake has low nutrient and algae levels (low productivity) and high clarity while a eutrophic lake has high nutrient and algae levels (high productivity) and low clarity. Mesotrophic lakes fall somewhere in the middle. For most lakes, the nutrient of concern is phosphorus. A more productive lake will support more plant life, which may be good for warmwater fish, but may lower the quality of the lake if growth becomes excessive.

The harmful algal bloom susceptibility section contains a summary of the available historical HAB data. Although the factors that lead to the formation of HAB’s is not yet well-understood, a history of HAB occurrences and high nutrient levels may indicate a susceptibility in the lake that could result in more HAB events in the future.

The invasive vulnerability section indicates if aquatic invasive species (AIS) are found in this lake or in nearby lakes. Invasive species are non-native and tend to rapidly colonize a waterbody once introduced, leaving little space for native species. Lakes with invasives or near other lakes with invasives are vulnerable to introductions of new AIS.

The next section is the priority waterbody list (PWL) assessment section. The PWL is a statewide inventory of the waters of New York State that DEC uses to track support (or impairment) of water uses, overall assessment water quality, causes and sources of water quality impact/impairment, and the status of restoration, protection and other water quality activities and efforts. A PWL assessment is broken into categories that include the following: potable water, swimming or public bathing, recreation, aquatic life, aesthetics, habitat, and fish consumption. All of the categories except aesthetics and habitat are accessed on a scale to determine if each of the listed uses are supported. The scale goes from best to worst in the following progression: fully supported, threatened, stressed, impaired, and precluded. Aesthetics and habitat are evaluated as good, fair, or poor. The cited PWL assessment reflects the “worst” assessment for the lake. The full PWL assessment for each lake can (or will eventually) be found on the DEC website by searching on “PWL” and the lake basin, at <http://www.dec.ny.gov/chemical/36730.html#WIPWL>.

The rest of the report contains a collection of tables and charts. A glossary of all the water quality and HABs indicators used in the plots and tables is included below. Of particular note are the seasonal change and average for the sampling season. There is also a seasonal change sparkline chart, which only shows the last year of summer trends. The average column summarizes the average of the last year of sampling results, with all samples weighted equally in the reported average. Data shown in these plots represent 0-2 meter

depth integrated surface samples and grab samples collected one meter from the bottom in the deepest section of thermally stratified lakes.

The next table contains a summary of shoreline (and open water if appropriate) HABs data for the lake, along with the associated HAB notification information. If a HAB is suspected, a sample from the worst part of the bloom (usually along the shoreline) is collected and sent in for laboratory confirmation. A HAB notification is added to the HAB database where entries are updated on a weekly basis. Additional information- samples or visual reports- are used to update these listings. The HABs Status plots show the algal component (total algae and fractions associated with cyanobacteria (blue green algae), green algae, diatoms, and other algae, as measured by chlorophyll *a*, in any collected samples, and the associated levels of total microcystin. The shoreline toxin data graphs include the World Health Organization (WHO) high risk criteria to protect swimmers and the EPA low risk criteria to protect those using *treated* (not raw lake) drinking water.

The next section of the report shows seasonal changes in water clarity, (extracted) chlorophyll *a*, surface and deep phosphorus (if deep samples are collected) and surface and deep ammonia levels. Surface samples are indicated with round markers, while deep samples are shown as triangular markers. If multiple years of samples were collected, results from all samples are shown, with previous years data shown in red.

The depth profile section shows the water temperatures, dissolved oxygen, chlorophyll, and phycocyanin (a measure of blue green pigments) as measured on a profiling electronic meter. Chlorophyll measures are “corrected” to reflect the expected extracted chlorophyll measurement based on the relationship between the surface integrated chlorophyll (extracted) data and the profiler unextracted data. As such, these results should be considered estimated relative values, and should not be compared to water quality criteria developed from extracted measurements only. Phycocyanin data are reported in relative units, although they are characterized as cells per mL.

The next section of the report includes Lake Use Scorecard. The scorecard presents the results of the existing Priority Waterbody List assessment for this lake in a graphical form and compares it to information from the current year from LCI data and other lake information. The scorecard also includes a column that lists some primary issues that could impact specific use categories. Multiple issues could affect each designated use, but only the primary issue is listed.

The final section of the report is the Lake Summary. This includes a brief summary of the most recent LCI data for the lake, although there is some comparison to previously LCI data when available. It is essentially the same as the Q&A section of reports generated through the NY Citizens Statewide Lake Assessment Program (CSLAP), and with the Lake Use Scorecard, represents perhaps the most easily understood single page summary of the LCI data for the lake. This was intentionally created as the last page of the report to allow easy copying and distribution to interested parties.



## Glossary of water quality and HAB indicators

**Clarity:** The depth to which a Secchi disk lowered into the water is visible, measured in meters. Water clarity is one of the trophic indicators for each lake.

**TP:** Total phosphorus, measured in milligrams per liter at the lake surface (1.5 meters below the surface). TP includes all dissolved and particulate forms of phosphorus. Total phosphorus is a second trophic indicator for each lake.

**Soluble P:** Dissolved phosphorus, measured in milligrams per liter at the lake surface, measured in water that passes through a 0.45 micron filter. It is an estimate of the amount of phosphorus available for biological uptake or growth, although available phosphorus is more accurately measured by soluble reactive P.

**Deep TP:** Total phosphorus measured in milligrams per liter at depth (1-2 meters above the lake bottom at the deepest part of the lake)

**Deep Soluble P:** Dissolved phosphorus measured at depth, measured in milligrams per liter

**TN:** Total nitrogen, measured in milligrams per liter at the lake surface. TN includes all forms of nitrogen, including **NO<sub>x</sub>** (nitrite and nitrate) and **NH<sub>4</sub>** (ammonia).

**Surface N:P Ratio:** The ratio of total nitrogen to total phosphorus, unitless (mass ratio), in surface samples analyzed for TP and TN. This ratio helps determine if a lake is phosphorus or nitrogen limited.

**Deep to Surface NH<sub>4</sub> Ratio:** The ratio of ammonia measured in deep and surface samples; this is a surrogate for lake anoxia when these ratios are > 10

**Chl.a (ug/l):** Chlorophyll a, measured in micrograms per liter as chlorophyll extracted from surface water samples using reagents and a desktop fluorometer

**pH:** A range from 0 to 14, with 0 being the most acidic and 14 being the most basic or alkaline. A healthy lake generally ranges between 6 and 9.

**Conductivity:** Specific conductance is a measure of the conductivity of water, measured as micromhos per centimeter and corrected to 25 degrees centigrade. A higher value indicates the presence of more dissolved ions that help conduct electricity. Conductivity results may indicate hard or softwater conditions with high ion concentrations resulting in hardwater.

**Total (or Dissolved) Organic Carbon:** Organic carbon measures the carbon (total or dissolved) in living material within the water, measured in milligrams per liter.

**True Color** is a visual measure of the brownness of the water, based on water passing through a 0.45 micron filter and compared to a visual series of standards developed from a platinum-cobalt standard (and thus measured as platinum units)



**Deep Manganese, Iron or Arsenic** measure total manganese, iron or arsenic levels in milligrams per liter in samples collected near the lake bottom. Elevated levels indicate anoxic conditions.

**BG Chl.a (ug/L):** Chlorophyll a from blue-green algae, measured in micrograms per liter. Readings above 25 ug/L are indicative of bloom conditions.

**HABs Reported?:** Were any algal blooms reported within a week of the dates listed, and, if so, were they located along the shoreline, in open water, or both?

**BGA:** Blue-green algae, as measured with a desktop or field fluorometer and reported as micrograms per liter of unextracted chlorophyll a

**Microcystin:** The most common HAB liver toxin; total microcystin above 20 micrograms per liter indicates a “high toxin” bloom. However, ALL BGA blooms should be avoided, even if toxin levels are low.

**Anatoxin-a:** Another type of toxin that may be produced in a HAB and may be more dangerous as it targets the central nervous system. Neither EPA nor NYS has developed a risk threshold for anatoxin-a, although readings above 4 micrograms per liter are believed to represent an elevated risk.